Sources and attribution

Historical manuscript notes of the I. M. Gelfand Seminar. MCCME digital archive: Notes of the talks at the I. M. Gelfand Seminar.

MCCME identifies M. A. Shubin as the note-taker. The Clay Mathematics Institute funded the scanning. MCCME acknowledges M. A. Shubin, S. I. Gelfand, the Clay Mathematics Institute and Jim Carlson. MCCME archive notice.

Archive chapters 1, 2, 3, 4, 5, 6, 7, 8, 9, manuscript frames 1–622. Catalogue snapshot: 5 October 2026.

Speakers named in the catalogue associations for these frames, using the catalogue's spelling:

I.M. Gelfand; R.L. Dobrushin; Irving Segal; Laurent Schwartz; S.G. Gindikin; A.Ya. Povzner; V.I. Arnold; A.A. Kirillov; I.I. Pyateski-Shapiro; M.I. Vishik; Yu.V. Linnik; E.A. Gorin; D.A. Kazhdan; V.P. Palamodov; A.S. Dynin; S.P. Novikov; Ya.G. Sinai; I.M. Gelfand, A.Ya. Povzner,Berezin; V.N. Latyshev; S.I. Gelfand; I.N. Bernstein; A.M. Stepin; R.A. Minlos; L.D. Faddeev; Paul Halmos; J.J. Kohn; Robert Finn; S.V. Smirnov; V.I. Matsaev; A.G. Kushnirenko; M.S. Agranovich; F.I. Karpelevich; V.A. Borovikov; V.B. Lidskii; G.E. Shilov; Lee Lorch; Louis Nirenberg; O.A. Oleinik; A.N. Parshin; D.B. Fuchs; S.G. Krein; Jean Leray; L.G. Makar-Limanov; A.Yu. Geronimus; Alan Weinstein ; M.L. Gromov; G.A. Margulis; Chandler Davis; V.M. Buchstaber; B.R. Vainberg; Gaetano Fikera; Dusa McDuff; Edwin Hewitt; B.V. Fedosov; A.M. Gabrielov; S. Rolevich; A.M. Perelomov; B.I. Rosenfeld; Vlastimil Ptak; Michael Atiyah; Pierre Deligne; A.M. Vinogradov; L.N. Vasserstein; Jack Morava; M.Sh. Birman; Yu.I. Manin; A.G. Kostyuchenko; V.I. Lomonosov; F.A. Berezin; G.M. Henkin; A.S. Mishchenko; A.N. Rudakov; A.I. Schnirelman; V.A. Ponomarev; Tony Springer; V.E. Zakharov; V.N. Tulovskii; A.B. Shabat; B.M. Gurevich; Yu. Koblenz; Enrico Guisti; Czeslaw Bessaga; B.A. Dubrovin; Graeme Segal; A.M. Polyakov; M.I. Graev; James King; Bert Kostant; E.S. Fradkin; I.M. Krichever.

A catalogue association does not by itself establish an exact talk boundary within a manuscript page or identify the writer of every note.

The modern LaTeX text is AI-transcribed. The English edition includes AI-translated passages and AI-transcribed passages originally written in English. Diagram reconstructions are AI-created and typesetting is AI-produced. Historical lecture and manuscript authorship remains with its human authors.

Rights in the original notes, scans and other third-party material remain with their authors and respective rights holders, including heirs. To the extent that the project holds copyright or related rights in its own contributions, it dedicates those rights under CC0 1.0 Universal. The dedication applies only to rights held by the project.

These editions are freely available and are published solely for non-commercial educational purposes. If a rights holder or their representative objects to publication, please identify the affected material in GitHub Issues so we can take it down.

Exact image URLs, file digests and catalogue associations accompany the editable sources.

Gelfand seminar — chapters 1–8 and the opening of chapter 9

Diplomatic translation. Source frames 1–622.

GELFAND-P000001

Monday, 21/IX. Cartesian and Boolean products of groups.

“Hironaka: on resolution of singularities.” Gelfand

A is a ring, $\mathcal{J}$ is a module over A.



Original source details: GELFAND-P000001

Uncertain reading. The letter for the module and ideal is rendered as $\mathcal{J}$; $\mathcal{I}$ or J are possible.

Blow-up — ? M is a manifold; $D \subset M$. [Beneath D:] a subset with singularities.

M_0^H is the blow-up. Blowing-up. The inverse image of D is D', a manifold of dimension $n-1$. D_0 is $(n-1)$-dimensional.



Original source details: GELFAND-P000001

Diagram and typed description. Three enclosed regions: D at left, D' and M_0^H at upper right, and a region labelled M_0' below. The upper and lower oblique arrows point left; a curved arrow rises from the lower region toward the upper right one. The lower-left arrow’s caption reads непр. / лин. отобр. [continuous/linear map]; the lower interior sign reads D_0 / D, with overlapping strokes. Some curve endings remain indistinct.



Typographic recreation; square brackets mark uncertain readings.

Original source details: GELFAND-P000001

Uncertain reading. The upper index on M_0 resembles H; the lower region’s label resembles M_0'.

The construction is Grothendieck’s. A is a ring, $\mathcal{J}$ is a module. Example. A is a ring of functions; $\mathcal{J}$ is the ideal of functions taking the value 0 on D.

One obtains a sheaf of rings and a sheaf of modules. A is a ring, $\mathcal{J}$ is an ideal. Construct X, O_X a sheaf of rings, $\mathcal{J}_X$ a sheaf of ideals, so that

$$(A, \mathcal{J}) \longleftarrow (X, O_X, \mathcal{J}_X).$$

[Beneath the arrow:] linear map.

$(A, \mathcal{J})$ is a sheaf generated by 1 ideal.

$\mathcal{J}_X$ is invertible, i.e. an ideal of the ring: $\exists f \in \mathcal{J}_X$ such that $O_X f = \mathcal{J}_X$. [Above the formula, an arrow to $\exists$:] generator.

(The ideal is principal if $\mathcal{J}$ is an ideal.) Then the zero variety is 1 equation.

A is a ring, $\mathcal{J}$ is an ideal. Typical example: R^2, the ideal $= 0$ at the origin.



Original source details: GELFAND-P000001

Uncertain reading. The next line: “Gluing a projective line into 0” [source: Вклеив. в 0 проект. прямой]; the beginning may read “Оклеив.”.

A, $\mathcal{J}$ are modules.

$$\mathcal{J} \otimes_A \mathcal{J}, \qquad \mathcal{J} \otimes_A \mathcal{J} \otimes_A \mathcal{J}, \dots$$

[Above the groups of tensor products:] symmetric; symmetric.

Consider formal sums

$$\sum_{k=0}^{N} a_k z^k.$$

Add and multiply. $x \otimes y = y \otimes x$.

$$a_0 \in A, \qquad a_1 \in \mathcal{J}, \qquad a_2 \in \mathcal{J} \otimes_A \mathcal{J} \quad —$$

GELFAND-P000002

The ring of these sums is $S_A(\mathcal{J})$. Consider homogeneous ideals [inserted above the line:] (graded). (Together with a polynomial it contains all its homogeneous components.)

Consider all homogeneous prime ideals in $S_A(\mathcal{J})$. Выбр. [source abbreviation] ideals which contain all polynomials, starting with degree 1.



Original source details: GELFAND-P000002

Uncertain reading. The end of the line after “contain all” is better read as “polynomials, starting with degree 1”; the middle strokes of the abbreviation “нач.” remain indistinct.

The collection of ideals is X. (The Zariski topology.) O_X, $\mathcal{J}_X$. If U is an open set, then O_U, $\mathcal{J}_U$.



Original source details: GELFAND-P000002

Uncertain reading. After “then”, the first letter has the same form as O_X above, the second as the ideal letter: O_U, $\mathcal{J}_U$; the latter may be $\mathcal{I}_U$.

$S_A(\mathcal{J})$ is the whole ring. The ring of fractions, numerators, denominators, not belonging to any of the ideals. Localize the ring at this set. Fractions of degree 1: $\mathcal{J}_U$.



Original source details: GELFAND-P000002

Uncertain reading. In the line about fractions, the abbreviations “numerator–denominator” and whether “not belonging” applies only to the denominator are unclear. No words are supplied from the meaning.

$$\Downarrow$$

[At right:] Grothendieck — blow up ideally.



Original source details: GELFAND-P000002

Uncertain reading. The right-hand note reads “Grothendieck — blow up ideally”; the last word may be “идеально” [ideally] or “идеалы” [ideals].

A is the ring of polynomials in 2 variables. $\mathcal{J}$ is the ideal of polynomials with $P(0,0)=0$.

$$A=\{P(x,y)\},\qquad \mathcal{J}=P(x,y)=a_1x+b_1y+\cdots.$$

$$\mathcal{J}\otimes_A\mathcal{J}\ \longleftrightarrow\ \{a_2x^2+2b_2xy+cy^2+\cdots\}.$$



Original source details: GELFAND-P000002

Uncertain reading. The coefficients in the quadratic polynomial read a_2, $2b_2$, c; the index on c and the shape of the thick two-headed arrow are uncertain.

Because of the interchange, one obtains the same as the square of the ideal. Then — the ideal of polynomials equal to 0 at this point. What will it blow up into? ?

$$\sum P_k(x,y)z^k,\qquad P_k(x,y)=ax^k+\cdots.$$

[At right:] Graded Σ of tensor products.

$$A=\{P_0(x,y)\}\longrightarrow S_A(\mathcal{J}),\qquad P_0(x,y)\sim P_0(x,y).$$

The set of prime ideals obtained from the ideal $P(0,0)=0$.

$$S_A\sim\sum P_kz^k,\qquad P_k\in\mathcal{J}^k,\qquad K\sim\sum P_kz^k.$$

It suffices to find the max. ideals of the quotient ring — (to find the ideals containing the given one).

$$S_A/K\ \longleftrightarrow\ a_0+(a_1x-b_1y)z+\cdots.$$

Original source details: GELFAND-P000002

Uncertain reading. In the last formula a minus is visible before b_1y, although the next scan has a plus. The visible minus is retained; the direction of the thick arrow is also uncertain.

GELFAND-P000003

All homogeneous max. ideals in it will be the points of the extension. There is no constant term (then also 1).

$$(a_1x+b_1y)z.$$

Only 1 linear combination of x and y. (Not 2, since then all.)

The ideals determine directions in the plane (замк. [source abbreviation] with all possible directions — the σ-process).



Original source details: GELFAND-P000003

Uncertain reading. The abbreviations in parentheses read “замк. всеми возм. напр.”; neither the first word nor the meaning of the sign σ is asserted.

Problem. In the space [cancelled:]



Original source details: GELFAND-P000003

Uncertain reading. The cancelled word before the drawing is illegible.

Original diagram

Typeset recreation

What results from gluing it in?

$$z = 0, \qquad xy = 0, \qquad \mathcal{J} = (z, xy).$$

[A line is drawn beneath the system.]

Dobrushin. [Cancelled before “Find”:]

Original source details: GELFAND-P000003

Uncertain reading. The cancelled beginning of the line cannot be read confidently.

Find an example of a gas in which phase transitions occur. A cube of the integer lattice. ℓ is the length. $V_\ell = \ell^\nu$. N points, $N < V_\ell$. They can occupy positions on the lattice $\theta = (x_1, \ldots, x_N)$.



Original source details: GELFAND-P000003

Uncertain reading. The configuration sign is rendered as θ; the handwritten sign also resembles b or Cyrillic “в”.

The Ising model. [Before the formula, a densely cancelled sign:]



Original source details: GELFAND-P000003

Uncertain reading. The separate cancelled sign before $U(\theta)$ is illegible.

$$U(\theta) = -\frac{1}{2}\sum_{i\neq j} u(x_i, x_j), \qquad u = \begin{cases} 0 & \text{in the other cases,} \\ 1; & \rho(x_i, x_j) = 1. \end{cases}$$

$u(\theta)$ is the number of pairs of neighboring points.



Uncertain reading. In the condition for the second branch a sign resembling ρ is visible; the semicolon after 1 is retained. In the caption below, the first letter resembles lowercase u rather than U.

Original source details: GELFAND-P000003

The basic axiom is the Gibbs distribution.

$$\mathsf{P}(B) = \frac{\sum\limits_{\theta\in B} \exp\{-U(\theta)/T\}}{Z(V_\ell, N)}, \qquad T > 0 \text{ — temperature.}$$

[Beneath the denominator:] normalizing factor.

$$Z(\ell, N) = \sum_{\theta\in\mathcal{B}} \exp\{-U(\theta)/T\}.$$



Uncertain reading. The denominator in the first formula reads $Z(V_\ell, N)$, the next line $Z(\ell, N)$; the set sign beneath the sum resembles $\mathcal{B}$.

Original source details: GELFAND-P000003

The molecules attract one another. ([Two filled signs with arrows:] neighbors $>$ their probability.)

Uncertain reading. In parentheses after "The molecules attract", there are filled signs and arrows; the reading "neighbors $>$ their probability" is uncertain.

Original source details: GELFAND-P000003

$B \subset \mathcal{B}$ is a collection of configurations.

$$p(\theta) = \frac{\exp\{-U(\theta)/T\}}{Z(\ell, N)}.$$

Take the limit $\ell \to \infty$; the cube expands to ∞. N_ℓ depends on ℓ. [A cancelled sign before the fraction:]



Uncertain reading. The cancelled sign before V_ℓ/N_ℓ is illegible.

Original source details: GELFAND-P000003

$$\frac{V_\ell}{N_\ell} = v = \text{const.}$$

The lattice grows. One can show that

$$\frac{1}{N_\ell} \log Z(\ell, N_\ell) \longrightarrow f(v, T).$$

GELFAND-P000004

$$p(v,T) = T\frac{\partial f}{\partial v} \qquad \text{by definition.}$$



Original source details: GELFAND-P000004

Uncertain reading. The heavily written first argument of p resembles v; no minus is visible before the derivative.

Phase transition. As for f: it is a monotone, convex function of v. Therefore $p > 0$, and p is a monotone function of v. Phase transition: $p(v, T)$ has a flat segment.



Original source details: GELFAND-P000004

Diagram and typed description. In the upper right-hand field is a bent, S-like curve with an almost horizontal middle segment and an arrow toward it; the caption reads “points of phase transition” [source abbreviation: точки фаз. перехода]. Precise axes and points in the original drawing are not identified confidently.



Typeset sketch; limitations are recorded in the note.

There is a physical hypothesis: 1 transition segment.



Original source details: GELFAND-P000004

Diagram and typed description. Intersecting wavy and oblique lines, horizontal and vertical axes, 0 and ∞. The strokes overlap; their exact separation into curves and the vertical label are unresolved.



Visible strokes; [?] marks the unreadable vertical label.



Original source details: GELFAND-P000004

Diagram and typed description. Neighboring drawing at right: a clean descending curve with a flat segment. This is a separate graph, not a reconstruction of the cancelled drawing at left.



Typeset recreation.

A flat segment occurs for sufficiently small T ($< T_{\text{crit}}$).

It admits an explicit solution for $n = 1$. Z and $f(v, T)$ are calculated. There are no phase transitions, which is considered physically natural.

$n = 2$. Onsager. $f(v, T)$ is calculated for particular v and T. A discontinuity of the derivative corresponds to phase transitions.



Original source details: GELFAND-P000004

Diagram and typed description. A graph with the T axis upward, the v axis to the right, and the label $1/2$ beneath a vertical through the vertex. The curve rises from the left to the vertex and descends to the right; the vertical line passes through the vertex, with a short wavy segment to its right. The precise geometry and the meaning of the wavy branch have not been established.



Typeset sketch; limitations are recorded in the note.

Kac, Helfand. Exact, in explicit form, for some cases [source endings: точн. в яв. виду для нек-рых случаях].



Original source details: GELFAND-P000004

Uncertain reading. The line reads “точн. в яв. виду для нек-рых случаях”; the endings may instead be “виде” and “случаев”.



Original source details: GELFAND-P000004

Diagram and typed description. Within the large frame, a small rectangular contour overlaps a rounded one; H lies inside and h above. The rounded contour protrudes to the right and left. Individual lines merge at the heavy intersections.



Visible contours and strokes; uncertain connections have not been completed.

$$\frac{\mu_H}{h^\nu}.$$

μ_H is the number of particles in H — a subcube. ν is the dimension.

$$\frac{\mu_H}{h^\nu} = \frac{1}{v} \qquad \text{as in the whole space.}$$

Law of large numbers.

$$\mathsf{P}\left\{\left|\frac{\mu_H}{h^\nu} - \frac{1}{v}\right| > \varepsilon\right\} \longrightarrow 0.$$



Original source details: GELFAND-P000004

Uncertain reading. In the probability formula the right vertical bar before $> \varepsilon$ is visible; a left bar before the fraction has not been read confidently.

$$\ell \to \infty, \qquad H \to \infty, \qquad d < \frac{h}{\ell} < 1 - d, \qquad d > 0.$$

Uncertain reading. At the lower right edge a small sign resembles “2” or a broken-off letter; it has not been adopted as a page number.

Original source details: GELFAND-P000004



Undeciphered passage. Along the extreme left edge is a narrow strip of neighboring handwritten text, cropped to isolated endings and strokes; no connected text can be read.

Original source details: GELFAND-P000004

GELFAND-P000005

If this does not hold, a phase transition takes place. Нагл. meaning. 2 phases coexist; the particles are distributed unevenly — — liquid and gas.



Uncertain reading. Нагл. [candidate abbreviation; the middle strokes are not fully distinguishable]

Original source details: GELFAND-P000005

[Above the line:] (law of large numbers). [Inserted above “phase transition”, with a bracket:] absence. (A closely related condition is necessary and sufficient for a phase transition

$$\mathsf{P}_\ell\left\{\left|\frac{\mu_H}{h^\nu}-\frac{1}{v}\right|>\varepsilon\right\}=O(e^{-N\beta}).$$



Uncertain reading. The exponent of e contains a heavily written sign before β; the candidate is $-N\beta$, but N is obscured by overlapping strokes. The parenthesis opened before “A closely related” is not clearly closed in the scan.

Original source details: GELFAND-P000005

[At right:] N is the number of particles.

Calculate the probability that

$$\mathsf{P}\{\mu_H=k\}=Z^{-1}\sum_{\theta\in\mathcal{B}_k}\exp\{-U(\theta)/T\}.$$

Over configurations in which H contains k particles. θ is a configuration of N particles. $\theta\in\mathcal{B}_k$. Then $\theta=(\theta_1,\theta_2)$. θ_1 is a configuration of k particles in H. θ_2 is a configuration of $(N-k)$ particles in $\overline{H}$.



Uncertain reading. The upper bar on H in the line about θ_2 is not completely distinct; the candidate is $\overline{H}$.

Original source details: GELFAND-P000005

$$U(\theta) = U(\theta_1) + U(\theta_2) + \gamma(\theta).$$

$U(\theta_1)$ is the interaction inside. $U(\theta_2)$: neighbors outside. $\gamma(\theta)$ is the interaction across the surface. $\gamma(\theta)$ can be neglected asymptotically. (Across the boundary: of the order of the number of boundary points) $V^{\nu-1/\nu}$ as $N \to \infty$. $k \sim dN$.



Uncertain reading. The exponent on V looks like $\nu - 1/\nu$, without a confidently distinguishable common numerator. A possible grouping is $(\nu - 1)/\nu$.

Original source details: GELFAND-P000005

$$|\gamma(\theta)| \le CN^{\frac{\nu-1}{\nu}}.$$

$$\sum \exp\{-U(\theta)/T\} = \sum_{\theta \in \mathcal{B}_k} \exp\{-U(\theta_1)/T\} \exp\{-U(\theta_2)/T\}$$
$$\times \exp\{\theta N^{2/3}\} =$$



Uncertain reading. The letter before $N^{2/3}$ resembles θ or Θ; below, the same letter is glossed as “bounded parameter”. It may differ from the configuration sign.

Original source details: GELFAND-P000005

θ is a bounded parameter.

$$= \exp\{\theta N^{2/3}\} \sum_{\theta_1} \exp\{-U(\theta_1)/T\} \sum_{\theta_2} \exp\{-U(\theta_2)/T\}.$$

[Beneath the first sum:] configurations.

GELFAND-P000006

Factor 1: Z, calculated for the subcube. Factor 2 — ditto — Z for the outer cube.

$$\mathsf{P}\{\mu_H = k\} = \frac{Z(H,k)Z(\overline{H}, N-k)}{Z(V,N)} \exp\{\theta N^{2/3}\}.$$

[Asterisk.] Apply to them the asymptotic formula

$$Z(V,N) \approx \exp\{-Nf(v,T)\},$$

$$Z(H,k) = \exp\{-kf(h^3/k,T)\}.$$



Uncertain reading. The numerator of the argument of f in this line visibly has exponent 3 on h, although ν is used later.

Original source details: GELFAND-P000006

It can also be proved for well-behaved regions (not a cube). The limiting formula does not depend on the region's shape.

$$Z(\overline{H},N-k) = \exp\{-(N-k)f((\ell^3-h^3)/(N-k),T)\}.$$

Substitute there under the assumption that f has a linear segment. If f has a linear segment (the derivative has a horizontal one), then terms cancel and we obtain

$$\frac{1}{N}\log \mathsf{P}\{\mu_H = k\rho\} \longrightarrow \begin{cases} 0 & \text{only at } \rho = 1/v \text{ (if there is no linear segment)}, \\ 0 & \rho \in \text{ the linear segment.} \end{cases}$$

[Cancelled by the second branch:]



Uncertain reading. The event's argument looks like $\mu_H = k\rho$, but the final sign may be θ or δ. The density letter at right resembles ρ. The cancelled text above the second branch has not been read.

Original source details: GELFAND-P000006



Original source details: GELFAND-P000006

Diagram and typed description. At right of the second branch of the limit is a small stroke: from the lower left, a line rises almost vertically, then runs almost horizontally to the right, and rises again at the right end. Separate axes, arrows and labels have not been established; the sketch's mathematical meaning requires the original image.



Visible stroke; no axes or values supplied.

$\mathsf{P} \to 0$ exponentially. ($1/v$ follows from the convexity of f.)

Arrangement of particles. Its boundary; around each particle a cube of side 1. $\Gamma'(\theta)$ is the boundary of the occupied region. $\Gamma(\theta)$ is the length [inserted below:] area.



Original source details: GELFAND-P000006

Diagram and typed description. At left is a vertical outline with two strong transverse strokes, diagonal hatching and separate short marks. At right, three cells form an L: two below and one above the left cell. In the left column, divisions merge with the hatching; the exact cell count is uncertain.



Visible contours and strokes; uncertain connections have not been completed.

Replace the Gibbs probability.

$$\mathsf{P}(\theta) = \frac{\exp\{-U(\theta)/T\}}{\sum \exp\{-U(\theta)/T\}} = \frac{\exp\{-\Gamma'(\theta)/(2T)\}}{\sum \exp\{-\Gamma'(\theta)/(2T)\}}.$$



Original source details: GELFAND-P000006

Uncertain reading. The prime on Γ in the two exponents after the equality is not completely clear; the visible letter resembles Γ' or Γ.

[At right:] $2\nu - \delta$. Unoccupied squares $\Gamma'(\theta)$. [Inserted:] at neighbors.

$$-U(\theta) \geq \sum(2\nu - \delta) = 2\nu N - \sum_{\Gamma'(\theta)} \delta.$$



Original source details: GELFAND-P000006

Uncertain reading. The sign after $-U(\theta)$ is written over another sign: candidates are $\geq$, $\leq$, and $=$. The sign before the final sum and the sum's index may belong to another term.

GELFAND-P000007

($U(\theta)$ is minus the number of neighbors.) A smaller boundary makes an arrangement more favorable. Force them into one corner, but this is unfavorable (there are few such arrangements in all). A finite number of clumps. (Inside the gas: liquid.)

Original source details: GELFAND-P000007

Diagram and typed description. The small frame contains two dark regions with light interior gaps. At upper left are a bent heavy stroke and separate short oblique marks. These marks have not been identified as letters or arrows.



Visible contours and strokes; uncertain connections have not been completed.

And this contradicts the law of large numbers.



Original source details: GELFAND-P000007

Diagram and typed description. Inside the large frame, the upper-left horseshoe-shaped region has an open lower gap and a small outlined part at its left tip. At right is a slanted ring. The large lower-left region contains an open or broken inner contour and a small central contour. Individual hatch marks are visible; some connections are uncertain.



Visible contours and strokes; uncertain connections have not been completed.

The whole boundary splits into connected cycles. Each arrangement has its own number. Number them

$$\Gamma_1(\theta) \geq \Gamma_2(\theta) \geq \cdots, \qquad \Gamma(\theta) = \sum_i \Gamma_i(\theta).$$

An arrangement is special if $\exists N < \infty$, $D < \infty$, $\delta > 0$.



Original source details: GELFAND-P000007

Uncertain reading. In this line the first finite parameter resembles N, whereas the later summation limit resembles M.

$$1) \quad \sum_{i=1}^{M} \Gamma_i(\theta) \leq D\ell^{\frac{\nu-1}{\nu}}.$$

[Beneath the sum:] Large. Of the order of the boundary length. (Almost the whole cube.)



Original source details: GELFAND-P000007

Uncertain reading. The exponent on ℓ in the first condition is written as a fraction, read as $(\nu-1)/\nu$; in GELFAND-P000010 the analogous line has $\nu - 1$.

$$2) \quad \text{all the others small} \qquad \sum_{i=1}^{M} \left(\Gamma_i(\theta)\right)^{\frac{\nu}{\nu-1}}.$$



Original source details: GELFAND-P000007

Uncertain reading. The visible limits of the second sum look like 1 and M, although the caption says “all the others small”. No condition is visible after the sum.

[Dividing line.]

24/IX. Thursday. 16 h, room 13-11. Prof. Segal (USA). Theory of functions in infinite-dimensional space.

$$+\Box\varphi = m^2\varphi + g\varphi^3.$$

$$F_f(\varphi) = \int (-\Box + m^2) f\varphi + g \int \varphi^3 f.$$

[Above φ^3:] φ — мн. [source abbreviation]. φ [arrow] C_0^∞ — functions.



Original source details: GELFAND-P000007

Uncertain reading. Above the note at right are the visible words “б, ф-й на” [fragment: functions on] and an arrow toward C_0^∞.

g is fixed. $F_f \in \Phi$ is a nonlinear functional of φ. Φ is a ring; one can multiply $F_1(\varphi)F_2(\varphi)$. Take the ideal generated by $(F_f : f \in C_0^\infty)$ — Ω.



Original source details: GELFAND-P000007

Uncertain reading. The index on F in the ideal’s definition resembles f; the source sign after the parenthesis is Ω or a calligraphic J.

Let $p = \Phi/\Omega$ be the function ring on the manifold of solutions of the given partial differential equation. To obtain a solution $(1) \stackrel{\text{def}}{=}$ a point of the space of maximal ideals of the ring p. An ordinary solution φ_0 [a check mark above the word] is assigned a maximal ideal: consider the map

$$F \longrightarrow F(\varphi_0),$$

a homomorphism into Φ, F_f is zero on the ideal Ω. This is a homomorphism of the quotient ring as well, i.e. a maximal ideal.



Original source details: GELFAND-P000007

Uncertain reading. After “a homomorphism into”, the visible letter resembles Φ.

GELFAND-P000008

A maximal ideal is a generalized solution of a nonlinear equation. The algebraic case.

$$f_1(x_1, \ldots, x_n) = 0, \qquad f_k(x_1, \ldots, x_n) = 0.$$

Solutions in terms of a ring: in the ring of all polynomials. The ideal generated by these functions is p, and the quotient ring is Φ/p.



Original source details: GELFAND-P000008

Uncertain reading. In the fraction, the numerator resembles Φ, P, or a heavily written A; the candidate Φ is retained.

Φ — all equations. This is the ring of algebraic functions. A point, the value at the point, is precisely a maximal ideal. In the algebraic case, conversely as well. Analogy: linear oscillations.

$$\int f(-\Box\varphi\ldots)\,dx.$$



Original source details: GELFAND-P000008

Uncertain reading. The part of the integral after $-\Box$ looks like $\varphi\ldots$, but the letter is partly inked over.

And the corresponding ideal.

Dobrushin. $\nu = 2, 3$. $V_\ell = \ell^\nu$, $N < V_\ell$, $\theta = (x_1, \ldots, x_N)$.



Original source details: GELFAND-P000008

Diagram and typed description. Original diagram and typographic recreation.



$\Gamma(\theta)$ is the boundary length. $U(\theta)$ is the number of neighbors (pairs of neighbors). The Gibbs distribution

$$p(\theta) = \frac{\exp\{U(\theta)/T\}}{\sum\limits_{\theta\in\mathcal{B}(V_\ell,N)} \exp\{U(\theta)/T\}} = \frac{\exp\{-\Gamma(\theta)/(2T)\}}{\sum\limits_{\theta} \exp\{-\Gamma(\theta)/(2T)\}}.$$

[Beneath the first sum:] all arrangements.

$$(\text{since } 2U(\theta) = 2\nu N - \Gamma(\theta)).$$

Phase transition. Let the lattice grow, $\ell \to \infty$, and let $N_\ell \to \infty$. The limit $V_\ell / N_\ell \to v$ is the specific volume. It turns out that

$$\frac{1}{N} \log \sum_\theta \exp\{U(\theta)/T\} \longrightarrow f(v, T).$$



Uncertain reading. Beneath the limit the name reads “Ван Хов” or “Ванхов” [Van Hove]; the middle and ending are heavily overwritten.

Original source details: GELFAND-P000008

(v, T) is called a point of phase transition if

$$\frac{\partial f(v,T)}{\partial v} = 0 \quad \text{in some neighborhood at } T = \text{const.}$$

Uncertain reading. Between T and const, the sign resembles $=$ or $\neq$; the candidate $=$ is retained, but the reading is not asserted.

Original source details: GELFAND-P000008



Undeciphered passage. At the extreme left edge is a narrow cropped column of handwritten endings from neighboring text; continuous words cannot be recovered.

Original source details: GELFAND-P000008

GELFAND-P000009

(Since the function is linear; a priori it is convex.)

$$Q(T) = \frac{S_\nu e(1 - e^{-1/(2T)})}{3(1 + e^{-\nu/T})} \sum_{k=2\nu}^{\infty} 3 \exp\{-1/(2T)\}^k k^{\frac{\nu}{\nu-1}}.$$

[After the first equality, a cancelled fragment:]



Uncertain reading. The cancelled sign after $=$ is illegible. In the numerator, the factor after S_ν resembles e; the upper summation limit resembles ∞ or a double stroke. The exponent k may apply to the factor 3 as well, but in the scan it stands by the closing brace.

Original source details: GELFAND-P000009

S_ν is the volume of a ν-dimensional sphere with surface 1.

$$S_2 = \frac{1}{4\pi}, \qquad S_3 = \frac{1}{C\sqrt{\pi}}.$$



Uncertain reading. The first factor in the denominator of S_3 resembles C, c, or 6; the written C is only a candidate.

Original source details: GELFAND-P000009

If

$$Q(T) < \frac{1}{v} < 1 - Q(T),$$

then a phase transition takes place.



Diagram and typed description. Original diagram and typographic recreation.



Original source details: GELFAND-P000009

[Dividing line.]

S is a subcube. $S_\ell \subset V_\ell$. K_ℓ is the side of S_ℓ.

$$0 < d < \frac{K_\ell}{\ell} < 1 - d.$$

Introduce a random variable. $\mu(S_\ell)$ is the number of points of the arrangement θ that fall in S_ℓ. $\mu_{S_\ell}(\theta)$. If

$$\mathsf{P}\left\{\left|\frac{\mu_{S_\ell}(\theta)}{K_\ell^\nu} - \frac{1}{v}\right|\right\} > \varepsilon\} \not\longrightarrow 0, \qquad \varepsilon > 0,$$

then there is a phase transition.



Original source details: GELFAND-P000009

Uncertain reading. After the right absolute-value bar, the scan shows a brace before $> \varepsilon$ and another after ε.

[Beneath the first fraction:] density in the subcube. [Beneath $1/v$:] density in the whole cube. And a closely related condition is necessary. (Physical meaning: coexistence of 2 phases.)

Original source details: GELFAND-P000009

Diagram and typed description. Original diagram and typographic recreation.



The boundary splits into components — — but a connection through corners ($\nu = 2$) or an edge ($\nu = 3$) is not counted.

$$\Gamma(\theta) = \sum_i \Gamma_i(\theta).$$

$\Gamma_i(\theta)$ is the length or area of a boundary component. Definition. Single out a special arrangement. It depends on 3 numbers, $N < \infty$, $D < \infty$, $\delta > 0$.



Original source details: GELFAND-P000009

Uncertain reading. The first letter resembles N, but admits M; the enlarged fragment does not resolve the distinction.

Number the cycles in decreasing order of length

$$\Gamma_1(\theta) \geq \Gamma_2(\theta) \geq \cdots .$$

GELFAND-P000010

Conditions.

$$1) \quad \sum_{i=1}^{M} \Gamma_i(\theta) \leq D\ell^{\nu-1}.$$

(Of the order of the surface of the large cube.)

$$2) \quad \sum_{i=M+1}^{\infty} \big(\Gamma_i(\theta)\big)^{\frac{\nu}{\nu-1}} \leq \frac{\min(N_\ell, V_\ell - N_\ell)}{S_\nu}(1-\delta).$$



Original source details: GELFAND-P000010

Uncertain reading. The inequality sign before the fraction is heavily overwritten: candidates are $\leq$ and $<$. The parameter in the upper limit of the first sum resembles M or N.

$$S_\nu \left(\Gamma_i(\theta)\right)^{\frac{\nu}{\nu-1}}$$

Area of a circle with length Γ_i. A ball has maximal volume; this is an upper bound on the volume of the region inside the cycles. (It is $<$ what is needed to contain all occupied points.) ([A word is cancelled; inserted above:] volume. Inside small cycles $<$ the shaded area and the white area.)



Original source details: GELFAND-P000010

Uncertain reading. The word beneath the inserted “volume” is heavily cancelled and illegible. The two lines write “Area”.

Original source details: GELFAND-P000010

Diagram and typed description. Four nested irregular rounded contours. The outer ring has uneven thick and thin strokes, retraced arcs above and at lower right, and separate ends bending inward. The inner ring has radial and oblique strokes. Lines merge in heavy areas; no additional closed boundaries or arrows have been established.



Visible irregular contours and strokes; no directions assigned.

Neither all the points nor all the empty sites can be forced into it. An example of an arrangement where the conditions do not hold.



Original source details: GELFAND-P000010

Diagram and typed description. The three upper dark regions have distinct light centres. Below the curved divider are a rounded contour with two right branches, an incomplete lower curve, several oblique and bent strokes, and a short branch on the right. Some connections at the lower intersections and gaps are uncertain.



Visible contours and strokes; uncertain connections have not been completed.

This is a phase transition. Everything reduces to 2 lemmas.

$1)$ $\exists M, D, \delta$ such that the probability that the conditions hold $\longrightarrow 1$, if the stated condition holds. [Beneath the parameters:] independent of everything.



Original source details: GELFAND-P000010

Uncertain reading. In the line after “if ... holds”, the word looks like “сформ.” [stated] or “строгое” [strict]; nothing is supplied from the meaning.

$2)$ Lemma 2. If almost all arrangements are special, then there is a phase transition. Idea of the proof of Lemma 2. G is the volume of the region enclosed by the small cycles.

$$G \leq N_\ell(1-\delta), \qquad \frac{G}{V_\ell} \leq \frac{1}{v}(1-\delta).$$



Original source details: GELFAND-P000010

Diagram and typed description. A grid of five columns and five rows; the second cell from the left in the fourth row from the top is marked. The left edge and four internal vertical lines have downward tips. Two upper horizontals stop short of the right edge; its lower endpoint is thickened and its exact shape is unclear. Caption: “Divided into subcubes”.



Divided into subcubes

Five downward tips; the uncertain right endpoint is a separate stroke.

There exists a subcube S_ℓ:

$$\frac{G \cap S_\ell}{V_\ell} \leq \frac{1}{v}(1-\delta).$$



Uncertain reading. In the numerator, the heavy sign before $\cap S_\ell$ resembles G; the denominator clearly resembles V_ℓ.

Original source details: GELFAND-P000010

GELFAND-P000011

Let all large cycles surround co / ∞.



Uncertain reading. surround co / ∞. [The two-loop sign before the verb is uncertain.]

Original source details: GELFAND-P000011

2 cases.



Diagram and typed description. Two small rectangular frames, each with four dark rounded marks. The right frame has light centres, an irregular chain of strokes above, and detached short and curved lines between the rounded marks and near the edges. Their exact connections and possible arrowheads are indistinct.

Visible interior strokes; connections and directions remain uncertain.

Original source details: GELFAND-P000011

Lemma. [Непрс.] a boundary of k [cancelled: точк.; inserted above/below: links] $\leq 3^k$.

Uncertain reading. Неprс. [uncertain source abbreviation]

Original source details: GELFAND-P000011

Uncertain reading. точк. [points; uncertain cancelled reading]

Original source details: GELFAND-P000011

Gain 3, loss.

Diagram and typed description. Beneath the words about gain and loss is a wavy, almost horizontal line, a gap before a separate right segment, and a long vertical segment extending downward. A detached short stroke lies above their junction; it has not been identified as a letter or arrow.

Original source details: GELFAND-P000011



The detached upper stroke is retained without assigning a letter or arrow.

$$\exp\left\{-\frac{1}{2T}\right\}, \qquad \left(3\exp\left\{-\frac{1}{2T}\right\}\right)^k.$$

Problem. (unsolved) Let N be large. Turn with probability $\frac{1}{3}$, but returning is forbidden [Cancelled: not].

Uncertain reading. *Cancelled.* не [not; uncertain candidate for a short word]

Original source details: GELFAND-P000011

What is [Cancelled: prob. ...] the expected distance he will travel in N steps?



Uncertain reading. *Cancelled.* вер. ... [prob.; candidate for the first abbreviation; the following cancelled writing is unreadable]

Original source details: GELFAND-P000011

(If returning is allowed, then $\sim \sqrt{n}$.) If returning is allowed, then
($\geq 2{,}6^n$ but $< 2{,}8^n$, conjecture e^n).



Uncertain reading.
($\geq 2{,}6^n$ but $< 2{,}8^n$, conjecture e^n); the first sign may also read $>$; additional strokes are uncertain

Original source details: GELFAND-P000011

[Horizontal divider.]

28/IX Segal. Theory of functions on the set of solutions of a relativistic differential equation. [In the left margin: They are all written this way.]

$$u' = Au + K(u) \qquad (A) \qquad u(t), \quad -\infty < t < +\infty,$$

$$A = -A^*, \qquad u \in L^2, \qquad u(t) \in H.$$

K is a given nonlinear operator. In integral form

$$u(t) = e^{A(t-t_0)}u(t_0) + \int_{t_0}^{t} e^{A(t-s)}K(u(s))\,ds \qquad (B).$$

When $K \in C^1$, i.e. $\partial_u K = K_u$ exists in the Fréchet sense and is continuous, every solution of (B) is a solution of A (if $u(t)$ is in the domain of A).

[Horizontal divider.]

Suppose (B) has a global solution for every initial datum at t_0 (u_0). (And $K \in C^1$.) In quantum mechanics

$$\Box\varphi = f(\varphi)$$

[Beneath □: d'Alembertian.]

$$u(t) = [\varphi(\cdot, t), \dot{\varphi}(\cdot, t)], \qquad \varphi = \varphi(\vec{x}, t).$$

K is a nonlinear operator, Немыц. / Намыц.

Uncertain reading. Немыц. / Намыц. [Nemyts. / Namyts.; the final source abbreviation is uncertain]

Original source details: GELFAND-P000011

$$\|[\varphi,\omega]\| \qquad \Box\varphi = m^2\varphi + f(\varphi)$$

[Beneath the formula: A shorter form.]

$$B = \sqrt{m^2 I - \Delta}, \qquad \|[\varphi,\omega]\| = \|B\varphi\|^2_{L^2} + \|\omega\|^2_{L^2}.$$

Uncertain reading. No square is visible above the norm on the left of the last formula; the right side contains squares.

Original source details: GELFAND-P000012

A is given by a matrix of order 2,

$$\begin{pmatrix} 0 & I \\ -B^2 & 0 \end{pmatrix}.$$

It is not self-adjoint, but in this norm it is self-adjoint.



Uncertain reading. Both places read “самосопр.” [self-adjoint]; $A = -A^*$ is written above.

Original source details: GELFAND-P000012

Any equation of relativistic physics can be written this way.

M is the collection of all solutions.

$$M = [u(\cdot);\ (**) \text{ satisfies}]$$

[At right/beneath the formula: of t; various B.]

Uncertain reading. различные B. [various B.; uncertain reading of the underlined note]

Original source details: GELFAND-P000012

Now let $K \in C^\infty$. M is a Banach manifold (every point has a neighbourhood homeomorphic to a Banach [Cancelled: illegible] space; the transition is a C^∞ function in the Fréchet sense).

Uncertain reading. *Cancelled.* unreadable word

Original source details: GELFAND-P000012

$$S_t : M \longrightarrow H, \qquad u(\cdot) \longmapsto u(t).$$

[At right: operator. set of sol. $\longrightarrow H$]

Uncertain reading. мн. реш. $\longrightarrow H$ / им. реш. $\longrightarrow H$ [set of sol. / им. sol.; the first source abbreviation is uncertain; the final arrow and H are visible]

Original source details: GELFAND-P000012

Theorem. There exists a unique C^∞ manifold structure for which the map S_t is a C^∞ isomorphism. $u(t, u_0)$ depends on u_0 in a C^∞ manner.

A true manifold. There is a tangent space $T_{u(\cdot)}$. The tangent map

$$dS_t : T_{u(\cdot)} \longrightarrow T_{u(t)}.$$

Of course, at every point it is isomorphic to the space itself.

$$\lambda \in T_{u(\cdot)}, \qquad dS_t(\lambda) = v(t) \in H.$$

Thus a function corresponds to each tangent vector. [Underlined and cancelled: Lemma.] Denote by $v(t)$ (not the value of v at the point t); variational equation, an equation of first order:

$$v' = Av + K_{u(\cdot)}.$$



Uncertain reading. No separate factor v is visible after $K_{u(\cdot)}$ on this line.

Original source details: GELFAND-P000012

Solutions of this equation arise from tangent vectors λ, and conversely.

1) Canonical differential form on M.

2) Poisson brackets (analogy with the finite-dimensional case).

GELFAND-P000013

3) Vector fields in M. In their terms there will be зд.



Uncertain reading. зд. [the final source abbreviation is uncertain]

Original source details: GELFAND-P000013

4) Canonical commutation relations.

5) A representation and an explicit definition of the operators will be given.

5/X. Segal. I. Renormalized field equation. 1) Derivation. 2) Existence and uniqueness.

II. Definition of the scattering matrix S. A. Classical S operator. B. Extension of generalized probability distributions to the nonlinear case.

III. Discussion of interpretation in terms of particle theory.

[Horizontal divider.]

Consider the equation

$$\Box\widetilde{\varphi} = m^2\widetilde{\varphi} + \widetilde{\varphi}^3,$$

$$[\widetilde{\varphi}(\vec{x}, t), \widetilde{\varphi}(\vec{x}', t)] = 0 = [\dot{\widetilde{\varphi}}(\vec{x}, t), \dot{\widetilde{\varphi}}(\vec{x}', t)].$$



Uncertain reading. Candidates for the source line: $[\widetilde{\varphi}(x), \widetilde{\varphi}(x')] = i\delta'(x - x')$ / $[\widetilde{\varphi}(x), \dot{\widetilde{\varphi}}(x')] = i\delta(x - x')$. The dot above the second letter, the additional stroke after δ, and the exact placement of the arguments are not fully distinguishable.

Original source details: GELFAND-P000013

Loran Schwartz. There are 2 types of measures: Radon measures and simply measures [inserted above the last word: abstract]. For now, restrict to positive measures. An abstract measure on a set X, F is a σ-algebra. μ is a measure. μ is σ-additive on F.

[Horizontal line.]

Once a measure is given, one can consider the μ-measurable sets, F_μ on X, and integrate measurable functions.

$$f : X \longrightarrow F, \qquad \int_X f(x)\, d\mu(x).$$

[At right: values in a Banach space; F is a Banach space.]

[Horizontal line.]

Radon measure. X is an arbitrary locally compact space. $C(X)$ consists of continuous functions with compact supports, with the inductive-limit topology, and let $C'(X)$ be the dual space. Its elements are measures on X.

GELFAND-P000014

μ is positive if $\mu(\varphi) \geq 0$ for $\varphi \geq 0$. A measure is bounded if

$$|\mu(\varphi)| \leq C \max |\varphi|.$$

The 2nd definition is a bounded positive Radon measure. The same Lebesgue extension is performed with it. The integral also exists (with values in a Banach space).

The σ-field constructed from a Radon measure depends on μ, but there exists one independent of μ (substantially): the field of Borel sets (min containing closed and open sets).

Uncertain reading. min containing closed and open sets [the beginning of the parenthetical note is uncertain]

Original source details: GELFAND-P000014

[Horizontal divider.]

Why do various mathematicians prefer Radon measures? Radon measures exist only on locally compact spaces (a restriction in probability theory). But [Cancelled: two illegible words] Radon measures are more convenient.

Uncertain reading. *Cancelled.* two short unreadable words

Original source details: GELFAND-P000014



Uncertain reading. For “right” measures there is разлож. / различ. единицы [decomp. / различ. of unity] (if [cancelled beginning] a measure $= 0$ on a system of neighbourhoods, then it is zero everywhere). [The first description of the measures and the abbreviation before “unity” are uncertain.]

Original source details: GELFAND-P000014

There are 5–15 theorems true for Radon measures (only).

$$X \xrightarrow{f} Y$$

[Beneath the arrow: topological spaces.] [Cancelled.]

Uncertain reading. a short word before “Select”

Original source details: GELFAND-P000014

Select the Borel field on X and on Y, and an abstract measure μ on X. Let $A \subset Y$. Then there is a measure $f(\mu)$ on Y:

$$f(\mu)(B) = \mu(f^{-1}(B)).$$

But if B is an arbitrary subset $A \subset X$, then [one sign cancelled]

$$f(\mu)(A) \qquad \mu(f^{-1}(A)).$$

Uncertain reading. The source alternates between A and B, and $A \subset X$ is read before the second pair of formulas.



Original source details: GELFAND-P000014

One can show that if the left side makes sense, the right side does too and they are equal; the converse is false. [Cancelled.]

Uncertain reading. an unreadable beginning of a line

Original source details: GELFAND-P000014

$$A \text{ — } f(\mu)\text{-measurable} \implies f^{-1}(A) \ \mu\text{-measurable}$$

If μ is a Radon measure, there is equivalence.

Example (contradictory)

$$X \subseteq Y = [0,1]$$

such that X is a Lebesgue-nonmeasurable set, $Y \setminus X$ has inner measure 0 (or the outer measure of $X = 1$). A subset of X is Borel $\Longleftrightarrow$ it is an intersection with a Borel set of Y. μ is an abstract measure.

GELFAND-P000015

Definition. $\mu(D)$. $D \subset X$ is Borel.

$$D = X \cap E, \qquad E \text{ — Borel in } Y,$$

$$\mu(D) \underset{\text{def}}{=} dx(E)$$

[Beneath $dx(E)$: Lebesgue measure.]

Original source details: GELFAND-P000015

Uncertain reading. In $dx(E)$ both letters are on the baseline; the case of the second letter is not fully distinguishable: $dx(E)$ / $dX(E)$.

The measure is the same (differs on a set of вн. measure 0).



Original source details: GELFAND-P000015

Uncertain reading. отлич. на мн-во вн. меры 0 [differs on a set of вн. measure 0; uncertain parenthetical source note]

We have defined an abstract measure on X. Its image [The following line repeats: its image] is dx. Take some (non-Borel) subset of $Y \setminus X$. It is nonmeasurable, but its inverse image is empty and hence measurable.

The aim of the talk is to show that local compactness is unnecessary. Let μ be a measure on F_B; then μ is a Radon measure if it is inner compact regular.

$$\mu \text{ Radon} \Longleftrightarrow \forall B,\ \forall \varepsilon > 0\ \exists \text{ compact } \subset B, \qquad \mu(b-k) \leq \varepsilon.$$



Original source details: GELFAND-P000015

Uncertain reading. Lowercase $b - k$ is read in the difference, although $\forall B$ precedes it. No separate set letter is visible between “compact” and $\subset B$.

[Horizontal divider.]

X is a topological space. Find a measure with all the properties of locally compact Radon measures. Suppose it is defined (set up) on Borel sets. A definition of a Radon measure valid beyond locally compact spaces. Let X be completely regular (such spaces can be embedded in compact spaces of maximal ideals).

$$X, \qquad \widehat{X} \text{ — Čech completion of } X$$

(maximal ideals of the algebra of continuous functions).

$$X \xrightarrow{i} \widehat{X}.$$

Complete regularity means that this is a homeomorphic map, rather than merely an injective map. Another definition of a Radon measure on X: a Radon measure on $\widehat{X}$ for which

$$\mu(\widehat{X} \setminus X) = 0.$$

One can show equivalence. In the locally compact case.

$$\mu \text{ Rad} \iff \forall B \text{ compact } \forall \varepsilon > 0 \; \exists \text{ compact} \quad \mu(B - k) < \varepsilon.$$

Original source details: GELFAND-P000015

Uncertain reading. The second sign in the difference resembles lowercase k; the first reads as B, but its case is uncertain ($B - k$ / $b - k$). No separate set letter or inclusion condition is visible after “compact”.

All the properties of Radon measures hold. The theorem’s proof is valid in $\widehat{X}$, and the rest is almost trivial. There is a single exception: [Cancelled: properties ... Borel ...] spaces.



Original source details: GELFAND-P000015

Uncertain reading. *Cancelled.* св-ва ... бор. ... [properties ... Borel ...; visible fragmentary candidates beneath the horizontal stroke; the complete cancelled phrase is unreadable]

— one cannot define the support of arbitrary Radon measures.

GELFAND-P000016

$X \subset K_0$ into a compact space (any one). Then an analogous definition of Radon measures exists. We obtain the same law.

[Horizontal divider.]

Compare with the definition of a nuclear space (spaces in which the 2 definitions of the tensor product coincide).

$$a(X) \supset R(X).$$



Original source details: GELFAND-P000016

Uncertain reading. The first symbol in the inclusion resembles a lowercase a with a large loop; A or a calligraphic form is not wholly excluded.

A Radon space if every abstract measure on it is a Radon measure.

3 properties of Radon spaces. 1) If X is Radon and $Y \subset X$, then Y is Radon $\iff$ it is universally measurable in X (measurable with respect to all Radon measures—for example, Borel, Suslin and analytic).

An important criterion. 2) If X is Radon, then it is universally measurable, i.e. measurable in every containing space and for every measure.

Original source details: GELFAND-P000016

Uncertain reading. The source abbreviation after “measurable ∀” reads объемл. / объем.; the ending and a possible superscript stroke are not fully distinguishable. It has not been expanded to a complete source word.

Probability theory—probability is always defined.

3) An example of a broad class of Radon spaces. Distributions, continuous functions, etc.? Let E be a T. L. C.—a separable Fréchet space or their countable inductive limit. F is of the same kind. Then $\mathrm{Hom}(E, F)$ is of the same kind (equipped with any topology between pointwise and compact convergence). In particular, the dual space, the space itself ($R \longrightarrow E$). All spaces of generalized functions, of C^∞ functions. And the operator space $\mathcal{L}(S, S)$ is also a Radon space.

Original source details: GELFAND-P000016

Uncertain reading. Above or beside the closing parenthesis is a short note “ф-и” [functions]. A separate stroke after $\mathcal{L}(S, S)$ cannot be securely distinguished from the note and parenthesis; the candidate $\mathcal{L}(S, S)'$ remains uncertain.

Application. Consider a stochastic process given as a probability on the space of all functions with simple (pointwise) convergence (a measure in this space). Take the subspace of continuous functions. It is measurable in R^R.

GELFAND-P000017

Hence the probability that a function is continuous always exists. Let it equal 1. Then there is a probability distribution on this subspace, and it can be defined simply as a Radon measure on C. It is concentrated on a countable number of compact sets (equicontinuous). If the probability that a function is continuous is 1, then with probability 1 all these functions have a common modulus of continuity. This is true for every stochastic process (there exists a common mod. of continuity with probability 1).

[A large unwritten area; isolated small horizontal or curved strokes are visible along its boundary in the middle of the frame.]



Original source details: GELFAND-P000017

Uncertain reading. Only lower parts of isolated letter-like strokes survive along the horizontal boundary of the large unwritten area; no complete word is readable.

$12/\mathrm{X}$. Gindikin. Weil. G is a semisimple Lie group such that among the real comp. there are no matrices of order 2.



Uncertain reading. The line reads “вещ. комп.” [real comp.] and “матр. 2-го пор.” [matr. of 2nd order].

Original source details: GELFAND-P000017

Γ is a discrete subgroup; G/Γ is compact. Consider deformations of Γ: $\gamma(t)$, with a discrete group $\Gamma^{(t)}$ for every t. A trivial method uses inner automorphisms:

$$g(t)\gamma g(t)^{-1}.$$

The quotient group is the same. Under these conditions, all deformations are trivial. It suffices to prove that

$$H^1(\Gamma, \mathfrak{g}) = 0.$$

$\mathfrak{g}$ is the Lie algebra, carrying a representation of Γ. If Γ is not discrete, Weil’s theorem holds, although $H^1(\Gamma, \mathfrak{g}) \neq 0$.



Uncertain reading. The condition reads “не дискр.” [not discrete].

Original source details: GELFAND-P000017

There is a representation $\rho(\gamma)$ in V^d. Then the dimension is

$$p = (2g-2)d + i + i'.$$

GELFAND-P000018

Laurent Schwartz.

E — TVS LCH QC.

[A note leads from H in the abbreviation: Hausdorff.] A locally convex topological vector space, quasi-complete (every closed bounded set is complete). $\mathcal{H}$ is a Hilbert subspace of E.

$$\mathcal{H} \subset E.$$

[Beneath the inclusion: the map is continuous; at right: in $\mathcal{H}$ there is a Hilbert metric.] The Hilbert topology does not coincide with, but is stronger than, the topology in E. Example.



Uncertain reading. The inclusion reads $L^2 \subset \mathcal{D}^1$ / $L^2 \subset \mathcal{D}'$; the heavy upper-right mark above $\mathcal{D}$ resembles both 1 and a prime.

Original source details: GELFAND-P000018

Another example is the space of constants:

$$(\alpha \mid \beta) = \alpha\overline{\beta}.$$

$\mathcal{H} \in \mathrm{Hilb}(E)$ — all Hilbert subspaces.

[Repeated in the left margin: $\mathrm{Hilb}(E)$, with an arrow to the following heading.] An abstract conical structure. Addition and multiplication by positive numbers must be defined, and an order introduced.

$$\mathcal{H} \in \mathrm{Hilb}(E), \quad \lambda \geq 0, \quad \lambda\mathcal{H}, \quad \mathcal{H}_1 + \mathcal{H}_2, \qquad \mathcal{H}_1 \leq \mathcal{H}_2.$$

For $\lambda = 0$, $\lambda\mathcal{H}$ is the zero subspace. For $\lambda \neq 0$, $\lambda\mathcal{H}$ is the same space with scalar product

$$(h \mid k)_{\lambda\mathcal{H}} = \frac{1}{\lambda}(h \mid k)_{\mathcal{H}}.$$

$\mathcal{H}_1 + \mathcal{H}_2$. If the intersection is zero, it is a direct sum.

$$\|h\|_{\mathcal{H}_1,\mathcal{H}_2} = \inf\left(\|h_1\|^2_{\mathcal{H}_1} + \|h_2\|^2_{\mathcal{H}_2}\right), \qquad h = h_1 + h_2.$$

[Beneath the formula: over all possible representations.]



Uncertain reading. No square is visible on the left of the norm formula, whereas both norms on the right are squared. The subscript has a comma between the two Hilbert-space symbols.

Original source details: GELFAND-P000018

GELFAND-P000019

$$\mathcal{H}_1 \oplus \mathcal{H}_2.$$

A direct sum as abstract Hilbert spaces.

$$(h_1, h_2) \longmapsto h_1 + h_2.$$



Diagram and typed description. A triangular diagram: at upper left $H_1 \oplus H_2$, at upper right E, and below the quotient $H \oplus H/\mathrm{Ker}$. The horizontal arrow runs from left to right into E; a diagonal arrow runs down from the direct sum to the quotient; the other diagonal arrow runs up from the quotient to E. The indices on the letters at the lower vertex are uncertain. At right: “Obtain an injective map.”



The lower Hs retain no reconstructed indices; the stroke above Ker is shown as a slash.

Original source details: GELFAND-P000019

The infimum is precisely the definition of the norm in a quotient space. But a quotient of a Hilbert space is itself a Hilbert space. Thus this is a Hilbert norm. Suppose

$$H_1 \subset H_2 \subset E,$$

then we say that $H_1 \le H_2$. [Below the first inclusion, an arrow i: an operator of norm ≤ 1.]

$$\|h\|_{H_1} \ge \|h\|_{H_2} > 0.$$

All the properties are easy to check:

$$(\lambda\mu)H = \lambda(\mu H), \qquad (\lambda+\mu)H = \lambda H + \mu H.$$

And all the others.

$$\mathcal{H}_1 + \mathcal{H}_2 \ge \mathcal{H}_1, \qquad \lambda\mathcal{H} \ge \mathcal{H} \iff \lambda \ge 1.$$

[At right of the first inequality and beneath the second line are heavily cancelled entries.]



Uncertain reading. the original letters and signs beneath the dense hatching are unreadable

Original source details: GELFAND-P000019

These are the axioms of a convex cone. There are necessary and sufficient conditions for realizing an abstract conical structure in евкл. / свкл. space.



Uncertain reading. евкл. / свкл. space [the initial letter of the source abbreviation is uncertain]

Original source details: GELFAND-P000019

GELFAND-P000020

[The first word of the heading is cancelled: Strict; inserted above: strictly convex.] abstract cone:

$$h \geq h_1 \iff \exists h_2 \text{ unique (!), such that } h = h_1 + h_2.$$

It will be proved that the cone of Hilbert subspaces can be embedded in a linear space; in particular, this condition holds. One must prove that if $H_1 \leq H$, there is a unique H_2 such that $H = H_1 + H_2$. Instead, a cone in a linear space will be constructed to which this one is isomorphic.

$$E \text{ — space of kernels}, \qquad H \in \mathcal{L}(E^*, E).$$

$\mathcal{L}$ is the space of linear operators from the antidual space (antilinear [Cancelled: illegible] functionals) to E, with the weak topology in E.

Uncertain reading. *Cancelled.* an unreadable short word

Original source details: GELFAND-P000020

By definition,

$$H \geq 0 \underset{\text{def}}{\iff} \forall e^* \in E^*, \qquad (He^* \mid e^*)_{E,E^*} \geq 0.$$

$$e^* \in E^*, \quad f \in E, \qquad (e^* \mid f)_{E^*,E} = \overline{(f \mid e^*)_{E,E^*}}.$$

$$\mathcal{L}^+(E^*, E) \subset \mathcal{L}(E^*, E).$$

[Beneath the formula: the cone of positive kernels.] Example. E is a Hilbert space; $\mathcal{L}^+$ denotes positive Hermitian operators.



Uncertain reading. $\mathcal{L}^+$ [the corrected or overwritten symbol is uncertain]

Original source details: GELFAND-P000020

This is a strictly convex cone. The cone Hilb is isomorphic to it. Let $\mathcal{H} \in \mathrm{Hilb}(E)$. The corresponding kernel must be constructed.

$$e^* \in E^*; \qquad h \longmapsto (h \mid e^*)_{E,E^*}.$$

[Beneath the right side: e^* is antilinear.]

GELFAND-P000021

This is a continuous linear functional on H itself as well, since the embedding is continuous; but then $\exists He^* \in \mathcal{H}$ by means of which this scalar product is expressed.

$$(h \mid e^*)_{E,E^*} = (h \mid He^*)_{\mathcal{H}}.$$

We have obtained a map $E^* \longrightarrow \mathcal{H} \longrightarrow E$. It is easy to check that this is a weakly continuous map from E^* to E.

$$\mathcal{H} \xrightarrow{c} E \qquad \text{injectively embedded.}$$

It induces a map

$$E^* \longrightarrow H^* \cong \mathcal{H} \hookrightarrow E.$$



Uncertain reading. The dual Hilbert-space designation is written H^*; the last arrow is combined with an inclusion sign.

Original source details: GELFAND-P000021

We have a map $E^* \longrightarrow E$, as required. Let $h = Hf^*$; then we obtain

$$(Hf^* \mid e^*)_{E,E^*} = (Hf^* \mid He^*)_{\mathcal{H}},$$
$$(He^* \mid e^*) \geq 0.$$

$$\mathrm{Hilb}(E) \longrightarrow \mathcal{L}^*(E^*, E).$$



Uncertain reading. The superscript on $\mathcal{L}$ resembles $*$; $+$ is possible.

Original source details: GELFAND-P000021

One must prove that this is an isomorphism. It will be proved to be one-to-one and onto. Algebraically simple. Topological difficulties. If H is the kernel corresponding to $\mathcal{H}$, then $\forall e^* \in E^*$

$$He^* \in \mathcal{H}, \qquad \mathcal{H}_0 = \{He^* : e^* \in E^*\},$$
$$u, v \in \mathcal{H}_0 \qquad (u \mid v)_{\mathcal{H}_0} = (Hf^* \mid e^*)_{E,E^*} = \overline{(He^* \mid f^*)}_{E,E^*}.$$



Uncertain reading. The relation of u, v to e^*, f^* is not written here; a bar is visible above the last scalar product.

Original source details: GELFAND-P000021

GELFAND-P000022

Mackey's theorem: a set is bounded if it is weakly bounded. Proof/prove [uncertain source abbreviation: Док-ц. / Док-ть]: the unit ball is weakly bounded.



Uncertain reading. The abbreviation at the start of the second line is Док-ц. / Док-ть; the final descending loop favours ц. No complete source word is supplied.

Original source details: GELFAND-P000022

Examples.

$$E = \mathcal{D}', \qquad E^* = \mathcal{D}, \qquad \mathcal{H} = L^2.$$

$\mathcal{L}(\mathcal{D}; \mathcal{D}')$ is the space of kernels, operators from $\mathcal{D}$ to $\mathcal{D}'$. $\mathcal{H} = L^2$ defines a natural map $\mathcal{D} \longrightarrow \mathcal{D}'$. If $\mathcal{H}$ is arbitrary, we obtain an arbitrary positive operator, but by the kernel

theorem it is given by a generalized function of 2 variables.

$$H_{x,\xi} \in \mathcal{D}'(R^n \times R^n), \qquad \iint H_{x,\xi}\varphi(x)\overline{\varphi}(\xi)\,dx\,d\xi \geq 0.$$

There is a correspondence between Hilbert subspaces of $\mathcal{D}'$ and such kernels. $\mathcal{H}^1$ is the space of functions, [Cancelled: illegible] L^2 with 1st derivatives.

Uncertain reading. *Cancelled.* an unreadable word before L^2

Original source details: GELFAND-P000022

$$(f \mid g)_{\mathcal{H}} = \int \left(\lambda f\bar{g} + \sum \frac{\partial f}{\partial x_i}\frac{\partial \bar{g}}{\partial x_i}\right) dx.$$

$\lambda > 0$ [immaterial / written / imposed; on them / on it]



Uncertain reading. неважно / написано / наложено [immaterial / written / imposed; uncertain word]; на них / на нём [on them / on it].

Original source details: GELFAND-P000022

The dual is $\mathcal{H}^{-1}$. To $\mathcal{H}^1$ corresponds the kernel $-\Delta + \lambda$.



Uncertain reading. This line writes that to $\mathcal{H}^1$ corresponds the kernel $-\Delta + \lambda$; $\mathcal{H}^{-1}$ is written separately above.

Original source details: GELFAND-P000022

If we consider functions on a domain $\Omega \subset R^n$, these too are examples:

$$\mathcal{H}^{-1}, \quad \mathcal{H}^1, \quad \mathcal{H}_0^1 \quad \text{closure of } \mathcal{D}_0.$$



Uncertain reading. The last symbol resembles $\mathcal{D}_0$; $\mathcal{D}$ or $\mathcal{D}_\Omega$ are possible.

Original source details: GELFAND-P000022

One can obtain existence theorems for solutions as generalized functions.

GELFAND-P000023

Uncertain reading. Several oblique strokes are cut off at the top edge; their meaning is unclear.

Original source details: GELFAND-P000023

Kushnirenko's result on the entropy of dynamical systems. Arnold. [Cancelled: This / what] Entropy is the rate at which initial data are forgotten.

Uncertain reading. *Cancelled.* Это / что [This / what].

Original source details: GELFAND-P000023

$$0 \qquad h \qquad +\infty.$$

Beneath 0: with slow mixing. Beneath $+\infty$: strong mixing. Entropy for abstract dynamical systems (a measure-preserving transformation T). M^n is a smooth manifold. M^n is compact. T is smooth, the measure of $M = 1$ and is given by a Riemannian metric. Then entropy is always finite and is estimated by local properties of the transformation.

$$h(T) \leq n \log \lambda.$$

n is the dimension of the space. λ is the expansion coefficient of $(n-1)$-dimensional area. The bound is attained.

$$\lambda = \sup \frac{dS(Tx)}{dS(x)}.$$

Proof from the isoperimetric inequality. h is estimated by area. Entropy of a partition: $h(\xi) = -\sum p_i \log p_i$.

Original source details: GELFAND-P000023

Diagram and typed description. At right is a circle with a diagonal divider from upper left to lower right, a doubled branch towards the lower left and an arc to the right. A narrow light slit separates the two left strokes, with a thickened left endpoint; a separate thick mark projects beyond the circle at the right edge. These thickened marks do not establish arrow directions.



The doubled lower-left trace and terminal hooks are drawn without assigning arrow directions; their exact reading remains unresolved.

The partition $T\xi$ and the intersection.

$$h(T^{n-1}\xi, \dots, T^2\xi \cdot T\xi \cdot \xi) \qquad n^2 \text{ pieces},$$
$$\text{Pieces } \sim k^n,$$
$$\lim \frac{h(\dots)}{n} = h(\xi).$$

[Before the fraction, log is cancelled.]



Uncertain reading. Dots stand between $T^2\xi$, $T\xi$, ξ; alongside is written n^2 pieces. The limit's result resembles $h(\xi)$.

Original source details: GELFAND-P000023

For equal ones, $\sum \frac{1}{k} \log k = \log k$. Entropy of a dynamical system:

$\sup(h(\xi)) = h(T)$—Kolmogoro-skaya [the source's split form].



Uncertain reading. The final word is divided across lines as Колмогоро- / -ская; letters may be lost in the abbreviation.

Original source details: GELFAND-P000023

GELFAND-P000024

The entropy of a partition is estimated by the area of its boundary. And boundary areas are easy to add! For a one-to-one transformation one can put $n-1$ instead of n, and [Cancelled: illegible] there is the same kind of bound.



Uncertain reading. *Cancelled.* an unreadable word

Original source details: GELFAND-P000024

19/X. [Cancelled heading: Laurent Schwartz.] A physicist on representations of Lie algebras. Kostant / Konstant / End B. Kostant 93, 53 (1959).



Uncertain reading. Костант / Констант / Конец [Kostant / Konstant / End; uncertain Russian word].

Original source details: GELFAND-P000024

Povzner. Definition of free energy.

$$H = p^2 + u, \qquad \frac{-\ln \frac{1}{N!} \iiint_V^N e^{-\beta(H + \text{[cancelled]})}\, dx}{N}.$$



Uncertain reading. After H inside the exponent are several cancelled signs; $+$ and overlapping strokes are visible.

Original source details: GELFAND-P000024

N is the number of integrals.



Original source details: GELFAND-P000024

Uncertain reading. The last word after "number" resembles интегралов [integrals]; интервалов [intervals] / частиц [particles] are possible.

$$\frac{V}{N} = \text{const}, \qquad \beta = \frac{1}{T},$$

$$\lim_{\substack{N\to\infty \\ V/N=v=\text{const}}} \frac{-\ln \frac{1}{N!} \iiint_V e^{-\beta H}\, dx}{N} \qquad \text{free energy.}$$



Original source details: GELFAND-P000024

Uncertain reading. The first triple integral has N above and V below; only V is distinguishable in the repeated formula.

Entropy from the thermodynamic formulas:

$$S = -\frac{\partial F}{\partial T}, \qquad \text{pressure} \quad p = -\frac{\partial F}{\partial V}.$$

Entropy can be defined as follows:

$$\frac{1}{N} \sum_{i,j=1}^{N} u(x_i, -x_j) \le \xi.$$



Original source details: GELFAND-P000024

Uncertain reading. Between x_i and $-x_j$ a stroke resembling a comma is visible; a difference sign alone is possible. The letter on the right resembles ξ.

Find all such x.

GELFAND-P000025

Take the volume of this region in phase space. P. In the upper-right margin: $x_i \in V$.

$$\lim_{N\to\infty} \frac{\ln \frac{1}{N!} P(\xi, V/N)}{N} = S(\xi, v) \pm c \ln T.$$



Uncertain reading. Before $c \ln T$ there is a cross above a separate horizontal line: $\pm$ / $+$.

Original source details: GELFAND-P000025

ξ is energy. In the right margin: since весь / всё [all; the source ending is uncertain] phase space in the momenta.



Uncertain reading. Весь / всё фаз. пр-во по импульсам [all phase space in the momenta; source grammar retained].

Original source details: GELFAND-P000025

S is a convex function of 2 variables. On Wigner's work (1932) on quantum mechanics. Let $\Psi(x)$ give the probabilities by the familiar formula $|\Psi^2(x)|$ and

$$\widetilde{\Psi}(p) = \int e^{-ipx/\bar{h}} \Psi(x)\, dx.$$



Uncertain reading. The first line has $|\Psi^2(x)|$, whereas below there is $|\Psi(x)|^2$; the exponent has not been moved.

Original source details: GELFAND-P000025



Uncertain reading. The denominator in the exponent is an h crossed by a stroke: $\bar{h}$ / h.

Original source details: GELFAND-P000025

If

$$\int P(x,p)\, dp = |\Psi(x)|^2, \qquad \int P(x,p)\, dx = |\widetilde{\Psi}(p)|^2,$$

then what is P? It is [стр.; uncertain source abbreviation] in Wigner's work, and from this one can pass from classical mechanics to statistical mechanics.



Uncertain reading. Она стр. / она стро. [It is стр. / стро.; the abbreviation before "in the work" is unresolved].

Original source details: GELFAND-P000025

Kirillov on Thoma's work. Elmar Thoma. Math. Zeitschr. 84 (1964). If G is a discrete noncommutative group, its representations are difficult to describe, but the characters can be found (positive [continuous / irreducible] functions).

$$\begin{pmatrix} a & b \\ 0 & 1 \end{pmatrix}.$$

The characters are the same (the same formulas as over the real, finite and p-adic numbers).



Uncertain reading. Positive непр. functions: the abbreviation непр. is not expanded; continuous / irreducible are possible contextual expansions.

Original source details: GELFAND-P000025

Laurent Schwartz. $s \in G$—a Lie group. dx is Haar measure (two-sided). $\mathcal{H}$ is a [Cancelled: illegible] topological vector space.

Uncertain reading. *Cancelled.* an unreadable word

Original source details: GELFAND-P000025

U_s is a representation in it. $a \in \mathcal{H}$, which is infinitely differentiable with respect to the group; its orbit is C^∞ as a function of s.

$$s \longrightarrow A_a(s) = U_s(a \in \mathcal{H} \qquad \text{trajectory.}$$



Uncertain reading. Between U_s and a is an opening delimiter stroke: (/ {. No closing delimiter is visible on this line.

Original source details: GELFAND-P000025

GELFAND-P000026

$A_a : G \longrightarrow \mathcal{H}$, which is C^∞. Instead of the representation U_s, one can consider U_μ and U_φ.

$$U_\mu = \int U_s \, d\mu(s).$$

Trajectory

$$U_s A_a(t) = A_a(st).$$

If there is such a curve, then it is an orbit, i.e.

$$\mathcal{H} \supset \mathcal{H}^m \supset \mathcal{H}^\infty.$$

By $\mathcal{H}^m$: the trajectory is m times differentiable. By $\mathcal{H}^\infty$: the trajectory is C^∞. One can prove that $\mathcal{H}^{+\infty}$ is dense in $\mathcal{H}$ (by averaging). Define

$$\mathcal{H}^{-\infty} \supset \mathcal{H} \supset \mathcal{H}^m \supset \mathcal{H}^{+\infty}.$$

Point generalized functions. We shall consider $U_s A_a(t) = A_a(st)$ as a distribution with respect to Haar measure.

$$U_\varphi A_a(\psi) = A_a(\varphi * \psi).$$

Generalized points of the representation space.

$$\begin{gathered} A : \mathcal{D}'(G; \mathcal{H}), \\ \forall \varphi \in \mathcal{D}(G), \quad A(\varphi) \in \mathcal{H}, \\ U_\varphi A(\psi) = A(\varphi * \psi). \end{gathered}$$

In the right margin, beside two vertical downward arrows: generalized points—its/their definition and доп./долж. [source abbreviation] possess the convolution property.



Original source details: GELFAND-P000026

Uncertain reading. Ее / её / их опр. [its/their definition]; доп. / долж. облад. св-вом свёртки [the abbreviation before “possess the convolution property” is unresolved].

In particular, ordinary points possess these properties. Topology of $\mathcal{H}^{-\infty}$ [Cancelled: illegible] from $\mathcal{D}'$. $\mathcal{H}^{-\infty}$ will be complete.



Original source details: GELFAND-P000026

Uncertain reading. *Cancelled.* an unreadable word

The group also acts in $\mathcal{H}^{-\infty}$. There the group acts C^∞.

$$U_\xi^{-\infty} A = \underbrace{A * \check{\xi}}_{\xi \text{ — finite supp.}}$$



Original source details: GELFAND-P000026

Uncertain reading. The index and final symbol resemble ξ / S / ζ; the final symbol has an inverted hat.

If $\xi = \delta$, then the original representation is obtained.

GELFAND-P000027

In particular, the Lie algebra also acts (δ').

. . . . . .

Problem. $\square X = A$, an equation with constant coefficients. This equation is solvable (Ehrenpreis). Let A be Lorentz invariant. Then there exists a Lorentz invariant X.

$$\mathcal{D}X = A.$$

The same for an arbitrary group and differential operator—a problem!

Uncertain reading. In the repeated formula, the letter before X is rounded: $\mathcal{D}$ / D; in the first formula there is a rectangle $\square$.

Original source details: GELFAND-P000027

Solution for the Lorentz group.

$$\square X = A.$$

One must [Cancelled: illegible] study Lorentz invariant functions.

Uncertain reading. *Cancelled.* a short unreadable word

Original source details: GELFAND-P000027

Consider $R^n \setminus 0$. This is $T(x_1^2 + \cdots + x_n^2 - x_0^2)$ of one variable. All непр. [unexpanded source abbreviation] because of noncompactness (otherwise one can average).



Uncertain reading. The source writes “Все непр. из-за некомпактности”; the adjective is abbreviated непр. and its expansion is not established.

Original source details: GELFAND-P000027

For X, seek an invariant distribution of one variable. The wave operator turns into an operator of one variable, but with variable coefficients. But for one variable it is solvable. But if there is a group with 2 invariants, then instead of a singularity at 1 point one obtains lines of singularities, etc. But our solution has a [chosen / removed] point. How everywhere? Use the [result / solution; uncertain source abbreviation] that a generalized function, invariant everywhere except кон. [source abbreviation], can be распр. [source abbreviation] to the origin. Power growth follows from Lorentz invariance.



Uncertain reading. In the final lines: выбр. точкой [a chosen / removed point]; рез. / реш. [result / solution]; кроме кон. [except кон.; unexpanded abbreviation]; в начало / в начале [to/at the origin]. The expansions of the abbreviated words remain uncertain.

Original source details: GELFAND-P000027

GELFAND-P000028

The Lorentz group is semisimple and the space is finite dimensional. A finite dimensional representation of a semisimple Lie group has a fixed point (e.g. at однор. 0 [uncertain source abbreviation]) (one of the definitions of a semisimple group).



Uncertain reading. In parentheses: при однор. 0 / при одноп. 0; the source abbreviations are retained.

Original source details: GELFAND-P000028

Another problem. G is a Lie group. A Lie operator X is an infinitesimal translation $Xf(g)$. Consider a polynomial in Lie operators. How to find elementary solutions? (fund.) $PE = \delta$.

$P(X_1, \ldots, X_n)$ a polynomial in Lie operators.

For [compact / finite; uncertain source abbreviation] groups this is probably false.



Original source details: GELFAND-P000028

Uncertain reading. The last faint sign in комп. [compact] is indistinct; кон. [finite] remains an alternative. The abbreviation is not resolved.

On the torus there is no elementary solution. There is no solution for the torus. But the torus has a fundamental group. And for the rotation group

$$\frac{\partial}{\partial x} - \alpha \frac{\partial}{\partial y}.$$



Original source details: GELFAND-P000028

Uncertain reading. The coefficient α has a small upper curve: α / α^2. No separate exponent 2 can be distinguished on the signs ∂.

In the right margin: α—irrational, good. approx.



Original source details: GELFAND-P000028

Uncertain reading. The last abbreviations in the margin are хорош. / хорошо [good/well]; аппрокс. [approx.]. Below the first is a small detached dark A/1-like stroke whose role is not clear.

Rotat. also has everywhere мн./им. [source abbreviation] singular.



Original source details: GELFAND-P000028

Uncertain reading. Before сингуляр. [singular.] is the short abbreviation мн. / им.

group?



Original source details: GELFAND-P000028

Uncertain reading. The separate following line reads группа? [group?]. No explicit connecting sign establishes its relation to the preceding abbreviated sentence.

Nontrivial even for operators of the 1st order.

$$E(P\varphi) = \varphi(0).$$

Suppose that for a [noncommutative / noncompact; uncertain source abbreviation] group everything will be in order. For the circle...



Uncertain reading. Некомм. / некомп. [noncommutative / noncompact]; the abbreviation before "group" is unresolved.

Original source details: GELFAND-P000028

GELFAND-P000029

2/XI. Kirillov. Elmar Thoma. 3 works, representations of countable noncommutative discrete groups. G. There is an explicit form for certain groups of $+$ definite functions constant on conjugacy classes of elements—extreme points of the set of such functions.

$$f(g) \quad + \text{ definite, if } \quad \|f(g_i g_j^{-1})\| \gg 0 \quad + \text{ definite.}$$
$$g_1, \ldots, g_n \quad \text{any collection of elements.}$$

$f(e) = 1 \longleftarrow$ a convex set M.

$$f(g_1 g_2) = f(g_2 g_1) \quad \text{(constant on conjugacy classes of elements),}$$
$$f(g) = f(g_1 g g_1^{-1}).$$

The extreme points are called characters of непр. [source abbreviation] representations.



Uncertain reading. After "characters" is written непр. / нер.; the abbreviation is not expanded.

Original source details: GELFAND-P000029

Example: $g \longrightarrow T(g)$, $\frac{1}{n} \operatorname{Sp} T(g)$ is an example of such a function. If the representation is irreducible, such functions form extreme points—easy to check. (The representation is uniquely determined by this function.) There are groups for which describing the representations is impossible (for set theoretic reasons—there are many of them), but the characters exist and are given by formulas.

$$\begin{pmatrix} \alpha & \beta \\ 0 & 1 \end{pmatrix} \quad \text{group of affine transformations of the line,}$$
$$x \longrightarrow \alpha x + \beta, \qquad \alpha, \beta \quad \text{rational.}$$

If α and $\beta \in$ a finite field (mod p), how to find all traces (irreducible representations). Representations—complex numbers. Not done if the representation is given

with $\alpha, \beta \in (\mathrm{mod}\, p)$.

$$\begin{pmatrix} \alpha & \beta \\ 0 & 1 \end{pmatrix} \begin{pmatrix} \gamma & \delta \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} \alpha\gamma & \alpha\delta + \beta \\ 0 & 1 \end{pmatrix}.$$

In the right margin: done for the rationals. One dimensional representations—all—$e^{\alpha \frac{2\pi i}{p}}$. $(p-1)$ representations depending only on α—characters of the multiplicative group.



Uncertain reading. In the exponent one can see $\alpha\, 2\pi i/p$.

Original source details: GELFAND-P000029

[Cancelled note; partial reading of the visible writing:]





Uncertain reading. Two fractional expressions, 0 and horizontal strokes are crossed out; bracket-like strokes run down the left and below. The first fraction reads $1/x$. The horizontal arrow and the second fraction cannot be read securely through the cancellations.

Original source details: GELFAND-P000029

GELFAND-P000030

$$\sum k_i^2 = p(p-1),$$

$$\sum{}' k_i^2 = p(p-1) - \underbrace{(p-1)}_{\text{one dim.}} = (p-1)^2.$$

In the right margin:

> Group ring—direct sum of matrix rings and precisely $\sum k_i^2$.

Conjecture: another representation of order $p-1$. Representation—a functor with an unknown field. For a field of infinite ord. there is an infinite dimensional (α, β).



Uncertain reading. Беск. пор. ест. бесконечномерн. [infinite ord., there is an infinite dimensional]; the connection of this abbreviated line to "functor with an unknown field" is not explicit.

Original source details: GELFAND-P000030

$\begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix}$ find the restr. of the repr. to such a group,

$$\begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix} \begin{pmatrix} 1 & \beta' \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} 1 & \beta+\beta' \\ 0 & 1 \end{pmatrix}.$$

Its one dimensional representations

$$\begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix} \longrightarrow e^{\frac{2\pi i k}{p}\beta}.$$

$\begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix}$ normal subgroup.

Transformations with [a short word cancelled]

$$\begin{pmatrix} \alpha & 0 \\ 0 & 1 \end{pmatrix} \begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix} \begin{pmatrix} \alpha^{-1} & 0 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} 1 & \alpha\beta \\ 0 & 1 \end{pmatrix}.$$



Uncertain reading. Between "with" and the matrix is a small obliterated sign or word.

Original source details: GELFAND-P000030

β is not needed (it commutes).

$$\begin{pmatrix} 1 & \beta \\ 0 & 1 \end{pmatrix} \longrightarrow T_\beta, \qquad T_{\beta_1+\beta_2} = T_{\beta_1} T_\beta.$$

[Cancelled: illegible] commute.



Original source details: GELFAND-P000030

Uncertain reading. *Cancelled.* a short word before коммут. [commute]



Original source details: GELFAND-P000030

Uncertain reading. No index 2 can be distinguished on the last T_β.

Decompose the space into eigenvectors with respect to T_β.

$$T_\beta e_k = e^{\frac{2\pi i k}{p}\beta} e_k,$$
$$S_\alpha T_\beta S_\alpha^{-1} = T_{\alpha\beta},$$
$$T_\beta S_\alpha e_k = e^{\frac{2\pi i}{p}\alpha k\beta}(S_\alpha e_k),$$
$$S_\alpha e_k = e_{\alpha k}.$$



Original source details: GELFAND-P000030

Uncertain reading. The source writes $S_\alpha T_\beta S_\alpha^{-1} = T_{\alpha\beta}$ and the factor $\alpha k\beta$ in the exponent beside $T_\beta S_\alpha e_k$. Cancelled signs lie below the denominator of the latter exponent.

At the lower right: multipliers can be taken equal to 1.



Original source details: GELFAND-P000030

Uncertain reading. The short word before “can” reads множ. / норм.; “equal” is plural in the source.

There will remain $(p-1)$ vector. It is written how it acts. A more beautiful realization.

$$x \longrightarrow \alpha x + \beta.$$

[At right: aff. line over a finite field.] $f(x)$ — functions on it.

$$T_g f(x) = f(\alpha x + \beta).$$

Const is invariant, so this repr. is reduc. We shall consider functions for which

$$\sum_x f(x) = 0 \qquad (\int = 0).$$

This is a $(p-1)$-dimensional repr.

$$\mathrm{Sp}(T_g) = \begin{cases} 1 & \text{when } \alpha \neq 1, \\ 0 & \text{when } \alpha = 1,\ \beta \neq 0, \\ p & \text{when } \alpha = 1,\ \beta = 0. \end{cases}$$



Original source details: GELFAND-P000031

Uncertain reading. In the third condition, the looped sign after $\alpha =$ resembles 1, α or p; the coloured 1 is a provisional candidate.

[Repeated separately at left beneath the brace: $\alpha \neq 1$. At right, underlined: irreducible.]

$$x = \alpha x + \beta, \qquad x = \frac{\beta}{1-\alpha}.$$

Must subtract the trace.

$$\mathrm{Sp}\, T_g = \begin{cases} 0 & \alpha \neq 1, \\ -1 & \alpha = 1,\ \beta \neq 0, \\ p-1 & \alpha = 1,\ \beta = 0. \end{cases}$$



Original source details: GELFAND-P000031

Uncertain reading. Heavy overwritten or cancelled strokes stand before 1 in the second condition. The earlier sign $\neq$ / $=$ cannot be established securely.

How is this related to dyn. systems?

Let α and β be real.

$$\beta \longrightarrow T_\beta, \qquad T_{\beta_1+\beta_2} = T_{\beta_1} T_{\beta_2},$$
$$S_\alpha, \qquad S_{\alpha_1\alpha_2} = S_{\alpha_1} S_{\alpha_2}, \qquad S_\alpha^{-1} T_\beta S_\alpha \blacktriangleleft = T_{\alpha\beta}.$$



Original source details: GELFAND-P000031

Uncertain reading. Between the last S_α and $=$ is a small separate filled wedge pointing left. Its visible shape is retained; its meaning has not been established.

[Horizontal line.] How can they be found? They can be brought to diagonal form (the repr. is unit.).

$$T_\beta f(\chi) = \chi(\beta) f(\chi).$$

[Cancelled at right of the formula: $\chi(\beta)$.] Bring to an operator of multiplication by a function, where

$$\chi(\beta_1 + \beta_2) = \chi(\beta_1)\chi(\beta_2).$$

[In the right brace:] $f(\chi)$ — a vector function, $\forall\chi$ — to a space [пр-ву; abbreviated in the source].



Original source details: GELFAND-P000031

Uncertain reading. The sign before χ resembles $\forall$; пр-ву is an abbreviation for “to a space”. The source does not write out the full word.

[In the left margin, rotated: dyn. syst. on the addit. group — $\longrightarrow$ the mult. group acts on it.]

$$S_\alpha f(\chi) = f_1(\chi),$$

$$T_\beta f_1(\chi) = T_\beta S_\alpha f(\chi) = S_\alpha T_{\alpha\beta} f(\chi) = \chi(\alpha\beta) f_1(\chi).$$



Original source details: GELFAND-P000031

Uncertain reading. Before $\chi(\alpha\beta)$ in the last equality, a symbol resembling S / S_α is heavily cancelled. Beneath the cancellation is $\longleftarrow$; beneath $\chi(\alpha\beta)$ is $\longrightarrow$. The cancelled sign remains unreadable.

[In the lower-right margin, within a stepped outline:] Each point — into an everywhere dense [пл.; uncertain abbreviated reading] set.



Original source details: GELFAND-P000031

Uncertain reading. The source abbreviation before мн-во [set] resembles пл. [dense]; its middle strokes remain uncertain.

Ergodic system. With different measures — different repr. Haar measure — cont./irred. repr. / gr. [непр. пр. / непр. гр.; uncertain expansions]

Original source details: GELFAND-P000031

Uncertain reading. The final source abbreviation resembles пр. / гр. [repr. / gr.]. The preceding непр. may abbreviate continuous or irreducible; the full words are not written. These expansions remain alternatives.

GELFAND-P000032

$\overline{\chi}_K(\alpha)$. [Beneath it:] norm. char.



Original source details: GELFAND-P000032

Uncertain reading. The barred symbol resembles $\overline{\chi}_K(\alpha)$; the index may be Cyrillic к and the argument may be g. The first source abbreviation beneath it resembles норм. [norm.]; its full form is not written.

$$\begin{array}{ccc|c} \begin{pmatrix} \alpha \neq 0 & \beta \\ 0 & 1 \end{pmatrix} & 0 & 0 \\ 1 \begin{pmatrix} 1 & \beta \neq 0 \\ 0 & 1 \end{pmatrix} & -\dfrac{1}{p-1} & 0 \\ 1 \begin{pmatrix} 1 & 0 \\ 0 & 1 \end{pmatrix} & 1 & 1 \end{array}$$



Original source details: GELFAND-P000032

Uncertain reading. The upper-left entry reads $\alpha \neq 0$: the final sign is a closed loop. A separate 1 precedes each of the two lower matrices.

[To the right of the first upper 0: Char. for finite groups.] If one passes to the lim. as $p \longrightarrow \infty$. [From the line about the limit, $\nearrow$ points to the lower-right 1.]



Original source details: GELFAND-P000032

Diagram and typed description. The left marginal word has two underlines and resembles Одном / Одному [one / to one, literal candidate readings]. Below it is a long low curve with outward arrowheads at both ends; the right end is beneath the limit. The label remains unresolved.

What remains for rational numbers.

Lemma. $G, G_0 \subset G$ [beneath G_0: norm. div.]. f — pos. def., $f(e) = 1$, const. on conj. M — the set of them. Consider $f|_{G_0}$. Also consider functions satisfying the same [a short entry is cancelled] conditions on G_0.

Uncertain reading. The short entry before the source abbreviation усл. is crossed out with heavy horizontal strokes; its letters cannot be established.

Original source details: GELFAND-P000032

Consider H_{G_0} — their extreme points. They coincide with the extreme points of the original / countab. [исх. / сч.; uncertain source abbreviation] gr.



Uncertain reading. The joined final source abbreviation resembles исх. гр. [original gr.]; сч. гр. [countab. gr.] remains an alternative. The full source words are not written.

Original source details: GELFAND-P000032

(For countable groups.) One must count how many conj. classes there are and then seek the representing. From + def. [Cancelled; provisional reading: something [чего-то; uncertain reading].] it follows that there are no other repr.

Uncertain reading. The crossed-out entry after Из + опр. [From + def.] resembles чего-то [something]; the heavy overlapping strokes do not establish a complete secure word.

Original source details: GELFAND-P000032

[In the left margin: 2nd work.]

Infinite symmetric group: permutations of the natural sequence (only a finite number of elements move — for countability). Conj. classes of elements are specified by cycles. — [A separate horizontal stroke at the left; a short entry is cancelled.]

Uncertain reading. The short sign or word before “cycle lengths” remains unreadable beneath two heavy horizontal strokes.

Original source details: GELFAND-P000032

Cycle lengths determine the conj. class of elements.

$$(n_2, n_3, \ldots),$$

only a finite number $\neq 0$.

GELFAND-P000033

Every character

$$\chi(n_2, n_3, \ldots) = \prod a_k^{n_k}.$$

a_k — a sequence of real numbers. For a finite group it is more complicated. [Above “finite”: (arbitr.); above “more complicated”: (char.) with a brace pointer.] (Frobenius, Young, Young diagr. — classification of tensors.) G_n — a subgr. isom. to the original — the first n stay in place. And the char. is the same (depends only on cycle lengths). From this follows multiplicativity of the char. in cycle length, and further. 3rd work.

There are countab. noncompact gr. Practically all are bad. Char. Type 1: there is a norm. div. G_0 such that G/G_0 is finite. [Inserted beneath norm. div. G_0:] isom. G / comm./compact G [изом. / ком.; uncertain source abbreviations].

Uncertain reading. The inserted source abbreviation resembles изом. G [isom. G]; ком. G [comm./compact G] remains an alternative with uncertain expansion. Its joined middle strokes remain uncertain.

Original source details: GELFAND-P000033

(Necessary and sufficient condition.)

$$\text{Thoma} \qquad \left.\begin{matrix}\text{Math. Zeits.}\\ \text{Math. Ann.}\end{matrix}\right\} \ 1964.$$

These are his first 3 works. Not done: characters for the gr. of matrices of order 2 over the field of rational numbers. What is a repr. of an alg. group with an unknown field?

$$\begin{pmatrix} \cdot & \cdot \\ 0 & 1 \end{pmatrix} \qquad \text{Unknown field}.$$

[At right: So that for char. of fields it gives the usual expr.] A way of writing char. of $\forall$ alg. gr. [A short entry is cancelled.]



Uncertain reading. After алг. гр. [alg. gr.] a short entry is heavily cancelled; its beginning resembles Это... [This...]. The remaining strokes do not establish the text.

Original source details: GELFAND-P000033

Repr. of types 1 and 2 are recovered from char. G is specified by a scheme of semigr. alg., assigned to $\forall$ field. Char. also. [Cancelled; provisional reading: Function / Func. [Функция / Функц.; uncertain reading]]

Uncertain reading. The cancelled source word resembles Функция / Функц. [Function / Func.]; the ending is obscured by horizontal strokes.

Original source details: GELFAND-P000033

Character — a functor of the field K. [At right: $\mathcal{F}(\cdot)$.] (A formula corresponds to the field K.) If there is an equality for several fields, then also always. (Similarly, e.g. only for finite ones.)

$$\begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix} \quad \text{with } \det = 1.$$

The conj. class of elements is determined by $\underbrace{\alpha + \delta}$. [Beneath the source abbreviation опр.: quant. At right: Sp.]

GELFAND-P000034

What do we know? Char. of the gr. of real matr. with det $= 1$. Complex —

$$\sigma(g) = \frac{\pi(\lambda_g) + \pi(\lambda_g^{-1})}{|\lambda_g - \lambda_g^{-1}|^2}.$$

[At right: Gelfand, Naimark, 1947.] $\pi(\lambda_g)$ — a mult. character of nonzero complex numbers. Real.

$$\sigma(g) = \begin{cases} \dfrac{\pi(\lambda_g) + \pi(\lambda_g^{-1})}{|\lambda - \lambda^{-1}|} & \text{if } \lambda \text{ is real.,} \\ 0 & \text{if } \lambda \text{ is complex.} \end{cases}$$

$$\sigma'(g) = \begin{cases} \dfrac{\pi(\lambda_{\min})}{|\lambda - \lambda^{-1}|} & \text{if } \lambda \text{ is real.,} \\ \dfrac{\pi(\lambda_g) + \pi(\lambda_g^{-1})}{|\lambda - \lambda^{-1}|} - \dfrac{\pi(\lambda_g) - \pi(\lambda_g^{-1})}{\lambda_g - \lambda_g^{-1}} & \end{cases}$$

[No condition is written at right in the second row of the last brace. In the left margin, rotated:] Vanguten / Vantsuten, 1947.

Original source details: GELFAND-P000034

Uncertain reading. The marginal surname resembles Вангутен / Ванцутен [Vanguten / Vantsuten]. Its joined middle strokes remain uncertain; the written year is 1947.

[Cancelled; provisional reading: repr. [предст.; uncertain reading]]

Original source details: GELFAND-P000034

Uncertain reading. The crossed-out source abbreviation resembles предст. [repr.]; a horizontal cancellation and two long strokes below it obscure parts of the letters.

p-adic numbers.

$$\sigma(g) = \begin{cases} \dfrac{\pi(\lambda_g) + \pi(\lambda_g^{-1})}{|\lambda_g - \lambda_g^{-1}|} & \text{if } \lambda_g \in K \text{ is real.,} \\ 0 & \lambda_g \overline{\in} K. \end{cases}$$

[Nonmembership is written in the source with a bar over $\in$. At right, beside a long vertical stroke:] Gelfand, Graev, 1963. Finite field.

$$\sigma(g) = \begin{cases} \pi(\lambda_g) + \pi(\lambda_g^{-1}) & \lambda \in K, \\ 0 & \lambda \overline{\in} K, \end{cases}$$

[At right: Frobenius, 1895.]

$$\sigma'(g) = \begin{cases} 0 & \lambda \in K, \\ -\pi(\lambda_g) - \pi(\lambda_g^{-1}) & \lambda \overline{\in} K. \end{cases}$$

GELFAND-P000035

Nat. [рз. / раз. / рез.; uncertain abbreviation] hist. was that one must pass to the group of adeles.



Original source details: GELFAND-P000035

Uncertain reading. The initial source abbreviations resemble Ест. [nat.] рз. ист. [hist.]; in the middle one only joined p-з-like strokes are distinct. The earlier раз. / рез. remain alternatives. The middle abbreviation is not expanded.

Gr. of adeles — the direct $\sum$ of the gr. of all p-adic numbers. In it there are rational numbers — the diagonal.

Vishik.

Original source details: GELFAND-P000035

Diagram and typed description. Beneath the surname is a narrow strip with irregular long edges and transverse strokes. Two strokes near the left meet at the lower edge; the following dividers have unequal spacing. No labels are written inside.



What one should work on in diff. eqns. For a lin. oper. with finite kernel and cokernel an index is introduced.

$$k = \dim \ker T, \qquad \ell = \dim \operatorname{coker} K, \qquad æ = k - \ell.$$



Original source details: GELFAND-P000035

Uncertain reading. The letter after coker resembles K. The looped index sign is represented by the provisional candidate æ; its exact letter has not been established.

1) If replaced by $\|T - T_1\| < \varepsilon$, then æ does not change. 2) Adding a compl. cont. [вп. непр.; abbreviated reading] oper. does not change the index.

Original source details: GELFAND-P000035

Uncertain reading. The source writes Доб. вп. непр. опер. [Adding a compl. cont. oper.]. The joined abbreviations are shown in their written form; the full words are not written out.

æ allows classification of elliptic eqns. on manifolds. (Atiyah and Singer) Homotopy classification. Vishik considers that the index is the only homotopy inv. A syst. with const. coeffs. in a ball has [a short entry is cancelled] as one more homot. inv. [Beneath this is a long cancelled parenthetical entry.]



Uncertain reading. A short entry after имеет [has] is cancelled; its descending loop remains visible. Beneath it a long parenthetical entry is crossed out with two horizontal lines; its ending resembles инв. [inv.]. The text remains unreadable.

Original source details: GELFAND-P000035

Can any one be transformed into any other (a large number of eqns. — stable). The question has an analogous meaning for a different class of nonlinear eqns. What is æ? What are the kernel and cokernel? $\sim$ a finite kernel. Quasilin. eqn.

$$Tu = v.$$

[At right: u — a manifold. It is required to be finite dimensional.] Principal part of a nonlinear eqn. Cokernel $\sim$ [a short wavy line]. [At right: In each point, linearize the eqn., and everywhere it is the same.] Problem: study the index of a nonlinear elliptic eqn. (This is a question of interpretations.) Quasilin.

$$\sum A(\dots u_0)\frac{\partial^2 u}{\partial x^2}.$$



Uncertain reading. The lower sign on u in the argument of A resembles 0 / ω; the joined dark strokes do not establish which. The dots and absence of sum indices are retained.

Original source details: GELFAND-P000035

16th. Linnik — "How to use funct. anal. in probability theory".

GELFAND-P000036

I. I. / I. M. Pyatetsky-Shapiro.



Uncertain reading. I. I. / I. M. Pyatetsky-Shapiro. The second initial is merged; its exact reading is not established.

Original source details: GELFAND-P000036

(Ilya Iosifovich). Linnik's work.

$$x^2 + y^2 + z^2 = m.$$

[At left:] ϕ.

Original source details: GELFAND-P000036

Uncertain reading. A separate looped sign with a right vertical stroke in the left margin resembles ϕ. No meaning is written beside it.

For which m are there integral solutions? It is known that solutions do not always exist. (When $m = 8a + 7$, there are no solutions.) [Beneath $8a + 7$: mod 8.] How the solutions are distributed on the surface of the 3-dimensional sphere. Rad. $m^{1/2}$.

Original source details: GELFAND-P000036

Diagram and typed description. Two irregular rounded contours, labels 1 and $\sqrt{m}$, diverging lines, three heavy points and a thick inner junction with a small leftward arrow. The junction of the inner strokes is not wholly clear.



Select a region on the unit sphere and see how many points project into it.

$$\frac{H_2(m)}{H(m)} \approx \text{mes}\,\Omega.$$



Original source details: GELFAND-P000036

Uncertain reading. The numerator subscript resembles 2; Ω remains an alternative. Beneath $H(m)$: total number. At right: an asymptotic exists; below: but there are m for which few. The last abbreviated entry is not wholly clear.

This holds under the following condition: if q is a prime m ranges over / пробл. [пробег. / пробл.; uncertain abbreviation] numbers: $\xi^2 + m = 0 \pmod q$ is solvable.



Original source details: GELFAND-P000036

Uncertain reading. Underlined: m пробег. / пробл. числа [m ranges over / пробл. numbers; uncertain abbreviated readings]. The middle and final strokes are joined; the second candidate is not expanded.

For any / small [любой / небол.; uncertain readings] such seq. this theorem holds.



Original source details: GELFAND-P000036

Uncertain reading. The joined word after For resembles любой [any]; it is followed by такой послед. [such seq.]. небол. [small; abbreviated reading] remains an alternative for the dark initial strokes.

Using q, construct a dyn. system on the sphere, whose behaviour obeys prob. laws: Fix q, consider [a short entry is cancelled] an integral point on the sphere and all orthog. matrices with entries of the form a/q.

Original source details: GELFAND-P000036

Uncertain reading. Before integral point, a short entry is cancelled with several dense strokes; the text has not been read.

(a is an integer.) There are finitely many of them, but rational [рацио.; uncertain abbreviation]



Original source details: GELFAND-P000036

Uncertain reading. After but the abbreviated source reading resembles рацио. [rational]. Its joined strokes remain uncertain; the complete word is not written.

They carry an integral point to a non-integral one. But among them there are finitely many carrying an integral point to an integral one. Construct such a flow (to every point its own orthog. matrix). e is a characteristic fn.

$$e(Tx) + e(T^2x).$$

[Rightward arrow: to Linnik, underlined.] This is a Markov chain.

GELFAND-P000037

Povzner. Naum Yakovlevich. Plan of stat. physics. Math. works.

Ruelle	2–3 works
Yang Lee	1 work

This is a revolution. Everything known mathematically about stat. physics. Kac — models. Problem. (Elem.)



Original source details: GELFAND-P000037

Diagram and typed description. A vertical with u, a horizontal with 0 at right; the curve falls steeply below the horizontal and then rises towards it at right. The right part is thickened. At left: grows. The precise junction of the thick strokes is not wholly clear.



$$\min \sum_{i,j=1}^{N} u(x_i - x_j).$$

x ranges in 2-dimensional space.

Set of x. There is a C such that the min. config. has everything in a sphere of rad. C. (Easy to show N^2, but in the case of a sphere N^3.) [Separate thick lines beneath N^2 and case.]

16/XI. A lin. operator in Hilbert space has an inv. subspace. Solved!!! Bull. Amer. Math. Soc.

Original source details: GELFAND-P000037

Uncertain reading. The entry reads Lui de Brange and ...; the surname ending is looped, with a possible final s. Year: 1964.

1964. Connected with Livshits's theory. [Below at left:] ϕ / ψ.

Original source details: GELFAND-P000037

Uncertain reading. A separate sign in the left margin has two upper strokes and a right lower loop; graphic candidates are ϕ / ψ. There is no caption.

det by Schur. One must take the substitution group, and instead of all — repr. det of a + definite matrix is a + definite matrix.

Arnold. Consider a dyn. system and the corresponding quantum system.



Original source details: GELFAND-P000037

Diagram and typed description. A nearly round contour around the intersection of a vertical and a horizontal rightward arrow labelled x. Inside are irregular vertical and wavy strokes; some intersections merge.



$$\psi(x)e^{\frac{i}{h}S(x)}.$$

Quantum particle.

$$\psi \in \mathcal{D}(\mathbf{R}^n), \qquad S(x) = \int p\,dx.$$

h is Planck's const. Seek the solution in the same form. A semiclass. asymptotic is obtained.



Original source details: GELFAND-P000037

Diagram and typed description. Unlabelled axes. A heavy point lies at right above the horizontal; an arch goes up and right from it, then down to a right arrowhead. No continuation beyond the frame is shown.



GELFAND-P000038

$$\frac{\psi(\xi(x))e^{\frac{i}{h}(S(x)+\int p\,dx)}}{\sqrt{\dfrac{D(X)}{D(x)}}}.$$

Uncertain reading. The argument of ψ is overwritten: $\xi(x)$ / x. The sign after $S(x)$ resembles $+$ / t. Under the radical the upper argument letter resembles X / x; no separate index is visible.



Original source details: GELFAND-P000038

[At right: norm. factor.] Holds only as $h \longrightarrow 0$, but when $D \neq 0$. (Through t, map. D is the det of our T in terms of the old ones.) The solution of the question reduces to top. inv. of a manifold. (At a turning point.) Index. [At right: During mov. the cohomology class changes.]



Original source details: GELFAND-P000038

Uncertain reading. При движ. меня. класс когомологий: During mov. the cohomology class changes. The first abbreviated words are joined; the final letters of the long word are clearer.

Linnik. Ideals of rings of fns. from the point of view of appl. to statistics. A. Cartan — on ideals of rings of holom. fns. (47 and 50). Analyt. sheaves appear (first with Oka). Appl. of the apparatus of analyt. sheaves. What is statistics?

$$(X, A, \mu) \xrightarrow{T} (Y, B).$$

[Beneath the first parentheses: space with measure. Beneath the second: space with a σ-system.] T is a measurable mapping (observation fn.). X is what we observe. The measure on Y is directly induced [a short entry is cancelled] from X.

Original source details: GELFAND-P000038

Uncertain reading. Between directly induced and from X, a short entry is heavily crossed out; the exact text is not established.

X is Euclidean space. A — Borel sets. μ — measure.



Original source details: GELFAND-P000038

Uncertain reading. In parentheses: об. набор. мер, мажор. / массы 1-й / 1-ой [об.; set of measures; major. / mass; 1st, uncertain abbreviated readings]. The joined strokes before 1-й are closer to мажор.; the exact abbreviation and ending remain uncertain.

There is a family of measures $\{P(x, \theta)\}$. [Beneath $P(x, \theta)$: given by a density.] We want to obtain info. about the parameter by observing X.

$$x_1, \ldots, x_n \in N(a, 1).$$

[Beneath $N(a, 1)$: Gaussian family. At right: 1 is precision, a is the parameter.]

$$x_i = a + \delta_i, \qquad \overline{X} \text{ arithm. mean}$$

δ_i — normal.

GELFAND-P000039

Stat. — finding estimates. Testing hypotheses $a = a_0$. $\theta \in \Omega$. (Ω — comp. in $\mathbf{R}^n$; region / δ_n [обл.; uncertain reading].)

Uncertain reading. After comp. in $\mathbf{R}^n$ a short entry resembles обл. [region] / δ_n; the exact reading remains uncertain.

Original source details: GELFAND-P000039

Null hypothesis $H_0 = \theta \in \omega$ (subspace). Testing with a fixed sample with randomization. A selected test is a fn. of the observations

$$0 \leq \varphi(x_1, \ldots, x_n) \leq 1.$$

[Beneath the formula: prob. meaning.] Observe with a random fn. and randomize with probabilities φ, $1 - \varphi$. [Cancellation at left and a separate sign below.]

Uncertain reading. A short entry is heavily cancelled. Beneath it is a separate sign resembling π / Π; no meaning is written.

Original source details: GELFAND-P000039

Simple test

$$\varphi = \begin{cases} 0 \\ 1 \end{cases}$$

reject or accept. [Downward arrow to the example:]

$$|\overline{x} - a_0| > \varepsilon \qquad \text{reject or accept}$$

Test quality is assessed as follows.

$$E(\varphi \mid H_0).$$

Expectation under hypothesis H_0 (param. $\in \omega$). [At right: meaningful only if 1 point.] H_1 — alternative.



Uncertain reading. A separate θ stands over H_1. The following C-like sign may be $\subset$; it is followed by compl. ω.

Original source details: GELFAND-P000039

$$E(\varphi, H'_a) \leq \alpha, \qquad E(\varphi \mid H'_1) = \max.$$



Uncertain reading. At left the lower sign at H resembles a / 0, and the upper stroke resembles / / 1. There is a comma between φ and H. At right the upper stroke at H_1 is separately visible.

Original source details: GELFAND-P000039

[Beneath the left expectation: simple hypothesis (fixed point). Beneath the right: (desirable).] Reject the true one not too often, but also reject [a short entry is cancelled] the false one often.

Uncertain reading. Before false, a tiny sign is heavily crossed out; the text beneath the cancellation has not been read.

Original source details: GELFAND-P000039

Similar tests. (At each point of the null hypothesis the prob. is α.) Two examples.

X is Gaussian distributed with centre at an unknown point a_1.
σ_1^2 is the variance.

Testing by means of inv. tests.

Uncertain reading. In the continuation: null, below it a short cancellation and гип. / ил. The joined strokes after the cancellation do not give an exact reading.

Original source details: GELFAND-P000039



Uncertain reading. θ — мног. / мнот. a_i. The final stroke of the abbreviation resembles г / т; the reading is not established.

Original source details: GELFAND-P000039

Question. $a_1 = a_2$?

$$N(a_1, \sigma_1^2), \qquad x_1, x_2, \ldots, x_n,$$
$$N(a_2, \sigma_2^2), \qquad y_1, \ldots, y_n.$$

[At right: σ_i^2 are unknown param.]

$$H_0: \quad a_1 = a_2,$$

$$E(\varphi \mid H_0') = \alpha, \qquad E(\varphi \mid H_1) = \max.$$

φ — ?

GELFAND-P000040

φ is inv. or similar if for every θ the expectation of φ is the same. (For every θ there is a prob. distrib.)

$$E(\varphi \mid H_0) = \alpha, \qquad E(\varphi \mid H_1') = \max.$$

H_1' is one point in the complement. Bayesian measure is a measure on parameter space. (Given beforehand — a priori distribution.) [At left a rightward arrow to the lines:] The measure depends on a 4-tuple of points $(a_1, a_2, \sigma_1, \sigma_2)$. Null hypothesis.



Original source details: GELFAND-P000040

Diagram and typed description. Beneath null hypothesis is an irregular narrow strip with diagonal strokes; a_1 and a comma stand separately at right. The right strokes merge with the upper edge.



Bayes measure.



Original source details: GELFAND-P000040

Diagram and typed description. Beside Bayes measure is an empty rectangle: its thick top extends rightwards, and the lower line continues beyond both vertical sides. There is no label inside.



Original source details: GELFAND-P000040

Uncertain reading. Uniform / Radon distrib. [Равном. / Радон.], от. / отл. 0. The first abbreviated reading is graphically closer to Равном.; the short entry before 0 remains uncertain and is not expanded.

One must be able to solve for every Bayesian distrib.-measure. Result: A prob. distrib. in $X \times Y$ with a given Gaussian measure (4-param.). Find $\varphi(x, y)$ such that

$$E\big(\varphi(x_1, \ldots, x_n, y_1, \ldots, y_m)\big).$$



Original source details: GELFAND-P000040

Uncertain reading. At right: for every admiss. Gaussian measure (= α when $a_1 = a_2$ and max integr. / param. [проинтегр. / параметр.; uncertain abbreviated readings] on the complement). The word after max is graphically closer to проинтегр.; neither candidate is asserted as certain.

Sufficient statistic — contains all info. about the parameters.

Problem not done. θ_1, θ_2 are complex variables. $f(\theta_1, \theta_2)$ in a ball, ideals are not known (All prim. ideals corresponding to the ideal equal to 0.) Glison / Glisson — ball and centre holom.



Uncertain reading. Глисон / Глиссон (Glison / Glisson) — ball and centre holom. The surname is joined; centre is underlined twice. The last abbreviation is not expanded.

Original source details: GELFAND-P000040



Uncertain reading. Suff. stat. ideals of fns., vanishing at 0 on zeroth / θ-th coeffs. [0-x / θ-x; uncertain reading], terms of polynomials. The short entry after on remains uncertain. End of frame.

Original source details: GELFAND-P000040

GELFAND-P000041

Gleason — Gorin.

J. Math. Mech. v. 13. N 1 (1964).



Uncertain reading. The upper digits resemble 13; heavier earlier strokes lie beneath them. The underlying numeral is not established.

Original source details: GELFAND-P000041

Consider a ball $z = (z_1, z_2)$,

$$|z_1|^2 + |z_2|^2 \leq 1$$

and fns., an. inside and cont. on the bdry., with $f(0,0) = 0$. Do there exist g_1, g_2 of the same type such that

$$f = z_1 g_1 + z_2 g_2$$

(max ideal; will z_1, z_2 be a basis? This can be done inside, but it is unknown whether it can be done on the boundary? For one var. it is trivial. For a bicylinder it is done (since the Taylor series conv. on the bicylinder and one can take ...). Without bdry. — then the ball can be replaced by any domain of holomorphy.

23/XI. Arnold. “On Maslov’s work”.

Consider, in partic., the Cauchy prob. for the Schrödinger eqn. Config. space.

$$\frac{i}{h}\frac{\partial \Psi}{\partial t} = \Delta\Psi - \frac{U(x)}{h^2}\Psi$$

$U(x)$ — potent. energy.



Original source details: GELFAND-P000041

Diagram and typed description. An open-topped U-shaped curve lies above an almost horizontal line with a rightward tip labelled x; its bottom does not touch the line. No vertical axis is drawn.





Original source details: GELFAND-P000041

Uncertain reading. The factor before the derivative is written i/h; h^2 stands beneath $U(x)$ at right.

$$\Psi|_{t=0} = \varphi(x)e^{\frac{i}{h}S(x)}$$

[Beneath $\varphi(x)$: fin.]

Original source details: GELFAND-P000041

Diagram and typed description. A small rounded rise with steep sides stands over a horizontal stroke; $\varphi(x)$ is written above at right. Separate arrowheads cannot be distinguished.



$S(x)$ can be $S(x) = px$.



Original source details: GELFAND-P000041

Diagram and typed description. Wavy and almost vertical strokes lie between rounded upper and lower contours, crossed by an almost horizontal stroke. Some individual connections at the ends and thickened parts cannot be distinguished securely.



Oscill. (rapid), пропод. / proport. φ.

Original source details: GELFAND-P000041

Uncertain reading. After Oscill. (rapid), the abbreviation resembles пропод. / пропорц. (proport.); the joined middle strokes do not support a secure expansion. It is followed by φ.

GELFAND-P000042

Seek the asympt. as $h \to 0$ in the form

$$\Psi = e^{\frac{i}{h}a(x,t)}.$$

a — a complex fn. Substitute and obtain a seq. of asympt. formulas for the solution of the prob. The first 2 terms have the form

$$\Psi(x,t) = \frac{\varphi(X(x,t))}{\sqrt{\frac{\partial x(X,t)}{\partial X}}} e^{\frac{i}{h}(S(X(x,t))+\int p\,dx)+O(h)}$$

Original source details: GELFAND-P000042

Uncertain reading. The entry $+O(h)$ is on the raised line after the phase parenthesis; there is no separate lower line for it.



Original source details: GELFAND-P000042

Uncertain reading. The first rounded sign in the numerator beneath the radical resembles D / ∂; the denominator shows ∂X. The upper argument is written (X,t).

[From the denominator: — from unit.; see Titchmarsh and Landau.] φ — given init. amplitude. X at $t = 0 = x$. X — [cancelled: a point from which one must].



Original source details: GELFAND-P000042

Uncertain reading. Beneath the cancellation: точка, из к-рой надо / наше (a point from which one must / ours); the final letters are crossed by the stroke.

[Below at left: (x, t).] Classical init. condition.

$$p = \dot{x}, \qquad \dot{x} = \frac{\partial S}{\partial x}$$

Original source details: GELFAND-P000042

Uncertain reading. A dot is visible over each x / X. The lower sign after ∂S resembles X / x; its case is not secure. No separate subscript is visible on the first sign.

S is given at the init. instant. n-dim. пв. / пб.



Original source details: GELFAND-P000042

Uncertain reading. After n-dim. is a short joined abbreviation resembling пв. / пб.; it is not expanded.



Original source details: GELFAND-P000042

Diagram and typed description. An almost horizontal line crosses a vertical one; an arch lies above them, with two vertical strokes from it. X is below the left stroke; x stands between the strokes. Inside: time t. An inclined stroke rises rightwards from the left junction, with a thickened start; its arrow direction is not established.



The formula is quasiclassical, valid when the Jacob. $\neq 0$. Quasicl. — when this formula holds.

$$\ddot{x} = -\frac{\partial U}{\partial x}$$

classical mechanics (x — vector). In quantum mech., $\forall t$ there is a wave fn. Ψ. $|\Psi|^2$ — prob. Eqn. of motion — Schröd.

$$\frac{i}{h}\frac{\partial \Psi}{\partial t} = \Delta\Psi - \frac{U(x)}{h^2}\Psi$$



Uncertain reading. The repeated equation has i/h at left and $U(x)/h^2$ at right; the two fractions are separately visible.

Original source details: GELFAND-P000042

(if there is no i, then it is the heat eqn.; if initially at a point, it later spreads out). Connected with the asympt. of eigenvalues. $\Psi|_{t=0}$ is given. $\Psi(x)$

Diagram and typed description. A long almost horizontal stroke with a thickened right end follows $\Psi(x)$. There is no caption over it or secure arrowhead.

Original source details: GELFAND-P000042

GELFAND-P000043

$S(x) = px$, then the de Broglie formula.

$$\frac{\partial S}{\partial x} = p$$

Usual method of finding the asympt. — seek the soln. in the form

$$e^{\frac{i}{h}S_0(x^t)+S_1(x^t)+hS_2(x^t)+\cdots}$$



Uncertain reading. A raised sign with a crossbar resembling t stands over x in all three arguments; readings x^t / $\dot{x}$. The subscript of the second S is blotted: S_1 / S_0.

Original source details: GELFAND-P000043

With respect to time [inserted above: diff.] $\frac{1}{h^2}$ ...The leading term must be sought as $e^{\frac{i}{h}S_0(x)}$. If S is real, then oscill.; if complex, then there is decay. Obtain a 1st-order eqn., and the 1st

fn. is real, and obtain oscill. Must take the asympt., hence 2 terms. Now must choose init. data for this asympt. Ω / δ is not allowed, since there are many extraneous frequencies (strongly localized).

Uncertain reading. Ω or δ: a loop with a horizontal lower stroke and a long left tail.

Original source details: GELFAND-P000043

$$\varphi(x,t)e^{\frac{i}{h}S(x,t)}$$

if substituted there, then for S a 1st-order eqn.

$$\frac{\partial S}{\partial t} = H\left(x, \frac{\partial S}{\partial x}\right), \qquad H = U(x) + \frac{\dot{x}^2}{2}$$

to which an ordinary eqn. corresponds. φ — density of the dyn. syst. (how they move according to class. mech.). Must take x and find X for it, so that our eqn. comes from X to x after t. The points carry φ with them.



Diagram and typed description. A bending curve has X below the left junction and x at its right end. A thick inclined stroke passes through the left junction. Its arrowhead or direction is not established.



Original source details: GELFAND-P000043

$\dot{x}$ is given from x (the dyn. syst. is given). For small t, single-valued.

$$\Psi = e^{iH}$$

unit. $\mathcal{D}$ — the Jacob. is added for unitarity. e — the phase factor rotates with varying amplitude. Maslov's work, when t is arbitrary rather than small. $t = 0$, Jacob. [an entry is cancelled] $= 1$ (identity transf.).



Uncertain reading. A heavily cancelled expression after Jacob. and before $= 1$; the individual signs are not established.

Original source details: GELFAND-P000043

The wave fn. of the oscillator. Pendulum.



Diagram and typed description. A parabolic arch, oscillating contour, almost horizontal stroke and central stroke intersect. Visible labels: φ, 0, x; a small upper sign resembles ξ, but its lower part joins the curve. Captions: in class. mech. wave fn.; exp decay. Exact connections of dense strokes and the number of oscillations are not established.



Original source details: GELFAND-P000043

GELFAND-P000044

If t is large, it may happen that the curve of init. data (n-dim. пв.) folds over.

Original source details: GELFAND-P000044

Diagram and typed description. Upper-left drawing: several bending arches cross inclined strokes, an almost horizontal line and a dense almost vertical bundle. Small tips appear at the upper-left end and inside the bundle; some individual connections overlap.

If there is a vertical tangent, then $\mathcal{D} = 0$, but afterwards there are 2 points and the formula is retained [(!) / (?)], but must add terms over the points γ_j / n_j — an integer.

Uncertain reading. After retained, a small parenthesized sign with a separate lower dot: (!) / (?). Its upper part is blotted.

Original source details: GELFAND-P000044

Uncertain reading. γ_j or n_j: the upper sign has a loop and two raised strokes; j lies below. The following entries resemble n_j.



Original source details: GELFAND-P000044

$$\int p\,dx) + i\,\frac{\pi}{2} n_j$$

[A sign between i and $\pi/2$ is cancelled.]



Original source details: GELFAND-P000044

Uncertain reading. A sign between i and $\pi/2$ is heavily cancelled; the readings $+$ / $-$ are not securely established.

Maslov's result — the n_j have been found. $n_j = \pm 1$ from general considerations. Go around the branch point in the complex plane; this can determine $\oplus$ or $\ominus$. All results also apply in optics.



Original source details: GELFAND-P000044

Diagram and typed description. Several inclined rays cross a bending envelope. A thick arrow points downwards to the right at the upper tangency. Short crossing strokes lie on the lower-right branch; their connection to the envelope is uncertain.



The rays envelop a curve. We shall follow the phase along a ray. For small λ — a phase jump of $\pi/2$ at the point of tangency. Answer n_j — the Morse index.



Diagram and typed description. The p axis points upwards and the horizontal axis rightwards. A family of bending and almost vertical strokes; x_1, x_2, X. Captions: curve of init. data; classical; degenerate here; after time t; after t; conj. points. A small dense sign is above the central vertical stroke; its reading and some individual intersections are not established.



Original source details: GELFAND-P000044

A trajectory is a soln. of a variational problem by the principle of least action.

$$\delta u = 0$$

$$\delta^2 u$$

a quadratic form. It has an index [a word is cancelled] (number of neg. squares).

Uncertain reading. A short word left of (number of neg. squares) is cancelled by dense strokes; its reading is not established.

Original source details: GELFAND-P000044

Or [a word is cancelled] the number of conjugate points.

Uncertain reading. A word above number of conjugate points is covered by several horizontal strokes; its reading is not established.

Original source details: GELFAND-P000044

The 1st part of Leray's work is devoted to related questions. Next time Povzner



Uncertain reading. Uang; a cancelled word between the names; and Brushlin / Brillin. Above the line: groups. The middle letters of the final surname are not secure.

Original source details: GELFAND-P000044

GELFAND-P000045

Berezin.

$$H = \frac{p^2}{2} + V(x)$$

(e.g. V grows). Let the surfaces $p^2 + V(x) =$ const all be bounded. Then the asympt. of eigenvalues [an abbreviation is cancelled]:



Uncertain reading. The cancelled abbreviation before values resembles ф-й / ф-и (fns.); horizontal strokes cross the upper letters.

Original source details: GELFAND-P000045

the volume of the region where $H \leq n\pi h$ — the asymptotic [a word is cancelled] of the eigenvalues.

Uncertain reading. A short word between asymptotic and eigenvalues is covered by dense ink; its reading is not established.

Original source details: GELFAND-P000045

Gelfand I.

$$-y'' + p(x)y = \lambda y$$



Diagram and typed description. A horizontal segment with short end strokes and labels 0, π. One arch lies above the segment; another curve begins above it, crosses it, and falls below. A dense junction lies near the right end; the nearby underline under zero at the endpoints is crossed out.



Original source details: GELFAND-P000045

Zero at the endpoints [the underline is crossed out]. $p = 0$, eigenfns., $\lambda = -n^2$.

Uncertain reading. In $\lambda = -n^2$, a separate horizontal stroke is visible between the equality sign and n; the minus is retained.

Original source details: GELFAND-P000045

Claim. The 1st eigenfn. has no zeros (Morse index 1). The 2nd — ditto — has one zero. This holds for $\forall$ eqn. The zeros interlace. A more precise theorem. If $y_0, \dots, y_n$ are eigenfns., then

$$\sum_{i=1}^{n} a_i y_i(x)$$

will have $\leq n$ zeros!! (resembles polynomials). [A cancelled determinant:]

$$\det \begin{vmatrix} y_0(x) & y_1 & \cdots \\ y_0'(x) & y_1' & \\ \vdots & \vdots & \\ y_0^{(n)}(x) & y'(x) & \end{vmatrix}$$



Uncertain reading. The lower second entry of the cancelled determinant resembles $y'(x)$ / $y_1^{(n)}(x)$; its subscript and derivative order are not established.

Original source details: GELFAND-P000045

This is equiv. to the condition

$$\begin{vmatrix} y_0(x_0) & y_1(x_1) & \cdots \\ y_0'(x_0) & y_1'(x_1) & \cdots \\ \vdots & \vdots & \\ y_0^{(n)}(x_0) & y_1'(x_1) & \end{vmatrix} \neq 0$$



Uncertain reading. The upper sign of $y_1\prime(x_1)$ in the second entry of the second row is overwritten. A single raised stroke is visible in the lower second entry: $y_1\prime(x_1)$; a possible order (n) is not established.

Original source details: GELFAND-P000045

Or [Above the following determinant:] this is the 1st eigenfn. $\neq 0$; 2nd-order eqn.,



Uncertain reading. The final abbreviation in the caption above the determinant: к-рая / к-рым (which); its ending is joined.

Original source details: GELFAND-P000045

$$\begin{vmatrix} y_0(x_0) & y_1(x_0) & \cdots \\ y_0(x_1) & y_1(x_1) & \cdots \\ \vdots & \vdots & \\ y_0(x_n) & y_0'(x_n) & \end{vmatrix} \neq 0$$



Uncertain reading. The lower second entry resembles $y_0\prime(x_n)$: a rounded subscript and raised stroke. Readings $y_1\prime(x_n)$ / $y_1(x_n)$ remain alternatives.

Original source details: GELFAND-P000045

Hence a linear comb. has $\leq n$ zeros if $x_0 < x_1 < \cdots < x_n$. Petrov. So that

$$\frac{\partial^2 u}{\partial x_1^2} - \frac{\partial^2 u}{\partial x_2} - \cdots + (p(x_1) + p(x_2) \ldots + p(x_n))\, u = \\ = \lambda u$$



Original source details: GELFAND-P000045

Uncertain reading. The first denominator is x_1^2; the second shows x_2 without a square. At the right edge: $u =$; below, another equality sign before λu. Both signs are retained.

Eigenfns., the variables separate. Eigenfns. $u_1(x_1)u_2(x_2)\dots u_n(x_n)$. The 1st eigenfn. $\neq 0$.

GELFAND-P000046

Planned.



Original source details: GELFAND-P000046

Uncertain reading. The first row begins with a long looped sign, then И / Н before Бернштейн. Readings: 1° I. Bernstein and S. Gilfand / F. N. Bernstein and S. Gilfand / 1° I. Bernstein and S. Gelfand. Full names are not established.

[Separately at the right:] Dyson. 2°. Novikov, on the work of Adams. 3°. Dynkin. 4°. Vinberg. 5°. Pyatetskii-Shapiro. [Cancelled.]



Original source details: GELFAND-P000046

Uncertain reading. The short cancelled and underlined heading before Pyat.-Shapiro resembles Пят. (Pyat.); dense strokes cover the earlier writing.

Pyat.-Shapiro. Problem of Klein and Serre. Consider the gr. of integer matrices of order n, $\Gamma(n)$, with det $= 1$. [Cancelled: How] describe all subgrs. Γ' of finite index? Ex.

$$\Gamma(n, N), \qquad A \equiv E \pmod{N}$$



Uncertain reading. A small inscription below $\Gamma(n, N)$ resembles λij / i, j; below $A \equiv E$: не гр. / на гр. (not gr. / on gr.). The letters and the attachment of the small inscription to the formula are not established.

Original source details: GELFAND-P000046

(on the diag., congruent to 1; off the diag., divisible by N).

GELFAND-P000047

Are these all the subgroups? Does Γ' always contain $\Gamma(n, N)$ (a congruence subgr.). For $n = 2$ this is false (Klein). $n \geq 3$, this is true (Serre). Connection with Lie groups. Consider the matrices

$$\begin{pmatrix} 1 & 0 & & \\ & \ddots & 1 & 0 \\ 0 & & & 1 \end{pmatrix}$$

[Cancelled symbol.]

Uncertain reading. A cancelled and overwritten sign before the elementary-matrix notation resembles E; the underlying strokes are not established.

Original source details: GELFAND-P000047

$E_{ke} = (\mathrm{id.} + E_{ke})$.



Original source details: GELFAND-P000047

Uncertain reading. The same E-shaped sign occurs on both sides of the equality; its second subscript resembles e / ℓ. Readings $E_{ke} = (\mathrm{id.} + E_{ke})$ / $e_{k\ell} = (\mathrm{id.} + E_{k\ell})$. The schematic matrix retains the visible ones, zeros and dots; unwritten entries have not been supplied.

The gr. $\Gamma(n)$ is generated by them. Take these matrices and their conjugates and raise them to the power N: E_{ke}^N, Γ^N. For $n = 2$ it has infinite index; $n \geq 3$, finite index. Γ/Γ^N. $\boxed{n = 2}$ $N = 2, 3, 4, 5$ is finite, 6 commut. / коннут. [коммут. / коннут.; uncertain abbreviation]



Original source details: GELFAND-P000047

Uncertain reading. After 6, the abbreviation коммут. / коннут. (commut. / коннут.; uncertain reading). Its initial letter has separate vertical and angled strokes. Below: $p = p(N)$; the letter resembles p. The abbreviation is not expanded.

Γ/Γ^N = fund. gr. of a surface, $p = p(N)$, a simple formula. Serre, Lazard, Bass (1964). Consider $a \equiv b\ (N)$, then for $n \geq 3$ / $N \geq 3$ there is a transf. $a \to b$ in Γ/Γ^N (elem. transf.).

Uncertain reading. After then for, the sign before ≥ 3 is heavily overwritten: $n \geq 3$ / $N \geq 3$. Vertical strokes resembling capital N are visible.



Original source details: GELFAND-P000047

Then cohomol. technique.

Gelfand. Tomorrow at the conf. on elem. particles, there will be considered [Cancelled.]

Original source details: GELFAND-P000047

Uncertain reading. A group designation before boxed $SU(3)$ is densely cancelled. Readings $SU(3)$ / $SU(2)$; the digit beneath the ink is not established.

$SU(3)$. Known particles are combined into groups, transforming into one another (multiplets). Another repr. of $SU(3)$. The idea $SU(2) \underset{\text{almost}}{\approx} SO(3)$. [Above the line: fns., lin. comb.] Combine by means of $SU(2) \times SU(3)$. The hypothesis is known also for $SU(6)$. Remark — actually the Lorentz group (with par. translations) (the Poincaré group). [Cancelled: $SU(2)$] $\longrightarrow$ Poincaré gr. Work of Todorov. Kadyshevsky, Muradyan, Tavkhelidze. Instead of $SU(6)$ — a 108-param. group.

GELFAND-P000048

Salam proposed a 144-param. group. Fulton, Wess. A 2-step gr. with a comm. normal divisor. $SU(3) \otimes SU(2)$ in some sense. Lorentz transf. — complex matrices.

$$\begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix}, \qquad \det = 1$$

(spinor repr. of the Lorentz gr.). Poincaré gr.

$$A = \begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix}$$

Vector — Hermitian forms of order 2.

$$H = \begin{pmatrix} a & b \\ \bar{b} & c \end{pmatrix}$$

A vector in 4-dim. space; a, c real, b complex.

$$H \to AHA^*$$

Lorentz, det is preserved. Poincaré gr.

$$\begin{pmatrix} A & H \\ 0 & A^{*-1} \end{pmatrix}$$

This is a group for $H \geq 0$ / $H = 0$ rot. (H transl.). $H = 1$ — par. transl.



Uncertain reading. The condition on H has an upper angled stroke and a lower horizontal stroke before 0; readings $H \geq 0$ / $H = 0$.

Original source details: GELFAND-P000048

[Cancelled.]

Uncertain reading. Before Matrix of order 4, a cancelled phrase begins gr.; the next word resembles Вращ. / Лоренца (rot. / Lorentz).

Original source details: GELFAND-P000048

Matrix of order 4.

$$\begin{pmatrix} A & H \\ 0 & A^{*-1} \end{pmatrix} \otimes SU(3)$$

Obtain a semisimple gr. with a radical (108-param.). One can describe what is needed to solve the theor. of elem. particles).

15/II. Kazhdan. Palam.'s result in purely alg. terms. Let A be an integral domain [domain inserted above a cancelled word] (ring without zero divisors), I a prim. ideal.



Uncertain reading. Область [domain] is inserted above a cancelled word; the candidate is кольцо [ring]. The dense strokes do not establish the whole word. The following целостности [integral, in integral domain] (ring without zero divisors) is legible.

Original source details: GELFAND-P000048

$$I \supset J$$

[Beneath J:] prime. And let $J \supset I^2$ [cancelled: $\neq$] 0.



Uncertain reading. I is introduced as a prim. ideal; prime is written beneath J in $I \supset J$. Next: $J \supset I^2$, with a cancelled sign resembling $\neq$ before 0. The letters and cancellation are retained.

Original source details: GELFAND-P000048

Every such ideal is given by diff. opers. of order 1.

GELFAND-P000049

A diff. oper. is a k / A / K-lin. oper.

Uncertain reading. The dense first-line sign before -lin.: k / A / K. The lower loop may belong to D on the following line; the attachment of the strokes is not established.

Original source details: GELFAND-P000049

$$D(a \cdot b) = aD(b) + D(a)b$$

An ideal is the zero of some collection of diff. opers. Let A/J^2 (of order 1 because of J^2). An operator into the ring A/J, rather than into the ring. Diff. everywhere, and the ans. on a subset. $aD(b)$ — multiplication by a. On J the oper. is A-linear [below: diff.]. Conversely, every A-lin. oper. on J [Cancelled strokes before the arrow.]



Original source details: GELFAND-P000049

Uncertain reading. Before the arrow from J, three dense, nearly vertical strokes with a loop are cancelled. An individual underlying letter is not established.

$$J \xrightarrow{f} A/J$$

Then it can be multiplied by an elem. b, again lin. [Above: bf.] $\exists b$ such that bf extends to a diff. of the whole ring. Everything follows from this. We shall consider $J(2)$ / $J(\xi)$ / $J(\ell)$ over the field of fractions.



Original source details: GELFAND-P000049

Uncertain reading. The parenthesized sign after J resembles 2 / ξ / ℓ, followed by over the field of fractions. Readings $J(2)$ / $J(\xi)$ / $J(\ell)$.

Functionals exist, appar. J lies in the ring of fractions. Multiply by b (since there are no zero divisors, then [a short sign is cancelled] ring of fr.).



Original source details: GELFAND-P000049

Uncertain reading. A short densely cancelled sign between then and ring of fr.; its reading is not established.

If A/J is a field, then $\forall$ functional extends to a diff. (Need to take the localization of A/J). There is a map of the field

$$A/J \longrightarrow A$$

[Beneath the arrow: hom.] such that the reverse hom. is the identity.

$$A/J \longrightarrow A \longrightarrow A/J$$

[Cancelled.]



Original source details: GELFAND-P000049

Uncertain reading. The cancelled heading before For now, arb. resembles Док-во. (Proof.); its reading remains uncertain beneath the strike.

For now, arb. $A/J \subset A$, $J \subset A$. Any elem. decomposes into a Σ (Σ as a lin. space).

GELFAND-P000050

On J it is already given. A lin. map $J \to A/J$ extends by 0 everywhere. A transcend. elem. anywhere.

$$y \to \hat{y}, \qquad x^2 = y$$
$$\hat{x}'^2 - \hat{y} = i_1; \qquad \hat{x} = \hat{x}' + i_2;$$
$$\hat{x}^2 = \hat{x}'^2 + 2\hat{x}' i_2 = \hat{y} + 2\hat{x} i_2 + i_1$$



Uncertain reading. The expansion has no i_2^2. The multiplier is $\hat{x}\prime$ in the first equality and $\hat{x}$ without a prime in the second. Both readings are retained.

Original source details: GELFAND-P000050

Hence i_2 is found (since A/J is a field). Instead of I, J was written, and conversely. General form of a diff. oper. in the polynomial ring.

$$\sum P_i(x_1, \ldots, x_n) \frac{\partial}{\partial x_i}$$

P_i are polynomials. Alg. theory of diff. eqns. over an arb. field. Dieudonné, Grothendieck: in alg. problems, passed to an arb. field. Ordinary eqn.

$$\frac{dx}{dt} = P(x, y)$$
$$\frac{dy}{dt} = Q(x, y)$$



Uncertain reading. The letter in the numerator of the first equation is heavily overwritten; the visible candidate is dx, and the earlier letter is not established.

Original source details: GELFAND-P000050

t is replaced by a local ring at $\forall$ point (t a local parameter).

$$x = \sum a_k t^k$$
$$y = \sum b_k t^k$$

Diff. eqns. over P^2.



Uncertain reading. An underlined P-like letter with a raised 2: P^2 / p^2. No double stroke is visible.

Original source details: GELFAND-P000050

$$D(x(t)) = f(x(t))$$

D is a diff. operator in the ring of elems. x. Ringed space. Points (x, y) and fibres. A ring at $\forall$ point. The fibre over each point is a power series in t (a power series in t at $\forall$ point).

GELFAND-P000051

$$Da = b.$$

Uncertain reading. In the left entry, a / α; no separate definition on this frame.

Original source details: GELFAND-P000051

Init. cond. — value in a max. ideal. Then localize. D carries over to any localization. The soln. must be an ideal. (?) The whole ring need not be given. It is known locally. x and y need not be specified.

Palamodov.

$\mathcal{P}$ — ring of polyn. $P(z_1, \ldots, z_n)$

[Before P: a sign is cancelled.]

Uncertain reading. a short densely cancelled symbol

Original source details: GELFAND-P000051

$\mathcal{H}$ — space of all fns. in a domain of holom. (e.g. a ball)

$$\mathcal{J} \subset \mathcal{P}$$

A prim. ideal with basis $P_1, \ldots, P_t$ Consider $\mathcal{J}\mathcal{H}$ Quotient space $\mathcal{H}/\mathcal{J}\mathcal{H}$ Construct $\mathcal{H}\{\mathcal{J}\}$, isomorphic to it by means of the operator $d(z, D)$

$$\mathcal{H}\{\mathcal{J}\} = \left\{\mathcal{H}(z)\big|_N \quad \forall \zeta \in N \quad \exists F_\zeta(z) \quad f(z) = d(z, D)F(z)\big|_N\right\}$$



Uncertain reading. The first function symbol inside the brace resembles $\mathcal{H}$ / h / f; $f(z)$ is written at right.

Original source details: GELFAND-P000051



Uncertain reading. The point sign after $\forall$ and the subscript of F resemble ζ / ξ; the operator letter in $d(z, D)$ resembles d / δ. The right formula reaches the frame edge; the lower N and closing brace are visible. A lower stroke at the right-hand F permits $F(z)$ / $F_\zeta(z)$.

Original source details: GELFAND-P000051



Uncertain reading. Below the first $\mathcal{H}(z)$: vector. comp. / конх. / конк.; see / an. / lin. oper. in coll. d / λ [комп. / конх. / конк., см. / ан. / лин. опер. в наб.; uncertain abbreviations].

Original source details: GELFAND-P000051

[Below $F_\zeta(z)$: analytic in a nbd.] Local theorem. There is a theorem with growth estimates. Res.

$$\mathcal{H}\{\mathcal{J}\} \cong \mathcal{H}/\mathcal{J}\mathcal{H}$$

The isom. is natural



Diagram and typed description. Below isom., a rightward arrow with a separate dot to its right; below natural, a separate thick almost horizontal line.

Original source details: GELFAND-P000051

GELFAND-P000052

Dynin. X — comp. manif. Over it, vect. bundles E_0 E_1



Diagram and typed description. Over X, two bundles E_0, E_1, with arrows to X.



Original source details: GELFAND-P000052

Sheaf of germs of C^∞-fns. of the 1st and 2nd bundles:



Original source details: GELFAND-P000052

Diagram and typed description. Above fns., inserted: sections.

sections
C^∞- fns.

$$\mathcal{E}(E_0) \qquad \mathcal{E}(E_1)$$

and morphisms

$$\mathcal{E}(E_0) \xrightarrow{A} \mathcal{E}(E_1)$$

([An entry is cancelled; below it, morph.] $\forall$ given by diff. operators)



Original source details: GELFAND-P000052

Uncertain reading. a short densely overwritten entry

Locally, $\mathcal{E}(E_0)|_U$ — smooth vector fns.



Original source details: GELFAND-P000052

Diagram and typed description. Two local entries; in the first, the lower restriction sign is densely overwritten: a / U. Downward arrow from $C^{n_0}(U)$ to $C^{n_1}(U)$, with $A(U)$ at right.

$$\begin{array}{lc} \mathcal{E}(E_0)|_a \approx & C^{n_0}(U) \\ & \downarrow{\scriptstyle A(U)} \\ \mathcal{E}(E_1)|_U \approx & C^{n_1}(U) \end{array}$$

diff. oper. — a matrix. Symbol — princ. part of the matrix. Locally $\sigma(A)(x,\xi)$ — princ. part of the char. matrix.

Original source details: GELFAND-P000052

Uncertain reading. The second argument of $\sigma(A)$ is densely overwritten; forms ξ / ζ / D are visible.

(Select terms of highest degree Formalize. Tang. bundle — vect. F



Original source details: GELFAND-P000052

Diagram and typed description. Diagram with X, $T(X)$, π, π^*E_0, π^*E_1, $\sigma(A)$.

$$\begin{array}{ccc} & X & \\ & {\scriptstyle\pi}\uparrow & \\ & T(X) & \\ \pi^*E_0 & \xrightarrow[\sigma(A)]{} & \pi^*E_1 \end{array}$$

A ellipt. if $\sigma(A)$ is a monomorphism (see Schwartz) Example.



Original source details: GELFAND-P000052

Diagram and typed description. At E_0, a leftward arrow; below E_0, fns.

$E_0 \longleftarrow X \times \mathbf{R}^1 \longrightarrow X$
fns.

$$\mathcal{E}(E_0) = C(X) \qquad C^\infty \text{— fns. on } X$$

GELFAND-P000053



Original source details: GELFAND-P000053

Diagram and typed description. Below d, ext. diff.

$C(X) \xrightarrow[\text{ext. diff.}]{d} C^1(X)$

Loc. $f(x) \longrightarrow \text{grad } f(x)$ symbol — mult. by the vector $\xi \in T(X)$ This is an example of an overdet. elliptic system.

$$f(x) \xrightarrow{d} \sum \frac{\partial f}{\partial x_i}\, dx_i$$

$$f(x) \longrightarrow \begin{pmatrix} \frac{\partial}{\partial x_1} \\ \vdots \\ \frac{\partial}{\partial x_n} \end{pmatrix} f(x)$$

$$E_0 = X \times \mathbf{R} \longrightarrow X \qquad E_1 : \Lambda T(X) \longrightarrow X$$



Original source details: GELFAND-P000053

Uncertain reading. After E_1, a dense cancellation before the colon; the sign before $T(X)$ resembles Λ / $\wedge$. No clear star at T is visible.

diff. forms — sections of such a bundle. Result.

$$\mathcal{E}(E_0) \xrightarrow{A} \mathcal{E}(E_1)$$

Take

$$0 \longrightarrow \ker A \longrightarrow \mathcal{E}(E_0) \xrightarrow{A} \mathcal{E}(E_1)$$

If A is ellipt., then

$$\dim H^i(X, \ker A) < \infty$$

special cases. 1°. Let A be ellipt. in Petrovskii's sense.

$$\mathcal{E}(\mathbf{R}^n) \xrightarrow{A} \mathcal{E}(\mathbf{R}^n)$$



Original source details: GELFAND-P000053

Uncertain reading. The first exponent is n; the upper sign at right permits n / ν.

Then the space of glob. solutions is finite-dimensional

$$H^0 \quad \text{— finite:} \qquad H^1 \quad \text{— defect. (fin. defect)}$$

$$H^1(X, \ker A)$$

2°. Ext. diff. oper.



Original source details: GELFAND-P000053

Diagram and typed description. Below $\ker d$, const. sheaf.

$\dim H^i(X, \underset{\text{const. sheaf}}{\ker d})$ — Betti numbers.

3°. Compl. an. Cartan–Serre–Kodaira theorem

GELFAND-P000054

Original source details: GELFAND-P000054

Diagram and typed description. Several letters in the heading are densely overwritten.

Proof.



Original source details: GELFAND-P000054

Diagram and typed description. Mac Lane inserted below within the parenthesis; two closing parentheses at right.

(read Godement, Cartan and Eilenberg)

Mac Lane)

$\mathcal{P} \longrightarrow$ a sheaf. How to compute homology.

$$0 \longrightarrow \mathcal{P} \longrightarrow \mathcal{P}_0 \longrightarrow \mathcal{P}_1 \longrightarrow \cdots .$$

a fine resolution.

$$0 \longrightarrow \underset{\text{sections}}{\mathcal{P}_0(X)} \xrightarrow{d_0} \mathcal{P}_1(X) \xrightarrow{d_1} \cdots$$



Original source details: GELFAND-P000054

Diagram and typed description. Below $\mathcal{P}_0(X)$, sections underlined.

$\underset{\text{sections}}{\mathcal{P}_0(X)}$

$$H^1(X, \mathcal{P}) = \ker d_1 / \operatorname{Im} d_0$$

$$0 \longrightarrow \ker A \longrightarrow \mathcal{E}(\mathbf{R}^n) \xrightarrow{A} \mathcal{E}(\mathbf{R}^n)$$



Original source details: GELFAND-P000054

Uncertain reading. The first exponent is n; the upper sign at right permits n / ν.

this is a fine resolution. H^1 — quotient. The others, for an oper. ellipt. in Petrov.'s sense, 0.



Original source details: GELFAND-P000054

Diagram and typed description. At left, Idea crossed out, beside Of proof with a wavy line; downward arrow and a long oval/stepped line.

~~Idea~~ Of proof

Our main prob. on the Euler char.

(altern. sum)

2 methods.



Original source details: GELFAND-P000054

Diagram and typed description. Kodaira and the line Reduc. to the Schwarz lemma have wavy lines; arrow to the following line.

Kodaira: space of solns. of an ellipt. eqn.

Reduc. to the Schwarz lemma,

does not carry over to higher hom. (no theorems A and B)



Original source details: GELFAND-P000054

Uncertain reading. Another method: introd. top. / thin. and вп.-непр. ident. oper. [введ. / ввод. топ. / тон.; the initial abbreviations are not established.]

Resolution from Ban. spaces. Banach sheaf. Sheaf $\mathcal{P}$: $U \longrightarrow \mathcal{P}(U)$ (presheaves) of Fréchet type $\mathcal{P}(U)$ — F-spaces, and the restr. maps are cont. Series of new sheaves

$$C^{p,r}(\mathcal{P})$$

Original source details: GELFAND-P000054

Diagram and typed description. The arrow from U has a wavy beginning and an arrowhead at right.

$U \rightsquigarrow C_U^{p,r}(\mathcal{P}(U))$

Vect.-valued diff. forms of degree p, smoothness r The sheaf splits, but if there is no фн. прдп. / прдл. [abbreviations not established], then it does not split.



Original source details: GELFAND-P000054

Uncertain reading. but if there is no фн. прдп. / прдл. [abbreviations not established],

GELFAND-P000055

For $\mathcal{P} = \mathcal{E}(E)$ Sheaf — a Fréchet space. de Rham resolution.

$$0 \longrightarrow \mathbf{R} \xrightarrow{d} C^{0,r} \xrightarrow{d} C^{1,r} \xrightarrow{d} \cdots .$$



Original source details: GELFAND-P000055

Diagram and typed description. Below the sequence, a long bracket.

[Below it, a sign is cancelled.]

Uncertain reading. a short densely cancelled sign

Original source details: GELFAND-P000055

Coeffs. — maps of U into diff. forms. coeffs. — smooth maps $U \longrightarrow \mathcal{P}(U)$ r — order of smoothness. Passing to the sheaf adds no new sections (but not in the gen. case, under the given assump.) Of the type of the de Rham resolution

$$0 \longrightarrow \mathcal{P} \longrightarrow \widehat{C}^{p,r}(\mathcal{P}) \xrightarrow{d} \widehat{C}^{1,r}(\mathcal{P}) \longrightarrow \cdots .$$



Uncertain reading. The first upper index at $\widehat{C}$ resembles p / 0.

Original source details: GELFAND-P000055

adjusted because of the order of smoothness Banach spaces result. $H^i(X, \mathcal{P})$ над. / нов. top.



Uncertain reading. над. / нов. top. [densely overwritten abbreviation].

Original source details: GELFAND-P000055

It does not depend on the choice of resolutions.

$$H^i(X, \mathcal{P})^{(r)} \longrightarrow H^i(X, \mathcal{P})^{(r-1)}$$

take the same Fréchet spaces (isomorphism) It is compl. cont. by the embedding theorem Gelfand. Problem: X — comp. with a sheaf of lin. top. spaces on it. Ex. X — a point. Just a space. Diff. oper. — endom. into itself [самёе / самёё себя].



Uncertain reading. endom. into itself [самёе / самёё себя; the word endom. is densely overwritten; below it, of the sheaf inserted and underlined].

endom.
of the sheaf

Original source details: GELFAND-P000055

(meaning preserved.) When it is of finite index. X — 1 point. $E+$ compl. cont. Riesz theorem. Then one can consider operators ellipt. of order ∞. Dynin. Hypoellipt. of the operator is needed. in the resolution, always the same sheaf ker A Merely cont. coeffs., will it be of finite index? Next time. Adams (Novikov), Berezin



Uncertain reading. (РиО / РиЭ).

Original source details: GELFAND-P000055

GELFAND-P000056

Diagram and typed description. Date in a frame open at the top; below it, Adams; Novikov underlined twice.

22/II.

Novikov S.P.

Adams.

Original source details: GELFAND-P000056

S^n how many lin. indep. vect. fields? (cont. f.)



Diagram and typed description. Below how many, $\nu(n)$.

how many
$\nu(n)$

Original source details: GELFAND-P000056

Triv. facts. Exist on odd-dim. sph. ($\nu(n) \geq 1$) on even-dim. sph., none ($\nu(n) = 0$)

$$\sum \text{ind. of sing.} = \text{Euler char.}$$

M^n — n-dim. м-о. / м-ф.



Uncertain reading. м-о. / м-ф. [the last sign of the abbreviation is dense].

$(m, \varphi(m)) \subset (M^n, \mathbf{R}^n)$
graph.

(m, T_m)
vector field

Original source details: GELFAND-P000056

$(m, 0)$ — canon. Its intersection index is the index of the singularity.



Uncertain reading. Below the line, a wavy bracket to $c(m,0)$ / $\varepsilon(m,0)$.

$c(m,0)$

Original source details: GELFAND-P000056

(Here only 1 and -1, but degree n). $E = 2$, so there are no fields. 2) S^3 and S^7 paralleliz.



Uncertain reading. Before the following equalities, a short cancelled entry; the upper sign of the second sphere resembles 7 / an asterisk.



Original source details: GELFAND-P000056

$\nu(3) = 3, \nu(7) = 7$ 3) $\nu(2n-1) \geq 1$ (S^{2n-1}) 4) If on S^{2m-1} there are k indep. fields ($\nu(2m-1) \geq k$), then on S^{2pm-1}, $\nu_{2pm-1} \geq k$

Uncertain reading. Короче / Корче (in short; middle letters run together; no colon).

Original source details: GELFAND-P000056

$$S^{m-1}, \quad \nu_m \geq k \quad \Longrightarrow \quad S^{pm-1}, \quad \nu_{pm-1} \geq k$$

Diagram and typed description. Below the sum, $\mathbf{R}^m$; at right, $\mathbf{R}^{pm}$.

$\sum_{i=1}^{m} x_i^2 = 1$ $\qquad$ $\mathbf{R}^{pm}$

$\mathbf{R}^m$

Original source details: GELFAND-P000056

Coords. p groups of m each



Uncertain reading. $x_i^{(j)}$ / $y_i^{(j)}$ [first symbol overwritten], $i = 1, \ldots, m$, $j = 1, \ldots, p$.

Original source details: GELFAND-P000056

let $p = 2$.



Diagram and typed description. Below each sum, $\mathbf{R}^m$. Asterisk after 1; no footnote on the frame.

$\sum_{\mathbf{R}^m} y_i^2 + \sum_{\mathbf{R}^m} z_i^2 = 1^*$

Original source details: GELFAND-P000056

$v(x)$ in $\mathbf{R}^m$, $\qquad v(x) \perp x \qquad$ (field on S^{m-1})



Original source details: GELFAND-P000056

Uncertain reading. The initial letter in $v(x)$ resembles Latin v / ν; no separate quantifier sign is established.

GELFAND-P000057

Put

$$\widetilde{v}(y,z) = \left(\|y\| v\left(\frac{y}{\|y\|}\right),\ \|z\| v\left(\frac{z}{\|z\|}\right) \right)$$

$\|y\|$ to cope with $y = 0$, all in the 2nd comp., of mod $= 1$, and $\perp$ (y, z) Indep. fields are obtained from indep. fields. Thus Hopf fields are obt. (On the right one can write other fields) can stabilize the problem: incr. dim. ~~Was~~ known classific (hard to construct.



Original source details: GELFAND-P000057

Diagram and typed description. At left, S^{m-1} in an oval; arrow down.



$$m = 2^b(2a+1) \qquad b = c + 4d \qquad 0 \le e \le 3,$$

Original source details: GELFAND-P000057

Uncertain reading. In the bounds $0 \le e \le 3$, the middle letter resembles e / c.

then the known number of fields

Original source details: GELFAND-P000057

Diagram and typed description. Frame open at the top; the exponent resembles e / c.

$$2^e + 8d - 1$$

$$\nu_{m-1} \ge 2^c + 8d - 1$$

In cases 3, 7 gives max. $b = 0$ (even — трв. / прв.).

Original source details: GELFAND-P000057

Uncertain reading. (even — трв. / прв.).

$b = 1, 2, 3$, [a sign is overwritten], simple, but req. methods of alg. top.



Original source details: GELFAND-P000057

Uncertain reading. densely overwritten sign / downward arrow

$b \le 12$ Toda, but m of order 3000 Adams proved this in all dimensions.



Original source details: GELFAND-P000057

Diagram and typed description. Two wavy underlines.

Adams

$*$ Reduced part of Atiyah's and Toda's ex. This leads to a problem on homot. gr. of spheres. finally

$$\nu_{m-1} = 2^c + 8d - 1$$

The odd factor plays no role. Here one assertion. $m \uparrow$ by a factor of 6, then the number of fields incr. by 8



Original source details: GELFAND-P000057

Uncertain reading. One sign in the factor, 6 / 8.

$(d+1)$ this is seen from the constr. in Bott periodicity.



Original source details: GELFAND-P000057

Uncertain reading. For $1*$ / $1\times$ all is known.

2 parall. sph., then Bott periodicity



Original source details: GELFAND-P000057

Diagram and typed description. Asterisks below 1, 2, 4, 8.

$\pi_i(BO)$.

$i=$	1	2	3	4	5	6	7	8
	$*$	$*$		$*$				$*$

where π_i of Grassm. mfld. is nontriv. $\mathbf{R}P^k$ — project. space Consid.



Original source details: GELFAND-P000057

Uncertain reading. In the lower index, 2 and $f(k)$ are visible: $2^{f(k)}$ / $2f(k)$. The small upper sign on $\widetilde{K}$ resembles 0. From the second summand a bracket to the lower entry.

$$K_{\mathbf{R}}(\mathbf{R}P^k) = \mathbf{Z} + \widetilde{K}^0_{\mathbf{R}}$$

$$K_{\mathbf{R}} = \mathbf{Z}_{2^{f(k)}}$$

K-functor, see Матен. / Матем. Atiyah and Hirzebruch



Original source details: GELFAND-P000057

Uncertain reading. Матен. / Матем.

GELFAND-P000058

Elem. of K — real vect. bundle, but with an equiv. relation. Add. — direct Σ. Mult. — tensor prod. of 2 vect. bund. 1 elem. in K, if

$$O_{N_1} \oplus \eta = O_{N_2} \oplus \zeta \quad \Longrightarrow \quad \eta \overset{K}{\sim} \xi$$



Original source details: GELFAND-P000058

Uncertain reading. After the second sum the sign resembles ζ; after the equivalence it resembles ξ / ζ. The initial oval permits O / 0.

$$O_N = X \times \mathbf{R}^N$$

Original source details: GELFAND-P000058

Uncertain reading. (Can, subgroups / induction [word overwritten and not established]).

Bund. up to equiv. — element of the K-funct. Совок. / Совап. — K-functor. Can add, mult.!



Original source details: GELFAND-P000058

Uncertain reading. Совок. / Совап.

Triv. bund. (Σ of tang. and norm. — triv., there is an inverse elem.) To each space assigns a ring) Over the sphere K-functor

$$K_{\mathbf{R}}(S^i) = \pi_i(BO)$$

(how many homot. maps to Grassm. mfld.)



Original source details: GELFAND-P000058

Diagram and typed description. Above large, the insertion Grassm. mfld.

K-funct. of sph. — bund. of Grassm. mfld. large dim.

BO — Grassm. mfld. — n-dim. lin. in N-dim. sp. (n and N large)



Original source details: GELFAND-P000058

Uncertain reading. everything stabilizes; the end of the word is crossed through, the exact boundary of the crossing is not established.

everything stabilizes

Vect. bund. with given base ⟵ neighb. of π_i. To the mfld. corresp.



Original source details: GELFAND-P000058

Uncertain reading. кас. / клас. сохрн. / сохрм. maps (abbreviations not fully established).

To the normal sheaf — norm. spher. map. Next an artificial device. $\mathbf{R}P^k$ subdiv. into cells (1 in each dim.) All vect. bund. over $\mathbf{R}P^i$ are constr. thus.

$$\sigma^i \quad \text{— } i\text{-dim. cell of } \mathbf{R}P^k$$



Original source details: GELFAND-P000058

Uncertain reading. After σ^i a short entry densely cancelled; below it, $\mathbf{R}P^i \longrightarrow \mathbf{R}P^{i-1}$. Above the first $\mathbf{R}P^i$ a small unidentified sign.

$\mathbf{R}P^i \longrightarrow \mathbf{R}P^{i-1}$

consid.



Original source details: GELFAND-P000058

Uncertain reading. Before S^i a dense short sign, its reading not established. Below, $\mathbf{R}P^k/\mathbf{R}P^{i-1}$ with a curved arrow.

$S^i = \mathbf{R}P^i/\mathbf{R}P^{i-1}$

$\mathbf{R}P^k/\mathbf{R}P^{i-1}$

All bund. are obtained thus. Bund. $S^i \longrightarrow$ bund. over $\mathbf{R}P^i \longrightarrow$



Original source details: GELFAND-P000058

Undeciphered passage. The arrow in the bottom line reaches the right edge; the next object is not visible in this frame.

GELFAND-P000059

$\longrightarrow$ bund. on $\mathbf{R}P^k$. $f(k)$ — number of asterisks to the left of k **Z** — invar. — dimension Crit. points appear on cycles

$\mathbf{Z}_{2^{f(k)}}$ cyclic gr. of order $f(k)$



Original source details: GELFAND-P000059

Uncertain reading. The index on **Z** permits $2^{f(k)}$ / $2f(k)$; the order caption visibly has $f(k)$, without a separate 2.

[At left an entry is cancelled.]

Original source details: GELFAND-P000059

Uncertain reading. short dense cancellation

$$\mathbf{R}P^k \subset \mathbf{R}P^{k+1}$$

there is a norm. sheaf — Möbius strip (this is a generator) of the group it must be added to itself $2^{f(k)}$ times



Original source details: GELFAND-P000059

Diagram and typed description. At left an almost horizontal line; five transverse arrows: two on the left down, the next three up. Two rightward arrows above the line, short on the left, long on the right. Below, an open oval arc with a gap at the lower right; its left end rises to the line and has an arrow, the right end is faint. No letter labels.



$$\underline{\nu^2 = 1} \qquad \lambda = \nu - 1$$
$$\lambda^2 = 1 + 1 - 2\nu$$
$$\lambda^2 = 2(1 - \nu)$$



Original source details: GELFAND-P000059

Uncertain reading. The narrow sign in ν resembles ν / v / V; some equality signs are overwritten. The last line is in a rounded frame open at the top.

$$\lambda^2 = -2\lambda$$

mult. structure. [A line is cancelled.]



Original source details: GELFAND-P000059

Uncertain reading. Long, densely crossed-out line on the left below the formulas

There is

Original source details: GELFAND-P000059

Diagram and typed description. Above the right side, two short horizontal strokes.

$$\mathbf{R}P^{n-1} \subset O_n$$

S^n is assigned to hyperpl. equators — into the orthog. group. Tang. sheaf — map.



Original source details: GELFAND-P000059

Uncertain reading. Above the arrow, a tight insertion $\mathbf{R}P^{n-1}$ / $\mathbf{R}P^n$ with an additional slanted connecting stroke; some signs are dense.

$$\begin{array}{ccc} & & \mathbf{R}P^{n-1} \\ & \nearrow & \\ S^{n-1} & \longrightarrow & O_n \end{array}$$

At symmetric points, the same. it is 2-sheeted (Gluing on the equator) rotation about it



Original source details: GELFAND-P000059

Uncertain reading. From the parenthesis about reflection an arrow down to $O(n)$; before $O(n)$ a black overwritten stroke, reading not established.

(reflection about it)

$$\downarrow$$

$$O(n)$$

axes of proj. space.

Uncertain reading. Albert Solom. / Soln.

Original source details: GELFAND-P000059

Schwarz.



Original source details: GELFAND-P000059

Diagram and typed description. Slanted line with a point and the label axis in $\mathbf{R}^n$.



$$\mathbf{R}P^{n-1}/\mathbf{R}P^{n-k-2} \longrightarrow O_n/O_{n-k-1}$$



Original source details: GELFAND-P000059

Uncertain reading. In the lower left exponent, $n-k-2$ / $n-n-2$; the arrow between the quotients is densely overwritten.

in fact an embedding.

GELFAND-P000060

1/III

V.P. Palamodov. $\mathcal{P}$ — ring of polyn. in $\mathbf{C}^n$, $\mathcal{J} \subset \mathcal{P}$ — ideal, primary, $P_1, \dots, P_s$ — gener. $\mathcal{H}$ — ring of entire funct. [a sign is cancelled] of a conv. region



Original source details: GELFAND-P000060

Uncertain reading. after funct. a short sign is densely crossed out

$\mathcal{H}/\mathcal{J}\mathcal{H}$ is described thus

$$\mathcal{H}\{\mathcal{J}\} = \{f|_N \quad f(z) = d(z,D)F_\zeta(z)\}$$
local part



Original source details: GELFAND-P000060

Uncertain reading. The subscript on F resembles ζ / s.

$$\mathcal{H}/\mathcal{J}\mathcal{H} \cong \mathcal{H}\{\mathcal{J}\}$$

Kazhdan says that this is obt. algebraically.

• Gelfand. Nelson's example. 2 self-adj. operators A and B. what [measures / changes] a self-adj. oper.? (not symm. closed)



Original source details: GELFAND-P000060

Uncertain reading. measures / changes

[In the right margin:]

$$i\frac{d}{dx}, \qquad y(a) = y(b)$$



Original source details: GELFAND-P000060

Uncertain reading. Below: or also / everywh. $= 0$; the short word and notation are not established.

Essentially self-adj. A (symm.), if there are no vect. orthog. to all ~~vect.~~ of the form

$$\overline{\overline{z}} = Ax - ix, \qquad \widetilde{z} = Ax + ix$$



Original source details: GELFAND-P000060

Uncertain reading. Above the first z two horizontal strokes, above the second a short uneven stroke: $\overline{\overline{z}}$ / $\widetilde{z}$.

(Then [an entry is cancelled] the same $\forall$ complex λ)



Original source details: GELFAND-P000060

Uncertain reading. short dense cancellation

otherwise $Ax - ix$ are everywhere dense $A - iE$ has inv. (in general?: if closed)

$$\left(i\frac{d}{dx} \quad \text{not even symm.} \quad \begin{matrix} f(a) = f(b) \\ f(a) = f(b) = 0 \end{matrix} \quad \begin{matrix} \text{essentially self-adj.} \\ \text{only symm.} \end{matrix}\right)$$

A and B essentially self-adj., $\alpha A + \beta B$ essentially self-adj., α, β — real.

$$\forall f \in \text{domain of def.} \qquad ABf = BAf.$$



Original source details: GELFAND-P000060

Uncertain reading. Above the domain of definition a short entry is densely overwritten; below it a curved stroke.

Nevertheless A and B do not commute.



Original source details: GELFAND-P000060

Diagram and typed description. At left Example. is crossed out and doubly underlined; to its right a double vertical stroke.

~~Example.~~ ||

A and B comm., if [reasonabl. / various / resolv.] funct. of them commute.



Original source details: GELFAND-P000060

Uncertain reading. reasonabl. / various / resolv.

$(A - \lambda E)^{-1}$
oper. bounded



Uncertain reading. Below λE lower strokes; whether a separate underline or parts of letters is not established.

Original source details: GELFAND-P000060

Comm. [a word is cancelled] also with B means that these oper. too [variabl. / commute].



Uncertain reading. a short word is densely crossed out

Original source details: GELFAND-P000060



Uncertain reading. variabl. / commute [final abbreviation not established].

Original source details: GELFAND-P000060

e^{iA} — unit. e^{iB} do not commute

[An entry is cancelled; beside it ($\forall$ bounded oper.).]

Uncertain reading. Short densely crossed-out entry

Original source details: GELFAND-P000060

GELFAND-P000061

Nelson's example.



Diagram and typed description. Square grid, heavy points and central hatching; labels $0, 1, 2, 3$ below, $1, 2, 3$ at left and 2 at right. Between 1 and 2 at left, an overwritten sign; the central overlapping strokes and exact gluing are not established.

Original source details: GELFAND-P000061



From the region between the squares, remove the heavy points The segments are glued each point is glued to the nearest boundary point along the horiz. or vert. The corners are glued together. Obtain a surface of genus $\underline{4}$ / $\underline{1}$ with one removed point

Uncertain reading. 4 / 1

Original source details: GELFAND-P000061

$$X = \frac{d}{dx}, \qquad y = \frac{d}{dy}$$

Uncertain reading. The second name to the left of the equality is y / Y; subsequently iY is written.

Original source details: GELFAND-P000061

iX, iY — formally self-adj. They commute But the corresp. oper. do not commute. Remove a measure-0 signif. / that is [значен. / значит.] traject. hit the vertices.



Uncertain reading. signif. / that is [значен. / значит.]

Original source details: GELFAND-P000061

e^X and e^Y — unit. oper. which do not commute.

$$e^{\frac{d}{dx}} f(x) = f(x+1)$$

(Taylor formula) Prove first for analytic funct., then for the whole Hilb. space by a limiting passage (the oper. is unitary) And it has to be moved.



Diagram and typed description. Square with a hole; hatching to the left of the hole and in the lower left region, two short strokes to its right. A slanted line runs from the lower left region down towards the caption. The boundaries of the overlapping strokes are not established.

Original source details: GELFAND-P000061



e^Y — region by 1 upwards, e^X will turn round

$$e^X$$

funct. with compact. / comp. [компт. / комп.] here.



Uncertain reading. compact. / comp. [компт. / комп.]

Original source details: GELFAND-P000061

Exclude a finite number of traject. e^{tX} — shift along the traject. of oper. X locally everywhere they commute what will happen to [an overwritten sign] the Laplace oper.?



Original source details: GELFAND-P000061

Uncertain reading. before oper., a dark overwritten stroke

deficiency index

$$\Delta f = if$$
$$\underline{\Delta = X^2 + Y^2}$$

(this follows from Nelson's theorem) It is not self-adj. (has a C^∞ solution, bound. cond., and at the point only $\int$ square.) The shift oper. themselves are def. on L^2, and not on periodic funct. 3 def e^{itA}:

$$1^\circ = \int_{-\infty}^{+\infty} \frac{e^{it\lambda}}{iA - \lambda}\, d\lambda$$
$$2^\circ = \int_{-\infty}^{+\infty} e^{it\lambda}\, dE_\lambda$$
$$3^\circ : \quad \frac{df}{dt} = iAf$$



Original source details: GELFAND-P000061

Uncertain reading. In the first entry the denominator is $iA - \lambda$; no separate factor before the integral is visible.



Original source details: GELFAND-P000061

Uncertain reading. Before the fraction in the third line, a short dark stroke; the exact reading is not established.

$\underset{\text{sol.}_{t,0}}{U} f_0 = f$ — unit. oper.

GELFAND-P000062

Sinai. Homol. / Posit. [Гомол. / Полож.] in dyn. systems.

Uncertain reading. Homol. / Posit. [Гомол. / Полож.]

Original source details: GELFAND-P000062

For an ergod. dyn. syst. [Crossed out: a short densely crossed-out entry; inserted above: with discr. spec.] the spectrum is always simple

Uncertain reading. a short densely crossed-out entry

Original source details: GELFAND-P000062

M, μ, $\{S_t\}$ — one-param. gr. in M In L^2_M / L^2_H a one-param. gr. of unit. oper.

Uncertain reading. L^2_M / L^2_H

Original source details: GELFAND-P000062

$$\underbrace{U_t}_{\text{simple}} f(x) = f(S_t x)$$

In the ergod. case every eigenvalue is simple Lebesgue spectrum: $\forall f$

$$(U_t f, f) = \int e^{it\lambda} p(\lambda)\, d\lambda$$

($p(\lambda)$ — integr.) (In general always $\int e^{it\lambda}\, d\mu$, here μ abs. cont.) Countably-mult. Leb. spec.: $\exists$ orthog. $f_1, f_2, \ldots$

$$(U_t f_i, f_j) = 0 \qquad (i \neq j)$$

and generate everything. In all known ex. the spectrum is countably-mult. Ex. Transf. of the torus.

$$\begin{pmatrix} a & b \\ c & d \end{pmatrix}, \qquad \det = 1, \quad \text{integer}$$

$$x \longrightarrow ax + by$$
$$y \longrightarrow cx + dy$$

Need to find autocorr. / autog. [автоκ. / автог.] Expand in a Fourier series and act.

Uncertain reading. autocorr. / autog. [автоκ. / автог.]

Original source details: GELFAND-P000062

$$f(x,y) \longrightarrow f(ax+by, cx+dy)$$
$$e^{2\pi i(mx+ny)} \longrightarrow e^{2\pi i((am+cn)x+(bm+dn)y)}$$

A matrix acts on the integer latt. Need to take trajectories

$$(m,n) \longrightarrow S(m,n) = (m',n')$$

The traject. is a hyperbola.



Original source details: GELFAND-P000062

Diagram and typed description. Above, two crossing strokes without explicit arrows. Below, an oblique line and two curved strokes; thickening at the crossing. The upper right end of the oblique line and the bottom end of the long curved stroke resemble arrows; the membership of the overlapping strokes is not established.



Real eigenvalues — contraction along one axis and expansion along the other (det $= 1$)

$$S^k \begin{pmatrix} m \\ n \end{pmatrix} \longrightarrow \lambda$$

(λ — eigenvalue)



Original source details: GELFAND-P000062

Uncertain reading. After the column $S^k(m,n)$, an arrow to λ; no additional factor at the column is visible.

The waves become ever denser and direct. Waves $\Longrightarrow$ towards an eigendir. The space decomposes into spaces of funct. with frequencies on hyperbolas. On the 1st hyperbola. A sequence of orthog. vect., each passes to the next

Original source details: GELFAND-P000063

Diagram and typed description. Above, a row of nine separate points.

(shift by 1 at the integer pts.) cont. Lebesgue spectrum. With the Bernoulli scheme — charact. of the group. Theorem. Measure $d\sigma(\lambda)$

Original source details: GELFAND-P000063

Diagram and typed description. Two crossing strokes; arrows to the right and upwards. No labels.

$\sigma \times \sigma$

$$\alpha = \lambda_1 + \lambda_2$$
$$\beta = \lambda_1 - \lambda_2$$
$$\text{measure} \quad d\sigma(\lambda_1) \times d\sigma(\lambda_2) = \underbrace{d\sigma^2(\alpha)}_{\text{convolution}}$$



Original source details: GELFAND-P000063

Uncertain reading. After the product of measures, $d\sigma^2(\alpha)$ is written, with convolution below; no separate factor in β is visible.



Original source details: GELFAND-P000063

Uncertain reading. Before /III, a densely overwritten sign: 8 / 4 / 1; below, Ya. Sinai / 2. Sinai.



Original source details: GELFAND-P000063

Diagram and typed description. A short horizontal stroke, a separate point, a longer almost horizontal stroke.

$M, \mu, \{S_t\}$. An eigenfunct.

$$U_t f_\lambda = e^{i\lambda t} f_\lambda$$

const. in mod (for an ergod. system) 15/III Todorov SU 22/III-65 In a year there will be a math. congress in Moscow. (March — April) [what is a “simple root”? connection with matrices] Gelf. [Гелф. / Гельф.] Probl.



Uncertain reading. Gelf. [Гелф. / Гельф.]

Original source details: GELFAND-P000063

1. Do alg. geom. over noncomm. rings!! 2. Alg. theory of diff. eqs. Povzner. Small parameter. Berezin. On funct. of many variables. Need to study not all funct., but specific ones — occurring in repr. theory and in stat. physics. Povzner a “wish” to Berezin. Kirillov. Ordinary dyn. syst. — time R or Z. Can have an arbitrary group preserving measure. Classific., invar.? [Before Spectrum, crossed out: a short entry under dense strokes.]



Uncertain reading. a short entry under dense strokes

Original source details: GELFAND-P000063

Spectrum — the set of irred. repr. into which the space of funct. on M decomposes

$$\begin{array}{ll} M & G \\ \underset{\text{funct.}}{H} & \underset{\text{unit. oper.}}{U_g : f(x) \longrightarrow f(g^{-1}x)} \end{array}$$

H decomposes into irred. compon., which are called the spectrum. G comm. — repr. [прдпр. / прдпрд.] are one-dimensional.

Uncertain reading. repr. [прдпр. / прдпрд.]

Original source details: GELFAND-P000063

G acts ergodically (no inv. funct. except const) For a compact gr. All transitive and reduce to describing subgroups. Ex. 1) Gordin and Whitehead.

$$G = \prod Z_2$$



Uncertain reading. Noncomm. group / Noncomp. group [Некомм. / Некомп.].

Original source details: GELFAND-P000063

Sequences of 0 and 1, a finite number not 0. $\sum$ usual. For it, the problem of describing repr. of virtual subgroups is solved

GELFAND-P000064

2) Dyadic-rat. numbers on the circle.

$$\underline{e^{i\frac{2\pi k}{2^n}}}$$



Uncertain reading. Overwritten strokes in the numerator: $2\pi k$ / πk.

Original source details: GELFAND-P000064

Countable. Dual gr. — 2-adic numbers. On it, already noncomm. facts. Point spectrum and cont. sp. Possibly, [crossed out: ϕ / illegible] prod. of funct., decomposed by sections.

Uncertain reading. ϕ / illegible

Original source details: GELFAND-P000064



Diagram and typed description. Two short sawtooth-like sections over horizontal underlines; the terminal strokes and some bends are uncertain.



Original source details: GELFAND-P000064

Cont. sp. gives a funct. decomposed over a discrete set. Oseledets: also held for an ordinary system. 2-dim. time.

$$\begin{pmatrix} a & b \\ 0 & 1 \end{pmatrix}$$



Diagram and typed description. Below the matrix, a long double underline with oblique strokes.

Original source details: GELFAND-P000064

Sinai's flows (equipped). Irred. repr. are few: one-dim. $|a|^{i\lambda}(\operatorname{sign} a)^{\varepsilon}$! And one infinite-dim. Connection with the Lorentz group.

Diagram and typed description. Wavy underline; below with [c], a short descending stroke with a bend.

Original source details: GELFAND-P000064

$$\begin{pmatrix} a & b \\ c & d \end{pmatrix}$$

Acts on Lobach. space (upper half-plane). About quot. by [crossed out: illegible] a discrete subgr. Will be compact, of negative curv.



Uncertain reading. illegible

Original source details: GELFAND-P000064

Tang. / oblique [Kac. / Koc.] bundle — a 3-dim. compact manif., on which acts an ergod. Lorentz gr.



Uncertain reading. Tang. / oblique [Kac. / Koc.]

Original source details: GELFAND-P000064

Discrete spectrum because of compactness. Homologies of dyn. systems. Operator

$$U_g = \alpha(x, g) f(xg).$$

A homomorphism then. $\alpha(x, g)$ — a cocycle. $|\alpha| = 1$.

$$\alpha \in Z^1(G, \underset{\text{gr. of functions}}{F}).$$

α equiv. if a continuous transf. exists. This happens if

$$\frac{\alpha}{\alpha_1} \in B^1(G, F)$$

General form of a boundary

$$\alpha_0(x, g) = \frac{\beta(xg)}{\beta(x)}$$

— homolog. to zero. Z^1/B^1 — homologies. Computed only if the gr. is transitive (then this is the set of repr. of the stabilizer subgr.). Homol. 0, not all const, but $e^{2\pi i t\lambda}$.

Diagram and typed description. At the right, a caption with a long curved underline.

λ from the spectrum.

Original source details: GELFAND-P000064

If a subgr., then the homol. gr. determines the dyn. system.

GELFAND-P000065

The collection of homol. is called a repr. of a virtual subgroup (although there is no subgr.). 2-dim. homol. of the spectrum of a dyn. system. f_λ — eigenfunct. Choose 1 fixed eigenfunct.

$$f_\lambda f_\mu = C_{\lambda,\mu} f_{\lambda\mu}$$

$C_{\lambda,\mu}$ — 2-dim. cocycles on the spectrum of a dyn. system.

$$C_{\lambda,\mu} C_{\lambda\mu,\nu} = C_{\lambda,\mu\nu} C_{\mu,\nu}$$

Equiv. to 1

$$C_{\lambda,\mu} = \frac{a_\lambda a_\mu}{a_{\lambda\mu}}$$

In the classical case these homol. are trivial ("the syst. is determined by the spectrum"). It is not known even whether a dyn. syst. is determined by its spectrum for finite groups (Gelfand thinks not). Rotation group of the icosahedron.

$$\begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix}, \qquad \alpha\delta - \beta\gamma' = 1$$



Uncertain reading. By γ in the determinant condition, an upper stroke is visible; γ' / γ.

Original source details: GELFAND-P000065

$\alpha, \beta, \gamma, \delta$ mod 5. (At a vertex, 5 triangles.) Klein. Lectures on the Icosahedron.

$$T_g f(x) = f(xg)$$

Need to recover X. There are shift oper., a group. But there are also oper. of mult. by a funct. (but if there is a ring, then the repr. in the ring determines the dyn. system). 29/III Viktor Nikolaevich. Connection between Lie algebras and assoc. algebras.

$$\begin{array}{ccc} L & \longrightarrow & U \\ \text{Lie alg.} & & \text{univ. envelop. alg.} \end{array}$$

Harish-Chandra — if L is simple, what can be said about U? Jacobson's problem: what is needed for U to be primitive (a faithful irred. module over it exists). Example. e_1, e_2, $[e_1, e_2] = e_1$ — U primitive. $[e_1, e_2] = 0$ — U non-primitive. (This is a polynomial ring, and a commut. primitive alg. is a field.) $A^{(-)}$ — a Lie alg. obtained from an assoc. alg. A (ab-ba). Which properties of A carry over to $A^{(-)}$? In A — Lie ideals. Baxter. If A is Jacobson semisimple.



Original source details: GELFAND-P000065

Diagram and typed description. If A is simple, then there are no Lie ideals either. (If there are no ordinary ideals, then there are no Lie ideals either.)

GELFAND-P000066

II / III. Burnside's probl. Kostrikin's result.



Uncertain reading. II / III

Original source details: GELFAND-P000066

(A — an alg. [Crossed out: illegible; below it: assoc.?]



Uncertain reading. illegible

Original source details: GELFAND-P000066

X — a finite set, [crossed out: illegible]

Uncertain reading. illegible

Original source details: GELFAND-P000066

generating A, $[X]$ $\supset X$.
generated Lie alg.

$\exists$ [crossed out: $\forall$] n, $\quad e \subset [X], \quad e^n = 0.$



Uncertain reading. $\exists\, n$, an overwritten sign before n; relation $e \subset [X]$ / $e \in [X]$.

Original source details: GELFAND-P000066

Then A nilpot. (i.e. $\forall$ elem. is nilpotent). Gelfand. Dixmier — unsolved problem: 2 rings $P(x, \frac{d}{dx})$ and $P(x, \frac{d}{dx}, y, \frac{d}{dy})$ (polynomials). Are these rings isomorphic? S. Gelfand. Dyson. 1. Orthog. ensemble.

$U^T = U$ symm.
$UU^* = 1$ and unit.

Inv. for the unit. gr.

$$U \longrightarrow VUV^T$$

(a homogeneous space of the unit. group). Density of the distribution of eigenval. $P(\theta_1, \dots, \theta_N)d\theta_1 \dots d\theta_N$ — measure of matrices, eigenval. (their args.) in $(\theta_1, \theta_1 + d\theta_1); \dots$. Stabilizer subgr.: $E \longrightarrow VV^T = E$ (real orthog. matrices). An inv. measure is introduced. Turns out

$$p_1(\theta_1, \dots, \theta_N) = C_1 \prod_{i<j} |e^{i\theta_i} - e^{i\theta_j}|$$

2. All unit. matrices. (Probab. of eigenvalues!) Group — unit. [Inner autom.] $U \longrightarrow VU$ [then a crossed-out sign: illegible, resembling V^*.]

Uncertain reading. illegible, resembling V^*

Original source details: GELFAND-P000066

$$p_2(\theta_1, \dots, \theta_n) = C_2 \prod_{i<j} |e^{i\theta_i} - e^{i\theta_j}|^2$$

Uncertain reading. In the last argument of p_2, the index is n / N.

Original source details: GELFAND-P000066

(Inv. measure of the unit. gr. $\int$ over conjugacy classes.) Distinct eigenval. are more probable. [Above θ: a circled letter: Δ / illegible; a triangular sign inside an oval. .]

Uncertain reading. Δ / illegible; a triangular sign inside an oval.

Original source details: GELFAND-P000066

Consider all matr., $-\alpha < \theta < \alpha$ contains no eigenvalues. The probability of this is calculated.

$$R_\alpha(\alpha) = \int_\alpha^{2\pi-\alpha} \int \dots \int_\alpha^{2\pi-\alpha} |e^{i\theta_i} - e^{i\theta_j}|^\beta \, d\theta_1 \dots d\theta_N$$



Uncertain reading. In this line, no definite $\prod$ is visible before the absolute value; the index of R resembles α, argument α / d.

Original source details: GELFAND-P000066

$\beta = 1, 2$. For Dyson, $\forall\beta$. Physical assumptions are made. Phys. analogy.

Diagram and typed description. A circle without labels.



Original source details: GELFAND-P000066

Conducting wire in the form of a circle, on it N charges, repelling by 2-dim. electrostat. Then the energy (potent.) = W. [Crossed out before the sum: $\prod_{i<j}$ / illegible.]



Uncertain reading. $\prod_{i<j}$ / illegible

Original source details: GELFAND-P000066

$$W = \sum_{i<j} \ln |e^{i\theta_i} - e^{i\theta_j}|$$

(Free charges.) With this, the gr. can. stat. functions.

$$\int_0^{2\pi} \int_0^{2\pi} \dots \int_0^{2\pi} e^{[-\beta W]}\, d\theta_1 \dots d\theta_N$$

GELFAND-P000067

$\beta = \frac{1}{T}$. $T = 1$ and $1/2$ correspond to the orthog. and unit. ensembles. The segment $(-\alpha, \alpha)$ is forbidden.



Diagram and typed description. A circle with a short dark right-hand section between the labels α and $-\alpha$. The thick terminal strokes do not establish arrows.



Original source details: GELFAND-P000067

Free energy.

$$R_\beta(\alpha) = e^{\beta[F(\alpha) - F(0)]}$$

F — free energy. (This equality can be taken as its def.) Consider matrices with no eigenval. in the interval $-\alpha < \theta < \alpha$. Their probability

$$\Psi_\beta(\alpha) = \int_\alpha^{2\pi-\alpha} \dots \int_\alpha^{2\pi-\alpha} \prod_{i<j} |e^{i\theta_i} - e^{i\theta_j}|^\beta \, d\theta_1 \dots d\theta_N$$



Uncertain reading. The initial letter Ψ in the integral is overwritten; the upper reading is Ψ, the lower one is not established.

Original source details: GELFAND-P000067

$$R_\beta(\alpha) = \frac{\Psi_\beta(\alpha)}{\Psi_\beta(0)}$$

(Need to calculate.) Phys. assumptions. Let N be large, introduce a density of eigenval. (instead of eigenval.). $\sigma(\theta)d\theta$. $\sigma(\theta)$ — δ-funct. at the points $\theta_1, \dots, \theta_n$. $\sigma(\theta)d\theta \longrightarrow$ number of eigenval. in the interval $d\theta$.

$$R_2(\alpha) = e^{(N^2 \ln \cos \frac{\alpha}{2})}$$



Diagram and typed description. The exponent is enclosed in round parentheses.

Original source details: GELFAND-P000067

Assumptions. 1) The distribution of eigenvalues is given by $\overbrace{\sigma_\alpha(\theta)}$. Under Dyson's assumpt., between $(-\alpha, \alpha)$ they are 0. (For $\forall$ matr., its own function.) Generalization — for Dyson [crossed out: an illegible word and a short fragment] any cont. funct. ($N \to \infty$).



Uncertain reading. an illegible word and a short fragment

Original source details: GELFAND-P000067

2) $F = V + F_1$. def:

$$V = \underbrace{-\frac{1}{2} \int_\alpha^{2\pi-\alpha} \int \sigma_\alpha(\theta)\sigma_\alpha(\varphi) \ln|e^{i\theta} - e^{i\varphi}| \, d\theta \, d\varphi}_{\text{Coul. energy}}$$

def:

$$F_1 = \int_\alpha^{2\pi-\alpha} \sigma_\alpha(\theta) f_\beta(\sigma_\alpha(\theta)) \, d\theta$$

f_β — a certain funct., written out explicitly.

GELFAND-P000068

The assumpt. consists in

$$R_\beta(\alpha) = e^{\beta(F(\alpha)-F(0))}$$

where σ is a funct. giving the minimum of the functional F (with $\int_\alpha^{2\pi-\alpha} \sigma(\theta)d\theta = N$).

$$f_\beta = U_\beta(\sigma) - \beta^{-1} S_\beta(\sigma)$$

where [in U_β, the first term is crossed out: illegible]

Uncertain reading. illegible

Original source details: GELFAND-P000068

$$U_\beta(\sigma) = -\frac{1}{2}\ln \pi\sigma + u(\beta)$$
$$S_\beta(\sigma) = \ln \frac{N}{2\pi\sigma} + S(\beta)$$



Uncertain reading. In the terms independent of σ, $u(\beta)$ / $U(\beta)$ and $S(\beta)$ / $s(\beta)$.

Original source details: GELFAND-P000068

U — potent. energy, S — entropy in the system. N charged points on a circle.

$$W = \sum_{i<j} \ln |e^{i\theta_i - i\theta_j}|$$



Uncertain reading. On the right-hand side of W, after the first e, $i\theta_i - i\theta_j$ is visible; a second e is not established.

Original source details: GELFAND-P000068

$\beta = \frac{1}{T}$. T — temperature. The distribution of these points will be the same as the distribution of eigenval.

$$\int\int = \int\int e^{\beta \sum \ln |e^{i\theta_i} - e^{i\theta_j}|} \prod d\theta_j$$



Diagram and typed description. The exponent of the last integral reads $\beta \sum \ln |e^{i\theta_i} - e^{i\theta_j}|$; no minus is visible before β.

Original source details: GELFAND-P000068

The canonical $\int$ of statistical physics in the plane. Next time: Minlos and S. Gelfand and Bernstein — monoidal transformations.

GELFAND-P000069

[Above the heading, a line is crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000069

$5/\overline{\text{IV}}$. I. Bernstein. Grothendieck top. and monoidal transformations. Dioph. eq. $F(x) = 0$. F — polyn. with integer coeff., $x_1, \ldots, x_n$. Usually reduce mod p. Everything in Z_p. $a_i, z_i \in Z_p$.



Uncertain reading. A small raised stroke is visible at z_i; z_i / z_i^1 / z_i'.

Original source details: GELFAND-P000069

If the sol. is known $\forall Z_p$, then there is inform. for any Z. Weil. Take F over the alg. closure of Z_p. Polyn. — surf. How many points over Z_p? $\mathcal{L}$ / Y — closure of Z_p.

Uncertain reading. $\mathcal{L}$ / Y

Original source details: GELFAND-P000069

$x \longrightarrow x^p$ — homomorphism (since the field has char. p) (automorphism of the ring $\mathcal{L}$ / Y).

Uncertain reading. $\mathcal{L}$ / Y



Original source details: GELFAND-P000069

The fixed elem. of the base field: $x^p = x$ in the base field and only these (since $\leq p$ solutions).

$$(x_1, \ldots, x_n) \longrightarrow (x_1^p, \ldots, x_n^p)$$

How many fixed points? These will be in Z_p. The coeff. are fixed under the automorphism. The number of fixed points is found using the Lefschetz formula. $f : X \longrightarrow X$. X — top. space. If f is in gen. position, then one can find $H^n \longrightarrow H^n$.

$$\frac{\sum(-1)^i \operatorname{Sp} f^* H^i}{\text{number of fixed points}}$$

— Lefschetz formula!



Uncertain reading. The exponent over f is overwritten; the upper layer resembles *, the lower one n.

Original source details: GELFAND-P000069

Sp $f^* H^i$ (H^i — cohomol.). Closed sets — $\bigcup$ of a finite number of alg. submanifolds of smaller dimensions. (Zariski top.) It is негусса / негуща — generally bad.



Uncertain reading. негусса / негуща

Original source details: GELFAND-P000069

Grothendieck generalizes and improves. Definition. Grothendieck top. C — category, X — distinguished object (one). New categ. C_X — objects — $(c, \varphi : c \longrightarrow X)$, $c \in C$. Mapping
pair

$(c_1, \psi : c_1 \longrightarrow X)$.



Uncertain reading. The letter in the second pair and on the right arrow: ψ / γ.

Original source details: GELFAND-P000069



def commutative. [To the left of the diagonal arrow, a stroke is crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000069

The elements of C_X are called open sets [inserted: over] X. A topology is introduced in X. This is no special case of ordinary top. — the reverse.

GELFAND-P000070

U — elem. of C_X — open sets. Fix a fam. of mappings
object

$$\{U_\alpha \longrightarrow U\}_{\alpha \in I}$$

There are terribly many such families. Some of these families are called coverings of U, if 1°. $\{U \xrightarrow{\text{id}} U\}$ [Crossed out and inserted above: is; the crossed-out word is illegible] a covering.

Uncertain reading. is; the crossed-out word is illegible

Original source details: GELFAND-P000070

Example. X — space (top.). C — open sets, mapping — inclusion (if no incl., then none). C_X is almost C (incl. in X). Covering U_α — completely covers U. 2°. $\{U_\alpha \to U\}$ — cov. $\forall \alpha$ there is a covering $\{U_{\alpha\beta} \to U_\alpha\}$, $\alpha \in I$. Then $\{U_{\alpha\beta} \to U\}$ — also a covering. 3°. [Before "def." a symbol is crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000070

Def. [crossed out: fibred; above: direct] product.



Uncertain reading. fibred

Original source details: GELFAND-P000070

[On the right:] $X \times Y$. A — categ., def. of product: $x, y \in A$. Product — object Z and





Uncertain reading. Both projections carry the same p-like sign; p / ρ, indices not established.

Original source details: GELFAND-P000070

If $T \in A$, and φ, ψ are given



then there exists a unique f



Diagram and typed description. The two arrows from T point to x, y; in the next diagram f points from T to Z.



Original source details: GELFAND-P000070

(If it exists, then it is called a product.) [Crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000070

The product is defined uniquely up to isomorphism $\underset{1}{\overset{\longrightarrow}{\longleftarrow}}$.

Diagram and typed description. Two opposing arrows, upper rightwards, lower leftwards; 1 below them.

Original source details: GELFAND-P000070

Example. X — top. space, elem. — open sets.

$$U \times V = U \cap V = Z$$

Mappings to U, V — incl. Ax. 3°. In categ. C_X there exists the product of any 2 [above: — two.] elements.



Diagram and typed description. Above "2", "— two." is inserted.

Original source details: GELFAND-P000070

(Here this is the intersect. of $\forall$ 2 sets.) Reason in C. Look at the categ. of sets with all mappings (product rel. to X



Diagram and typed description. Two arrows with unlabelled upper objects meet at X.

Original source details: GELFAND-P000070

pairs (x, y) map to 1 element. (If X is a point, then the direct product.)

GELFAND-P000071

Ax. 4. (intersection is defined)

Given $f : V \to U$ (open sets) and a covering $\{U_\alpha \to U\}$.

$$\{V \times_U U_\alpha \to V\} \quad \text{will also be a covering.}$$

Product in categ. C_U.





Diagram and typed description. An arrow $V \to U$; two oblique arrows from V and U meet at X. The arrows have no labels.

Original source details: GELFAND-P000071



$U_\alpha \cap V$

also coverings



Diagram and typed description. A circle with an external letter U; the inner sign resembles O / 0, with a heavy upper stroke and a stroke inside.

Original source details: GELFAND-P000071

Uncertain reading. At the extreme right edge, a separate vertical stroke resembling 1; a complete leaf number is not readable.

Original source details: GELFAND-P000071

Presheaf. $U \to P(U)$ (ab. group)

$$U \to V, \qquad P(U) \leftarrow P(V).$$

And ax. $1 \to 1$ and functor.

Not every presheaf is a sheaf.

Uncertain reading. “This is a functor” is densely crossed out / overwritten.

Original source details: GELFAND-P000071

Let there be a sect. $P(U)$ and a covering $\{U_\alpha \to U\}$. Then a mapping is def. $P(U) \to P(U_\alpha)$, hence $P(U) \to \prod P(U_\alpha)$.

Sheaf ax. — 1°. This is an embedding.

$$0 \to P(U) \to \prod P(U_\alpha).$$

2°. If $\xi_\alpha \in P(U_\alpha)$, $\xi_\beta \in P(U_\beta)$ are compat. with each other, [?],



Uncertain reading. after the comma, short upper strokes; before "images", a crossed-out sign is illegible

Original source details: GELFAND-P000071

$$\begin{array}{ccc} P(U_\alpha) & & \\ & \searrow & \\ & & P(U_\alpha \times_U U_\beta) \\ & \nearrow & \\ P(U_\beta) & & \end{array}$$

the images coincide,

Uncertain reading. At the left, a note "U_α-mor. U" / "U_α-kor. U".

Original source details: GELFAND-P000071

then there exists [Inserted above: sect.] $\xi \in P(U)$ such that they are obtained from it.



Diagram and typed description. Above "exists", "sect." is inserted.

Original source details: GELFAND-P000071

Top. over a point — unusual sheaves. To a point — fields, this is Galois theory, and

Original source details: GELFAND-P000071

Uncertain reading. “gon.” / “gom.” [гон. / гом.] — topol. of Galois groups.

Sheaf ax. in the form of an exact seq.

$$0 \to P(U) \to \prod_{\alpha} P(U_\alpha) \overset{f-g}{\underset{\swarrow}{\rightrightarrows}} \prod_{\alpha,\beta} P(U_\alpha \times_U U_\beta).$$



Original source details: GELFAND-P000071

Uncertain reading. Below, at the end of the arrow pointing down and left, a densely crossed-out sign; the exact reading is not established.

[In the right margin:]

$U \times_X V$ in [crossed out: illegible] C_X;
$U \times_U V$ in categ. C_U.



Original source details: GELFAND-P000071

Uncertain reading. In the upper marginal note, between “in” and C_X, a densely overwritten fragment.

2 mappings.

$$U_\alpha \times_U U_\beta \to U_\alpha,$$
$$U_\alpha \times_U U_\beta \to U_\beta.$$

Whence

$$P(U_\alpha) \to P(U_\alpha \times_U U_\beta),$$
$$P(U_\beta) \to P(U_\alpha \times_U U_\beta).$$

Therefore def. [?],

Original source details: GELFAND-P000071

Uncertain reading. before $P(U_\alpha)$, densely crossed-out signs, probably a product sign

$$\prod P(U_\alpha) \to \prod P(U_\alpha \times U_\beta),$$

and [?]:



Uncertain reading. in the next line, both on the left and on the right, $\prod P(U_\alpha \times U_\beta)$ is visible

Original source details: GELFAND-P000071

$$\prod P(U_\alpha \times U_\beta) \to \prod P(U_\alpha \times U_\beta).$$

$$\prod_\alpha P(U_\alpha) \xrightarrow{f} \prod P(U_\alpha \times U_\beta),$$
$$\prod_\beta P(U_\beta) \xrightarrow{g} \prod_{\alpha,\beta} P(U_\alpha \times U_\beta).$$

GELFAND-P000072

Gindikin. Eigenval. on a symm. space. Need to know roots. Sem. Sophus Lie, [?], Pontryagin.



Uncertain reading. “Dzheloben” / “Dzhelobe” / “Dzhekobson” [Джелобен / Джелобе / Джекобсон]

Original source details: GELFAND-P000072

G. Topic: study of Dyson, $\forall$ symm. spaces.

$12/\overline{\text{IV}}$. Stepin. Kirillov's probl. Construct an example [crossed out: an illegible word]



Uncertain reading. an illegible word

Original source details: GELFAND-P000072

of a dyn. syst. with cont. spectrum, dyadic-rat. numbers on the circle G. Every elem. — of finite order. (not with discr.) $g \to T_g$. Suff. to specify



Uncertain reading. “perekh.” / “pred.” [перех. / пред.]

Original source details: GELFAND-P000072

images of $1/2^k$.

$$T^2_{1/2^k} = T_{1/2^{k-1}}.$$

$T_0 = E$, T_1 — [?], refl.

Uncertain reading. a crossed-out word resembling “rotation” / “refl.”

Original source details: GELFAND-P000072

Next, break up the segments. (pieces) preserving orientation.



Original source details: GELFAND-P000072

Uncertain reading. The underlined word's ending: "segments" / "segment" [отрезки / отрезка]; a full stop follows it.

[On the right:] $1/2^k \to T_k$.



Original source details: GELFAND-P000072

Uncertain reading. At the left before the heading, a densely overwritten sign; the exact reading is not established.

What is it desirable for participants in the seminar to know?

1. Representations. Lie groups and Lie algebras. Symmetric spaces. Simple Lie groups.
2. 

Original source details: GELFAND-P000072

Uncertain reading. "Homologies" / "Homolies" and "Representations" are crossed out.

   Sheaves. Homol. algebra (fundamentals). Vector bundles.
3. Elements of algebraic geometry.
4. Quantum mechanics (nonrelativ.). Cauchy $\int$ of several variables according to Gindikin will be incl.

an illegible sign.

Original source details: GELFAND-P000072

Uncertain reading. an illegible sign

   Nuclear spaces and measures (Wiener measure).

S. Gelfand. $R_2(\alpha)$ calculated exactly. [?]:

Original source details: GELFAND-P000072

Uncertain reading. In the exponent after the parenthesis, a densely overwritten sign before 2, probably n^2

$$R_2(\alpha) = \left(\cos\frac{\alpha}{2}\right)^{n^2}.$$

(This is asserted, but not proved.) This probl. is replaced by another for which this is the exact answer.

Dyson's 3rd paper. $S(\theta)$.

$$(\theta_1, \theta_1 + d\theta_1), \qquad (\theta_2, \theta_2 + d\theta_2).$$





Diagram and typed description. A circle; at the upper right, two short transverse strokes and a short curved stroke; at the lower right, a heavy mark pointing outward. The marks have no labels.

Original source details: GELFAND-P000072

Prob. that there is an eigenval. in the 1st interval, one in the 2nd, and none between. This is

$$F(\theta_1, \theta_2) d\theta_1 d\theta_2.$$

It depends on the difference.

$$F(\theta_1; \theta_2) = S(\theta_1 - \theta_2).$$



Uncertain reading. Between $F(\theta_1; \theta_2)$ and the equals sign, densely crossed-out signs; the original entry is illegible.

Original source details: GELFAND-P000072

This ~~$S(\theta)$~~ —

Diagram and typed description. At the bottom, $S(\theta)$ is crossed out.

Original source details: GELFAND-P000072

[On the right:] easy to prove.

$$S(\theta) = \frac{d^2 R}{d\theta^2}.$$

GELFAND-P000073

$R(2\alpha)$ — prob. that there are no eigenval. in $(-\alpha, \alpha)$.

$$R_1(2\alpha) = \det \left| \delta_{pq} - \frac{1}{\pi} \int_{-\alpha}^{\alpha} \cos p\theta \cos q\theta \, d\theta \right|, \qquad p, q = \frac{1}{2}, \ldots, m - \frac{1}{2}, \quad 2m \geq n.$$

Uncertain reading. The relation sign: $2m \geq n$ / $2m = n$; its upper stroke slopes and the sign is heavily written.

Original source details: GELFAND-P000073

Asymptotics [?]:



Uncertain reading. In the exponent on t, $17/8$ is visible; the first sign is heavily written.

Original source details: GELFAND-P000073

$$R_1(t) \sim A t^{17/8} \exp\left[-\frac{1}{4}t^2 - \frac{1}{2}t\right], \qquad \underline{\underline{t = \alpha n}}.$$

And other results (analogous).

Minlos. Elems. of the matrix (Hermit.) — random numbers with Gauss. distr.



Diagram and typed description. Below the word “matrix”, “(Hermit.)” is inserted.

Original source details: GELFAND-P000073

Brownian motion.

———— • ————

Diagram and typed description. Two horizontal strokes with a point between them.

Original source details: GELFAND-P000073

What is the angle of k-dim. subspaces in an n-dim. space?

Kazhdan. Res. of Gromov from Leningrad; [?].



Original source details: GELFAND-P000073

Uncertain reading. “who caught a bird on the move” [схватившего птицу на ходу / схватившему птицу на ходу]; the participle’s ending is uncertain

Dvoretzky’s res. $\forall \varepsilon, k\ \exists$ a space of a suff. large number of dims., such that $\forall$ [crossed out: an illegible word beneath several heavy strokes]

Original source details: GELFAND-P000073

Uncertain reading. an illegible word beneath several heavy strokes

convex centrally symm. body $\exists$ a section almost a ball (k-dimensional). Dvoretzky did it head-on (70 pp.). (In a space of a large number of dims., there is almost a circle in a section.) Gromov is weaker, but [?].



Original source details: GELFAND-P000073

Uncertain reading. “also req. relat. size of the ball and conv. was” [ещё треб. относит. велич. шара и вып. было]; the short phrase is not fully legible

[Inserted below:] a stronger theorem is obt.

Def. $G_{n,k}$. $M_{n,k}$ — a k-dim. plane and a point of its unit sphere.

$$M_{n,k} \xrightarrow{S_k} G_{n,k}.$$



Original source details: GELFAND-P000073

Uncertain reading. Above the arrow, S_k; the small lower index is heavily written.

A bundle of spheres over $G_{n,k}$ (Grassm.). Convex body $\to$ a function on $M_{n,k}$ [?].



Original source details: GELFAND-P000073

Uncertain reading. (func. determ. by the 1st vector (its H и отк. convex body)); the two middle signs and the following abbreviation are unclear

[On the right, crossed out: a short word beginning with “П”; the remainder is illegible.]

Uncertain reading. a short word beginning with “П”; the remainder is illegible

Original source details: GELFAND-P000073

Let us expand it in sph. funcs. If n is large, then $\exists$ a fibre such that the first ℓ funcs. vanish (except 1). $\forall$ repr. of the unit. group $\exists n$ such that $\forall$ funcs. on $M_{n,k}$ $\exists$ a fibre such that the proj. $= 0$. Conv. — compactness on funcs.

Uncertain reading. a densely overwritten sign; the exact reading is not established.

Original source details: GELFAND-P000073

Fourier coeffs. — many 0.

GELFAND-P000074

Kirillov. A convex body (centrally symm.) in R^3 (R^n). Draw plane sections through the centre. The areas of all its sects. are known. The body is recovered from the areas of the sections.



Uncertain reading. ($\forall$ body [inserted “odin.” / “odinak.” (equal)] sect. areas is a ball).

Original source details: GELFAND-P000074

Consider S^2 and a func. on it. Can it be recovered if the $\int$ over great circles is known (even funcs.). This probl. is solved triv. using expansion in sph. funcs.



sect. $\longrightarrow$ norm.

vect.





Diagram and typed description. An outer oval and an irregular inner contour; an oblique vector pointing upward to the right, a short downward arrow, an angle mark and short transverse strokes. Beside them, “sect.” and “norm.” are crossed out; “vect.” is inserted below the latter. Farther right, a separate oblique arrow has a heavy mark at its lower end.

Original source details: GELFAND-P000074

Uncertain reading. Inside the inner contour, a winding sign; its exact reading as a letter is not established.

Original source details: GELFAND-P000074

On the sphere, a vect. of the same direction. A func. on the sphere $\to$ [crossed out: an illegible entry beneath several heavy strokes]



Uncertain reading. an illegible entry beneath several heavy strokes

Original source details: GELFAND-P000074

$r^2/2$ (so that the $\int$ equals the area). A convex body $K \longrightarrow$ a func. on the sphere. We obtain a probl. of $\int$ geometry. If all the shadows of the convex body (areas) are known, is the body known? Reduces.

19/IV. Faddeev. Ludwig (the younger). What is the characteristic determ. of the Sturm–Liouville oper.? On the half-line. (For a matrix — zeros — eigenval., Fredholm det.) A — a matrix, $w(\lambda) = \det(A - \lambda E)$.

Diagram and typed description. Notation for the characteristic determinant: $w(\lambda)$.

Original source details: GELFAND-P000074

Then

$$\frac{d}{d\lambda} \ln w(\lambda) = -\operatorname{Tr}(A - \lambda E)^{-1}.$$

(Check using eigenval.) Determ. $w(\lambda)$ up to mult const. The same in $\int$ eqns.

$$Ly = -y'' + q(x)y, \qquad y'(0) = y'(\pi) = 0.$$

The resolvent — an $\int$ oper. with a smooth kernel and the trace exists. The determ. — an entire func. of λ and its zeros — eigenval. of the St.–Liouv. probl.

$$\psi(x,\lambda), \qquad \left.\begin{matrix}\psi(0,\lambda) = 1\\ \psi'(0,\lambda) = 0\end{matrix}\right\} \quad \underline{\psi'(\pi,\lambda) = w(\lambda).}$$



Original source details: GELFAND-P000074

Uncertain reading. The normalized solution's letter: ψ / φ; an open left branch, a right loop and a descending stroke.

Original source details: GELFAND-P000074

Diagram and typed description. Two short horizontal strokes with a point between them.

$y(0) = 0$, $q(x) \to 0$, $x \to \infty$ suff. rapidly. The res. has no trace; the resolvent does not decrease, by [?],



Original source details: GELFAND-P000074

Uncertain reading. "nevb." / "neub." [невб. / неуб.]

the part has a triv. form. Regularize it.

$$r(x,x,\lambda) = \frac{1}{2i\sqrt{\lambda}} - O(1).$$



Original source details: GELFAND-P000074

Diagram and typed description. In the right margin, a double almost vertical stroke and y''.

y'' The resolvent is not an entire func. (Poles, we obtain — the spectrum.) The res. — the kernel $K(x,y,\lambda)$.

GELFAND-P000075

What singularities? [?]:



Uncertain reading. After $-y''$, the sign before λy is overwritten; the initial right-hand side is crossed out and $\delta(x - x_0)$ is written below

Original source details: GELFAND-P000075

$$-y'' - \lambda y = \delta(x - x_0).$$

It will be the resolvent. There are 2 lin. indep. sols. So as not to grow. The 1st deriv. must have a jump.



Diagram and typed description. The horizontal axis rises slightly to the right. Two branches meet at a peak above it; the left rises, the right decreases. A vertical segment goes from the axis through the peak and a little above it. There are no labels.

Original source details: GELFAND-P000075

$\lambda > 0$ does not work (sin and cos), $e^{\pm\sqrt{-\lambda}\,x}$. When crossing the axis, $\sqrt{\ }$ changes sign. This does not fit into the general theor. of operators.



Uncertain reading. (where the resolvent is multivalued); the beginning of “multivalued” [многозначна] is heavily written.

Original source details: GELFAND-P000075

— one must go outside the Hilbert space. 2-dim. case: ln (many-sheeted).

For the cont. spectrum, let

$$f(x, \sqrt{\lambda}) \sim e^{i\sqrt{\lambda}x}, \qquad x \to \infty.$$

Then $w(\lambda) = f(0, \sqrt{\lambda})$ (in the phys. lit., the Jost func.).



Diagram and typed description. Notation in the line with the Jost function: $w(\lambda)$.

Original source details: GELFAND-P000075

On the whole axis, it is no longer expressed through 1 solution.

$$f_1(x, \sqrt{\lambda}) \sim e^{i\sqrt{\lambda}x}, \quad x \to +\infty,$$
$$f_2(x, \sqrt{\lambda}) \sim e^{-i\sqrt{\lambda}x}, \quad x \to -\infty.$$

Their Wronskian — is the determ.

$$f_1' f_2 - f_1 f_2' = W(\lambda).$$

(Does not depend on the point — $\to$ the 2nd coeff. $= 0$.) How, knowing the determ., to write an identity for eigenval.

$$\frac{1}{2\pi i}\oint h(\lambda)\frac{W'(\lambda)}{W(\lambda)}\,d\lambda =$$

det — an entire func. of λ, discr. 0 on the $+$ axis. For good $h(\lambda)$

$$= \sum h(\lambda_i) \quad \text{over zeros } \lambda_i \text{ of } W(\lambda).$$

$h(\lambda) = \lambda^s$.

Uncertain reading. Below $h(\lambda) = \lambda^s$, a short expression is crossed out: the first sign is 1 / λ, followed by poorly distinguishable strokes.

Original source details: GELFAND-P000075

[Before the next line, densely crossed out: a short entry; its exact reading is not established.]

Uncertain reading. a short entry; its exact reading is not established

Original source details: GELFAND-P000075

Deform the contour. We obtain.





Diagram and typed description. Axes with arrows upward, downward and to the right; on the left, two short lines merge at the origin. The upper curve goes downward to the right to an arrow; from its end, an S-shaped line bends to the right of the origin and goes downward to the left to another arrow. There are no labels.

Original source details: GELFAND-P000075

$$\int_{-\infty}^{0} |\lambda|^s \frac{W'(\lambda)}{W(\lambda)}\, d\lambda = \sum_i \lambda_i^s.$$

(Re s, so that the $\int$ converges.) And its analyt. cont. automatically regularizes it. ($\int$ — the jump.) W has known asymptotics (therefore its decrease is known).

$$\frac{W'(\lambda)}{W(\lambda)} = d_1 - \frac{d_2}{\sqrt{\lambda}} - \frac{d_3}{\lambda} - \dots$$

s is taken negative and then it is proved that the left and right sides — are analyt. funcs. of s. [?]:



Uncertain reading. On the right, the letter y with a prime: $y'(0)$ and $y'(\pi)$.

Original source details: GELFAND-P000076

$$\sum_n (\lambda_n - n^2 - c_0) = \frac{1}{4}\big(y'(0) - y'(\pi)\big).$$

Diagram and typed description. Two short separating strokes with a point between them.

Original source details: GELFAND-P000076

How to calculate the trace?

$$\sum \lambda_n = \int K(x,x)\, dx.$$

Diverges. (Sum of diag. elems.) Diag. elems.

$$-\delta''(x_1 - x_2) + q(x)\delta(x_1 - x_2).$$



Diagram and typed description. In the diagonal element, the first δ has two primes; the second δ has none.



Original source details: GELFAND-P000076

$x_1 = x_2$: nothing is calculated. $-y''$ has eigenval. n^2!! Subtract

$$\sum (\lambda_n - n^2) = \mathrm{Sp}\, q(x)\delta(x_1 - x_2) = \delta(0) \int_0^\pi q(x)\, dx.$$

$\to c_0$, so that $\int q(x)$ [crossed out: a sign resembling d and densely overwritten signs] $= 0$.

Uncertain reading. a sign resembling d and densely overwritten signs

Original source details: GELFAND-P000076

$$\sum(\lambda_n - n^2 - c) = 0, \qquad \delta(0) = 0.$$

c — asymptotics. [Separately on the right:] $\int_0^\pi q(x)\,dx$. [On the left, crossed out: “this is a func.” [это ф-я] / a short illegible entry.]

Uncertain reading. “this is a func.” [это ф-я] / a short illegible entry

Original source details: GELFAND-P000076

True if there is a δ-func. everywhere (periodic conds.). At the end, incomplete δ-funcs.; there one obtains $1/4$. G. $\mathrm{Sp}(AB - BA) = 0$. Problem.

Diagram and typed description. Before Gindikin’s name, two short separating strokes with a point between them.

Original source details: GELFAND-P000076

Gindikin. Integration of funcs. of several complex vars. (z, w): a bicyl. $D_z \times D_w$. $\int$ of a func.

$$f(z,w) = \frac{1}{(2\pi i)^2} \iint_\Omega \frac{f(\zeta,\eta)\,d\zeta\,d\eta}{(\zeta - z)(\eta - w)}.$$



Diagram and typed description. A double integral with lower notation Ω and factor $1/(2\pi i)^2$.

Original source details: GELFAND-P000076

[In the numerator before $f(\zeta,\eta)$, crossed out: f with a parenthesis; the arguments and following signs are densely overwritten.]

Uncertain reading. f with a parenthesis; the arguments and following signs are densely overwritten



Original source details: GELFAND-P000076

The next interesting example — a Weil domain (generaliz. bicyl.). There is a set of funcs. $\chi_i(z,w)$, $i=1,\dots,\ell$ — holom. And D_i are specified in the complex plane (1-dim.). A Weil domain: $(z,w)\colon \chi_i(z,w)\in D_i$. 2 funcs., z and w, $z\in D_z$, $w\in D_w$ — a bicylinder!

GELFAND-P000077

Let there be two of them, χ_1,χ_2 — a skew bicylinder. This is simply a bicyl. in other coords.! (χ_1,χ_2 — new vars.). The int. can be written from a change of vars. Formula: Weil.

$$f(z,w)-f(\zeta,\eta)=(z-\zeta)P_1(z,w,\zeta,\eta)+(w-\eta)P_2(\ ).$$

Lem. There is a decomposition. But this is wrong; [crossed out: a short entry beneath dense horizontal strokes; its reading is undetermined]

Uncertain reading. a short entry beneath dense horizontal strokes; its reading is undetermined

Original source details: GELFAND-P000077

— possible in any domain of holomorphy. (Gelfer's theor.) $\forall D$, $(z,w)\in D$, $(\zeta,\eta)\in D$; for a domain of holom. (Cartan's theor. B). Apply to χ_i:

$$\chi_i(z,w)-\chi_i(\zeta,\eta)=(z-\zeta)P_1^i(\ )+(w-\eta)P_2^i(\ ).$$

$$f(z,w)=\frac{1}{(2\pi i)^2}\int_\Omega \frac{(P_1^1P_2^2-P_1^2P_2^1)f(\zeta,\eta)\,d\zeta\,d\eta}{(\chi_1(\zeta,\eta)-\chi_1(z,w))(\chi_2(\zeta,\eta)-\chi_2(z,w))}.$$



Uncertain reading. Below Ω: "skeleton ($\partial=\times$ bdy. of dom.)"; the sign above the beginning of the parenthesis: ∂ / D / an illegible sign.

Original source details: GELFAND-P000077

If there are ℓ funcs., then the formula has the form $\chi_1, \dots, \chi_\ell$:

$$f(z,w) = \frac{1}{(2\pi i)^2} \sum_{i,j} \int_{\Omega_{ij}} \frac{(P_i^1 P_j^2 - P_i^2 P_j^1) f(\zeta,\eta)\, d\zeta\, d\eta}{(\chi_i(\zeta,\eta) - \chi_i(z,w))(\chi_j(\zeta,\eta) - \chi_j(z,w))}.$$



Diagram and typed description. In the numerator: $P_i^1 P_j^2 - P_i^2 P_j^1$; $1, 2$ above, i, j below.

Original source details: GELFAND-P000077



Uncertain reading. The lower index of the right-hand χ in the first denominator factor: i / j / a densely overwritten illegible sign.

Original source details: GELFAND-P000077

Ω_{ij}

$\downarrow$

preimage of the boundary
of the corresp. dom.



Diagram and typed description. A downward arrow from Ω_{ij} to “preimage of the boundary of the corresp. dom.”.

Original source details: GELFAND-P000077

Domain $\chi_i(z,w) \in D_i$.



Diagram and typed description. Two closed rounded contours, the small one inside the large one; without labels or arrows.

Original source details: GELFAND-P000077

Decomp. into a $\sum$ of funcs. analyt. in larger doms.



Uncertain reading. (For non-dom. [“result.” / illegible], it is impossible even to write, whereas $\forall$ dom. [“result.” / illegible] is approx. by Weil doms.).

Original source details: GELFAND-P000077

Gindikin: A contin. analogue of a Weil dom. Dom. $\chi(z, w, \alpha) \in D_\alpha$.

$$\chi(\alpha, z, w) - \chi(\alpha, \zeta, \eta) = (z - \zeta)P_1(\alpha, z, w, \zeta, \eta) + (w - \eta)P_2(\alpha, \ldots).$$

Smooth in α.

GELFAND-P000078

$$f(z, w) = \int \frac{d\alpha}{(2\pi i)^2} \int \frac{P_1(\alpha, \ldots)P_2'(\,) - P_2P_1'}{(\chi(\alpha, \zeta. \, - \chi(\alpha, z, \ldots)} f(\zeta, \eta)\, d\zeta\, d\eta.$$

[Above the numerator:] Wronskian det. (Derivs. in α



Diagram and typed description. Above the numerator,“Wronskian det. (Derivs. in α”; primes at P_2 and the last P_1.

Original source details: GELFAND-P000078



Uncertain reading. In the denominator, one χ difference; opening parentheses before the first χ and its α; after the first ζ, a short sign: point / comma / illegible; on the right, one closing parenthesis after the ellipsis. A small upper sign is undetermined.

Original source details: GELFAND-P000078

Some new conds. on the dom. (general position, etc.).

$$\chi(\alpha, z, w) \in D_\alpha$$

$$\overline{D_\alpha}$$



Original source details: GELFAND-P000078

Uncertain reading. At the upper D, the lower sign is densely overwritten: α / an illegible corrected sign; below D, a nearly horizontal stroke thickened at the right (underline / arrow?); below that a separate D_α.

$\int$ already over the entire boundary.



Original source details: GELFAND-P000078

Diagram and typed description. A wavy underline beneath "$\int$ already over the entire boundary.".

In a partic. case [crossed out: a short entry beneath two dense horizontal strokes, with a lower slanting stroke; its reading is undetermined]

Original source details: GELFAND-P000078

Uncertain reading. a short entry beneath two dense horizontal strokes, with a lower slanting stroke; its reading is undetermined

the formula for the inverse Radon transform. χ_α — linear, then tube doms.

GELFAND-P000079

[The upper part of the sheet is without text.] $26/\overline{\overline{\text{IV}}}$. I. Bernstein.



Original source details: GELFAND-P000079

Diagram and typed description. The date $26/\text{IV}$ with two strokes above IV and one below; the name is underlined separately.

Cohom. with coeffs. in a sheaf in Grothendieck top. All coverings are fixed. In categ. C, $\forall$3objects X, Y, Z, $\exists T = Z \times_X Y$. Categ. of sets.





Diagram and typed description. Z and Y above X; two slanting arrows toward X, f on the left, φ on the right.

Original source details: GELFAND-P000079

T: take $Z \times Y$ and in it those pairs (z, y) such that $f(z) = \varphi(y)$. They form T and there are maps. If f and φ are to a point, this is the ordinary direct prod. If f and φ are embeddings in X, then $Z \times_X Y = Z \cap Y$ in X. [Crossed out: "Pres..." [Предп...] / a short entry beneath dense horizontal strokes; the ending is undetermined.]



Uncertain reading. "Pres..." [Предп...] / a short entry beneath dense horizontal strokes; the ending is undetermined

Original source details: GELFAND-P000079

Open sets — a category. A presheaf S — a contravar. functor from this categ. to the categ. of ab. groups.

$$U \to X$$
$$\Gamma(U)$$

A substantive example — the topology of a point (in fact of a field).



Diagram and typed description. A wavy underline beneath "A substantive example — the topology of a point"; "Ax." and "of a sheaf." are underlined separately.

Original source details: GELFAND-P000079

Ax. of a sheaf. $\{U_\alpha \to U\}$ a covering. There is $\Gamma(U) \to \Gamma(U_\alpha)$; hence there is $\Gamma(U) \to \prod_\alpha \Gamma(U_\alpha)$.

$$0 \to \Gamma(U) \to \prod_\alpha \Gamma(U_\alpha).$$

This is an embedding. U_β — this too is a covering. [Crossed out: U with overwritten lower signs: α / β / illegible; long horizontal strokes converge on the right.]



Uncertain reading. U with overwritten lower signs: α / β / illegible; long horizontal strokes converge on the right

Original source details: GELFAND-P000079

$U_\alpha \times_U U_\beta \to U_\alpha$.

GELFAND-P000080

There is $\Gamma(U_\alpha) \to \Gamma(U_\alpha \times_U U_\beta)$ and into $\prod_\beta \Gamma(U_\alpha \times_U U_\beta)$. [Below the top line, to the left of the product:] $\delta_2\Gamma(U_\alpha)$.



Uncertain reading. The lower digit at δ: 2 / 1; a dense lower stroke.

Original source details: GELFAND-P000080

$$0 \to \Gamma(U) \to \prod_\alpha \Gamma(U_\alpha) \xrightarrow{\delta_1 - \delta_2} \prod_{\alpha,\beta} \Gamma(U_\alpha \times_U U_\beta).$$

$$\prod_\beta \Gamma(U_\beta) \xrightarrow{\delta_2} \prod_{\beta\alpha} (U_\alpha \times_U U_\beta).$$



Uncertain reading. On the right, a parenthesis immediately after $\prod_{\beta\alpha}$, without a visible Γ.

Original source details: GELFAND-P000080

This seq. must be exact at the 2nd factor. (If the sect. over the pieces is 0, it is obtained from the 0th sect. over all of U.) Those agreeing on intersections can be glued.

Continuation of the seq.

$$0 \to \Gamma(U) \to \prod_{\alpha} \Gamma(U_\alpha) \overset{\delta_1}{\underset{\delta_2}{\rightrightarrows}} \prod_{\alpha,\beta} \Gamma(U_\alpha \times U_\beta) \overset{\longrightarrow}{\underset{\longrightarrow}{\rightrightarrows}} \prod_{\alpha,\beta,\gamma} \Gamma(U_\alpha \times U_\beta \times U_\gamma).$$

[On the right:] 3 maps by pairs.





Diagram and typed description. Three parallel rightward arrows between the products and, below, four separate parallel rightward arrows.

Original source details: GELFAND-P000080

$U_\alpha \times U_\beta \times U_\gamma \to U_\beta \times U_\gamma$. Assoc. from uniqueness of the prod.

$$\prod_{\beta,\gamma} \Gamma(U_\beta \times U_\gamma) \to \prod_{\alpha} \Gamma(U_\alpha \times U_\beta \times U_\gamma).$$

Next 4 maps.

$$0 \to \Gamma(U) \to \prod \Gamma(U_\alpha) \overset{\delta_0-\delta_1}{\longrightarrow} \prod_{\alpha,\beta} \Gamma(U_\alpha \times U_\beta) \overset{\delta_0-\delta_1+\delta_2}{\longrightarrow} \prod \cdots \overset{\delta_0-\delta_1+\delta_2-\delta_3}{\longrightarrow} .$$



Original source details: GELFAND-P000080

Diagram and typed description. Upper arrow labels: $\delta_0 - \delta_1$, $\delta_0 - \delta_1 + \delta_2$, $\delta_0 - \delta_1 + \delta_2 - \delta_3$; after the last product, an ellipsis.

This is for an arbitrary presheaf. The compos. of 2 adjacent maps $= 0$. (Easy to check.) [On the right:] ker / Im.

Proof
in cat.



Uncertain reading. On the left, “Proof in cat.” / “Proof in id.”; the last letters are undetermined, with an angular stroke to the right and below.

Original source details: GELFAND-P000080

$$\varepsilon \longrightarrow \prod_{\alpha} \varepsilon_\alpha(U_\alpha) \longrightarrow \prod_{\alpha}\prod_{\beta} \varepsilon_{\alpha\beta}$$

sect.

$$\prod_{\gamma}\prod_{\alpha} \varepsilon_{\gamma\alpha}$$



Uncertain reading. In the lower term $\prod_\gamma \prod_\alpha \varepsilon_{\gamma\alpha}$: the order and last letter of the indices are uncertain ($\gamma\alpha$ / $\gamma\delta$); a slanting arrow downward to the right. Below the first ε, “sect.”.

Original source details: GELFAND-P000080

[In the right margin:]

$$U_{\alpha\beta} \to U,$$
$$\Gamma(U) \to \Gamma(U_{\alpha\beta}),$$
$$\varepsilon \to \varepsilon_{\alpha\beta}.$$

Def. the same. ker / Im. Čech cohom. covering.

GELFAND-P000081

$$0 \longrightarrow \prod(U_\alpha) \overset{\delta_0-\delta_1}{\longrightarrow} \prod_{\alpha\beta} \Gamma(U_\alpha \times_U U_\beta) \longrightarrow$$



Uncertain reading. Before (U_α), $\prod$ is visible; a separate Γ is not established.

Original source details: GELFAND-P000081

In this seq. sect.

Uncertain reading. The last abbreviation: “сеч.” / “cer.” (“sect.” / “seg.”); upper joined strokes.

Original source details: GELFAND-P000081

$$H_0(S) = \Gamma(U)$$

Čech cohom. of the whole space. Embedded $\{U_\gamma \to U\}$ in $\{U_\alpha \to U\}$, if $\forall\gamma$ a map is given.





Original source details: GELFAND-P000081

Diagram and typed description. Above, $U_\gamma \to U_\alpha$; both slanting arrows point to the lower U.

Obtain a map of the chain / of chains (“цепочки” / “цепочек”), commut. with $\underset{\text{(functor!)}}{\delta}$ and therefore a map of cohomology.

Uncertain reading. of the chain / of chains (“цепочки” / “цепочек”)

Original source details: GELFAND-P000081

Original source details: GELFAND-P000081

Diagram and typed description. Below δ, “(functor!)” is inserted.

This map does not depend on the manner of embedding. (Easy to understand.) Ind. limit $\hat{H}(U, P)$. [On the right:] $\underline{P}$ — a sheaf.



Original source details: GELFAND-P000081

Diagram and typed description. The separately written P on the right is underlined; the letter in $\hat{H}(U, P)$ has no underline.

For an exact seq. of sheaves there must be an exact seq. of cohom.

$$0 \to H^0(x, \Phi) \to H^0(a, Q) \to H^0(\dots, R) \to H^1(\dots, \Phi)$$



Original source details: GELFAND-P000081

Uncertain reading. The first argument x / X; the next resembles a; the sheaf letter Φ / P. The upper digit of the last H: 1, with dense overlaid strokes.

For coverings they exist, but on passing to [crossed out before “limit”: illegible]
the limit, exactness is not preserved.



Original source details: GELFAND-P000081

Uncertain reading. illegible

1. Paracomp. spaces in top. it is done. New def. (ax.) now only for sheaves. Exact seq. of presheaves

$$0 \to P \to Q \to R \to 0$$

[Before “If”, a mark is crossed out: illegible.]

Original source details: GELFAND-P000081

Uncertain reading. illegible

If $\forall U$

$$\begin{array}{ccccccccc} 0 & \to & P(U) & \to & Q(U) & \to & R(U) & \to & 0 \\ & & \downarrow & & \downarrow & & \downarrow & & \\ 0 & \to & P(V) & \to & Q(V) & \to & R(V) & \to & 0 \end{array}$$

exact seq. (sections).
($\forall$ sect. given maps and commut. diagr. $V \to U$



Original source details: GELFAND-P000081

Uncertain reading. Two rows with $P(U), Q(U), R(U)$ and $P(V), Q(V), R(V)$; three downward arrows cross the intervening handwritten annotation. The abbreviation before “given”: “сеч.” / “сек.” (“sect.”).

($\forall$ open set U given maps and gluing.)



Original source details: GELFAND-P000081

Undeciphered passage. After “gluing.”, one closing parenthesis is visible; the parenthesis of the preceding annotation is not closed separately.

Exact seq. of sheaves.



Original source details: GELFAND-P000081

Diagram and typed description. Wavy underlines at “Čech cohom. of the whole space.”, “Exact seq. of presheaves” and “Exact seq. of sheaves.”; a straight line at “New def. (ax.) now only for sheaves.”.

S — an ab. category.



Diagram and typed description. Before “ab. category”, the letter S with upper and lower terminal strokes.

Original source details: GELFAND-P000081

Sheaves — an ab. cat. as a subcat. of presheaves. Ker and Coker are defined. Ax.: isom. of the image and coimage.

GELFAND-P000082

$$0 \to F' \to F \to F'' \to 0$$

Exact seq. (as sheaves).

$$0 \to F'_p \to F_p \to F''_p \to [\text{crossed out: } 0]$$

[Below F'_p: presheaves.]



Uncertain reading. Lower indices p / ρ; the last 0 is heavily crossed out.

Original source details: GELFAND-P000082

Not necess. 0(!) — the categ. is wider!. In another category.

$$0 \to iF' \to iF \to iF'' \longrightarrow$$

The def. of cohomology is based on this being [crossed out: illegible]

a nonexact seq.

Uncertain reading. illegible

Original source details: GELFAND-P000082

(In the difference between sheaves and presheaves — the whole theor. of cohom.) C^1 — the Riem. sph. and 2 points.



Uncertain reading. C^1 / P^1; the initial sign is C-like.

Original source details: GELFAND-P000082

Exact seq. of kogf. — exact seq. of sheaves.

Original source details: GELFAND-P000082

Uncertain reading. “когф.” / “коэф.” / “когр.” (kogf. / koef., coeff. / kogr.); the middle letter has dense strokes.

Sheaf of germs [an arrow is crossed out: arrow / illegible]
of hol. fns. $= 0$ at the 2 points. $\mathcal{J}$.

Original source details: GELFAND-P000082

Uncertain reading. arrow / illegible

$$0 \to \mathcal{J} \to O \to O/\mathcal{J} \to 0$$

Sect. $\underset{\frown}{0}$, $\underset{\frown}{1}$ in $O/\mathcal{J}$ are not obtained.



Original source details: GELFAND-P000082

Uncertain reading. Before $0, 1$, the abbreviation “сек.” / “сеч.” (“sect.”); both numbers are underlined with arcs.

2 stalks. (Sect. is not an epimorphism.) Locally this map is onto. Sometimes the 0th sheaf is constr. from a presh. Criterion of exactness in sheaves — if locally exact.



Original source details: GELFAND-P000082

Diagram and typed description. At “wider!”, a double straight line; below 0 and 1, arcs; at “Criterion of exactness in sheaves”, a wavy line.

Morphism ...

$$\text{exact seq. of sheaves} \iff \text{exact seq. of “stalks”}.$$

Morphism of presh. $\longrightarrow$ a fam. of morph. of ab. gr. ___"___ of sheaves $\longrightarrow$ maps of each section.



Original source details: GELFAND-P000082

Diagram and typed description. At the start of the second line, a repetition sign: two short vertical strokes between horizontal strokes.

The addit. cat. of presheaves and sheaves are abelian. If there is an exact seq. of sheaves, then the seq. is exact locally. (Also in top. spaces.) (Here stalks cannot be def. in principle.) Presh. exact on fine coverings. Presh. compared on all sets, and sheaves on fine ones.

$$0 \to \underset{\text{const.}}{C} \to \underset{\text{fns.}}{\Omega^0} \to [\text{a sign is crossed out}]\Omega \to 0$$



Original source details: GELFAND-P000082

Uncertain reading. The sign before Ω is heavily crossed out; illegible.



Original source details: GELFAND-P000082

Diagram and typed description. Below C, “const.”; below Ω^0, “fns.”.

Pass to [crossed out: sheaves / illegible] presheaves.



Original source details: GELFAND-P000082

Uncertain reading. sheaves / illegible

$$0 \to C \to f$$

(diff. forms!)



Original source details: GELFAND-P000082

Uncertain reading. On the right, the annotation “(diff. forms!)” / “(diff. forms)”; a dot near the lower end of the parenthesis. Below, separately, “functor i”.

Original source details: GELFAND-P000082

Uncertain reading. f / $\mathcal{F}$.

[A short fragment is crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000082

Cohom. $\longrightarrow$ derived functor i.

GELFAND-P000083

$$0 \to F' \to F \to F'' \to 0$$

Req. that there be an exact seq. [On the right:] H — presheaves. 1.

$$0 \to iF' \to iF \to iF'' \to H^1(F') \to H^1(F) \\ \to H^1(F'') \to H^2(F') \longrightarrow \dots$$

(Ax. of derived functors.)



Diagram and typed description. After iF'', the terms $H^1(F')$, $H^1(F)$, $H^1(F'')$, $H^2(F')$; then an arrow and an ellipsis.

Original source details: GELFAND-P000083

$$i : S \longrightarrow \underline{P}$$



Diagram and typed description. In $i : S \longrightarrow P$, a straight line below the final P.

Original source details: GELFAND-P000083

[Crossed out: illegible]
a functor (left exact).

Uncertain reading. illegible

Original source details: GELFAND-P000083

[On the right:]

$$0 \to A \to B \to 0$$
$$\Downarrow$$
$$0 \to iA \to iB \to iC$$



Original source details: GELFAND-P000083

Uncertain reading. In the upper row, 0 is visible after B; in the lower row the last term is iC, without a corresponding C above.

Derived functor

$$R^q i : S \to P, \quad \text{but}$$
$$R^0 i = i$$



Original source details: GELFAND-P000083

Uncertain reading. The upper index in $R^q i$: q / ν, with an upper loop and a slanting lower stroke; in the next row, $R^0 i = i$.

1:

$$0 \to R^0(A) \longrightarrow \dots$$

Exact seq. 2. For inject. objects S

$$R^q(S) = 0, \qquad q > 0.$$

[A row is crossed out: “For inject.” / illegible.]



Original source details: GELFAND-P000083

Uncertain reading. “For inject.” / illegible

Prov., that they exist if in S' there are enough inject. objects (an embedding into an inj. obj. exists for any).



Original source details: GELFAND-P000083

Diagram and typed description. At the start of the row, the abbreviation “Доказ.” (“Prov.”); a comma after the full stop.



Original source details: GELFAND-P000083

Diagram and typed description. In the words “if in S' there are enough”, a separate upper stroke after S.

See Grothendieck, “Lectures on hom. algebra”. Val.: on the whole space, of the derived functor, is called cohom. of the whole space. Next time. ~~Berezin~~

Original source details: GELFAND-P000083

Diagram and typed description. “Next time.” is underlined with a straight line; the following “Berezin” is crossed out.

“Another form. of Plancherel for diff. oper.” Berezin and Sinai “Ukoren. Dobrushin” / “Igor. Dobrushin” (“Укорен. Добрушин” / “Игорь. Добрушин”), possibly, Halmos.



Original source details: GELFAND-P000083

Uncertain reading. “Ukoren. Dobrushin” / “Igor. Dobrushin” (“Укорен. Добрушин” / “Игорь. Добрушин”)

GELFAND-P000084

$10/\overline{\text{V}}$. Halmos. Inv. subsp. of a cont. oper. in Hilb. sp. (compl.)



Original source details: GELFAND-P000084

Diagram and typed description. The V in the date has an upper and a lower bar; “Halmos.” and the heading are underlined.

$$A : H \to H$$

Inv. sp. — closed and inv. M. $\exists M$ — ? ($M \neq 0, H$) The gen. probl. is not solved, [crossed out: illegible]

Uncertain reading. illegible



Original source details: GELFAND-P000084

(known if A is Herm. or norm.). Several class. — for completely cont. (von Neumann, ...). [In the margin: counterex.] In finite / In compact (“В конечн.” / “В компактн.”) cond. reduce to known res.



Original source details: GELFAND-P000084

Uncertain reading. In finite / In compact (“В конечн.” / “В компактн.”)

Aronshain [?] and Smith.



Original source details: GELFAND-P000084

Uncertain reading. Aronshain (“Ароншайн”); interior strokes of the name are uncertain.

If A is subnormal (∃ an extension of H, crossed out: illegible; and on it an ext. $\tilde{A}$ is norm.), — also not solved.



Original source details: GELFAND-P000084

Uncertain reading. illegible



Original source details: GELFAND-P000084

Diagram and typed description. The definition is enclosed in round parentheses; a wavy stroke above A in “ext. $\tilde{A}$”.

(In a finite-dim. sp., subnormal $\longrightarrow$ normal.) In infinite dim. — the shift

$$e_1 \to e_2,\ e_2 \to e_3, \dots$$

If add / prove (“доп.” / “док.”) e_{-n}, then it will be normal.



Original source details: GELFAND-P000084

Uncertain reading. add / prove (“доп.” / “док.”)

Internal conditions of subnorm.

$$A^*A \longrightarrow AA^* \geq 0$$

Original source details: GELFAND-P000084

Uncertain reading. Between A^*A and AA^*: $\longrightarrow$ / $-$; the right end of the stroke is pointed.



Original source details: GELFAND-P000084

Uncertain reading. (necess. and suff.); the words have overwritten strokes.

(The adj. of a subnorm. need not be subnorm.) See Halmos, Bram. Generalizations. A^2 completely cont. — positive ans. (∃ an inv. subsp.) A. Robinson, Bernstein in terms of pred. calc. / inn. pred. / inf. pred. (“исч. предик.” / “инн. предик.” / “инф. предик.”)

Uncertain reading. pred. calc. / inn. pred. / inf. pred. (“исч. предик.” / “инн. предик.” / “инф. предик.”)



Original source details: GELFAND-P000084

Proof of the schem. method.



Diagram and typed description. Wavy lines below “A^2 completely cont.” and “Proof of the schem. method.”

Original source details: GELFAND-P000084

p [A sign is crossed out: ∀ / illegible]

a polynomial $p \neq 0$, $p(A)$ completely cont. Then ∃ an inv. subsp.



Uncertain reading. ∀ / illegible

Original source details: GELFAND-P000084

$e \in H$, $\|e\| = 1$.

Rasst. $\{e, Ae, A^2e, \ldots\} = H$

Uncertain reading. The abbreviation before the brace: “Расст.” / “Рассм.” (“Rasst.” / “Rassm.”); the final joined strokes are uncertain.

Original source details: GELFAND-P000084

(Otherwise there is a subsp.) ∴ therefore.



Diagram and typed description. Three dots in a triangle and the word “therefore” are enclosed in a box.

Original source details: GELFAND-P000084

$e, Ae, \ldots$ may be considered lin. indep. Otherwise there is a finite-dim. subsp. (then the 1st to the generated / the 1st to each (“1-е к порожд.” / “1-е к каждой”) inv. subsp.)



Uncertain reading. the 1st to the generated / the 1st to each (“1-е к порожд.” / “1-е к каждой”)

Original source details: GELFAND-P000084

Orthogonalize

$$\{e, Ae, \ldots, A^{n-1}e\} = \{e_1, e_2, \ldots, e_n\}$$



Diagram and typed description. The last exponent is $n-1$; on the right, the indices 1, 2, n.

Original source details: GELFAND-P000084

$e_1, e_2, \ldots$ — $\perp$, $\| \| = 1$. The matrix has the form

$$a_{mn} = (Ae_n, e_m)$$

$$\begin{pmatrix} * & * & * \\ * & * & * \\ 0 & * & * \\ 0 & 0 & * \end{pmatrix}$$
$$0 \quad 0 \quad 0$$



Diagram and typed description. The three lower zeros continue below the ends of the round parentheses; above, $a_{mn} = (Ae_n, e_m)$.

Original source details: GELFAND-P000084

GELFAND-P000085

If 1 beyond the diag., then 0. Image of e:

$$Ae = \lambda_1 e_1 + \lambda_2 e_2$$

and so on.



Diagram and typed description. In “Image of e” and Ae, no lower index; on the right, $\lambda_1 e_1 + \lambda_2 e_2$.

Original source details: GELFAND-P000085

A^k has the matrix $a^{(k)}_{mn}$ (add k diagonals below). (Farther than k units from the main diag., 0.) On the kth diag.

$$a^{(k)}_{n+k,n} = \prod_{j=1}^{k} a_{n+j,n+j-1}$$

Matrix $p(A)$, deg k.

$$a^{(p)}_{mn} = (p(A)e_m, e_n)$$



Uncertain reading. For $p(A)$, the notation $(p(A)e_m, e_n)$; on P000084 it was (Ae_n, e_m).

Original source details: GELFAND-P000085

Below the kth diag. — 0. On the kth diag. — the same as for the kth power of A (up to a factor). e_n converges weakly to 0, therefore $p(A)e_n$ converges strongly to 0.



Diagram and typed description. First "converges weakly to 0", then "converges strongly to 0".

Original source details: GELFAND-P000085

$$\prod_{j=1}^{k} d_{n+j,n+j-1} \longrightarrow 0, \qquad n \to \infty.$$



Diagram and typed description. In the first product, the letter a; in the product with an arrow to 0, the letter d. In both, the limits $j = 1, k$ and the indices $n + j$, $n + j - 1$.

Original source details: GELFAND-P000085

Product of numbers below the diagonal. Change both indices.

$$d^{(p)}_{m,n} = (p(A)e_m, e_n)$$

Uncertain reading. The upper sign on d: (p) / (1); a short joined stroke inside the parentheses.

Original source details: GELFAND-P000085

Choose a subseq. of elem. from / elem. (“от.” / “эл.”) below the diag. $\to 0$.



Original source details: GELFAND-P000085

Uncertain reading. from / elem. (“от.” / “эл.”)

Take the smallest of the k elem., it $\to 0$.

$$a_{k(n)+1,k(n)} \longrightarrow 0$$



Original source details: GELFAND-P000085

Diagram and typed description. In the row with an arrow to 0: $a_{k(n)+1,k(n)}$.

Consider. [A symbol is crossed out: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000085

$$H_n = \{e_1, \dots, k(m)\}$$



Original source details: GELFAND-P000085

Uncertain reading. The last term $k(m)$ / $k(n)$, without a confidently visible e before it; the lower index on H: n / m.

P_m — a projector. $P_m \to 1$ in the strong oper. top. $\underline{P_n A P_n}$ — the projection of A onto H_n.



Original source details: GELFAND-P000085

Uncertain reading. First the index m, then n in $P_n A P_n$ and H_n.

It is reduced to Δ form.

$$\{0\} = H_n^{(0)} \subset H_n^{(1)} \subset H_n^{(2)} \subset \dots \subset H_n^{k(n)}.$$

In it, an increasing seq. of subsp., inv. with respect to $P_n A P_n$. They are $\approx$ inv. with respect to A.



Original source details: GELFAND-P000085

Diagram and typed description. The sign Δ before “form”; in the chain, the upper (0), (1), (2) and $k(n)$; in the last row, $\approx$.

GELFAND-P000086

Idea — choose a seq., allowing passage to the limit. Another idea

$$f_n \cong g_n \quad \underset{\text{def}}{\iff} \quad \|f_n - g_n\| \to 0$$



Original source details: GELFAND-P000086

Diagram and typed description. A straight underline below “Idea”, a wavy underline below “Another idea”; def below the two-way arrow.

If f_n is bounded $\Rightarrow$

$$AP_nf_n \cong P_nAP_nf_n.$$

Original source details: GELFAND-P000086

Diagram and typed description. On the left AP_nf_n, on the right $P_nAP_nf_n$.

The calc. is based on the fact that the coeff. of the unknown / off-diag. (“неиз.” / “недиаг.”) matrix elem. $\to 0$.



Original source details: GELFAND-P000086

Uncertain reading. unknown / off-diag. (“неиз.” / “недиаг.”)

(A appl. — goes 1 outside H_n and $\to 0$.) [Added below the end: coeff.]



Original source details: GELFAND-P000086

Diagram and typed description. In parentheses “A appl. — goes 1 outside H_n and $\to 0$”; below the end, the addition “coeff.”.

By ind., the same for $\forall$ powers of A:

$$A^kP_nf_n \cong (P_nAP_n)^kP_nf_n.$$



Original source details: GELFAND-P000086

Uncertain reading. Inside the parentheses the third P_n is overwritten; the exponent k has dense strokes.

But for $k = 0$ this is false.

$$\|P_nf_n - f_n\| \to 0.$$



Original source details: GELFAND-P000086

Diagram and typed description. In the row "But for $k = 0$ this is false", a visible 0; below, $\|P_n f_n - f_n\| \to 0$.

But if this req. is imposed on f_n, then this will be true for all powers (and for polyn.). 1) $\{f_n\}$ bounded,

$\Rightarrow$

$$p(A)P_n f_n \cong p(P_n A P_n) f_n.$$



Original source details: GELFAND-P000086

Uncertain reading. $P_n f_n \cong f_n$ / $P_n f_n \neq f_n$

Spec. particular case

$$f_n = P_n e \cong e$$
$$p(P_n A P_n)e \cong p(A)e \neq 0.$$



Original source details: GELFAND-P000086

Diagram and typed description. An e follows both $p(P_n A P_n)$ and $p(A)$; at the end $\neq 0$.



Original source details: GELFAND-P000086

Uncertain reading. The second relation in $f_n = P_n e \cong e$: $\cong$ / $\neq$, with a crossing diagonal stroke.

[On the right: powers of A are independent.]



Original source details: GELFAND-P000086

Uncertain reading. Overwritten strokes near "powers of A"; the lower layer is illegible.

Hence

$$\lim \|p(P_n A P_n)\| = d > 0.$$



Original source details: GELFAND-P000086

Uncertain reading. After the closing parenthesis inside the norm, no confidently visible e; in the following parentheses, a single wavy sign $\sim$.

($\sim$ means, the lim exists and is such.)

$$\|p(P_n A P_n)e \longrightarrow p(P_n A P_n)P_n^{(i)} e\|$$

$i = 0, 1, \ldots, k(n)$.



Original source details: GELFAND-P000086

Uncertain reading. Between the terms inside the norm, a visible arrow rather than an ordinary minus sign.

In Π_n, triang. basis, $P_n^{(i)}$ — projection onto the first i vectors.



Uncertain reading. Π_n / H_n.

Original source details: GELFAND-P000086

$i = 0, 1, \ldots, k(n)$. $i = 0 \Rightarrow$ obtain the zero subsp. $i = k(n) \equiv 0$.



Diagram and typed description. The first row $i = 0 \Rightarrow$ "obtain the zero subsp."; the next $i = k(n) \equiv 0$.

Original source details: GELFAND-P000086

$$\exists n: \quad \|p(P_nAP_n)e\| > \frac{3}{4}d.$$

Diagram and typed description. Before the norm $\exists n$:; inside it a final e; after the norm $> \frac{3}{4}d$.

Original source details: GELFAND-P000086

$i(n)$:

$$\frac{d}{2} \leq \|p(P_nAP_n)e \longrightarrow p(P_nAP_n)P_n^{(i)}\|$$

and $< \frac{d}{2}$ for $\underline{i-1}$.



Uncertain reading. The parameter d / α; in this last norm after $P_n^{(i)}$, no confidently visible e.

Original source details: GELFAND-P000086

GELFAND-P000087

[Crossed out: As i incr., the diff. decreases.]



Uncertain reading. Abbreviations under two lines: "возрастан." / "возрастан", "разност." / "разность" ("incr.", "diff." / "difference").

Original source details: GELFAND-P000087

$> \frac{3}{4}d$ and for max i it is 0.



Uncertain reading. The parameter in the upper row: d / α.

Original source details: GELFAND-P000087

$$\{P_n^{(i(n)-1)}\}, \qquad \{P_n^{(i(n)}\}$$



Uncertain reading. In the first exponent $(i(n) - 1)$; in the second a visible opening parenthesis before $i(n)$, without a separate second closing parenthesis.

Original source details: GELFAND-P000087

— bounded seq. of projectors. Choose a weakly conv. subseq.

$$\{P_{n_j}^{i(n_j)-1}\} \searrow Q^- \qquad \searrow Q^+$$

$$Q_j^- \qquad\qquad Q_j^+$$



Original source details: GELFAND-P000087

Diagram and typed description. On the left $\{P_{n_j}^{i(n_j)-1}\}$, an inclined arrow to Q^-; below the left part Q_j^-. On the right an inclined arrow to Q^+, below it Q_j^+. The upper starting point of the right arrow has no separate label.

$$m^- = \{f : Q_j^- f \to f\}$$
$$m^+ = \{f : Q_j^+ f \overset{\text{(strongly)}}{\longrightarrow} f\}.$$



Original source details: GELFAND-P000087

Uncertain reading. The minus above the first Q_j is overwritten; m / M in the left-hand notation.

[On the right: where they give the identity operator.] (On M^- them Q^- is 1.)

Original source details: GELFAND-P000087

Uncertain reading. M^- is inserted before "them"; the original phrase is not amended.

Constr. of inv. subsp. m^- and m^+ — closed subsp. (from the fact that Q_j^- and Q_j^+ are bounded seq.). Both are inv. with respect to the oper. A, which is obtained by passage to the limit (from the long paragraph, uncomplicated from ①) and using comp. $p(A)$.



Original source details: GELFAND-P000087

Diagram and typed description. Here lower-case m^-, m^+; the reference has a circled 1; at the end $p(A)$.

$$e \notin M^- \qquad (\text{so that } M^- \neq H).$$



Original source details: GELFAND-P000087

Diagram and typed description. Capital M^- in both places; before it $e \notin$, in parentheses $M^- \neq H$.

$M^+ \neq \{0\}$ — this is already less simple.

$$\{Q_j^+ e\} \quad \text{converges weakly.}$$

$$p(A)Q_j^+ e \longrightarrow \underset{\text{def}}{f}$$

Strongly conv. (compactness used once more).



Original source details: GELFAND-P000087

Diagram and typed description. Below f the label def; before it an arrow, on the left $p(A)Q_j^+ e$.

$$f \neq 0, \qquad f \in M^+.$$



Diagram and typed description. The sequence has $Q_j^+ e$ with a $+$; below, $f \neq 0$, $f \in M^+$.

Original source details: GELFAND-P000087

If also $M^+ \neq H$, then we obtain an inv. subsp. But here, if $M^+ = H$, then $M^- / N^- \neq \{0\}$.



Uncertain reading. M^- / N^-

Original source details: GELFAND-P000087

The proof is not difficult and is intuitively clear. If $Q^+ \to E$, then the seq. of oper. of rank 1 less [A short fragment is crossed out: illegible.]

not would / cl. (“бы” / “бл.”) to E (lim comp. comp.).

Uncertain reading. illegible

Original source details: GELFAND-P000087



Uncertain reading. would / cl. (“бы” / “бл.”)

Original source details: GELFAND-P000087

GELFAND-P000088

Unsolved problems. (and solved ones)



Diagram and typed description. “Unsolved problems.” is underlined; the parentheses are outside the underline. Below, “Conjecture.” is separately underlined.

Original source details: GELFAND-P000088

p — entire fn., $p(A)$ — comp., then triv. $\exists M$ (use for polynomials). de Branges — Rovnyak announced $\forall$ cont. oper., but with an error in the proof. From their reasoning follows:

$$\|A\| < 1, \quad 1 - A^*A \text{ comp.} \quad \Rightarrow \quad \exists \text{ inv. subsp.}$$



Diagram and typed description. The first sign is $<$; then $1 - A^*A$ and a double arrow to $\exists$.

Original source details: GELFAND-P000088

Res. of Sakhnovich, Livshits and brodsky. $A + iB$, A — self-adj., B in some sense small (nuclear, etc.).



Original source details: GELFAND-P000088

Diagram and typed description. At the start $A + iB$; “nuclear, etc.” continues on the second line.

Nagy — Foias / Foas

Original source details: GELFAND-P000088

Uncertain reading. Foias / Foas

$$\|A\| \leq 1, \qquad \begin{matrix} A^n \not\longrightarrow 0 \\ A^{*n} \not\longrightarrow 0 \end{matrix} \quad \text{(strongly)},$$

$\Rightarrow \exists$ inv. subsp.



Original source details: GELFAND-P000088

Uncertain reading. Both arrows are crossed by an inclined stroke.

Triv. structure $\{0, 1\}$.



Original source details: GELFAND-P000088

Diagram and typed description. Two elements $\{0, 1\}$; then the question about an operator in Hilb. sp. and “Not solved.”

$\exists$ an oper. in Hilb. sp. with such a struct. of inv. subsp.? Not solved. Another probl. Struct. $\{0, 1, 2, \ldots, \infty\}$. Does an oper. with such a struct. exist? Affirm. answer Donoghue (1957).



Original source details: GELFAND-P000088

Diagram and typed description. Written $\{0, 1, 2, \ldots, \infty\}$; the date in parentheses (1957).

$$\begin{pmatrix} 0 & \frac{1}{2} & & & \\ & 0 & \frac{1}{4} & & \\ & & \cdot & \frac{1}{8}\,[?] & \\ 0 & & & \cdot & \\ & & & & \cdot \end{pmatrix}$$



Diagram and typed description. Within round parentheses two small 0s, $1/2$, $1/4$; the third densely overwritten coefficient $1/8$ / $1/6$; a large 0 below and separate dots down to the right.

Original source details: GELFAND-P000088

Exact cond. on the numbers above the diag. are unknown (so that precisely these occur). $\exists$ an oper. with the struct. of all integers $\to$ unknown.



Diagram and typed description. “all integers”; then an arrow and “unknown”.

Original source details: GELFAND-P000088

$$[0,1] \longmapsto$$

— such a structure $\exists$ operator.



Diagram and typed description. On the left the label $[0,1]$, then a segment with two end strokes. Below $(Vf)(x) = \int_0^x f(y)\,dy$.

Original source details: GELFAND-P000088

$$(Vf)(x) = \int_0^x f(y)\,dy$$

(answ. in the 1950s). Conjecture. A measure on the line μ.

$$-\infty \qquad\qquad +\infty$$



Diagram and typed description. Below the line $-\infty$ on the left, $+\infty$ on the right.

Original source details: GELFAND-P000088

$$\mu(x) = 1, \qquad L^2(\mu).$$

[Above the first argument: (x).]



Uncertain reading. Visible $\mu(x) = 1$ and another (x) above; μ / M. Below the first letter a separate short mark: 2 / illegible sign.

Original source details: GELFAND-P000088

$$(Af)(x) = \int_0^x f(y)\, d\mu(y).$$



Uncertain reading. The lower limit is visible as 0.

Original source details: GELFAND-P000088

Possibly, the struct. of inv. subsp. is isomorphic to supp μ.



Uncertain reading. In $L^2(\mu)$ and after supp the letter μ / M.

Original source details: GELFAND-P000088

GELFAND-P000089

Possible counterexample. X — sp. with measure μ. T — transf., preserving measure (in Russian a dyn. system). φ — bounded fn. [Crossed out before the formula: Oper. / illegible.]

Uncertain reading. Oper. / illegible

Original source details: GELFAND-P000089

[Above the formula: in L^2.]

$$(Af)(x) = \varphi(x) f(Tx).$$



Diagram and typed description. Above X, T, φ; above the formula "in L^2"; on the right $f(Tx)$.

Original source details: GELFAND-P000089

∃ examples of transf. with simple cont. spectrum.



$$Tx = x + \alpha \pmod 1, \qquad \alpha \text{ — irr.}$$
$$\varphi(x) = x.$$



Original source details: GELFAND-P000089

Diagram and typed description. A segment with two end strokes, labels 0, 1 below. On the right $Tx = x + \alpha \pmod 1$, "α — irr.", then $\varphi(x) = x$.

Study in detail
this operator



Original source details: GELFAND-P000089

Diagram and typed description. In the right margin two vertical strokes; a wavy line below "this operator".

Conjecture: [Crossed out: on one… / on a giv… ("на один…" / "на дан…") / illegible.] no inv. subsp. (∀ vector cyclic).



Original source details: GELFAND-P000089

Uncertain reading. on one… / on a giv… ("на один…" / "на дан…") / illegible

In fact, not a single cyclic vector is known.



Original source details: GELFAND-P000089

Diagram and typed description. In parentheses ∀ vector cyclic; below "not a single cyclic vector is known".

∃ an example of an oper. A in $L^2(0,1)$ (Ornstein), close to an oper. without inv. subsp. ∀ vector $\in L^{2+\varepsilon}$ cyclic (!).



Original source details: GELFAND-P000089

Diagram and typed description. In the first line $L^2(0,1)$ and the name Ornstein; below ∀, $\in L^{2+\varepsilon}$ and (!).

(A transf. for which Lebesgue measure is quasi-inv. — measure 0 to measure 0 — but an inv. measure does not exist.)



Original source details: GELFAND-P000089

Diagram and typed description. "measure 0 to measure 0"; after the line break "but an inv. measure does not exist".

— • —

Gelfand's question: why are inv. subsp. needed, and what can replace them?



Original source details: GELFAND-P000089

Diagram and typed description. "Gelfand's question" is underlined; before and after the question, separators with a dot between two lines.

— • —

Another professor, speaking English (beginning with F) (a Hungarian from Romania), something like Foytsh / Foyshi (“Фойтш” / “Фойши”)



Uncertain reading. Foytsh / Foyshi (“Фойтш” / “Фойши”)

Original source details: GELFAND-P000089

[A repeated entry is densely overwritten: oyshi / Foyshi (“ойши” / “Фойши”) / illegible.]

Uncertain reading. oyshi / Foyshi (“ойши” / “Фойши”) / illegible

Original source details: GELFAND-P000089

$$E, \qquad |\lambda| < 1, \qquad \textcircled{H}(\lambda) : E \longrightarrow E_*,$$
$$\|H(\lambda)\| \leq 1.$$



Diagram and typed description. Separately E; $|\lambda| < 1$; the first letter H is circled, the right E has a lower star; below $\|H(\lambda)\| \leq 1$.

Original source details: GELFAND-P000089

[The letter H in the first entry is circled.] Analyt. in the strong oper. top. (analyt. contraction).

$$\{E, E_*, \textcircled{H}\}$$

[The last letter in the triple is circled.]



Uncertain reading. The circled sign in the triple: H / Θ / illegible; above, the circled H has two clear upright strokes.

Original source details: GELFAND-P000089

Sp. of fns. with values in the initial Hilb. sp. E. $L^2(E)$ — L^2 on the circ. 2π.



Original source details: GELFAND-P000089

Diagram and typed description. In the upper line Hilb. sp. E; then $L^2(E)$, 2π and $H^2(E)$; the exponent has $+int$.

$$H^2(E) \qquad \int_0 u(t)e^{int}\,dt = 0, \qquad n = 1, 2, 3, \ldots$$



Original source details: GELFAND-P000089

Uncertain reading. The integral clearly has a lower 0; no separate upper limit is visible.

(boundary values of analyt. fns.). Not everything has been done in the non-finite-dimensional case. Inv. aff. transf. $A : H_1 \longrightarrow H_2$,



Original source details: GELFAND-P000089

Uncertain reading. The abbreviation aff. / diff. (“афф.” / “дифф.”); below $H \to H$ and “Jordan form”.

H_1, H_2 — finite-dimensional. ($H \to H$ — Jordan form.) Various analogues of Jordan blocks.

$$\int_0^x f(x)\,dx.$$

Original source details: GELFAND-P000089

Diagram and typed description. Upper limit x, lower 0; the integrand and the differential also have x.

GELFAND-P000090

$20/\overline{\text{IX}}$. Kohn. $\bar\partial$ — Neumann probl.

M



Original source details: GELFAND-P000090

Diagram and typed description. Date $20/\text{IX}$: strokes above and below IX; Kohn underlined; on the left M in an oval.

$M \subset C^n$ bounded dom.

Original source details: GELFAND-P000090

Uncertain reading. The exponent above C is dense: n / m.

$$u_{\bar z_j} = \frac{1}{2}(u_{x_j} + iu_{y_j}) = \alpha_j.$$



Diagram and typed description. In the first definition a bar above z_j; on the right $\frac{1}{2}$, the sign $+$ and i, then α_j.

Original source details: GELFAND-P000090

Given α_j, when does $\exists u$ and how does it depend on α. Connection with class. theorems.

$$\bar\partial u = \alpha,$$
$$\sum u_{z_j}\, d\bar z_j = \sum \alpha_j\, d\bar z_j$$
under cond. $\alpha_{j\bar z_k} = \alpha_{k\bar z_j} \qquad (\bar\partial\alpha = 0).$



Diagram and typed description. Bars above z_j in the differentials; condition $\alpha_{j\bar z_k} = \alpha_{k\bar z_j}$, on the right $(\bar\partial\alpha = 0)$.

Original source details: GELFAND-P000090



Uncertain reading. In the sum the subscript z_j has no confidently visible bar; above, in the definition, $\bar z_j$ is clear.

Original source details: GELFAND-P000090

Levi problem.



Diagram and typed description. The heading has a straight underline; in the question p, M, the sign $\exists$ and abbreviations.

Original source details: GELFAND-P000090

Given $p \in \partial M$ (bound.), [Crossed out: which (“какая”) / illegible.]

$\exists$ a holom. fn. in M, which does not continue beyond the point p? Exists.

Uncertain reading. which (“какая”) / illegible

Original source details: GELFAND-P000090

The class. Levi theor. solves this probl. locally:



Diagram and typed description. A wavy line under the whole sentence from “The class.” to “locally:”.

Original source details: GELFAND-P000090

$\underset{0}{\overset{r}{x}}$ — equ. of the boundary.





Diagram and typed description. An irregular closed curve, $-$ inside and $+$ outside above right. Below r a small crossed sign resembling x, then 0; their exact reading and role are not established.

Original source details: GELFAND-P000090

$$\underline{dr \neq 0}$$



Diagram and typed description. The entry $dr \neq 0$ has a straight underline; below "(point nonsingular)".

Original source details: GELFAND-P000090

(point nonsingular). At pt. $p \in \partial M$

$$\sum r_{z_i}(p)a^i = 0 \qquad \text{hyperpl.}$$



Diagram and typed description. Above the formula "At pt. $p \in \partial M$"; in the formula a^i and $= 0$; on the right "hyperpl.".

Original source details: GELFAND-P000090

$$\sum r_{z_i \bar{z}_j}(p)a^i \bar{a}^j$$

— Levi form.



Uncertain reading. The boundary function's letter resembles r / τ, the boundary sign ∂ / b.

Original source details: GELFAND-P000090

If it is pos. def. on the indicated hyperplane,
then there exists in a neighb. of pt. p [Crossed out: illegible.]
a fn., not cont. beyond the point p.

Uncertain reading. illegible

Original source details: GELFAND-P000090



Diagram and typed description. Abbreviations “pos. def.”, “on the indicated hyperplane”, then “exists in a neighb. of pt. p”.

Original source details: GELFAND-P000090

($\exists$ a polynomial W, such that the zeros are arranged thus:



)



Diagram and typed description. An irregular closed curve; at the right edge a nearly vertical stroke and a stroke running out to the right. Label p inside, left and below their junction. The exact position of the dense overlapping strokes is not established.

Original source details: GELFAND-P000090

A good answer to that probl. ($\bar\partial$) leads to a glob. sol. of the Levi probl. Let the $\bar\partial$-probl. be solvable for the dom. M ($\forall\alpha$, $\bar\partial\alpha = 0$, $\exists u$, $\bar\partial u = \alpha$). Let

$$g = \begin{cases} 1 & \text{in a neighb. of } p, \\ 0 & \text{outside } U \end{cases}$$

— cut-off fn.



Diagram and typed description. The entry g has a brace, 1 “in a neighb. of p”, 0 “outside U”; on the right “cut-off fn.”.

Original source details: GELFAND-P000090

Denote $\alpha = \bar\partial\left(\frac{g}{W}\right)$. W — the previously constr. polynomial. α — smooth up to the boundary.



Diagram and typed description. On the left $\alpha = \bar\partial(g/W)$; on the right W — the previously constr. polynomial; below “smooth up to the boundary”.

Original source details: GELFAND-P000090



Original source details: GELFAND-P000090

Diagram and typed description. Three irregular nested contours and an inclined stroke; a gap at the lower right of the outer contour. p inside the small contour. No labels U or boundary are visible at the contours; dense intersections are not fully distinguishable.

Solve the equ. someh., obtain u, consider $h = u - \frac{g}{W}$.



Original source details: GELFAND-P000090

Uncertain reading. After “equ.” the abbreviation “к-л.” (someh.); the second letter is dense, the exact reading is not fully established. Then u, $h = u - \frac{g}{W}$.

h holom. (since $\bar{\partial} = 0$) [A stroke crossed out: arrow (“стрелка”) / illegible.]

Original source details: GELFAND-P000090

Uncertain reading. arrow (“стрелка”) / illegible

u does not continue.

Original source details: GELFAND-P000090

Uncertain reading. Before “does not continue” the letter u is visible.

Analogo / Analogously (“Аналого” / “Аналогично”) is also possible, but there it continues beyond the point.



Original source details: GELFAND-P000090

Uncertain reading. Analogo / Analogously (“Аналого” / “Аналогично”)



Diagram and typed description. An outer contour; an inner contour with a lower notch; hatching between them. At the notch a small oval and an oblique stroke above it; several long strokes with downward arrows. Dense intersections and some stroke ends are not fully distinguishable.

Original source details: GELFAND-P000090

[Crossed out to the right of the drawing: illegible.]

Uncertain reading. illegible

Original source details: GELFAND-P000090

Must take into acc. the geom. structure of the entire domain as a whole.



Diagram and typed description. The last sentence breaks to “domain.”; above “but there it continues beyond the point”.

Original source details: GELFAND-P000090

GELFAND-P000091

$a^{p,q}$ — space of forms of type p, q.



Diagram and typed description. $a^{p,q}$; space of forms of type p, q.

Original source details: GELFAND-P000091

$$a^{p,q-1} \xrightarrow[\text{eqn}]{\bar\partial} a^{p,q} \xrightarrow{\bar\partial} \alpha^{p,q+1}.$$



Original source details: GELFAND-P000091

Diagram and typed description. Two arrows with $\bar\partial$; under the first, eqn is enclosed in an oval.

Uncertain reading. The initial and middle letters have the form a; the last in the chain and the following notation have the form α. The local a/α variation is retained.



Original source details: GELFAND-P000091

General theorems. $\alpha^{p,q}$ — Hilb. scalar product. $\varphi, \psi \in D_{\bar\partial^*}$.

$$Q(\varphi,\psi) = (\bar\partial\varphi, \bar\partial\psi) + (\bar\partial^*\varphi, \bar\partial^*\psi).$$

[At the right:] ($\bar\partial$ on smooth forms of 1st degree without boundary conditions).

Original source details: GELFAND-P000091

Diagram and typed description. $D_{\bar\partial^*}$, two terms in $Q(\varphi,\psi)$; at the right, parentheses about smooth forms of 1st degree without boundary conditions.

$$\boxed{\bar\partial^*\bar\partial\varphi + \bar\partial\bar\partial^*\varphi = \alpha}$$



Diagram and typed description. Equation with two terms and right side α; frame at the left, bottom and right, with no top side.

Original source details: GELFAND-P000091

With the aid of a pos. def. prob. [Crossed out: illegible] of higher order solve a prob. of 1st order.

Original source details: GELFAND-P000091

Uncertain reading. After prob., a former short expression is densely crossed out; an initial 1-/4-like stroke, the rest illegible.

But here it is used that the syst. is of 1st order and the solvability cond. is of 1st order. (On gen. overdet. syst. ∃ work of Spencer.) Connection with the Neumann prob.



Original source details: GELFAND-P000091

Diagram and typed description. Syst. of 1st order, solvability cond. of 1st order; in parentheses ∃ work of Spencer; then connection with the Neumann prob.

A priori est.

$$\int_{\partial M} |\varphi|^2 \, dS \leq CQ(\varphi, \varphi) \qquad \forall \varphi \in D_{\bar{\partial}^*} \cap \alpha^{p,q}.$$



Original source details: GELFAND-P000091

Diagram and typed description. The integral has ∂M, integrand $|\varphi|^2 dS$; $\leq CQ(\varphi, \varphi)$ and $\forall \varphi \in D_{\bar{\partial}^*} \cap \alpha^{p,q}$.

(but not min. $\sum$ of squares of 1st derivs., $n = 1 \sim \int$ Dirichlet).

Original source details: GELFAND-P000091

Diagram and typed description. Before $\sum$, min.; then squares of 1st derivs., $n = 1 \sim \int$ Dirichlet.

Attempt to apply projection (loc.) no, led nowhere. (Cohn spent 2 years on this, $\int$ eqns and so on.) Simplest case of the Neumann problem. Cohn and Rossi Ann. Math. 1965 on holom. continuation of forms (!) into the domain.



Original source details: GELFAND-P000091

Diagram and typed description. Attempt to apply projection (loc.); Cohn in two places; 2 years, $\int$ eqns; Rossi, Ann. Math. 1965; (!) after forms.

Plans for the future.



Original source details: GELFAND-P000091

Diagram and typed description. Wavy line beneath the heading Plans for the future.



Original source details: GELFAND-P000091

Uncertain reading. The word for in the heading is densely overwritten; the earlier strokes are illegible.

Study: Vinberg (algebraic groups),



Original source details: GELFAND-P000091

Diagram and typed description. Study: has a straight underline; Vinberg (algebraic groups).

Atiy[?] (...detail[?]; the beginning in parentheses is densely overwritten), alg. geometry.



Original source details: GELFAND-P000091

Uncertain reading. Atiy[?] (...detail[?]; the beginning in parentheses is densely overwritten), alg. geometry.

read for basic instruction: [Crossed out: Latin G... / Cyrillic Г...; the rest of the name is illegible.] and Rossi “functions of several complex variables” 1965 (sheaves, cohom. and so on).



Original source details: GELFAND-P000091

Uncertain reading. Latin G... / Cyrillic Г...; the rest of the name is illegible.



Original source details: GELFAND-P000091

Diagram and typed description. After the cancelled name, and Rossi; functions of several complex variables, 1965; in parentheses, sheaves, cohom. and so on.

Review by Dieudonné of the work of Grothendieck (Man. / Mat.[?] 9:1); the abbreviated first word is not entirely certain.

Original source details: GELFAND-P000091

Uncertain reading. (Man. / Mat.[?] 9:1); the abbreviated first word is not entirely certain.

27/IX Finn. Ideas in the Gauss–Bonnet theor.



Original source details: GELFAND-P000091

Diagram and typed description. Separate straight lines under the date and Finn; short bars above and below IX.

Generalization of Cohn–Vossen: the surf. is not closed, but complete (e.g., a paraboloid).



Original source details: GELFAND-P000091

Diagram and typed description. The surf. is not closed, but complete; in parentheses, e.g., a paraboloid.

$C = 2\pi$ [Crossed-out sign: illegible]; $\chi = 1$.



Original source details: GELFAND-P000091

Uncertain reading. After the first $C = 2\pi$ a sign is densely crossed out; its exact reading is not established.





Diagram and typed description. Two lines opening upward; the small one at the left has a short curved transverse stroke with thickened ends. Its exact role and direction are not established. To its right $C = 2\pi\chi$; by the large one $\chi = 1$, below, for it $C < 2\pi$.

Original source details: GELFAND-P000091

($C = \int K\, dS$).



Diagram and typed description. $C = \int K dS$ is enclosed in round parentheses.

Original source details: GELFAND-P000091

Cohn–Vossen theor.: $\forall$ complete surf. $C \leq 2\pi\chi$.



Diagram and typed description. The last line has $\forall$ complete surf. and $C \leq 2\pi\chi$.

Original source details: GELFAND-P000091

GELFAND-P000092

Aim of the work — to replace the inequality by an equality.



Diagram and typed description. Aim of the work — to replace the inequality by an equality.

Original source details: GELFAND-P000092

Next time a review by Volevich[?]

on var., anal. bundles.

Original source details: GELFAND-P000092

Uncertain reading. Volevich[?]

$Kohn$'om[?]

Original source details: GELFAND-P000092

Uncertain reading. $Kohn$'om[?]; dense beginning of the name and ending after the apostrophe.

Gelfand. [Crossed out: Atiy...; ending illegible.] Atiyah.



Original source details: GELFAND-P000092

Uncertain reading. [Crossed out: Atiy...; ending illegible.] Atiyah.

Fixed-point theorems.



Original source details: GELFAND-P000092

Diagram and typed description. Straight lines under Gelfand. and Atiyah.; wavy line under Fixed-point theorems.

(contains Brouwer's theor., the Lefschetz formula, the theor. that a lin. space has an eigenvector, Weyl's theor. on traces of reps. and so on.)



Original source details: GELFAND-P000092

Diagram and typed description. At the beginning of the parentheses, contains; then Brouwer's theor., the Lefschetz formula, eigenvector, Weyl's theor. on traces of reps.

X — diff. manifold and on it n vector bundles $E_1, \dots, E_n$. $\Gamma(E_i)$ — sections of E_i. (each bundle — its own dim.)



Original source details: GELFAND-P000092

Diagram and typed description. X, n, $E_1, \dots, E_n$ and $\Gamma(E_i)$; in parentheses, each bundle — its own dim.; the last ending of the Russian word for its own is tight.

Example: $X \times I$ (I — a straight line). Space of functions.

Original source details: GELFAND-P000092

Diagram and typed description. Straight underline under Example:; $X \times I$, I — a straight line, space of functions.

Elliptic complex (generalizes ell. diff. operators).



Original source details: GELFAND-P000092

Diagram and typed description. Wavy line under Elliptic complex; then generalizes ell. diff. operators.

$$\Gamma(E_1) \xrightarrow{d} \Gamma(E_2) \xrightarrow{d} \cdots \xrightarrow{d} \Gamma(E_n).$$

a seq. of linear maps such that 1° $d^2 = 0$.



Original source details: GELFAND-P000092

Diagram and typed description. Three arrows with d; $\Gamma(E_1)$, $\Gamma(E_2)$, ellipsis, $\Gamma(E_n)$; 1°, $d^2 = 0$.

2°. Consider $e \in E_{i,x_0}$, $s(x) \in \Gamma(E_i)$, such that $s(x_0) = e$. Let $f(x)$ be a function taking the value 0 at the point x_0. Consider $d(f^m s(x)) = s_1(x) \in \Gamma(E_{i+1})$.



Original source details: GELFAND-P000092

Diagram and typed description. $e \in E_{i,x_0}$; $s(x_0) = e$; function $f(x)$ vanishes at x_0; $d(f^m s(x)) = s_1(x) \in \Gamma(E_{i+1})$.

Then, if [Crossed out: $\exists$ with an illegible continuation.] $\exists m$,

such that $\forall x_0$ $(f(x_0) = 0)$ $s_1(x_0)$ depends only on the 1st differentials of f at the point x_0, the operator is called differential. ($\exists m$ such that $\forall f$, $\forall x_0$, $\forall s$ and so on.) The least m is called the order of the diff. operator such that $s(x_0) = e$. (In a neighbourhood of the point this is a local diff. operator.)



Original source details: GELFAND-P000092

Uncertain reading. [Crossed out: $\exists$ with an illegible continuation.] $\exists m$,



Original source details: GELFAND-P000092

Diagram and typed description. Three $\forall$ signs in parentheses; the least m, then such that $s(x_0) = e$; in the final parentheses, in a neighbourhood of the point.

$$df = (\eta, dx).$$

df — [Short word crossed out: illegible] vector; η — gradient (from [tang. inserted above densely overwritten strokes] space).

$\eta \in T_x^*$.



Original source details: GELFAND-P000092

Uncertain reading. df — [Short word crossed out: illegible] vector; η — gradient (from [tang. inserted above densely overwritten strokes] space).



Original source details: GELFAND-P000092

Diagram and typed description. $df = (\eta, dx)$; alongside, η — gradient; below, $\eta \in T_x^*$.

$$\sigma(d, \eta)e$$

— a lin. function of e, called the symbol of the diff. operator.

Original source details: GELFAND-P000092

Uncertain reading. First argument: d added above a densely cancelled sign; the former sign is illegible.

Example. Laplace operator. $m = 2$.

$$\frac{\partial^2(f^2(x)s(x))}{\partial x^2} = 2\left(\frac{\partial f}{\partial x}\right)^2 s(x).$$



Original source details: GELFAND-P000092

Diagram and typed description. Straight underline under Example.; $m = 2$; $f^2(x)s(x)$ in the second derivative; on the right $2(\partial f/\partial x)^2 s(x)$.

Symbol $2(\eta_1^2 + \eta_2^2 + \cdots + \eta_n^2)$.



Original source details: GELFAND-P000092

Diagram and typed description. Factor 2; $\eta_1^2 + \eta_2^2 + \cdots + \eta_n^2$.

Consider.

$$0 \longrightarrow E_{1,x_0} \overset{\sigma(\eta,d)}{\longrightarrow} E_{2,x_0} \overset{\sigma(\eta,d)}{\longrightarrow} \cdots \longrightarrow E_{n,x_0} \longrightarrow 0.$$



Original source details: GELFAND-P000092

Diagram and typed description. Zero endpoints; E_{1,x_0}, E_{2,x_0}, ellipsis, E_{n,x_0}; $\sigma(\eta, d)$ over the first two arrows.

The complex is elliptic if $\forall \eta \neq 0$ this seq. is exact.



Original source details: GELFAND-P000092

Diagram and typed description. The last line has $\forall \eta \neq 0$ and this seq. is exact.

GELFAND-P000093

Examples. 1) X — a domain in R^n. sheaf 1 ($X \times R$).



Original source details: GELFAND-P000093

Diagram and typed description. Straight underline under Examples.; 1), X, R^n, sheaf 1, $X \times R$.

Original source details: GELFAND-P000093

$$-\Gamma(1) \xrightarrow{\Delta} \Gamma(1).$$

Laplace operator.



Original source details: GELFAND-P000093

Uncertain reading. A short horizontal stroke before the first $\Gamma(1)$: minus / dash.

2) de Rham complex.



Original source details: GELFAND-P000093

Diagram and typed description. 2) de Rham complex.

Original source details: GELFAND-P000093

$$T^* \wedge T^* \wedge \cdots \wedge T^* = \Lambda^k\,[?].$$



Original source details: GELFAND-P000093

Uncertain reading. The Λ itself is densely overwritten; small exponent k[?], also n- / x- / κ-like.

T — [Beginning of the word densely overwritten; former letters illegible] tang. space.



Original source details: GELFAND-P000093

Uncertain reading. [Beginning of the word densely overwritten; former letters illegible] tang. space.

X — manifold. T_x — tang. space at the point x,



Original source details: GELFAND-P000093

Diagram and typed description. X — manifold; T_x — tang. space at the point x.

Original source details: GELFAND-P000093

Uncertain reading. [At the right: compact entry crossed out; T-/Phi-like strokes, exact reading undetermined.]

$$\Gamma(\Lambda^0) \xrightarrow{d} \Gamma(\Lambda^1) \xrightarrow{d} \cdots \xrightarrow{d} \Gamma(\Lambda^n).$$



Original source details: GELFAND-P000093

Uncertain reading. [Signs densely cancelled before the first $\Gamma(\Lambda^0)$, a separate short stroke at the left; after $\Gamma(\Lambda^n)$, an arrow and a 0-like sign are crossed out.]

[At the right:] sections — diff. forms.

Original source details: GELFAND-P000093

Diagram and typed description. At the right, sections — diff. forms.; wavy line under diff. forms.

Symbol at the 1st step — $(\eta_1, \ldots, \eta_n)$.

$$d(s(x)f(x)) = s(x_0)\eta = e\eta \qquad (df(x_0) = \eta).$$



Original source details: GELFAND-P000093

Diagram and typed description. At the 1st step $(\eta_1, \ldots, \eta_n)$; $s(x_0)\eta = e\eta$; in parentheses $df(x_0) = \eta$.

In the 2nd place

$$d(s(x)f(x))\big|_{x=x_0} = s(x) \wedge df(x)\big|_{x=x_0} = e \wedge \eta.$$



Original source details: GELFAND-P000093

Diagram and typed description. Two restrictions $x = x_0$; $s(x) \wedge df(x)$ and $e \wedge \eta$.

(each subsequent symbol — multiplication by η).

Original source details: GELFAND-P000093

Diagram and typed description. Each subsequent symbol — multiplication by η, in parentheses.

Exactness: if $e \wedge \eta = 0$, then $e = a \wedge \eta$.



Original source details: GELFAND-P000093

Diagram and typed description. Wavy line under Exactness:; $e \wedge \eta = 0$, $e = a \wedge \eta$.

(minors of the 2nd ord. $= 0$, then the vectors [pryam.: meaning unclear] [Final signs crossed out; dense entry, arrow and 0-like ending; exact reading undetermined.]

)



Original source details: GELFAND-P000093

Uncertain reading. [Final signs crossed out; dense entry, arrow and 0-like ending; exact reading undetermined.]

3) $\bar{\partial}$ and so on.



Original source details: GELFAND-P000093

Diagram and typed description. 3); horizontal bar above ∂; and so on.

$4/\overline{\text{X}}$ Continuation. $\Gamma(E)$ — seq.



Original source details: GELFAND-P000093

Diagram and typed description. Date $4/\overline{\text{X}}$; Continuation. underlined with two straight lines.

$$d(f^m(x)s(x))\big|_{x_0} = \sigma(d,\eta)e, \qquad s(x_0) = e.$$



Original source details: GELFAND-P000093

Diagram and typed description. $d(f^m(x)s(x))\big|_{x_0} = \sigma(d,\eta)e$; at the right $s(x_0) = e$.

η — 1st differential of f. $\eta \in T^*_{x_0}$.



Original source details: GELFAND-P000093

Diagram and typed description. At the right $s(x_0) = e$; η — 1st differential of f; $\eta \in T^*_{x_0}$.

Ell. operators can be other than differential.



Original source details: GELFAND-P000093

Diagram and typed description. Ell. operators can be other than differential.

Original source details: GELFAND-P000093

Uncertain reading. [Short word crossed out before the heading; dense horizontal strokes and a descending stroke; former letters illegible.]

Endomorphism of a complex.



Original source details: GELFAND-P000093

Diagram and typed description. Straight underline under Endomorphism of a complex.

$$\Gamma(E_1) \longrightarrow \Gamma(E_2) \longrightarrow \cdots \longrightarrow \Gamma(E_n).$$

Original source details: GELFAND-P000093

Diagram and typed description. $\Gamma(E_1) \longrightarrow \Gamma(E_2) \longrightarrow \cdots \longrightarrow \Gamma(E_n).$

It induces [Short sign / word densely cancelled before map; illegible.]
a map:

$$T_i^* : H^i(E) \longrightarrow H^i(E).$$

Original source details: GELFAND-P000093

Uncertain reading. [Short sign / word densely cancelled before map; illegible.]



Original source details: GELFAND-P000093

Diagram and typed description. It induces ... a map:; $T_i^* : H^i(E) \longrightarrow H^i(E)$.

[At the right:] T — endom. of the complex, $T_i : \Gamma(E_i) \to \Gamma(E_i)$, commutes with d. $(T_{i+1}d = dT_i)$. ↙



Original source details: GELFAND-P000093

Uncertain reading. At the right a slanting arrow crosses the end of the word complex and passes near the arrow between $\Gamma(E_i)$ and $\Gamma(E_i)$; its exact connection is unclear. Formulas: $T_i : \Gamma(E_i) \to \Gamma(E_i)$, $(T_{i+1}d = dT_i)$.

For an ell. complex they are all finite-dimensional. (In the case of an ell. operator it has an index difference.)



Original source details: GELFAND-P000093

Diagram and typed description. They are all finite-dimensional; in parentheses, In the case of an ell. operator it has an index difference.

In the de Rham complex these are the usual cohom. with real coeffs.

Original source details: GELFAND-P000093

Diagram and typed description. In the de Rham complex these are the usual cohom. with real coeffs.

$$L(T, E) = \sum_{i=1}^{n} (-1)^i \operatorname{tr}(T_i^*).$$



Diagram and typed description. $L(T, E)$; sum from $i = 1$ to n; $(-1)^i \operatorname{tr}(T_i^*)$.

[Under L:] Lefschetz number, homological. [At the right:] ⇓ for the de Rham complex this is the usual Lefschetz number. [At the bottom:] Lefschetz-Atiyah-Bott.



Original source details: GELFAND-P000093

Diagram and typed description. Under L: Lefschetz number, homological; at the right a downward arrow with two strokes and for the de Rham complex this is the usual Lefschetz number; at the bottom Lefschetz-Atiyah-Bott.

GELFAND-P000094

Let $f : X \longrightarrow X$.



Original source details: GELFAND-P000094

Diagram and typed description. Let; $f : X \longrightarrow X$.

Consider.

$$\psi_i : \Gamma(f^{-1}(E_i)) \longrightarrow \Gamma(E_i).$$



Uncertain reading. At the first ψ_i, a dense additional stroke precedes the clear i; former index / sign illegible. The first entry has $\Gamma(f^{-1}(E_i))$, the repeated entry $\Gamma(f^{-1}E_i)$.

Original source details: GELFAND-P000094

lifting — ~~by a map of sheaves~~ f by a map of sheaves.



Uncertain reading. By a map of sheaves is crossed out, partly obscured by strokes. A short sign is densely cancelled before the second Γ; exact reading undetermined.

Original source details: GELFAND-P000094

$$\psi_i : \Gamma(f^{-1}E_i) \longrightarrow \Gamma(E_i),$$

$$E_{i,f^{-1}x} \xrightarrow{\psi_{i,x}} E_{i,x}.$$

Uncertain reading. The left fibre index visibly has $f^{-1}x$.

Original source details: GELFAND-P000094

It is not uniquely determ. by f.



Diagram and typed description. It is not uniquely determ. by f.

Original source details: GELFAND-P000094

de Rham sheaf: f uniquely induces a map of de Rham sheaves. (natural lifting).



Diagram and typed description. f uniquely induces a map of de Rham sheaves; natural lifting in parentheses.

Original source details: GELFAND-P000094

$$\boxed{f : X \longrightarrow X}.$$



Diagram and typed description. Rectangular frame around $f : X \longrightarrow X$; the natural-lifting parenthesis is above its upper border.

Original source details: GELFAND-P000094

Suppose that f has only a finite number of isol. fixed points of the simplest structure.



Diagram and typed description. Suppose that f has only a finite number of isol. fixed points of the simplest structure.

Original source details: GELFAND-P000094

Brouwer theorem for the interval $[0, 1]$. $f : x \to f(x)$.



Diagram and typed description. Wavy line under Brouwer theorem; $[0, 1]$; $f : x \to f(x)$.

Original source details: GELFAND-P000094



ρ — fixed point of this map.
At it we have $\psi_i(\rho)$: [An E-like fibre entry crossed out; indices illegible.] $E_{i,\rho} \to E_{i,\rho}$.
In the tang. space$^{(x)[?]}$ there is a linear transformation.



Diagram and typed description. Rectangle labelled 0 and 1, two ascending lines, dense crossing. The crossing geometry is unclear. An angular line runs above and to the left of the adjoining lines about ρ, the fibre and the tangent space, then extends left below the drawing.

Original source details: GELFAND-P000094



Diagram and typed description. ρ — fixed point of this map.

Original source details: GELFAND-P000094



Uncertain reading. Before the new $E_{i,\rho}$ an E-like entry with unread indices is cancelled. An insertion (x)[?] is above the underlined space; the precise letter is uncertain.

Original source details: GELFAND-P000094

It is denoted $J_\rho(f)$ in the tang. space to X.



Original source details: GELFAND-P000094

Diagram and typed description. $J_\rho(f)$; in the tang. space to X.

The point is isolated $\Leftarrow$ it is sufficient that

$$\det(1 - J_\rho(f)) \neq 0.$$

(by the implicit-function theorem).



Original source details: GELFAND-P000094

Diagram and typed description. Heavy leftward arrow $\Leftarrow$; $\det(1 - J_\rho(f)) \neq 0$; by the implicit-function theorem.

The point [short crossed-out word illegible] singular fixed, if it is 0, regular, if $\neq 0$.



Original source details: GELFAND-P000094

Uncertain reading. After point, a short word is densely cancelled; former letters cannot be recovered. Then singular fixed, if it is 0, regular, if $\neq 0$.

The graphs $(x, f(x))$ and (x, x) intersect transversally.



Original source details: GELFAND-P000094

Diagram and typed description. $(x, f(x))$ and (x, x); intersect transversally.

Consider the number

$$\frac{\operatorname{tr} \psi_i(\rho)}{|\det(1 - J_\rho(f))|}.$$



Original source details: GELFAND-P000094

Diagram and typed description. $\operatorname{tr} \psi_i(\rho)$ above $|\det(1 - J_\rho(f))|$.

At the point ρ there are 2 lin. transf. $\psi_i(\rho)$ — the fibre into itself, and a transf. of the tang. space.



Original source details: GELFAND-P000094

Diagram and typed description. At the point ρ — 2 lin. transf.; $\psi_i(\rho)$ — the fibre into itself; transf. of the tang. space.

$$\sum (-1)^i \frac{\operatorname{tr} \psi_i(\rho)}{|\det(1 - J_\rho(f))|} = \sigma(\rho).$$



Original source details: GELFAND-P000094

Diagram and typed description. $\sum(-1)^i$ with no visible limits; $\operatorname{tr} \psi_i(\rho)$; $|\det(1 - J_\rho(f))|$; $\sigma(\rho)$.

This number does not depend on the complex, but depends only on f and the induced maps in the fibres (but the map of fibres is not arbitrary, it must commute with the complex).



Original source details: GELFAND-P000094

Diagram and typed description. Does not depend on the complex; f and induced maps in the fibres; in parentheses, but the map of fibres is not arbitrary, it must commute with the complex.

ψ_i must be an endomorphism!



Original source details: GELFAND-P000094

Diagram and typed description. ψ_i must be an endomorphism!

GELFAND-P000095

Theorem of Atiyah–Bott.

Original source details: GELFAND-P000095

Diagram and typed description. Only Theorem is underlined; Atiyah–Bott; number 64.

Let there be an ellipt. complex d, $f : X \to X$ and its lifting ψ, which is an endomorphism of this complex. Then the formula holds



Original source details: GELFAND-P000095

Diagram and typed description. Ellipt. complex d; $f : X \to X$; its lifting ψ, which is an endomorphism of this complex.

$$L(T, E) = \sum_{\rho} \sigma(\rho)$$

over all fixed points.

Original source details: GELFAND-P000095

Diagram and typed description. $L(T, E) = \sum_{\rho} \sigma(\rho)$; over all fixed points.

T is given by the pair f and ψ.



Original source details: GELFAND-P000095

Diagram and typed description. T is given by the pair f and ψ.

Proof.

Original source details: GELFAND-P000095

Diagram and typed description. Proof is underlined.

First unclearly[?] and incompletely (ideas)



Original source details: GELFAND-P000095

Uncertain reading. First word after First: unclearly[?] / inexactly[?]; crowded middle strokes.

$d : \Gamma(E)_i \longrightarrow \Gamma(E)_{i+1}$, construct a new operator from it.



Original source details: GELFAND-P000095

Diagram and typed description. $d : \Gamma(E)_i \longrightarrow \Gamma(E)_{i+1}$; indices i, $i+1$ are outside the parentheses; construct a new operator from it.

Introduce a scalar product on $\Gamma(E)$.



Original source details: GELFAND-P000095

Diagram and typed description. Introduce a scalar product on $\Gamma(E)$.

Introduce the "Laplacian oper."

$$\Box = d^*d + dd^*.$$



Original source details: GELFAND-P000095

Diagram and typed description. Laplacian oper.; $\Box = d^*d + dd^*$.

Maps each $\Gamma(E)$ into itself.



Original source details: GELFAND-P000095

Diagram and typed description. Maps each $\Gamma(E)$ into itself.

Hodge theorem (generalized): $\Box$ has a discr. positive spectrum, to each eig. number corresponds a finite number of eig. values.



Original source details: GELFAND-P000095

Diagram and typed description. Discr. positive spectrum; to each eig. number corresponds a finite number of eig. values.

$\Gamma_\lambda(E_i)$ — subspace corresp. to the eig. value λ. (eig. functions)



Original source details: GELFAND-P000095

Diagram and typed description. $\Gamma_\lambda(E_i)$; subspace corresp. to the eig. value λ; eig. functions.

$$d : \Gamma_\lambda(E_i) \longrightarrow \Gamma_\lambda(E_{i+1}).$$

Original source details: GELFAND-P000095

Diagram and typed description. $d : \Gamma_\lambda(E_i) \longrightarrow \Gamma_\lambda(E_{i+1})$.





Original source details: GELFAND-P000095

Uncertain reading. $\Box d = d\Box$ in an oval; a separate small i-like stroke[?] is to the right of the last square.

$$d : \Gamma(E_1) \longrightarrow \Gamma(E_2) \longrightarrow \cdots \longrightarrow \Gamma(E_n).$$



Original source details: GELFAND-P000095

Diagram and typed description. $d : \Gamma(E_1) \to \Gamma(E_2) \to \cdots \to \Gamma(E_n)$.

Now consider

$$d : \Gamma_\lambda(E_1) \longrightarrow \Gamma_\lambda(E_2) \longrightarrow \cdots \longrightarrow \Gamma_\lambda(E_n).$$



Original source details: GELFAND-P000095

Diagram and typed description. Now consider; $d : \Gamma_\lambda(E_1) \to \Gamma_\lambda(E_2) \to \cdots \to \Gamma_\lambda(E_n)$.

Γ_λ are already finite-dimensional ($d^2 = 0$), homologies arise here too.



Original source details: GELFAND-P000095

Diagram and typed description. Γ_λ are already finite-dimensional; $(d^2 = 0)$; homologies arise here too.

$$H^i\{\Gamma_\lambda(E)\} = \begin{cases} H^i(E), & \lambda = 0, \\ 0, & \lambda \neq 0. \end{cases}$$



Original source details: GELFAND-P000095

Diagram and typed description. $H^i\{\Gamma_\lambda(E)\}$; $H^i(E)$ at $\lambda = 0$, 0 at $\lambda \neq 0$.

(indices exist only for defin.[?] oper.)

Original source details: GELFAND-P000095

Uncertain reading. Abbreviation after for: defin.[?] / diffin.[?]; unexpanded.

For the de Rham compl. — Hodge theorem — every [crossed-out expression illegible]



Original source details: GELFAND-P000095

Diagram and typed description. For the de Rham compl. — Hodge theorem — every.

[Crossed-out expression illegible] closed form homologous to a harmonic one.

Uncertain reading. Two densely crossed-out expressions: after every and before closed; former letters undetermined.

Original source details: GELFAND-P000095



Original source details: GELFAND-P000095

Diagram and typed description. Closed form homologous to a harmonic one; two short rightward arrows under homologous.

Calculate the trace: $\sum$ diag. elem. $\equiv \sum$ eig. values.



Original source details: GELFAND-P000095

Diagram and typed description. Calculate the trace; $\sum$ diag. elem. $\equiv \sum$ eig. values; three horizontal bars.

(1. Trace as $\int K(x,x)\,dx$, and $\sum$ of traces in each subspace



Original source details: GELFAND-P000095

Diagram and typed description. (1.; trace as $\int K(x,x)\,dx$; and $\sum$ of traces in each subspace.

(inv. eig.)



Original source details: GELFAND-P000095

Diagram and typed description. Inv. eig. in parentheses.

$\lambda \neq 0$ [short sign densely crossed out, illegible] no trace, $\lambda = 0$ calc. through homologies.
}[?]



Original source details: GELFAND-P000095

Uncertain reading. After $\lambda \neq 0$, a short sign / arrow[?] is densely cancelled. No trace is legible, then $\lambda = 0$ calc. through homologies. A large closing bracket-like sign at right: brace / parenthesis[?].

GELFAND-P000096

$11/\overline{\underline{X}}$ Seminar plan.



Original source details: GELFAND-P000096

Diagram and typed description. $11/\overline{\underline{X}}$; upper and lower bars at X; Seminar and plan have wavy underlining.

1. Integro-diff. operators (Agranovich). (2 hours)



Original source details: GELFAND-P000096

Diagram and typed description. Integro-diff. operators; Agranovich; beneath the parenthesis, (2 hours).

2. Atiyah–Singer on the index. Kirillov or Gelfand. Dynin. (yearly sem. Cartan-Schwartz and Vishik's sem. 64–65.)



Original source details: GELFAND-P000096

Diagram and typed description. Atiyah–Singer on the index; Kirillov or Gelfand; Dynin; yearly sem. Cartan-Schwartz and Vishik's sem. 64–65.

3. Statistical physics (Minlos , 3 meetings).
Robert Adl'fovich[?]



Original source details: GELFAND-P000096

Diagram and typed description. Statistical physics; Minlos; 3 meetings; first name and patronymic below the surname.



Original source details: GELFAND-P000096

Uncertain reading. Below Minlos: Robert Adl'fovich[?] / Robert Adol'fovich[?]; the small loop after d is uncertain.

4. Adeles and adele groups (Graev [crossed-out M-like sign, illegible] Mark Iosifovich). (2 meetings)



Original source details: GELFAND-P000096

Diagram and typed description. Adeles and adele groups; Graev Mark Iosifovich; (2 meetings).



Original source details: GELFAND-P000096

Uncertain reading. Between Graev and Mark, an M-like sign is densely cancelled; former reading undetermined.

5. Linear algebraic groups. Kirillov Gelfand



Original source details: GELFAND-P000096

Diagram and typed description. Linear algebraic groups; Kirillov / Gelfand in a column at right.

6. Work of Bott and Chern (Acta Math.) Gelfand Vol. 114[?] $N = 1–2$



Original source details: GELFAND-P000096

Diagram and typed description. Work of Bott and Chern; Acta Math.; Gelfand; volume notation below the journal name.



Original source details: GELFAND-P000096

Uncertain reading. Dense volume signs: Vol. 114[?] / Vol. III[?]; $N = 1–2$. A short sign / word is crossed out below.

(transfer[?] of Nevanlinna's theorem on zeros of funct. to [densely crossed-out fragment illegible] curves sect. of vect. sheaves.)



Original source details: GELFAND-P000096

Uncertain reading. First word in parentheses transfer[?] / transferred[?]. A fragment is densely cancelled before curves; then sect. of vect. sheaves.

7. Riemann–Roch–Grothendieck theorem. Kazdan[?] D. A.



Original source details: GELFAND-P000096

Uncertain reading. Two straight underlines below parts of the title: the ann–Roch area and the start of Grothendieck; precise boundaries uncertain. Surname Kazdan[?] / Kazhdan[?].

Kazdan[?]. Riemann–Roch theorem.



Original source details: GELFAND-P000096

Uncertain reading. The surname with a wavy underline: Kazdan[?] / Kazhdan[?]; dense sign between a and d.

To a vect. sheaf corresp. a cohom. class — Chern class.



Original source details: GELFAND-P000096

Diagram and typed description. To a vect. sheaf corresp. a cohom. class; Chern class, the Latin surname with a Russian ending in the source.

Chern classes.

Original source details: GELFAND-P000096

Diagram and typed description. Chern classes is underlined; the start of classes is written densely.

X — classical alg. variety, aff. space



Original source details: GELFAND-P000096

Diagram and typed description. X — classical alg. variety, aff. space.

alg. funct. on it — polynomials, this is the simplest[?] alg. variety.



Uncertain reading. Alg. funct. on it — polynomials; this is the simplest[?] / this is the most simple[?]; ending of the last word dense; then alg. variety.

Original source details: GELFAND-P000096

Affine alg. varieties. Let a collection of polynomials be given

$$p_1(x_1, \ldots, x_n), \ldots, p_k(x_1, \ldots, x_n)$$



Diagram and typed description. Affine alg. varieties; collection of polynomials $p_1(x_1, \ldots, x_n), \ldots, p_k(x_1, \ldots, x_n)$.

Original source details: GELFAND-P000096

(let the field K be alg. closed)



Diagram and typed description. Let the field K be alg. closed; uppercase K.

Original source details: GELFAND-P000096

Consider collections of points — satisfy an eqn., aff. alg. var.-



Diagram and typed description. Consider collections of points; satisfy an eqn.; aff. alg. var.- with a final dash.

Original source details: GELFAND-P000096

— alg. funct. — restrictions of polynomials —



Diagram and typed description. — Alg. funct. — restrictions of polynomials —.

Original source details: GELFAND-P000096

— quotient ring by the ideal spanned by polyn.



Diagram and typed description. Quotient ring by the ideal spanned by polyn.

Original source details: GELFAND-P000096

Alg. prevariety — space loc. isomorphic to an aff. variety.



Diagram and typed description. Alg. prevariety; space loc. isomorphic to an aff. variety.

Original source details: GELFAND-P000096

GELFAND-P000097

If add. conditions

$$Q_1(x_1, \ldots, x_n) \neq 0,$$
$$Q_i(x_1, \ldots, x_n) \neq 0,$$



Original source details: GELFAND-P000097

Uncertain reading. Q_1, Q_i; x_n) underlined in the first line. Between the lines below Q_1, a dot ·, and a short dash – farther right; their role is undetermined. At right, (all at once $\neq 0$).



Original source details: GELFAND-P000097

Uncertain reading. Two lines at right are densely crossed out; an initial parenthesis, loops, horizontal and slanting strokes remain visible; no reliable reading established.

(all at once $\neq 0$) then also an alg. var.

Original source details: GELFAND-P000097

Diagram and typed description. Then also an alg. var.

funct. — from rat. funct. with poles outside these points.



Original source details: GELFAND-P000097

Diagram and typed description. Funct. — from rat. funct. with poles outside these points.

Example: line, alg. funct. — polynomials.



Original source details: GELFAND-P000097

Diagram and typed description. Example is underlined; line, alg. funct. — polynomials.

Space given with a stock of funct.



Original source details: GELFAND-P000097

Diagram and typed description. Space given with a stock of funct.

Consider points $x \neq 0$. Funct. now $\frac{P(x)}{x^m}$[?].



Original source details: GELFAND-P000097

Uncertain reading. Consider points $x \neq 0$; fraction $\frac{P(x)}{x^m}$[?]. The denominator exponent is m- / n-like and written densely.

Aff. var. — zeros of some funct. and others do not turn into 0.



Original source details: GELFAND-P000097

Diagram and typed description. Aff. var. — zeros of some funct. and others do not turn into 0.

General alg. var.: ∀ point there exists an open nbhd., isomorphic to an aff. alg. variety. (at first only a diff. var. or ringed space)



Original source details: GELFAND-P000097

Diagram and typed description. General alg. var. underlined; ∀ point, open nbhd., isomorphic to an aff. alg. variety; below, parentheses concerning a diff. var. or ringed space.

Ringed space — [short crossed-out fragment illegible]

Original source details: GELFAND-P000097

Uncertain reading. Between the dash and var., a short sign / word is densely cancelled; reading undetermined.

var. with a sheaf of rings.
(space)



Original source details: GELFAND-P000097

Diagram and typed description. Var. with a sheaf of rings; (space) inserted below var.

Every aff. alg. var. — ringed space.



Original source details: GELFAND-P000097

Diagram and typed description. Every aff. alg. var. — ringed space.

On it one introduces the Zariski top. (So that all alg. funct. are cont. — closed sets — zeros of a finite number of alg. funct. /[?].



Original source details: GELFAND-P000097

Uncertain reading. Zariski top.; opening parenthesis before So that; after alg. funct., a slash /[?] / closing parenthesis)[?], then a period.

Sheaf of rings — an open set in it this is also an alg. variety.



Original source details: GELFAND-P000097

Diagram and typed description. Sheaf of rings — an open set in it this is also an alg. variety.



Original source details: GELFAND-P000097

Uncertain reading. In the left margin, faint, dotted and loop-like traces; before the following formula, a dense A-like sign. No reliable complete words read; origin of the traces undetermined.

$C^2 \setminus 0$ is not an aff. alg. variety.



Original source details: GELFAND-P000097

Diagram and typed description. $C^2 \setminus 0$ is not an aff. alg. variety; written C, without an additional vertical bar.

open set

Every aff. alg. variety[?] cont... [ending crossed out]



Original source details: GELFAND-P000097

Diagram and typed description. Above aff., open set is inserted with a lower brace and a downward point; insertion position retained.

Original source details: GELFAND-P000097

Uncertain reading. Ending of the word variety: handwritten -iya[?] / -iye[?]; last sign ya-/e-like.

Original source details: GELFAND-P000097

Uncertain reading. Cont...: the ending is densely crossed out; zhit-like letter tops remain above the strokes[?]. Possible whole word contains[?]; cancelled letters not securely determined.

open subset, being an alg. variety.



Original source details: GELFAND-P000097

Diagram and typed description. Open subset, being an alg. variety.

Sheaf [n-/i-like sign, illegible] of rings — must def. the group of sections



Original source details: GELFAND-P000097

Uncertain reading. Sheaf has a wavy underline. Before of rings, a separate dense n-/i-like sign; whether cancellation or insertion is undetermined.

on basic open sets obtained by eqns. of the form $R_2(x) \neq 0$[?], the ring of alg. funct. on this set.



Original source details: GELFAND-P000097

Uncertain reading. The group of sections on basic open sets; eqns. of the form $R_2(x) \neq 0$[?] / $R_1(x) \neq 0$[?]; subscript with a curved top and a long base, 2-like. Then the ring of alg. funct. on this set.

Obtain a sheaf of germs of alg. funct. ringed space.



Original source details: GELFAND-P000097

Diagram and typed description. Obtain a sheaf of germs of alg. funct. ringed space; no separate comma visible after funct.

Ringed space — prealg.[?] var., if it is loc. isomorphic to an aff. alg. var. (as a ringed space)



Original source details: GELFAND-P000097

Uncertain reading. Abbreviation after the dash prealg.[?] / prev.[?]; dense letters after pred. In the next line loc. is written densely; then isomorphic to an aff. alg. var.; below, (as a ringed space).

GELFAND-P000098

Aff. alg. var.

$$\begin{cases} p_1 = \\ \vdots \\ p_m = 0 \end{cases}$$
$$Q \neq 0$$

[Crossed out: open[?], remainder illegible] closed set.



Uncertain reading. Under the left brace, $p_1 =$ with no visible right-hand side, dots, $p_m = 0$; below, $Q \neq 0$. At right, dense cancellation before closed set; otkr.-like remnants (open)[?], full reading undetermined.



Original source details: GELFAND-P000098

$R_i(x_1, \ldots, x_n) = 0$. R_i — polynomials.



Diagram and typed description. Closed set; $R_i(x_1, \ldots, x_n) = 0$, R_i — polynomials.

Original source details: GELFAND-P000098

Basis of open sets — one condition $U_S : S \neq 0$. (such is cont. in every open — — leave 1 condition).



Diagram and typed description. $U_S : S \neq 0$; in parentheses two separate dashes: after open and before leave 1 condition.

Original source details: GELFAND-P000098

The group of sections is given thus —



Diagram and typed description. The group of sections is given thus —; then $\Gamma(U_S)$ and rat. funct. on R^n. Written R, without an additional vertical bar.

Original source details: GELFAND-P000098

$\Gamma(U_S)$ — all rat. funct. on R^n which do not turn into ∞ anywhere on our set.

$$\Gamma(U_S) = [?] \left\{ \frac{P(x)}{Q(x)} \right\}$$

Uncertain reading. Between $\Gamma(U_S)$ and the brace, two horizontal bars with dense overwriting between them: $=$ with alteration / rewritten sign; $\neq$ remains an unestablished alternative. No definite diagonal stroke read.

Original source details: GELFAND-P000098



Diagram and typed description. $\Gamma(U_S)$, overwritten sign, $\left\{ \frac{P(x)}{Q(x)} \right\}$; no separate period visible after the right brace.

Original source details: GELFAND-P000098

Identify, if on U_S one value. This is a ring.



Diagram and typed description. Identify, if on U_S one value.

Original source details: GELFAND-P000098

(This will be a sheaf, easy to prove that this will really be the gr. of sections.)



Uncertain reading. This is a ring. In parentheses: This will be a sheaf, easy to prove that this will really be the gr. of sections. A short horizontal stroke lies below the final letter of the translated really; its role is undetermined. The upper breve belongs to the source letter y-short.

Original source details: GELFAND-P000098

Isom. of sheaves. obtained by the definition of an isomorphism



Diagram and typed description. Isom. of sheaves. obtained by the definition of an isomorphism; period after sheaves.

Original source details: GELFAND-P000098

of bases[?] homeom. nat.

Uncertain reading. At the line end, baz.[?] / bez.[?]; the middle letter has a loop, the last a descending stroke. Next line: homeom. nat.; the abbreviation remains uncertain.



Original source details: GELFAND-P000098





Uncertain reading. Top row $E \leftrightarrow E'$, two heavy downward arrows to B, B'. The upper ends and arrowheads are dense; their exact outlines are undetermined. No horizontal arrow visible between B and B'.

Original source details: GELFAND-P000098

If E is a subsheaf of funct., then $B \longrightarrow B'$ induces $E' \longrightarrow E$.



Diagram and typed description. In the line, $B \longrightarrow B'$ induces $E' \longrightarrow E$; the prime strokes are raised at the second letters.

Original source details: GELFAND-P000098

(A priori only commut.) Require that the isom. be an isom. arising from considerations of the base. (natural!) simply coincidence!



Diagram and typed description. (A priori only commut.) Require that the isom. be an isom. arising from considerations of the base. (natural!) simply coincidence!

Original source details: GELFAND-P000098

$C^2 \setminus 0$ is a prealg. var.



Uncertain reading. $C^2 \setminus 0$ is a prealg. var. Above prealg., two separated horizontal strokes, the right higher; a dot beside the lower. Their role and association with the words are undetermined. Written C, without an additional vertical bar.

Original source details: GELFAND-P000098

Choose 2 straight lines[?].

Original source details: GELFAND-P000098

Uncertain reading. After Choose 2, cramped pryamye (straight lines)[?] / pryamki[?]; the middle and final strokes are dense.

1st on $x \neq 0$, 2nd $y \neq 0$. Our set — their union. Each of them an aff. var.



Original source details: GELFAND-P000098

Diagram and typed description. 1st on $x \neq 0$, 2nd $y \neq 0$. Our set — their union; each of them an aff. var.





Original source details: GELFAND-P000098

Uncertain reading. Within a rectangular frame, heavy vertical and horizontal lines intersect. The left end is pointed, the right and lower ends thickened; the role of the thickenings and exact form of possible arrowheads are undetermined. No letter labels or separate circle visible at the intersection.

Then agree. sheaves of rings already clear[?].



Original source details: GELFAND-P000098

Uncertain reading. Then agree. sheaves of rings already clear[?]; final word clear[?] / easy[?]. Below the line are two separate strokes, under the end of agree. and part of sheaves; exact association of the underlining remains uncertain.

Points of $\overset{\text{pre}}{\vee}$ alg. var. may be inseparable for funct.



Original source details: GELFAND-P000098

Diagram and typed description. Above the gap before alg., pre is inserted with a V-shaped insertion mark. Points is written densely; next-line ending funct.

pre-
Example of pr. aff. alg. var.



Original source details: GELFAND-P000098

Diagram and typed description. The heading Example of pr. aff. alg. var. has a wavy underline. Above alg., pre- is inserted with a lower curly brace. The abbreviation pr. is not expanded.

$$p_1(x_1, \ldots, x_n[?]) = 0,$$
$$, \quad - \qquad - [?]$$
$$p_k(x_1, \ldots, x_n[?]) = 0,$$
$$Q(x_1, \ldots, x_n[?]) \neq 0.$$



Original source details: GELFAND-P000098

Uncertain reading. In the three lines, the final indices x_n[?] / x_m[?] are dense; in the second line there is an additional upper stroke. The subscript 1 on the first p has a dense horizontal base. Between the first and second lines, three separate short marks: the left comma-/dot-like, and two dashes; their role is undetermined.

The last cond. is not obligatory, any [crossed-out word illegible] aff. alg. var. can be given without using these [crossed-out word illegible] conditions (∃ var., isomorphic to it).



Original source details: GELFAND-P000098

Uncertain reading. After any, a word densely cancelled with long horizontal strokes and a loop at left; below, after these, a second densely crossed-out word. No secure letter-by-letter reading of either established.



Original source details: GELFAND-P000098

Diagram and typed description. The last cond. is not obligatory; then without using these ... conditions; below, (∃ var., isomorphic to it). The source ending usloviyakh is retained.

GELFAND-P000099

Take (x, y) with the condition

$$\begin{cases} P_i(x) = 0, \\ Q(x)y - 1 = 0 \end{cases}$$

$(x_1, \ldots, x_n, y)$



Diagram and typed description. System with a left brace: $P_i(x) = 0$, $Q(x)y - 1 = 0$. At the upper right, $(x_1, \ldots, x_n, y)$; the number 66 with an angular stroke to its left and below.

Original source details: GELFAND-P000099

They are isomorphic.

Diagram and typed description. They are isomorphic.

Original source details: GELFAND-P000099

Let there be a rng.[?] $P(x)$ and an ideal I[?] — the first aff. alg. var. $P(y)$ J — the 2nd aff. alg. var.

Their product — — the ring $P(x, y)$ with the ideal

$$\{I[?] \otimes [P(y)] + [?]\,[P(x)] \otimes J\}$$



Uncertain reading. The first ideal I[?] / J[?]: upper bar and lower left hook, with a lower loop in the formula. Between the summands, a densely overwritten $+$[?] / $\oplus$[?]. The abbreviation before the first ring is kol.[?] / kol'.[?].

Original source details: GELFAND-P000099



Diagram and typed description. Their product — and the following line — the ring $P(x, y)$ with the ideal: two separate dashes.

Original source details: GELFAND-P000099

? [?]

Original source details: GELFAND-P000099

Uncertain reading. At right, a circled ?-/2-like sign; a separate lower dot below the main curved stroke. Reading undetermined.

(as a set — the usual prod.)



Original source details: GELFAND-P000099

Diagram and typed description. (as a set — the usual prod.).

The ring of funct. on it — the tensor pr. of the rings of funct. on those var.



Original source details: GELFAND-P000099

Diagram and typed description. The ring of funct. on it — the tensor pr. of the rings of funct. on those var.

Pr. prod. of any prealg. var. — [crossed-out text illegible]



Original source details: GELFAND-P000099

Diagram and typed description. Pr. prod. of any prealg. var. —. The abbreviation Pr. is retained.

X, Y — $\overset{\text{pre}}{\vee}$ alg. varieties.



Original source details: GELFAND-P000099

Diagram and typed description. Above the gap before alg., pre is inserted, with a V-shaped insertion mark below; in the line, X, Y.

$\{U_i\}$ $\{V_j\}$ — 2 covers by aff. open subvarieties. $X \times Y$ is covered by $U_i \times V_j$. This is a napr.[?] var.



Original source details: GELFAND-P000099

Uncertain reading. Upper line: $\{U_i\}$, $\{V_j\}$ — 2 covers by aff. open subvarieties; below, $X \times Y$ is covered by $U_i \times V_j$. After This is, a napr.[?]-like abbreviation, read uncertainly.

[Densely crossed-out initial text illegible] Note that the prod. of var. is not the prod. of top. spaces (the top. is not the top. of the prod.).



Original source details: GELFAND-P000099

Uncertain reading. After the dash in the product line, dense cancellation; below, a separate angular stroke and a black mark. Before Note, initial text is densely crossed out. Letter-by-letter readings of the cancellations undetermined.



Original source details: GELFAND-P000099

Diagram and typed description. Note that the prod. of var. is not the prod. of top. spaces (the top. is not the top. of the prod.).

Consider $X \times X$. Choose in it

in it a struct.



Original source details: GELFAND-P000099

Diagram and typed description. In the line: Consider $X \times X$. Choose in it; below the line, separately, in it a struct.

Prealg.[?] subvar. — a closed subset in the top.[?] of Zariski. It is itself a prealg. var.



Original source details: GELFAND-P000099

Uncertain reading. At the beginning, Prealg.[?]; the middle letters are densely overwritten; earlier strokes unread.



Original source details: GELFAND-P000099

Uncertain reading. Subvar. — a closed subset in the top.[?] of Zariski. The source abbreviation tp.[?] / top.[?] is cramped. Next line: It is itself a prealg. var.

In $X \times X$ there is the diagonal (x, x). If it is closed, the var. is called algebraic.



Original source details: GELFAND-P000099

Diagram and typed description. In $X \times X$ there is the diagonal (x, x). If it is closed, the var. is called algebraic.

[This is stand. — a presheaf is called a sheaf if the diagonal is closed.
The top. in X is separated if the diag. $X \times X$ is closed.)



Original source details: GELFAND-P000099

Uncertain reading. A presheaf is called a sheaf if the diagonal is closed. The first word is written predpuchok (presheaf); its cramped joined strokes are retained in the adjacent original.



Original source details: GELFAND-P000099

Uncertain reading. The top. in X is separated if the diag. $X \times X$ is closed.); the aside begins with a square bracket and ends with a round parenthesis. Association of the unequal brackets undetermined.

Example of a prealg. but non-alg. X. (U_1, U_2) — a cover, U_1, U_2 — isom. to a line. $U_1 \cap U_2$ isom. to a line with a point removed.



Original source details: GELFAND-P000099

Diagram and typed description. Example has a straight underline; (U_1, U_2), U_1, U_2, $U_1 \cap U_2$ and a removed point.



Original source details: GELFAND-P000099

Uncertain reading. One nearly horizontal line with a thickened point; above it x', below it x''. Exact outline of the thickening undetermined.

☛ Check that the diag. is not closed.



Original source details: GELFAND-P000099

Uncertain reading. Before Check, a separate dense black sign with two rightward projections; its role and exact outline undetermined. Check that the diag. is not closed.

GELFAND-P000100

Classes of cycles modulo lin. equiv.



Original source details: GELFAND-P000100

Diagram and typed description. The entire heading Classes of cycles modulo lin. equiv. has a straight underline.

[a more precise inv. than cohom.)



Uncertain reading. A more precise inv. than cohom.; the opening bracket is angular, with a lower rightward foot, and its reading as [/ (is not fully established; the closing parenthesis is round.

Original source details: GELFAND-P000100

X — an alg. variety, subvar. — a closed set in the top. of Zariski.



Diagram and typed description. X — an alg. variety; subvar. — a closed set in the top. of Zariski.

Original source details: GELFAND-P000100

V_i — subvarieties.



Diagram and typed description. V_i — subvarieties; lower index i.

Original source details: GELFAND-P000100

$$\sum_{\text{for.[?]}} a_i V_i \text{ — cycles} \qquad (a_i \text{ — integers})$$



Uncertain reading. Below the summand, the short source annotation for.[?] / form.[?]; after the distinct f-, o- and r-shaped letters, a cramped upper exit stroke. Formula $\sum a_i V_i$ and, at right, (a_i — integers).

Original source details: GELFAND-P000100

$\sum b_i U_i$. 2 cycles are linearly equiv. if

$X \times P^1$ in it there are subvar. $X \times a$, $X \times b$ $a, b \in P^1$



Original source details: GELFAND-P000100

Diagram and typed description. $\sum b_i U_i$. 2 cycles are linearly equiv. if; a period after U_i.



Original source details: GELFAND-P000100

Diagram and typed description. $X \times P^1$; the words in it there are subvar.; at right $X \times a$, below it $X \times b$ and $a, b \in P^1$.

(P^1 cov. by two ord. lines — an alg. var.)



Original source details: GELFAND-P000100

Diagram and typed description. (P^1 cov. by two ord. lines — an alg. var.); the source abbreviation ob. and both parentheses.

They are can. isom. to X.

Original source details: GELFAND-P000100

Uncertain reading. At left, a black vertical star-/letter-like mark with projections. Its approximate form is reproduced; letter reading and purpose undetermined.

Original source details: GELFAND-P000100

Diagram and typed description. They are can. isom. to X.

2 cycles are equiv. if [crossed out: illegible] ∃ a 3rd cycle, $W[?] \in X \times P^1$, giving in intersect. with [crossed out: illegible] $X \times a$ the first, and with $X \times b$ the second.



Original source details: GELFAND-P000100

Uncertain reading. After if, an expression with an initial v-like stroke is cancelled; after with, another word with a lower loop is cancelled. Full readings of the cancellations undetermined.



Original source details: GELFAND-P000100

Uncertain reading. ∃ a 3rd cycle, $W[?] \in X \times P^1$; the letter $W[?]$ has cramped ascending strokes and may look N-like. A short lower comma follows cycle. The continuation with $X \times a$ and $X \times b$ occupies three lines.

Example. X — a surface, U, V — curves.



Original source details: GELFAND-P000100

Diagram and typed description. Example. is underlined including the period; X — a surface, U, V — curves.

They are lin. equiv. if ∃ [crossed-out sign illegible] a funct. with zeros on U and poles on V.

Original source details: GELFAND-P000100

Uncertain reading. Between the existence sign and funct., a small dense sign: a closed horizontal loop with a transverse stroke; letter reading undetermined.



Original source details: GELFAND-P000100

Diagram and typed description. They are lin. equiv. if ∃ ... a funct. with zeros on U and poles on V.

Consider $X \times P^1$. Take in it $a = 0$ and $b = [?]\ \infty$. In $X \times P^1$ take the cycle $(x, f(x))$



Uncertain reading. Before ∞, after b, a dense short horizontal mark, $=$[?]; two separate bars cannot be distinguished confidently. On the next line, $(x, f(x))$: a tall f stroke with a crossbar. The initial source Rassm. (Consider) has dense lower strokes; a separate underline is not established.

Original source details: GELFAND-P000100

Def. of Chern[?] classes (alg. varieties)

Uncertain reading. In the current word Chern[?], inner and final strokes are densely overwritten; earlier letters are not separable.

Original source details: GELFAND-P000100



Diagram and typed description. A straight line runs under Def. of classes and the name Chern; at right, (alg. varieties).

Original source details: GELFAND-P000100

They are giv. with fin.[?] axioms.

Original source details: GELFAND-P000100

Uncertain reading. Before axioms, a short source kon.[?] / nek.[?], corresponding to fin.[?] / some[?]; cramped middle joins do not establish letter order.

Original source details: GELFAND-P000100

Diagram and typed description. They are giv. with ... axioms.; a period at the end of the line.

[Crossed-out initial sign illegible] Functor from the category [crossed-out circled sign illegible]



Original source details: GELFAND-P000100

Uncertain reading. At left before Functor, an earlier sign with a tall left stroke is densely cancelled; after category, another sign is cancelled and enclosed by a loop. Letter readings undetermined.

Original source details: GELFAND-P000100

Diagram and typed description. Functor from the category; separate cancellations at right and left.

Algebr. sheaf, algebr. K-functor.

Original source details: GELFAND-P000100

Diagram and typed description. Algebr. sheaf, algebr. K-functor.

$A(X)$ —
— gr. of lin. equiv.
cycles



Diagram and typed description. At right $A(X)$ —; on the next line another dash before gr. of lin. equiv., with cycles below.

Original source details: GELFAND-P000100

The map $K(X) \longrightarrow A(X)$ is linear.



Diagram and typed description. The map $K(X) \longrightarrow A(X)$ is linear.; an arrow directed to the right.

Original source details: GELFAND-P000100

Axioms.

Diagram and typed description. Axioms. has a straight underline.

Original source details: GELFAND-P000100

1. [Crossed-out continuation illegible]



Uncertain reading. Final entry: 1. and a densely crossed-out line with two long transverse strokes. Below it, down to the lower edge, there are no further legible axioms.

Original source details: GELFAND-P000100

GELFAND-P000101

$18/\overline{X}$. I.M. Gelfand.

X

$E_1, \ldots, E_n$

$$\Gamma(E_1) \xrightarrow{d} \Gamma(E_2) \xrightarrow{d} \cdots \xrightarrow{d} \Gamma(E_n)$$

[Crossed out at right: Diff.[?] oper.[?]] Ell. complex.



Uncertain reading. Two densely crossed-out entries: Diff.[?] / Differ.[?] and oper.[?]. The distinct remnants do not establish all cancelled letters.

Original source details: GELFAND-P000101

$$d\big(f^m(x)s(x)\big)\big|_{x_0} = \sigma(d,\eta)s(x_0), \qquad df\big|_{x_0} = \eta$$

σ — symbol of the diff. oper.

$$0 \longrightarrow E_{1,x_0} \underset{\sigma(d,\eta)}{\longrightarrow} E_{2,x_0} \longrightarrow \cdots \overset{\sigma(d,\eta)}{\longrightarrow} E_{n,x_0} \longrightarrow 0.$$



Original source details: GELFAND-P000101

Diagram and typed description. At the first arrow between fibres, $\sigma(d,\eta)$ is below; at the last, above; zeros at both ends.

Map. $T : \Gamma(E) \longrightarrow \Gamma(E)$. $\qquad \Gamma(E_i) \longrightarrow \Gamma(E_i)$

$f : X \longrightarrow X$

φ induc.[?] bundle.



Original source details: GELFAND-P000101

Uncertain reading. Between φ and bundle, the connected source abbreviation induc.[?] / endom.[?]; the first letter is densely overwritten, with a tall middle stroke and an upper arch.





Original source details: GELFAND-P000101

Uncertain reading. Crossed-out square: upper E_i labels, with a possible added upper stroke at left; rightward and downward arrows, $X \to X$ below. Several long cancellation strokes; exact hidden indices and outlines undetermined.

$$\begin{array}{ccc} E_i & \xrightarrow{\varphi} & E_i \\ \downarrow & & \downarrow \\ X & \xrightarrow{f} & X \end{array}$$



Diagram and typed description. Upper arrow $E_i \xrightarrow{\varphi} E_i$, two downward arrows; lower arrow $X \xrightarrow{f} X$.

Original source details: GELFAND-P000101

(In the simplest cases φ determines f — — forms f determ. the map of tang. vectors)

Endom., if it commut. with d.

T is an oper. in a C^∞-space. The theorem reduces to the study of the trace (it is calc. in 2 ways)

Theorem 1. The complex has finite [crossed-out word illegible] homologies.

Uncertain reading. Between finite and homologies, a word is densely crossed out; an upper arch and a lower stroke remain. Full reading undetermined.

Original source details: GELFAND-P000101

Let ω^n be a form of ord. n on X, not taking the value 0. Use it to introduce a Hermitian structure. (Let it exist once and for all. Noninvariant, but simpler.)

$$\int \langle s, \alpha(s') \rangle = \int_X \overline{(s, s')}\, \omega.$$



Diagram and typed description. At left, angle brackets containing $s, \alpha(s')$; at right, integral over X, a bar over (s, s'), then ω.

Original source details: GELFAND-P000101

$$d^* \underset{\text{def}}{=} \alpha^{-1} \cdot d' \circ \alpha.$$



Uncertain reading. The top of the initial d is dense, with a star beside it. Below the equality, def; at right $\alpha^{-1} \cdot d' \circ \alpha$. No separate sign is securely readable inside the dense part.

Original source details: GELFAND-P000101

$s \in \Gamma(E)$, $s' \in \Gamma_c(E')$.



Uncertain reading. The lower part of the first Γ is overwritten; the second Γ has an open lower loop, read as c, possibly o-like.

Original source details: GELFAND-P000101

E' — the dual sheaf.

$$\Box \underset{\text{def}}{=} d^*d + dd^*$$

[A separate black mark below and to the left of the definition.]

Uncertain reading. A separate dense blot with small dots and slanting strokes; letter reading and purpose undetermined.

Original source details: GELFAND-P000101

(d' — simply the adjoint operator)

$\Box$ — an ellipt. operator, taking each $\Gamma(E_i)$ into itself.

$\Gamma_\lambda(E)$ — sections satisfying the eqn. $\Box s = \lambda s$. Since $\Box$ is elliptic, for $\forall \lambda$ a fin. number of distinct lin. indep. eig. functs. [dense separate sign illegible].

Uncertain reading. After eig. functs., a separate dense closed black entry with inner vertical strokes; an H-like reading is not established.

Original source details: GELFAND-P000101

$$\square d = d\square$$

$$\Gamma_\lambda(E_1) \xrightarrow{d} \Gamma_\lambda(E_2) \xrightarrow{d} \cdots \longrightarrow \Gamma_\lambda(E_n)$$

Diagram and typed description. The second closing parenthesis has a low outgoing stroke touching the next line; no separate comma established.

Original source details: GELFAND-P000101

Introduce the homology groups [below, crossed-out formula illegible].



Uncertain reading. Below homology groups, two long transverse strokes cross a short formula; upright bases and an upper slanting stroke remain. Full reading undetermined.

Original source details: GELFAND-P000101

$$H^i(\Gamma_\lambda(E)) = \operatorname{Ker} d\big|_{\Gamma_{\lambda[?]}(E_i)}$$





Uncertain reading. After the vertical bar, Γ with a dense lower sign λ[?], then (E_i); the initial Ker has a capital K.

Original source details: GELFAND-P000101



Uncertain reading. At right a slanting quotient stroke; below, densely crossed-out Im d[?], then three separate dots. The cancelled middle strokes remain unread.

Original source details: GELFAND-P000101

GELFAND-P000102

Without proof this work asserts Hodge's theorem

$$H^i(\Gamma_\lambda(E))^{*[?]} = \begin{cases} H^i(E) & \lambda = 0 \\ 0 & \lambda \neq 0. \end{cases}$$



Original source details: GELFAND-P000102

Uncertain reading. Above the right closing parentheses, a small dense star-like mark; its exact attachment to the parentheses and notation is undetermined.

Dynin. For $\lambda \neq 0$ — here 0. (d for $\lambda \neq 0$ maps eig. functs. [crossed-out word illegible] exact compl.



Original source details: GELFAND-P000102

Uncertain reading. Before exact compl., a short entry is densely crossed out. After it, exact compl.; the final source letters are cramped, with a separate arch above them. The cancelled letters remain unread.

$$H^i(\Gamma_\lambda(E)) = \mathrm{Ker}(\Box - \lambda)$$

this is Hodge's theor. $\forall \lambda$



Original source details: GELFAND-P000102

Diagram and typed description. Three sides of a frame below the formula and at both edges, open at the top. At right Ker$(\Box - \lambda)$, with an initial capital K.

(∀ ell. oper. [crossed out: illegible] $\square - \lambda$ — a new letter, again Hodge's theor....



Original source details: GELFAND-P000102

Uncertain reading. After ell. oper., a short abbreviation is densely cancelled; a question mark lies immediately below it. Full reading undetermined.



Original source details: GELFAND-P000102

Diagram and typed description. Visible opening round parentheses before d and before ∀ ell. oper.; the last line has three separate dots after Hodge. No closing parentheses read in this fragment.

Bernstein. Same. $H^i(\Gamma_\lambda(E)) = 0$, $\lambda \neq 0$. Let $s \in \Gamma_\lambda(E_i)$ and let $ds = 0$. [?] $\square s = dd^*s$. Then $\lambda s = d(d^*s)$ and $s = d\left(\frac{d^*s}{\lambda}\right)$, d^*s is an eig. funct. (d^* commut. with $\square$).

Original source details: GELFAND-P000102

Uncertain reading. Before $\square$, a tall dense stroke with a closed upper loop and a lower slanting exit: d[?] / opening parenthesis[?]. Reading undetermined.



Original source details: GELFAND-P000102

Diagram and typed description. The entry $s = d\left(\frac{d^*s}{\lambda}\right)$: a long horizontal bar passes near the base of the outer d and across the parentheses; a separate comma at right.

$d^*s \in C^\infty$ follows from the theor. on ell. eqns. Gelfand again. For $\lambda = 0$ transfer Hodge's proof literally.



Original source details: GELFAND-P000102

Diagram and typed description. Wavy lines below Dynin. and Bernstein.; a straight line below Gelfand again. In the line before the last heading, theor. and ell. are separately underlined.

$$\Gamma(E) = \sum \Gamma_\lambda(E) \qquad \text{(discr. spectrum)}$$



Original source details: GELFAND-P000102

Diagram and typed description. $\Gamma(E) = \sum \Gamma_\lambda(E)$; no separate index visible below the summation sign.

Besides the oper. T, introduce

$$\boxed{T_\lambda = \pi_\lambda \circ T \circ i_\lambda,}$$

where $i_\lambda : \Gamma_\lambda(E) \longrightarrow \Gamma(E)$, $\pi_\lambda : \Gamma(E) \longrightarrow \Gamma_\lambda(E)$ — orthog. projection.



Original source details: GELFAND-P000102

Diagram and typed description. Rectangular frame around $T_\lambda = \pi_\lambda \circ T \circ i_\lambda$; a final comma inside the frame. Below, the line with π_λ and orthog. projection; above the frame (discr. spectrum).

(oper. T in this cell) Lefschetz number for T.

T — a map of sections, thus a map of sections $\Gamma(E) \to \Gamma(E)$

$$L(T, E) = \sum (-1)^i \operatorname{tr}(T_i^* | H_i[?]).$$



Uncertain reading. After the vertical bar, an H-like letter is densely overwritten; a separate i lies at the lower right, with a dot above it. The main letter and index placement remain uncertain: $H_i[?]$ / $H^i[?]$.

Original source details: GELFAND-P000102

By Hodge's theor. $T_{\lambda=0} = T^*$.

$\Pi_0[?] = T^{*[?]}$



Uncertain reading. At left $T_{\lambda=0} = T^*$. At right, the first letter has a long top bar and a lower 0: $\Pi_0[?]$ / $\pi_0[?]$ / $T_0[?]$. Above the right T, a dense star-like entry; one or two overlapping stars cannot be distinguished securely.

Original source details: GELFAND-P000102

$$\sum(-1)^i \operatorname{tr}(T_0|E_i) = L(T,E)$$
$$\sum(-1)^i \operatorname{tr}(T_\lambda|E_i) = 0 \qquad \lambda \neq 0$$

[At right, two densely crossed-out entries illegible.]

Uncertain reading. Two small dense cancellations in the right margin: the upper one has a lower loop, the lower a long rising slanting stroke. Letter readings undetermined.

Original source details: GELFAND-P000102

(the trace in hom. is the same as the trace in the spaces themselves)
(By Hodge's theor. $H^i(E) = \Gamma_0(E_i)$)

$$\Box s = 0 \Longrightarrow \underline{ds = 0}.$$



Diagram and typed description. In $\Box s = 0 \Longrightarrow ds = 0$, a thick overwritten arrow; below $ds = 0$, a horizontal line, with a separate dot at right.

Original source details: GELFAND-P000102

(from immed.[?] def. and so on)



Uncertain reading. After from, a dense connected source abbreviation neposr. (immed.)[?] / polozh. (positive)[?]; at right def. and so on, then a closing round parenthesis. Dense overwriting above the early middle strokes.

Original source details: GELFAND-P000102

Must give meaning to $\sum(-1)^i \operatorname{tr}(T|E_i)$. Regulariz. it.
In 2 ways.



Diagram and typed description. First line: Must give meaning, the sum, and Regulariz. it at right. Below at left: In 2 ways.

Original source details: GELFAND-P000102

GELFAND-P000103

In finite $\Gamma_\lambda(E)$

$$d : \Gamma_\lambda(E_1) \longrightarrow \Gamma_\lambda(E_2) \longrightarrow \cdots$$

(finite-dimensionality) T — its map into itself. Then

$$\sum (-1)^i \operatorname{tr} T|_{E_i} = \sum (-1)^i \operatorname{tr} T|_{H_i}$$

(and $H^i = 0$)

(invar. of the Euler characteristic)



Original source details: GELFAND-P000103

Diagram and typed description. The first chain has two arrows, then an ellipsis; finite-dimensionality in parentheses. In the trace equality, E_i and H_i have subscripts after the restriction bars; the next parenthesis has $H^i = 0$ with superscript i.

Consider.

$$\sum_\lambda (1+\lambda)^{-z} \operatorname{tr}(T_\lambda | E_i) = \operatorname{tr}^z(E_i)$$

Theorem. The series conv. for $\operatorname{Re} z > \frac{1}{2} \dim X$ (on the asympt. of eig. functions) (Dunford and Schwartz, vol.2)

This is an anal. funct. of z in the half-plane.



Original source details: GELFAND-P000103

Diagram and typed description. The exponent of $(1+\lambda)$ is $-z$, with a separate short minus stroke. At right, $\operatorname{tr}^z(E_i)$. Beneath, Theorem. is underlined; $\operatorname{Re} z > \frac{1}{2} \dim X$ and two parentheses.

$$L(T, E) = \sum (-1)^i \operatorname{tr}^z E_i \qquad \forall z$$



Original source details: GELFAND-P000103

Diagram and typed description. At left, $L(T, E)$; at right the trace has superscript z, then E_i without parentheses. Farther right, a separate $\forall z$ with a dense first sign.

(everything except convergence is proved [densely overwritten sign illegible]

—



)



Uncertain reading. After proved, a dense vertical entry with a lower oblique looplike exit. Former letters remain inseparable even under enlargement; exact reading undetermined.



Original source details: GELFAND-P000103

Diagram and typed description. After the dash, a small rectangular grid of horizontal and vertical strokes. The typographic recreation shows the visible lines; dense intersections and borders are not fully distinguishable. No letter label or definite role of the grid is read.

Original source details: GELFAND-P000103

Since $T \sim$ is bounded (asympt. of eig. functions)

(on anal. cont., a pole at $z = 0$)



Diagram and typed description. After T, a separate wavy $\sim$ sign, then bounded; asympt. of eig. functions in parentheses. Beneath, a separate parenthesis: on anal. cont., a pole at $z = 0$.

Original source details: GELFAND-P000103

Example. S^1

$d = \frac{d}{dt}$, ell. oper., $\Box = \frac{d^2}{dt^2}$.



Diagram and typed description. A circle with t at right. The initial d in the first derivative's denominator is densely overwritten, followed by t; former strokes are inseparable. The entry for □ is d^2/dt^2 with a positive sign.

Original source details: GELFAND-P000103

$T = (f, \varphi)$,

$$dS(x) = s(x)$$
$$Ts(x) = \varphi(x)s(f(x))$$



Diagram and typed description. At left, $T = (f, \varphi)$ and a comma. At upper right, $dS(x) = s(x)$: the first S is uppercase, the second s lowercase. Beneath, $Ts(x) = \varphi(x)s(f(x))$.

Original source details: GELFAND-P000103

Diagram and typed description. At left beneath $T = (f, \varphi)$, a separate wavy line; below it, an almost horizontal stroke with a thickened right end. The typographic recreation preserves the general course of the lines; direction of the thickening and purpose of the sketch are undetermined. There are no axis or function labels.

Original source details: GELFAND-P000103

Definition [?] of a pseudodiff. oper.:

Uncertain reading. Between the heading and pseudodiff., a dense overwritten sign with a right vertical and several transverse strokes: P[?] / illegible. No secure letter reading established.

Original source details: GELFAND-P000103

X — manifold. $\Gamma(E), \Gamma(F)$ — 2 bundles on X

$$P : \Gamma_c(E) \longrightarrow \Gamma(F)$$

$\Gamma_c(E)$ — sections with compact support. [Crossed out: Called[?]]

Uncertain reading. Before Lin. oper. is called, a short abbreviation with a long lower oblique cancellation stroke. Source Naz.[?] (Called[?]); former letters are densely joined and not securely read. A separate period follows.

Original source details: GELFAND-P000103

A lin. oper. is called pseudodiff. if $\exists$ a seq. of numbers $n_1 > n_2 > n_3 > \cdots \to -\infty$
and satisfies the following conditions

$$e^{-i\lambda g} \underline{P}(e^{i\lambda g} s)$$

$g \in \Gamma(1)$ (C^∞ funct.), 1 — trivial sheaf, $s(x) \in \Gamma_c(E)$, $dg \neq 0$ on supp s, if there is an asympt. expansion.

GELFAND-P000104

$$\sim \sum_0^\infty P_j(s, g) \lambda^{n_j}$$



Uncertain reading. Three right-pointing signs. The first and third have dense lower ends and separate tiny traces; the middle one is overwritten and joins the following n. Separate lower equality strokes are not established: $>$[?] / $\geq$[?].

Original source details: GELFAND-P000103



Original source details: GELFAND-P000103

Diagram and typed description. The heading Definition has a straight underline. In the exponential expression, P has a short underline; exponents $-i\lambda g$ and $i\lambda g$. In parentheses, C^∞ funct. At right, $dg \neq 0$; beneath, on supp s and a comma.

Original source details: GELFAND-P000103

Uncertain reading. To the right of asympt. expansion., a short dense isolated mark: an upper loop, a horizontal exit to the right and a lower projection. Letter reading and association undetermined.



Original source details: GELFAND-P000104

Diagram and typed description. Continuation of the formula: a separate $\sim$, lower limit 0 without $j =$, upper ∞, then $P_j(s,g)\lambda^{n_j}$.

$26/\overline{X}$ Continuation. Ell. complex.



Original source details: GELFAND-P000104

Diagram and typed description. X in the date has separate over- and underlines. Continuation. has its own underline; then Ell. complex.

In E_i — a Hermitian metric, and in X — integration. Introduce oper. d^*, $\square = dd^* + d^*d$, $\square d = d\square$

$\square s = \lambda s$, $\square$ self-adj. and positive, elliptic, $\lambda > 0$. $\square s = 0 \Longrightarrow ds = 0$

$$d\Gamma_\lambda(E_i) \subset \Gamma_\lambda(E_{i+1})$$



Original source details: GELFAND-P000104

Uncertain reading. At right in $\square d = d\square$, the last square's right edge is broken and faint. Its other sides are distinguishable; the exact right boundary of the sign is damaged in the held scan. Beneath, separate entries $\lambda > 0$ and $\square s = 0 \Longrightarrow ds = 0$.

$$0 \xrightarrow{d} \Gamma(E) \xrightarrow{d} \Gamma(F) \xrightarrow{d} 0$$

d — simply an elliptic operator, $ds = 0$ — the kernel. Image $s_1 = ds_*$,



Uncertain reading. The first s has a lower sign resembling 1, possibly i. The star-like sign after the second s lies close to the baseline; its height is ambiguous: $s_1 = ds_*$ / $s_i = ds^*$ / illegible index.

Original source details: GELFAND-P000104

Homology: Ker $d|_E$, Coker $d|_F$. The Lefschetz number — the index



Diagram and typed description. All three arrows of the first chain are labelled d. Homology: has a wavy underline; Ker and Coker begin with capitals. Index has a separate straight underline.

Original source details: GELFAND-P000104

$$\Gamma_\lambda(E_i) \xrightarrow{d} \Gamma_\lambda(E_{i+1}) \longrightarrow \cdots$$

already a finite-dimensional complex, its hom. $= 0$ for $\lambda \neq 0$ and $= H^i$ [crossed out: for] [illegible phrase] for $\lambda = 0$.



Uncertain reading. After H^i, the source word при (for) is densely crossed out. Then joined loops: самое конеч.[?] (most finite.[?]) / само конеч.[?] (itself finite.[?]); the first word is not securely read. Finally, for $\lambda = 0$.

Original source details: GELFAND-P000104

T_i^* H^i

$$\sum(-1)^i \operatorname{tr}(T_i^*) = L(T, E)$$

Compute through fixed points.

T — a map of X, commutes with d.



Diagram and typed description. At left, separate T_i^* and H^i, without an arrow between them. At right, an equality with $L(T, E)$. Beneath, T — a map of X, commutes with d.; at right, Compute through fixed points.

Original source details: GELFAND-P000104

T is a map of $\Gamma_\lambda(E_i)$ Introd. operators π_λ and i_λ. inclusion of Γ_λ into all of Γ, and projection onto [crossed out: illegible entry]

$\Gamma_\lambda(E_i)$.

Uncertain reading. After onto, a short densely cancelled entry with an upper loop and transverse strokes. Former letters remain inseparable; followed by a separate active $\Gamma_\lambda(E_i)$.

Original source details: GELFAND-P000104

$$T_\lambda = \pi_\lambda \cdot T i_\lambda$$

(select the blocks corresp. to Γ_λ)



Diagram and typed description. Entries for inclusion of Γ_λ into all of Γ and projection onto $\Gamma_\lambda(E_i)$. The formula has one multiplication dot before T; no separate dot between T and i_λ. Beneath, a parenthesis about selecting blocks.

Original source details: GELFAND-P000104

Commut. unnecessary, suff. [dense overwritten sign]



in the blocks.

Uncertain reading. Between suff. and the sketch, a dense vertical entry with two dark clusters and a lower oblique exit. No letter reading established; the sign is retained separately from the blocks.

Original source details: GELFAND-P000104



Diagram and typed description. Three empty squares descend from upper left to lower right within parentheses; neighbouring corners touch. The typographic recreation preserves the three outlines and parentheses; exact sizes and dense joints remain undetermined.

Original source details: GELFAND-P000104

Then $\boxed{T^* = T_0}$

$$0 \longrightarrow \Gamma_0(E_1) \xrightarrow{d} \Gamma_0(E_2) \xrightarrow{d} \cdots$$

all $d = 0$ since $\Box s = 0$.



Diagram and typed description. The equality $T^* = T_0$ has a full rectangular frame. The first arrow from 0 is unlabelled, the next two have d; then an ellipsis. At right, all $d = 0$; beneath, since $\Box s = 0$.

Original source details: GELFAND-P000104

All homology in Γ_0

$$\Gamma(E_i) = \Gamma_0(E_i) + \quad \Gamma_{\lambda_1}(E_i) \quad + \quad \cdots$$
$$\downarrow \qquad\qquad |$$
$$\text{homol. } 0$$



Diagram and typed description. A short downward arrow beneath $\Gamma_{\lambda_1}(E_i)$; a separate vertical stroke with a dense lower end beneath the ellipsis. Beneath, homol. 0. No arrow beneath $\Gamma_0(E_i)$. A separate arrowhead on the right stroke is not established.

Original source details: GELFAND-P000104

In the 1st row [crossed out: illegible word] kernel $\Gamma_0(E_i)$



Uncertain reading. Before kernel, a short horizontal cancelled entry with dense joined strokes. No secure letter reading.

Original source details: GELFAND-P000104

$$
\begin{array}{ccccccc}
0 & \longrightarrow & \Gamma_0(E_1) & \longrightarrow & \Gamma_0(E_2) & \longrightarrow \\
 & & \| & & \| & \\
 & & H^{[?]}(E) & & H^{[?]}(E) &
\end{array}
$$



Uncertain reading. Beneath two terms of the chain, vertical double strokes and entries $H^{[?]}(E)$. Both superscripts are densely overwritten: $H^{*}(E)$ / $H^{i}(E)$ / illegible degree. Former strokes remain inseparable even under enlargement. The chain's last arrow has no visible continuation or ellipsis.

Original source details: GELFAND-P000104

Remark. π_λ commutes with d.

Diagram and typed description. Remark. has a straight underline; then π_λ commutes with d.

Original source details: GELFAND-P000104

$$
\begin{cases} \sum (-1)^i \operatorname{tr}(T_0^i) = L(T, E) \\ (-1)^i \operatorname{tr}(T_\lambda^i) = 0 \end{cases}
$$



Uncertain reading. A shared left brace. Only the first row starts with $\sum$; no separate sum is visible before $(-1)^i$ in the second row. T has superscript i in both rows; lower signs 0 and λ.

Original source details: GELFAND-P000104

GELFAND-P000105

If there is a seq. of spaces

$$0 \longrightarrow A_1 \xrightarrow{d} A_2 \xrightarrow{d} \cdots \xrightarrow{d} A_n \longrightarrow 0, \qquad d^2 = 0.$$

and maps T_i, comm. with d. Then

$$\sum_{\text{in chains}} (-1)^i \operatorname{tr} T_i = \sum_{\text{in homol.}} (-1)^i \operatorname{tr}(T_i^*) \qquad \text{(Euler's formula)}$$

(Euler's formula is obtained by taking $T = E$)



Diagram and typed description. The chain's end arrows are unlabelled, its internal arrows have d. Beneath the left sum, a separate stroke and in chains; beneath the right, a stroke and in homol. At right, a parenthesis Euler's formula.

Original source details: GELFAND-P000105

Proof: represent.

$$A_i = \underset{Z \text{ 3 summands.}}{Z} + C_Z, \qquad Z = B + \text{compl.}$$

and then consider T there.



Diagram and typed description. Proof has a straight underline; the colon is to the right of the line. Beneath the first Z, a separate entry Z 3 summands. The second entry is $Z = B +$ compl.; then and then consider T there.

Original source details: GELFAND-P000105

It suffices to replace $\operatorname{tr} T_\lambda$ by $\operatorname{tr} T_\lambda^*$, and [crossed out: illegible entry] $H_\lambda = 0$.



Uncertain reading. Before $H_\lambda = 0$, a long densely cancelled entry with loops at both ends and a horizontal stroke. Former letters remain inseparable.

Original source details: GELFAND-P000105

Introduce

$$\operatorname{tr}^z(E_i) = \sum_\lambda (1+\lambda)^{-z} \operatorname{tr}(T_\lambda^* | E_i)$$

for $\operatorname{Re} z > \frac{1}{2} \dim X$,



Diagram and typed description. The sum has subscript λ, the factor exponent $-z$, and T_λ a superscript star. The next line is for $\operatorname{Re} z > \frac{1}{2} \dim X$, followed by a comma.

Original source details: GELFAND-P000105

[At right:]

$$\lambda_n \sim n^{K/\dim X}$$



Uncertain reading. The exponent's numerator is a K-like sign with a straight left stroke and two right branches: K / κ.

Original source details: GELFAND-P000105

$$\sum(-1)^i \operatorname{tr}^z(T_i^i) = L(T,E) \qquad \text{for all } z.$$



Uncertain reading. In parentheses after tr, a dense T with a lower i-like sign and a separate upper i-like sign: T_i^i / T_i / illegible superscript.

Original source details: GELFAND-P000105

Continuation theorem (reference to Narashimhan a[?] and others.)



Uncertain reading. A Latin name with joined m/h/n-like loops and a separate final a: Narashimhan a[?] / Narasimhcan a / Narasimhana. Beneath, Nirenberg with a densely overwritten ending; then two more names.

Original source details: GELFAND-P000105

[Above and others.: katase.[?]]

Uncertain reading. A separate small entry above and others.: source катасэ. / катасэ. (katase.[?]) / illegible. The last sign resembles э; some forms also permit a Latin c.

Original source details: GELFAND-P000105

[Beneath: Nirenberg, Cohna[?], Hörmander.]

Uncertain reading. The middle Latin name between commas: Cohna / Cohn a. Between h and final a, dense joined strokes; exact separation of letters is undetermined.

Original source details: GELFAND-P000105

$\mathrm{tr}^z T^i$ extends to the whole plane, is analytic throughout the plane (!) and at $z = 0$

$$\mathrm{tr}^0(T^i) = \mathrm{tr}^{[?]}(T^i)$$

where tr^b — the trace, calc. in the usual way through generalized functions.



Diagram and typed description. The heading Continuation theorem has a wavy underline. The text twice mentions the whole plane, with a separate (!) and at $z = 0$. T has superscript i.

Original source details: GELFAND-P000105



Uncertain reading. The second tr's superscript is densely overwritten and joins surrounding strokes: b[?] / illegible. Beneath and later at left, tr^b is clearly written.

Original source details: GELFAND-P000105

$T = E$ does not work (giving $\zeta(s)$[?] with poles), but consider [Insertion beneath $T = E$:] ($\mathrm{tr}\, E = \infty$ at $z = 0$).

an oper. [illegible sign], having a finite no. of fixed points (simple).



Uncertain reading. Before (s), a large zigzag sign with a rounded lower exit: ζ[?] / Σ[?]. Beneath the line, a separate parenthesis $\mathrm{tr}\, E = \infty$ at $z = 0$.

Original source details: GELFAND-P000105



Original source details: GELFAND-P000105

Uncertain reading. After oper., a dense vertical overwritten entry with several transverse projections and lower legs; no secure letter reading. Then a comma, having a finite no. of fixed points (simple).

tr^b: T is given as a kernel, $\int \kappa(x,x)\,dx$.



Original source details: GELFAND-P000105

Uncertain reading. The kernel letter has a K-/к-like form: κ / K. A short dense sign in the integral, a taller left stroke in the two-argument formula. The handwritten height does not establish alphabet or case.

tr^b — calc. through fixed points. [Above fixed: (generalized functions).] (A version using a seq. of functions, conv.[?] to a δ-function) Some variant of the b-trace.



Original source details: GELFAND-P000105

Uncertain reading. In the parenthesis, the word before to a δ-function is densely overwritten: source сход.[?] (conv.[?]) / illegible beginning. Former strokes remain inseparable. Above the preceding fixed, a separate insertion (generalized functions).

[At right:] $\delta(x,a)$ — δ at the point a.

$$s(x) \longrightarrow \varphi s(f(x))$$

(transf.[?] of traces) $x \longrightarrow f(x)$

$$\kappa(x,y) = \delta(y\,[?]\,f(x))$$



Original source details: GELFAND-P000105

Uncertain reading. The first argument and following sign to the right of δ are densely overwritten. Readings $y - f(x)$ / $y, f(x)$ / illegible. No separate untouched minus stroke can be distinguished between the overwritten y and f.

The operator's trace $\int \kappa(x,x)\,dx$.

$$\int \delta(x, f(x))\,dx$$

— the number of fixed points; if there is φ, the trace of φ enters. Justified as usual.



Original source details: GELFAND-P000105

Diagram and typed description. At right, $\delta(x,a)$ with a comma and an entry about the point a. The lower integral $\delta(x, f(x))$ also has a comma. At left, the map with φ; at right, a parenthesis source пробр. следов (transf.[?] of traces) and a separate $x \longrightarrow f(x)$.

Next time Kazhdan will also speak.

Kazhdan 5 minutes.



Original source details: GELFAND-P000105

Diagram and typed description. The entire first phrase has a straight underline. Beneath, Kazhdan is separately underlined, followed by 5 minutes.

X — top. space, O — sheaf of rings, M — sheaf of modules. It is of finite type if $\forall x \in X\ \exists U \underset{x}{\Downarrow}$

and a fin. set of sections $f_i \in \Gamma(U, M)$, such that $\forall y \in U$, the f_i in the fibre over y generate [crossed out: illegible word] the module M_y.



Original source details: GELFAND-P000105

Diagram and typed description. Beneath U after $\exists$, a double downward arrow to x. This x is separate from y in the next line over y. The text first has $\forall x \in X$, then $\forall y \in U$.



Original source details: GELFAND-P000105

Uncertain reading. Between generate and module, a long densely cancelled word with a lower loop at left and a horizontal stroke to the right. Former letters remain inseparable.

$$f_i \in \Gamma(U, M) \qquad \exists \text{ map } O_U^n \longrightarrow M_U \qquad \text{from the set } f_i$$
$$a_1, \ldots, a_n \longrightarrow a_1 f_1 + a_2 f_2 + \cdots + a_n f_n.$$

Ker is called the sheaf of relations. Req., that $\forall$ set

GELFAND-P000106

of sections the sheaf of rel. should be of finite type.



Original source details: GELFAND-P000105

Diagram and typed description. O has superscript n and subscript U; M has subscript U. The coefficient arrow points right; at right a linear combination through $a_n f_n$ and a period. On the last line the abbreviation source Треб. (Req.) has a separate following comma; the line ends $\forall$ set.

(Insuff. for fixed sections f_i, since a point, 1, a non-Noeth. ring)



Original source details: GELFAND-P000106

Uncertain reading. Between a point, and a non-Noeth. ring, a separate 1 with a following comma. The sign has no label; its role is undetermined.

(see Serre, “Coher. alg. sheaves”)

If $N \subset M$, N — a subsheaf of fin. type, then it is coherent. (For Noeth. rings one can require less)



Original source details: GELFAND-P000106

Diagram and typed description. The page begins with the continuation of sections the sheaf of rel. should be of finite type. The reference has a comma after Serre, then quotation marks. The next assertion has a separate $N \subset M$, then N — a subsheaf of fin. type.

If in an exact seq.

$$0 \longrightarrow M' \longrightarrow M \longrightarrow M'' \longrightarrow 0$$

2 [densely crossed out: illegible word; written above: sheaves[?]] are coher., the 3rd is coher. too.



Original source details: GELFAND-P000106

Diagram and typed description. The chain has M with one prime, M without primes, and M with two primes; all four arrows are unlabelled.



Original source details: GELFAND-P000106

Uncertain reading. Above the densely cancelled entry, source пучка (sheaves)[?] / illegible. Beneath the addition, long horizontal strokes and lower loops; the former word remains inseparable.

x. The f_i gen. the module at the point x; then they gen. the module in a neighb. of the point x.



Original source details: GELFAND-P000106

Diagram and typed description. An isolated x followed by a period at the beginning. In the lower line, two separate straight strokes at neighb. and point; none beneath the last x.

S. Gelfand. Alg. def. of the K-functor. A — a (commut.) ring. $K_0(A)$. Consider left proj. modules over A and form the free group $[P]$ on them, abelian. Quotient by exact seq.

$$0 \longrightarrow P_1 \longrightarrow P \longrightarrow P_2 \longrightarrow 0$$

by the rel. $[P] - [P_1] - [P_2]$, obtaining $K_0(A)$



Original source details: GELFAND-P000106

Diagram and typed description. S. Gelfand. is separately underlined. The chain has P_1, P, P_2; the next line has $[P] - [P_1] - [P_2]$, with no $= 0$ written beside it, then obtaining $K_0(A)$.

$(P = P_1 + P_{[?]})$.



Original source details: GELFAND-P000106

Uncertain reading. The last lower sign in the parenthesis has two rounded parts and a dense lower curve: 2[?] / 3[?]. The neighbouring chain and relation have lower 2 signs with flatter ends. The final index remains undetermined.

What if one takes $E(X)$ and all modules of finite type.



Original source details: GELFAND-P000106

Uncertain reading. Before (X), a rounded E-like letter with three exits to the right: E / calligraphic E / an ε-like form. Alphabet and exact case are not established by this sign.

P — in topology, a loc. triv. bundle (sheaf of rings of cont. functions)

A proj. mod over A is loc. free in the localization at a prime ideal (all if A is commut.). A proj. mod over a loc. [crossed out: ring] is free.



Diagram and typed description. After loc., the next line has ring crossed out, then a separate is free. The parenthesis says all if A is commut.

Original source details: GELFAND-P000106

$1/\overline{XI}$ Smirnov. Positive-def. functions on a group. Describe the extreme points. (cont. representations) for groups G obtained from a nilp. alg. by introducing mult. by the Campbell — Hausdorff formula.



Diagram and typed description. XI in the date has separate over- and underlines. Smirnov. is separately underlined. Then Positive-def. functions on a group and the entry about the Campbell — Hausdorff formula.

Original source details: GELFAND-P000106

Gelfand. Again on Atiyah. $S(x) \in \Gamma(E_i)$, $\varphi(x)s(f^{-1}(x))$. This is $\int \kappa(x,y)s(y)\,dy$. For fixed y, $\kappa(x,y) \in \mathrm{Hom}(E_y, E_x)$,



Diagram and typed description. An uppercase S(x) at the beginning; lowercase s after $\varphi(x)$ and in the integral. The first f has an explicit superscript -1. Hom has lower signs y and x. The kernel letter has K-/κ-like strokes.

Original source details: GELFAND-P000106

[Densely crossed out: tr[?]] $= \int \kappa(x,x)\,dx$.



Uncertain reading. Before the equality, a dense overwritten entry: tr[?] / illegible. The upper transverse stroke and lower loops merge; former lines remain inseparable.

Original source details: GELFAND-P000106

$$\kappa(x,y) = \text{[crossed out: ?]}\,\varphi(x)\delta(y-f(x)).$$



Uncertain reading. Between the equality and $\varphi(x)$, a dense cancelled vertical sign with upper and lower loops. Exact reading undetermined. A minus stroke is visible in the following δ argument: $y - f(x)$.

Original source details: GELFAND-P000106

The operator's trace $\int \operatorname{tr}(\kappa(x,x))\,dx$.

$$\int \operatorname{tr}(\varphi(x))\delta(x-f(x))\,dx = \sum_{\rho} \frac{\operatorname{tr}\varphi(\rho)}{|1-J_\rho(f)|}.$$

(by the change-of-variables formula for the δ-function)



Uncertain reading. The sign before subscript ρ is curved, with a short upper exit and a hooked lower part: $J_\rho(f)$[?] / $D_\rho(f)$ / $Д_\rho(f)$. Two vertical outer bars. No separate det entry is visible in the denominator.

Original source details: GELFAND-P000106

Lemma from lin. algebra. C_i — lin. spaces. $d^2 = 0$. T commutes with d.

$$\begin{array}{ccccccccccc} 0 & \longrightarrow & C_1 & \xrightarrow{d} & C_2 & \xrightarrow{d} & \cdots & \xrightarrow{d} & C_n & \longrightarrow & 0 \\ & & \downarrow{\scriptstyle T_1} & & \downarrow{\scriptstyle T_2} & & & & \downarrow{\scriptstyle T_n} & & \\ 0 & \longrightarrow & C_1 & \xrightarrow{d} & C_2 & \longrightarrow & \cdots & \longrightarrow & C_n & \longrightarrow & 0 \end{array}$$



Diagram and typed description. Two horizontal chains, with 0 at their ends. The upper row has three internal d labels; the lower row has d only between C_1 and C_2. Three downward vertical marks labelled T_1, T_2, T_n. The right mark has a dense diamond-like lower end; beneath it the lower C_n is densely overwritten. The typographic recreation preserves direction and labels; dense contours remain inseparable.

Original source details: GELFAND-P000106

$$\frac{\operatorname{Ker} d|C_i}{\operatorname{Im} C_{i-1}} = H^i.$$



Diagram and typed description. The manuscript fraction bar is oblique. Above it, Ker $d|C_i$; beneath, a dense Im C_{i-1}, with no separate d or restriction bar visible after Im. At right, $= H^i$.

Original source details: GELFAND-P000106

$T_i^* : H^i \longrightarrow H^i$.

$$\sum (-1)^i \operatorname{tr} T_i = \sum (-1)^i \operatorname{tr}(T_i^*).$$



Diagram and typed description. At left, $T_i^* : H^i \longrightarrow H^i$. In the last equality both sums have superscript i on (-1); tr T_i at left, tr(T_i^*) at right.

Original source details: GELFAND-P000106

GELFAND-P000107

[Crossed out at the top: This[?] C^∞ that[?]; the rest illegible.]



Uncertain reading. A long stroke crosses the top line; dense writing beneath it on the left, C^∞ in the middle, that[?] on the right. The word boundaries and exact reading are not established.

Original source details: GELFAND-P000107

This is a finite analogue.

Applications.

1. Usual Lefschetz formula. $X \xrightarrow{f} X$ isol. sing. points. De Rham complex. [On the right:]

$$\Big(\sum \text{mult. of fixed points} =$$
$$= \sum \text{traces on cohom.}$$



Diagram and typed description. This is a finite analogue. is separate from the crossed line. Applications. is underlined. On the right an opening parenthesis precedes the sum; an equals sign ends the upper line and another begins the lower one. No closing parenthesis is visible.

Original source details: GELFAND-P000107

$$\operatorname{tr} \varphi_i(\rho) = \det -1\,;$$

(computed by eigenvalues)



Uncertain reading. After det a horizontal minus and a 1-like sign; the readings -1 / $-I$ and an illegible argument remain undistinguished. A long line below the entire expression turns upward at the right.

Original source details: GELFAND-P000107

[On the right:]

$$\sum \pm 1 \quad \text{over fixed points.}$$

$$\sum (\pm 1)\lambda_{i_1} \cdots \lambda_{i_k} \qquad J_\rho = \begin{pmatrix} \lambda_1 & & 0 \\ & \ddots & \\ 0 & & \lambda_n \end{pmatrix}$$

[A diagonal ellipsis lies between λ_1 and λ_n in the matrix.]



Diagram and typed description. The sum has a separate (± 1), then $\lambda_{i_1} \cdots \lambda_{i_k}$. On the right a J-like letter with subscript ρ; inside parentheses λ_1 at upper left, λ_n at lower right, zeros at the other corners and a diagonal ellipsis between them.

Original source details: GELFAND-P000107

2. Complex case. $f : X \longrightarrow X$ — holom.

$$\sum f_{i_1 \cdots i_k}\, dz_{i_1} \wedge \cdots \wedge dz_{i_k}$$

$f_{i_1 \cdots i_k}$ holom. and holom. diff. $H^{i,0}($



Diagram and typed description. To the right of the lines of forms a long vertical stroke downward and a horizontal stroke to the right from it; the corner has no arrows or labels. The parenthesis at $H^{i,0}($ remains open.

Original source details: GELFAND-P000107

[Densely crossed out below $H^{i,0}($: illegible.]



Uncertain reading. Below the open parenthesis dense horizontal strokes slope upward to the right; individual letters are not distinguished.

Original source details: GELFAND-P000107

$$\sum (-1)^i \frac{\operatorname{tr} \varphi(E_i)}{|(1 - J(f))|^2} =$$

[Crossed out: $\sum_\rho \operatorname{Re}($; followed by:]

$$\sum_\rho \operatorname{Re}\left(\frac{2}{1 - J_f}\right)$$



Uncertain reading. The vertical strokes at the denominator are thickened: absolute value / double bars. Inside, a J-like letter / handwritten Cyrillic D; the numerator of the active sum on the right is 2, with two close horizontal lines below it.

Original source details: GELFAND-P000107





Uncertain reading. Two intersecting lines, arrows upward and to the right; the horizontal line continues beyond the arrowhead. In an oval $z \to a_1 z$, separately a circled a, below it $|a|^2$. Above the vertical line crossed a-like signs with illegible lower strokes; the exact reading of this writing is not established.

Original source details: GELFAND-P000107

When the transf. ‖ is fractional-linear, this is the fixed-point theorem.



Original source details: GELFAND-P000107

Diagram and typed description. Two vertical lines stand between transf. and fractional-linear. The final words fixed point. are on the next line.

$$= \frac{1}{[?]} \left(\frac{1}{\overline{\overline{1 - J(f)}}} + \frac{1}{1 - J(f)} \right)$$



Uncertain reading. Below the first separate 1 a dense sign: 2[?] / 1[?] / illegible. The first inner fraction has two long horizontal lines, the second one; the first extra line may indicate conjugation of the fraction or denominator.

Original source details: GELFAND-P000107

The real trace, is [crossed out: illegible] the sum of the complex and complex-conjugate traces.



Original source details: GELFAND-P000107

Uncertain reading. Between is and the sum a densely crossed horizontal record with a vertical stroke at the right; individual letters are not distinguished.

Appl. also to [heavily overwritten: illegible] fractional-linear transf. of projective space.



Original source details: GELFAND-P000107

Uncertain reading. After also to two dense superposed signs. Under the abbreviation for space two separate short lines; the preceding overwritten writing is illegible.

Kazhdan. Definition of homology of anything.



Original source details: GELFAND-P000107

Diagram and typed description. The surname and three parts of the heading have separate underlines. The Russian words for of anything are joined by a hyphen.

C — an abelian category. an object Q is called injective if the functor $F(A) = \mathrm{Hom}(A, Q)$ is exact. ($A' \subset A \; \forall f$ [crossed out: an illegible word] extends)





Original source details: GELFAND-P000107

Diagram and typed description. Within the parentheses $A' \subset A$; from A' an arrow downward to the right labelled f, from A downward to Q an arrow with φ at the right. There is no superscript at $F(A)$.



Original source details: GELFAND-P000107

Uncertain reading. After $\forall f$ above extends a densely crossed word; its letters are not separated.

The categ. has enough injective objects if $\forall A\ \exists$ inj. $Q \parallel 0 \longrightarrow A \longrightarrow Q$. [cat. of sheaves]



Original source details: GELFAND-P000107

Diagram and typed description. Before $0 \to A \to Q$ two vertical lines, with the lower part thickened. On the right a separate record in square brackets cat. of sheaves.

Let there be [crossed out: illegible] a functor $F(A)\ C \xrightarrow{F} C'$ covar. and left exact, i.e.

$$0 \longrightarrow A \longrightarrow B \longrightarrow \underbrace{C \longrightarrow 0}_{\text{may also be left out.}} \Longrightarrow 0 \longrightarrow F(A) \longrightarrow F(B) \longrightarrow F(C)$$



Original source details: GELFAND-P000107

Uncertain reading. Between there be and a functor a small densely crossed record, with a downward projecting stroke; the exact reading is not established.



Original source details: GELFAND-P000107

Diagram and typed description. F above the arrow at $C \to C'$. Beneath $C \to 0$ in the original sequence an arc with may also be left out. In the sequence after the large arrow the last visible term is $F(C)$, followed by no dot or zero.

and C has enough inj. obj. Derived functors (they $\exists$ and are unique) — functors from cat. C to C', satisfying the conditions:

1) $F^0(A) = F(A)$

2) $F^{[?]}(Q) = 0\ (i > 0)\ \forall$ injective Q



Original source details: GELFAND-P000107

Uncertain reading. In condition 1 the superscript is 0. In condition 2 the superscript above F is filled in, with a small upward projection: i[?] / 0[?] / illegible; separately $(i > 0)$ at the right.

3) $\forall$ exact seq. $0 \longrightarrow A \longrightarrow B \longrightarrow C \longrightarrow 0$ there is an exact seq.

$$0 \longrightarrow F^0(A) \longrightarrow F^0(B) \longrightarrow F^0(C) \xrightarrow{\delta} F^1(A) \longrightarrow F^1(B) \xrightarrow{\delta}$$



Original source details: GELFAND-P000107

Diagram and typed description. At the bottom the sequence begins 0, then three terms with superscript 0, then an arrow with δ, two terms with superscript 1 and another arrow with δ.



Undeciphered passage. The last arrow is at the right edge; the following term is not visible in this frame.

Original source details: GELFAND-P000107

[Above the final arrows: induced[?] with a stroke continuing to the right.]



Uncertain reading. The readings are induc.[?] / induc...[?]; the ending merges into a long rightward stroke ending beside the last δ. The precise attachment of the stroke is not established.

Original source details: GELFAND-P000107

GELFAND-P000108

Moreover 3') Let there be another exact seq. and a map.

$$\begin{array}{ccccccccc} 0 & \longrightarrow & A' & \longrightarrow & B' & \longrightarrow & C' & \longrightarrow & 0 \\ & & \downarrow & & \downarrow & & \downarrow & & \\ 0 & \longrightarrow & A & \longrightarrow & B & \longrightarrow & C & \longrightarrow & 0 \end{array}$$



Diagram and typed description. Two rows $0 \to A' \to B' \to C' \to 0$ and $0 \to A \to B \to C \to 0$; three vertical arrows downward from the primed letters. The arrows have no labels.

Original source details: GELFAND-P000108

$$\begin{array}{ccc} F^0(A) & \xrightarrow{\delta} & F^1(A) \\ \uparrow & & \uparrow \\ F^0(C') & \xrightarrow{\delta} & F^1(A') \end{array}$$



Uncertain reading. At upper left $F^0(A)$: the two slanting sides and crossbar of A are visible. At upper right $F^1(A)$, below $F^0(C')$ and $F^1(A')$; both vertical arrows point upward.

Original source details: GELFAND-P000108

Theorem: If A has enough inj. obj., the derived functors exist and are unique.



Original source details: GELFAND-P000108

Diagram and typed description. A separate large A in the hypothesis. Theorem is underlined, with the colon to the right of the line. Exist and are unique continues the writing on the next line.

15/XI Matsaev Complete proof of the Atiyah-Bott theorem.



Original source details: GELFAND-P000108

Diagram and typed description. XI has lines above and below. A straight underline below the surname; a wavy underline below Complete proof of the Atiyah-Bott theorem.

$$\cdots \longrightarrow \Gamma(E_i) \xrightarrow{d} \Gamma(E_{i+1}) \longrightarrow \cdots$$

Given T, acting on Γ and commuting with d, T_i^*,



Original source details: GELFAND-P000108

Diagram and typed description. d above the middle arrow of the complex, subscript $i+1$ on the right. On the next line T_i^*, followed by a comma.

[Densely crossed out: an illegible sign; to the right a T-like sign[?].]



Original source details: GELFAND-P000108

Uncertain reading. Dense crossed writing slopes upward to the right; farther right a separate small sign with a horizontal top and slanting stem: T[?] / illegible.

$$L(T, E) = \sum (-1)^i \operatorname{tr} T_i^*$$

[On the right:] (Here we do not need z — does not depend)



Original source details: GELFAND-P000108

Diagram and typed description. T in the sum has a superscript star and subscript i. In the right parenthesis z, then we do not need, below — does not depend.

$$\sum_i \sigma(\rho) \qquad \sigma(\rho) = \sum \frac{(-1)^i \operatorname{Sp} \varphi_i(\rho)}{|\det(1 - I_f(\rho))|}$$



Uncertain reading. Beneath the first sum a small sign with a separate dot above: i[?] / illegible index. In the denominator an I-like letter with a wide base / a J-like letter; followed by subscript f and (ρ).

Original source details: GELFAND-P000108

The formal proof is trivial, since

$$L = \sum_i (-1)^i \operatorname{tr} T_i$$

(elem. theorem of lin. algebra) $\operatorname{tr} T_i$ formally give this sum. T_i is given by the kernel $\varphi\delta(y - f(x))$. The trace is precisely $\sum$ over fixed points.



Diagram and typed description. In the formal sum T has subscript i without a star. In the kernel a horizontal minus follows y, then $f(x)$. Fixed points. is carried to the next line.

Original source details: GELFAND-P000108

Smooth by the kernel

$$(1 + \square)^{-z} T_i = T_{i,z}, \qquad \square = d\delta + \delta d$$

(assume a Riem. metric is given, Herm. adjoint oper.) [Crossed out: $(1 + \square)^{-z}$.] The trace already exists in the usual sense.



Diagram and typed description. Exponent $-z$; a comma in the right-hand $T_{i,z}$. A separate formula with a square, d and δ. Below, a crossed copy of $(1 + \square)^{-z}$.

Original source details: GELFAND-P000108

$$\operatorname{tr} T_{iz} = \sum_\lambda \pi_\lambda T i_\lambda (1 + \lambda)^{-z}$$

Uncertain reading. The indices of the left-hand T are densely overwritten: iz / i,z. On the right π_λ, T, i_λ and $(1 + \lambda)^{-z}$; no separate tr is visible after the sum.

Original source details: GELFAND-P000108

$\sum_i (-1)^i \operatorname{tr} T_{iz}$ continues to the whole plane and at $z = 0$ is an integral as a number.



Diagram and typed description. Subscript i in the sum; after the whole plane and, the continuation at $z = 0$ is an integral as a number.

Original source details: GELFAND-P000108

$$T_{iz} = \underbrace{(1+\square)^{-z}}_{\text{it is given by an integral kernel for sufficiently large } \operatorname{Re} z} T_i$$



Original source details: GELFAND-P000108

Diagram and typed description. Beneath $(1+\square)^{-z}$ a straight bracket with a short downward stroke; the explanation below it ends in Re z.

and this kernel is arranged as follows: [crossed out: an illegible word]



Original source details: GELFAND-P000108

Uncertain reading. After arranged as follows: two dense, almost horizontal crossing strokes; the original letters are not separated.



Original source details: GELFAND-P000108

Uncertain reading. An unlabelled square; the diagonal goes from upper left to lower right, thickening at the latter corner. Thickening / arrowhead[?]; it has no separate label.

off the diag. the kernel is C^∞, and on the diag. breaks in the derivative (contr.[?] to Katz and Narasimhan)



Original source details: GELFAND-P000108

Uncertain reading. In parentheses the abbreviation contr.[?] with a dense ending, then to Katz and Narasimhan. Before the parenthesis derivative.

The discussion concerns $(1+\square)^{-z}$ (without T_i).



Original source details: GELFAND-P000108

Diagram and typed description. The final parenthesis reads without T_i. A separate $(1+\square)^{-z}$ precedes it.

$$\mu_1(x)(1+\Box)^{-z}\mu_2(x)$$

is already given by a C^∞ kernel if supp[?] μ_1 μ_2 at the edges.



Uncertain reading. The outer letters μ_1, μ_2 / M_1, M_2; the first sign is more angular. After if, supp[?] / diff.[?] / illegible; below, at the edges. The precise separator between the two letters after the abbreviation is not distinguished.

Original source details: GELFAND-P000108

GELFAND-P000109

Diagram and typed description. An empty quadrilateral in the upper-left margin; no diagonal or labels. The side ends do not join at lower right; a small gap also at upper left.

Original source details: GELFAND-P000109

When can one correctly multiply two generalized fn.s with singularities on two transversal manifolds.



Diagram and typed description. The writing starts When and ends manifolds. There is no question mark at the end.

Original source details: GELFAND-P000109

μ_1, μ_2 [crossed out: illegible]

$\cap$ supp. off the curve[?], then [crossed out: illegible]

the fn. is given by a fn.



Uncertain reading. Between μ_1, μ_2 and $\cap$ a short densely crossed record. The first μ has an angular top and a long lower stroke.

Original source details: GELFAND-P000109



Original source details: GELFAND-P000109

Uncertain reading. After then and before fn., dense crossed writing; the original signs are not separated.



Original source details: GELFAND-P000109

Uncertain reading. Off the curve[?] / off the straight line: the initial letter of the final word is dense, the next has a long lower stroke.

Suff. condition: each of them is a smooth δ-fn., and to it is applied an operator $P\delta_S$, if P is pseudodiff. (for example, simply diff.)



Original source details: GELFAND-P000109

Diagram and typed description. A wavy underline below Suff. condition. After operator, a separate $P\delta_S$; then if P is pseudodiff. The parenthesis ends simply diff.)

To it one can apply [densely crossed out: an illegible sign]

a pseudodiff. operator.



Original source details: GELFAND-P000109

Uncertain reading. Between apply and pseudodiff., a short dense sign with a lower slanting stroke.

A smooth fn. on a manifold — $\int$ over the manifold. This is a cont. oper. on C^∞ fn.s and therefore on generalized fn.s. One must approximate the δ-fn.s by C^∞ fn.s in a special way, then the product will have a limit.



Original source details: GELFAND-P000109

Diagram and typed description. After the dash a separate integral sign without limits. Then two sentences on the cont. oper. and approximation of δ-fn.s; ending in limit.

$$\delta(x_1) \cdot \delta(x_2) = \delta(x_1, x_2)$$



Original source details: GELFAND-P000109

Diagram and typed description. A dot between the first two factors; on the right $\delta(x_1, x_2)$ without a separate final period.



Original source details: GELFAND-P000109

Uncertain reading. Intersecting vertical and horizontal lines without labels. To the right of the intersection a short thickening and slanted stroke: arrowhead[?] / unevenness of the line. No separately marked point.

(supp. in 4-dim. space transvers. intersect. of diag.)



Original source details: GELFAND-P000109

Diagram and typed description. The parenthesis below the formula: supp. in 4-dim. space transvers. intersect. of diag.

Kazhdan. X_P — an open set in the Zariski top. $P \neq 0$.



Original source details: GELFAND-P000109

Diagram and typed description. The surname Kazhdan. is underlined. Then X_P, on the right $P \neq 0$.

[On the left, crossed out: an illegible word.]



Original source details: GELFAND-P000109

Uncertain reading. Below the underlined surname and to the left of This is a basis, several dense crossing strokes.

This is a basis of open sets on an aff. alg. variety. Sect. of the sheaf on X_P: $R(x)$: $\frac{Q(x)}{P^n}$,

[A short sign crossed out: =[?] / illegible.]

they are identified if the diff. becomes 0 on the variety.



Original source details: GELFAND-P000109

Diagram and typed description. Colons after X_P and after $R(x)$. Numerator $Q(x)$, denominator P^n; a comma on the right.

Original source details: GELFAND-P000109

Uncertain reading. Before they, a short dark sign with two almost horizontal strokes; original sign =[?].

$\Gamma(X_P, O_X)$. Aff. alg. variety — a finite number of eq.s. X_P is again an aff. space.



Original source details: GELFAND-P000109

Diagram and typed description. A period after $\Gamma(X_P, O_X)$. The final line reads precisely again an aff. space.

An algebraic sheaf — a sheaf of modules over this sheaf of rings. Of finite type — loc. isom. to a quotient of a direct sum.



Original source details: GELFAND-P000109

Diagram and typed description. Two lines: the definition of an algebraic sheaf and Of finite type — loc. isom. to a quotient of a direct sum.

A coher. sheaf — further ∀ [crossed out: illegible] open set and ∀ finite coll. of sections, the sheaf of rel.s is of finite type.



Original source details: GELFAND-P000109

Uncertain reading. After the first ∀ a densely crossed word. Then open set and ∀ finite coll.; continuation on the next line of sections, the sheaf of rel.s is of finite type.

Theorem: the sheaf O itself is coherent.

Original source details: GELFAND-P000109

Diagram and typed description. Theorem is underlined, with the colon to the right. After the sheaf a separate O, then itself is coherent.

First for the whole aff. [crossed out: variety[?] / illegible.] [Inserted above: space.] From this everything follows autom.



Original source details: GELFAND-P000109

Uncertain reading. Beneath the insertion space, a crossed record variety[?]. After it a period; From this everything follows continues on the same line, autom. below.

X_P — an open set. Consider a finite collection of sections

$$\left(\frac{Q_1}{P^n}, \frac{Q_2}{P^n}, \ldots, \frac{Q_i}{P^n}\right)$$

Sheaf of relations:



Original source details: GELFAND-P000109

Diagram and typed description. The tuple has subscripts $1, 2, \ldots, i$, denominators P^n; no separate period after the parenthesis. On the right Sheaf of relations:

Ring $A = k[x_1, \ldots, x_n]$. [On the right again: Sheaf of relations]



Original source details: GELFAND-P000109

Diagram and typed description. Ring $A = k[x_1, \ldots, x_n]$ with a final period. On the right Sheaf of relations is repeated without a final sign.

$$O_X + O_X + \cdots + O_X \underset{\text{over } X_P}{\longrightarrow} O_X$$



Original source details: GELFAND-P000109

Diagram and typed description. Everywhere O_X; plus signs between the initial summands. Beneath the rightward arrow over X_P.

$$d_{3[?]}\, d_2 \cdots d_i \longrightarrow \frac{d_1 Q_1}{P^n} + \frac{d_2 Q_2}{P^n} + \cdots + \frac{d_i Q_i}{P^n}$$



Original source details: GELFAND-P000109

Uncertain reading. The first lower index on the left resembles 3 / 1; its lower end is very dense. The first d on the right has index 1. Then on the left d_2, ellipsis and d_i; no period at the end of the formula.

Kernel — the fibre of the sheaf of rel.s over a point

Original source details: GELFAND-P000109

Diagram and typed description. The final line reads fibre, then of the sheaf of rel.s over a point. No separate final sign after the last word.

GELFAND-P000110

Consider the following map:

$$A + A + A + \cdots + A \longrightarrow A$$



Original source details: GELFAND-P000110

Diagram and typed description. A colon after map; no labels on the rightward arrow. No separate period after the final A.

One can dispense with P, the rel.s are the same, Kernel — a submodule, A is Noetherian, $d_1 \cdots d_i$ and generate [crossed out: an illegible sign] the sheaf of rel.s over any point (Hilbert's theorem)



Original source details: GELFAND-P000110

Uncertain reading. On the left before the sheaf of rel.s, a short crossed sign. On the preceding line d_1, ellipsis, d_i and generate; the right end of the last word reaches the image edge.

[The whole line crossed out: From coher. of the ring it follows that every sheaf is coher., then[?]; individual portions illegible.]



Original source details: GELFAND-P000110

Uncertain reading. Long strokes cross the whole line. The reading From coher. of the ring it follows that every sheaf is coher., then is partial; exact letters beneath the dense portions are not established.

From this autom. follows coher. of the sheaf $\forall$ aff. variety. $Y \subset X$, Y is closed, O_X is on X, J_Y[?] — the sheaf of ideals ($= 0$ on Y).



Original source details: GELFAND-P000110

Diagram and typed description. A separate $\forall$ after coher. of the sheaf. On the next line $Y \subset X$, then Y is closed.

The sheaf on Y by def. $O_X/J_Y = O_Y$. O_Y is also coher., since the kernel J_Y is a coher. sheaf. The struct. sheaf on any alg. variety is coherent.



Original source details: GELFAND-P000110

Uncertain reading. The ideal letter J[?] / I-like: a curved stroke at the top, a dense loop below. In the formula a slash between O_X and this letter with subscript Y; on the right $= O_Y$. After kernel on the next line the same letter.

Properties of the ring of sections of the sheaf A.



Original source details: GELFAND-P000110

Diagram and typed description. The whole line Properties of the ring of sections of the sheaf A. has a wavy underline.

From this the cohomology of any coher. sheaf on an aff. variety is trivial. (From this one can compute cohom. using an aff. cover — — and conversely — Chevalley's theorem $H^i = 0 \Longrightarrow$



Original source details: GELFAND-P000110

Undeciphered passage. After $H^i = 0$ a double arrow pointing right; there is no continuation to its right. The parenthesis opened before the second From this is not closed.

$$A = k[x_1, \ldots, x_n].$$

Hilbert's theorem on zeros: J is an ideal, P is a polynomial vanishing on the corresp. alg. variety, then $P^k \in J$



Original source details: GELFAND-P000110

Diagram and typed description. A final period after the ring $A = k[x_1, \ldots, x_n]$. A colon after Hilbert's theorem on zeros. P has exponent k; no separate period after J.

Corollary. A is the ring of sections for any aff. variety.



Original source details: GELFAND-P000110

Diagram and typed description. A wavy underline beneath Corollary. Then A is the ring of sections for any aff. variety.

Glob. sect. on the whole [crossed out: illegible] aff. space — polyn.[?] on the whole space.



Original source details: GELFAND-P000110

Uncertain reading. Between whole and aff., a short crossed record; its lower-right end forms a loop.



Original source details: GELFAND-P000110

Uncertain reading. After the dash the abbreviation mnog.[?] / mnozh.; the final sign joins the preceding one closely. Polyn.[?] is a tentative reading; the abbreviation is not expanded.

Theor. Any sheaf on an aff. variety [dense sign: illegible] is generated by sect. and its cohom. in higher dim. is triv.



Original source details: GELFAND-P000110

Uncertain reading. Between variety and is generated, a separate dense sign with a lower stroke. No word coher. is visible before sheaf in this line.

Lemma 1. X — a variety (affine), P — a polyn., $X_P = \{P \neq 0\}$.



Original source details: GELFAND-P000110

Diagram and typed description. Lemma 1. has a straight underline. Affine is in parentheses. On the right $X_P = \{P \neq 0\}$.

A coher. sheaf over X, [crossed out: vanishing on X_P[?].] [Separately crossed out on the right: illegible.]

and there is a section s vanishing on X_P. Then $\exists m$ such that $P^m s = 0$. This is an easy reformulation of Hilbert's theorem.



Original source details: GELFAND-P000110

Uncertain reading. After sheaf, long crossing strokes; portions of vanishing, on X_P[?] are distinguished. Farther right a separate densely crossed record.



Original source details: GELFAND-P000110

Diagram and typed description. The uncanceled line and there is a section s vanishing on X_P. Then $\exists m$ such that $P^m s = 0$.

Let X be the aff. line

Original source details: GELFAND-P000110

Uncertain reading. A horizontal line with a marked point; no label at the point. At the left end a short downward slant: left arrowhead[?] / bend in the line. No arrowhead is visible on the right.

$k[x]$ — germs of polyn.s vanishing at the point 0, quotient — one-dim.



Original source details: GELFAND-P000110

Diagram and typed description. To the right of the drawing $k[x]$ — germs; on the next line of polyn.s vanishing at the point 0, quotient — one-dim.

Examination in hom. algebra — following Grothendieck. — class test.



Original source details: GELFAND-P000110

Diagram and typed description. The wavy underline runs from Examination to Grothendieck. After it class, and test. is carried below without an underline.

Lemma 2. $F \subset O_X^{n[?]}$ — direct $\sum$. [Below, with an insertion sign: subsheaf.]



Original source details: GELFAND-P000110

Uncertain reading. After direct, a separate $\sum$ / Σ with a period to the right. The superscript of O_X is n[?] / m-like; the small upper strokes merge. Subsheaf is inserted beneath F.

Let there be a section s defined on X_P. Then for large m, $P^m s$ extends to the whole X.



Original source details: GELFAND-P000110

Diagram and typed description. The section s is defined on X_P. On the last line $P^m s$ extends to the whole X. A final period is visible.

GELFAND-P000111

(also Hilbert's theorem).

$$\left(\frac{O_1[?]}{p^k}, \ldots, \frac{O_i[?]}{p^k}\right)$$

mult. by p^k, but this may not be a sect. of O_X^n.



Original source details: GELFAND-P000111

Uncertain reading. Rounded O-like signs in the numerators, with lower 1 and i; their lower portions join the fraction bars. Readings O / Q are not fully distinguished. Beneath, O_X^n and O_X^n/F.

$O_X^n/F \longrightarrow 0$ already nepr.[?]



Original source details: GELFAND-P000111

Uncertain reading. After already, a short joined entry source непр.[?] (nepr.[?]); its middle and final strokes merge densely. The abbreviation is not expanded. Before already, an arrow to a separate 0.

Now it already suffices for the proof that the cohom. of $F \subset O_X^n$ are zeros. X — an aff. variety, $(X_{p_1}, X_{p_2}, \ldots, X_{p_i})$ a cover. The cohomology of X with coefficients in F in this cover are zeros.

$22/\overline{XI}$. I.M. Gelfand. [Crossed out: an illegible entry.] Bott, Chern Acta Math., 1965, 114 $N = 1$–2.

Original source details: GELFAND-P000111

Uncertain reading. Before Bott, a densely canceled entry with a Cyrillic Б-like beginning; its former letters are not established. A separate comma follows the cancellation.

Theories of Nevanlinna for several variables.



Original source details: GELFAND-P000111

Diagram and typed description. XI has separate over- and underlines; the surname with initials has a straight underline. The heading Theories of Nevanlinna for several variables. has a long wavy underline.

Picard's theorem, the more precise theorem of Nevanlinna: one can estimate the number of zeros in a circle of radius R (may be less). R_a — where it takes a.



Original source details: GELFAND-P000111

Diagram and typed description. Before the lower a, a large R-like letter with a slanting right leg. At right, a dash and where it takes a.

Most values are taken equ. often. Defect — if not taken, then 1; if less often, then a numer. char. The $\sum$ of defects does not exceed two. $\frac{a(z)}{b(z)}$ omits at most 2 values. $(a(z), b(z))$ a merom. fn. — a curve in C^2, a value — a line (only the ratio matters). This curve intersects all lines except, perhaps, two. Generalization. In 3-dim. space an entire curve $(a(z), b(z), c(z))$ intersects all planes passing through 0, except, perhaps, three. (In n-dim. a finite number.)

For us this? $-y'' + p(x)y = \lambda y$ — an eqn. on the int. $[0, \pi]$ with conditions [At right:] $y(0) = 0$, $y'(0) = 0$.

[Crossed out: an illegible short sign.] λ [ne sushch.; abbreviation unexpanded], $y(0) = y(\pi) = 0 \Rightarrow$ a countable number of eig. values.



Original source details: GELFAND-P000111

Uncertain reading. The right endpoint of the interval and the argument in the second entry $y(0) = y(\pi) = 0$ are densely overwritten. The current sign has π-like strokes; the former entry is not established.



Original source details: GELFAND-P000111

Diagram and typed description. Two separate lines in the upper right field: $y(0) = 0$ and $y'(0) = 0$. Both final signs are oval, with a white centre.



Original source details: GELFAND-P000111

Uncertain reading. Written source не сущ. (ne sushch.), with a period and following comma. The expansion of this abbreviation is not established on this line.

Original source details: GELFAND-P000111

Uncertain reading. Immediately before λ, a short dense cancellation with a loop on the left and horizontal strokes. The former sign is unread.

Possibly, for most boundary conditions there is an eigenvalue $y(0) = 0$, $ay'(\pi) + by(\pi) = 0$. Consider the solution

$$\begin{cases} y(0,\lambda) = 0 \\ y'(0,\lambda) = 1. \end{cases}$$

It is analytic in λ.



Diagram and typed description. Two lines $y(0,\lambda) = 0$, $y'(0,\lambda) = 1$.. Below them a horizontal line turns upward vertically at right. To the left of the second line a separate short curved stroke, unconnected to the lower line.

Original source details: GELFAND-P000111

Eig. values — when $ay'(\pi,\lambda) + by(\pi,\lambda) = 0$ has a nonzero solution. An analytic curve intersects almost[?] all [crossed out: an illegible word], lines, and by Picard's theorem even infinitely many. (At most one)



Uncertain reading. Before all, a densely joined word: source почти (almost) / наши (our); its middle strokes are not fully distinguished. After all a long crossed-out entry; active lines follows at right. The next line ends (At most one).

Original source details: GELFAND-P000111

How from general considerations do we obtain completeness (a curve in a function space) — this has not been done. One must prove a theorem in a Banach space — an analytic curve in a Banach space (possibly, false) [Crossed out: an illegible entry.] does not pass through a finite number of hyperplanes.



Uncertain reading. Before does not pass, a separate dense cancellation with a long downward stroke. The former letters are not separated.

Original source details: GELFAND-P000111

$$ay'(\pi,\lambda) - by(\pi,\lambda) = 0.$$



Diagram and typed description. In the last formula a separate horizontal minus stroke between ay' and by. The derivative stroke at y' is visible; both arguments are (π,λ).

Original source details: GELFAND-P000111

GELFAND-P000112

The points into which it falls must be poln.[?]



Uncertain reading. The line ends poln.[?] / polny; the middle strokes are densely joined, with a separate dot at the right. The ending is not established.

Original source details: GELFAND-P000112

What is to be done for several complex variables? All these are examples of sl.[?] analytic sheaves (in these terms both Borel's theorem and G. Weyl's theorem are formulated).



Original source details: GELFAND-P000112

Uncertain reading. Before analytic there is a short sl.-like entry with a dense right stroke and a dot. The abbreviation is unexpanded.

There is no satisfactory theory analogous to Nevanlinna's theorems. Distribution of the zeros of n functions of n variables — ?

§ 2. Characteristic classes (Chern classes)



Original source details: GELFAND-P000112

Diagram and typed description. At the left are § and a separate 2 with a dot. No underline is visible below the heading. At the right, (Chern classes).

X — manifold, E — vector bundle, $T = T(X)$ — [Crossed out: unreadable entry.] tangent bundle.

Original source details: GELFAND-P000112

Uncertain reading. Before the abbreviation for tangent a short prefix is densely crossed out; its individual earlier letters are not established.

$A^i(X)$ — sheaf of differential forms of order i. $\sum A^i(X) = A(X)$ — a ring. d — differential in $A(X)$, $A(X, E)$ — sheaf of differential forms on X with values in E.

$$A(X, E) = A(X) \otimes_{A^{0[?]}(E)} \Gamma(E).$$



Original source details: GELFAND-P000112

Uncertain reading. Below the first tensor sign, $A^{0[?]}(E)$: above A is a round mark with a small opening, 0 / i; in parentheses an E-like letter. Below the next tensor sign, a separate $A^0(X)$.

Notation.

$$\Gamma(E) \otimes_{A^0(X)} \Gamma(F) \longrightarrow \Gamma(E \otimes F)$$

— this multiplication is denoted simply by a dot. E — vector bundle over X. Definition. A connection on E is a differential operator D on $\Gamma(E)$ satisfying the requirement:

$$D : \Gamma(E) \longrightarrow \Gamma(T^* \otimes E), \qquad D(fs) = df \cdot s + f \cdot Ds, \quad s \in \Gamma(E),\ f \in A^0(X).$$



Original source details: GELFAND-P000112

Uncertain reading. In the underlined Definition. the middle letters are densely overwritten; the earlier strokes have not been read separately.

T^* — kokas.[?] (!)



Original source details: GELFAND-P000112

Uncertain reading. After T^*, a short entry kokas. / konas.; the second consonant is densely joined to neighbouring strokes. A separate (!) is at the right.

Introduce local coordinates $\{s_i(x)\}$ in a neighbourhood U — linear frames at each point x.



Original source details: GELFAND-P000112

Diagram and typed description. Before the brace the words local coordinates are written; after the brace, linear frames. The handwritten word koordinat has a long upper arc at d and a separate final stroke.

$$Ds_i = \sum_{j=1}^{n} \theta_{ij} s_j.$$

θ_{ij} — connection matrix $\theta(s, D)$. Its values — differential forms.

$$K(s, D) = d\theta(s, D) - \theta(s, D) \wedge \theta(s, D).$$



Original source details: GELFAND-P000112

Diagram and typed description. After the first $\theta(s, D)$ is a separate horizontal minus stroke; between the following matrices is $\wedge$.

Not 0, since this is a product of matrices

$$\sum_{l} \theta_{il}(s, D) \wedge \theta_{lj}(s, D).$$



Original source details: GELFAND-P000112

Diagram and typed description. Below the sum is a separate l; the first θ has lower i, l, the second lower l, j. Both factors have arguments (s, D).

This exterior 2-form is called the curvature. 2-forms commute with one another, so a det of forms makes sense. The characteristic classes are called

$$C(E, D[?]) = \mathrm{Det}\left(1 + \frac{2\pi}{i} K(s, D)\right).$$



Original source details: GELFAND-P000112

Uncertain reading. In $C(E, D[?])$ the second argument is pale and round, with a dense left stroke; D / a C-like letter.



Original source details: GELFAND-P000112

Diagram and typed description. In the fraction 2π is above the bar and i below; before the fraction is a plus, and at the right $K(s, D)$.

These are closed 2-forms. [At the right:] Forms of different orders — and a collection of characteristic classes.



Original source details: GELFAND-P000112

Diagram and typed description. The bottom line literally has 2-forms. A separate entry in the right margin: Forms of different orders — and a collection of characteristic classes.

GELFAND-P000113

73

Prove that C does not depend on the choice of basis and is a closed form; in fact it does not depend on the choice of connection either. Independence of the choice of basis.

$$\begin{aligned} s'_i = \sum A_{ij} s_j, \qquad s' &= As; \\ Ds' &= dA \cdot s + A\theta(s, D)s, \\ Ds' &= \theta(s', D)s', \\ dA + A\theta(s, D) &= \theta(s', D)A. \end{aligned}$$

Substitute this into the definition of K.

$$\boxed{AK(s, D) = K(s', D)A}$$

$$dA \cdot \theta(s, D) + Ad\theta(s, D) = d\theta(s, D)A + \theta(s', D)dA.$$



Original source details: GELFAND-P000113

Uncertain reading. In the first $d\theta$ on the right the argument is s without a separate prime. In the next θ the argument is s' with a prime.

Original source details: GELFAND-P000113

Diagram and typed description. On the right between $d\theta(s, D)A$ and $\theta(s', D)dA$ is a separate plus with intersecting horizontal and vertical strokes.

"$A^{-1}KA^{+1}$[?]" the same det.



Original source details: GELFAND-P000113

Uncertain reading. Above the final A are two dense raised strokes, currently $+1$[?]; the right vertical stroke is close to the closing quotation mark. No separate minus is visible.

V. I. Arnold. Progress in the theory of singularities of differentiable mappings.
$f : M^m \longrightarrow N^n$ — 2 manifolds.



Original source details: GELFAND-P000113

Uncertain reading. In the target N^n the capital letter is densely overwritten; the individual earlier strokes are unread.

$R^m \longrightarrow R^n$, $0 \longrightarrow 0$. Whitney, Thom, Malgrange, B. Morin, Broadman, Mather, (Haefliger, H. Levin, M. Mors).



Original source details: GELFAND-P000113

Diagram and typed description. The Latin list has Broadman, H. Levin and M. Mors; before Morin is a B-like capital.

The simplest case — Morse's theorem $n = 1$ — critical points $df = 0$. ← isolated for general position. Determined by [Crossed out: an od...-like entry, continuation unreadable.] index and signature. (Morse lemma) — a model for the theory.



Original source details: GELFAND-P000113

Uncertain reading. After the abbreviation for determined a short token with an od...-like beginning is cancelled. The middle and ending are densely covered by strokes.

Study the roughness[?] of singularities (if changed slightly, equivalent or not).



Original source details: GELFAND-P000113

Uncertain reading. The beginning of the word after study is densely overwritten. The current reading is grubost'[?] (roughness), with a b-like upper arc and ending ost'; the earlier strokes are not established.



f, g are equivalent if obtained by a change of variables.



Original source details: GELFAND-P000113

Diagram and typed description. The upper and lower rows are $R^m \to R^n$, with f above and g below. Vertical arrows point down: h on the left, k on the right.

$d^2 f$ without zeros — reducible to a quadratic form. For the komp.[?] source manifold they form an everywhere pl.[?] open set.

Original source details: GELFAND-P000113

Uncertain reading. After for is a short komp.[?] / norm.; after everywhere a short pl.[?] / na. with a dot. The abbreviations are unexpanded. At the right, open set.

$R^m \longrightarrow R^1$ is solved. Whitney's first result (55) $R^2 \longrightarrow R^2$. An example of singularities. Singular points — rank of the differential $= 1$ and they are of 2 classes (folds and cusps). They are structurally stable (0 can be avoided). Ordinary point ~~$(x,y) \longrightarrow (x,y)$~~ $y_1 = x_1$, $y_2 = x_2$.



Original source details: GELFAND-P000113

Uncertain reading. The entry $(x,y) \longrightarrow (x,y)$ is crossed out by two long horizontal lines. At the right, separately $y_1 = x_1$, $y_2 = x_2$.

Fold point: [Crossed out: (x,y)[?], other strokes unread.] structurally stable.



Original source details: GELFAND-P000113

Uncertain reading. Below the heading an (x,y)-like entry is densely crossed out; below the lower slanting strokes the individual letters are not separated.

$$\boxed{\begin{aligned} y_1 &= x_1^2, \\ y_2 &\to x_2. \end{aligned}}$$



Original source details: GELFAND-P000113

Diagram and typed description. Two lines in one frame. The first is $y_1 = x_1^2$. In the second, between y_2 and x_2 is an arrow-like sign, a horizontal stroke with a point at the right.





Original source details: GELFAND-P000113

Diagram and typed description. Two separate oblique strips. The upper one has a curved front edge and an internal line; the x_1 axis points right, x_2 obliquely upward. The lower strip has no labels.

Cusp point:

$$y_1 \overset{[?]}{\to} x_1,$$
$$y_2 = x_2^3 - x_1 x_2.$$



Uncertain reading. At y_1 is a sign with two closely spaced strokes, $\to$ / $=$; at the right x_1. The second line is $y_2 = x_2^3 - x_1 x_2$, with a separate minus. A long straight line is below both lines.

Original source details: GELFAND-P000113

z^2 singularity unstable; under deformation splits into 3 cusp points.



Diagram and typed description. At the right an entry is framed, open at the right edge, with a step in the lower outline. The text begins with z^2, and the next line has into 3 cusp points.

Original source details: GELFAND-P000113

Whitney's theorem: any [Crossed out: unreadable entry.] mapping is approximated by such ones.



Uncertain reading. Between any and the abbreviation for mapping is a short dense cancellation. The earlier letters are not established.

Original source details: GELFAND-P000113

Points of the 3rd type are isolated, of the 2nd type in M^m a nonsingular 1-dimensional manifold; in N it has singularities.

GELFAND-P000114

Cusp. Jacobian

$$\begin{vmatrix} 1 & 0 \\ -x_2 & 3x_2^2 - x_1 \end{vmatrix}.$$

$3x_2^2 - x_1 = 0$ a parabola. At 0 a fold, but more complicated as a whole.



Diagram and typed description. At the right are separate lines At 0 a fold, but / more complicated as a whole.

Original source details: GELFAND-P000114





Diagram and typed description. At the left a parabola with vertex at the origin, x_1 right,x_2 up. At the right two branches with a common point,directed right; y_1 right,y_2 up.

Original source details: GELFAND-P000114

Where does the parabola go? [Crossed out: $y_2 = [?]y_1^{3/2}$.]

Uncertain reading. In the cancelled entry y_2,an equals sign and $y_1^{3/2}$ are visible. The coefficient and intervening strokes are densely covered.

Original source details: GELFAND-P000114

$y_2 = -Cy_1^{3/2}$.

$$\boxed{y_2^2 = -y_1^3}$$

$y_1 > 0$.



Diagram and typed description. The corner frame has $y_2^2 = -y_1^3$,with a separate minus. Below and to the left is a separate $y_1 > 0$.



Original source details: GELFAND-P000114

The mapping is not a fold on the whole parabola. Away from the point 0 a fold. Consider lines parallel to the x_2 axis. $x_1 = \text{const} \Rightarrow y_1 = \text{const}$. $y_2 = x_2^3 - Cx_2$.



Diagram and typed description. In the line $x_1 = \text{const}$ an arrow points to $y_1 = \text{const}$. Below is $y_2 = x_2^3 - Cx_2$,with a large C-like letter before x_2.

Original source details: GELFAND-P000114



П[?]



Uncertain reading. Several curves pass through the common intersection of the axes. At the right,next to the curve with turns,is $c > 0$; below,$c < 0$ and a curved arrow. At the right is a separate Cyrillic-P-/ П-like mark,meaning unestablished.

Original source details: GELFAND-P000114

$c < 0$ the lines are mapped izom.[?] $c > 0$.

Original source details: GELFAND-P000114

Uncertain reading. After the abbreviation for mapped,a short izom.[?] / monot.-like word has densely joined middle strokes. The abbreviation is unexpanded.





Diagram and typed description. At the left a parabola,axes and two separate verticals. At the right a pointed two-branch curve with several vertical strokes and a short curved internal line. Between the sketches is $c > 0$.

Original source details: GELFAND-P000114

A cusp occurs on all luchesnykh[?] branakh[?].



Original source details: GELFAND-P000114

Uncertain reading. In the first disputed word a vertical diagram stroke crosses the middle: luchevykh / luchesnykh. In the second,the initial strokes are b-/g-like: branakh / granyakh. The full reading is not established.

Problem. [Crossed out: z^2[?] and unreadable strokes.] $z \longrightarrow z^2 + \varepsilon\overline{z}$ — general position. $\varepsilon = 0$ singularity at 0; for $\varepsilon \neq 0$ it moves, there will be folds and cusps. And only this is stable.

Original source details: GELFAND-P000114

Uncertain reading. After Problem. a z-like sign with an upper 2 is cancelled; the right part of the entry is covered by long strokes.

Scientific definition of a cusp. One of the known systems of invariants. Rank $= r$[?] — manifold Σ_r.



Original source details: GELFAND-P000114

Uncertain reading. After the equals sign the letter is densely overwritten; currently r[?],with earlier round strokes unread separately. Below,similar signs occur at Σ_r and in the sequence r_1, r_2.

M^m is partitioned into manifolds. ~~Codim.~~

Codim. sing. = product of coranks $(m-r)(n-r)$

manifold

(This is a question about independent minors of a rectangular matrix of rank r.)



Original source details: GELFAND-P000114

Uncertain reading. The first Codim. is crossed out by long horizontal lines. Below,a separate repetition Codim. sing.



Original source details: GELFAND-P000114

Diagram and typed description. Below sing. is a brace pointing up with the label manifold; below that,a long corner frame. Product of coranks has a wavy underline; at the right,$(m-r)(n-r)$.

Σ_r — smooth manifolds in R^m; consider our mapping on the manifolds themselves (parabola). Rank on these manifolds. Σ_{r_1,r_2}, $r_2 < r_1$ — submanifold — rank levels. Σ_{r_1,r_2,r_3}. To each [Crossed out: unreadable word.] singularity corresponds a set of numbers r_1, r_2, r_3.



Uncertain reading. After to each a long word,resembling osobennosti,is cancelled. Upper and lower horizontal strokes cover most letters.

Original source details: GELFAND-P000114

Invariant of a singularity $r_1 \geq r_2 \geq \cdots \geq 0$.

GELFAND-P000115

Whitney sing.: Σ_0 ordinary. The first index is the corank. Cusp: Σ_{10}. It is proved that this is a manifold.



Diagram and typed description. For Whitney,Σ_0,with ordinary below it; for the cusp,Σ_{10}. At the right,The first index is the corank.

Original source details: GELFAND-P000115

[Crossed out: D...]

For the partition in the space of Taylor-series segments. (Brodman) — the old naive approach.

Uncertain reading. Before for the partition,a short cancelled entry; a Cyrillic-D-like beginning is visible,the other letters covered by strokes.

Original source details: GELFAND-P000115

It is known that Σ is not a complete classification. (There is an example $R^9 \longrightarrow R^9$.) General theory. Consider the space of Taylor series. (3 classes — C^∞, analytic, formal power series.) [At the right:] $R^m \longrightarrow R^n$; C^∞ has Taylor series.

$$y = \sum_{\substack{[?]\\ k \geq 0}} a_k x^k, \qquad a_k \text{ — a vector}, \quad k = (k_1, \ldots, k_m).$$



Uncertain reading. Below the sum,$k \geq 0$[?] / $k > 0$; the small strokes of the sign are joined. At the right,a_k is a vector,$k = (k_1, \ldots, k_m)$.

Original source details: GELFAND-P000115

Local theories. C^∞ — the most difficult, analytic — the most interesting, formal series — the simplest. Mappings are equivalent if there is a change. A partition into pieces arises — a stratification. Study of this partition.

$$\begin{array}{ccc} R^m & \xrightarrow{\quad f \quad} & R^n \\ {\scriptstyle h}\downarrow & & \downarrow{\scriptstyle k} \\ R^m & \xrightarrow{\quad g \quad} & R^n \end{array}$$

h, k — formal diffeomorphisms (1st terms with Jacobian $\neq 0$).



Diagram and typed description. Two rows $R^m \to R^n$: above,f; below,g; vertical arrows down,h on the left,k on the right.

Original source details: GELFAND-P000115

There is an example (> 9) with infinitely many invariants. ↓ Thom proved that in the space of power series a part of infinite codimension is singled out, that the rest are stable in the topological sense.



Uncertain reading. General theory. has a straight underline,with middle letters overwritten. Thom has a wavy underline; at the left,a short arrow down. Earlier strokes of the name cannot be read separately.

Original source details: GELFAND-P000115

(Thom's invariants in R^9 are invariants of smooth,but not nepr.[?])



Uncertain reading. The final abbreviation is nepr. / nerp.; the joined middle strokes do not give an unambiguous letter order.

Original source details: GELFAND-P000115

(Thom does not want to publish the proof,he is working on biology. The proof was recounted,for a whole year,but nobody understood it: Malgrange, Cartan, Arnold and others.) $\bigcup X_\gamma + X_\infty$, X_γ singularities stable in the topological sense.



Diagram and typed description. Before X_γ is a large union sign without a lower index; between X_γ and X_∞ is a separate plus.

Original source details: GELFAND-P000115

For some dimensions Thom's analytic difficulties do not arise. (Singularities differentially stable.) Apparently the problem is solved where there is [Crossed out: unreadable word.] a classification. (In small dimensions.)

Uncertain reading. Between there is and classification,a long cancelled entry covered by several horizontal strokes.

Original source details: GELFAND-P000115

There are Σ that are differentially stable $\Sigma_{1,\ldots,1,0}$. Not all Σ are differentially stable. Another result of Mother. (Milnor's student.)



Diagram and typed description. The name has a round o: Mother. In the lower repetition,Mother'a.

Original source details: GELFAND-P000115

$\delta y = \varphi(x)$. $h(x)$ — variation in X — a vector field.





Diagram and typed description. Crossing axes and two nearby arcs above the horizontal,with $f(x)$ at the lower arc. A separate horizontal arrow right below the axis is labelled $h(x)$,and a vertical arrow up at the left,$k(y)$.

Original source details: GELFAND-P000115

Change of variables — the function changes by $f'(x)h(x) + k(y)$. In the 1st approximation one must solve the equation

$$\varphi(x) = f'(x)h(x) + k(y).$$



Uncertain reading. In the first formula,$k(y)$ is densely overwritten; below,in a separate equation,is a clean $k(y)$. The earlier strokes of the first letter are unread.

Original source details: GELFAND-P000115

The corresponding theorem says that for stability it is necessary and sufficient that the corresponding linear problem be solvable. ($\forall\varphi(x)$) (sek. verkhnikh.[?] sheaves[?])



Uncertain reading. The beginning is sek.; the next word is verkhnikh.[?] / ver...nikh.-like,the full reading unestablished. The last word is puchki / puchka.

Original source details: GELFAND-P000115

(This is Mother's 1st theorem. Moreover,it suffices for $\varphi(x)$ given by a polynomial of degree equal to dim. ℓ[?].)



Original source details: GELFAND-P000115

Uncertain reading. After dim.,a densely overwritten sign,ℓ- / N-like; earlier strokes are covered.

But the proof is incorrect. Modern technique (nonlinear functions in C^∞ spaces). All dimensions for which everything is good have been found. $R^2 \longrightarrow R^2, R^3$ (Whitney); in R^4 unknown, in R^5 already known (there are no singularities at all any more). Immersion (immersion). For $m = n$ up to 8 all mappings are stable (approx.).

GELFAND-P000116

Thom — a continuous invariant (stable). It is not topological — it is an invariant of smooth mappings. Under continuous deformation one can deform them. 29/XI. Once again about[?] characteristic classes. [Crossed out: unreadable word.]

(I. M. Gelfand.)

Original source details: GELFAND-P000116

Uncertain reading. After classes.,a long densely cancelled entry; the letters are covered by horizontal strokes.



Original source details: GELFAND-P000116

Uncertain reading. Before characteristic,a round densely overwritten letter,o[?],with its own straight underline. Parts of the heading are underlined separately. Beautiful observation. and Classification: below have wavy underlines.

Consider E over X,a connection $D : \Gamma(E) \to \Gamma(T^* \otimes E)$. f (function) $\in A^0$, $s \in \Gamma(E) \Rightarrow$ $D(fs) = f \cdot Ds + df \cdot s$. [At the right:] (Here T is the tang.[?] bundle.)



Uncertain reading. Before and at the beginning of kas.,a dense correction; the earlier strokes cannot be read separately.

Original source details: GELFAND-P000116

[In the margin:] ② More precisely — tensor product in $A \otimes_{A^0} \Gamma(E)$.

Diagram and typed description. Below f is the label function,joined to the letter by a short stroke. In the tensor product,A^0 is below $\otimes$. In the right margin,2 is circled.



Original source details: GELFAND-P000116

Cartan's moving frame (locally): s_i $(i = 1, \ldots, n)$, n — dim.[?] of the fibre.
Linearly independent at $\forall$ point.



Uncertain reading. In n — dim. of the fibre,the abbreviation for dimension is densely overwritten; earlier letters are covered.

Original source details: GELFAND-P000116

$D(s_i) = \sum \theta_{ij} s_j$,coefficients from A^1 (forms). $\|\theta_{ij}\|$ is called the connection matrix (in Cartan — ω).



Diagram and typed description. For sections an s-like letter recurs: $s \in \Gamma(E)$,s_i,s_j; below,$s = (s_1, \ldots, s_n)$. The initial D in $D(fs)$ is overwritten.

Original source details: GELFAND-P000116

$$\|K_{ij}\| = K(s,D) = d\theta(s,D) - \theta(s,D)\wedge\theta(s,D), \qquad s=(s_1,\dots,s_n).$$

(This is a matrix.) (Matrix product,but the product is exterior.) The form

$$C(E,D) = \det\left|I + \frac{i}{2\pi}K(s,D)\right|.$$



Original source details: GELFAND-P000116

Diagram and typed description. In the determinant,before $K(s,D)$,a fraction with i in the numerator and 2π in the denominator.

The entries are forms of even order,they commute and one can take det. A $\sum$ of forms of different orders. These are the characteristic classes associated with the given bundle. This does not depend on the choice of connection. [Idea of the proof according to Gelfand: closedness and this are proved,θ[?] changed.

The form no longer depends on the connection,$\int$ can be expressed through $\int$ over the boundary. A variation of the connection inside has no effect.]

Original source details: GELFAND-P000116

Uncertain reading. Before changed,a dense θ- / paragraph-like sign,with a round upper and dense lower stroke.

It does not depend on the choice of frame. Bianchi identity:

$$dK(s,D) = -[K(s,D),\theta(s,D)].$$

(Derivative of the curvature tensor.)



Original source details: GELFAND-P000116

Diagram and typed description. The curvature formula has a minus before $\theta\wedge\theta$. The Bianchi identity has a minus before the commutator; the order inside the brackets is $K(s,D),\theta(s,D)$.

Beautiful observation. $g_{\alpha\beta}(x)$ — a Riemannian metric,we shall take all successive derivatives of $g_{\alpha\beta}(x)$ and form tensors from them. How does one find all tensors that can be formed from $g_{\alpha\beta}(x)$? Classification: they are functions of the curvature tensor and all covariant derivatives of the curvature tensor (of any order) (algebraic expressions in them). But what algebraic relations? (Between first covariant derivatives — the Bianchi identity.) Introduce normal coordinates (po[?] geodesics) mr.[?] bundle.



Original source details: GELFAND-P000116

Uncertain reading. At the beginning of the parentheses,a short po[?]-like word. After the parentheses,mr.[?] / metr.-like abbreviation before bundle; the full reading is unestablished.

$$g_{\alpha\beta}(x) = g_{\alpha\beta}(0) + g_{\alpha\beta,\delta\delta}x^{\delta}x^{\delta} + g_{\alpha\beta,\delta\delta\varepsilon}[?]x^{\delta}x^{\delta}x^{\varepsilon}.$$



Original source details: GELFAND-P000116

Uncertain reading. In the second term,two δ-like letters in the subscripts and at both x's. In the third,the subscripts are $\delta\delta\varepsilon$[?] / $\gamma\delta\varepsilon$,with the middle letter overwritten; the superscripts are also δ- / γ-like,the last ε.

In a normal system they are all tensors. This system of tensors,and here the algebraic relations are simpler.

GELFAND-P000117

V. I. Arnold. Stable flow. $\dot{x} = f(x, C)$; g^t — a group of diffeomorphisms. There are chemical and biological models (Thom). x △ sums of substances,c — a parameter.



Original source details: GELFAND-P000117

Diagram and typed description. Between x and sums of substances,a triangle with a dot inside. The right parameter label uses lowercase c,the equation uppercase C.

Consider one (stable). A number of kogrubost[?] is introduced.

$$\begin{array}{ccc} X & \xrightarrow{g^t[?]} & X \\ \downarrow & & \downarrow \\ X & \xrightarrow{h[?]} & X \end{array}$$



Original source details: GELFAND-P000117

Uncertain reading. Four X's; above the upper horizontal arrow,an overwritten g^t[?],above the lower,an h-like letter. Horizontals right,verticals down,with no labels at the verticals.

Stable if for $\forall$ nearby h there is a perturbation of X. One cannot consider only stable ones (when parameters change,one may pass through nonstable parameters). (x, C) — a point of kogrubost[?] 1,if for nearby parameter values stable,etc. As a mapping $X \times C \longrightarrow X \times C$,stable. (How many terms of the Taylor series must be taken.) A centre — an infinite degree of nonstability.

Original source details: GELFAND-P000117

Diagram and typed description. Next to the entry about a centre,three nested closed round lines. They have no labels.

Thom's theorem on germs of Taylor series $\vartheta = \vartheta^{\infty} + \bigcup_{\gamma} \vartheta^{\gamma}$.

[Below the formula:] codim. ∞



Original source details: GELFAND-P000117

Uncertain reading. The recurring letter is ϑ[?] / θ / O-like,with a large upper loop; the superscripts are ∞ and gamma-like.



Original source details: GELFAND-P000117

Diagram and typed description. Below the formula,a separate annotation codim. ∞,underlined twice.

In ϑ^γ,an open subset of finite negrub.[?] In ϑ^γ singularities are described by finitely many parameters,inside [Crossed out: unreadable short token.]

ϑ^γ,all are diffeomorphic. (Tr-ie for differential equations.)

Uncertain reading. After inside,a short dense cancellation; separately at its left,another short horizontal stroke.

Original source details: GELFAND-P000117

In ϑ^∞,complete chaos (but they are of finite codim.[?]). All 1-parameter ones are in ϑ^∞.



Uncertain reading. In the first lines after number and point,a ko-/negrubosti-like word; literally kogrubosti[?]. In the right annotation,finite negrub.[?]; in the lower parentheses,finite korazm.[?] / kogrub.-like abbreviation. Initial and middle strokes are joined.

Original source details: GELFAND-P000117

For self-mappings,the invariants are unknown. (F. Bendixson's theorem: $\frac{dy}{dx} = \frac{P}{Q}$ on CP^2,then by finitely many σ-processes one reaches Bendixson singular points $x^p \frac{dy}{dx} = \lambda y + P(x,y)$. Already an invariant relative to σ-processes. A σ-process — substitute $\frac{y[?]}{x}$.

For 3 variables unknown. On a birationally equivalent manifold,simple singular points. Acta Math. 1901.)

Uncertain reading. At the beginning of the parentheses,a separate F-like Latin letter with a dot. The beginning of the next word is overwritten; the current reading is theorem.

Original source details: GELFAND-P000117

Uncertain reading. The numerator is y[?] / h-like,densely overwritten; the denominator x. Beside it,a short pointer bent down.

Original source details: GELFAND-P000117

On the Weierstrass preparation theorem. (Malgrange.)

$$P(y) = y^n + \sum_{i=1}^{n-1} y^i a_i(x,z).$$



Original source details: GELFAND-P000117

Uncertain reading. In the first argument of a_i,a dense cancellation,currently x[?]. Below,a separate clean $a_i(x,z)$.



Original source details: GELFAND-P000117

Diagram and typed description. The first sum's lower limit is explicitly $i=1$,the upper $n-1$.

Distinguished polynomial $a_i(x,z)$,$a_i(0,0)=0$.

Original source details: GELFAND-P000117

Uncertain reading. The second 0 in $a_i(0,0)=0$ is densely overwritten; earlier strokes are covered.

Spät Ruckert.



Original source details: GELFAND-P000117

Diagram and typed description. The name V. I. Arnold. is underlined,the next line Stable flow. separate. The heading On the Weierstrass preparation theorem. is underlined; below,$a_i(x,z)$ is also underlined. The Latin entry is Spät Ruckert.

$P(y,x,z)$; y — one variable, $x=(x_1,\dots,x_m)$,$z=(z_1,\dots,z_n)$ — spare ones. 3 forms (C^∞,analytic,formal series).

$$f(x,y,z)=P(y,x,z)\qquad Q(y,x,z)\qquad +\sum_{0}^{n-1} y^i b_i(x,z).$$

of the same class



Diagram and typed description. Below $Q(y,x,z)$,a frame with the label of the same class,joined to the right of the entry by a short line. The remainder sum's lower limit is 0.

Original source details: GELFAND-P000117

(Division is possible.) (One can do this on relative sets.) [[This works for Bendixson: the process must be finite.]] The quotient by the ideal generated by P has finite dimension [Crossed out: unreadable token.] over

[Below at the right:] the corresponding ring.

Uncertain reading. Before over,a short entry is densely cancelled; the hidden letters are unread.

Original source details: GELFAND-P000117

Diagram and typed description. Over stands at the end of the upper line. The corresponding ring. is below at the right,at the end of the next line.



Original source details: GELFAND-P000117

(Malgrange: for C^∞ this is also true,but there is no longer uniqueness.) 1) Let P nearby have n real roots — by interpolation it will be C^∞,but (the approximating polynomial by Lagrange's theorem is uniquely determined by the description — this is difficult).





Diagram and typed description. Axes:x right,y up. Three separate branches leave the origin into the first quadrant. At the right,the label $P(x,y)=0$.

Original source details: GELFAND-P000117

2) [Crossed out: $f(y,x)$-like entry.]

$f(x)$ flat at 0 (all derivatives 0).



Uncertain reading. In the cancelled entry,the arguments look like y,x. Below it,a clean $f(x)$. The first division formula ends with a separate $+f(x)$.

Original source details: GELFAND-P000117

Divide by $y^2 + x^2$. Trivial answer.

$$f(x) = (y^2 + x^2) \cdot 0 + f(x).$$

$$f(x) = (y^2 + x^2) \left(\frac{f(x)}{y^2 + x^2} \right) + 0$$

C^∞ by Łojasiewicz (potom. E[?]).

Original source details: GELFAND-P000117

Uncertain reading. In the last parentheses,potom. and a separate E- / epsilon-like sign. The abbreviation's expansion is unestablished.



Original source details: GELFAND-P000117

Diagram and typed description. The fraction $f(x)/(y^2 + x^2)$ is circled. A curved line with a round endpoint runs right from it toward the entry C^∞ by Łojasiewicz. At the right of the equality,a separate $+0$.

GELFAND-P000118

Another formulation. $f(y, x)$,$f(0, 0) = 0$. Let $\frac{\partial^n f}{\partial y^n}(0, 0) \neq 0$. This is possible if f is not flat.



Original source details: GELFAND-P000118

Diagram and typed description. In the condition,n is the derivative order in y,followed by $(0, 0) \neq 0$.

Weierstrass's theorem:∃ a distinguished polynomial P,

$$f(y,x) = P(y,x)Q(y,x), \qquad Q(0,0) \neq 0.$$



Uncertain reading. In $P(y,x)$ the second argument is densely overwritten,the current letter x[?]. In $Q(0,0)$ the first 0 is overwritten; earlier strokes are covered.

Original source details: GELFAND-P000118

V. I. Arnold.

Diffeomorphisms of the annulus,preserving area,homotopic to the identity.



Diagram and typed description. Another formulation. has a wavy underline; Arnold's name a straight one. Canonical mappings. below also has a wavy underline.

Original source details: GELFAND-P000118



Diagram and typed description. Three nested round lines; at the top of the middle one,a dense triangular stroke. At the right,Ω.

Original source details: GELFAND-P000118

$\forall\gamma$ — a closed curve,going around 0, $\underset{\text{intersection points}}{A\gamma\cap\gamma} \geq 2$ (otherwise one does not obtain area preservation). Has significance for the 3-body problem. For n bodies [Crossed out: unreadable word.]

the original problem — tori,annulus $\Omega = T^n \times B^n$,$B^n \subset R^n$ — a domain. Diffeomorphism,homotopic to the identity,$A : \Omega \longrightarrow \Omega$. $\Omega = \underset{q,\,\mathrm{mod}\,2\pi}{T^n}$. In R^n,coordinates $p = (p_1, \ldots, p_n)$.

Uncertain reading. After for n bodies,a dense cancellation before original problem; the hidden letters are unread.

Original source details: GELFAND-P000118



Diagram and typed description. The upper entry is $\Omega = T^n \times B^n$,below a separate $\Omega = T^n$; under T^n,the label $q,\,\mathrm{mod}\,2\pi$.

Original source details: GELFAND-P000118

Consider the form $p\,dq = p_1\,dq_1 + \cdots + p_n\,dq_n$. Canonical mappings. preserve the form:

$$\oint_{A\gamma} p\,dq = \oint_{\gamma} p\,dq.$$



Diagram and typed description. Both integrals have closed contours; below the left sign,$A\gamma$,below the right,γ.

Original source details: GELFAND-P000118

(Only these are considered.) (This is globally canonical.) For $n = 1$ this is the enclosed area. Transfer this to the n-dimensional case; instead of γ,T^n — but there it bounds nothing. Theorem. Consider the torus $T : p = 0$,then $AT \cap T \geq 2^n$ (at least 2^n points).



Diagram and typed description. The first entry is $A\gamma \cap \gamma \geq 2$,with intersection points below it. In the theorem,$AT \cap T \geq 2^n$; below,in words,at least 2^n points.

Original source details: GELFAND-P000118

Proof: under the additional [Crossed out: unreadable entry.]

assumption $AT \Rightarrow p = p(q)$.



Uncertain reading. Between under the additional and assumption,a short densely cancelled entry,with an opening-parenthesis-like stroke at the left.

Original source details: GELFAND-P000118



Diagram and typed description. After AT,a thick arrow-like sign right,then $p = p(q)$.

Original source details: GELFAND-P000118

But some consequences dok.[?] completely.



Uncertain reading. The word after some reads consequences; following it,a dense short abbreviation,dok.[?] / ekh.-like. Its full expansion is unestablished.

Original source details: GELFAND-P000118





Diagram and typed description. Above,a straight line and a single-valued arched curve with two intersections. Below,a different straight line and a looped self-crossing curve; below it,not this.

Original source details: GELFAND-P000118

Use Morse's theorem (n-dimensional torus).

GELFAND-P000119

6/XII Gelfand.



Diagram and typed description. Straight lines above and below XII; Gelfand's name has a straight underline. Complex case. below has a wavy underline.

Original source details: GELFAND-P000119

On X, a vector bundle E. T^* — cotangent. $D : \Gamma(E) \xrightarrow{\delta} \Gamma(T^* \otimes E)$.

Uncertain reading. Above the arrow, a small δ- / s-like sign; its exact reading is unestablished.

Original source details: GELFAND-P000119

$D(fs) = df \cdot s + f \cdot Ds$.

Uncertain reading. The D in the last Ds is densely overwritten; the earlier strokes are unread.

Original source details: GELFAND-P000119

$A(X) = \sum A^p(X)$ — forms. $A(X, E) = A(X) \otimes_{A^0(X)} \Gamma(E)$ — forms with coefficients in the bundle.



Diagram and typed description. Below the tensor-product sign, $A^0(X)$.

Original source details: GELFAND-P000119

s_i — a set of sections, at $\forall$ point a frame in the fibre over x. $D(s_i) = \sum \theta_{ij} s_j$; θ — connection matrix. Curvature $K = d\theta - \theta \wedge \theta$ and characteristic classes (2-form — they commute and one can write det)

$$C(E, D) = \det\left(1 + \frac{i}{2\pi} K\right).$$



Diagram and typed description. In parentheses, singular 2-form, then they commute and one can write det.

Original source details: GELFAND-P000119

This does not depend on the choice of connection. Complex case. An analytic vector bundle is given. It is Hermitian if a Hermitian metric is given in the fibres.
$A(X) = \sum A^{p,q}(X)$; $A^{p,q}(X)$:

$$df_1 \wedge \cdots \wedge df_p \wedge d\overline{f}_{p+1} \wedge \cdots \wedge d\overline{f}_{p+q}.$$

(f_i — an analytic section.)

Uncertain reading. The last index $p+q$ / $p+g$ is densely corrected; its last letter remains disputed.

Original source details: GELFAND-P000119

$$\begin{aligned} d &= d' + d'', \\ d' &: A^{p,q} \longrightarrow A^{p+1,q}, \\ d'' &: A^{p,q} \longrightarrow A^{p,q+1}, \\ D &= D' + D'', \\ D' &: \Gamma(E) \longrightarrow A^{1,0}(X,E), \\ D'' &: \Gamma(E) \longrightarrow A^{0,1}(X,E), \\ \Gamma(T^* \otimes E) &= A^1(X,E). \end{aligned}$$



Diagram and typed description. For d', at the right $p+1, q$; for d'', $p, q+1$. For D', type $1,0$; for D'', $0,1$.

Original source details: GELFAND-P000119

The connection decomposes into a sum of 2 connections. s_i given, consider $N_{ij} = \langle s_i, s_j \rangle_x$ — functions of X. (Hermitian matrix.) Theorem: if there is a Hermitian space, then there is a unique connection compatible with it. From the Hermitian bundle N, a connection is uniquely determined such that

1° D preserves N; 2° $s \in \Gamma_U(E)$ analytic $\Rightarrow D''s = 0$.

(Preserves the holomorphic structure.) (Parallel transport — a linear transformation.)



Diagram and typed description. At the start, Theorem is underlined. Below, From the Hermitian bundle N; the word is bundle.

Original source details: GELFAND-P000119



Uncertain reading. The s in item 2 is densely overwritten; the earlier sign is unread. Below Γ, subscript U.

Original source details: GELFAND-P000119

$$d\langle s, s'\rangle = \langle Ds, s'\rangle + \langle s, Ds'\rangle.$$

(Differentiation formula.)

$$\langle s \otimes \alpha, s' \otimes \beta\rangle = \langle s, s'\rangle \cdot \alpha \wedge \beta.$$

(The scalar product of forms is a form.)



Uncertain reading. No separate bar over β is visible in this product.

Original source details: GELFAND-P000119

$$N = \|N_{ik}\| = \langle s_i, s_k\rangle, \qquad dN = \theta N + N\bar{\theta}^t.$$

θ of type $1, 0$ — equivalent to condition 2. $d'N = \theta N$.



Diagram and typed description. In the matrix, indices ik; in the second term $N\bar{\theta}^t$, a bar over θ and a superscript t at its right. At the bottom, $d'N = \theta N$.

Original source details: GELFAND-P000119

$\theta = d'N \cdot N^{-1}$. (The connection constructed from the Hermitian metric must have this form.) And conversely, from N one easily obtains a connection.

$$d\langle s_i, s_j\rangle = \langle s_i, Ds_j\rangle + \langle Ds_i, s_j\rangle.$$

Relation between N, θ and K.



Original source details: GELFAND-P000120

Diagram and typed description. Below Relation between N, θ and K, a long straight line.

[Crossed out: a short unreadable entry.]

Original source details: GELFAND-P000120

Uncertain reading. At the left below the heading, dense cancelled strokes; their exact letters are unestablished.

E — a holomorphic bundle. θ — of type $(1,0)$.

$$K = d''\theta, \qquad d''K = 0,$$
$$d'K = -[K,\theta] \quad \text{Bianchi identity.}$$

$d'\theta = \theta \wedge \theta$. $\underline{d'\theta = \theta \wedge \theta}$? $\theta = d'N \cdot N^{-1}$, differentiate.

$$d'\theta = -d'N \cdot N^{-1} d'N \cdot N^{-1}.$$



Original source details: GELFAND-P000120

Uncertain reading. A minus in the differentiated product. Above at the right, a positive equality; at the left, its underlined repetition with a question mark.

$$K = d\theta - \theta \wedge \theta$$
$$= d'\theta + d''\theta - \theta \wedge \theta = d''\theta.$$



Original source details: GELFAND-P000120

Diagram and typed description. In the identity $d'K = -[K,\theta]$, a minus before the bracket. Below, the equality chain ends with $d''\theta$.

Let E be one-dimensional over an analytic manifold, at $\forall$ point a Hermitian metric. $K = d''\theta$, $\theta = +d'N \cdot N^{-1}$. $N(s)$ — a function on X — positive $N(x)$. $K = d''d' \log N(x)$. The characteristic class — the same up to a factor, a form of type $(1,1)$.



Original source details: GELFAND-P000120

Diagram and typed description. An explicit plus before $d'N$. On one line, $N(s)$, then $N(x)$. Below, $K = d''d' \log N(x)$.

[Crossed out: a K-like beginning, the continuation unreadable.]



Original source details: GELFAND-P000120

Uncertain reading. Before All classes, a short K-like fragment is cancelled; the hidden strokes are unread.

All classes of type (p,p) (since $K = d''\theta$ is of type $(1,1)$). Watts Proceedings National Academie of Science. vol. 54, $N = 4$ homology in terms of the ring of continuous functions. (Washington? Oct. 65)



Original source details: GELFAND-P000120

Diagram and typed description. Watts and Proceedings National Academie of Science. vol. 54, $N = 4$ have wavy underlines. In parentheses, Washington?; Oct. 65 also has a wavy underline.

Λ — a K-algebra (K — a given ring). (In the application, $k = R$.)

$$F^0 = \Lambda, \qquad F^p = \Lambda \otimes_K F^{(p-1)}.$$

functions of p variables. $F^{(p-1)}$ — φ.



Original source details: GELFAND-P000120

Uncertain reading. In the left annotation, exponent $p-1$ / $p+1$, with a dense intervening stroke.



Original source details: GELFAND-P000120

Diagram and typed description. At the right, $F^0 = \Lambda$, then $F^p = \Lambda \otimes_K F^{(p-1)}$; below them, functions of p variables.

$$\mu_F(f_0 \otimes \cdots \otimes f_p) = f_0 f_1 \cdots f_p.$$

(Restriction map to the diagonal.)

$$d_i^p(f_0 \otimes f_1 \otimes \cdots \otimes f_p) = f_0 \otimes f_1 \otimes \cdots \otimes f_{i-1} \otimes 1 \otimes f_i \otimes \cdots \otimes f_p.$$

$d^p = \sum(-1)^i d_i^p$. $\{d^p, F^{(p)}\}$ — a complex.



Uncertain reading. The f_1 in the left parentheses is densely overwritten; the earlier index is unread.

Original source details: GELFAND-P000120



Diagram and typed description. Between f_{i-1} and f_i, an inserted 1. The sum has no written limits; below, $\{d^p, F^{(p)}\}$.

Original source details: GELFAND-P000120

Let M be a maximal ideal. $\mu_F^{-1}(M) \Rightarrow$ a maximal ideal in $F^{(p)}$ — arises from this map. (The point on the diagonal corresponding to them.) f is called vanishing near M, if f lies in the kernel of the localization of F^p at $\mu_p^{-1}(M)$.



Uncertain reading. Near and the final M are densely corrected; M is visible, the earlier letters are unread.

Original source details: GELFAND-P000120



Diagram and typed description. In the first entry, $\mu_F^{-1}(M)$; in the localization line, $\mu_p^{-1}(M)$. Both p and (p) occur on F.

Original source details: GELFAND-P000120

$\exists g$ such that $gf = 0$, $g \overline{\in} \mu_p^{-1}(M)$.



Uncertain reading. Above the sign $\in$ beside g, a separate horizontal bar.

Original source details: GELFAND-P000120

$N^p = \{f$ [Crossed out: an unreadable entry.] in a strip around the diagonal $\}$.



Original source details: GELFAND-P000120

Uncertain reading. After f, a densely cancelled $= 0$-like entry. It remains crossed out.

$d^p N^p \subset N^{p+1}$. $\{N^p, d^p\}$, F/N — a complex. Its homology [Crossed out: several unreadable letters.] is denoted H^p.

(Theorem — they coincide with the usual Alexander–Spanier cohomology.)



Original source details: GELFAND-P000120

Uncertain reading. After homology, several letters are cancelled by two lines.



Original source details: GELFAND-P000120

Diagram and typed description. In the line, Its homology; in the final parentheses, Alexander–Spanier cohomology. Both $\{N^p, d^p\}$ and F/N are written.

GELFAND-P000121

On the work of N. Levinson Duke, 1961 p. 345–353

$f(y, x_1, \ldots, x_n)$ — analytic in many variables. [Crossed out: a short unreadable entry.] There exists [Crossed out: a word resembling Diffeomorphism.] a diffeom.

[Inserted: anal.] [Crossed out: that[?].] (of coord.), such that

(local property)

Given $\left| \begin{array}{l} \dfrac{\partial^i f}{\partial y^i}(0,0) = 0 \\ \\ \dfrac{\partial^n f}{\partial y^n}(0,0) \neq 0 \end{array} \right|$ $\left| \begin{array}{l} i = 0, \ldots, n-1 \\ \\ d^n(x) y^n + \sum_0^{n-1} d^i(x) y^i \\ \\ d^n(0) \neq 0. \qquad d^i(0) = 0. \end{array} \right|$



Original source details: GELFAND-P000121

Uncertain reading. After variables, a short dense cancellation. After There exists, a long cancelled word with a Diffeomorphism-like beginning; covered letters have not been supplied.



Original source details: GELFAND-P000121

Uncertain reading. A separate anal. stands below the main line near the cancelled word. Before (of coord.), a cancelled entry resembling that; after the parentheses, a separate clean that.



Original source details: GELFAND-P000121

Diagram and typed description. Given at the left; the two conditions have a separate left vertical and a right vertical. A lower stepped line runs to the polynomial at the right; beyond it, two vertical lines. Above it, (local property).



Original source details: GELFAND-P000121

Diagram and typed description. The first coefficient has superscript n; the sum has lower limit 0, upper $n-1$; then $d^i(x)y^i$. Beneath, separate $d^n(0) \neq 0$ and $d^i(0) = 0$.

Also, if there are 2 variables, one can make an actual polynomial (!)



Original source details: GELFAND-P000121

Diagram and typed description. Before polynomial, the abbreviation nast., with a separate full stop. After polynomial, a separate (!).

(if $n = 3$, this is not always possible — Whitney's example)

$$f(x,y,z) = xy(y-x)(y-xz[?])(x\varphi(z) - y[?]), \qquad \varphi(0) = 0,$$

$\varphi(z)$ — any transcendental function. Zeros — (4 surfaces)



Original source details: GELFAND-P000121

Uncertain reading. In the fourth factor, after the minus, a densely corrected entry; xz is inserted above it. The covered lower strokes have not been read.



Original source details: GELFAND-P000121

Uncertain reading. In the last factor, after the minus, a dense correction before a y-like letter; the preceding strokes have not been established separately.



Original source details: GELFAND-P000121

Diagram and typed description. In the example line, a separate $\varphi(0) = 0$. Below, after Zeros, the entry (4 surfaces); further down, at $\forall$ point 4 tangent planes.

Even a diffeom. [The end of the abbreviation is crossed out]: [Crossed out: an unreadable phrase.]



Original source details: GELFAND-P000121

Uncertain reading. After Even, a diffeom.-like entry is visible, with its ending densely covered; after the colon, a long cancellation with several lines. In the next line, the words ratio of planes are underlined.

At $\forall$ point 4 tangent planes. (They pass through one line.) Anharmonic ratio of planes — an invariant of diffeomorphisms. Singularities of curves. $\forall$ quadruple $(1, 2, 3, 4; \quad 1, 2, 3, 5)$ [Crossed out: $\forall$ and a short unreadable entry.]

Original source details: GELFAND-P000121

Uncertain reading. Before On this, a separately cancelled $\forall$ and a following short sign or word. These signs are crossed by one long line.

On this singular line, this is a function of z. $A_1,\ A_2$.



Original source details: GELFAND-P000121

Diagram and typed description. At the right, separate A_1, A_2; the lower horizontal stroke of 2 is extended.





Original source details: GELFAND-P000121

Uncertain reading. The horizontal axis points right with A_1; the vertical points up. Beside its A, the lower right stroke merges with the beginning of the arc; subscript 2[?]. The arc in the first quadrant initially rises, then descends gently.

This was a transcendental curve. But for a polynomial with such a structure, str.[?] this curve, it must be algebraic.



Original source details: GELFAND-P000121

Uncertain reading. After structure, a short str.-like entry; its abbreviation has not been expanded. The final line reads must be algebraic.

[Crossed out: a short unreadable sign.]

Original source details: GELFAND-P000121

Uncertain reading. At the left before Arnold., a separate densely cancelled sign with a rounded left stroke.

Arnold. Hydrodynamics, ideal fluid.



Original source details: GELFAND-P000121

Diagram and typed description. Arnold. has a straight underline. Hydrodynamics, ideal and fluid. have separate wavy underlines.

Stationary flows of ideal fluid in 3-dimensional space. D — a bounded domain, and ideal fluid flows there (stationary flow).





Diagram and typed description. A closed rounded contour; D at the left. Inside, a short arrow points right and up.

Original source details: GELFAND-P000121

Theorem. $\vec{v}$ — the velocity vector field (tangent on the boundary).

$$\vec{\tau}[?] = \operatorname{rot} v.$$



Uncertain reading. The letter at the left has a rightward arrow above it. The letter is τ- / r-like; its exact reading is unestablished. After rot, a separate v with no visible overhead arrow.

Original source details: GELFAND-P000121

Let $\vec{\tau}$[?] and $\vec{v}$ be not everywhere collinear; let [Crossed out: an unreadable word.] v be analytic everywhere.

Uncertain reading. Before the last v, a separate dense cancellation; a short initial k-like stroke is visible, the other letters covered.

Original source details: GELFAND-P000121



Uncertain reading. In the condition not everywhere collinear, the first disputed letter has a short horizontal stroke overhead with no clearly separate head; v has a rightward arrow.

Original source details: GELFAND-P000121

Then D is divided by an analytic subset into cells (a finite number) — finite tsilindru[?] [na / ili?] polnotoriyu[?], and in them the flow is arranged as follows. On the cylinder — rotations.



Original source details: GELFAND-P000121

Uncertain reading. After finite, the ending is tsilindru[?] / cylinders; between it and polnotoriyu, a short na- / ili-like entry. Joined strokes do not give an unambiguous reading; no standard term has been substituted.

On the torus, $\dot{\varphi}_1 = \lambda_1, \quad \dot{\varphi}_2 = \lambda_2$ ([Crossed out: a word beginning vrashch...] [Below:] winding of the torus.)



Original source details: GELFAND-P000121

Uncertain reading. In the parentheses, the upper entry is densely crossed out; vrashch...-like initial strokes are visible. The lower separate line is winding of the torus.

If everywhere collinear, there are examples when this is not so. Ideal fluid

$$\frac{\partial v}{\partial t} = \pm\underbrace{[\overline{\tau}, v]} \qquad \text{(eq. of mot.)}$$

Poisson bracket



Original source details: GELFAND-P000121

Diagram and typed description. Before the bracket, a separate $\pm$. A short bar above its first letter. Below the bracket, a line with a short upturn at the right and the label Poisson bracket; at the right, (eq. of mot.).

Proof:

$$\operatorname{rot}(a * b) = [a\ b] + a \operatorname{div} b - b \operatorname{div} a$$

($a * b$ — vector product.)



Original source details: GELFAND-P000121

Diagram and typed description. Between a and b, a star-shaped sign. At the right, $[a\ b]$ with no written comma, then $+a \operatorname{div} b - b \operatorname{div} a$. In parentheses, vector product.

Original source details: GELFAND-P000122

Diagram and typed description. At the upper right, 78; an angular line at its left and below it, with no upper or right side.

v is called the velocity field of ideal fluid if

1) $\operatorname{div} v = 0$
2) $[v, \operatorname{rot} v] = 0$
3) Tangent on the boundary.

this is a prav.[?] definition in a simply connected domain.



Original source details: GELFAND-P000122

Uncertain reading. To the right of the three conditions, a separate note: this is a prav.[?] definition in a simply connected domain. The disputed abbreviation has prav.- / prib.-like strokes; the full word has not been expanded.



Original source details: GELFAND-P000122

Diagram and typed description. The conditions are numbered $1), 2), 3)$. The second has $[v, \operatorname{rot} v] = 0$; the third, Tangent on the boundary. At the right, two separate parallel vertical lines.

At $\forall$ point, 2 vector fields, R^2 — the orbits of the plane. 2 vector fields and the div of both 0, commuting, then the orbits are compact (everything in a finite domain) (If $b_1 = 0$ — the 1st Betti number $= 0$ One must preserve circulation also over large domains.



Original source details: GELFAND-P000122

Diagram and typed description. In the condition, separate $b_1 = 0$ and the 1st Betti number $= 0$. An opening parenthesis before If; no closing parenthesis is visible after the last 0. The next line is One must preserve circulation also over large domains.

Mathematical theorem. $b_1 = 0$, finite mn., 2 commuting fields with div $= 0$, then the orbits are compact.

$$\text{rot}(a * b) = 0, \qquad a \times b = \text{diff.}, \quad \text{orthogonal sections},$$

orbits — level lines of a function — compact.

Original source details: GELFAND-P000122

Uncertain reading. After $a \times b =$, the entry is diff.; its abbreviation has not been expanded. In the first product inside rot, the sign is star-shaped.



Original source details: GELFAND-P000122

Diagram and typed description. Mathematical theorem. is underlined. After $b_1 = 0$, finite mn.; below, the rot of the product equals 0. At the end, a separate line: orbits — level lines of a function — compact.

If there is no boundary, the compact orbits are tori; if noncompact, then cylinders. The action of the line — winding. (Experiments are visible in photographs.) There are cylinders too. 2 rotating cylinders, fluid there.



Division into tori, neighbouring ones rotate in different directions.

Diagram and typed description. Three overlapping ring contours with inner loops and short side strokes. No separate labels or arrows are visible on the rings. At the right, Division into tori, neighbouring ones rotate in different directions.



Original source details: GELFAND-P000122

13/XII. Arnold. What is ideal fluid?



Original source details: GELFAND-P000122

Diagram and typed description. Separate straight lines above and below XII; Arnold. is underlined separately. Below, the question What is ideal fluid?

Fluid flow in a bounded domain, [Crossed out: a short unreadable sign.] Interesting to study instability.

Uncertain reading. Before Interesting, a separate densely crossed-out short sign; its letter or meaning is unestablished.

Original source details: GELFAND-P000122

v — velocity field, $\operatorname{div} v = 0$ (incompressible). (Makes sense on a Riemannian manifold.)





Original source details: GELFAND-P000122

Diagram and typed description. A closed oval contour. Inside, a right-and-up arrow; D is also inside, to the right and below the arrow.

Newton's equation

$$\frac{DV}{Dt} = \mathcal{F}.$$

$\mathcal{F}$ — force. $\frac{DV}{Dt}$ — acceleration of a particle (not the partial derivative).



Original source details: GELFAND-P000122

Diagram and typed description. In Newton's equation, numerator DV, denominator Dt; a separate straight line beneath the whole fraction. At the right, a calligraphic F-like letter, and its repetition beside force.

$v(x, y, z, t)$. If there are no external forces

$$\mathcal{F} = -\underline{\operatorname{grad} p[?]} + \mathcal{F} + \nu\Delta v$$

(They are potential.)

$$\boxed{p[?] \text{ — pressure.}}$$

Δv — Laplacian of the vector field. ν — viscosity.



Original source details: GELFAND-P000122

Diagram and typed description. In the equality, after the underlined grad with a p-like letter, separate $+\mathcal{F}$ and $+\nu\Delta v$. Below, Δv — Laplacian of the vector field and ν — viscosity.



Original source details: GELFAND-P000122

Uncertain reading. In the pressure label, a p-/ρ-like letter with a long lower stroke. Around the label, left, lower and right lines; no upper side is drawn. The letter's shape differs from the disputed sign in the gradient of the system below.

$$\frac{DV}{Dt} = \frac{\partial v}{\partial t} + v\frac{\partial v}{\partial x}$$

(Navier–Stokes equation)



Original source details: GELFAND-P000122

Diagram and typed description. In the left fraction, numerator DV with a capital V-like letter; the right fractions have small v. The last denominator is ∂x.

It is known that for small t a solution exists, and in the 2-dimensional case there is existence, uniqueness, etc. (Yudovich) (Applicable there)



Original source details: GELFAND-P000122

Diagram and typed description. After existence, uniqueness, etc., two separate parentheses: (Yudovich) and (Applicable there). A closing parenthesis follows there; no continuation is written inside it.

$$\begin{cases} \dfrac{\partial v}{\partial t} = -v\dfrac{\partial v}{\partial x} - \operatorname{grad}\varphi[?] + F + \nu\Delta v \\ \operatorname{div} v = 0 \end{cases}$$

ud. bound. cond.

In the space of vector fields with $\operatorname{div} v = 0$ — a dynamical system.



Original source details: GELFAND-P000122

Uncertain reading. After grad, the letter is φ- / p-like, with a long stroke through the rounded part. A minus precedes it. Then a separate plain F, followed by $+\nu\Delta v$. A common brace at the left.



Original source details: GELFAND-P000122

Diagram and typed description. A short oblique pointer leads from $\operatorname{div} v = 0$ to a note above the line: ud. bound. cond. The first abbreviation is ud.; it has not been expanded.

Limiting cases — — viscosity large and small. Large viscosity — a unique equilibrium position. Everything $\to$ the solution of the corresponding elliptic equation. What if viscosity decreases? Eigenvalues for the variational equations (stable solution) λ moves right.



Original source details: GELFAND-P000122

Diagram and typed description. In the question, decreases is underlined; below, (stable solution), then a separate λ moves right.





Original source details: GELFAND-P000122

Uncertain reading. Two intersecting lines with no clearly separate arrowheads. Several points at the left; above the horizontal, a dense λ-like sign and a separate point. The sign's reading is unestablished.



Original source details: GELFAND-P000122

Undeciphered passage. The lower edge of the scan passes through the vertical stroke and the lowest point of the diagram. Their continuation beyond the edge is not visible.

GELFAND-P000123

For $\nu = 0$, we shall be symm. about both axes (syst. stationary points Hamil.[?])
(Poiseuille flow and others) — but it is unstable.)



Original source details: GELFAND-P000123

Uncertain reading. In the parentheses, syst. stationary points, then a Hamil.-like abbreviation; its full word is unestablished. Alternative reading: nachnut.



Original source details: GELFAND-P000123

Diagram and typed description. In the first line, $\nu = 0$, then we shall be symm. about both axes. After the following line, a separate closing parenthesis after unstable.

Conditional theorem: if at $\nu = 0$ there is stable flow, then the spectrum is like this



Uncertain reading. Axes with arrows up and right. To the right above the intersection, a dense curved trace with short adjoining strokes. Its reading as a letter or separate points is unestablished.

Original source details: GELFAND-P000123



Original source details: GELFAND-P000123

Diagram and typed description. Conditional theorem: above a separate line, if at $\nu = 0$ there is stable flow, then the spectrum is like this. The drawing has no readable axis labels.

Motion of ideal fluid — geodesics on a Lie gr. (∞-dimensional — diffeomorphisms of the domain)



Original source details: GELFAND-P000123

Diagram and typed description. In the heading line, geodesics on a Lie gr.; at the right in parentheses, ∞-dimensional — diffeomorphisms of the domain. The word domain continues below.

G — Lie gr., e — identity. A — Lie alg. (tangent space at 1), A^* — dual space.



Original source details: GELFAND-P000123

Diagram and typed description. Beside A, parentheses: tangent space at 1; the numeral 1 is written. Beside A^*, separately, dual space.

$L : A \to A^*$ — symm. and positive definite (scalar product)

$$\langle a, b\rangle = \langle La, b) = (a, Lb).$$

Defines a left-inv. metric on the gr.

$$\langle a, b\rangle_g = \langle \widetilde{\Lambda}_{g^{-1}} a, \widetilde{\Lambda}_{g^{-1}} b\rangle. \qquad L_g : TG_g \to T^*G_g$$



Original source details: GELFAND-P000123

Diagram and typed description. A single rightward arrow from A to A^*; after it, symm. and positive definite, then scalar product in parentheses.



Original source details: GELFAND-P000123

Uncertain reading. The first opening bracket after the equality has an angular upper part and two lower strokes, one rounded. Its bracket type is unestablished. After b, a round closing bracket; the last pair is (a, Lb).



Original source details: GELFAND-P000123

Uncertain reading. Wavy strokes above both Λ-like signs; the choice between capital Λ and small λ is not finally established. Subscripts g^{-1}.



Original source details: GELFAND-P000123

Diagram and typed description. In the line before the formula, the Russian word metrika ends in a. The left pair has subscript g; at the right, separately, $L_g : TG_g \to T^*G_g$.

$G = SO(3)$. geodesics — rotation of a rigid body about a fixed point (metric — kinetic energy).



Original source details: GELFAND-P000123

Diagram and typed description. After $SO(3)$, a separate full stop; then geodesics — rotation of a rigid body about a fixed point. On the next line, parentheses: metric — kinetic energy.

$$G = \mathrm{SDiff}\, D. \qquad \langle a, b\rangle = \int_D (a, b)\, dx.$$

Ideal fluid flows — geodesics.



Original source details: GELFAND-P000123

Diagram and typed description. The integral has lower subscript D, and the integrand pair (a, b) is in round brackets. A separate next line: Ideal fluid flows — geodesics.

$$G: \quad x \to ax + b \qquad a > 0.$$

[Crossed out: a short unreadable sign or word beneath $a > 0$.]

Dynamical syst. — geodesic flow on the Lobachevsky plane. (Look at the inv. metric.)

Original source details: GELFAND-P000123

Uncertain reading. Below the active $a > 0$, a densely crossed-out entry with a lower loop; its letters and sign are unestablished.



Original source details: GELFAND-P000123

Diagram and typed description. Arrow $x \to ax + b$; above the crossed-out entry, $a > 0$. At the right, Dynamical syst. — geodesic flow on the Lobachevsky plane; below, separate parentheses: Look at the inv. metric.

$$\langle [a, b], c\rangle = \langle b, B(c, a)\rangle$$



Original source details: GELFAND-P000123

Diagram and typed description. In the first pair, $[a, b]$ and c; in the second, b and $B(c, a)$. After the round bracket, the final angle bracket, with a short thickening at the bottom.





Original source details: GELFAND-P000123

Diagram and typed description. At the left, a closed oval contour; inside, a curve with an arrow, $\dot{g}$, $g(t)$ and a separate lower point. The label $g(t)$ touches the contour's right edge.



Uncertain reading. Upper row $A \leftarrow TG_g \rightarrow A$, with wavy Λ- and Π-like signs above the arrows, subscripts g^{-1}. Separate downward arrows L and L_g. In the lower row, A^* at the left, T^*G_g in the middle, and at the right A with a dense star or overlaid stars: A^* / A^{**}. The lower right arrow points left. The lower left line has two overlaid tips in opposite directions; its active direction is unestablished. Wavy signs with stars and subscripts g^{-1} above the lower arrows.

Original source details: GELFAND-P000123

1966 yr. 7/II Kushnirenko: “On invariant dynamical systems”

I. M. Gelfand. on the envelop. alg. of a Lie algebra



Diagram and typed description. The year is in a rectangular frame with a thickened lower stroke. At 79, left and lower frame sides. Lines above and below II in the date; Kushnirenko and Gelfand. are underlined separately from the date and initials. The Russian title ends with sistem.

Original source details: GELFAND-P000124

Every Noeth. ring (without zero divisors) — an Ore ring

$$\begin{pmatrix} \forall a, b \neq 0 & \exists x, y \neq 0, \\ & xa = yb \end{pmatrix}$$



Diagram and typed description. Two dots over e in the Russian abbreviation nyot. At the right, parentheses with $\forall a, b \neq 0$, $\exists x, y \neq 0$; below, $xa = yb$.

Original source details: GELFAND-P000124

An Ore ring embeds in a skew field (these are est. classes) (elements of the form ab^{-1})



Diagram and typed description. In the right parentheses, these are est. classes; est. is an abbreviation. Below, separate parentheses: elements of the form ab^{-1}, with negative one on b.

Original source details: GELFAND-P000124

$a \neq 0, b \neq 0.$

$$\underbrace{a, ab, \ldots, ab^n}_{\mathcal{I}_n[?] \text{ — left ideal}}$$

(Noeth. — an increasing collection of left ideals stops.)



Uncertain reading. A long lower brace beneath the sequence. Below it, a capital I-/J-like letter with a lower loop and subscript n, then left ideal; its exact letter is unestablished. At the right, separate parentheses beginning Noeth.

Original source details: GELFAND-P000124

$$ab^{n+1} = x_0 a + x_1 ab + \cdots + x_n ab^n, \qquad x_0 a = (\quad) b$$



Diagram and typed description. In the first equality, powers $n+1$ and n, subscripts $0, 1, n$. In the second, after $x_0 a =$, round brackets with an empty interval, then b.

Original source details: GELFAND-P000124

Diff. oper. of [Crossed out: an f-n-like abbreviation.] Grin[?], this is a skew field!! (and conversely)



Uncertain reading. After of, a short densely cancelled entry with an f-like beginning. The following name reads Grin / Grim; its penultimate letter is unestablished.

Original source details: GELFAND-P000124



Original source details: GELFAND-P000124

Diagram and typed description. The line from Diff. oper. of through skew field!! has a common underline. A comma after the disputed name; at the right, separate parentheses: and conversely. Two exclamation marks.

$D_{n,k}$ — skew field of ratios of diff. oper. For different n and k, nonisom. $R_{n,k}$ — ring of diff. oper. in n variables (k param., commuting).



Original source details: GELFAND-P000124

Diagram and typed description. Two different capitals, D and R, with the same subscripts n, k. Beside R, separately, n variables and parentheses: k param., commuting.

a, $[a]$ — oper. leading term, principal part. In the leading part, p and q commute. $[ab] = [a][b]$

$$b = a_1 a_2^{-1} \qquad \text{Consider} \quad \frac{[a_1]}{[a_2]}$$

it depends only on b, and not on the manner of representation.



Original source details: GELFAND-P000124

Diagram and typed description. A separate comma at a, $[a]$. Square brackets around the principal parts; below, p and q, then $[ab] = [a][b]$.

Original source details: GELFAND-P000124

Diagram and typed description. In $b = a_1 a_2^{-1}$, negative one on a_2. At the right, a fraction with $[a_1]$ and $[a_2]$ in square brackets; below, it depends only on b, and not on the manner of representation.

Peremn.[?] under norm.[?] b[?]



Original source details: GELFAND-P000124

Uncertain reading. The next fragment: a Peremn.-like abbreviation, under, a norm.- / peremn.-like abbreviation, and a final v-/b-like letter at the line edge. The abbreviations and final letter are not unambiguously established; no continuation is visible after it.

det — a map to a commut. [Crossed out: two short signs or words.] gr. Universal det — a map to the quotient by the commutator subgroup. The same in a skew field, universal — ?

Original source details: GELFAND-P000124

Uncertain reading. Between commut. and gr., two separate dense cancellations. The first has an f-/f-ya-like lower stroke; the second, covered kom-like strokes. The active gr. is at the right of both.



Original source details: GELFAND-P000124

Diagram and typed description. At the start, Latin det; then Universal det — a map to the quotient by the commutator subgroup. The final phrase, The same in a skew field, universal — ?, ends with a question mark.

Find all automorphisms of this skew field (difficult problem). (Fourier tr. + multiplication by a function)



Original source details: GELFAND-P000124

Diagram and typed description. In the first line, all automorphisms of this skew field and parentheses: difficult problem. In the second, Fourier tr., a separate plus, then multiplication by a function.

Dimension. of a ring (algebra)



Original source details: GELFAND-P000124

Diagram and typed description. Dimension. is underlined once, of a ring with two separate lower lines. Parentheses: algebra, after ring.

$\alpha = (a_1, \ldots, a_s)$ — a set of generators



Original source details: GELFAND-P000124

Diagram and typed description. At the left, α; a tuple in round brackets, with extreme subscripts 1 and s. After the dash, a set of generators.

$$\sup_{\alpha} \overline{\lim}_{N\to\infty} \frac{d(\alpha, N)}{\ln N} = \mathrm{Dim}_{\chi[?]}(A)$$

$d(\alpha, N)$ — the number of linearly independent monomials of degree $\leq N$.



Uncertain reading. Below Dim, a dense χ- / z- / α-like sign; its exact reading is unestablished. At the right, round brackets with A.

Original source details: GELFAND-P000124



Diagram and typed description. A lower α at sup; a separate horizontal line above lim, with $N \to \infty$ below. Numerator $d(\alpha, N)$, denominator $\ln N$. At the right, separately, $d(\alpha, N)$ — the number of linearly independent monomials of degree $\leq N$.

Original source details: GELFAND-P000124

$$\dim R_{n,k} = 2n + k.$$



Diagram and typed description. In the final line, dim with small d, $R_{n,k}$ and $2n + k$, then a full stop.

Original source details: GELFAND-P000124

GELFAND-P000125

14/II M. S. Agranovich.



Original source details: GELFAND-P000125

Diagram and typed description. Lines above and below II in the date. Beneath the name M. S. Agranovich., two lines with oblique hatching between them.

$\sigma(x,\xi)$ — a fn. $x=(x^1,\dots,x^n)$, $\xi=(\xi_1,\dots,\xi_n)$.



Original source details: GELFAND-P000125

Diagram and typed description. The first sign is σ; the coordinates of x have superscripts $1, n$, and those of ξ have subscripts $1, n$.

Initially pos. homog. in ξ

$$\sigma(x,t\xi)=t^s\sigma(x,\xi),\qquad t>0,\quad s\geq 0.$$



Original source details: GELFAND-P000125

Diagram and typed description. The exponent of t is s. After $t>0$, a separate $s\geq 0$ followed by a period.

it [Crossed out: bud[?].] is called the symbol of the following oper.:



Uncertain reading. After it and before is called, a short crossed-out bud-like word; the exact reading of the covered strokes is undetermined.

Original source details: GELFAND-P000125

$$Au(x)=\text{[Crossed out: } F^{-1}_{\xi\to x}\sigma(x[?],\xi)(Fu)(\xi)]$$
$$F^{-1}_{\xi\to x}\sigma(x,\xi)(Fu)(\xi)=\sigma(x,D)u$$



Uncertain reading. After $Au(x)=$, a crossed-out formula with $F^{-1}_{\xi\to x}$, σ, parentheses and $(Fu)(\xi)$. Interior strokes, including the first argument of σ, are covered; the reading of the entire crossed-out expression remains incomplete. A separate active formula is to the right.

Original source details: GELFAND-P000125

Differential oper. (homog.)

$$A = \sum_{|\alpha|=m} a_\alpha(x) D^\alpha. \qquad D^\alpha = D_1^{\alpha_1} \cdots D_n^{\alpha_n}$$



Original source details: GELFAND-P000125

Diagram and typed description. The summation condition is $|\alpha| = m$. To the right of D^α are factors with subscripts $1, n$ and superscripts α_1, α_n.

$$D_j = -i \frac{\partial}{\partial x^{\alpha[?]}}.$$



Original source details: GELFAND-P000125

Uncertain reading. The superscript of x in the denominator has a rounded counter and a hooked upper stroke: α- / a- / i- / j-like. The exact sign is undetermined.

$$Au = F^{-1}_{\xi \to x} \sum a_\alpha(x) \xi^\alpha F u$$



Original source details: GELFAND-P000125

Diagram and typed description. Beneath F^{-1}, the direction $\xi \to x$. In the sum, $a_\alpha(x)$ and ξ^α, followed by Fu.

$\underline{s = 0}$ — a singular integral operator. In particular, the oper. of multiplication by the fn. $\sigma(x)$.



Original source details: GELFAND-P000125

Diagram and typed description. Only $s = 0$ is underlined. The second line says multiplication by the fn. $\sigma(x)$.

Another example $\Lambda = \sqrt{-\Delta}, \qquad \Lambda u = F^{-1}|\xi|Fu.$



Original source details: GELFAND-P000125

Diagram and typed description. Capital Λ appears twice. Under the root are a minus sign and Δ; to the right, the modulus $|\xi|$.





Original source details: GELFAND-P000125

Diagram and typed description. Two axes with arrows; the horizontal one is labelled $|\xi|$. A mark 1 on the vertical axis. The curve runs along zero, rises and becomes almost horizontal; the label is $\varphi(|\xi|)$. The right end of the curve extends beyond the horizontal arrow.

For $s < 0$ include the factor [Before σ, a K-like sign is crossed out.]

$$\underline{\varphi(|\xi|)\sigma(x,\xi)}$$

(the difference is inessential)



Original source details: GELFAND-P000125

Uncertain reading. Dense overlapping strokes at σ, including a K-like sign; the exact reading of the cancelled sign is undetermined. Beneath the product is a lower line with short vertical edges. To the right, a separate parenthesis: the difference is inessential.

Classical approach: expand $\sigma(x,\xi)$ in a series. Let $s = 0$.



Original source details: GELFAND-P000125

Diagram and typed description. Classical approach: is underlined. To the right, expand $\sigma(x,\xi)$ in a series; beneath it, Let $s = 0$.

$$\sigma(x,\xi) = \sum a_{mk}(x)Y_{mk}(\xi), \qquad |\xi| = 1$$

$|\xi|^m Y_{mk}(\xi)$ — a harmonic polyn. of degree m.



Original source details: GELFAND-P000125

Diagram and typed description. Both occurrences of Y have subscript mk. Beneath the first formula is $|\xi| = 1$; the next line has $|\xi|^m Y_{mk}(\xi)$ and harmonic polyn. of degree m.

$$Au = \sum a_{mk}(x) F^{-1} Y_{mk}(\xi) Fu \qquad (1)$$

$k = 0, 1, \ldots, k_m$, $Y_{00} \equiv 1$.



Original source details: GELFAND-P000125

Diagram and typed description. The formula has number (1) at the right. Beneath it, the range $k = 0, 1, \ldots, k_m$ and a separate $Y_{00} \equiv 1$.

[Crossed out: FY[?].] F of spherical fns. also gives spherical fns. (they arose from reps. of the rotation grp.)



Original source details: GELFAND-P000125

Uncertain reading. Before the active F, F- and Y-like signs are crossed out. The parenthesis they arose from reps. of the rotation grp. belongs to the following phrase.

$$m > 0, \qquad F^{-1} Y_{mk}(\xi) Fu = \int \frac{1}{\gamma_m[?]} \frac{Y_{mk}(x-y)}{|x-y|^n} u(y)\, dy \qquad (\text{v.p.})$$





Original source details: GELFAND-P000125

Uncertain reading. In the denominator of the separate fraction $1/(\gamma_m[?])$, a looped Greek sign with an upper crossing stroke; candidates γ_m and δ_m. Subscript m is visible.

[Crossed out: Au[?].]

$$Au = \text{v.p.} \int K(x, x-y)u(y)\,dy$$

(the calculations are formal)



Uncertain reading. To the left of the active Au, an earlier Au-like beginning is crossed out with several intersecting strokes, including a tall vertical one.

Original source details: GELFAND-P000125



Diagram and typed description. The active Au is to the right of the cancelled beginning. The integrand is $K(x, x-y)u(y)\,dy$, preceded by v.p.; to the right, the parenthesis the calculations are formal.

Original source details: GELFAND-P000125

3rd def. Consider the fn.

[Crossed out: $x - y$[?], parentheses and a z-like sign.] $K(x, z)$ pos. homog. in z of degree $-n$.



Diagram and typed description. A separate line beneath 3rd def. Then Consider the fn.

Original source details: GELFAND-P000125



Uncertain reading. Above the active $K(x, z)$, densely cancelled signs: an x-y-like portion, parentheses and a z-like sign at the right. The order and complete reading of the cancelled argument are undetermined.

Original source details: GELFAND-P000125

$$\int_{|z|=1} K(z[?], z)\, dS_z = 0.$$



Uncertain reading. The end says degree $-n$. Beneath the integral is $|z| = 1$, and dS has subscript z. The first argument of K is a z- / ξ- / x-like sign with dark horizontal strokes; its exact reading is undetermined. The second argument is z-like.

Original source details: GELFAND-P000125

Diagram and typed description. The frame around 80 has left and bottom sides.

Original source details: GELFAND-P000126

Let it stabilize as $x \to \infty$.

$$\sigma(x, \xi) = \sigma(\infty, \xi) + \sigma'(x, \xi)$$



Diagram and typed description. The first line has $x \to \infty$. In the decomposition, the last σ has a prime; the first summand has argument ∞.

Original source details: GELFAND-P000126

σ' is compactly supported in ξ.



Uncertain reading. After compactly supported in, a visible ξ-shaped sign with upper and lower horizontal strokes.

Original source details: GELFAND-P000126

$$\sigma(x, D) = \sigma(\infty, D) + \sigma'(x, D)$$



Diagram and typed description. The second argument is D in all three places. The last σ has a prime and is preceded by a plus sign.

Original source details: GELFAND-P000126

$$\widetilde{Au}[?] = \sigma(\infty, \xi[?])\widetilde{u} + \frac{1}{(2\pi)^{n/2}} \int \widetilde{\sigma}'(\xi - \eta, \eta)\widetilde{u}(\eta)\, d\eta \qquad (2)$$





Uncertain reading. A wavy line above Au; surrounding arcs at the left and below. The right portion at u and the equality sign is densely overwritten; the exact reading of the corrected strokes is undetermined.

Original source details: GELFAND-P000126



Uncertain reading. The second argument in $\sigma(\infty, \xi[?])$ is overwritten and ξ-like. The denominator is $(2\pi)^{n/2}$; the integrand is $\widetilde{\sigma}'(\xi - \eta, \eta)\widetilde{u}(\eta)\, d\eta$. Number (2) is at the left.

Original source details: GELFAND-P000126

Diagram and typed description. In the side bracket, the Latin names Cohn and Nirenberg, with and between them. The left line is almost straight and vertical, and the right line is curved.

Original source details: GELFAND-P000126

$\widetilde{\sigma}$ is the Fourier transf. in the 1st variable.



Diagram and typed description. A wavy line above σ. The end says in the 1st variable, with digit 1.

Original source details: GELFAND-P000126

To what extent are they equiv.? If the symbols are very good. [Crossed out: Was[?].]

Насколько они эквивал.? Если симв. очень хорошие. ~~Если~~





Uncertain reading. After good., a short cancelled word resembling Was; its middle strokes are covered by intersecting lines.

Original source details: GELFAND-P000126

In the general case the defs. are inequivalent (lead to different classes of oper.)

В общем случае опр. неэквив. (прив. к разн. кл. опер.)

Original source details: GELFAND-P000126

Diagram and typed description. After inequivalent, a separate parenthesis: lead to different classes of oper.

In which spaces the oper. is bounded.

$$H^\ell = W_2^{(\ell)}, \qquad \|u\|_\ell^2 = \int |\widetilde{u}|^2 (1+|\xi|^2)^\ell \, d\xi$$

В каких пр-вах опер. огран.

$H^\ell = W_2^{(\ell)}$ $\|u\|_\ell^2 = \int |\widetilde{u}|^2 (1+|\xi|^2)^\ell d\xi$

Original source details: GELFAND-P000126

Diagram and typed description. The superscript of H is ℓ; W has subscript 2 and superscript (ℓ). Both the norm and weight have ℓ; $|\widetilde{u}|$ and $|\xi|$ are squared.

$$\|Au\|_{\ell-s} \quad \text{[Crossed out: } \|[?]\|_s\text{]} \quad \leq C\|u\|_\ell$$

for a smooth fn. σ, expansion in a series is rapid.

$\|Au\|_{\ell-s}$ [illegible] $\leq C\|u\|_\ell$



Uncertain reading. Between the active left norm and $\leq C\|u\|_\ell$, a densely crossed-out term. Norm-like vertical lines and an s-like sign at the lower right are visible; the interior reading is undetermined.

Original source details: GELFAND-P000126



Original source details: GELFAND-P000126

Diagram and typed description. Two lines at the right: for a smooth fn. σ, then expansion in a series is rapid.

$$\Sigma : |\xi| = 1, \qquad \|\sigma(x,\xi)\|_{\Sigma,q} \le \text{const} \quad (\text{indep. of } x). \qquad (3)$$



Original source details: GELFAND-P000126

Diagram and typed description. The norm has subscripts Σ, q. The sign before const has a lower line; at the right, the parenthesis indep. of x. Number (3) is at the right.

The symbol is a fn. of x with values in $H_q(\Sigma)$.



Original source details: GELFAND-P000126

Diagram and typed description. The subscript of H is q, with Σ in parentheses.

Theorem. For $q > \dfrac{n-1}{2}$ and est. (3) holding, the sing. $\int$ oper. (1) is bounded in L_2. ($\|Au\|_0 \le C\|u\|_0$)



Original source details: GELFAND-P000126

Diagram and typed description. Theorem. is underlined. The condition is $q > (n-1)/2$, with references (3) and (1); the end has L_2 and a separate parenthesis with norms having subscript 0.

Lemma.

$$\|\sigma(x,\xi)\|_q^2 \sim \sum m^{2q} |a_{mk}|^2$$

($q = 0$ Parseval's equality, $q > 0$ properties of spherical fns.)



Original source details: GELFAND-P000126

Diagram and typed description. Lemma. is underlined. A dense wavy sign between the norm and sum; the exponent of m is $2q$, and a has subscripts mk. Beneath it, a separate parenthesis with $q = 0$ and $q > 0$.

Proof of the thm.

$$S_{\mu\nu} = \sum_{m=\mu}^{\nu} \sum_{k} a_{mk}(x) A_{mk} u.$$



Original source details: GELFAND-P000126

Diagram and typed description. Proof of the thm. is underlined. At the left, $S_{\mu\nu}$; at the right, the first sum has limits $m = \mu$ and ν, the second has subscript k, and the end is $A_{mk}u$.

$$|S_{\mu\nu}u|^2 \le \sum m^{2q}|a_{mk}(x)|^2 = \sum m^{-2q}|A_{mk}u|^2$$

Uncertain reading. Two horizontal lines between the sums, an equality sign. The exponent of the first m is $2q$, and that of the second is $-2q$.



Original source details: GELFAND-P000126

$$\int |S_{\mu\nu}u|^2\,dx \le [?]\|\sigma(x,\xi\|^2_{0,q}$$
$$\sup_x$$
$$\sum_{m=\mu}^{\nu} m^{-2q} \sum_k \int Y^2_{mk}(\xi)\widetilde{u}(\xi)\,d\xi$$

Uncertain reading. After dx, an overwritten $\le$- / $\Leftarrow$-like sign. No closing argument parenthesis is visible after ξ in the norm; sup x is written separately beneath it. Y_{mk} is squared; it is followed only by $\widetilde{u}(\xi)$, without a visible modulus or square.



Original source details: GELFAND-P000126

Use the identity

$$\sum_k Y_{mk}^2(\xi) = \text{const}\,(k_m + 1)$$



Original source details: GELFAND-P000126

Diagram and typed description. Use the identity precedes the formula. The sum has subscript k; at the right, the parenthesis $(k_m + 1)$.

(on spherical fns. with a given m, a nontriv. irred. rep. λ In the matrix



Original source details: GELFAND-P000126

Diagram and typed description. The bottom line ends with λ In the matrix; there is an opening parenthesis at the left, with no closing parenthesis on this image.

GELFAND-P000127

middle row of $Y_{mk}(\xi)$ (see the book Reps. of the rotation grp.) — and the matrix is unitary.



Original source details: GELFAND-P000127

Diagram and typed description. The first word is middle; then row of $Y_{mk}(\xi)$. At the right, the parenthesis see the book Reps. of the rotation grp.; beneath it, a separate line — and the matrix is unitary.

$$\int |S_{\mu\nu} u|^2 \, dx \le \|\sigma\|_{0,q}^2 \cdot \sum m^{2q} k_m \|u\|_0^2.$$



Original source details: GELFAND-P000127

Diagram and typed description. The exponent of m is $2q$, with no visible minus before 2. A separate multiplication dot follows the norm with subscripts $0, q$.

$$k_m \sim m^{n-2}, \qquad -2q + n - 2 < -1$$

Then the series will converge.



Original source details: GELFAND-P000127

Diagram and typed description. The first formula has k_m and exponent $n - 2$. The next line begins with a minus before $2q$, then $+n - 2 < -1$. At the right, Then the series will converge.

$q = \frac{n-1}{2}$. there will no longer be conv.



Original source details: GELFAND-P000127

Diagram and typed description. A period follows the fraction $(n-1)/2$; then there will no longer be conv.

No smoothness in ξ is needed.

Original source details: GELFAND-P000127

Diagram and typed description. After in, a dense ξ-shaped sign; the phrase says no smoothness is needed.

[Crossed out: 2nd thm.]



Original source details: GELFAND-P000127

Diagram and typed description. 2nd thm. is crossed out with two long lines.

Conditions on $K(x,z)$ in its terms



Original source details: GELFAND-P000127

Diagram and typed description. Two separate lines beneath $K(x,z)$. Conditions on is at the left, and in its terms at the right.

$$K(x,z) = \frac{k(x,z)}{|z|^n}$$



Original source details: GELFAND-P000127

Diagram and typed description. At the left, $K(x,z)$; at the right, numerator $k(x,z)$ and denominator $|z|^n$.

$$\|k(X,z)\|_q \le \text{const} \qquad q > -\frac{1}{2}$$
$$(\text{Norm on } |z|=1)$$



Diagram and typed description. The first argument of k is X-shaped. A short horizontal minus precedes $1/2$; a separate parenthesis says Norm on $|z| = 1$.

Original source details: GELFAND-P000127

Example ($n = 2$)

$$K(z) = \frac{z_1}{(z_1^2 + z_2^2)^{3/2}}.$$



Diagram and typed description. Example is underlined, with the parenthesis $n = 2$ beneath it. The numerator is z_1; the denominator is the sum of two squares to the power $3/2$.

Original source details: GELFAND-P000127

$$\widetilde{Au}(\xi) = \sigma(\infty,\xi)\widetilde{u}(\xi) + \frac{1}{(2\pi)^{n/2}} \int \widetilde{\sigma}'(\xi-\eta,\eta)\widetilde{u}(\eta)\,d\eta$$



Diagram and typed description. Wavy lines above Au, u and σ'. The denominator is $(2\pi)^{n/2}$. The arguments of $\widetilde{\sigma}'$ are $\xi - \eta, \eta$.

Original source details: GELFAND-P000127

$\sigma'(x,\xi)$ is smooth in X through order $n+1$.



Diagram and typed description. After in, a separate X-shaped sign. Two lines beneath $n+1$.

Original source details: GELFAND-P000127

$$|\widetilde{\sigma}'(\xi-\eta,\xi[?])| \le \frac{\text{const}}{(1+|\xi-\eta|^2)^{(n+1)/2}}.$$

Uncertain reading. The last argument at the left is densely overwritten and ξ- / η-like. The denominator at the right is $1+|\xi-\eta|^2$ to the power $(n+1)/2$. The exact reading of the overwritten argument is undetermined.





Original source details: GELFAND-P000127

Estimate: convolution with an $\int$ fn. And the oper. is bounded in L_2.



Original source details: GELFAND-P000127

Diagram and typed description. After with, a separate integral-like sign and fn. The second phrase is And the oper. is bounded in L_2.

$$\left| \int \widetilde{\sigma}'(\xi-\eta,\eta)\widetilde{u}(\eta)\,d\eta \right| \le c \int \left(\frac{1}{1+|\xi-\eta|^{\text{[illegible]}}} \right) \widetilde{u}(\eta)\,d\eta$$



Uncertain reading. The power of $|\xi-\eta|$ in the right denominator is densely corrected: $n+1$ / $(n+1)/2$; its exact reading is undetermined. Large parentheses surround the fraction; they are followed by $\widetilde{u}(\eta)$ without a visible modulus.

Original source details: GELFAND-P000127

1. Commutation formula.



Diagram and typed description. Digit 1 with a period; then Commutation formula.

Original source details: GELFAND-P000127

2. $A \cdot B - A \underset{\sigma_1\sigma_2}{\circ} B$ — lower order.



Diagram and typed description. A dot between the first A and B, and a circle in the second product. Beneath $A \circ B$, a separate $\sigma_1\sigma_2$; at the right, — lower order.

Original source details: GELFAND-P000127

Hence pseudolocality.



Diagram and typed description. A separate phrase Hence pseudolocality., with a period.

Original source details: GELFAND-P000127

[End of the expression crossed out: $u \longrightarrow$ [?].]
Generalization to manifolds and elliptic theory.



Uncertain reading. A u-like letter at the left, a long line with an arrow to the right and a densely cancelled endpoint. Looped and vertical strokes at the end; the complete reading is undetermined.

Original source details: GELFAND-P000127



Original source details: GELFAND-P000127

Diagram and typed description. The concluding phrase is Generalization to manifolds and elliptic theory. Elliptic is written with dense strokes.

GELFAND-P000128

Let us start again.
Sing. $\int$ operator: (of order 0)



Original source details: GELFAND-P000128

Diagram and typed description. Let us start again. is underlined. Below, Sing. and a separate integral-like sign; of order 0 in parentheses.

$$(1)\quad \widetilde{Au}(\xi) = F_{x\to\xi}\sigma(x,\xi)u(x)$$
$$(2)\quad \widetilde{Au}(\xi) = \sigma(x,\xi)\widetilde{u}(\xi) +$$

(C. and N.;) (early works)



Diagram and typed description. In both initial definitions, σ has no detached prime. In the second line, a plus follows $\widetilde{u}(\xi)$; no continuation is written. At the right, separate parentheses C. and N.; and early works.

Original source details: GELFAND-P000128

$$(1)\quad \widetilde{Au}(\xi) = \sigma(\infty,\xi)u(\xi) + \int \widetilde{\sigma}'(\xi-\eta,\xi)\widetilde{u}(\eta)\,d\eta$$



Diagram and typed description. The first term contains $u(\xi)$ with no tilde. In the integral, σ has a detached prime and a tilde; the second argument is ξ.

Original source details: GELFAND-P000128

$$(2) \quad \widetilde{\mathcal{A}[?]u}(\xi) = \sigma(\infty, \xi)u(\xi) + \int \widetilde{\sigma}'(\xi - \eta, \eta)\widetilde{u}(\eta)\, d\eta$$



Original source details: GELFAND-P000128

Uncertain reading. The second operator sign is heavily overwritten: $\mathcal{A}$- / B-like, with a tilde above it and u. The exact overwritten letter is unresolved. The first term again has $u(\xi)$ without a tilde.

But they differ by an operator of lower order (-1).

$$|\widetilde{Au} - \mathcal{A}u| = \int [\widetilde{\sigma}'(\xi - \eta, \xi) - \widetilde{\sigma}'(\xi - \eta, \eta)]\widetilde{u}(\eta)\, d\eta$$



Original source details: GELFAND-P000128

Diagram and typed description. At the left, vertical bars and a tilde only above the first Au; the second operator is calligraphic. At the right, an integral without an outer modulus, the difference in square brackets.

$$\mathcal{A}^* = B[?] \qquad \mathcal{A}$$



Uncertain reading. After calligraphic $A^* =$, a heavily overwritten looped B-like sign. Beneath it, $\overline{\sigma}$. At the right, a separate calligraphic A-like letter; its connection to the equality is unresolved.

Original source details: GELFAND-P000128

(All this is done by Taylor's formula)



Diagram and typed description. The entire phrase is in parentheses; the source contraction for formula and Taylor's name.

Original source details: GELFAND-P000128

Gelfand's question:

Can polyn.[?] be replaced by others, so as to obtain the same algebra.



Uncertain reading. The source contraction after replaced: многочл. / многом.; the exact final part is unresolved. Gelfand's question: is underlined.

Original source details: GELFAND-P000128

The symbol is defined on the cotang. bundle.



Diagram and typed description. A separate phrase: The symbol is defined on the cotang. bundle.

Original source details: GELFAND-P000128

21/II–66 I. M. Gelfand. (works of Gelfand, Graev, Shapiro)



Original source details: GELFAND-P000128

Diagram and typed description. II has horizontal lines above and below. Date 21/II–66. The name I. M. Gelfand. is underlined; at the right, parentheses with three surnames.

Consider R^n or C^n. The $\int$ of functions over k-dim. subspaces are given.

? How to recover the function itself.



Original source details: GELFAND-P000128

Diagram and typed description. At the left, a separate question mark. In the first line, R^n, C^n and a separate integral-like sign before the contraction for functions.

(E.g. over lines in 3-dim. space. Over all of them is too much, [Crossed out: 6 param.[?]] 4 param. What needs to be known. which functions can result.



Original source details: GELFAND-P000128

Uncertain reading. Before 4 param., 6 пар. / 6-пар. is crossed out; horizontal lines cross the contraction, and a separate hyphen is unresolved. The initial parenthesis in this passage has no visible closure.

Knowing $\int$ over lines $\Rightarrow$ $\int$ over planes $\Rightarrow$ the function (:)



Original source details: GELFAND-P000128

Diagram and typed description. Two separate $\Rightarrow$ signs; after the function, parentheses containing a colon.

But if a 3-param. family of lines?

An explicit formula cannot be obtained in the general case.

— . —



Original source details: GELFAND-P000128

Diagram and typed description. After the question, a separate sentence about an explicit formula. Below, two horizontal strokes with a dot between.

R^n Consider k-dim. subspaces with measure h — a notion of volume is given in them. (k-dim. plane with a frame (unit parallelep.))



Original source details: GELFAND-P000128

Diagram and typed description. After measure, a separate h-like sign. At the end, two nested parentheses, frame and unit parallelep.

$H_{n,k}$ — the set of all such k-dim. planes with volume.

They are parallel if there exists a translation taking one into the other with volume preserved.



Original source details: GELFAND-P000128

Diagram and typed description. The subscript of H is n, k. The final sentence ends with volume preserved.

GELFAND-P000129

$G'_{n,k}$ — this is the set of equivalence classes under the relation of parallelism.



Original source details: GELFAND-P000129

Diagram and typed description. A detached prime above G, and subscripts n, k. The phrase ends with parallelism.

$$f(x) \Rightarrow \varphi(h) = \int_h f(x)\, d\sigma$$

a function on $H_{n,k}$.



Original source details: GELFAND-P000129

Diagram and typed description. The integral has subscript h; at the right, $d\sigma$. A separate phrase: a function on $H_{n,k}$.

Conditions on $\varphi(h)$ — ?

how to find $f(x)$ from $\varphi(h)$ [Crossed-out sign: illegible] in the most economical way?



Original source details: GELFAND-P000129

Uncertain reading. After $f(x)$, a dense crossed-out B-like sign; its exact reading is unresolved. The active sentence continues with most.

§1. Construction of the operator $\mathcal{X}$[?].



Uncertain reading. The operator sign is X-like / χ; the exact notation is unresolved. The same sign recurs in the concluding line. A straight underline beneath §1, a wavy one beneath the title.

Original source details: GELFAND-P000129

S_β. $\beta \in R^n$. Consider all k-dim. [Crossed out: subsp.] [Inserted above: hyperpl.], passing through β.

One parallel will be singled out.



Diagram and typed description. Subsp. is crossed out, hyperpl. inserted above the line. The active line has k-dim., passing through β; below, One parallel will be singled out.

Original source details: GELFAND-P000129

$$S_\beta : G'_{n,k} \longrightarrow H_{n,k}$$

This is a global section.

consider $H_{n,k} \to G'_{n,k}$.

Original source details: GELFAND-P000129

Diagram and typed description. The subscript of S is β. In the first map, the arrow goes from $G'_{n,k}$ to $H_{n,k}$; in the next line, the opposite direction.

$$S^*_\beta : \quad \varphi(h) \to \varphi(\alpha, \beta), \qquad \alpha \in G'_{n,k}$$

With β fixed, we obtain a function on $G'_{n,k}$.



Original source details: GELFAND-P000129

Diagram and typed description. A superscript star on S_β. An arrow after $\varphi(h)$, then $\varphi(\alpha, \beta)$; at the right, $\alpha \in G'_{n,k}$.

R^n consider a symm. multilinear form $B(\xi_1, \ldots, \xi_k)$, $\xi_i \in R^n$.



Original source details: GELFAND-P000129

Diagram and typed description. Symm. multilinear form and $B(\xi_1, \ldots, \xi_k)$. The exponent on the last R is n.

From it is constructed a skew-symm. form [Crossed out: from[?]] [Inserted above: of] k^2 vectors



Uncertain reading. Beneath the inserted of, a short heavily crossed-out word, resembling source из; its exact reading is unresolved. Then k^2 vectors.





Original source details: GELFAND-P000129

$$\Xi = \begin{Vmatrix} \xi_{11} & \cdots & \xi_{1k} \\ \xi_{21} & \cdots & \xi_{2k} \\ \\ \xi_{k1} & \cdots & \xi_{kk} \end{Vmatrix}.$$



Diagram and typed description. Double vertical bars, rows with first indices 1, 2, k, and horizontal dots. There is a blank gap between the second and last rows; no vertical dots are visible.

Original source details: GELFAND-P000129

$$\mathrm{Det}_B(\Xi) = \sum \pm B(\ldots) —$$

— a number depending on the entries of [Crossed-out sign: illegible] Ξ.



Uncertain reading. Before the active Ξ, a short crossed-out vertical sign; its exact reading is unresolved. In the preceding line, $\sum \pm B(\ldots)$ and a separate stroke at the right.

Original source details: GELFAND-P000129

For vectors $\xi \in R^1$, $B = \xi_1 \cdots \xi_k$ this is the ordinary det.



Diagram and typed description. The exponent on R is a separate digit 1. Then the product $\xi_1 \cdots \xi_k$ and ordinary det.



Original source details: GELFAND-P000129

(lin. with a constant term — inhomog.)



Original source details: GELFAND-P000129

Diagram and typed description. A separate parenthesis: lin. with a constant term — inhomog.

Remark. If B is defined on a quotient space (B vanishes on $\alpha_0 \subset R^n$, [Crossed out: would have to[?]] $B = 0$ if at least 1 vector is in α_0, then $\mathrm{Det}_B(\Xi)$ too is in fact defined for ξ_{jk} from R^n/α_0 (does not depend on the choice of representative)



Original source details: GELFAND-P000129

Uncertain reading. The source words resembling должны бы are crossed out; their exact reading is unresolved. The first word after the opening parenthesis is B-like, then vanishes on $\alpha_0 \subset R^n$. Remark. has a wavy underline.



Original source details: GELFAND-P000129

Diagram and typed description. After the condition $B = 0$ if at least 1 vector is in α_0, the text continues through R^n/α_0 and the parenthesis does not depend on the choice of representative. The initial parenthesis before B has no separate visible closure.

$\mathcal{X}$[?]$\varphi(h)$ will be a differential form on $G'_{n,k}$ with coefficients depending on α.



Original source details: GELFAND-P000129

Diagram and typed description. The operator sign before $\varphi(h)$ repeats the sign in the title. The last line reads with coefficients depending on α.

GELFAND-P000130

$$S^*_\beta \varphi(h) = \varphi(\alpha, \beta)$$



Original source details: GELFAND-P000130

Diagram and typed description. Subscript β and superscript star on S. At the right, $\varphi(\alpha, \beta)$.

If we fix $\alpha[?] = \alpha_0$ and move β along α_0, nothing changes. (Depends not on β, but not [нем./мен.?], when β moves $\| \alpha$).



Original source details: GELFAND-P000130

Uncertain reading. Before $= \alpha_0$, a heavily overwritten α-like letter with loops and a vertical stroke; the exact reading is unresolved.



Original source details: GELFAND-P000130

Uncertain reading. After but not, the source contraction нем. / мен.; the exact reading and expansion are unresolved. The parenthesis begins: Depends not on β.

Fix $\varphi(\alpha_0, \beta)$, consider $d^k_\beta \varphi(\alpha_0, \beta)$ — — a symm. k-linear form of k differentials $d\beta$.



Original source details: GELFAND-P000130

Diagram and typed description. Superscript k and subscript β on d. A separate dash after the expression, and another at the start of the next line; then k-linear and k differentials $d\beta$.

It is defined not from β, but from the quotient by α_0. Defined on the quotient space.



Original source details: GELFAND-P000130

Diagram and typed description. The phrase not from β, but from the quotient by α_0. Then Defined on the quotient space.

Consider k^2 vectors ξ_{ij}, construct from this form

$$\mathrm{Det}_{d^k_\beta(\varphi(\alpha_0,\beta))}(\Xi)$$



Original source details: GELFAND-P000130

Diagram and typed description. The entire expression $d^k_\beta(\varphi(\alpha_0,\beta))$ is beneath Det; at the right, large parentheses containing Ξ. In the line above, k^2 vectors ξ_{ij}.

This depends on the vectors ξ up to vectors of α_0.



Original source details: GELFAND-P000130

Diagram and typed description. Up to vectors of α_0 at the end of a separate line.

Theorem. Construct from it a skew-symm. differential form in $G'_{n,k}$.



Original source details: GELFAND-P000130

Diagram and typed description. Beneath Theorem., a separate long line to the right, two vertical strokes and two looped portions to their left. A typographic rendition of the strokes is provided alongside; there are no labels or stated geometric meaning.

Take a frame in the plane α_0, nearby frames $e_1, \dots, e_{n[?]}$, $e'_i = e_i + \xi_i$.

ξ_i — increments.



Uncertain reading. The last subscript on e is n-like; its exact reading is unresolved. At the right, the formula $e'_i = e_i + \xi_i$, and beneath it, ξ_i — increments.



Original source details: GELFAND-P000130

(planes up to small quantities of higher order)

They define the same plane $\Leftrightarrow \xi_i - \widetilde{\xi_i} \in \alpha_0$.



Diagram and typed description. After $\Leftrightarrow$, two ξ with subscripts i and a short minus between them; a tilde over the second. At the right, $\in \alpha_0$.

Original source details: GELFAND-P000130

k nearby planes

$$e'_{ij} = e_i + \xi_{ij} \qquad j = 1, \dots, k$$

Consider as Ξ a matrix defining k nearby planes.



Diagram and typed description. Two subscripts i, j on e'; at the right, $j = 1, \dots, k$. The next line contains Ξ and k nearby planes.

Original source details: GELFAND-P000130

Theorem 1.

1. [Crossed-out B-like sign: illegible] $\mathrm{Det}_B(\Xi)$ depends only on the position of the planes, and not on the matrix itself.

Теорема 1. 1. Det$_B(\Xi)$ зав. только от положе. плоск., а не самой матр.



Original source details: GELFAND-P000130

Uncertain reading. Between 1. and the active Det, a dense B-like sign or short entry is crossed out; its full reading is unresolved.

2. The resulting form is a k-form (skew.) in $G'_{n,k}$.

2. Получ. форма есть к-форма (кос.) в $G'_{n,k}$.

Original source details: GELFAND-P000130

Diagram and typed description. The second item contains k-form, the parenthesis skew. and $G'_{n,k}$.

$$\sum \varphi \ldots \quad d\alpha_1 \wedge [?] \ldots$$

$d\alpha_i$ — some coordinates in G.

$\Sigma\varphi\ldots$ $d\alpha_1\Lambda\ldots$ $d\alpha_i$ – какие-то коорд. в G.

Original source details: GELFAND-P000130

Uncertain reading. Ellipses after φ and after $d\alpha_1$ with a $\wedge$- / Λ-like sign. The exact notation of the sign is unresolved; the remaining factors and indices are not written out.

It is called $\mathcal{X}[?]\varphi$.



Original source details: GELFAND-P000130

Uncertain reading. After called, an X-like / χ-like operator sign before φ; its exact notation is unresolved.

Theorem 2. For $\varphi(h)$ to be the $\int$ of $f(x)$ over h, it is necessary and sufficient that $\mathcal{X}[?]\varphi$ be a closed form, i.e.



Original source details: GELFAND-P000130

Diagram and typed description. Theorem 2. is underlined. The full sentence contains necessary and sufficient, and a closed form, i.e.

$$d\mathcal{X}[?]\varphi \text{ must } = 0$$

(system of differential equations — — equations of the family)



Original source details: GELFAND-P000130

Diagram and typed description. After the operator expression, the word must, an equals sign and 0. At the right, parentheses with system of differential equations, two dashes at the line junction, and equations of the family.

GELFAND-P000131

A form in α and β: $\psi[?](\alpha,\beta)\,d\alpha$.



Original source details: GELFAND-P000131

Uncertain reading. The first letter of the form has an open left branch, a right loop and a downward stroke: ψ / φ. Its exact notation is unresolved.

A form on $R^n \times G'_{n,k}$. One can prove that it is defined on H — a form on H which transforms with the map

$$\pi : H_{n,k} \longrightarrow G'_{n,k}.$$

Forms on G': π^* assigns a form on H. Consider the forms from H (obtained),



Original source details: GELFAND-P000131

Diagram and typed description. The first product contains R^n and $G'_{n,k}$. The map goes from $H_{n,k}$ to $G'_{n,k}$; below, a separate π^*, a form on H and the parenthesis obtained.

[Crossed out: a short unreadable sign.] tensor mult. by fns. on H. These are precisely the forms on H with coeffs. $d\alpha$.

Uncertain reading. Before tensor mult., a short dense sign with loops and crossing strokes is cancelled; its full reading is unresolved.

Original source details: GELFAND-P000131

Thm. 3. Let γ be a curv. [Crossed out: several unreadable letters or strokes.] k-dimensional cycle in $G'_{n,k}$.



Uncertain reading. Between curv. and k-dimensional, a short entry is densely crossed out. Loops are visible below; its exact reading is unresolved. Thm. 3. is underlined.

Original source details: GELFAND-P000131

$$\int_\gamma \mathcal{X}[?]\psi[?] = C_\gamma f(\beta).$$

Uncertain reading. The sign after the integral has crossing loops: X-like / χ / κ; its exact notation is unresolved. Below, the same sign is called a diff. oper.

Original source details: GELFAND-P000131



Diagram and typed description. In both occurrences of $C_\gamma f(\beta)$, a tall thin opening parenthesis follows f; no separate upper stroke on f is visible.

Original source details: GELFAND-P000131

C_γ — up to π, is the intersection index of γ with the Euler cycle (all k-dim. subspaces lying in a $(k+1)$-dimensional space).



Diagram and typed description. After up to, a separate π with a long upper stroke. The parenthesis contains all k-dim. subspaces and a $(k+1)$-dimensional space; the source word for cycle continues at the beginning of the lower line.

Original source details: GELFAND-P000131

For some parities there is no local inversion formula ([Crossed out: only k-dim.[?]] cf. Radon).



Uncertain reading. In the parentheses before cf. Radon, horizontal lines cancel an entry with parts resembling only and k-dim.; the complete reading of the covered strokes is unresolved.

Original source details: GELFAND-P000131

In C^n there is an analytic formula, but there $C_\gamma \neq 0$ always. There is always an inversion formula there. One must know not only ψ[?], but also its derivatives.



Diagram and typed description. The first phrase says parities. The next part contains C^n, then $C_\gamma \neq 0$ and a separate sentence about an inversion formula. The lower line ends with its derivatives.

Original source details: GELFAND-P000131

[Crossed out: a beginning resembling $\delta(h) =$.]

Original source details: GELFAND-P000131

Uncertain reading. To the left of the active integral, an earlier $\delta(h) =$ entry is crossed out by two long lines. The upper part of the opening parenthesis is thin; the covered interior strokes remain unread.

$$\int_h f(x)\, d\mu = \delta(h) \cdot f(x).$$

[At right:] in h, Eucl. measure.



Original source details: GELFAND-P000131

Diagram and typed description. The integral has subscript h; at the right, a dot between $\delta(h)$ and $f(x)$. A separate right-hand note: in h, Eucl. measure.

$$C_\gamma f(\beta) = \int_\gamma \mathcal{X}[?]\psi[?](h).$$

$$C_\gamma(\delta(x-\beta), f(x)) = \int_\gamma \mathcal{X}[?](\delta(h), f(x)).$$

$$C_\gamma \delta(x-\beta) = \int_\gamma \mathcal{X}[?]\delta(h).$$



Diagram and typed description. In the formulas with $\delta(x-\beta)$ and $\delta(h)$, the tall thin strokes form opening parentheses; no separate apostrophe between the letter and parenthesis is visible. In the penultimate line, both pairings are in round brackets.

Original source details: GELFAND-P000131

[At right:] $\mathcal{X}$[?] — diff. oper.; $\int$ — over the cycle γ.



Diagram and typed description. The right-hand note contains the operator sign and diff. oper.; the next line is the integral over the cycle γ. Beneath the formula, two horizontal strokes with a dot between them.

Original source details: GELFAND-P000131

In C^n lines are given by parametric eqns.

$$x = \alpha t + \beta.$$

$$(\delta(h), f) = \int f(\alpha t + \beta)\, dt\, d\bar{t}.$$



Diagram and typed description. The parametric equation has plus β. In the last line, the round pairing $\delta(h), f$ is at the left; the integrand is $f(\alpha t + \beta)$, followed by dt and $d\bar{t}$, with a separate bar only over the final t.

Original source details: GELFAND-P000131

GELFAND-P000132

$\mathcal{X}$[?] — forms of type $(1[?], 1)$.



Uncertain reading. Intersecting strokes in the first numeral of type $(1, 1)$; a 1 / 4-like reading. The overwritten numeral has not been read definitively.

Original source details: GELFAND-P000132

$$\mathcal{X}[?]\psi[?] = \sum_{i=1}^{n} \left(\frac{\partial^{n[?]}}{\partial \beta_i} d\alpha_i \cdot \sum_{i=1}^{n} \frac{\partial}{\partial \overline{\beta}_i} d\overline{\alpha}_i \right) \psi[?].$$



Uncertain reading. A dense raised n-like sign at the first ∂; the covered strokes have not been read.

Original source details: GELFAND-P000132

Uncertain reading. The intersecting looped operator is X-like / χ / κ. The form letter has an open left branch, a right loop and a descending stroke: ψ / φ. The precise symbols remain uncertain. A separate dot stands between the first $d\alpha_i$ and the second sum.



Original source details: GELFAND-P000132

Final form.:

$$C_\gamma \delta(x) = \int_\gamma \left(\sum \frac{\partial}{\partial \beta_i} d\alpha_i \wedge \sum \frac{\partial}{\partial \overline{\beta}_i} d\overline{\alpha}_i \right)$$



Diagram and typed description. The left side is $C_\gamma \delta(x)$; the integral has subscript γ. A $\wedge$ stands between the sums in parentheses. The heading Final form.: is underlined.

Original source details: GELFAND-P000132

[At right, crossed out: an entry resembling $\delta(x - \beta)$ and unread strokes.]

Uncertain reading. To the right of the parenthesis, a densely cancelled entry has a δ-like beginning, parentheses and a β-like part; the complete former kernel and subsequent strokes remain unread.

Original source details: GELFAND-P000132

[Below at right, crossed out:]

$$\delta(\alpha_1 x \text{[?]} \beta_1, \ldots, \alpha_{n-1} x \text{[?]} \beta_{n-1})|_{\beta=0} .$$



Uncertain reading. The cancelled line begins with $\delta(\alpha_1 x \ldots \beta_1, \ldots)$ and ends with $|_{\beta=0}$. Lines cross the intermediate signs by β_i; their precise reading remains uncertain.

Original source details: GELFAND-P000132

[Inserted below:]

$$\delta(x_1 - \alpha_1 x_n - \beta_1, \ldots, x_{n-1} - \alpha_{n-1} x_n - \beta_{n-1})\, d\text{[?]}$$



Uncertain reading. A dense overwritten d- / x-like sign follows the inserted kernel. Its precise reading remains uncertain.

Original source details: GELFAND-P000132

Lines[?] dep. on fewer param., not $2n$.

Original source details: GELFAND-P000132

Uncertain reading. The ending of the first word permits a singular or plural reading; its precise reading remains uncertain. The remainder reads dep. on fewer param., not $2n$.

Klein's work on the top. (Karpelevich) (1896) (4 lectures at Princeton).

Original source details: GELFAND-P000132

Diagram and typed description. Klein's work on the top. has a straight underline. The name in parentheses is followed by 1896; farther right, 4 lectures at Princeton, with the last words below.

One point fixed. Rot. of the top — a curve in the group of rot. of 3-dim. space. Coord. in this group. 2 ways (Euler angles φ, θ, ψ). Product of three rot., [Crossed out: a short dense sign.] about axes Z, X and Z.



Uncertain reading. Before about axes, short dense К- / и-like strokes are crossed out. The complete reading remains uncertain.

Original source details: GELFAND-P000132

Isom. of $SO(3)$ and the gr. of fractional-lin. subst.

$$z \longrightarrow \frac{\alpha z + \beta}{\gamma z + \delta}.$$

$\begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix}$ unitary with det. 1 — [Crossed out: an unread sign.] stereograph. projection.



Original source details: GELFAND-P000132

Diagram and typed description. The text reads Isom. of $SO(3)$ and the gr. of fractional-lin. subst.; at right, a fraction with $\alpha z + \beta$ and $\gamma z + \delta$. Below the line, a matrix and unitary with det. 1.

Uncertain reading. Between the dash and stereograph. projection is a dense cancelled sign resembling φ or an arrow. Its precise reading remains uncertain.

Original source details: GELFAND-P000132

(Rotate the sphere — fractional-lin. map of the plane.) (This is the 1st lecture.)
2nd lecture.



Diagram and typed description. Wavy lines under Karpelevich, under 1st lecture in parentheses, and under 2nd lecture.

Original source details: GELFAND-P000132

φ, ψ, θ sought as functions of time. $\begin{pmatrix} \alpha & \beta \\ \gamma & \delta \end{pmatrix}$ as functions of time are simpler. Eqs. of motion:

$$T = \frac{1}{2}(\varphi'^2 + \psi'^2 + 2\varphi'\psi' \cos\theta + \theta'^2).$$

[At right:] (All moments of inertia $= 1$ rel. to the point of attachment — sphere-top.)



Diagram and typed description. Primes and squares at φ, ψ, θ; the mixed term is $2\varphi'\psi' \cos\theta$. A separate parenthesis at right: All moments of inertia $= 1$ rel. to the point of attachment — sphere-top.

Original source details: GELFAND-P000132

Potential energy [Crossed out: a p- / ρ-like beginning.] $V = p$[?] $\cos\theta$.

Uncertain reading. Before V, a letter with a loop and a descending stroke is cancelled with long lines: p / ρ. The complete former beginning remains unread.

Original source details: GELFAND-P000132

p[?] — dist. to c. of g.



Uncertain reading. In V and in the following line, a letter p / ρ with a loop and a descending stroke. The precise symbol remains uncertain.

Original source details: GELFAND-P000132

θ — axis Z with c. of g. vert.



Diagram and typed description. Two segments from a common lower endpoint, one nearly vertical, the other sloping upward to the right. Two dense points lie on the oblique segment, with a p / ρ label below. The drawing has no angle arc or axis labels. Beside it: θ — axis Z with c. of g. vert.



Original source details: GELFAND-P000132

$$\frac{d}{dt}\frac{\partial T}{\partial \varphi'} = 0.$$

$$\begin{cases} \varphi' + 2\psi' \cos\theta = n, \\ \psi' + 2\varphi' \cos\theta = e, \\ T + V = h. \end{cases}$$



Diagram and typed description. In each of the first two lines, a clear 2 follows the plus. The right side of the first line is n, of the second e; the third line is $T + V = h$.

Original source details: GELFAND-P000132

Express φ', ψ' in terms of $\cos\theta = u$ and subst. into that eq.



Diagram and typed description. The addition $= u$ is above the end of $\cos\theta$. The last phrase ends with into that eq.

Original source details: GELFAND-P000132

$$dt = \frac{du}{\sqrt{U}}, \qquad d\varphi[?] = \frac{n - eu}{1 - u^2}\, dt.$$



Uncertain reading. The letter in the second differential has an open branch and a descending stroke: φ / ψ. The precise symbol remains uncertain.

Original source details: GELFAND-P000133

$$U = 2p[?]u^3 - 2hu^2 + 2u(\ldots).$$

A polynomial of degree 3. t — ellipt. $\int$. Its inversion is carried out.



Uncertain reading. After 2, a letter with a loop and a descending stroke: p / ρ. The first term is $2pu^3$, then a minus before $2hu^2$ and a plus before $2u(\ldots)$; the ellipsis is in parentheses.

Original source details: GELFAND-P000133

[Crossed out: a short unread beginning.] 28/II.

Uncertain reading. Before 28/II, a short looped sign is densely cancelled; its complete reading remains uncertain.

Original source details: GELFAND-P000133

Continuation of Agranovich's talk.



Diagram and typed description. The Roman II in the date has upper and lower bars. The heading Continuation of Agranovich's talk. has a wavy underline.

Original source details: GELFAND-P000133

$$Au(x) = \underset{\xi \to x}{F^{-1}_{\xi \to x}}\big(F_{x \to \xi}\, \sigma(x,\xi) u(x)\big).$$

$$\sigma(x, t\xi) = t^s \sigma(x, \xi).$$

This def. differs inessentially.



Diagram and typed description. A separate $\xi \to x$ below the outer F^{-1}; $x \to \xi$ below the inner F. The whole right side of the definition has a wavy underline. Below it, the condition with $t\xi$ and t^s.

Original source details: GELFAND-P000133

[In the right margin:] For $s < 0$, the symbol is mult. by a fn. cutting out the sing. at [Crossed out: an unread sign.] $\xi = 0$.



Uncertain reading. Between at and $\xi = 0$, a short densely cancelled entry; the covered strokes remain unread. The complete marginal note ends with $\xi = 0$.

Original source details: GELFAND-P000133

[At left, crossed out: $Au(x) =$ and an unread continuation.]



Uncertain reading. The beginning $Au(x) =$ of the cancelled line is visible; long lines and dense strokes cover its continuation.

Original source details: GELFAND-P000133

$\|u\|_{\ell+s} \geq$ [?] $C\|$[cancelled] $Au\|_{\ell}$.



Uncertain reading. The comparison sign is overwritten: $\geq$ / $\leq$. A dense sign before Au inside the right norm is cancelled. The altered strokes have not been read definitively.

Original source details: GELFAND-P000133

1) Boundedness theorem.

2) Composition theorem.

$$A_1 \underset{\sigma_1}{\cdot} A_2 \underset{\sigma_2}{} - A_1 \underset{\sigma_1 \cdot \sigma_2}{\circ} A_2 = T.$$

[At right:] ord. $s_1 + s_2 - 1$.



Diagram and typed description. A σ_1 below the first A_1, a σ_2 below A_2. Below $A_1 \circ A_2$, the entry $\sigma_1 \cdot \sigma_2$. Above at right, ord. $s_1 + s_2 - 1$.

Original source details: GELFAND-P000133

Corollaries.

1°. $\varphi(x)A - A\varphi(x)$ up to podch. kom.d. sovp.[?] with an oper. having symbol $\varphi(x)\sigma(x,\xi)$.



Uncertain reading. The uncertain abbreviations are retained in transliteration: podch. kom.d. sovp. / podch. kam.d. svya.; their full reading remains uncertain. A horizontal stroke stands between $\varphi(x)A$ and $A\varphi(x)$. Corollaries. has a wavy underline.

Original source details: GELFAND-P000133

2°. $\varphi(x)\cdot\psi(x)=0 \Rightarrow \varphi A(\psi\,\cdot)$ — an oper. of order 1 less. [Crossed out: a short unread word.] (With the commutator — will be 0.)



Uncertain reading. After order and before the parenthesis, a short densely cancelled entry. In parentheses: With the commutator — will be 0.

Original source details: GELFAND-P000133

3°. Let $s=0$. Suppose there is an estimate $\|Au\|_1 \le c\|u\|_0$ (smoothing oper.). Then the symbol is ident. 0 and the operator 0.



Diagram and typed description. The left norm has subscript 1, the right 0; the sign is $\le$. Then smoothing oper. in parentheses, symbol ident. 0, and operator 0.

Original source details: GELFAND-P000133

Let $\sigma(x,\xi_0)\neq 0$. Consider the symbol $\bar\sigma\sigma>0$ at (x,ξ_0). Smoothing mult. by bounded will be smoothing. Zamen[?] levo-rymi[?] and Σ. One can obtain >0 everywhere. $\sigma(x_0,\xi)>0$ and $\neq 0$ can no longer be smoothing.



Uncertain reading. The divided word is retained in transliteration: levo-rymi / neko-rymi; the full reading remains uncertain. It is preceded by Zamen / Zatem. The final line reads $\sigma(x_0,\xi)>0$ and $\neq 0$ can no longer be smoothing.

Original source details: GELFAND-P000133

$3)$ Coordinate transformation theorem. $x=x(y)$ — inf. smooth, nondeg.



Diagram and typed description. Number $3)$, then Coordinate transformation theorem. After $x=x(y)$, the abbreviations inf. smooth, nondeg.

Original source details: GELFAND-P000133

$$\tilde{\sigma}(y,\eta) = \sigma\left(x(y), \left(\frac{\partial x}{\partial y}\right)^{\prime -1[?]} \eta\right).$$



Uncertain reading. After the matrix's closing parenthesis, a separate raised apostrophe-like / t-like stroke, followed by -1. The precise superscript reading remains uncertain.

Original source details: GELFAND-P000133

GELFAND-P000134

Transformation law, as for homogeneous char. polynomials [Crossed out: pseudodiff.[?]]. [Below the line:] diff. oper.



Uncertain reading. At the end of the first line, a word resembling pseudodiff. is crossed out; the covered letters remain incompletely read. Separately below: diff. oper.

Original source details: GELFAND-P000134

Consider $\varphi A\psi - \varphi\tilde{A}\psi = T$ — this is a subord. oper.

Authors. $s = 0$: Calderon, Zygmund, Mikhlin, Kohn, Nirenberg, Vishik and Eskin (Fourier series in x, with coeff. depending on ξ). $s > 0$ integer — Dynin[?]. But the orig. def. — Calderon, Zygmund. Sili, Kohn, Nirenberg — manifold without boundary.



Uncertain reading. In the name after $s > 0$ and in the following underlined pair, dense joined strokes: Dynin / Dynkin. The precise reading remains uncertain. In Latin script in the first line: Calderon, Zygmund, Kohn, Nirenberg.

Original source details: GELFAND-P000134

Sili and Dynin[?] — oper. on manifolds.



Original source details: GELFAND-P000134

Diagram and typed description. Below the pair of names, a double wavy strip with short cross-strokes.

Let $\underline{s=0}$. A — sing. $\int$ oper. on the manifold V. Consider φ and ψ on V. 1) $\operatorname{supp}\varphi \cap \operatorname{supp}\psi = \varnothing \Rightarrow \varphi A(\psi u) = Tu$ $(\|Tu\|_1 \le c\|u\|_0)$.

2) Let $\operatorname{supp}\varphi$ and ψ lie in a coord. nbd. Then

$$\varphi A\psi = \varphi A_\nu \psi + Tu,$$

where A_ν — a sing. $\int$ oper., written in local coordinates.



Diagram and typed description. In the first condition, two supports with empty intersection, then Tu and an estimate with indices 1 and 0. The local formula has $+Tu$ at right.

Original source details: GELFAND-P000134

The symbol is evidently well-defined as a function on the cotangent bundle. (A_ν on the overlap.) Hence, in particular, the symbol transformation formula.



Original source details: GELFAND-P000134

Diagram and typed description. Two overlapping rounded contours, x at left and y at right. Above, φ; below, ψ; inside the overlap, a small loop with a heavy point and an oblique stroke.



$$\varphi A\psi. = \varphi A_x\psi + T_1 = \varphi A_y\psi + T_2.$$

Hence

$$\begin{array}{ll} \varphi A_x\psi & -\varphi A_y\psi \quad \text{smoothing.} \\ \| & \\ \varphi \tilde{A}_y\psi + \text{smoothing.} & \end{array}$$

[At right:] Hence smoothing symbol.



Diagram and typed description. A separate point after the first ψ and before the equals sign. Below the first term, two vertical strokes, then $\varphi\tilde{A}_y\psi+$ smoothing. Separately at right: Hence smoothing symbol.

Original source details: GELFAND-P000134

$$A = \sum \varphi_\nu A, \qquad \psi_\nu = \begin{cases} 1 & \text{in a nbd. of supp}\,\varphi_\nu, \\ 0 & \text{outside the nbd.} \end{cases}$$

$$A = \sum \varphi_\nu A\psi_\nu + \text{smoothing.} = \sum \varphi_\nu A_\nu \psi_\nu + \text{smoothing.}$$



Diagram and typed description. In the first sum, only A follows φ_ν. The two cases for ψ_ν are 1 in a nbd. of the support of φ_ν and 0 outside the nbd. The lower line has two sums with ψ_ν; in the second, A also has subscript ν.

Original source details: GELFAND-P000134

Final remark: An operator is constructed from the symbol. $\sigma(x,\xi)$ on the cotang. bundle, $\sigma_\nu(x,\xi)$ on U_ν and a partition. An oper. of order ℓ[?] acts boundedly from $H_{\ell[?]} \to H_{\ell[?]}$.



Uncertain reading. The order letter and both indices have the same looped appearance: ℓ / e. Both spaces are written with the same index. Final remark: has a wavy underline.

Original source details: GELFAND-P000134

Composition thm.:

$$\underset{\sigma_1}{A} \cdot \underset{\sigma_2}{B} - \underset{\sigma_1\cdot\sigma_2}{A \circ B} = T.$$



Diagram and typed description. A σ_1 below A, a σ_2 below B, and $\sigma_1 \cdot \sigma_2$ below $A \circ B$. The circle is between A and B; the upper loop above this part belongs to iz (from) in the preceding line. The heading Composition thm.: has a wavy underline.

Original source details: GELFAND-P000134

GELFAND-P000135

Proof.

$$A = \sum \varphi_k A_k \psi_k + T, \qquad B = \sum \varphi_\ell B_\ell \psi_\ell + T_2.$$

$$AB = \sum_{k,\ell} \varphi_k A_k \overbrace{\psi_k \varphi_\ell}^{A^\circ[?]} B_\ell \psi_\ell + \ldots =$$

ψ_ℓ



Uncertain reading. An arc above $\psi_k \varphi_\ell$ has an A°- / T°- / t°-like label; the exact reading is unsettled. Below are two converging curved strokes and the label ψ_ℓ.

Original source details: GELFAND-P000135

$$= \sum_k \sum_\ell \varphi_k \, \psi_\ell \, A_\ell \, \psi_k \, \varphi_\ell \, B_\ell \psi_\ell . \quad =$$

$$= \sum_k \sum_\ell \varphi_k \, \overbrace{\psi_{\ell[?]} \, \tilde{A}_\ell \cdot (\varphi_\ell \cdot \psi_{k[?]})}^{} \cdot B_\ell \psi_\ell + \ldots =$$



Uncertain reading. Below the second line are two curved arrows pointing left. In the next line, $\psi_{\ell[?]}$ before $\tilde{A}_\ell$ is crossed out; $(\varphi_\ell \cdot \psi_{k[?]})$ is inserted above, with its second part heavily crossed out. Below the insertion are joined arcs and an angular insertion mark. The obscured indices remain partly unread.

Original source details: GELFAND-P000135

$$= \sum_\ell \varphi_\ell A_\ell \circ B_\ell \psi_\ell + \text{smooth.}$$

The theor. on compos. is proved.



Diagram and typed description. The first three product lines also end with an equals sign; the following lines begin with an equals sign.

Original source details: GELFAND-P000135

Original source details: GELFAND-P000135

Diagram and typed description. Two intersecting contours with diagonal hatching in their overlap. The upper label is $U_{\ell[?]}$, the lower $U_{k[?]}$; the dense indices remain unsettled.



Elliptic theory. A_s, $\sigma(P,\xi_P)$; ξ_P is a cotang. vector. Elliptic operator: $\sigma(P,\xi_P)\neq 0$ for $\xi_P\neq 0$ (if a matrix, then det). Theorem 1. Ellipticity is equivalent to being Noetherian. a) Prove that an elliptic oper. is Noetherian. Consider σ^{-1}, also a symbol, homog. of degree $\underline{\underline{-s}}$, $\sigma^{-1}\leftrightarrow B$.



Diagram and typed description. A has the subscript s. The degree $-s$ has a double underline.

Original source details: GELFAND-P000135

$$BA = I_1 + T_1, \qquad AB = I_{2[?]} + T_2.$$

Hence normal Noetherianity. $d(A) < \infty, \quad \beta(A) < \infty$.



Uncertain reading. The subscript below the second I is heavily overwritten; a 2-like sign is visible, while the former stroke remains unread.

Original source details: GELFAND-P000135

b) Noeth. $\Rightarrow$ ell. $s = 1$.

$$\|u\|_1 \le C(\|Au\|_0 + \|u\|_0)$$

from Noetherianity. Passage to R^n, elim. the depend. of the symb. on x. Functions with small supports and a symb. indep. of x. $\sigma(x_0, \xi_0) = 0$ and the est. leads to a contradiction:

$$\varphi(x) e^{i\lambda\langle x, \xi_0\rangle}.$$



Diagram and typed description. The exponent is $i\lambda\langle x, \xi_0\rangle$. The line above has $\sigma(x_0, \xi_0) = 0$.

Original source details: GELFAND-P000135

Theorem 2 (on smoothness). $Au = f, \quad s = 0$. Let $u \in H_0,\ f \in H_1 \ \Rightarrow\ u \in H_1$.

$$Au = f, \quad u + \underset{\substack{\uparrow \\ H_1 \text{ (smooth.)}}}{T_2} f = Bf \in H_1 \ \Rightarrow\ u \in H_1.$$



Diagram and typed description. T_2 is followed by f. Below T_2, an arrow points up from the label H_1 (smooth.).

Original source details: GELFAND-P000135

Theorem 3. Homotop. stability of the index $\chi(A) = d(A) - \beta(A)$.



Diagram and typed description. The final formula is $\chi(A) = d(A) - \beta(A)$.

Original source details: GELFAND-P000135

GELFAND-P000136

Under small deformations of the symbol, the index does not change. A continuous deform. is approx. by a smooth deform. The oper. A with $\sigma\left(x, \frac{\xi}{|\xi|}\right)$ and B with $\underset{s}{\sigma(x,\xi)}$ have the same index.



Diagram and typed description. An s is written separately beneath ξ in the second symbol. $B = A\Lambda^s$ is underlined; the margin has "up to smooth." with an oblique stroke and an angular line. Below $\chi(\Lambda^s)$ are two vertical strokes and 0. Below $|\xi|$ are two lines with short ends.

$$\underline{B = A\Lambda^s},$$

up to smooth. Λ symb. $\underline{\underline{|\xi|}}$

$$\chi(B) = \chi(A) + \underset{\|}{\chi(\Lambda^s)}.$$
$$0$$

Original source details: GELFAND-P000136

(Λ^s is a selfadj. symbol—and the index of a selfadj. oper. is 0.)

Index theorem. (Sili) V_n, $n \times n$ systems. $\sigma(P, \xi_P)$ is a unitary matrix.



Diagram and typed description. $S^*(V)$ and the sphere on the right are underlined. Below the first space, $2n-1$ is underlined, with "dim." beneath; an oblique stroke leads to the label "unit cotang. sphere".

$$\underline{S^*(V)} \xrightarrow{\sigma} U(n) \xrightarrow{\rho} \underline{S^{2n-1}}$$

$\underline{2n-1}$ dim. — unit cotang. sphere

Original source details: GELFAND-P000136

$$\operatorname{ind} A = \frac{1}{(n-1)!} \deg(\rho \circ \sigma) \iff \operatorname{ind}_{(n-1)\times(n-1)} B = 0.$$

The operation $A\#B$ is used—$\operatorname{ind} A\#B = \operatorname{ind} A \cdot \operatorname{ind} B$. For boundaries of domains in R^{n+1}, such a formula holds. (the right side is correct) Left formula.



Diagram and typed description. Below B, separately, is $(n-1) \times (n-1)$. The product of indices on the right has a dot; after ind on the left is $A\#B$. The preceding line has $\rho \circ \sigma$.

Original source details: GELFAND-P000136

Hermander's approach. Theor. [Crossed out: two unread words] on change. It is inconvenient that the symbols are C^∞.



Uncertain reading. Before "on change" are two heavily crossed-out words. The obscured letters remain unread.

Original source details: GELFAND-P000136

$$e^{-i\lambda g} A[f e^{ig\lambda}] \sim \sum_0^\infty P_j(f,g)\lambda^{s_j}, \qquad s_j \downarrow -\infty.$$



Diagram and typed description. The exponent on the left is $-i\lambda g$, and inside the first brackets it is $ig\lambda$; on the right are λ^{s_j} and $s_j \downarrow -\infty$. The lower summation limit is 0.



Original source details: GELFAND-P000136

$f \in C_0^\infty(\Omega), \quad g \in C^\infty(\Omega)$, real, grad $g \neq 0$ on supp f.

$$\lambda^{-s_N}\left[e^{-i\lambda g}A[fe^{i\lambda g}] - \sum_0^{N-1} P_j(f,g)\lambda^{s_j}\right] \in \text{a bounded set in } C^{q[?]}(\Omega).$$



Uncertain reading. The exponent on C has an upper loop and a long descending stroke: q / ℓ. The exact reading remains unsettled. Before the bracket is λ^{-s_N}, and the upper summation limit is $N-1$.



Original source details: GELFAND-P000136

$g \in$ a compact subset of $C^\infty(\Omega)$, and A must be a continuous oper. from C_0^∞ to C^∞.



Diagram and typed description. f belongs to $C_0^\infty(\Omega)$, and g is real; the text has grad $g \neq 0$ on supp f. Below are "$g \in$ a compact subset of $C^\infty(\Omega)$" and the continuity condition on A.

Original source details: GELFAND-P000136

$\Omega \subset R^n, \quad g = \langle x, \xi \rangle$ —fund. Consider analogous diff. oper.



Diagram and typed description. The final lines have $\Omega \subset R^n$, the linear phase $g = \langle x, \xi \rangle$, and "Consider analogous diff. oper.".

Original source details: GELFAND-P000136

GELFAND-P000137

Kirillov. Borel and Titse[?]. Reductive groups (part). Algebraic groups.



Uncertain reading. The second surname has dense final letters: Titse / Tits. The exact reading remains unsettled.

Original source details: GELFAND-P000137

Algebr. variety—a locally aff. scheme. From the ring A, construct a ringed space; Spec A—the prime ideals of A. $A = C[x_1, x_2]$. A prime ideal is generated either by $((x_1 - a), (x_2 - b))$, or by an irreduc. polynomial $I = (P(x_1, x_2))$. It is equipped with the
(point)
corresponding ringed-space structure.



Diagram and typed description. The point example has outer parentheses and separate parentheses around $x_1 - a$ and $x_2 - b$, with "(point)" below. The second example has $I = (P(x_1, x_2))$.

Original source details: GELFAND-P000137

An algebr. group—an algebr. variety, with multipl. $G \times G \to G$, given everywhere by a regular (rat.) function. Chevalley's struct. theorem: in every alg. group G there is a max. linear group G_0 such that G/G_0 is an abelian variety.



Diagram and typed description. The text has G_0 and G/G_0; the structural-theorem heading has a wavy underline.

Original source details: GELFAND-P000137

Linear groups are singled out from $GL(n, K)$—algebr. relations. [Crossed out: unread word].



Original source details: GELFAND-P000137

Uncertain reading. After the line about algebr. relations, a separate word is heavily crossed out; the obscured letters remain unread.

Abelian variety —complete and a group (complete—“comp.”—e.g. projective)—then the group is commutative.



Original source details: GELFAND-P000137

Diagram and typed description. “Complete” is explained in parentheses by “comp.” and the projective example; the phrase about commutativity follows.

Theorem: every hom. from ab. f.[?] into linear, and conversely, is trivial.



Original source details: GELFAND-P000137

Uncertain reading. After “ab.” is a rounded sign with a descending stroke: f. / gr. The exact reading remains unsettled.

For example, an algebraic torus—an ab. variety.



Original source details: GELFAND-P000137

Diagram and typed description. The text reads “algebraic torus—an ab. variety”.

The groups G_a, G_m—additive [Crossed out: unread short word] [Inserted above: and multi.] groups of the field (alg. groups). They are linear.



Uncertain reading. “And multi.” is inserted above the crossed-out short word. The obscured word remains unread.

Original source details: GELFAND-P000137

$$\begin{pmatrix} 1 & * \\ 0 & 1 \end{pmatrix} \qquad (x).$$



Diagram and typed description. On the left is a matrix with $1, *, 0, 1$; on the right, separately, is (x).

Original source details: GELFAND-P000137

Solvable groups: $\exists$ chain of normal subgroups

$$G_0 = G \supset G_1 \supset \ldots \supset G_m = \{e\}.$$

Such that $G_i/G_{i+1} = \begin{cases} G_{a[?]}, \\ G_m. \end{cases}$



Uncertain reading. In the first alternative, the subscript is a- / 0-like; the exact reading remains unsettled. The chain has $G_0 = G$, then G_1, and ends with $G_m = \{e\}$.

Original source details: GELFAND-P000137

$\Longleftrightarrow$ (imprec.[?] def. but reason.)



Uncertain reading. The first abbreviation resembles “netchno.” / “netochno.”; its exact letters remain unsettled. The following words are “def. but reason.”.

Original source details: GELFAND-P000137

Radical—max connected (Zariski top.) [Inserted above: solvable] normal subgroup.



Diagram and typed description. “Solvable” is inserted above “normal”, with an arc below and an angular insertion mark.

solvable

normal

Original source details: GELFAND-P000137



Uncertain reading. At the lower edge is $R_u(G)$, with two groups of long strokes and ditto marks; below the first is “(unip.[?] radical)”, with part of the first word obscured. On the right is “from nilpo:: [?] matrices”; the abbreviation and following marks remain unsettled.

$R_u(G)$ — —— 〃 ———— ———— 〃 —

(unip.[?] radical)

from nilpo:: [?] matrices



Original source details: GELFAND-P000137

GELFAND-P000138

(Nilpot. $(u-E)^k=0$.) Reductive group—its radical is a torus. (Direct product of several mult. groups of the field.)

$$G \text{ semisimple} \iff R(G)=1.$$



Diagram and typed description. $R(G)$ is written above "torus", with an arc below and an angular stroke.

$R(G)$

torus

Original source details: GELFAND-P000138

$GL(n,K)$—reductive, $SGL(n,K)$—semisimple. Classif. of semisimple groups: 4 infinite series and 5 exceptional (as for Lie groups). Basic notions—max torus and a root system.

$$\begin{pmatrix} a & b \\ -b & a \end{pmatrix}$$

real matrices—isom. to the group of complex numbers under mult.—a torus. All max tori are conjugate. (A root system is associated with a torus.)



Diagram and typed description. The text has $SGL(n,K)$. The real matrix has a, b above and $-b, a$ below.

Original source details: GELFAND-P000138

21/III.



Uncertain reading. Below the date is a dense wavy band: heavy underlining / a cancelled line. There are too few distinguishable letters.

Original source details: GELFAND-P000138

Borovikov.



Diagram and typed description. A rounded contour, with M below left and N above right; a chord, interior strokes and angles φ_M, φ_N. The label is "L with normals". The dense lower part and exact joins remain partly unread.



L with normals

Original source details: GELFAND-P000138

Theorem.

$$\iint \cos\varphi_M \cdot \cos\varphi_N \, dM \, dN = 2\pi S.$$

(S—area.)



Diagram and typed description. The visible formula has $\cos\varphi_M \cdot \cos\varphi_N \, dM \, dN = 2\pi S$; no distance denominator is visible.

Original source details: GELFAND-P000138

Gelfand.



Diagram and typed description. A rounded contour with a repeated left stroke, an interior section arc and the label $S(x)$ on the right. Short upper arcs are visible at the ends; the dense left join remains partly unread.

Original source details: GELFAND-P000138

$$M\left(\int S'^2(x)[?]\,dx\right) = V.$$



Uncertain reading. After S is a tall vertical stroke, then a separate raised 2: S'^2 / S^2 with an extra stroke. The exact reading remains unsettled.



Original source details: GELFAND-P000138

M—a universal constant (of the type of π).

Lidskii. (Viktor Borisovich.)

$$f(z) = \sum_{k=1}^{N} e^{\alpha_k z} \mathcal{P}_k(z).$$

$\mathcal{P}_k(z)$—polyn. and asympt. series in $\frac{1}{z}$.

$$\sum z_n^{-\sigma} = \text{[Crossed out: unread sign]}\ \zeta(\sigma).$$



Uncertain reading. Before $\zeta(\sigma)$ is a heavily crossed-out vertical sign; its former reading remains unsettled.

Original source details: GELFAND-P000138

$\zeta(\sigma)$ is always entire in σ. z_n are the zeros of $f(z)$.

$$\mathcal{P}_k(z) \simeq p_k(z) + \sum_{s=0}^{\infty} \frac{a_s}{z^s}.$$



Diagram and typed description. The first sum runs from $k = 1$ to N, with exponent $\alpha_k z$ and factor $\mathcal{P}_k(z)$. The lower sum runs from $s = 0$ to ∞.

Original source details: GELFAND-P000138

The usual ζ-function—not all 0[?] sin (not from $-\infty$). Proof—
— $\int$ Cauchy.



Uncertain reading. Between “all” and sin is a rounded sign: 0 / O. The contracted wording remains unsettled. In the proof note, a dash occurs both at the end of the line and before $\int$ Cauchy.

Original source details: GELFAND-P000138

Gindikin. Generalization of a parabolic eq.

$$\frac{\partial u}{\partial t} + F\left(\frac{1}{i}\frac{\partial}{\partial x}\right) u$$ [Crossed out: unread ending]



Uncertain reading. After u is a heavily crossed-out $= 0$-like ending; the exact reading remains unsettled.

Original source details: GELFAND-P000138

In place of $\frac{\partial u}{\partial t}$—any pseudo-operator $P\left(\frac{\partial}{\partial t}\right)$. A family of oper. is associated with P, such that with $\frac{\partial u}{\partial t}$ one obtains parabolic.



Diagram and typed description. The text has $P\left(\frac{\partial}{\partial t}\right)$; the final line associates P with a family of operators and repeats $\frac{\partial u}{\partial t}$.

Original source details: GELFAND-P000138

GELFAND-P000139

Instead of ellipt. — V-ellipt., map. in a cone, corresp. to hyperb. polyn.



Diagram and typed description. Opening line: V-ellipt., map. in a cone, corresp. to hyperb. polyn.

Original source details: GELFAND-P000139

Walk along a line — heat eqn.



Diagram and typed description. The word “Walk” is underlined; this stroke forms the top of the name’s frame. The bottom of the frame is reinforced.

Minlos.

Original source details: GELFAND-P000139

Ising model.



Original source details: GELFAND-P000139

Diagram and typed description. Lattice: four cells in each direction. The intersections are dense; individual filled cells or state markings have not been established.



L — subset of the lattice. (only at exist. [?] points)



Original source details: GELFAND-P000139

Uncertain reading. Middle abbreviation: “exist.” / “neighb.”; the dense joins do not permit a definite expansion.

$E(L)$ — number of neighbors.

$$\Xi[?] = \sum_L e^{-\beta E(L) - \mu N(L)}.$$

$N(L)$ — number of points.



Uncertain reading. Three separate horizontal bands before the sum: Ξ / stylized Z. The next formula has a Z-like sign.



Original source details: GELFAND-P000139

$$\lim \frac{\ln Z}{N} = f(\theta[?], \beta).$$



Uncertain reading. The first argument of f is a loop with a lower stroke: θ / ϑ / ρ; the exact reading is unsettled.

Original source details: GELFAND-P000139

And so on. And so forth [?]



Original source details: GELFAND-P000139

Uncertain reading. Final short entry: “and so forth” / “and T, λ” / “and T, ρ”. After “and” is an underlined t-/T-like sign; the final sign has an arch and two legs, Cyrillic п-/П-/Π-/n- or λ-/Λ-like, with a dot to its right.

Chapter 2

GELFAND-P000140

Gelfand seminar. $5/\overline{\text{IX}}$

1. There will be systematic stat. physics. (Minlos)
2. Status of pseudodifferential operators. (Vishik and Agranovich)
3. Algebraic groups (Kirillov)

5

Valuable information: Atiyah's lectures on the K-functor require no prior knowledge except the def. of a topological space and of an n-dimensional vector space (In degree of clarity [?] it is not comparable even to Milnor)

Original source details: GELFAND-P000140

Uncertain reading. The original word for "clarity" has a short stroke after its first three letters: a hyphen / a connecting handwriting stroke; the word is retained with this qualification.

4. Deformations of every kind. (provisional name: nonlinear analysis), including Kodaira and Spencer.

Hirzebruch's result. (Gelfand)

$$\begin{cases} z_1^3 + z_2^{3k-1[?]} + z_3^2 + z_4^2 + z_5^2 = 0 \\ |z_1|^2 + |z_2|^2 + |z_3|^{2[?]} + |z_4|^2 + [?]\,|z_5|^2 = \varepsilon \end{cases}$$

$3k-1$



Original source details: GELFAND-P000140

Uncertain reading. The exponent on z_2 begins $3k$; its ending is heavily overwritten: $3k-1$ / another overwritten ending. Separately at the right, $3k-1$ is circled with an oval. The written exponent on z_1 is 3.



Uncertain reading. In the second line, the right bar and exponent at $|z_3|$ are heavily overwritten; $|z_3|^2$ is given with this qualification. Between $|z_4|^2$ and $|z_5|^2$ the sign resembles $+$ but is dense.

Original source details: GELFAND-P000140

10 unk. and [crossed-out unread fragment] 3 eqns.



Uncertain reading. A short crossed-out fragment after "and": a 7-like sign and further dense strokes; the original content is unreadable.

Original source details: GELFAND-P000140

Milnor: this is homeomorphic to S^7

Hirzebruch: for $k = 1, 2, \ldots, 28$ there are different diff. structures there, and thereafter everything repeats periodically and these are all the Milnor spheres.

S^{11} there are 992 of them and they are obtained by such equations.

GELFAND-P000141

Bass (Kazhdan [?]) rigidity of arithm. subgroups.

Uncertain reading. The third letter of the Cyrillic surname between "Ka" and "dan" is a dense connected stroke: "Kazhdan" / "Kazdan".

Original source details: GELFAND-P000141

$SL(n, Z) \subset SL(n, R)$ — a rigid subgroup,

[A short opening and a word before "every" are crossed out.]



Uncertain reading. The initial crossed-out designation resembles "II." / Cyrillic "Te."; the following heavily cancelled word is unreadable.

Original source details: GELFAND-P000141

every deformation, (i.e. a map) $(n > 2)$

$$SL(n, Z) \times [0, 1] \longrightarrow SL(n, R)$$

which is continuous and a homomorphism for $\forall t \in [0, 1]$, at $t = 0$ it is the inclusion) is trivial, i.e. it is an inner automorphism with respect to $g(t)$ (a curve in the group)

$$\varphi(h \times t) = g(t)h \cdot g(t)^{-1}, \qquad h \in SL(n, Z)$$

Weil's theorem is proved only for the case when the quotient space is compact.

The prob. reduces to a problem about congruence subgrps. over a finite field. (If there are two homomorphisms, it is unknown whether they can be joined)

Existence of deformations — nontrivial

$$H^1(\Gamma, \mathfrak{g}) : * [?] \qquad \text{(Borel, Bass)}$$
$$\uparrow$$
finite no. of generators



Uncertain reading. After $H^1(\Gamma, \mathfrak{g})$ are small colon-like and star-like strokes; their literal reading is not established. Below the expression is "finite no. of generators" with an upward arrow.

Original source details: GELFAND-P000141

$\mathfrak{g}$ — the Lie algebra.

In $\mathfrak{g}$ there is a lattice of integer matrices L. (L — a lattice in the Lie algebra)

$$H^1(\Gamma, \mathfrak{g}) = H^1(\Gamma, L) \underset{Z}{\otimes} R$$

Prove that $H^1(\Gamma, L)$ is finite, It suffices to prove that $\exists \underset{\text{prime}}{p}$ such that multiplication by p is an epimorphism

$$H^1(\Gamma, L) \xrightarrow{p} H^1(\Gamma, L) \longrightarrow H^1(\Gamma, L/pL)$$
$$(\text{from } 0 \longrightarrow L \xrightarrow{p} L \longrightarrow L/pL \longrightarrow 0)$$

It suffices to prove that the right-hand term is 0.

One can reduce the matter to the case when Γ is finite: in place of Γ — $\Gamma/[\Gamma_p, \Gamma_p]$, Γ_p — the grp. of elems. congruent to 1 modulo p.

GELFAND-P000142

Thus, it suffices to prove that

$$H^1(\Gamma/\Gamma_p, L/pL) = 0$$

and everything reduces to fin. groups. The same Borel an incredibly difficult proof. Bass — only for split ones.

Smale (Anosov)

Arnold. U-system (according to Anosov)

$$g : H[?] \underset{\text{diff.}}{\longrightarrow} H[?],$$

if



Uncertain reading. The domain and range letters are written like H; H / M. The precise definition below has TM_x. Beneath the arrow is "diff.".

Original source details: GELFAND-P000142

there are 2 dirs.

Original source details: GELFAND-P000142

Diagram and typed description. Two separate intersections of horizontal and nearly vertical segments; a gap in the upper part of the first vertical stroke. There are no arrows or letter labels.



along the 1st it stretches [?], along the other it contracts ($\leq$, $\geq$ estimates on contraction and stretching)

Original source details: GELFAND-P000142

Uncertain reading. The final letter of the contraction after "along the 1st" has dense joined strokes: Cyrillic "растяг." / "растяж.", both contractions of "stretching". The contracted original is not expanded into a claimed exact Russian word.

> Example: autom. of the torus, nothing more was known.
> Smale asserts that he has found manifolds besides the torus and their U-automorphisms and all such automorphisms (conjecture).

Precise def.: $\exists TM_x = X_x \oplus Y_x, \forall \xi \in X_x, g^*\xi \in X_{gx}$,
a Riem. metric exists

$$|g^*\xi| < \theta|\xi|, \quad 0 < \theta < 1,$$
$$\forall \eta \in Y_x, \quad |g^*\eta| > \frac{1}{\theta}|\eta|.$$

(this is a V [?]-cascade)



Original source details: GELFAND-P000142

Uncertain reading. The opening heading has U, whereas this sign resembles V: V-cascade / U-cascade.

Autom. of the torus — eigendirections of the corresponding matrix.

All [crossed-out unread word] — a quotient of a nilp. group by a discrete subgroup.

new examples

(nil-manifolds)



Original source details: GELFAND-P000142

Uncertain reading. The crossed-out word after "All" has Cyrillic с/ю/д-like remnants; the original word is unreadable. The insertion "new examples" is visible beneath a spanning curved mark.

G/Γ, $G =$



— of order 6



Uncertain reading. A matrix in round parentheses, six diagonal positions, two upper-triangular blocks. At the top a, b, below c; in the lower block a^*, b^*, c^*; two 0 signs outside the blocks. The six dense diagonal marks are shown as dots: 1 / black dots; their exact literal reading is not established.

Original source details: GELFAND-P000142

$$\Gamma = \begin{Bmatrix} a = m + n\sqrt{3}, & a^{*[?]} = m - n\sqrt{3} \\ b = m' + n'\sqrt{3}, & \text{,,,,,,} \\ c = m'' + n''\sqrt{3}, & \end{Bmatrix}$$

G/Γ is compact.

Dim. $3 + 3$

contract. and expand.



Uncertain reading. A short dense mark above the second a: a star / a stroke; a^* is given with this qualification. Six short repetition strokes stand at the right of the b line; their content is not expanded. An encompassing right brace. The horizontal rule beneath "G/Γ is compact." runs above "Dim. $3 + 3$".

Original source details: GELFAND-P000142

GELFAND-P000143

Anosov proper.

Cascade — iterations of a diff. homeomorphism (with continuous time — a flow) Describe typical dynamical systems — cascades. (an everywhere dense set, open)

Structurally stable flow — passes to an equivalent one under a small (C^1) perturbation. (equiv. — differ by a diffeom.)

2-dimensional case: Andronov–Pontryagin thm. — structurally stable systems are described (a finite number of "stable" cycles and singular points and saddle separatrices in general position — — do not intersect, do not coincide.) Their set is open, dense.

Andronov–Pontryagin system.

1. A fin. number of equilibria and periodic trajectories, all locally structurally stable

(conditions on eigenvalues and multipliers) (in the multidimensional case this is already nontriv.)

2. Separatrices in general position

(Cond.,
Conditionally stable manifolds,
Asympt. bundles,
horospheres,
horocycles)

(Manifolds of incoming and outgoing —
— see Coddington and Levinson)

3. All trajectories as $t \longrightarrow \pm\infty$ tend to equilibria and periodic solutions.

[Two lines are densely cancelled with straight and wavy strokes. Surviving fragments: 4) / ∀ [?], “separatrices in general position”, “(do not intersect”, 2 [?], Cyrillic “собр.”; below, “this is not very” [unread ending].]



Uncertain reading. The initial cancelled sign resembles 4) / ∀; further surviving fragments are “separatrices in general position”, “(do not intersect”, a 2-like sign and Cyrillic “собр.”; below, “this is not very” and a dense ending. The complete original statement is unreadable.

Original source details: GELFAND-P000143

4 assertions.

1. All A.–P. — structurally stable — (?)

2. All structurally stable — A.–P.
3. A.–P. are dense
~~(Cyrillic дру [?]~~
4. Structurally stable are dense

Refuted
by Smale.



Diagram and typed description. After item 1, a hook-shaped question mark with a separate dot is circled. At the right of items 2–4 are two vertical rules and the words “Refuted by Smale”.

Original source details: GELFAND-P000143



Uncertain reading. A short cancelled parenthesis beneath item 3: Cyrillic “дру” / “друг” / unreadable.

Original source details: GELFAND-P000143

GELFAND-P000144

7

Structurally stable system: $\dot{w} = f(w)$.

$$\forall \varepsilon\ \exists \delta, \quad \forall g, \quad \|g - f\|_{C^1} < \delta,$$

$\exists \varepsilon$-homeom., taking trajectories of f to trajectories of g.

For a cascade: commutative diagram

($\exists\varepsilon$-homeom. χ)



Diagram and typed description. Four M nodes; f above, g below, both horizontal arrows point right, both vertical arrows down. At the left, χ; at the right, a short x- / χ-like sign.



Original source details: GELFAND-P000144

(For flows it is natural to assume that the speed may change; if this is forbidden, almost no structurally stable ones remain)

A subset $b|$ [?] of a manifold M with a smooth cascade is called a U-subset (hyperbolic subset)

compact,

invariant,

$\exists\Theta$ and a decomposition of the tangent bundle over $b|$ [?] into a direct sum, having the indicated properties. (U ...)



Uncertain reading. Subset designation: $b|$ / b_1 / another sign; a loop and a separate tall stroke. Repeated after “over”.

Original source details: GELFAND-P000144

(the tangent space of the whole [unreadable short cancelled fragment] manifold is decomposed.)



Uncertain reading. After “whole”, a short fragment is densely cancelled; the literal word cannot be read.

Original source details: GELFAND-P000144

Example: 1) a hyperbolic equilibrium (e.g. stable — — expanding — the whole space)

2) any U-system

3) There are examples when such a set is a torus, a Cantor set, etc.

Smale systems.

Nonwandering point.

Wandering region: $\exists n_0$ such that

$$\forall n \geq n_0, \quad g^n U \cap U = \varphi\,[?]$$



Uncertain reading. At the right of the equality, a crossed oval with a long lower stroke: a φ- / $\varnothing$-like sign. “Smale systems” has a straight underline; the next two headings have wavy underlines.

Original source details: GELFAND-P000144

A point is called wandering if it has a wandering neighbourhood.
A nonwandering point — a point that is not wandering, i.e.

$$\forall U_p\ \forall n \quad \exists g\,[?] \in U_p, \quad m > n: \quad g^m q \in U_p.$$



Uncertain reading. After $\exists$ is a g- / q-like letter; at the end, after g^m, a q-like letter.

Original source details: GELFAND-P000144

The set of nonwandering points is closed. (denoted — Ω)

Smale system (def)

1. Ω — hyperbolic.
2. $\overline{\Gamma} = \Omega$ (periodic points are dense in Ω — nonwandering [?])



Uncertain reading. The explanation ends at the lower boundary: “— неблужд.” (nonwandering) / a similar contraction; dense strokes.

Original source details: GELFAND-P000144

Γ_n — set of points of period n.

$$\Gamma = \bigcup_{n\geq 1} \Gamma_n\,[?] \quad (g^n p = p)\,[?]$$



Uncertain reading. After the union sign, Γ_n-like signs, the opening parenthesis and g are densely overwritten; the exponent is n-like. The original overwritten signs are undetermined. At the left are two slanting strokes with a short transverse stroke.

Original source details: GELFAND-P000144

GELFAND-P000145

It can happen that all points are nonwandering, but there are no periodic ones (e.g. nil-flows [?])

Uncertain reading. Faint parenthetical entry: “ниль-потоки” (nil-flows) / “нуль-потоки” (null-flows); the middle letter is not quite clear.

Original source details: GELFAND-P000145

Conjectures.

$\{\overline{\Gamma} = \Omega\}$ — everywhere dense — proved by [Goto / P’yu / G’yu?]; 1964 (only in C^1) !!

Uncertain reading. The surname before “; 1964”: “Гото” (Goto) / “Пью” (P’yu) / “Тью” (G’yu); faint lettering.

Original source details: GELFAND-P000145

Smale systems are everywhere dense (?)

A great problem to which it is worth devoting one’s life.

Apparently 2 follows from 1 (Prob. 70%), so it suffices to prove that systems with hyperbolic Ω are dense.

Theorem S. D. T. [?] (Smale) (Spectral Decompositio [?] theorem)

Uncertain reading. The first letter is S-shaped, the middle letter a looped D / Cyrillic “Д”, the last T-shaped: S. D. T. / S.Д.T.

Original source details: GELFAND-P000145



Uncertain reading. The word ending before “theorem”: Decompositio / Decomposition; the last visible sign is o- / a-like. An additional final n is undetermined.

Original source details: GELFAND-P000145

on the structure of Smale systems.

$$\Omega = \bigcup_{i=1}^{k} \Omega_i$$

Ω_i — invariant, closed and topologically transitive.

All theorems follow from 1 alone.

GELFAND-P000146

$12/\overline{\text{IX}}$ Gelfand sem.

G. E. Shilov.

$$S = \{x \in H,\ |x| \leq 1\}$$

— the unit ball of a Hilbert space.

$L(S)$ — ring of all weakly continuous functions.

$$L(S) \subset \overline{R} \subset C(S)$$

$C(S)$ — strongly continuous functions.

$$R = \{f((e_1, x), \ldots, (e_n, x), |x - a_1|, \ldots, |x - a_m|),$$

$\overline{R}$ — closure



Uncertain reading. After the long formula for R, a closing round parenthesis and a comma are visible; a closing brace for the initial { is not visible.

Original source details: GELFAND-P000146



Uncertain reading. The chain $L(S) \subset R \subset \overline{R} \subset C(S)$ is cancelled; the first letters and first inclusion sign are overwritten, and the beginning is not fully established.

Original source details: GELFAND-P000146

PIM of the ring $L(S)$ — the Hilbert ball

PIM of $\overline{R}$ — a bicompact extension.

$$M_\tau(f(x), z) \qquad M^*_\tau(f(x), z)$$

Uncertain reading. The mean's subscript is τ- / r-like; the same looped sign occurs in the later limit formula and squared in its denominator.

Original source details: GELFAND-P000146

$e_1, e_2, \ldots, e_n, \ldots$ — an orthogonal basis, determining an increasing chain of subspaces $E_1 \subset E_2 \subset \ldots$

over the sphere over the ball

The means — the limit of finite-dimensional ones. If they exist, they are equal.

The means are defined on $\overline{R}$.

(For R, one can simply write down formulas).

M_τ — a multiplicative functional. This is a max ideal, but it is not a value at a point, but a value in bicompact extensions.

From the point z, lines $M_\tau(z)$ are drawn in the space of max ideals.

$$\Delta f(z) = \lim_{\tau \to 0} \frac{M_\tau[f(x), z] - f(z)}{\tau^2}.$$

$\|$ stick into the point z.



Uncertain reading. The looped sign in M_τ, below the limit and in τ^2 is τ / r / an undetermined letter. At the right of the formula are two vertical rules and "stick into the point z".

Original source details: GELFAND-P000146

This is a first-order operator!!

$$\Delta(fg) = f \cdot \Delta g + (\Delta f)g$$

Dirichlet problem.

Σ — a closed surface (star-shaped)
(weak)



Original source details: GELFAND-P000146

Diagram and typed description. An irregular rounded closed contour with Σ at the upper right; seven radiating strokes, with small gaps at the centre. Several pass beyond the contour, the lower-left one ends inside; the left stroke bends before the centre. The lower-right stroke thickens at the contour; a separate arrowhead / point is undetermined.



$$\Delta u(x) = 0,$$
$$u(x)|_{x=\sigma} = f(\sigma)$$

GELFAND-P000147

There is uniqueness and continuous dependence for $f \in \overline{R}$ and surfaces of the form

$$\sum_{k=m+1}^{\infty} \xi_k^2 = \varphi(\xi_1, \ldots, \xi_m)$$

(surface of rotation) about a subspace [unreadable short cancelled fragment] of finite codimension.



Original source details: GELFAND-P000147

Uncertain reading. Before “of finite codimension”, a short fragment is densely cancelled; the literal word is undetermined.

and bounded curvature.

The solution formula — the angular mean of the boundary functional.

$\Delta u = g \in \overline{R}$ — also explicit

Next, $\Delta u = \varphi(x, u(x))$ is solved by the fixed-point method.

I. M. Gelfand.

$u = (u_1, \ldots, u_m\,[?])$

Original source details: GELFAND-P000147

Uncertain reading. The last component subscript has a dense m- / n-like shape; below, $n = 1$ and $n = 2$ are written separately.

$$\frac{\partial u}{\partial t} = A(u)\frac{\partial u}{\partial x}$$

Hyperbolic (at $\forall$ point, $A(u)$ has real eigenvalues)

Is there uniqueness? Shock waves — the solution may be nonunique.

$n = 1$ — always uniqueness if $f(u)$ is convex

Hydrodynamic equations — [cancelled: “nonunique” / “may” / unreadable] uniqueness too. ($n = 2$)

Uncertain reading. Before “uniqueness too”, a word is cancelled: “может” (may) / “неод.” (nonunique) / another short fragment; the cancellation crosses the letters.

Original source details: GELFAND-P000147

In the general case it is unclear where there is uniqueness and where there is not.

Magn. [?] hydrodyn. — uniqueness too.

Uncertain reading. The first abbreviation before “hydrodyn.”: “Магн.” (Magn.) / “Мал.” (Mal.); the strokes after “Ма” are joined.

Original source details: GELFAND-P000147

A purely mathematical question: at $\forall$ point u, draw the eigenvectors — 3 families of lines — — characteristics.

Convexity: possibly, growth of λ along the characteristics

Better:

$$\frac{\partial u}{\partial t} = \frac{\partial f(u)}{\partial x}$$

(divergence form)

There is work by Godunov, but it concerns a narrow class of systems.

When is there uniqueness upon adding viscosity:

$$\frac{\partial u}{\partial t} = A\frac{\partial u}{\partial x} + \varepsilon\frac{\partial^2 u}{\partial x^2} \quad ?$$

This reduces to the [unreadable cancelled word] question of ordinary differential equations.



Uncertain reading. In the source, between “к” (to) and “вопросу” (question), a densely cancelled word with a looped lower stroke; the literal reading is undetermined.

Original source details: GELFAND-P000147

GELFAND-P000148

I. Bernstein.

Part of what Atiyah spoke about.

g — a compact Lie group. R_g — the ring of finite-dimensional representations (direct sum, tensor product and formal differences), commutative.

An embedding

$$R_g \longrightarrow K(B_g)$$

B_g — the classifying space, K — the K-functor.

A representation corresponds to a vector bundle on B_g (associated).

(I.) If the ring R_g is completed at the ideal of representations of dimension zero, there will be an isomorphism

$$\widehat{R}_g \longrightarrow k(B_g)$$

(The dimension of an element of the form of a difference of two representations — the difference of their dimensions)

Example.

$$g = S^1, \qquad R_{S^1} = \sum_{i=-\infty}^{+\infty} n_i x^i,$$

n_i — integers, finitely many nonzero.

The ideal is generated by the element $x - 1 = y$.

$$\widehat{R}_{S^1} = Z[[y]]$$

(formal power series)

Only positive powers

$$\left(\frac{1}{1-y} = 1 + y + y^2 + \dots\right)$$

$$B_g = CP^\infty,$$
$$k(CP^\infty) = \lim K(CP^n).$$

On CP^n, the canonical bundle (fibre CP^1), total space CP^{n+1}.

Every element of $K(CP^n)$ is $\underline{P}(x-1)$.

Precisely

$$K(CP^n) \cong [?]\ P(x)/(x-1)^{n+1}.$$



Uncertain reading. The relation sign has a wavy upper stroke and lower horizontal strokes: ≅ / ≃ / an overwritten sign. The numerator has a P-shaped letter.

Original source details: GELFAND-P000148

Next time, a lecture by Minlos on statistical physics.

GELFAND-P000149

19/IX. Gelfand sem.

I. Bernstein (continuation).

$K(B_g)$ is defined as follows:
Let

$$(B_g)_1 \longrightarrow (B_g)_2 \longrightarrow \dots$$

be the skeleta of the corresponding dimensions

$$K_1 \longleftarrow K_2 \longleftarrow \dots$$

One must take the projective limit.
The K-functor of a finite polyhedron is defined in the usual way (ring [overwritten: K-like sign, ?] bundl.[?]) ~~[unread long entry]~~) .

$\longrightarrow$ •



Original source details: GELFAND-P000149

Uncertain reading. After “ring”, an overwritten K-like sign and a “рассл.”-like abbreviation. Then dense cancellation with lower strokes and another closing parenthesis; a rightward arrow and dot below the beginning of the cancellation. The literal reading of the cancelled ending is not established.

Question of I. M. Gelfand. generalize the notion of the K-functor and classifying space so that the theorem remains valid also for locally compact Lie groups. (the left-hand side makes sense) — — one must also use infinite-dimensional representations.



Original source details: GELFAND-P000149

Diagram and typed description. A wavy line below the heading. The faint parenthesis reads “the left-hand side makes sense”; the abbreviation at the right of the preceding line is “лок.”.

Dimension — a factor[?] in the Plancherel formula.

$\longrightarrow$ • —



Original source details: GELFAND-P000149

Uncertain reading. The joined word after the dash: “factor” / “exponent” / unclear entry. Below it, a long rightward arrow, a dot and a short slightly rising stroke.

Let X be a g-space (i.e. there is a map $g \times X \longrightarrow X$, continuous in both arguments, and there is an action of g on X)

$K_g(X\,[?])$ — the K_g[?]-functor.



Uncertain reading. At the second K, small loop-shaped strokes stand to the right, above and below: a K_g / K^g / K_g^0-like entry; a separate 0 is not established. In the parentheses of the first K_g, an X-like letter is densely overwritten.

Original source details: GELFAND-P000149

A g-bundle $E \xrightarrow{p} X$ — a vector bundle, then E ... — a g-space, g acts compatibly with p. In the fibres g must preserve the linear structure.

In the usual way, sum and tensor product are defined and formal differences are introduced.

Example. K_g — the functor of a point — — linear spaces with representations of g, this will be exactly R_g.

~~[Cyrillic H-like beginning, ?]...~~

Uncertain reading. Before “Generalization”, a short cancelled fragment with a Cyrillic H-like beginning; the remaining letters are not established.

Original source details: GELFAND-P000149

Generalization. Instead of a point — a g-space X.

The left-hand side $K_g(X)$ — already generalized.

$$\begin{array}{c} E \\ \big\downarrow g\,[?] \\ B_g \end{array}$$

E — a g-space (g acts on the right).



Uncertain reading. Below, E over B_g, a downward arrow and a small g-like loop-shaped sign to its right; the exact reading of the label is not established.

Original source details: GELFAND-P000149

Let X be a G [?]-space. Introduce the space $X_G = E \times_G X$ (in $E \times X$, the orbits of the group G are identified). If X is a point, then $X_G \cong B_G$ — Grassmann.



Original source details: GELFAND-P000150

Uncertain reading. The loop-shaped group sign and its repeated indices: G / g / $\mathcal{G}$; rendered as G with this qualification.

Theorem. (a generalization of the one formulated at the beginning)

$$\widehat{K}_G(X) \xrightarrow{\sim} K(X_G).$$

There is a map $K_G(*) \longrightarrow K_G(X)$, so $K_G(X)$ — — a module over R_G. Completion is taken with respect to the ideal J of the ring R_G.

An exact def. can also be given as follows:

$$\widehat{K}_G(X) = K_G(X) \underset{R_G}{\otimes} \widehat{R}_G.$$

1. Reduction to the unitary group U.

Let $G \subset U$. Then $K_G(X) = K_U(U \times_G X)$.

The action of G on U: $g : u \longrightarrow ug^{-1}$. On $U \times_G X$, U acts on the left. Moreover, $X_G = (U \times_G X)_U$.

It is clear why one cannot restrict oneself to such

2. Reduction to the torus case.

(For the torus it holds, since for the circle verif. [?] directly.)



Original source details: GELFAND-P000150

Uncertain reading. After “окр.” (“circle”), a contraction resembling Cyrillic “пров.” / “пр-в.”; its middle strokes are joined. The parenthesis contains “непосредств.” (“directly”).

~~[unread cancelled sign]~~.

Original source details: GELFAND-P000150

Uncertain reading. Before $T \subset U$, a short number-like sign is densely cancelled; its original reading is not established. A separate dot at the right.

$T \subset U$, T is a maximal torus in U.

$$\begin{array}{ccc} X_T & K_U(X) & K_U(U \times_T X) \\ \downarrow U/T & \downarrow & \downarrow \\ X_U & K(X_U) & K_T(X) \end{array} \qquad U \times_T X \xrightarrow{U/T} X$$



Diagram and typed description. At the left, $X_T \longrightarrow X_U$ downward with U/T. Two double vertical rules separate three parts. In the square, $K_U(X)$ and $K_U(U \times_T X)$ above, $K(X_U)$ and $K_T(X)$ below; solid horizontal arrows rightward, dashed arrows backward, both vertical arrows downward. To the right of the right vertical arrow, a question-like hook with a thickened base; a separate dot cannot be distinguished. Separately at the right, $U \times_T X \longrightarrow X$ with U/T above the arrow.

Original source details: GELFAND-P000150

(and odd [?])
The upper arrow is a map into a direct summand (i.e. there exists „inverse is constructed above and below functorially. „inverse“)

Hence the left arrow is also an isomorphism.



Uncertain reading. Above the first “inverse”, a parenthesized insertion: Cyrillic “и нечётное” / “и нечётн.” / “и нечёткое” / “и нечётная” / a dense contraction after “and”. The middle and final strokes are not securely separable. “summand” and the last “inverse” are underlined.

Original source details: GELFAND-P000150

GELFAND-P000151

R. A. Minlos.

A phys. system is descr. by a set of states $\mathcal{L}_\sigma\,[?]$ and a function $H(a)$ on [unreadable sign], which is called the Hamiltonian fn. (a real-valued fn.). — the pair $(\mathcal{L}\,[?]; H(a), a \in \mathcal{L}_\sigma\,[?])$.

Original source details: GELFAND-P000151

Uncertain reading. After "on" a letter with an upper loop and a lower stroke is densely crossed out; the original reading is not established.



Original source details: GELFAND-P000151

Uncertain reading. The state space: $\mathcal{L}_\sigma$ / a single handwritten $\mathcal{G}$-like letter; the right loop may be part of the letter or a separate σ. At the start of the pair a separate subscript is not established.

3 types.

1. Classical system — tuples

$$(p_1, \ldots, p_N, x_1, \ldots, x_N)$$

All p_i independently range over $\mathbb{R}^\nu$ (in physics $\mathbb{R}^3$) — — the set of momenta.

All x_i range over a region [unreadable sign] $\Omega \subset \mathbb{R}^\nu$, called the vessel (the reg. is bounded).



Original source details: GELFAND-P000151

Uncertain reading. Before Ω there is a short densely crossed-out sign; the original reading is not established.

The tuple x_i — configurations of the particles

$$(\underbrace{p_1, \ldots, p_N}_{\mathbb{R}^{N\nu}}, \underbrace{x_1, \ldots, x_N}_{\Omega^N})$$

Notation (will sometimes be consid.)

$$(\Omega_\delta)^N : \quad |x_i - x_j| > \delta$$

(the particles — "hard" balls)

This is the set of states.

Hamiltonian fn.:

$$H(a) = \frac{1}{2m} \sum |p_i|^2 + V(x_1, \ldots, x_N), \qquad m > 0$$

V is called the potential energy.

In what follows we consid. only fns. V of the form

$$V(x_1, \ldots, x_N) = \sum_{i \neq j} U(|x_i - x_j|)$$

(a system with pairwise interaction)

$U(r)$ [?] — the potential — is def. either for $r > 0$, or for $r > \delta$.

$$\{\mathcal{L}_{\sigma\Omega,N}\,[?], H_{m,U(r)}\}$$



Original source details: GELFAND-P000151

Uncertain reading. The loop-shaped state-space sign with its right loop recurs inside the brace; Ω, N are clearly visible below. The rendering of the principal sign as $\mathcal{L}_\sigma$ remains provisional.

Ω — the vessel, N — the number of particles, m — the mass, $U(r)$ [?] — $\longrightarrow$ potential energy.



Original source details: GELFAND-P000151

Uncertain reading. The letter in $U(r)$ and before > 0, $> \delta$ has a short loop-shaped top and a lower stroke to the right: r / a τ-like handwritten sign. The rendering as r is provisional; the repetitions appear in the original fragments.

GELFAND-P000152

15

Identical sys. — differ either in the number of particles or in the vessel. (the same — mass and potential)

δ — is contained in $U(r)$ [?].

2. Configurational system.

Obt. from the preceding one. A state — $(x_1, \ldots, x_N)$ — the region Ω^N or its subregion $(\Omega_\delta)^N$.

$$H(a) = \sum_{i \neq j} U(|x_i - x_j|)$$

— without kinetic energy.

$$(\mathcal{L}_{\sigma\Omega,N}\,[?], H^N_{U(r)})$$



Original source details: GELFAND-P000152

Uncertain reading. The state-space letter repeats the loop-shaped sign: $\mathcal{L}_\sigma$ / a single $\mathcal{G}$-like letter; the right loop may be part of the letter or a separate σ. Below are Ω, N.

System 1 reduces to system 2. (see below).

3. Discrete model system.
In R^ν a cubic lattice, Ω — a subset of it. A state — a tuple of N lattice sites $(x_1, \ldots, x_N)$, in which no two are equal.

$U(x)$ — an even function on the lattice.

$$H(a) = \sum_{i \neq j} U(x_i - x_j)$$

(Isotropy, e.g. — spherical symm. — is not justified here)

The results of stat. physics depend only on the qualit. properties of $U(r)$ [?], but physicists use only the potential

$$U(r) = \frac{a}{r^{12}} - \frac{b}{r^6}, \qquad \begin{matrix} a > 0 \\ b > 0 \end{matrix}$$

What matters to us is the growth at 0 and the decay at ∞.



Original source details: GELFAND-P000152

Diagram and typed description. The vertical axis has an upward arrow; no horizontal arrow is established. Neither axis has letters. The branch comes from above to the right of the vertical axis, crosses the horizontal, forms a negative well and approaches the horizontal from below. The upper end of the branch is thick, with short lateral strokes; a separate arrow meaning is not established. No exact scale is given.



In the presence of δ:



Original source details: GELFAND-P000152

Diagram and typed description. Two axes with arrows. At the right is a dotted vertical; above it $+\infty$, a thick mark at its intersection with the horizontal, and δ to the right. The branch leaves the thick mark for a well and rises below the horizontal axis. The dense ink at the intersection is rendered without an established function value at δ or an assertion of closedness.



Sometimes only a potential of compact support is consid.



Original source details: GELFAND-P000152

Uncertain reading. The repeated letter in $U(r)$ and the denominators has a loop-shaped top and a lower stroke to the right: r / a τ-like sign. Its rendering as r is provisional; the original repetitions appear in the fragments.

GELFAND-P000153

The particles are small (δ [?]) compared with the region.



Original source details: GELFAND-P000153

Uncertain reading. The sign in parentheses: δ- / r-like; its upper part touches the upper frame boundary and is cut off.

Consid. a seq. of vessels Ω_N which expands and fills the whole space (e.g. similar cubes)
Let us consider

$$\{\mathcal{L}_{\sigma\Omega_N,N}\,[?], H^N_{m,U(r)}\}$$



Original source details: GELFAND-P000153

Uncertain reading. In the first brace a loop-shaped letter with a right loop: $\mathcal{L}_\sigma$ / a single $\mathcal{G}$-like sign; below are Ω_N, N. The rendering of the principal sign is provisional.

Original source details: GELFAND-P000153

Uncertain reading. The letter in $U(r)$ has a short loop-shaped top and a lower stroke to the right: r / a τ-like sign. Its rendering as r is provisional; the original notation appears in the fragment.

$$\frac{|\Omega_N|}{N} \longrightarrow v \quad \text{(limiting specific volume)}$$

$|\Omega_N|$ — the volume of the region Ω_N

(Thermodyn. limiting transition)
In most cases everything depends only on v, and the shape of the vessel is immaterial.

Gibbs distribution.
It is assumed that a probability distr. is given on $\mathcal{L}_\sigma\,[?]$ In the equilibrium case it is postulated (if everything is independent of time)

$$p(a) = \frac{1}{Q} e^{-\beta H(a)}, \qquad \beta > 0$$

$$Q = \int_{\mathcal{L}_\sigma\,[?]} e^{-\beta H(a)}\, da.$$

Uncertain reading. The loop-shaped state-space letter: $\mathcal{L}_\sigma$ / a single $\mathcal{G}$-like sign; the right loop may be part of the letter or a separate σ. The form recurs beneath the integral.

Original source details: GELFAND-P000153

For lattice systems the same formula, but p now gives the probabilities themselves, rather than densities.

A phys. sys. with a given Gibbs distr. is called a small canonical ensemble

$$\begin{pmatrix}\text{in the classical case}\\ \mathcal{L}_{\sigma\Omega,N}\,[?], H^N_{m,U(r),\beta}\end{pmatrix}$$



Uncertain reading. In the classical-case parenthesis the loop-shaped state-space sign recurs: $\mathcal{L}_\sigma$ / a single $\mathcal{G}$-like letter. Below are Ω, N; H has N above and $m, U(r), \beta$ below.

Original source details: GELFAND-P000153

In the thermodyn. limiting transition identical systems are always consid. (β is also fixed)

$$p(a) = \frac{1}{Q} e^{-\beta \frac{1}{2m} \sum p_i^2} e^{-\beta \sum U(|x_i - x_j|)}$$

$$\mathcal{L}_\sigma\,[?] = R^{\nu N} \times \Omega^N$$



Uncertain reading. The same loop-shaped state-space sign appears in the last line; its rendering as $\mathcal{L}_\sigma$ is provisional. At the right is $R^{\nu N} \times \Omega^N$.

Original source details: GELFAND-P000153

Our distr. is a product of simpler distributions and only the Gibbs distr. in the configuration space is of interest. Where $U(r)\,[?] = +\infty$, the density will be 0. There are distr. fns. for a subsystem ($\int$ over the others)

Original source details: GELFAND-P000154

Uncertain reading. The argument in $U(r)$: r / a τ-like handwritten sign with a short upper loop and a downward bend. Its rendering as r is provisional.

Correlation functions are convenient.

$$p(x_1) = \frac{1}{Q}\int e^{-\beta\sum U(x_i - x_j)}\, dx_2 \ldots dx_N$$

$$p(x_1, \ldots, x_k) = \ldots \int \ldots dx_{k+1} \ldots dx_N$$

~~$\tau_{[?]}(x_1, \ldots, x_{[?]})$~~



Original source details: GELFAND-P000154

Uncertain reading. A crossed-out expression resembling $\tau_k(x_1, \ldots, x_N)$ / $\tau_2(x_1, \ldots, x_2)$; the lower indices and middle strokes are covered by two lines. The original indices are not established.

$$\tau_k(x_1, \ldots, x_k \mid N, \Omega, \beta)\,[?] = \frac{N!}{(N-k)!} p(x_1, \ldots, x_k)$$



Uncertain reading. The correlation sign has a short wave above and a downward bend: τ / an r-like sign. Here and in its repetitions τ is a provisional rendering.

Original source details: GELFAND-P000154

Summatory fn. $F(a)$, $a\,(x_1, \ldots, x_N)$

Of the 1st order $F(a) = f(x_1) + f(x_2) + \ldots + f(x_N)$

Of the 2nd order $F(a) = \sum_{i \neq j} f(x_i, x_j)$, f — symmetric.

and so on.

Mean for summatory fns. F:

$$\langle F\rangle = N\langle f(x_1)\rangle = N\int_\Omega f(x)p(x)\,dx$$
$$= \int_\Omega f(x)\tau_1(x)\,[?]\,dx$$

(it suffices to know the 1st correlation function)



Uncertain reading. In the first mean formula the sign before the index 1 repeats the τ / r-like form; τ_1 is a provisional rendering. Both integration regions are explicitly Ω.

Original source details: GELFAND-P000154

Similarly for the 2nd order:

$$\langle F\rangle = \iint_{\Omega\,\Omega} f(x_1,x_2)\tau_2(x_1,x_2)\,[?]\,dx_1dx_2$$



Uncertain reading. The second mean formula has the same τ / r-like sign, here with index 2. Two Ω symbols are written beneath the double integral.

Original source details: GELFAND-P000154

Probabilistic (phys.) meaning.

$C \subset \Omega$, C — a subregion, $n_C(a)$ — the number of particles that fall in the subregion, $a = (x_1, \ldots, x_N)$. This is a summatory quantity of the 1st order, with

$$f(x) = \begin{cases} 1, & x \in C, \\ 0, & x \notin C \end{cases}$$

Uncertain reading. Two small angular crossed signs in the left margin; their letter reading and meaning are not established.

Original source details: GELFAND-P000154

Therefore

$$\langle n_C(a)\rangle = \int_C \tau_1(x)\,[?]\,dx$$

$$\frac{\langle n_C(a)\rangle}{|C|} = \frac{1}{|C|}\int \tau_1(x)\,[?]\,dx$$



Uncertain reading. No lower domain is visible on the final integral; the preceding formula explicitly has C. The repeated correlation sign is provisionally rendered as τ_1.

Original source details: GELFAND-P000154

GELFAND-P000155

For a small region we obtain that $\tau_1(x)\,[?]$ — the "local mean density" at the point x.



Uncertain reading. At the beginning the sign before the index 1: τ / an r-like handwritten sign; its rendering as τ_1 is provisional.

Original source details: GELFAND-P000155

Another probabil. meaning:

Diagram and typed description. A separate approximate circle with a dot inside; ΔC at the upper right edge and x_0 below.



Original source details: GELFAND-P000155

ΔC — a small nbhd. of x_0.
The probability that $n_{\Delta C} = 1$ is $\tau_1(x_0)\,[?]\Delta C$.

$$p(n_{\Delta C} = 1) = \tau_1(x_0)\,[?]\Delta C + o(\Delta C)$$



Uncertain reading. The provisionally rendered sign τ_1 recurs in the verbal line and the equality. The last term is written $o(\Delta C)$.

Original source details: GELFAND-P000155

Original source details: GELFAND-P000155

Uncertain reading. Between the lines of the first probability explanation is a separate dense ink mark with an irregular outline; no letter reading or meaning is established.

26/IX. Gelfand Sem.

R. A. Minlos. Lecture 2.

$\tau(x_1, x_2)$ [?]$\Delta x_1 \Delta x_2$ — the prob. of a particle falling in Δx_1 and a second one in Δx_2.

Original source details: GELFAND-P000155

Uncertain reading. Before (x_1, x_2) is the same τ / r-like sign; no separate index 2 is visible on it. Its rendering as τ is provisional.

Original source details: GELFAND-P000155

Diagram and typed description. Two separate approximate outlines, with x_1, x_2 below; dense crossed strokes inside, whose separate letter reading is not established. A short stroke above the right outline. Sizes and distance are not given.

$\Omega_N \longrightarrow \infty$ — the thermodyn. limiting transition.

$$\frac{|\Omega_N|}{N} \longrightarrow v = \frac{1}{\rho}, \qquad \rho \text{ — density.}$$

Hypothesis: 1)

$$\tau_k(x_1, \ldots, x_k \mid N, \Omega, \beta)\,[?] \longrightarrow \vec{\tau}_k(x_1, \ldots, x_k \mid v, \beta)\,[?]$$

This is assumed (limiting correlation function)

Moreover, it is assumed that $\forall \tau_k\ \exists v_N$ such that

$$(v_N \underset{\longrightarrow}{\text{depends}} \text{ only on the vessel and on } [?]\ k)$$



Original source details: GELFAND-P000155

Uncertain reading. The short notation before k: “ot” (on) / an “o.”-like contraction; the reading is not established. A separate right arrow beneath “depends.”

$$2)\quad \left|\begin{matrix}\tau_k(x_1,\dots,x_k \mid N,\Omega,\beta)\,[?]\\ -\vec{\tau}_k(x_1,\dots,x_k \mid v_N,\beta)\,[?]\end{matrix}\right| < C_k\gamma\big(\min_{\text{dist.}}|x_i,\partial\Omega|\big),$$

where $\gamma(r) \longrightarrow 0$ as $r \longrightarrow \infty$.



Uncertain reading. The principal letter: τ / an r-like sign. Above the limiting function is a horizontal stroke with a right-pointing head. In the bound γ has a long lower stroke; "dist." is written beneath $|x_i, \partial\Omega|$.

Original source details: GELFAND-P000155

Volume [?]
and v [?]
we discuss [?]
Ideal
gas — all [?]
[dense unreadable sign]
const and
need to obtain 0



Uncertain reading. Beyond two vertical lines are words resembling "Volume and v we discuss," then "Ideal gas — all" / "... without ...," const, "and need to obtain 0." The first connective and endings are faint; a dense unreadable sign follows the gas line. These readings are provisional.

Original source details: GELFAND-P000155

γ depends on the potential. For a potential of compact support $\gamma(r) \longrightarrow e^{-\lambda r}$.



Uncertain reading. A right arrow between $\gamma(r)$ and $e^{-\lambda r}$; separate limit conditions are not repeated in this line.

Original source details: GELFAND-P000155

~~[unreadable sign]~~

Uncertain reading. Before “We then have” a short sign or number is densely crossed out; the original reading is not established.

Original source details: GELFAND-P000155

We then have $v_N \longrightarrow v$ as $N \longrightarrow \infty$.

3) Assume that the limiting correlation fns. are invariant under translations. Hence $\vec{\tau}_1\,[?] = \text{const} = \rho$.



Uncertain reading. In the last line the provisionally rendered sign τ_1 recurs with a horizontal right arrow above it; then const $= \rho$.

Original source details: GELFAND-P000155

GELFAND-P000156

17

4) Continuity with respect to v and β.

This theorem should hold except at exceptional values of v and β. (assumed)

Proved only for small v and β (under some assumptions). (this will be done later — — Ruelle)

5) All $\vec{\tau}_k\,[?]$ are bounded.



Uncertain reading. The principal letter is τ- / r-like; its rendering as τ is provisional. Above it is a horizontal stroke with a right-pointing head; both lines of item 5 have the index k.

Original source details: GELFAND-P000156

$\vec{\tau}_k$ [?] exist for all v, not [?] for all v with such [?] a rate of convergence.



Uncertain reading. The short word after the comma is “не” (not) / “но” (but). The beginning of the word rendered as “such” is densely overwritten; the original reading beneath the strokes is not established.

Original source details: GELFAND-P000156

Uncertain reading. At the right beside item 5 is a separate small dense mark with an irregular outline; no letter reading is established. Below are two horizontal rules and a separate diamond-shaped central dot; the right end of the left rule is thickened.

Original source details: GELFAND-P000156

On the Gibbs distribution. (at Gelfand’s request)

$$a(p_1, \dots, p_N, x_1, \dots, x_N)$$

Diagram and typed description. One unfilled approximate circle without labels or arrows to the left of the paragraph on motion; no sizes are specified.



Original source details: GELFAND-P000156

Motion on the surface of constant energy $H(a) = \text{const}$. Assume that it is ergodic and there is an invariant measure.

Perhaps any distribution, as the number of particles increases, leads to the Gibbs distribution. (Gelfand)

Not any: if there is no ergodic hypothesis (Arnold)

Representativity of mean values.

$$P_\sigma\,[?]\big(|F - \langle F\rangle| > \varepsilon\big) \longrightarrow 0 \quad \text{as the number of particles increases.}$$

Then the random variable (function; physical quantity) is called representative.

This is imprecise, since there is no single function F.



Original source details: GELFAND-P000156

Uncertain reading. The subscript of P is short, with an upper hook and a lower loop: σ / τ / an r-like sign. Its rendering as σ is provisional. The heading has a wavy underline; below it is the remark about the absence of a single function F.

The needed example. (summatory function)

$$F_N(x_1,\dots,x_N)=\sum_{i\neq j} f(x_i-x_j),$$

f is one and the same, $\int |f(\xi)|\,d\xi<\infty$.

$$\begin{aligned}\langle F_N\rangle &= \iint \tau_2\,[?](x_1,x_2\mid N,\Omega,\beta)f(x_1-x_2)\,dx_1\,dx_2 = \\ &= \iint \vec{\tau}_2\,[?](x_1-x_2\mid v,\beta)f(x_1-x_2)\,dx_1\,dx_2+o(|\Omega|)= \\ &= |\Omega|\int \vec{\tau}_2\,[?](\xi\mid v,\beta)f(\xi)\,d\xi+o(|\Omega|).\end{aligned}$$



Uncertain reading. In the first line the principal τ- / r-like sign has no stroke above it; in the following two it has a stroke with a right-pointing head. All three lines have the index 2. The letter is rendered provisionally. Integration domains are not separately indicated; equality signs are repeated at the ends and beginnings of the lines.

Original source details: GELFAND-P000156





Uncertain reading. To the right of the last equality, a loop-shaped sign, a plus and an F-like form are crossed out. The first reading is not established; F is provisional. The cancellation strokes are diagonal.

Original source details: GELFAND-P000156

Thus,

$$\left\langle \frac{F_N}{N} \right\rangle \sim v \int \vec{\tau}_k\,[?](\xi \mid v, \beta) f(\xi)\, d\xi \quad \text{— already const}\,.$$



Uncertain reading. The final index is k- / 2-like; its rendering as k is provisional. Above the principal letter is a horizontal stroke with a right-pointing head; the letter itself is τ- / r-like. Before the integral, v is written.

Original source details: GELFAND-P000156

GELFAND-P000157

Uncertain reading. In the upper left margin is a densely cancelled loop-shaped sign resembling 6; its original reading is not established. At its right is a separate dot.

Original source details: GELFAND-P000157

One more hypothesis (but it already follows from these, though with difficulty):

$$6) \quad \left| \begin{matrix} \bar{\tau}_{k+s}(x_1, \ldots, x_k, y_1, \ldots, y_s \mid v, \beta) \\ -\bar{\tau}_k(x_1, \ldots, x_k \mid v, \beta)\bar{\tau}_s(y_1, \ldots, y_s \mid v, \beta) \end{matrix} \right| [?] \leq$$
$$\leq C_{k,s}\gamma\big(\min_{i,j} |x_i - y_j|\big)\,[?].$$

(multiplicative property; for the ideal gas 0).



Uncertain reading. The principal letter in all three functions is τ- / r-like; its rendering as τ is provisional. Above each is a flat horizontal stroke. The minimum has i, j; between x_i and y_j is a dense horizontal sign rendered as a minus. The $\leq$ signs are repeated at the end and beginning of the lines.

Original source details: GELFAND-P000157

We shall prove that

$$\underset{\text{variance}}{DF_N} \sim dN, \qquad d \text{ — const}.$$

Hence $D\frac{F_N}{N} \sim \frac{d}{N}$ and by Chebyshev's inequality we already obtain ~~[unreadable word]~~ representativity of the mean.

Original source details: GELFAND-P000157

Uncertain reading. After "obtain" a word is densely cancelled, with a loop-shaped stroke below it. Its original reading, including a possible repetition of "represent.", is not established. The following words are "representativity of the mean".

This is proved by direct calculation:

$$DF_N = \langle F_N^2 \rangle - \langle F_N \rangle^2.$$

$$\underbrace{F_N^2}_{\substack{\text{summatory [?]}\\ \text{qty. of 4th ord.}}} = 2\sum_{i\neq j} f^2(x_i - x_j)$$

$$+ 4 \sum_{\substack{i,j,k\,[?]\\ \text{noncoinc. [?]}}} f(x_i - x_j) f(x_k - x_j) +$$

$$+ \sum_{\substack{i,j,k,s\\ \text{unequal}}} f(x_i - x_j) f(x_k - x_s).$$



Original source details: GELFAND-P000157

Uncertain reading. Beneath F_N^2 is a short arc; at the left is "summatory" or a similar abbreviation, then "qty. of 4th ord.", enclosed below by a long curved rule. Beneath the triple sum are i, j and a dense k-like third sign and an abbreviation resembling "noncoinc."; these readings are provisional. Beneath the quadruple sum are i, j, k, s and "unequal".

We calculate

$$\langle F_N^2 \rangle = 2 \iint f^2(x_1 - x_2) \tau_2\,[?](x_1, x_2)\, dx_1\, dx_2 + 4 \ldots$$

and use the decay estimates.

Original source details: GELFAND-P000157

Uncertain reading. The function in the last integral has a principal τ- / r-like sign without a stroke above it and the index 2; its rendering as τ is provisional. It is followed by $+4\ldots$ and the complete line about decay estimates.

D. Kazhdan. His results.

1) G is a simple real or p-adic Lie group containing as a subgroup $SL(3, P)$ [?], P [?] is the corresponding field. Γ is a discrete subgroup with a quotient space of finite volume.



Original source details: GELFAND-P000158

Uncertain reading. In the argument of $SL(3, P)$ and before "corresponding field" is a sign with an upper loop and a descending stroke: P / a ρ-like form. Its rendering as P is provisional.

Then a)

$$\Gamma / \underbrace{[\Gamma, \Gamma]}_{\text{commutator subgroup}} \quad \text{is finite.}$$

b) Γ has a finite number of generators. (even from any set of generators a finite one can be selected)

2) G is an algebraic group over the rational numbers Q, containing $SL(3, Q)$. Something about representations.

The proof uses the isolation of the trivial representation.

Prof. Lodzhs. [?] (Canada) jointly with P. Szego.



Original source details: GELFAND-P000158

Uncertain reading. The name: "Лоджс." / "Ходжс." / "Лорчс." / "Лорче."; the first letter is dense, the middle has a conspicuous upper loop, and the ending is c-like. The reading is provisional. Beneath the professor/Canada line are wavy and straight rules; beneath P. Szego is a wavy rule.

$$y'' + f(x)y = 0, \qquad 0 < x < \infty.$$



Original source details: GELFAND-P000158

Diagram and typed description. A horizontal line, a short vertical at the left, four dense early crossings and a dot at the bottom of the vertical. Three upper waves alternate with lower ones, ending at the right in a short downward curl. No labels, sizes or exact coordinates are given; the contour is approximate.



Sturm: (1836) if $f(x)$ increases, the zeros get closer and conversely.

Theorem, if f has a higher degree of monotonicity.
Let

$$(-1)^j f^{(j+1)}(x) \geq 0, \qquad 0 < x < \infty, \quad j = 1, \ldots, N$$

and $f(\infty) > 0$. Then

$$(-1)^n \Delta^{n+1} x_k > 0, \qquad n = 1, \ldots, N+1; \quad k = 1, 2, \ldots$$

This holds for the Bessel functions $\nu > \frac{1}{2}$ [?], Airy [?] and others.



Original source details: GELFAND-P000158

Uncertain reading. In an oval above the line after Bessel: $\nu > 1/2$ / $\upsilon > 1/2$; the sign and dense fraction are rendered provisionally. The next name is Airy / Airy: the initial A-like sign is densely overwritten, then a dot above i, an r-like bridge and a lower y-loop.

The wave areas have the same property.

$$M_k = \int_{x_k}^{x_{k+1}} |y(x)|^\lambda \, dx, \qquad \lambda > -1.$$

$\lambda = 0$ — differences of zeros, $\lambda = 1$ — wave areas,

$\lambda = -1$ — diff. of derivs. ([unreadable abbreviation] parts) (Gelfand's remark) $\dfrac{1}{y'(x_k)}$.



Original source details: GELFAND-P000158

Uncertain reading. Beneath "diff. of derivs." is a parenthesis: "ин. части" / "м. части" / "... parts"; the first abbreviation is not established. The main line has $\lambda = -1$; at the right is $1/y'(x_k)$.

GELFAND-P000159

I. M. Gelfand.

Repetition of I. Bernstein. (also Atiya)

G is a compact group. K_G is a functor, $K_G(X)$.

Original source details: GELFAND-P000159

Diagram and typed description. E above X, with a downward arrow between them and no additional labels.

$$\begin{array}{c} E \\ \downarrow \\ X \end{array}$$

E, X are G-spaces; a vector bundle. Fiber to fiber — linearly. Formal differences.

This is a contravariant functor.

Generalization of the notion of a classifying space. Consider

$$E \times_G X = X_G.$$

the orbits of G are contracted to a point; E is the universal space.

If X is a point, then $X_G = B_G$, i.e. $*_G = B_G$.

Uncertain reading. After "If" a dense X is written over earlier strokes. Their original reading is not established.

Original source details: GELFAND-P000159

Theorem. $K_G(X)$ approximately coincides with $K(X_G)$ (already the ordinary K-functor)

$K_G(X)$ is a ring, $X \longrightarrow \bullet$, hence $R_G \longrightarrow K_G(X)$

and therefore ~~[unreadable word]~~ this is an R_G-module (a ring over a subring)

Uncertain reading. Between "therefore" and "this" a word or group of letters is densely cancelled, with a loop-shaped stroke below it; the original reading is not established.

Original source details: GELFAND-P000159

I. Bernstein. The most essential part of the proof: a construction with elliptic operators.



Original source details: GELFAND-P000159

Diagram and typed description. Y above X, a downward arrow, and M_x to its right. Beside it is the description of M as the fiber and the arrow $K(X) \longrightarrow K(Y)$.

$$\begin{array}{c} Y \\ \downarrow \; M_x \\ X \end{array}$$

M is a manifold, the fiber; $K(X) \longrightarrow K(Y)$. Sometimes a reverse map can be constructed.

Let there be on X a family of differential operators D_x: acting in a sheaf over M_x (the fibers over x). Let there be over Y 2 sheaves N_1, N_2.

$$D_x : \Gamma(N_1|_{M_x}) \longrightarrow \Gamma(N_2|_{M_x})$$

— an elliptic operator (or a complex)

For example, the de Rham complex.

$K(Y)$ is a $K(X)$-module. Construct such a map of $K(X)$-modules. V is a sheaf on Y.

$$M_x : \quad D_x \otimes 1 : \Gamma(N_1 \otimes V)_{M_x} \longrightarrow \Gamma(N_2 \otimes V)_{M_x}.$$

An elliptic operator; $\mathrm{Ker}, \mathrm{Coker} < \infty$. The difference of elements in the K-functor gives the required element.

If there is a map

$$X \longrightarrow \underset{\text{Fredholm ops.}}{F(H, H\,[?])}$$



Uncertain reading. The second letter inside $F(H,H)$ is densely overwritten; an H-like sign with lower strokes. The original form beneath them is not established.

Original source details: GELFAND-P000160

then one can def. Ker – Coker as a bundle over X

$$x \longrightarrow A_x$$
$$x \longrightarrow A_x(1-t) + t \cdot A_x P_v$$

P_v — a projector. onto a дп. [?] subspace to V.



Uncertain reading. The small subscript of P in the formula and explanation is v- / V-like; below it the subspace is denoted by capital V.

Original source details: GELFAND-P000160



Uncertain reading. Before “subspace” is an abbreviation resembling “дп.” / “дн.”; the second letter has a joined lower stroke. It is provisionally rendered as “дп.” without expansion. Beneath the end of the line, “к V” (“to V”) is written separately.

Original source details: GELFAND-P000160

Already const. dim. of the kernel (locally)

Bundle $\underline{ind\, V}$.

Next time, Nirenberg’s report and Minlos.

GELFAND-P000161

3/X. Gelfand's sem.

Nirenberg.

Informal expos. of Seeley and Hörmander's index f-la. The f-la is analytic, without any topology, no connections with topology and how the leading terms disappear in it. However, according to Gelfand, the Atiyah–Singer f-la can be written analyt. [as the degree of a mapping, etc.] The same situation for Pontryagin classes.

L — ellipt. operator on a comp. m-fold. Consid. [?] eigenfns.

Original source details: GELFAND-P000161

Uncertain reading. Before "eigenfns.", the abbreviation is "Рассм." / "Расм.": the middle joined strokes are not completely separable. Provisionally rendered as "Consid.", without expansion.

$$L^*L\Psi = \lambda\Psi, \qquad \lambda > 0,$$
$$LL^*(L\Psi) = \lambda L\Psi.$$

- -

$$\| \quad \underline{LL^*\varphi = \lambda\varphi \Rightarrow \varphi = L\Psi}$$



Original source details: GELFAND-P000161

Diagram and typed description. Below the second formula is a dashed line. The formula on the right is separated by a double vertical line and has a wavy underline.

$$E_\lambda(L^*L) \overset{L\,[?]}{\longleftrightarrow} E_\lambda(LL^*), \qquad \text{their dim} = d_\lambda \quad \begin{matrix}\text{for } \lambda>0!\\ \text{(but not for } \lambda=0)\end{matrix}$$



Original source details: GELFAND-P000161

Uncertain reading. Above the two-way arrow is a small sign with a vertical stroke and a lower stroke to the right, resembling L / l; the upper dot meets the level of the dashed line. Provisionally rendered as L.

One can consider

$$(I + L^*L)^s, \qquad \operatorname{Re} s \ll 0$$

Then this is an integr. operator with a good kernel and its action is expressed through eigenfns. [Crossed out: unread word.]



Uncertain reading. Below “eigenfns.” a word resembling “original” is densely crossed out; the internal joined strokes do not permit a confident complete reading.

Original source details: GELFAND-P000161

$$\int K_s(x,y)u(y)\,dy =$$
$$= \int \sum_j \Psi_j(x)\overline{\Psi}_j(y)(1+\lambda_j)^s u(y)\,dy$$

Ψ_j — scalar fns. or sections of a bundle.

$$\mathrm{Tr}\,(I+L^*L)^s = \int \mathrm{Tr}\,K_s(x,x)\,dx$$
$$= \int \sum \Psi_j(x)\overline{\Psi}_j(x\,[?])(1+\lambda_j\,[?])^s\,dx =$$
$$= \sum d_{\lambda_j}(1+\lambda_j)^s$$



Uncertain reading. In the second integral the argument after $\overline{\Psi_j}$ and the beginning of the parenthesis $(1+\lambda_j)$ are very faint: x / another faint argument; $1+$ / faint strokes.

Original source details: GELFAND-P000161

Consider

$$\mathrm{Tr}\,(I+L^*L)^s - \mathrm{Tr}\,(I+LL^*)^s =$$

Everything cancels, except the terms with $\lambda = 0$

$$= \dim\ker L - \dim\ker L^* = \text{æ}\,[?](L) \qquad \text{— index!}$$



Uncertain reading. The sign before (L) has two joined loops: χ / x / an “æ”-like sign. Provisionally rendered as “æ”.

Original source details: GELFAND-P000161

($L^*L\varphi = 0 \;\Rightarrow\; L\varphi = 0$ etc.)

Does not depend on s!

What follows — study of the trace of integr. operators.

A — ellipt. of order $m>0$. — $(I + L^*L)$ —

$$|\arg a(x,\xi) - \pi| \geq \delta > 0, \qquad |\xi| = 1$$

|
this is assumed

(a more gen. situation than $I + L^*L$)

$$\sigma(A) = a_m(x,\xi) + a_{m-1}(x,\xi) + \dots$$



Diagram and typed description. Below "ellipt.": "of order $m > 0$.". Below the angular condition: a short vertical stroke and "this is assumed".

Original source details: GELFAND-P000162

Take $m = 1$ (multipl. by an invertible one)
usual def.:

$$A^s = \frac{1}{2\pi i} \int \lambda^s (\lambda - A)^{-1}\, d\lambda, \qquad \|(\lambda - A)^{-1}\| \leq \frac{C}{1 + |\lambda|}$$



contour, enclos. spectrum.

Uncertain reading. Two long lines, open on the left, joined by a rounded turn on the right; inside, a dashed line with an arrow to the right. Thickening at the bottom of the right turn: the direction of traversal is undetermined.

Original source details: GELFAND-P000162

Thus for negat. powers. For posit. powers multiply by a positive integer power.
We must compute $\int \operatorname{Tr} K_s(x,x)\, dx$
$K_s(x,x)$ — kernel of the operator A^s, $\operatorname{Re} s \ll 0$.
(i) $s \longrightarrow K_s$ — holom. mapping of the region $\operatorname{Re}(ms) < -n - k$ into kernels of class C^k on $M \times M$
(smooth dep. of the kernel on s)

(ii) C — comp. in $M \times M$, not [Crossed out: unread word.] [Inserted above with a bracket: intersec. with] the diagonal, then



Uncertain reading. Between “not” and “the diagonal” a word is densely crossed out; above it, “intersec. with” is inserted with a bracket. Beneath the cancellation are separate loops without a confident literal reading.

Original source details: GELFAND-P000162

$s \longrightarrow K_s|_C$ continues [Crossed out: unread short word.] to a holom. mapping

Uncertain reading. After “continues” a short word resembling “all” / “everything” is crossed out.

Original source details: GELFAND-P000162

of the entire plane into $C^\infty(C)$

(not analyt. in x, since the coeffs. are infinitely differ.)

(iii) for every x, $K_s(x,x)$ is a meromorphic fn. on the entire plane with poles (simple), possibly only at

$$-\frac{n}{m},\quad \frac{1-n}{m},\quad \frac{2-n}{m},\dots,-\frac{1}{m},\quad \frac{1}{m},\quad \frac{2}{m},\dots$$

$(0$ — regul. point$)$

At $s=0$ this is not the identity operator! ([Crossed out: unread short word.] the kernel is not a δ-fn.)



Uncertain reading. Before “the kernel is not”, short joined strokes are densely crossed out, possibly “this”; the literal reading is undetermined.

Original source details: GELFAND-P000162

$$\text{(iv)}\quad (2\pi)^n K_0(x,x) = \frac{1}{m}\int_{|\xi'|=1} d\xi' \int_{-\infty}^{0} b_{-m-n}(x,\xi;\lambda)\,d\lambda$$

K_0 has no singularities. in calc. through coeffs. [Below “coeffs.”: of oper. A.]

A^s — pseudodiff. oper. and its symbol is obtained in a natural way by subst. the symbol in place of A in the f-la for A^s.

The index — difference of two exprs. of type (iv).

GELFAND-P000163

Minlos. Lecture 3.

$(\mathcal{Y}_{\Omega,N}\,[?], H(\alpha), \beta)$



Uncertain reading. The first sign before Ω, N is calligraphic: a tall looped stem, a left arc and a right loop; $\mathcal{Y}$ / $\mathcal{G}$ / another handwritten sign. The same sign occurs later before the mapping and in the distribution. Provisionally rendered as $\mathcal{Y}$.

Original source details: GELFAND-P000163

Can one specify a "limiting sp." possessing asympt. props.? Probably yes, but the proof is again for low density.

Pass to indistinguishable particles

$$\mathcal{Y}'_{\Omega,N} \underset{x_i \neq x_j}{\longrightarrow} C_{\Omega,N}$$

$C_{\Omega,N}$ — N-point subsets of the vessel.

H can be consid. on C, since it is symmetric

The Gibbs distr. is transferred

$$P_{C_{\Omega,N}}(c) = P_{\mathcal{Y}_{\Omega,N}}\Big(\underset{\text{preimage.}}{\widetilde{c}} \Big)$$

* the compl. of $\mathcal{Y}'$ has measure 0.

C_∞ — finite or countable subsets of R^ν (having no accum. points), $d \in C_\infty$.

A Gibbs distr. can be defined on it.

First single out the σ-algebra.

Cylindr. set. $U \subset R^\nu$

$$S_{U,k} \quad (d : n(d,U) = k)$$

the number of points falling in U equals k.

A finite coll. of nonintersect. sets [?]



Uncertain reading. The ending of the abbreviation after "nonintersect." is densely overwritten, with an upper loop and a lower rounded knot; provisionally rendered as "sets". The original strokes underneath the overwriting are undetermined.

Original source details: GELFAND-P000163

$$S_{U_1,U_2,\ldots,U_s;k_1,k_2,\ldots,k_s} = \{d : n(d,U_1) = k_1, \ldots\}$$

The σ-alg. generated by these cylindr. sets. The usual Gibbs distr. generates a measure on this σ-algebra. The resulting measures satisfy the condition of uniform strong mixing. this is the limiting measure. Its existence is proved for low densities.

$$\mu(S_{U_1U_2,k_1k_2}) - \mu(S_{U_1,k_1})\mu(S_{U_2,k_2}) \longrightarrow 0,$$
$$d(U_1, U_2) \longrightarrow \infty$$

(unif. strong mixing)

uniformly over all pairs U

Difficulty — [Unread short word.] exist. on



Uncertain reading. After the dash before “exist.”, a short word: “there is” / “its” / another reading; the joined middle strokes do not permit a confident complete reading.

Original source details: GELFAND-P000163

[Crossed out: unread long word.] cylindr. sets*



Uncertain reading. After “on”, a long word with two descenders is densely crossed out: “correl.” / another word; the readable parts do not permit a confident reconstruction.

Original source details: GELFAND-P000163

This $\longrightarrow$ reformul. of props. of correlation fns.

GELFAND-P000164

26

Props. following from this.

1°. For almost all d, the mean density exists —

— a consequence of Birkhoff's thm. and ergodicity of the measure.

Gelfand's propos.: start with axioms on correlation functions. How to single them out?

Thermodyn. quantities.

E energy $\quad P$ pressure $\quad S$ entropy $\quad F$ free energy

$$Z = \frac{1}{N!} \int_{\mathcal{Y}_{\Omega N}\,[?]} e^{-\beta H(a)}\, da$$



Uncertain reading. The integration-domain sign matches the calligraphic looped sign in the preceding frame: $\mathcal{Y}$ / $\mathcal{G}$ / another sign; the subscripts here are ΩN without a clearly visible comma. Provisionally rendered as $\mathcal{Y}$.

Original source details: GELFAND-P000164

— normaliz. factor.

They are all expressed through $\ln Z$

We shall prove that $\lim \frac{\ln Z}{N}$ exists

GELFAND-P000165

27

$10/\overline{\text{X}}$ Gelfand's sem.

Minlos Lecture 4.

E energy $\quad P$ pressure $\quad S$ entropy

$(\mathcal{Y}\,[?], H(a), \beta)$



Uncertain reading. In the triple, the first sign is the same looped calligraphic sign: $\mathcal{Y}$ / $\mathcal{G}$ / another sign. Provisionally rendered as $\mathcal{Y}$.

Original source details: GELFAND-P000165

1°. $E = \langle H(a)\rangle$. For $H(a) = \sum U(|x_i - x_j|)$ representativeness was proved, i.e.

$$\langle H(a)\rangle \approx \underset{N,\Omega\longrightarrow\infty}{Ne}, \qquad e = e(v\,[?], \beta)$$



Original source details: GELFAND-P000165

Uncertain reading. The argument in $e(v, \beta)$ is written in a v- / ν-like form; the Latin / Greek sign is undistinguished.

$$\langle H(a)\rangle = \frac{\int H(a) e^{-\beta H(a)}\, da}{Z} = -\frac{\partial}{\partial\beta} \ln Z$$

2°. $p(x) = \tau_1(x)\,[?]$. $\quad P = \dfrac{1}{S}\int p(x)\, d\sigma$

(Before the lim. transition)



Original source details: GELFAND-P000165

Uncertain reading. The sign with subscript 1 after $p(x) =$ has an upper arc and a lower hook: τ_1 / r_1; it recurs in the parentheses below.

There is a hypothesis that $p(x) \longrightarrow const$ in the thermodyn. lim. transition. this does not follow from the earlier hypotheses (that $\tau_1 \longrightarrow const$, since this is on $\forall$ finite segment)

$$p = \frac{\partial \ln Z}{\partial V};$$

3°. Entropy of the Gibbs distr.:

$\forall$ distr. $\pi(x)$

$$S = \int \pi(x) \ln \pi(x)\, dx; \qquad \frac{S}{N} = \frac{1}{N}\ln Z - \frac{1}{\beta}\frac{\partial}{\partial\beta}\frac{\ln Z}{N}$$

The lim. of entropy per 1 particle exists.

———— · ————

V. I. Arnold. On Maslov's works.

R^{2n} — phase sp. $p_1, \ldots, p_n, q_1, \ldots, q_n$, if 3 structures are introduced

1) metric $p^2 + q^2$ and scalar prod. (Eucl. structure) (x, y)

2) compl. structure $z = p + iq$, $R^{2n} = C^n$,

I — oper. of multipl. by i.

3) symplect. structure

$[x, y] =$ [Crossed out: unread sign.] (Ix, y)

real scalar prod.

orthog. [unread abbrev.]



Original source details: GELFAND-P000165

Diagram and typed description. The structures are numbered 1), 2), 3). Beside (Ix, y) is a stepped outline, with the lower caption “real scalar prod.”; on the right, an abbreviation after “orthog.” and a pointer from I.



Original source details: GELFAND-P000165

Uncertain reading. Before (Ix, y) a short mathematical sign / term is densely crossed out; the separate strokes do not permit a confident reading.



Original source details: GELFAND-P000165

Uncertain reading. After “orthog.” the abbreviation is densely overwritten: “transf.” / “prod.” / another reading; the beginning and a descender are visible.

this is a skew-sym. form

In mechanics there is only the 3rd structure in [unread abbrev.] sp.



Original source details: GELFAND-P000165

Uncertain reading. Before “sp.” the abbreviation looks like “кас.” / “касс.” / another term; the exact reading is undetermined.

Preserv. of these structures: $O(2n)$, $GL(C, n)$, $Sp(n)$

It is easy to prove that the pairwise intersecs. equal the triple one (from [3])

this is $U(n)$.

A subsp. R^n is called Lagrangian, if the 3rd form is 0 on it $(IR^n \perp R^n)$. E.g., the real and purely imaginary ones.

$$[R^n, R^n] = 0$$

Example. $p = p(q)$ — Lagrangian m-fold $\iff \exists S(q)$, such that $p = \dfrac{\partial S(q)}{\partial q}$

$n = 1$ — every curve is a Lagr. m-fold

$n = 2$ — not every one.

Lagr. planes are real-like, $U(n)$ acts transitively

$O(n)$ leaves the real plane in place.

Lagr. planes $\Lambda(n) = U(n)/O(n)$ — Lagr. Grassmann m-fold

(Lagr. planes have dim. $\leq n$, but here only those of dim. n)

M — Lagrangian m-fold (the tang. sp. at $\forall$ point is Lagrangian)

Construct the mapping

$$\left.\begin{array}{c}\Lambda(n)\\ \downarrow\\ S^1\end{array}\right\} \quad (\text{det of a unit. transf. } U(n))^2$$



Original source details: GELFAND-P000166

Diagram and typed description. The vertical mapping $\Lambda(n) \to S^1$ is joined by a right brace to the square of the determinant.

up to [?] $O(n)$

det $= \pm 1$



Original source details: GELFAND-P000166

Uncertain reading. After “with precision” are two joined looped strokes resembling “до” (“up to”) / the sign $\approx$; provisionally rendered as “up to”.

$U(n)$ takes the real plane to our Lagrangian one.



Original source details: GELFAND-P000166

Diagram and typed description. Three rows: SO, O, S^0; SU, U, S^1; $S\Lambda, \Lambda, S^1$. Arrow labels: det, $\det^2$, z^2.



$S\Lambda$ — fibre of the corresp. bundle.

This is a diag. of bundles.

M^n — Lagr. m-fold. There is a tangent mapping
[Overwritten unread sign.]

Original source details: GELFAND-P000166

Uncertain reading. Before the chain $S^1 \longrightarrow M^n$ is a densely overwritten sign: ∀ / a crossed-out expression; the original sign is undetermined.



Original source details: GELFAND-P000166

Diagram and typed description. Below the chain from M^n to the last S^1 is a long line; γ is on the first arrow, $\det^2$ on the last.

$$S^1 \xrightarrow{\gamma} M^n \longrightarrow \Lambda(n) \xrightarrow{\det^2} S^1$$

$M^n \longrightarrow S^1$ defines a katsikl [?] (in the reverse direction)



Original source details: GELFAND-P000166

Uncertain reading. The word after “defines” looks like “кацикл” / “коцикл” / “нацикл”; the initial letter and first vowel are not confidently distinguished. Provisionally transliterated as “katsikl”.

γ — a curve in M^n

$$\ell\,[?](\gamma) = \deg(\mathrm{Det}^2 \circ \tau \circ \gamma),$$
$$\ell\,[?] \in H^1(M, Z)$$



Original source details: GELFAND-P000166

Uncertain reading. The sign before (γ) and before $\in H^1$ has a tall stem and a lower loop: an l- / ℓ- / μ-like sign. Provisionally rendered as ℓ.

This is the Maslov index, occurring in asymptotic f-las, in particular, the Morse index is obtained (the number of conjug. points on a geod.)

There is another geom. def. of Maslov’s.

GELFAND-P000167

$17/\overline{X}$ Gelfand Sem. Minlos. Lecture 5.

Phase transitions.

29

I. M. Gelfand. Tannaka—Krein duality thm.

G — finite group or compact.

Given irreduc., finite-dimensional reps. in the spaces $A_1, \dots, A_n$

$$A_i \otimes A_k \cong \sum A_j$$

(Tensor prod. decomp. into irreducible representations)

Consider $\sum A_j$ (each 1500 times)

$$A_i \otimes A_j \longrightarrow \sum A_j;$$

i.e. there is a collection of maps d_{ij} into an abstr. module.

If [crossed-out unreadable entry; inserted above: properties of these multiplicities], then the group can be recov. in the finite case, but not in the compact case.



Uncertain reading. After “If” a long entry is crossed out; “properties of these multiplicities” is written over / above it. The two lower strokes and separate lower marks do not give a complete reading of the cancelled entry.

Original source details: GELFAND-P000167

But let the maps d_{ij} into the direct sum be given, then the group can now be reconstructed.

Let $\xi_i \in A_i$.

$$T_i(g)\xi_i \otimes T_k(g)\xi_k = \sum T_{ij}\,[?](g) d^j_{ik}(\xi_i, \xi_k)$$



Uncertain reading. The subscript on the right-hand T has joined or overwritten strokes: ij / j; provisionally rendered as ij. The superscript on d has a loop and upper dot, rendered as j.

Original source details: GELFAND-P000167

In place of $T_i(g)$ write arbitrary C_i — lin. transformations.

Let [?] the formula hold:

Original source details: GELFAND-P000167

Uncertain reading. The word before "the formula hold" is densely overwritten; provisional reading "Let", with the internal cancelled strokes unread.

$$C_i\xi_i \otimes C_k\xi_k = \sum C_j d^j_{ik}(\xi_i, \xi_k).$$

This eq. has solutions $C_i = T_i(g)$.

Then $C_i = T_i(g)$. Thus, all solutions of these eqs. will be $T_i(g)$ and everything is recov. from d^j_{ik}.

There is a generalization to $SL(2, R)$.

Nirenberg.

Varadhan.

$$\frac{\partial u}{\partial t} = \sum a^{ij}(x) u_{x^i x^j}, \qquad u(x, 0) = \delta(x - y)$$

Study the behavior of the fund. solution.

Original source details: GELFAND-P000167

Diagram and typed description. Three arrows from a common point; the vertical one is dashed with t, the right one has x, the lower-left one is unlabelled.



Then

$$u(x) = e^{-\left(\frac{g(x,y)}{t} + o(\frac{1}{t})\right)}, \quad t \longrightarrow 0$$

first term of the exp. in x.

For heat cond.

$$u = C\frac{e^{-\frac{(x-y)^2}{4t}}}{t^{n/2}}$$

$$g(x, y) = d^2(x, y)$$

$d(x, y)$ [crossed-out unreadable term] — dist. along geodesics



Original source details: GELFAND-P000167

Uncertain reading. After $d(x, y)$ a term is densely crossed out; the internal letter strokes are obscured.

($t^{n/2}$ enters $o(\frac{1}{t})$)
in the metric gener. by a^{ij}.
Also elliptic eigenvalues of the Laplace oper. in a domain in the same spirit.

GELFAND-P000168

24/$\overline{X}$. Gelfand Sem.
Vishik. Lecture 1.
I. Defn. [?] of Kohn—Nirenberg.
II. Thm. on boundedness.



Original source details: GELFAND-P000168

Uncertain reading. The abbreviation after I looks like “Opr-yo.” / “Opr-e.”; the upper stroke of the final letter is undetermined, provisionally transcribed “Opr-yo.” and translated “Defn.”.

Prof. Lodzhs. [?] On the Sturm—Liouville eq.



Original source details: GELFAND-P000168

Uncertain reading. The surname after “Prof.” has joined middle and final strokes: “Lodzhs.” / “Loszh.” / “Loskh.” / “Lorch.”; provisionally rendered “Lodzhs.”.

31/$\overline{X}$ Gelfand Sem.
Vishik. Lecture 2.

$$\sigma(A) = a(x,\xi) \longleftrightarrow A$$

$$A.Bu = C_0u + \ldots + C_{s-1}u + T_su,$$

where

$$\sigma(C_k) = \sum_{|\alpha|=k} \frac{1}{\alpha!}\partial^\alpha a(x,\xi) D^\alpha b(x,\xi)$$

$$\partial^\alpha = \frac{\partial^{|\alpha|}}{\partial\xi^\alpha}, \qquad D^\alpha = \left(\frac{1}{i}\frac{\partial}{\partial x}\right)^\alpha$$



Original source details: GELFAND-P000168

Diagram and typed description. A straight bracket with short raised ends under the product $a(x,\xi)b(x,\xi)$; label $\sigma+\lambda$.

$$\sigma(C_0) = \underbrace{a(x,\xi)b(x,\xi)}_{\sigma+\lambda}$$

T_s — oper. of order $\sigma + \lambda - s$.

$$\zeta(\xi)a(x,\xi) = h(x,\xi), \qquad \zeta(\xi)b(x,\xi) = g(x,\xi)$$

$$\widetilde{Au}(\xi) = (2\pi)^{-n/2} \int \widetilde{h}(\xi-\eta,\eta)\widetilde{u}(\eta)d\eta$$
$$\widetilde{Bu}(\eta) = (2\pi)^{-n/2} \int \widetilde{g}(\eta-\tau,\tau)\widetilde{u}(\tau)d\tau$$

$$\widetilde{A.Bu}(\xi) = (2\pi)^{-n/2} \int \widetilde{h}(\xi-\eta,\eta)\widetilde{Bu}(\eta)d\eta =$$

$$= \dots \int \widetilde{h}(\xi-\eta,\eta)d\eta \int \widetilde{g}(\eta-\tau,\tau)\widetilde{u}(\tau)d\tau =$$
$$= \dots \int \left(\int \widetilde{h}(\xi-\eta,\eta)\widetilde{g}(\eta-\tau,\tau)d\eta \right) \widetilde{u}(\tau)d\tau$$

Expand $\widetilde{h}$ by Taylor's formula at $\eta = \tau$

$$\widetilde{h}(\xi-\eta,\eta) = \sum_{|\alpha|\le s-1} \frac{1}{\alpha!}\partial^\alpha \widetilde{h}(\xi-\eta,\tau)(\eta-\tau)^\alpha + h_s(\xi-\eta,\eta,\tau)$$

GELFAND-P000169

$$\int \widetilde{h}(\xi-\eta,\eta)\widetilde{g}(\eta-\tau,\tau)d\eta$$
$$= \int \widetilde{h}(\xi-\eta,\tau)\widetilde{g}(\eta-\tau,\ [?]\,\tau)d\eta +$$
$$+ \sum \frac{1}{\alpha!} \int \partial^\alpha \widetilde{h}(\xi-\eta,\tau)(\eta-\tau)^\alpha \widetilde{g}(\eta-\tau,\tau)d\eta$$



Original source details: GELFAND-P000169

Uncertain reading. In the first right-hand integral, between $\eta - \tau$, and the final τ, is a small densely overwritten sign; a possible cancelled ξ / another sign is undetermined.

30

The 1st convolution corresp. to the product $h(x,\tau)g(x,\tau)$
Everything follows from this.
Defn.

$$\tau_0, \tau_1, \dots, \tau_k, \dots \searrow -\infty$$
$$A_0, A_1, \dots, A_k, \dots$$

A_i homog. of order τ_i with symbols $a_i(x,\xi)$

$$A \sim \sum_{k=0}^{\infty} A_k$$

(In advance $A_i : S \longrightarrow S$)

$$A - \sum_{k=0}^{N} A_k = T_{N+1} \quad \text{— oper. of order } < \tau_N.$$

Symbol [crossed-out formula resembling $\sigma(A)$, reading undetermined]

Original source details: GELFAND-P000169

Uncertain reading. After “Symbol” a formula resembling $\sigma(A)$ is crossed out; dense strokes inside the parentheses leave the reading ambiguous.

formal sum

$$\sum_{k=0}^{\infty} a_k(x,\xi) = \sigma(A)$$

Symbol 0 — $A \in \mathcal{L}_{-\infty}$ [?] (order $-\infty$)



Original source details: GELFAND-P000169

Uncertain reading. The calligraphic letter before $-\infty$ has a tall stem with upper and lower loops: $\mathcal{L}$ / $\mathcal{Y}$ / another handwritten sign. Provisionally rendered as $\mathcal{L}$.

Theorem: the symbol of an oper. is uniquely determ.

$\forall$ [crossed-out unreadable abbreviations] symbol there exists an operator.



Original source details: GELFAND-P000169

Uncertain reading. After $\forall$ two abbreviations are crossed out: “oper. exists” / another entry; lower strokes and a connecting long line are visible.

Pseudodiff. operators form an algebra.

$$\sigma(A.B) = \sum \frac{1}{\alpha!} \partial^{\alpha} \sigma(A) D^{\alpha} \sigma(B)$$

O. A. Oleinik.

One particular problem in mechanics.

Viscous fluids. u, v — veloc. (plane). Navier—Stokes eqs.

$$\begin{cases} \dfrac{\partial u}{\partial t} + u\dfrac{\partial u}{\partial x} + v\dfrac{\partial u}{\partial y} = -\dfrac{1}{\rho}\dfrac{\partial p}{\partial x} + \nu\Delta u \\ \dfrac{\partial v}{\partial t} + u\dfrac{\partial v}{\partial x} + v\dfrac{\partial v}{\partial y} = -\dfrac{1}{\rho}\dfrac{\partial p}{\partial y} + \nu\Delta v \\ \dfrac{\partial u}{\partial x} + \dfrac{\partial v}{\partial y} = 0 \end{cases}$$

ν — viscosity (small)

$\nu = 0$ — Euler eqs. (ideal fluid).

Even for small ν these terms cannot be crossed out (Prandtl)

Ideal fluid: bdy. cond. — normal component of veloc. $= 0$

viscous — both comp. $= 0$ (sticking)



Original source details: GELFAND-P000169

Uncertain reading. Beside the boundary conditions on the left is an arc open to the left and convex to the right. Above and below it are short strokes and arrows pointing right; several separate strokes to the right. No labels; the exact directions of all short strokes are undetermined.



There are always narrow neighb. where strongly otlip. [?]



Original source details: GELFAND-P000169

Uncertain reading. The final abbreviation reads “otlip.” / “otlich.” / another ending; the initial letters “ot” are visible, then joined strokes. Provisionally rendered by the transliteration “otlip.”.

GELFAND-P000170



Typeset diagram



Original source details: GELFAND-P000170

v does not change (bdy. conds. preserved).

u changes strongly.

The Prandtl eqs. remain:

$$\begin{cases} \dfrac{\partial u}{\partial t} + u\dfrac{\partial u}{\partial x} + v\dfrac{\partial u}{\partial y} = -\dfrac{1}{\rho}\dfrac{\partial p}{\partial x} + \nu\dfrac{\partial^2 u}{\partial y^2}, \\ \cancel{\dfrac{\partial p}{\partial y} = 0} \\ \dfrac{\partial u}{\partial x} + \dfrac{\partial v}{\partial y} = 0. \end{cases}$$

p does not change along the normal and it is consid. to be a known fn., obtained from the eqs. of an ideal fluid. $p = p(t, x)$.

Typeset diagram



Original source details: GELFAND-P000170

$$u|_{y=0} = 0, \qquad v|_{y=0} = 0, \qquad u|_{x=0} = u_0(x).$$



Uncertain reading. The subscript sign in the third condition resembles x: $u|_{x=0} = u_0(x)$. An alternative reading is a y-like sign.

Original source details: GELFAND-P000170

$$u(t,x,y) = U(t,x) \qquad y \longrightarrow \infty.$$

$$\begin{cases} \dfrac{\partial u}{\partial t} + u\dfrac{\partial u}{\partial x} + v\dfrac{\partial u}{\partial y} = \nu\dfrac{\partial^2 u}{\partial y^2} - \dfrac{1}{\rho}\dfrac{\partial p(t,x)}{\partial x}, \\ \dfrac{\partial u}{\partial x} + \dfrac{\partial v}{\partial y} = 0. \end{cases}$$

$$u|_{y=0} = 0, \qquad v|_{y=0} = v_0(x,t), \qquad u|_{x=0} = u_0(x),$$

$$u|_{t=0} = u_0(x,t),$$



Uncertain reading. In the condition at $t = 0$, the second argument on the right resembles t: $u_0(x,t)$. The alternative of a y-like lower loop remains.

Original source details: GELFAND-P000170

$$\lim_{y \to +\infty} u(t,x,y) = U(t,x).$$

The soln. is unique, if it exists.

One can prove that it exists for an interval $0 \le t \le T$ for the whole body in the flow (separation may occur, but not instantaneously).

Near the beginning of the flow around the body, it exists for $\forall t$.

$$\frac{\partial p}{\partial x} \le 0.$$

The solution is always stable if it exists and is a nast. [?] bdy. layer.



Uncertain reading. The last abbreviation in the first line reads “nast.”; an alternative reading is “nasl.”. The joined final strokes are dense. The abbreviation is not expanded.

Original source details: GELFAND-P000170

GELFAND-P000171

$14/\overline{XI}$. Sem. of Gelfand.

Agranovich. Lecture 3 on pseudodiff. operators.

Problems of diff. geom.

1. There is a complete Riem. manif. of neg. curvature.

$f \in C_0^\infty(\Omega)$, a ball B is given and $\int$ over any sphere containing B, $= 0$. Prove that $f = 0$ outside B.

(Khelgason) Done for const. curvature. (Khelgason)



Uncertain reading. The surname in both parentheses: “Khelgason” / “Khel’gason”; the joined middle strokes are not fully distinct.

Original source details: GELFAND-P000171

2. [Crossed out: illegible sign]

Uncertain reading. Before Calabi is a small densely cancelled sign with a vertical stroke and lower loop: a star / cancelled letter.

Original source details: GELFAND-P000171

Calabi

$U(x)$ [?] — conv. funct. in R^n.



Uncertain reading. The first function letter is reinforced and overwritten: a U- / u-like sign; the internal overlapping strokes cannot be separated.

Original source details: GELFAND-P000171

$$\det\left(\frac{\partial^2 u}{\partial x_i \partial x_j}\right) \equiv 1.$$

Prove that U is a polynomial of degree 2.

Proved for $n = 2$ and for $n \leq 5$ Calabi.

3. $u(x) \in C^\infty(R^n)$, satisf. [?] the foll. condition:

(Calabi)



Uncertain reading. The end of the abbreviation translated “satisf.” is reinforced with overlapping strokes; it is followed by “the foll. condition:”.

Original source details: GELFAND-P000171

[Crossed out:]

$$\left(1+\sum u_{x_i}^2\right) \text{ [illegible] } \left(\sum {u''_{x_jj}}^2\right)$$
$$-\sum u''_{x_i}\,[?]$$
$$\left(1+\sum u_{x_i}^2\right)\left(\sum {u''_{x_jj}}^2\right)-\sum u''_{x_ix_j}u'_{x_i}u'_{x_j}=0.$$



Uncertain reading. The first line is densely cancelled. Between the first closing parenthesis and the next sum are inseparable overlapping strokes; the ending is $-\sum u''_{x_i}$-like, with uncertain indices and upper strokes. In the uncancelled line a separate raised 2 is visible after the double prime on u_{x_jj}; double j / compressed x_jx_j remains uncertain.

Original source details: GELFAND-P000171

Is it true that u is linear?

(These are the eqns. of min. surfaces.)

Done. (there is a reference in De Giorgi [?])



Uncertain reading. The Latin name: De Giorgi / De Gicrigi / De Giccilgi-like joined middle letters. Before the name is the Russian “y” (“in”, here), with additional vertical strokes.

Original source details: GELFAND-P000171

4. M is a comp. Riem. manif.

$$L_1^2(M),\quad \langle\varphi,\psi\rangle=\int_M \varphi\psi\,dx+\int\langle d\varphi,d\psi\rangle\,dx.$$

GELFAND-P000172

[source number: 33]

$$D(\varphi)=\frac{1}{2}\int_M |d\varphi|^2\,dx \quad \text{— sp. } D^1\,[?].$$



Uncertain reading. Before “sp. D^1” is a dense horizontal stroke: dash / arrow, with an overwritten left end; its direction is undetermined.

Original source details: GELFAND-P000172

$$(L_1^2(M),D)$$
$$(L_1^2(M'),D').$$

There is an isometry of $L_1^2(M)$, inducing a diffeom. of M and M'. Prove that M' and M are isometric.

Invariants — eigenvalues of the Laplace oper.

[Crossed out: ~~Er~~ [?]]

Original source details: GELFAND-P000172

Uncertain reading. Above number 5 is a short cancelled word: “Er” / “Or”; its joined strokes are not fully distinct.

5. M is an n-dim. comp. irreduc. symm. sp.

Δ is the Laplace oper.

V — eigensp. [?], corresp. to the smallest eigenvalue $\neq 0$.

$$\varphi : M \longrightarrow V^*.$$



Original source details: GELFAND-P000172

Uncertain reading. After the abbreviation translated “eigen” is a compressed “pr-i”- / “pr-vo”-like contraction; the final strokes are not fully separate. Before 0 is $\neq$; the map ends in V^*.

If not [?] compact.



Original source details: GELFAND-P000172

Uncertain reading. Before “compact” are faint joined strokes: “If not compact.” / “If … compact.”.

6. M is a complete noncomp. Riem. manif. (3-dim.) of pos. curvature (Ricci tensor > 0).

Will V here go to ∞.

(For 2-dim. manif. prov. by Kn-Fossen [?])



Original source details: GELFAND-P000172

Uncertain reading. The surname is “Kn-Fossen” / “Kon-Fossen”; the middle strokes and possible second “s” are joined.

7. M is a comp. n-dimensional manif. Do ∞-many [Crossed out: ~~par~~ [?]] intersect. geodesics exist.



Original source details: GELFAND-P000172

Uncertain reading. Before “intersect.” is cancelled “par” / a short word with a descending stroke; the contraction is not expanded.

(actually [?] distinct)



Original source details: GELFAND-P000172

Uncertain reading. The first long word in parentheses is read as “actually”; some internal strokes are joined. The second word is “distinct”.

3. [?]

Original source details: GELFAND-P000172

Uncertain reading. The number after 7 looks like “3.” / “8.”: a small upper loop and an open lower arc.

M is a comp. simply connected Riem. manif. in which all geodesics are closed and have the same length. Prove that it is diffeom. to a symm. sp. [Crossed out: $\rho =$ [?] illegible] of the 1st type. (?)

Original source details: GELFAND-P000172

Uncertain reading. Before “of the 1st type” is a cancelled $\rho =$- / $p =$-like sign with an overlapping continuation.

There is an analyt. manif., diffeom. to a sphere, but not isometr.
(Bott). Bott proved that it has the same cohom. [?] structure.



Original source details: GELFAND-P000172

Uncertain reading. The internal strokes in the contraction before “structure” are joined; it is read as “cohom.”. Under it are two short strokes. Bott is written twice, the first time in parentheses.

9. Does a contact structure exist on every comp. M^3?

GELFAND-P000173

$21/\overline{XI}$. Sem. of Gelfand.

Arnold.

Lecture 1.

Theory of singularities of diff. mappings.

$$f : M^m \longrightarrow N^n.$$

$y = x^2$.

Typeset diagram

Original source details: GELFAND-P000173

Stab. [Crossed out: illegible word] sing.

Undeciphered passage. Between “Stab.” and “sing.” is a densely cancelled short word; the letters beneath the cancellation strokes are unrecovered.

Original source details: GELFAND-P000173

(for a nearby diff. mapping, reduced to the same form)

$y = x^3$.



Typeset diagram



Original source details: GELFAND-P000173

Unstab. sing.

Original source details: GELFAND-P000173

Uncertain reading. At $y = x^2$ is a U-shaped line with an almost vertical internal stroke and a horizontal line below it. At $y = x^3$ are axes with upward and rightward arrows, an S-like line from lower left to upper right, and small oblique strokes left of the crossing. The axes have no letter labels; exact contacts in the dense crossing are undetermined.



Original source details: GELFAND-P000173

Typeset diagram

$$\begin{array}{ccc} M^m & \xrightarrow{\ f\ } & N^n \\ {\scriptstyle h}\downarrow & & \downarrow{\scriptstyle k} \\ M^m & \xrightarrow{\ g\ } & N^n \end{array}$$

Top. stab. $\exists$ homeom. h and k.

(diff.)

$\downarrow$

Diff. stab.

Stability at 0 — the same on neighborhoods.

(germs of a mapping)

(One can change the manifolds so that the mapping is given by the same formulas)

Rang max [?] — stable (nondeg. funct.).

Original source details: GELFAND-P000173

Uncertain reading. The beginning of the line: Rang max / Ring max / min max; the first sign is tall and looped, the final stroke of the first word descends.

Morse lemma — nondeg. quadr. form ($R^n \to R^1$ stab.)

Theorem [?] of Whitney $M^2 \to N^2$ also an exhaustive res.



Original source details: GELFAND-P000173

Uncertain reading. The first source word is "Teorem"-like; its short final strokes are joined. Then Whitney and a map with two upper 2s.

Morse M is comp. 1) stab. mappings $M \to R^1$ form an open everywhere dense set.

2) Conditions for stability (necess. and suff.):

GELFAND-P000174

M.1 All crit. [Crossed out: z [?], illegible] points nondeg.

Original source details: GELFAND-P000174

Uncertain reading. Before “points” is a cancelled short word with a “z”-like beginning; the reading “values” abbreviated / overlapping short strokes.

M.2 All crit. values are distinct.

3) loc. assertion loc. stability $\Longleftrightarrow$ one can choose coords. so that the funct. is written (one of the ways)

$$y = x_1$$
$$y = x_1^2 + \ldots + x_k^2 - x_{k+1}^2 - \ldots - x_m^2.$$

(stab. both top. and diff.)

Whitney's theorem.

1) Stab. mappings are dense.

2) $f : M^2 \to R^2$ stab. $\Longleftrightarrow$

$\Longleftrightarrow$ W1 [?] all crit. points nondeg.



Original source details: GELFAND-P000174

Uncertain reading. The first underlined number is W1 / M1; the angular strokes overlap heavily. The equivalence sign is written twice, again $\Longleftrightarrow$ before the number. The next number is W2.

W2 crit. values are transverse (images of folds)

3) Stab. at a given point $\Longleftrightarrow$ the mapping is written by one of the formulas:

1. $y_1 = x_1, \quad y_2 = x_2,$
2. $y_1 = x_1, \quad y_2 = x_2^2$ (folds),
3. $y_1 = x_1, \quad y_2 = x_1 x_2 + x_2^3.$

Original source details: GELFAND-P000174

Typeset diagram



Original source details: GELFAND-P000174

Uncertain reading. A sphere-like outline with a transverse ellipse whose upper arc is dashed; below it are an open oval and a plane with gaps in the upper edge and lower left corner. There are no labels or connecting arrow; the precise projection is unspecified.

2. — fold points, these are curves where the Jacobian $= 0$.

W2 — images of folds [Crossed out: ~~not~~ [?]] intersect. transvers.



Original source details: GELFAND-P000174

Uncertain reading. Before “intersect.” is a short crossed “not”-like word / dense crossed sign.

W3 — images of cusps are distinct.

3.



Original source details: GELFAND-P000174

Typeset diagram





Original source details: GELFAND-P000174

Uncertain reading. At left are axes x_1, x_2, a line with two leftward branches and short strokes, and a “cusps” callout to the lower branch. At right are axes y_1, y_2 and two thick branches meeting near their crossing. Exact stroke placement and contact in the dense crossing remain uncertain.

Original source details: GELFAND-P000174

Typeset diagram



For $x_1 > 0$, monot. on vert. lines.

$$x_1 = \text{const} \Rightarrow y_1 = \text{const}\,.$$

For $x_1 < 0$ there will be



Typeset diagram



Original source details: GELFAND-P000174



Original source details: GELFAND-P000174

Uncertain reading. An arrowless horizontal line and a curve descending from upper left, then a trough, a rise above the horizontal and a descent at right. There are no letter labels; crossing placement is specified only by the drawing.

Short strokes on the parab. [?] — directions of degeneracy.
A cusp is where the dir. of degen. is tangent to the parabola.



Uncertain reading. The first line has “parab.” / a compressed “prab.”-like contraction with overlapping initial strokes. The last line writes “parabola” in full.

Original source details: GELFAND-P000174

GELFAND-P000175

[source number: 36]

Stability — the roots must merge (transition from a nonmonot. map to a monotone one)
This is odd [?]. order.



Uncertain reading. The ending of “odd” / the abbreviated Russian word is compressed; a separate dot follows it, before “order”.

Original source details: GELFAND-P000175

$$z \longrightarrow z^2$$

Unstable singularity.

Sought [?] perturbation:

$$z \longrightarrow z^2 + \varepsilon\bar{z}.$$



Uncertain reading. The first word has “Iskanoe” / “Iskomoe”-like joined strokes. The second word is “perturbation”; the final z has a horizontal bar. The lower oblique strokes belong to the adjacent drawing.

Original source details: GELFAND-P000175



Typeset diagram



Original source details: GELFAND-P000175

Typeset diagram



Original source details: GELFAND-P000175



Original source details: GELFAND-P000175

Typeset diagram



Uncertain reading. Three nested circles with a central point and three points on the middle circle; callout “Sing.”. Beside them are three loop-like petals, three heavy points, connecting strokes and a small central contour. At right are concave triangular contours, an upper loop, an outer dashed arc, lower dashed loops and short oblique strokes. Exact connectivity remains uncertain at the dense crossings.



Original source details: GELFAND-P000175

(Where did the circles go?)

Large circles make 2 turns (trefoil [?] knot)

Большие окр. делают 2 оборота (трилистн, узел)



Original source details: GELFAND-P000175

Uncertain reading. “Trefoil” is abbreviated with a fused final letter; a separate descending stroke follows its dot. The number of turns is written 2.

Up to dim. 5-6 there is a classific.

Theorem 1 (Thom)

For maps $R^9 \to R^9$ (and higher), everywhere density of stable germs does not hold.

(from R^9 there are differential invariants and they men.[?])

Starting from 12, there are infinitely many invariants.



Uncertain reading. The Russian abbreviation “men.” / similar strokes remains unexpanded. “Starting from 12” is emphasized below by a wavy line with raised ends.

Original source details: GELFAND-P000175

Thom:

Theorem 2.

There exists a discrete topol. classific. exists!!!

(What it looks like — is unknown)

(If from the space of all maps one discards A_∞ — infinite codim.

$$A = \bigcup_{\gamma \in \Gamma} A_\gamma + A_\infty.$$

Γ — a countable set.

Each A_γ — finite codim.; all germs of A_γ are topol. equiv. to one another, for different A_γ inequivalent.

(in A jet [?] alg. varieties with topol. [?]

topol. stable



Uncertain reading. The right insertion has “jet” / “struct.” and “topol.” / “that”; an opening parenthesis. Below it, separately, “topol. stable” with an oblique leader from the finite-codimension line; the exact attachment of the insertion is not established.

Original source details: GELFAND-P000175

(A line maps to a point — a map ent. [?] in A_∞)



Uncertain reading. The Russian contraction is “ent.” / joined “vl.”-like strokes; “maps” and “to a point” are separately underlined.

Original source details: GELFAND-P000175

$f : M^m \to N^n$ a map germ.

Jet of ord. [?] k: $j_0^k(f)$ — the equivalence class of maps having contact of ord. k



Uncertain reading. “Jet” is doubly underlined. The first Russian “ord.” has superposed strokes; the next line has “contact of ord. k”.

Original source details: GELFAND-P000175

$$f(x) - g(x) = o(x^k) \quad \text{at the point } 0.$$



Uncertain reading. The remainder sign is a small oval o / O; its argument is x^k without absolute-value bars. The line lies at the lower edge of the frame.

Original source details: GELFAND-P000175

GELFAND-P000176

Jets of order 0 — the image of a point
„ 1 — the image and its differential.

$$j_0^k(f) \quad \text{defined invariantly} \quad \text{(def. invar.)}$$

Jets of fixed ord. — an alg. variety (in coordinates — — Taylor series). The bundle of jets of maps from M to N

$$J^k(M, N) \quad \text{— a bundle over } M.$$

For $N = R^n$ this is a vector bundle.

(With natural topol., diff. and alg. structure)

$$R^n \longrightarrow R^1.$$

$J_x^k(R^n, R^1)$ [?] — the ring of truncated polynomials



Uncertain reading. Initial letter J / j with dense transverse strokes through its vertical part; subscript x and superscript k are separately visible.

Original source details: GELFAND-P000176

$$R[x_1, \ldots, x_n]$$

$$j_x^k(f) = j_x^k(n, 1)$$
$$(f : R^n \to R^1).$$

$$j_0^k(n,1) = R[x_1,\dots,x_n]/M^k \qquad (M=(x_1,\dots,x_n)).$$



Uncertain reading. The denominator visibly has M^k; no superscript $+1$ is visible. The M has a long left leg; short neighboring strokes remain unexpanded.

Original source details: GELFAND-P000176

A variety of finite codim. e [?] in $J^k(M,N)$ at a point, if it is given by e [?] equations.



Uncertain reading. The letter for codimension and number of equations is heavily retraced: e / an ε-like form. "Variety" is underlined.

Original source details: GELFAND-P000176

Natural map:

$$f \xrightarrow{j} j_x^k(f).$$

ξ [?]

Uncertain reading. At right a separate vertical three-lobed sign: ξ / flourish; no connection to the formula is shown.

Original source details: GELFAND-P000176

Admissible

[Cancelled: illegible] [Cancelled: ~~Adm.~~ [?]] set: inverse images of sets of finite codim. in one of the J.



Undeciphered passage. The cancelled short word at left is unrecovered. In the next word, "Adm." / "This"-like superposed strokes; underlined "Admissible" inserted above, followed by underlined "set:".

Original source details: GELFAND-P000176

Consider $f : M^m \longrightarrow N^n$.

$$x \in \Sigma^i(f), \quad \text{if}$$
$$\dim \operatorname{Ker} df\big|_x = i.$$



Typeset diagram



Original source details: GELFAND-P000176



Original source details: GELFAND-P000176

Uncertain reading. Horizontal and vertical lines without arrows or letters; a heavy point near the crossing, a rounded curve with two leftward branches. Exact contact inside the heavy point remains uncertain.

Σ^0 — all points without the parab.

Σ^1 — the whole parabola.

Theorem.

The set of all maps where Σ^i are varieties is dense, and

$$\operatorname{codim} \Sigma^i = \underline{\operatorname{corang}_x} \cdot \operatorname{corang}_y .$$

$$\underline{(i =)(m - r)} \qquad \underline{n - r}.$$



Original source details: GELFAND-P000176

Uncertain reading. The upper formula has a dot between coranks; the first corank is underlined. Below, separately, "$(i =)(m - r)$", a heavily crossed connecting stroke with a right arc, and underlined $n - r$. No clear product sign is recovered between the lower factors; two short heavy strokes lie under m at the edge.

(r — rank of the diff.)

(This formula is, however, obvious.)

GELFAND-P000177

[source number: 37]

$z \longrightarrow z^2$ is already unstable.

The condition on Σ^i — an algebraic subset in J — the required codimensions (minors $= 0$).

In $J^1(M, N)$ the varieties $\Sigma^1, \Sigma^2, \ldots$ are defined only by germs.

An actual map $\Rightarrow$ a section.

(Corank [?] — codim. of the image d..)



Uncertain reading. The opening “Corank” / “Codim.” is heavily overwritten and doubly underlined. Two small separate strokes follow d; they are not expanded into a map name.

Original source details: GELFAND-P000177



Typeset diagram

$$A \xrightarrow{f} B \xleftarrow{g} C$$

Original source details: GELFAND-P000177



Uncertain reading. At left $A \to B$, with f above the arrow. At right $B \leftarrow C$ with g; the right end of the heavy stroke also has a pointed thickening, so the appearance of two heads remains uncertain.

Original source details: GELFAND-P000177

f, g are transverse if $\forall a \in f^{-1}(b), c \in g^{-1}(b)$ at the point $b \in B$

the relation holds:

$$f_* TA_a + g_* TC_c = TB_b \qquad \text{(may intersect).}$$

2 lines in R^3 are not transverse at even 1 point (if they intersect) (they may intersect).

If a map is transverse to a subvariety, (g — the embedding $C \subset B$), then the inverse image of the variety — is a variety.

Its Codim is the same

$$\operatorname{codim} f^{-1}C\big|_A = \operatorname{codim} C\big|_B.$$

If $f : M \longrightarrow N$ is transverse to Σ^i, then all is well.

One can perturb $\forall$ map.

Further classific.

$$\Sigma^i f \subset M, \qquad f : M \longrightarrow N.$$

Suppose that the section defined by the map f is transverse to Σ^i in the jets.

At $\forall$ point $x \longrightarrow J$. It is transverse to the map Σ^i (without f) [?] in J.



Original source details: GELFAND-P000177

Uncertain reading. After “without f”, a closing sign with several bends: a round parenthesis / curled stroke. Both letters are J; the phrase reads “map Σ^i”.

There arises a map



Original source details: GELFAND-P000177

Typeset diagram

$$f|\Sigma^i f \subset M \longrightarrow N$$



Original source details: GELFAND-P000177

Typeset diagram





Original source details: GELFAND-P000177

Uncertain reading. A rounded curve with a right vertex and two leftward branches, without axes or labels. Four long strokes on the upper branch; three long and one short stroke near the left edge on the lower branch. Exact stroke lengths and contacts remain uncertain.

GELFAND-P000178

The same classific. is applied to it:

$$\Sigma^j f | \Sigma^i f$$

$x \in \Sigma^{ij}(f)$ — a subvariety (Boardman 1965).

(One can perturb) $\forall$ numbers of indices.

Thm.

1. $\forall k$ in $J^k(M,N)$ algebraic subvarieties are defined

$$\Sigma^I \qquad I = (i_1, \dots, i_k)$$

(independent of f.)

Codim is $\nu(I)$ [?] has been calculated (complicated).



Uncertain reading. The function sign is ν / a v-like form, followed by argument I in parentheses. “Codim” is in Latin letters.

Original source details: GELFAND-P000178

2. Every map is approximated by a map transverse to all these

$$\Sigma^I(f).$$

Classific. Σ^{110} and so on.

This is not a complete set of invariants (first in R^4), but [?] by rank drops are not distinguished.



Uncertain reading. The word after the comma is “but” / “by”: the first joined sign has two rising legs. Then “by rank drops are not distinguished”, with no separate subject. The Russian “not complete” is written separately; the exponent on R is4.

Original source details: GELFAND-P000178

GELFAND-P000179

28/XI. Sem. Gelfand.

[Arnold [Cancelled: UR [?]]]



Uncertain reading. After the surname, inside square brackets, two or three heavily cancelled signs: UR-like / Ch-like superposed strokes. The word is not established.

Original source details: GELFAND-P000179

$$f : M^m \longrightarrow N^n.$$

$$\Sigma^i(f) = \{x \in M^m : \dim \ker df_x = i\} \quad \text{— a subset.}$$

if it is a variety, then

$$\Sigma^{ij}(f) = \Sigma^j\Sigma^i(f) = \Sigma^j(f|\Sigma^i f) \quad \text{— Thom's naive def..}$$

(forget)

For $\forall$ multi-index $i_1, i_2, \ldots, i_k = I$ is defined

$$\Sigma^I(f),$$

if varieties are obtained at every step.

There must be

$$i_1 \geq i_2 \geq \ldots$$

$$K_1 = \text{Ker}\, df_x, \qquad K_2 \subset K_1 \quad \text{— next kernel on the subsequent}$$

subvariety.

There is a subset independent of the map $\Sigma^I \subset J^k(M, N)$ (is constructed)

A — the ring of functions on a variety with coord. system $x_1, \ldots, x_m$
$B \longrightarrow$ an ideal in A.

The new ideal — the Jacobian extension of B of ord. k $\Delta_k(B)$ — — to the functions from $B \ni \{f\}$ adjoin the minors formed from them

of order k $\left|\frac{\partial f_i}{\partial x_j}\right|$ and adjoin to the ideal.

[Cancelled: ~~This~~ [?]] They also generate $\Delta_k(B)$.



Uncertain reading. Initial cancelled "This..." / similar joined letters with a superposed horizontal stroke. The readable following phrase begins "They also generate".

Original source details: GELFAND-P000179

This does not depend on coordinates (in fact an invar. constr.)

$$\frac{\partial f}{\partial x'_i} = \sum_j \frac{\partial f}{\partial x_j} \cdot \frac{\partial x_j}{\partial x'_i}.$$

($k = 1$ [?] are expressed)
through one another



Uncertain reading. The first sign is k / a κ-like form; $= 1$ is visible. The closing parenthesis follows “are expressed”, while “through one another” is separate below at the frame boundary.

Original source details: GELFAND-P000179

GELFAND-P000180

Relation of extensions of different orders.

$k \nearrow \ldots$ ideals $\searrow \ldots$ (decrease)

The extension $\Delta_k(B)$ is critical if k is max for which the ideal is not yet all of B.

$$\Delta_{k-1}B = A, \qquad \Delta_k B \subset A$$

$\Delta_0 B = A$ by [cancelled: illegible] definition.



Uncertain reading. Between "by" and "definition" is a small densely overwritten sign with a downward stroke: a φ-like sign / an unidentified contraction. The cancelled text is undetermined.

Original source details: GELFAND-P000180

Example: the ideal generated by x^3.

$k = 1$ $\quad \Delta_1 = \{x^2\}$ $\quad$ critical 1st

$$\Delta_1^2(\Delta_1 x^2) = \{x\}$$



Uncertain reading. The small upper sign on the first Δ_1 resembles 2 / a densely overwritten upper sign. Inside the parentheses, $\Delta_1 x^2$; at right, $\{x\}$.

Original source details: GELFAND-P000180

The extension is performed several times.

Definition: $\Delta^k = \Delta_{m-k+1}$ $\quad (f : M^m \longrightarrow N^n)$

Def. of Boardman:

Consider a map f:

$$y_1 = f_1(x_1, \ldots, x_m)$$
$$\ldots$$
$$y_n = f_n(x_1, \ldots, x_m), \qquad f(0) = 0$$

The ring of germs of smooth functions at 0.

Consider the ideal generated by $f_1, \ldots, f_n$, $\quad B = \{f_i\}$

In form the def. depends on coordinates, but in fact it does not.



Original source details: GELFAND-P000180

Typeset diagram





Original source details: GELFAND-P000180

Uncertain reading. The insertion at left reads "Consider the jet of ord. k of the map f": Russian "struyu" / "struya"-like joined and reinforced strokes; the final letter and the beginning of the abbreviation for "map" are not fully separate. A vertical line separates the insertion.

It does not depend on the map f, but only on the jet of ord. k.

The ideal does not depend on X.

Nor does it depend on Y (needs checking).

Main theorem.

This Σ^I is an algebraic variety in the space of jets, and its codimensions have been calculated (functions $= 0$ and $\neq 0$, polynom.)

$$c(I) = (m - n + i_1)\mu(i_1, i_2, \ldots, i_k) - (i_1 - i_2)\mu(i_2, \ldots, i_k) -$$
$$-(i_2 - i_3)\mu(i_3, \ldots, i_k) - \ldots - (i_{k-1} - i_k)\mu(i_k)$$

GELFAND-P000181

[source number: 42]

$\mu(i_1, \ldots, i_r)$ is the number of seq. $j_1, \ldots, j_r$ such that

$$1)\ j_1 \geq \ldots \geq j_r$$
$$2)\ i_s \geq j_s \geq 0 \quad \text{for all } \underline{1 \leq s \leq r}.$$

Theorem of Boardman

1. Σ^I is a variety in the space of jets.

2. [Cancelled: illegible] codimension formula.



Uncertain reading. Before “codimension formula” several joined letters with a downward stroke are cancelled. The literal cancelled reading is undetermined.

Original source details: GELFAND-P000181

3. f determines a section in the space of jets, base $\longrightarrow$

$\longrightarrow$ into the space of jets



Original source details: GELFAND-P000181

Typeset diagram



For almost all f, transv. to Σ^i

Then Thom’s naive def. and its red. [?] to Σ^i is applicable;

i.e., $f \in \Sigma^I$ in Thom’s sense $\Longleftrightarrow$ the germ of f at $\forall$ point $\in \Sigma^I$ in Boardman’s sense.



Uncertain reading. After “its” the source contraction reads “priv.” / “pril.”: the final joined stroke forms a loop; the expanded word is undetermined. “Red.” is provisional. The source “is applicable” is singular; on the following line both Σ have a superscript capital I.

Original source details: GELFAND-P000181

Almost all are transv. by the general theorem.

$\underline{R^n \longrightarrow R^n}$.

exact

When do sing. {codim. n) first appear



Uncertain reading. “Exact” is inserted above the source abbreviation for “sing.” and connected to it by a lower brace. Before “codim.” a reinforced bracket-like sign: a left brace / an overwritten parenthesis; at right a parenthesis.

Original source details: GELFAND-P000181

n	1	2	3	4	5	6	7	8	(9)
I	1	11	1_3	1_4	1_5	1_6	1_7	1_8	1_9
				2			21		3

x^2 Σ^{11}

(cusp)

(Need to write out precisely)

(For a general map, more precisely. These are in fact all; further ones are not known.)

10
1_{10}
$2, 2$
$2, 1, 1$

In R^4 [cancelled: illegible] Σ is not a complete set of inv.



Uncertain reading. Between R^4 and Σ a small sign is densely cancelled; the literal reading is undetermined. The source words for “not complete” are written separately.

Original source details: GELFAND-P000181

In dim. 16, sing.: 4 of them.

$n = 9$:

on M^8 — one-dim. folds

M^7 — two-dim. cusps

M^5 — sing. of type 2.

The table is easily comp. using the combinat. formula.

1_9: the rank drops by 1 on M^8, then by another 1 on M^7.

GELFAND-P000182

Theorem (Moren [?])
(generaliz. of Whitney).



Original source details: GELFAND-P000182

Uncertain reading. The parenthesized name: “Moren” / “Morin” / Cyrillic “Moren”; the joined third letter and following vowel are not unambiguous. “Theorem” is underlined; below, “(generaliz. of Whitney).”.

$$j_0^{k+1} f \in \Sigma^{1_n 0}$$
$$\Updownarrow$$



Original source details: GELFAND-P000182

Uncertain reading. The small subscript on 1 in the superscript of Σ: n / k, heavily reinforced. At left, jet order $k+1$; the final 0 is separate.

(e.g. [?] 110)
0: transversality.



Original source details: GELFAND-P000182

Uncertain reading. The right parenthesis before 110 has Russian “na pr.” / joined “napr.”; the abbreviation’s strokes are not fully separate. Beneath is the separate line “0: transversality.”.

$\exists$ coordinates in which

$$x_1 = y_1$$
$$\dots$$
$$x_{n-1} = y_{n-1}$$
$$y_n = x_1 x_n + x_2 x_n^2 + \dots + x_{n-1} x_n^{n-1} + x_n^{n+1}$$

(there, a cubic straight away)
(For classes 1_n, sing. det. up to diffeom.)
For type 20 the class is not a complete inv.

(up to diffeom.)

$$\Sigma^{20} \quad \text{codim. } 4$$
$$f : R^4 \longrightarrow R^4$$

The variety [cancelled: sing.?] is divided into 7 pieces of different nature.



Original source details: GELFAND-P000182

Uncertain reading. After “The variety” a cancelled contraction resembles “sing.” / another cancelled inscription. The joined letters under the strokes do not give a certain full reading. The entire line is underlined.

Quadratic differential of a map.

$f : M^m \longrightarrow N^n$

(In J^k, two diffeomorphism groups of M^m and N^n —

— orbits arise. (at singular points, what orbits))

$$f_x : TM_x \longrightarrow TN_{f(x)}$$

There are $Ker\, f_x \subset TM_x$, $\quad Coker\, f_x = TN_{f(x)}/Im\, f_x$.

$$f_{xx} : Ker\, f_x \longrightarrow Coker\, f_x$$

(a quadratic map, i.e., $\psi : A \longrightarrow B$

$$A \xrightarrow{\Delta} A \times A \xrightarrow{\overline{\psi}} B$$
$$\Delta \circ \overline{\psi} = \psi)$$

Def. using a system of coordinates.



Original source details: GELFAND-P000182

Typeset diagram



$X : TM_x \longrightarrow M$ (natural coord. syst.)

$y : TN_y\,[?] \longrightarrow N \qquad (\xi \longrightarrow \xi t)$



Uncertain reading. The first letter X is capital, the second y lowercase. In TN_y, the N is densely overwritten: N / an M-like lower stroke; the exact underlying form is undetermined. At right, $\xi \longrightarrow \xi t$.

Original source details: GELFAND-P000182

GELFAND-P000183

[source number: 43]

$\xi \in Ker\, f_x$

$X\xi$: a point of the variety

$$\lim_{t\to 0} \frac{(y^{-1} f X\xi t / Im\, f_x)}{t^2}$$

It is easy to prove that this does not depend on the choice of coord. syst.

(The cubic diff. cannot be def. this way)

Look into this!

A bilinear map $f_{xx} \Longrightarrow$ a pencil of quadr. forms.

Let $\alpha \in \underbrace{CoCoker\, f_0}_{(Coker\, f_0)'} = C'$

αf_{00} is a quadr. form on the kernel.

(already a pure quadr. form)

A plane in the space of quadr. forms.

It does not depend on [cancelled: illegible] the choice of coordinates.



Uncertain reading. Before “the choice of coordinates” a short inscription is densely cancelled; the literal reading is undetermined.

Original source details: GELFAND-P000183

$$C' \longrightarrow \text{Qu.}_{Ker\, f_0}$$

Example. $\Sigma^{20} : R^4 \longrightarrow R^4$

$$2 = dim\, Ker\, f_0,$$

Hence $dim\, Coker\, f_0 = 2$

forms: a 3-dim. space

(in 2 vars.)

$$ax_1^2 + 2bx_1x_2 + cx_2^2.$$

There is a classific. by rank



Typeset diagram



Original source details: GELFAND-P000183

$$\text{Rank} < 2 \quad \Longrightarrow \quad \text{cone } b^2 = ac$$

(inv. def.)

There is also a plane there (a map of a plane into the space of quadr. forms). It can have different positions

(intersects, is tangent, [cancelled: illegible], on different sides $\pm$)



Uncertain reading. After “is tangent” is a cancelled inscription with an oval loop / parenthesis and lower strokes; the literal reading is undetermined. After it, “on different sides $\pm$”.

Original source details: GELFAND-P000183

These positions (a total of 7 pos., including degeneracies), if different, will be different classes of maps.

And there are indeed 7 orbits.

GELFAND-P000184

The maps can be written.

$$y_1 = x_1 x_2$$
$$y_2 = x_1^2 \pm x_2^2 + \underbrace{x_1 x_3 + x_2 x_4}_{\text{added for transversality.}}$$
$$y_3 = x_3$$
$$y_4 = x_4$$

———— · ————

In R^5 there can be a curve Σ^{20} with different sing. along the curve.
In the complex case, Σ^{20} $\pm$ do not differ, but the parab. [?] case remains.



Uncertain reading. After “but”, the contraction reads “parab.” / “pereob.” / “perekhod.”; the joined middle strokes do not give an unambiguous full reading.

Original source details: GELFAND-P000184

Σ^{20}: all sing. are stable, there is a diff. classific.
Σ^{30}: this is no longer so.

———— · ————

Thm. of Thom.

$$\Sigma^{30} : R^9 \longrightarrow R^9$$
$$dim\, Ker\, f_0 = 3$$
$$dim\, Coker\, f_0 = 3$$

the space of sing. is not discrete (there are moduli)
(Everything is still quadratic)
Lemma. For $n \geq 3$, the dimension of the orbit

$$GL(n, R) \times GL(n, R)$$

in $H(n, n)$: quadr. forms in n vars.

(change of vars.)

[cancelled: ?] in the space and image



Uncertain reading. Beneath “(change of vars.)”, before “in the space and image”, a short sign with joined loops is cancelled. The original inscription is undetermined. A bent stroke connects the parenthesis and interlinear insertion.

Original source details: GELFAND-P000184

$codim$ orbits > 0

(no orbits of full dim.)

group $2n^2$, forms $\frac{n^2(n+1)}{2}$, and there is always

a one-dim. stationary subgroup ≥ 1

(mult. by a number there and there)

$\underline{n = 3}$ and higher.

Hence it follows that moduli exist.



Original source details: GELFAND-P000184

Typeset diagram





Uncertain reading. At left a vertical axis n, below a horizontal m, two rising lines, four rectangular outlines, and a lower strip with six vertical strokes. The labels $n > 2m$, “emb.”, “Whitney”, and “Morse thm.” are legible; the small right label is “im. dial.” / “mil. diap.” / an undetermined contraction. Dense crossings at the origin and separate short strokes do not establish additional numerical boundaries.

Original source details: GELFAND-P000184

In cells $9, 9$ and $6, 9$

it has been determined where there are moduli

(*J.* Mather: announced)

He also: classific. of stable sing.

GELFAND-P000185

[source number: 44]

The only inv. of stable sing. is the local ring.

Local ring (inv., but. [?] all the preceding.) and prepar. theorem



Uncertain reading. The short inscription between “inv.,” and “all the preceding.” reads Russian “no.” / “ne.” / an undetermined contraction. The source spelling is “predid.”; the heading words and “and” are separately underlined.

Original source details: GELFAND-P000185

$$f : M^m \longrightarrow N^n, \qquad f(0) = 0.$$

$$O_* [?] = \frac{E_x}{(f_* \mathfrak{M} [?] E_y) E}$$



Uncertain reading. The initial letter is O without a diagonal tail; the reinforced lower sign is $*$ / x / f. The lower right stroke of $\mathfrak{M}$ is joined to the letter: part of its form / subscript 1; a separate index is undetermined. After the parenthesis, a separate E without a visible subscript, beneath the common quotient slash. The later Q has a separate tail.

Original source details: GELFAND-P000185

E_x: the ring of germs of infinitely diff. functions on M at 0.

E_y: similarly, in y

$\mathfrak{M} E_y$: the max ideal.

f_* is def. naturally.

Meaning: “the ring of functions on the coalesced inverse image.”

Example. $f(x) = x^2$,

$$\mathfrak{M} E_y = y E_y = a_1 y + \dots$$
$$f_* \mathfrak{M} E_y = a_1 x^2 + a_2 x^4 + \dots$$

Mult. by E: add everything above the 2nd.

$a_1 x^2 + \ldots$

Take the quotient: $a + bx$

Typeset diagram



Original source details: GELFAND-P000185

the ring of functions on 2 coalesced points (an infinites. pair of points)

Let us move: it will remain so, and let $y \longrightarrow 0$.



Original source details: GELFAND-P000185

Typeset diagram

$dim\, Q =$ multiplicity of the point 0

$f : C^n \longrightarrow C^m$

in the analytic case

(in the general case)

Apparently so.

Theorem: (Mather)

Stable sing. are equiv. $\Longleftrightarrow$ their local rings coincide.

Another theorem. (Mather)

a sing. is stable $\Longleftrightarrow$ it is infinitesim. stable.

The latter means:

At the point: $y = f(x)$



Typeset diagram



Original source details: GELFAND-P000185

h and k must exist infinitesimally.



Typeset diagram



Original source details: GELFAND-P000185



Uncertain reading. Axes N upward and M rightward; a wavy graph with a maximum and minimum, and seven crossing segments. The four middle segments have distinguishable upper arrowheads; the densely bent far-left stroke does not give a certain direction. Separate arrowheads on the two right segments are undetermined. At right, an oblique stroke toward “graph of f”; exact attachments of dense strokes remain uncertain.

Original source details: GELFAND-P000185

A section of the bundle, parallel to N.

This is also a vect. field (a vertical vect. field).

GELFAND-P000186

Every vertical field φ must be representable as a sum.

$$\varphi = f_*\xi + f^*\eta$$

(transfer)

$$\overset{\uparrow}{f_*}, \quad \overrightarrow{f^*}$$

[Cancelled: illegible] One can check that the maps written earlier are stable.



Uncertain reading. Before “One can check”, a short sign / contraction with a high upper loop is cancelled; the literal inscription is undetermined.

Original source details: GELFAND-P000186

Weierstrass prepar. thm.

(parametric reduction)

If Q is finite-dimensional $(dim\, Q = r)$ and has generators

$$e_1(x), \ldots, e_r(x)$$

(functions that become generators after quotienting)

then every germ $\varphi(x) \in E_x$ [cancelled: ?] has an expansion:



Uncertain reading. Beneath the raised insertion “has”, a joined word with an initial loop and lower teeth is cancelled. The literal reading is undetermined; then follows “an expansion:”.

Original source details: GELFAND-P000186

$$\varphi(x) = \psi_1(y)e_1(x) + \ldots + \psi_r(y)e_r(x)$$

$dim\, Q$: the correct def. of multiplicity.

Theorem (Mather)

Σ^{20} is divided into parts.

1°. Five series of rings Q

2°. Remainder $codim = \infty$

$f : M^m \longrightarrow N^n$

(need to def. a map of one of the series)

Singularities of the five series are stable:

$$n \geq m1. \quad \mathrm{I}_{a,b} \qquad R[x,y]/\{x,y,x^a+y^b\}\,[?] \qquad b \geq a \geq 2$$



Uncertain reading. In the first denominator, a separate low stroke between x and y resembles a comma: $\{x,y,x^a+y^b\}$ / $\{xy,x^a+y^b\}$. A separate low stroke is visible; the first and second exponents are a,b.

Original source details: GELFAND-P000186

$$n \geq m2. \quad \mathrm{II}_{a,b} \qquad /\{xy,x^a-y^b\} \qquad b \geq a \geq 2 \quad \text{even}$$

$$n > m3. \quad \mathrm{III}_{a,b} \qquad /\{x^a,y^b,xy\}$$

$$n > m4. \quad \mathrm{IV}_a \qquad /\{x^a,xy^{a-1},x^2+y^2\} \qquad a \geq 3$$

$$\mathrm{V}_a \qquad /\{x^a,x^2+y^2\} \qquad a \geq 3$$



Uncertain reading. The four left lines read $n \geq m1.$, $n \geq m2.$, $n > m3.$, $n > m4.$. No separate arithmetic sign is distinguishable between m and the digits; these may be row numbers / part of an abbreviated condition. No separate plus or minus is distinguishable.

Original source details: GELFAND-P000186

The codimensions have been calculated.

(for all series)

The symb. Σ^{20} is strat. into subvarieties

(This is the strongest res. on the classific. of singularities)

Next time $13/II$ — 1967.

GELFAND-P000187

Gelfand sem.

Plan.

1.	Kirillov Harish-Chandra	≈ 10 lectures.
2.	Anosov Maslov and semiclassics	2 lectures.
3.	Kazhdan A. Weil.	6–7 lectures.
4.	Dynkin Index.	3 lectures.
5.	Anosov Pfaff eqs. (1st order)	1 lecture.
6.	KG-functor (Bernstein)	2 lectures.

Next time Kirillov and Anosov.

Kirillov. Lecture 1.

A series of works by H.-Ch., leading to a descr. of all irred. unit. reps. of real semisimple Lie groups.

Today, the scheme of the proof of one theorem (on characters).

G: a real semisimple Lie group. (reductive—for ind.)

On it, consider diff. operators commuting with both left and right translations.

This is a polynomial ring in generators $D_1, \dots, D_\ell$: the rank of the group.

$$G = SL(n), \qquad \ell = n - 1,$$

one oper. of each degree, beginning with the second.

Gelfand: E_{ik}

$$x = (\dots), \qquad f(x(1 + te_{ik})) = \\ = f(x) + tE_{ik}f + \dots$$

In the full group, $\sum E_{ii}$ (it is triv. in SL)

$$\sum E_{ik}E_{ki}$$
$$\sum E_{ij}E_{jk}E_{ki}$$
$$\dots$$

The rest are expressed through the first n.

(see Gelfand, 1947)

K. Consider generalized functions on the group that are “sols. of all these eqs.”.

R: the ring of all polynomials in $D_1, \dots, D_\ell$.

J: [cancelled: illegible] an ideal such that $dim\,(R/J) < \infty$.



Uncertain reading. Before “ideal”, a short word is cancelled: a high initial loop and several crossed lower strokes. The readings “vse” / “vsyo” (“all”) are undetermined.

Original source details: GELFAND-P000187

GELFAND-P000188

[source number: 51]

Consider generalized functions T such that

$$T^x = T \quad \text{for } x \in G$$

(x: an inner autom.)—const. on classes of conj. elements.

$$\langle T^x, f\rangle = \langle T, f^{x^{-1}}\rangle, \qquad f^{x^{-1}}(y) = f(x^{-1}yx)$$

G.: $D_1, \dots, D_\ell$: Laplace operators on the group.
Let $D_iT = \lambda_i T$; then T is an eigenfunction. (generalized)
Among them, seek "spherically symm." (zonal) ones

$$T(y) = T(x^{-1}yx).$$

Then it is an actual function and, moreover, summable (locally)
[In the right margin: Schwarz[?]]

Original source details: GELFAND-P000188

Uncertain reading. An underlined surname in the margin: "Schwartz" / "Schwarz"; the middle joined letters are compressed, and long strokes cross and surround the inscription. Its exact spelling is undetermined.

One can consider generalized eigenfunctions:

$$(D - \lambda)^2 T = 0$$

(not R, but $JT = 0$).

$$r(D_1, \dots, D_\ell)T = 0, \qquad r \in J.$$

For a max ideal, these are simply eigenfunctions (λ_i)
It is not necessarily continuous!
K.

$$\begin{aligned} &1) \quad T^x = T \quad \text{for } x \in G \\ &2) \quad DT = 0 \quad \text{for } D \in J \end{aligned}$$

Then it is locally summable.

Abelian group ⇒ all diff. operators, even[?] analytic, since there is an elliptic eq.



Uncertain reading. The joined word before "analytic": "even" / "further" (source dazhe / dalee). The converging middle strokes admit both readings; the literal reading is unresolved.

Original source details: GELFAND-P000188

General idea: in a nbhd., functions actually depending on ℓ params., satisfying ℓ eqs., construct an elliptic eq., away from singular points.

Characters become 1 at ∞—may have discontinuities.

How is this proved?

The set of classes of conj. elements is arranged thus: open subsets that are subvarieties $GL(n)$: distinct eigenvalues.

Diagon. of codim. 2 or 3, in turn, has subsets, etc. (2 eigenvalues coincide, etc.)—

—stratification.

GELFAND-P000189

At a reg. point $y \in G$, this is an analytic function.

In a nbhd. of y, construct a new coord. system.



Original source details: GELFAND-P000189

Typeset diagram



classes of conj. elements

transv. section.

On $U \times V$, there is a generalized function independent of [cancelled: illegible] one coord.,



Uncertain reading. Between "of" and "one coord.", a small sign is heavily cancelled: V / $\forall$ / another sign. Its literal reading is undetermined; the word "one" follows the cancelled sign.

Original source details: GELFAND-P000189

reducing to a generalized function on the section. (see L. Schwarz)

$$D_1, \ldots, D_\ell$$

generate almost all diff. operators on the section

(already of finite codim. in the ring of all diff. operators)

$$\Delta = D_1^2 + D_2^2 + \ldots + D_\ell^2$$

is already elliptic on the section.

here

$$\Delta^n + c_1 \Delta^{n-1} + \ldots + c_n \in J$$

Thus, $\Delta T = 0$, Δ is elliptic.

The arbitrary case reduces to this by induction on the dim. of the group.

3 different cases.

x — 1) semisimple
2) nilpotent
3) identity.

1)—reduces to the centralizer of y: a reductive group, of smaller dim. if y is not central. (then the whole group)

2) nilpotent—a special device

3) $x = e$: ln, exp reduce to the study of the Lie algebra—

—2 separate works.

The idea for semisimple elements: passage to polar coords.

(radial part of the Laplace operator)

a: a semisimple element

G acts on [cancelled: ?] g—
—Lie alg.



Uncertain reading. After “on”, before the legible g, a symbol with loops and a long lower stroke is cancelled: g / another sign. The original inscription is undetermined.

Original source details: GELFAND-P000189

if Ad_a $(z \longrightarrow aza^{-1})$

is reduced to diagonal form, i.e. without Jordan blocks

(For $SL(n)$, the matrix itself has no Jordan blocks)

z: the centralizer of [cancelled: illegible] a in the algebra.



Uncertain reading. Before the separate legible a, a small symbol with several loops is heavily overwritten / cancelled. Its original reading is undetermined.

Original source details: GELFAND-P000189

reg. elem.

(for [cancelled: ?] —a Cartan subalgebra)



Uncertain reading. After “for”, beneath the boxed insertion “reg. elem.”, an inscription is cancelled: a / x_0 / another symbol. Several original strokes merge with cancellation lines; the reading is undetermined.

Original source details: GELFAND-P000189

GELFAND-P000190

[source number: 52]

Take a section (still redundant for now)

Berezin's thm. for reg. elements: restriction of operators to a Cartan subalgebra.

Ξ: the Lie group corresponding to $\mathfrak{z}$.

Construct a map

$$\begin{aligned} \varphi\colon G \times \Xi &\longrightarrow G \\ (x, y) &\longmapsto (ay)^x = xayx^{-1} \end{aligned}$$

Further notation:

$$V_a(y) = \det\bigl(Ad(ay)^{-1} - 1\bigr)_{\mathfrak{g}/\mathfrak{z}}$$

$$\Xi' = \{y \in \Xi : V_a(y) \neq 0\} \quad \text{— "reg. points" of } \Xi$$

($V_a \neq 0$, since the eigenvalue 1 is no longer present; it is on $\mathfrak{z}$)

Thm. 1 (Lemma 14)

$$\operatorname{rang} d\varphi = n = \dim G \qquad \text{on } G \times \Xi'$$

(locally this is the max of the rank: projection type)

Proof. X, Z: a pair of tangent vectors.

$$d\varphi(X, Z) = Z + \bigl(Ad(ay)^{-1} - 1\bigr)X,$$

from which everything follows.

Nondegenerate on the quotient.

Z provides full rank on the whole space.

Result from another work.

$$d\mu \quad M^m \xrightarrow{\pi} N^n \quad d\nu \quad \text{— measures}, \qquad m \geq n$$

$\operatorname{rg} d\pi = n$.

One can transfer generalized functions from M to N (

Можно с M на N переносить обобщ. ф-и (Γ: локально)

Uncertain reading. Γ?



Original source details: GELFAND-P000190

: locally)

$$\alpha \in C_0^\infty(M) \quad \longrightarrow \quad f_\alpha \in C_0^\infty(N),$$

so that $\forall F$ on N there will be

$$\int_M \alpha \cdot F \circ \pi \, d\mu = \int_N F f_\alpha \, d\nu$$

(For [cancelled:

(для ∫ Nx ... это интегр. по линиям перем.)

Uncertain reading. $M\times$?

Original source details: GELFAND-P000190

] $N \times \ldots$, this is integration over the extra variables.)

This is done linearly, a partition of unity; locally this is a direct product.

GELFAND-P000191

Perspective: apply to φ.

Useful notation. (for illegibility)

On $M \times N$, there is a function (smooth)

D_1, D_2 —diff. operators on M, N.

$$f(x; D_1 : y; D_2) = (D_{1x} \times D_{2y} f)(x, y)$$

(apply D_1 in x and D_2 in y)

The identity operator is omitted.

$$f(x : y; D_2) \quad —$$

—explained in only one work.

Another notation.

$$G, \quad f(x) \text{ on } G, \qquad f(x : y) = f(xyx^{-1})$$

Next time, generalize Berezin's theorem.

For identity operators D_1 and D_2:

$$f(x : y)$$

and everything applies to it.

Dynin.

X —a smooth compact manifold

E_1, E_2 —bundles on X

$$A\colon \Gamma(E_1) \longrightarrow \Gamma(E_2) \quad \text{— lin. diff. operator}$$

Pseudodiff. operators.

$\{U_i\}$ $\quad \varphi_i$ — subord. partition of 1

$$\psi_i \varphi_i = \varphi_i$$

1) $\psi_i A(\varphi_i \cdot)$ — an ordinary pseudodiff. operator in the space of vector-valued functions

2) $\varphi\psi = 0 \;\Rightarrow\; \psi A(\varphi \cdot)$ a smoothing operator.

GELFAND-P000192

[source number: 53]

Example:

$$d\colon \Gamma(\Lambda T(x)) \longrightarrow \Gamma(\Lambda T(X))$$



Uncertain reading. The case x/X in both arguments of T is not fully distinguishable; lower-case x at left and capital X at right are typographic candidates.

Original source details: GELFAND-P000192

all forms (inhomog.)

$$\Lambda T(X) = \bigoplus_k \Lambda^k T(x)$$



Uncertain reading. In both T arguments, crossed x/X signs of varying size; their case is undetermined. Candidates: X at left and x at right.

Original source details: GELFAND-P000192

δ: —the adjoint operator (in the Riem. metric)

$$\delta = d^*.$$

$d + \delta$—the Cauchy-Riemann operator

$\Delta = (d + \delta)^2$ —the Laplace operator.

$$\Delta\colon \Gamma(\Lambda^k T(X)) \longrightarrow \Gamma(\Lambda^k T(X)).$$



Uncertain reading. The undetermined case x/X affects both T arguments on this line; capital X signs are candidates, not established readings.

Original source details: GELFAND-P000192

Hodge's theorem:

$$\ker \Delta\big|_{\Gamma(\Lambda^k T(X))} = H^k(X, C)$$



Uncertain reading. In the argument of T beneath the restriction sign, a small crossed x/X sign; its case is undetermined. Candidate: X.

Original source details: GELFAND-P000192

(a very simple fact, see Moren, connection with the heat eq.)

Next time.

6–7 —Kirillov
7–8 —Anosov.

GELFAND-P000193

Gelfand sem. $20/\overline{\text{II}}$.
Kirillov. Lecture 2.

The case where the fibre has positive dimension. (xyx^{-1})—
—y is not central.
Let a be a semisimple element.
Take a section intersecting each class of conj. elements in 1 element.

$$\mathfrak{g} \text{ — Lie alg.}, \qquad \mathfrak{z} = \{X : \operatorname{ad}_a X = X\}, \qquad \underset{\text{subgroup corresp. to } \mathfrak{z}.}{\Xi} \subset G.$$

The section is the conn. component of the centralizer of a.
Everything reduces to the group Ξ.
We shall construct a new generalized function and diff. operator.
How does one specify diff. operators on a Lie group?
Consider left-invariant diff. operators ($\exists$ a left-invariant one at $\forall$ point, agreeing with ours up to lower-order terms).

D_y: the left-invariant operator agreeing with D at y.

$D_y \in \mathfrak{g}$ describes the whole operator (on the whole group at once).

We shall restrict a diff. operator to a subset.



Typeset diagram



Original source details: GELFAND-P000193

We shall regard diff. operators along the fibres as zero.

Fibres close to a may have greater dimension.

$$f(x; D_1 : y; D_2) = \underline{f(x : y; \Gamma_y(D_1 \otimes D_2))}$$

(D_1 in x, D_2 in y)

[def.?] Γ_y [?]



Uncertain reading. Inside the enclosure, candidate “def. Γ_y”; some strokes of the word and the final punctuation (; / ! / :) are undetermined.

Original source details: GELFAND-P000193

The explicit form of replacing operators in both variables by an operator in y.

$$\frac{\partial^2 f}{\partial x \partial y} = f(x; [d \,/\, \partial\, ?] : y; d)$$



Uncertain reading. The first operator after x; is heavily overwritten: d / ∂. The square brackets give candidates; the following separator is a colon, and the second operator d is legible.

Original source details: GELFAND-P000193

Γ_y depends bilinearly on D_1, D_2, or—linearly on $D_1 \otimes D_2$.

GELFAND-P000194

[source number: 57]

Explicit expression for Γ_y. (g_1, g_2: elements of the enveloping algebra.

$$f(x; g_1 : y; g_2) = f(x : y; \Gamma_y(g_1 \otimes g_2)).$$
$$\Gamma_y(g_1 \otimes g_2) = \sigma_y(g_1) \cdot g_2,$$

where $\sigma_y(g_1)$ is a representation of the enveloping algebra, i.e.

$$\sigma_y(gh) = \\ = \sigma_y(g)\sigma_y(h).$$

Now it suffices to calculate σ_y on the generators of the enveloping algebra.

$$\sigma_y(X) = L_{X^{y^{-1}}} - R_X \qquad (X \text{ from the Lie algebra}).$$

$$\sigma_y(X) : g \longrightarrow X^{y^{-1}} g - gX$$

Derivation.

[Cancelled: (le...?]

Uncertain reading. A short beginning, "(ст..." ("(le..."), beneath two cancelling lines; the further reading is undetermined.

Original source details: GELFAND-P000194

(leading term)—on a basis:

$$\Gamma_y(X_1 \cdots X_r \otimes Y_1 \cdots Y_s) = X_1' \cdots X_r' Y_1^{[*\,?]} \cdots Y_s;$$



Uncertain reading. Above Y_1, a sign with several rays: an asterisk or a cancelled prime. The brackets and question mark qualify the candidate.

Original source details: GELFAND-P000194

$$X_i' = (\operatorname{ad} y^{-1} - 1) \cdot X_i$$

[Cancelled: $f(x; g_1$?]

Uncertain reading. Candidates for the unfinished fragment: $f(x; g_1$ / $f(x, g_1$. The sign after $f($ and the separator are crossed out; no closing parenthesis is supplied.

Original source details: GELFAND-P000194

G.

$$X_1X_2\cdots X_rY_1\cdots Y_r\, f(xyx^{-1})$$

The operators must be transferred to y; Y_i remains, while
[cancelled: if?]

Uncertain reading. One heavily crossed-out word before the next line; candidate “if” is undetermined.

Original source details: GELFAND-P000194

if X commutes with y, nothing changes.
(It is easy to check all [inserted: this])

— · —

K.



Original source details: GELFAND-P000194

Typeset diagram

$$\begin{array}{lccccc} \Gamma_y: & & \mathfrak{g}\otimes\mathfrak{g} & \longrightarrow & \mathfrak{g} & (\mathfrak{g}\text{—enveloping algebra}) \\ & & \cup \quad \cup & & & \\ 0 & \longrightarrow & \underline{\underline{\mathfrak{q}}}\otimes\underline{\underline{\mathfrak{z}}} & \xrightarrow{\Gamma_y} & \mathfrak{g}\longrightarrow 0 & \text{isomorphism!} \end{array}$$

$\mathfrak{g} = \mathfrak{z} + \mathfrak{q}$,
[cancelled: where? / sub.?]

Uncertain reading. A short crossed-out word after the equality: “where” / “sub.”; middle and final strokes merge with the cancelling line.

Original source details: GELFAND-P000194

$\mathfrak{q}$: a complementary subspace, invariant under $\mathrm{Ad}\,\mathfrak{z}$: $[\mathfrak{z},\mathfrak{q}]\subset\mathfrak{q}$.

$\underline{\underline{\mathfrak{z}}}$, $\underline{\underline{\mathfrak{q}}}$ are now generated by them in the enveloping algebra.

Choose y regular (i.e. $[\nu/v/V]_a(y)\neq 0$). Then the map



Uncertain reading. The first sign in the condition: ν / v / V. Subscript a, argument y and $\neq 0$ are legible; the case and alphabet of the first sign are undetermined.

Original source details: GELFAND-P000194

Γ_y, by the formula, is nondegenerate and unique in its leading term,

GELFAND-P000195

D: an operator on the group,

$$D \longrightarrow \underbrace{\delta_{a,\, G[|\,;\,/]\Xi}(D)}_{\Delta}$$

—an operator on $a\Xi$— —a submanifold.



Uncertain reading. Between G and Ξ in the subscript of δ, a nearly vertical stroke: | or /. The square brackets and semicolon in the typesetting separate candidates for one sign.

Original source details: GELFAND-P000195

The correspondence is constructed so that for functions constant on the orbits it is all the same.
[Cancelled formula: at the beginning, φ?; at the end, (D)?]



Uncertain reading. Possible separate remnants of the cancelled formula: φ at the beginning and (D) at the end. The complete formula is undetermined.

Original source details: GELFAND-P000195

Undeciphered passage. The middle and remaining undetermined part of the cancelled formula are illegible.

Original source details: GELFAND-P000195

$$\Delta_{ay} = \alpha(D_{ay})$$
$$D - \alpha(D) \in \Gamma_y(\mathfrak{q}^+ \otimes \mathfrak{z})$$

($\alpha(D)$: the constant term of D. $\mathfrak{q}^+$: elements having no constant term).
Next time, the transfer of generalized functions again.

$\smile$

27/II Gelfand Seminar.
Kirillov, Lecture 3.
Transfer of generalized functions.

Consider an auxiliary map:

$$\varphi : G \times \Xi' \longrightarrow G$$
$$(x, y) \longrightarrow xayx^{-1}$$

(Ξ': the regular elements of Ξ, $[\nu/v/V]_a(y) \neq 0$)



Uncertain reading. The V-shaped sign in the regularity condition: ν, v or V. Subscript a, argument y and condition $\neq 0$ are legible.

Original source details: GELFAND-P000195

$$\operatorname{rank} \varphi = \dim G.$$

Now generalized functions are transferred from G to Ξ. First they are transferred to $G \times \Xi'$.

T: generalized functions on G. We must learn to transfer ordinary functions in the forward direction. Roughly speaking, this is integration (locally).

GELFAND-P000196

[source number: 58]

$$M \longrightarrow N, \qquad C_c^\infty(M) \longrightarrow C_c^\infty(M)$$

Volumes dx and dy are given on M and N. (differential forms)

$$\alpha(x) \longrightarrow f_\alpha(y)$$

The condition must be satisfied: $\forall F(y)$

$$\int_M \alpha(x) F(\varphi(x))\, dx = \int_N F(y) f_\alpha(y)\, dy$$

Theorem: such a map exists and is continuous in the topology of these spaces.

Example.

$$\begin{matrix} M & = & N & \times & P \\ & & dy & & dz \end{matrix} \qquad (dx = dy\, dz).$$

Then the map is integration with respect to z.

— · —

[Cancelled: M? / $\forall M$?]

Uncertain reading. Angular strokes before $G \times \Xi'$: M or $\forall M$; the cancelling lines cannot confidently be separated from the original signs.

Original source details: GELFAND-P000196



Original source details: GELFAND-P000196

Typeset diagram

$$G \times \Xi' \xrightarrow{\varphi} G$$

$$\underbrace{T'} \longleftarrow T \quad \text{—generalized functions on } G$$

generalized functions

T' is invariant under translations in its first factor

$$\langle T', f(x,y)\rangle = \langle T', f(x'x,y)\rangle$$

Lemma. A generalized function invariant under translations is $\int$ with respect to Haar measure (const)

$$— \cdot —$$

T' depends only on the second argument (integrate over the first).

$$T' = 1 \otimes \sigma_T$$

An explicit formula expressing σ_T through T can be given (K.)



Original source details: GELFAND-P000196

Typeset diagram

$$\langle \sigma_T, \beta \rangle = \left\langle T, \int_G \gamma(z)\beta(a^{-1}z^{-1}xz)\,dz \right\rangle,$$

β: a function on Ξ

where $\gamma(z)$ is any function satisfying the condition

$$\int_G \gamma(z)\,dz = 1$$

It has no meaning.

Diagram and typed description. A sloping dashed line runs through the formula region toward “It has no meaning.” Its purpose—cancellation or connection with the note—is undetermined.



Original source details: GELFAND-P000196

GELFAND-P000197

Thus, we have:

$$D \longrightarrow \Delta \qquad = \delta_{a,G/\Xi}(D)$$
$$T \longrightarrow \sigma_T^{[/?]}$$

Original source details: GELFAND-P000197

Uncertain reading. A thin interrupted stroke at the upper right of σ: possibly σ'_T, or a separate nonmathematical stroke beside σ_T. The possible prime is qualified by brackets and a question mark.

$a \in U_G \subset G \qquad \Xi \supset U_\Xi \ni 1$

[Between them, cancelled: Ξ?]



Original source details: GELFAND-P000197

Uncertain reading. One cancelled sign with three horizontal levels; candidate Ξ is undetermined.

Lemma.

$$\sigma_{DT} = \Delta\sigma_T$$

(Essential use of $\Gamma_{ay} : \mathfrak{g} \times \mathfrak{g} \longrightarrow \mathfrak{g}$.)

Facts.

1) The operators Δ generate an ideal of finite codimension in the center of the group Ξ.

(On the Cartan subalgebra, these are operators symmetric under the Weyl group)



Typeset diagram

$$\begin{array}{ccc} G & & \Xi \\ & \overset{\alpha}{\longrightarrow} & \\ \mathfrak{g} & & \mathfrak{z} \\ & & \\ Z(\mathfrak{g}) & \longrightarrow & Z(\mathfrak{z}) \end{array}$$

Original source details: GELFAND-P000197

$Z(\mathfrak{g})$ is the center of the enveloping algebra; the image of $Z(\mathfrak{g})$ lies in the center $Z(\mathfrak{z})$ (can be checked). and the ideal it generates is of finite codimension.



Typeset diagram

$$\begin{array}{ccc} \cup & & \cup \\ & & \\ I & \longrightarrow & J \end{array}$$

Original source details: GELFAND-P000197

Then a complete reduction to Ξ is obtained

$$\sigma_T \text{ is locally integrable} \quad \Longrightarrow \quad T \text{ is locally integrable too}$$

a in the center $\Longrightarrow$ reduce by translation

Original source details: GELFAND-P000197

Undeciphered passage. The cancelled text after “reduce by translation” is completely covered by strokes and has not been read.

to the case $a = e$,

there is a special technique (3 papers

Original source details: GELFAND-P000197

Undeciphered passage. The cancelled text between “3 papers” and the name is completely covered by strokes and has not been read.

by Harish-Chandra)

GELFAND-P000198

[source number: 59]

6/III. Vishik Seminar. 1. Continuation of Agranovich's report. 2. Continuation of G. I. Eskin's report.

Gelfand Seminar.

Kirillov
$x^2 + y^2 - z^2 = c$, T is invariant under
[Cancelled: this gr...? / this f...?]

Original source details: GELFAND-P000198

Uncertain reading. A cancelled word and the beginning of the next: "this gr..." / "this f..."; the continuation is undetermined.

the group preserving this function.

$$P\left(\frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2} - \frac{\partial^2}{\partial z^2}\right) T = 0,$$

will T be locally integrable?

Original source details: GELFAND-P000198

Undeciphered passage. One cancelled word before the following parenthesis is illegible; a period remains at the right.

(T: the closure of local functions constant on the layers)



Original source details: GELFAND-P000198

Typeset diagram



Original source details: GELFAND-P000198

Uncertain reading. The large upper oval, smaller upper loop, lower oval, crossing diagonals, concave side curves and internal arcs. The purpose of the internal A-/U-shaped strokes and dark lower endpoints is undetermined; no letter labels are assigned to them.

Outside the cone, the system is elliptic.

Arnold.

C. J. Earle, J. Eells.

X^2: a two-dimensional compact manifold (oriented)

$\mathrm{Diff}_0(X)$: the group of its diffeomorphisms homotopic to the identity.

Its topology has been calculated!

$$\mathrm{Diff}_0 X = \begin{cases} X = S^2\ [:\ ?] & \underset{\text{conformal maps}}{G} \times \underset{\text{contractible}}{\mathrm{Diff}(S^2 - a, b, c)} \quad (a, b, c \text{ fixed}) \\ X = T^2 & T^2 \times \underset{\text{contractible}}{\mathrm{Diff}(T^2 - a)} \\ \text{genus} \geq 2 & D \sim 0 \quad \text{contractible} \end{cases}$$

Original source details: GELFAND-P000198

Uncertain reading. After $X = S^2$, two dots at right and a separate sloping stroke at left. A colon with an additional stroke / a three-dot sign; the typeset colon is qualified by brackets and a question mark.

The proof is based on work by [Alfers / Alfors] and Bers on quasiconformal maps, to which any diffeomorphism contracts.

Original source details: GELFAND-P000198

Uncertain reading. The vowel after “ф” in the surname: “Альферса” / “Альфорса”, rendered as Alfers / Alfors.

Diff is a Lie group in the new understanding of smooth structure.

GELFAND-P000199

Anosov. Statement of the problem.

$Lu = f$, $u(x) \in H$, H is Hilbert.

In H there is an operator A; 0 is not an eigenvalue; A is self-adjoint.

L may depend on A as well.



Original source details: GELFAND-P000199

Typeset diagram

$$-\frac{h^2}{2}\frac{d^2}{dx^2}+U(x)$$



Fourier transform with coefficient h

$$\frac{p^2}{2}+U\left(\frac{h}{i}\frac{d}{dp}\right)$$

(pseudodifferential operator)— $\overline{\mathcal{F}}_{p\to x}\,\sigma(x,p)\,\mathcal{F}_{x\to p}\,f(x)$

$$e^{\pm i\frac{1}{h}(p,x)}=$$

(h for dimensionlessness).

According to Maslov, $\frac{1}{h}$ is an operator; since everything is a function of h

$$=e^{\pm iA(p,x)}$$

A-Fourier transform:



Original source details: GELFAND-P000199

Typeset diagram

$$\phi^{A}_{x\to p} f(x) = \left(\int e^{iA(x,p)} f(x)\, dx \right).$$

$$\frac{|A|^{n/2}}{(\sqrt{2\pi})^n}$$



Uncertain reading. The oval sign with a vertical stroke in this formula and the two final transforms: ϕ / Φ. Typeset using candidate ϕ; the case is undetermined.

Original source details: GELFAND-P000199

Consider

$$\mathcal{L}(x, \hat{p}, A^{-1}) f(x) = \overline{\phi^{A}}_{p\to x}\, L(x, p, A^{-1})\, \phi^{A}_{x\to p}\, f(x)$$

GELFAND-P000200

[source number: 60]

13/III Gelfand Seminar.
Parshin on Mumford.

Uncertain reading. A separate blackened mark to the right of the heading. Its sign and purpose are undetermined.

Original source details: GELFAND-P000200

G is an algebraic group, X is a variety, G acts regularly on X,
if

$$G \times X \longrightarrow X$$



Original source details: GELFAND-P000200

Typeset diagram

$$\begin{array}{ccc} G \times G \times X & \xrightarrow{\sigma \times 1} & G \times X \\ \downarrow{\scriptstyle \mu \times [1?]_X} & & \downarrow{\scriptstyle \sigma} \\ G \times X & \xrightarrow{\sigma} & X \end{array}$$

[cancelled: ?]



Uncertain reading. The left label: $\mu \times [1?]_X$; the overwritten middle sign is undetermined. Candidate 1 is qualified by a question mark. The top label reads $\sigma \times 1$; the lower X is overwritten.

Original source details: GELFAND-P000200

Original source details: GELFAND-P000200

Undeciphered passage. The completely cancelled former entry before the lower-left $G \times X$ is illegible.

Equivalent points—obtained by the action of G—an orbit.

The set of orbits—? When is it an algebraic variety, and in what sense?

$$\underset{\text{orbits}}{X/G} \longleftarrow X$$

Property of regular maps of algebraic varieties.

Original source details: GELFAND-P000200

Typeset diagram



Original source details: GELFAND-P000200

Uncertain reading. Intersecting horizontal and vertical lines and two curved branches in each sector. There are no labels. Some ends are thickened and hooked; the presence and directions of possible arrows are undetermined.

A structure cannot be introduced; this is possible only after removing a point.

The dim of the stabilizer can only be larger (in comparison with the generic stabilizer).

Theorem. If X/G has an algebraic structure



Original source details: GELFAND-P000200

Typeset diagram

$X \to X/G$

and $[\sigma?/\pi?]$ — regular.



Original source details: GELFAND-P000200

Uncertain reading. The insertion above the line, “and [overwritten sign]—regular,” is connected by an enclosure to $X \to X/G$. The loop-shaped sign: σ / π; the original reading beneath the heavy strokes is undetermined.

then all orbits must have the same dim. (in partic., be closed).

Reductive group (k of char. 0)

The quotient exists $\Longleftrightarrow$ all orbits are closed.

GELFAND-P000201

Dynin, Lecture 2.

$\Sigma(\mathbb{R}^n)$ from maps

$$\sigma\colon \mathbb{R}^n \times S^{n-1} \longrightarrow GL = \varinjlim GL(m,\mathbb{C})$$

with compact support

Outside $K_\sigma \times S^{n-1}$, $\sigma = 1$.

Theorem. ∃ one and only one map

$$\Sigma(\mathbb{R}^n) \xrightarrow{\text{ind}} \mathbb{Z},$$

with the following properties:

(Ī) Homot. stability.

(II̅)

$$\text{ind}(\sigma_0 \oplus \sigma_1) = \text{ind}\,\sigma_0 + \text{ind}\,\sigma_1$$

$\Sigma(x)$ from maps

Original source details: GELFAND-P000201

Uncertain reading. The argument after Σ is a crossed x/X sign; its case is undetermined. Candidate in the line: x.

$$\sigma\colon T_0(X) \longrightarrow GL = \varinjlim GL(m, \mathbb{C}),$$

such that outside $K_\sigma \subset X$ we have $\sigma = 1$.

In the class of X whose tangent bundle is stably trivial, there exists one and only one function ind with properties Ī, II̅ and

(III̅)

$$\Sigma(X) \times \Sigma(Y) \xrightarrow{\#} \Sigma(X \times Y)$$

$$\text{ind}(\sigma_x \# \sigma_y) = \text{ind}\,\sigma_x \cdot \text{ind}\,\sigma_y.$$



Original source details: GELFAND-P000201

Uncertain reading. The four σ subscripts contain crossed x/X and forked y/Y signs; their case cannot be established from the strokes. Candidates in the line: x, y.

(IV̅) Invariant with respect to [excision / cutting off / trimming].



Original source details: GELFAND-P000201

Uncertain reading. The beginning is faint; the ending “резания” is legible. Candidates: “вырезания” / “отрезания” / “обрезания” (excision / cutting off / trimming).

$$\text{supp}\,\sigma \subset U \subset X \Longrightarrow \text{ind}(\sigma|U) = \text{ind}\,\sigma$$

(V)



Typeset diagram



$\Longrightarrow \quad \operatorname{ind}\sigma = 0$

Original source details: GELFAND-P000201

Uncertain reading. The left sloping arrow label has a loop and a descending stroke: p / ρ. The candidate in the line is qualified by brackets and a question mark.

Original source details: GELFAND-P000201

(VI) For $X = \mathbb{R}^1$ there is the Noether-Muskhelishvili formula

$$\operatorname{ind}(\sigma) = \frac{1}{2\pi} \Delta_{\mathbb{R}^1 \times S^0} \arg\det\sigma.$$

GELFAND-P000202

20/III Continuation of Parshin's report.
The case of project. varieties.
27/III.

$$A(\omega,\eta_n) = A_-(\omega,\eta_n)\ M_- \underbrace{\qquad}_{(\eta_n+i)^{n_j(\omega)}\delta_{ij}} M_+ \qquad A_+(\omega,\eta_n)$$

But $n_j(\omega)$ depend on ω.
And under this assumpt. a regularizer is constructed.

One-dimensional problem

$$\mathcal{A}(\omega,\eta_n)u_+(\eta_n)+G(\omega,\eta_n)\varrho=\ell f(\eta_n)+u_-(\eta_n)$$

$$(\varrho=\varrho_1,\dots,\varrho_M)$$



Uncertain reading. The repeated auxiliary-unknown glyph has a closed upper loop and a lower curl: ϱ / s. Candidate at every corresponding occurrence: ϱ.

Original source details: GELFAND-P000202

$$\big(B(\omega,\eta_n),u_+(\ )\big)_{\eta_n}+E(\ )\varrho=g\big|_\ell$$

Uncertain reading. The lower glyph at the vertical stroke after g has a small loop: ℓ / e. Candidate in the line: ℓ; the literal letter is undetermined.

Original source details: GELFAND-P000202

(restr. to the bndry)

$$\ell-M=m_+(\omega)-m_-(\omega)$$

$\mathcal{A}_\omega(u_+,\varrho)$ — one-dimensional problem

Uncertain reading. The initial glyph in the lower underlined line: $\mathcal{A}_\omega(u_+,\varrho)$ / $\alpha_\omega(u_+,\varrho)$. The first candidate is in the line; the entire line has a wavy underline.

Original source details: GELFAND-P000202

It is solvable (there is exist. and uniqueness)

$R_\omega(f,g)$ depends cont. on ω.

GELFAND-P000203

The same in the n-dimensional case: $A(\xi',\xi_n)$ also has a right and a left regularizer. (factor out $|\xi'|$).

A_+, A_- — homog. of degree 0,

ξ_-^α enters M_-.

A regul. $R^\omega(\ell f;g)$ is constructed, and then localization. (with respect to ω)

See the work of Simonenko [In the left margin: Supposedly]

Original source details: GELFAND-P000203

Uncertain reading. Immediately after the surname is a heavily inked vertical mark: ! / an overwritten illegible sign. A separate dot is indistinguishable.

(in abstr. form, a disc. of inverse operators of ellipt. oper., depending on a parameter) Eskin.

Original source details: GELFAND-P000203

Typeset diagram



$A(x,\xi)$ — an ellipt. symbol.

A condition on the variation of $A(x,\xi)$ along the boundary.

Original source details: GELFAND-P000203

Typeset diagram



Original source details: GELFAND-P000203

Uncertain reading. Two irregular oval outlines with transverse hatching; the thin interior contour is visible with breaks. Its closure is undetermined. There are no labels or definite arrows inside.

$\Gamma_\varepsilon = \Gamma \times [0,\varepsilon)$, coord. (x', ξ', x_n, ξ_n)

$$A(x,\xi)$$

$$a_+(x') = A(x', 0, 0, 1)$$

$$a_-(x') = A(x', 0, 0, -1)$$

$b(x') = a_+(x')^{-1} a_-(x')$ — measure of nonellipt.

$$\gamma(x') = \frac{1}{2\pi i} \cdot \ln b(x')$$

Typeset diagram

Original source details: GELFAND-P000203



Original source details: GELFAND-P000203

Uncertain reading. To the left of a), b) are two nearly parallel long lines with lower arrowheads. The upper left branch and right side tick are visible; whether the left branch is an upper arrowhead is undetermined.

a) Req. that the branches of ln can be chosen so that [crossed out: на / их / illegible] $\gamma_j(x')$ — are cont. on all [Γ ?]

Original source details: GELFAND-P000203

Uncertain reading. After “чтобы” (so that), approximately two letters lie beneath two thick strokes: “на” (on) / “их” (their) / illegible. The writing is crossed out.

Original source details: GELFAND-P000203

Uncertain reading. The last heavily overwritten sign in a): Γ / an overwritten illegible sign. Candidate Γ in the line is qualified by a question mark.

(locally this is always poss.)

b) $|\operatorname{Re}\gamma_i(x') - \operatorname{Re}\gamma_j(x')| < 1$ on Γ

This is the class $\widehat{\mathcal{E}}_\alpha$.

Original source details: GELFAND-P000203

Uncertain reading. The main letter beneath the hat: $\widehat{\mathcal{E}}_\alpha$ / $\widehat{\varepsilon}_\alpha$. Subscript α and upper hat are visible; the first candidate is in the line.

(For fixed x' one can — argum. into one interv. $[1/\lambda/\uparrow ?]$ — they must not spread apart)

Original source details: GELFAND-P000203

Uncertain reading. The sign after "интерв." (interv.): 1 / λ / an upward arrow. Its shape does not establish an interval length.

$$\mathcal{A} = \begin{pmatrix} a_1(x,\xi) & & 0 \\ & \ddots & \\ 0 & & a_p(x,\xi) \end{pmatrix}$$

GELFAND-P000204

[source number: 65]

a: factorize — $\kappa_j(x')$.

Original source details: GELFAND-P000204

Uncertain reading. The looped glyph with subscript j and argument (x'): $\kappa_j(x')$ / $\chi_j(x')$ / $x_j(x')$. The first candidate is in the line.

γ_j will be κ_j and this class is not obtained.

Original source details: GELFAND-P000204

Uncertain reading. The sign after "будут" (will be): κ_j / χ_j / x_j. Candidate in the line: κ_j.

$$b = e^{2\pi i \kappa_j(x')}, \qquad \gamma_j = \kappa_j$$



Original source details: GELFAND-P000204

Uncertain reading. Both right-hand looped glyphs: κ_j / χ_j / x_j. Candidate in the exponent and in the right-hand equality: κ_j.

This is for oper. in ordinary spaces.

Main question: when does there globally exist $[G \in E \,/\, G \notin E \,/\, G \,\&\, E \,/\, G$ and $E\,?]$ (and B)?

Uncertain reading. A heavily overwritten sign between G and E: $\in$ / $\notin$ / an ampersand / "and". All four readings remain open.

Original source details: GELFAND-P000204

27/III Atiyah's work as presented by S. Gelfand.
(following Petrovskii)
(Report No.319 in the Bourbaki sem.).
Consider a homog. hyperb. eqn with const. coefficients

$$Pu = \sum_{|\alpha|=m} a_\alpha D^\alpha u$$

in $\mathbb{R}^n$.
a_α — real.
[Crossed out at the left: R^n / Ha(On)]

Uncertain reading. An overwritten or crossed-out fragment: R^n / "Ha" (On). Neither reading is established.

Original source details: GELFAND-P000204

Hyperbolicity: (with respect to ξ_0):

$$\sum a_\alpha \xi^\alpha = a(\xi_0, \ldots, \xi_n)$$

$\forall$ nonzero tuple $(\xi_1, \ldots, \xi_n) \neq 0$

$$a(\xi_0, \ldots, \xi_n) = 0$$

has exactly m real distinct roots.
We seek the sol. of the problem

$$\begin{cases} Pu = \delta(x_0, \ldots, x_n), \\ \quad \text{with the addit. condition} \\ u = 0 \quad \text{for } x_0 < 0. \end{cases}$$

It is denoted E and is unique by the uniqueness thm for the sol. of the Cauchy problem.

It is known that it is arranged as follows:

$$\text{Cone} \qquad a(\xi_0, \ldots, \xi_n) = 0 \qquad A$$

Its dual cone B in the space $(x_0, \ldots, x_n)$.



Original source details: GELFAND-P000204

Undeciphered passage. An entire crossed-out entry is illegible. Possible candidate: “гиперпл.” (hyperpl.).

cone of hyperpl.,
tang. to A.

$$b(x_0, \ldots, x_n) = 0$$

One must take cone B, the solution is analyt. in $\forall$ connected comp. of the [complement (genitive) / complement (nominative)] of B.

Original source details: GELFAND-P000204

Uncertain reading. The ending of the last word before B: “дополнения” (complement, genitive) / “дополнение” (complement, nominative).

GELFAND-P000205

Domain $\overset{C}{/}$ — a lacuna if $E(x) \equiv 0$ on C.
(conn. comp.)

Original source details: GELFAND-P000205

Typeset diagram



Original source details: GELFAND-P000205

Uncertain reading. A downward-pointing cone, the upper oval, small looped contour, two short vertical strokes, and generators. The inner loop may be part of a section or a letter φ/ρ; its literal identity and the exact joins of the strokes are undetermined. No arrow directions are marked.

Stable lacuna — if it — is a lacuna for nearby eqns.
There is a nec. and suff. condition for the existence of a stable lacuna —
— certain cycles on alg. varieties are homologous to zero.
Eqn $a = 0$ — [м / и]

Uncertain reading. The short glyph after the dash: “м” (m) / “и” (and).

Original source details: GELFAND-P000205

$$(\xi_0, \ldots, \xi_n) \subset \mathbb{C}P^n$$

Uncertain reading. The rounded sign open to the right: $\subset$ / $\in$. No middle stroke is distinguishable; candidate in the line: $\subset$.

Original source details: GELFAND-P000205

$a(\xi) = 0$ — defines the variety A (complex)

It is assumed that already in $\mathbb{C}P^n$ it is nonsingular (there are no complex singular points).
This can always be achieved by a real change of coeff. (small).

$$A_{\mathbb{R}} = A \cap \mathbb{R}P(n)$$

Let there be a point $\begin{matrix} x \\ \| \\ (x_0, \ldots, x_n) \end{matrix}$. We shall construct 2 cycles from it

1.

$$x_0\xi_0 + x_1\xi_1 + \ldots + x_n\xi_n = 0 \quad \text{— a plane (complex)}$$



Original source details: GELFAND-P000205

Typeset diagram

$$\begin{matrix} A_x & = A \cap \{(x, \xi) = 0\} \\ | & \\ \text{also has} & \\ \text{a real part} & \end{matrix}$$

$$(A_x)_{\mathbb{R}} = A_x \cap \mathbb{R}P(n); \qquad \text{its dim} = n - 2$$

This is a chain in homology (a cycle) — a sum of spheres:

$$\beta_x \in H_{n-2}(A_x)$$

For the wave eqn.

$$\frac{\partial^2}{\partial x_0^2} - \Delta u$$

$$x = (1, 0, \ldots, 0).$$

$$A = \{\xi_0^2 - \xi_1^2 - \ldots - \xi_n^2 = 0.\}$$

$$A_x : \quad \xi_0 = 0. \Rightarrow A_x = \{\xi_1^2 + \ldots + \xi_n^2 = 0\} \quad —$$

— in project. space this will be 0 (no points)

GELFAND-P000206

[source number: 66]

2. Another cycle.

Consider the map

$$\xi \mapsto \text{sign}(x, \xi),$$
$$\xi \in A_R,$$

Original source details: GELFAND-P000206

Typeset diagram

~~$\alpha =$ a cycle.~~

Original source details: GELFAND-P000206

Typeset diagram

~~$\partial\alpha \in (A_R)_x$~~

It gives a cycle.

> Split A_R by the plane
> (x, ξ) into 2 parts
> and one with $+$, the other
> with $-$.

$$\{(x, \xi) > 0\} - \{(x, \xi) < 0\}$$
$$(a \in C_{n-1}(A))$$

We obtain an $(n-1)$-dim. chain on $A \quad (C_{n-1}(A))$

$$\partial a \in (A_x)_R \quad \text{— a cycle}$$

Thus an elem. $\alpha_x \in H_{n-1}(A, Ax)$ is defined, and

Original source details: GELFAND-P000206

Uncertain reading. The second group argument looks like Ax on a common baseline; candidate A_x is also possible. In the line: $H_{n-1}(A, Ax)$.

from the exact homology seq.:

$\partial\alpha_x \in H_{n-2}(A_x)$

[Crossed out: and / H / another sign],

Uncertain reading. The densely crossed-out sign between the group and comma: “и” (and) / H / another sign.

Original source details: GELFAND-P000206

$\partial\alpha_x = 2\beta_x$.

If x varies in a connected comp. of the cone’s complement, then α_x, β_x do not change.

Uncertain reading. The crossed-out parenthesis: “(in $H_{n-\ldots}$)” / “(in H_n)”; the exact index beneath the dense strokes is undetermined.

Original source details: GELFAND-P000206

α_c, β_c — the corresp. cycles. (homology elem.).

$$\alpha_c \in H_{n-1}(A, A_c), \qquad \beta_c \in H_{n-2}(A_c)$$

Theorem. m — order of the eqn, $n+1$ — dim. of the space, m, $n+1$ are even.

a) $m \geq n+1 \Rightarrow \alpha_c = 0$ — a nec. and suff. condition for c to be a stable lacuna

b) $m < n+1 \Rightarrow \beta_c = 0$ — ——— // ——————————— // ———

——— // ———————————————

Proof: the explicit form of E.

On $CP(n)$ consider a form of type $(n,0)$ (holomorphic) with a single pole of order $(n+1)$ (it is unique)



Typeset diagram

$\Omega \quad \cong O(-n-1)$

|

holom. forms

Original source details: GELFAND-P000206

There are no global reg. sections. (hence uniqueness)

$$\omega = x_0\, dx_1 \wedge \ldots \wedge dx_n - x_1\, dx_0 \wedge dx_2 \wedge \ldots$$

— (in affine space) — area of the sphere.

GELFAND-P000207

Use the residue form ω_a on the surface $a = 0$.

$$\frac{\omega}{a} = \frac{da}{a} \wedge \omega_a + \Theta$$

Uncertain reading. The last sign and its repetition in the parenthesis have an oval with a horizontal bar: Θ / θ. Case is undetermined; candidate in the line: Θ.

Original source details: GELFAND-P000207

($\Theta = 0$ on $[a = 0 / a = \varphi ?]$)

Uncertain reading. The last heavily overwritten sign in the underlined parenthesis: $a = 0$ / $a = \varphi$. Both readings remain open.

Original source details: GELFAND-P000207

$m \geq n + 1$ — the Herglotz—Petrovskii formula

$$E(x) = c \int_{A_R} \operatorname{sgn}(x, \xi)(x, \xi)^{m-n-1} \omega_a$$

(see the 1st issue)

gen. func.

Chapter 3

GELFAND-P000208

[source number: 1]

1

Year 1967. Gelfand Seminar.

18/IX. Kirillov.

Formula (without proof or contradictory examples) for characters of irreduc. repres. of Lie groups.

$$\chi(x) = p(x)^{-1/2} \int_{\Omega} e^{i\langle F,x\rangle}\beta \qquad (\beta = \beta(F))$$

$x \in \mathfrak{g}$, $F \in \mathfrak{g}^*$, Ω — an orbit in $\mathfrak{g}^*$ under G,

β — a differ. form, $p(x)$ — the density of Haar measure.

(Not all orbits, but certain ones satisfying integrality cond., precisely [formulated: ending -емый / -емым?]}.



Uncertain reading. The final word ending is merged: “формулируемый” / “формулируемым” (formulated/formulable, with different endings). The closing sign has bends like a curly delimiter; candidate in the line: }.

Original source details: GELFAND-P000208

(G — a group, T — a unitary repres., $\chi(g) = \operatorname{tr} T(g)$ (in finite dim.)

In the general case χ — a gen. function

$$\langle \chi, \varphi\rangle = \int_G \varphi(g)T(g)\,dg \quad \text{— already has a trace.}$$

(Such a def. of the char.).)



Diagram and typed description.

G acts in $\underset{\text{Ad}}{\mathfrak{g}}$ and in $\mathfrak{g}^*$; there is a system of orbits there.

Original source details: GELFAND-P000208

All this is in a small nbhd of e — where there is exp.

β is constructed from the struct. const. of the algebra.

[Crossed out: illegible.]

Original source details: GELFAND-P000208

Undeciphered passage. One word beneath dense repeated loops. Undetermined candidates: “Предложения” (Proposals) / “Продолжение” (Continuation). The letters beneath the strokes are illegible.

Planned.

1. Expository talks on logic. (including the solution of the continuum hypothesis)
2. Lidskii “Asymptotics of eigenv. of self-adj. oper.”
3. Work of Kirillov; Kazhdan; Graev.

Example. $G = SO(3)$, $\mathfrak{g} = \mathbb{R}^3$, $\mathfrak{g}^* = \mathbb{R}^3$,
the action — rotations.
Orbit — S^2.

$$p(x) = \frac{\sin \tau}{\tau}, \qquad \text{where } \tau = \|x\|.$$



Original source details: GELFAND-P000208

Uncertain reading. The repeated radial-variable glyph has an upper stroke and a hooked leg: τ / r. Candidate in the line: τ; the literal letter is undetermined. No square on the ratio is distinguishable.

A fact from analysis (on the Fourier transform of δ on S_λ)

$$(\delta_{S_\lambda})^\vee \equiv \frac{\sin \lambda\tau}{\tau}$$



Original source details: GELFAND-P000208

Uncertain reading. Above the closing parenthesis is a short two-stroke mark: $\sim$ / $\vee$. The densely inked sign between parenthesis and ratio: $\equiv$ / $=$. Candidates in the line: $\vee$, $\equiv$; neither reading is established. The radial variable is the same as in the preceding ratio: τ / r.

GELFAND-P000209

β — ordinary surface of the sphere.

Answer.

$$\chi(x) = \frac{\sin \lambda\tau}{\sin \tau}.$$



Original source details: GELFAND-P000209

Uncertain reading. The radial grapheme is the same as on the preceding page: τ / r. Candidate in the ratio: τ; the literal letter is undetermined.

All this for $\lambda = 2n + 1$ (countably many repres.)

$\beta(x)$ — $\int$ over cycles of the orbit of certain integral forms.

Work of Fuchs and Gelfand.

Fuchs. Study of principal bundles

[Crossed out: illegible.]

Original source details: GELFAND-P000209

Undeciphered passage. A short, densely crossed-out entry between “bundles” and “with fiber”. The letters are undetermined.

with fiber G (top. group)

Types of invar. — as top. spaces and classif. spaces.

$\mathfrak{g}$ — a group



Original source details: GELFAND-P000209

Uncertain reading. The looped group sign: lowercase fraktur-like $\mathfrak{g}$ / handwritten uppercase G. Candidate $\mathfrak{g}$ is repeated in subscripts, arrow labels, and under the hat; the upright G above has a different form. The letter case is undetermined.



Original source details: GELFAND-P000209

Diagram and typed description.

$E_{\mathfrak{g}}$
$\downarrow \mathfrak{g}$ — universal bundle
$B_{\mathfrak{g}}$

($E_{\mathfrak{g}}$ [Crossed out: illegible.]

Original source details: GELFAND-P000209

Undeciphered passage. One word beneath repeated dense strokes before “aspherical”. The letters are undetermined.

aspherical, i.e. $\pi_k(E_{\mathfrak{g}}) = 0$, $k > 0$).

A char. class is determ. by specifying $\alpha \in H^q(B_{\mathfrak{g}}; A)$

(Maps of principal bundles [перестан. / перестав. (commute?)] with the group action).

Original source details: GELFAND-P000209

Uncertain reading. The penultimate strokes before the period in the abbreviation “перестан.” / “перестав.” (commute?) are merged. Neither reading is established.

Analogously, instead of H^q — any contravar. functor h to the category of sets.

All char. classes — $h(B_{\mathfrak{g}})$

(this is if h — a homotopy functor)

$\hat{\mathfrak{g}}$ — a max. comp. subgroup

(all of them are homot. equiv. and their classif. spaces hom. equivalent.)
and equiv. to $\mathfrak{g}$.

G. Problem: find the actual classif. space of noncomp. groups, without identifying it with the max. comp. subgr.



Original source details: GELFAND-P000209

Typeset diagram

$$\begin{array}{c} E \\ \downarrow \mathfrak{g} \\ X \end{array}$$

base only Hausdorff
a condition replacing loc. triviality,
which in the completely regul. case coincides
with usual loc. triv.

GELFAND-P000210

[source number: 2]

2

The following property is required to hold:
consider the cone over $\mathfrak{g}$

Original source details: GELFAND-P000210

Uncertain reading. The looped group sign is the same as on the preceding page: fraktur-like lowercase $\mathfrak{g}$ / handwritten uppercase G. Candidate in the lines and diagrams: $\mathfrak{g}$; the letter case is undetermined. The heading has a wavy underline.

Original source details: GELFAND-P000210

Uncertain reading. The outer cone outline, rounded base, and internal curved paths. Closure of the paths and possible arrow directions are undetermined.



$\mathfrak{g}$ acts on it with one fixed point.

$\forall x \in X$, $\exists$ a map $E \longrightarrow C\mathfrak{g}$, commuting

with the group action; the fiber over [Crossed out: an illegible sign.]

Original source details: GELFAND-P000210

Undeciphered passage. Before x a sign with a lower loop is densely crossed out. Undetermined candidates: y / g.

x maps isomorphically onto the base of the cone
(Local triviality follows from this).
(For a completely regul. base (there exists a function 1 at the point, 0 outside a given nbhd) loc. triviality $\Longrightarrow$ this property.)
(but in this case the theory becomes trivial and all computed invar. are trivial)

D. Kazhdan's remark: then the height of the cone determines a cont. function on X.
So this def. is incorrect.

$\mathfrak{g}$ — a Lie group, $\mathfrak{g} \subset gL(n,\mathbb{R})$ — a closed subgr.



Original source details: GELFAND-P000210

Uncertain reading. The first letter before L has a lower loop: $gL(n,\mathbb{R})$ / $GL(n,\mathbb{R})$. Candidate in the line: gL; the letter case is undetermined. The group sign itself is the same as in the cone heading.

(i.e. $\mathfrak{g}$ acts on $\mathbb{R}^n$).
There exists a construction which makes a vector bundle (induced) from a principal bundle
$E^* = E \times \mathbb{R}^n/\mathfrak{g}$.
$(x,y) = (gx, gy)$



Original source details: GELFAND-P000210

Uncertain reading. Between the pairs are two short dense strokes merged with the opening parenthesis of the right-hand pair: $=$ / $\sim$. Candidate in the line: $=$; the sign is undetermined.



Original source details: GELFAND-P000210

Diagram and typed description.

$$\begin{array}{ccc} E^* & \longrightarrow & \mathbb{R}^n \\ \downarrow{\scriptstyle \mathbb{R}^n} & & \\ X & & \end{array}$$

There must exist a map $E^* \longrightarrow \mathbb{R}^n$,

[Crossed out: illegible.]

Original source details: GELFAND-P000210

Undeciphered passage. A short word before “linear” is crossed out by two strokes. The letters are undetermined.

linear on the fibers and
such that at a certain point x_0 (given)
it — an isomorphism.
(No compatibility with the group action).

this is the def. of loc. triviality (for Hausd.) and this is precisely the requirement.
Kazhdan’s remark cannot be repeated.

GELFAND-P000211

E is recovered from E^*.
One cannot construct a classif. space, but there is an analogue.
Example:
[An undetermined thickened sign.]

Original source details: GELFAND-P000211

Uncertain reading. Before the group notation is a separate thickened sign with a lower loop and a transverse stroke: “в” (in) / a crossed-out earlier sign. Neither candidate is established.

$\mathfrak{g} = \mathbb{R} \subset gL(1, \mathbb{R})$ — matrices with det > 0.



Original source details: GELFAND-P000211

Uncertain reading. The first letter before L has a lower loop: gL / GL. Candidate in the line: gL; the letter case is undetermined. The looped group sign itself is the same as on the preceding pages: $\mathfrak{g}$ / G, candidate $\mathfrak{g}$.

A nontrivial (principal) $\mathbb{R}$-bundle (also “universal”).
The direct product of countably many lines in the Tych. topology.

$$(x_1, x_2, \ldots) \quad \text{— sequences}$$

$$\alpha(x_1, \ldots) = (x_1 e^{\alpha}, \ldots)$$

The quotient space S cannot be embedded in E (!) — — there are no sections.
Fact: in $\mathbb{R}^\infty$ one cannot choose one point on each ray.

Proof.

S is Hausdorff, but every cont. function on it is const,

so such a map — to a point (coords. — cont. functions).

(Show that with [рассет. / рассеч.? (section?)]

Original source details: GELFAND-P000211

Uncertain reading. After "with" the source abbreviation is "рассет." / "рассеч." (section?). The last letter has an upper stroke and a downward stroke; the reading is undetermined.

$$\sum \frac{1}{2^n} \frac{|x_i|}{1+|x_i|} = 1/2$$

one obtains a discontinuous map.)

Suppose there is f. (a cont. function).

$$(x_1, x_2, \ldots)$$

$$a_i = f(\underbrace{0, \ldots, 0}_{i}, 1, \ldots, 1, \ldots)$$

$$a = f(x_1, x_2, \ldots)$$

We shall prove that $a = \lim_{i\to\infty} a_i$.

$\forall \varepsilon > 0 \; \exists$ a nbhd of the point

[Crossed out: an illegible sign.]

Original source details: GELFAND-P000211

Undeciphered passage. Before the coordinate parenthesis a sign is densely crossed out. The original grapheme is undetermined.

$(x_1, x_2, \ldots) \in S$,

where the difference is $< \varepsilon$. (from a).

$$(x_1^0, x_2^0, \ldots)$$

(A neighborhood — if the preimage is open)

GELFAND-P000212

[source number: 3]

3

A neighborhood in E

$$|x_1 - x_1^0| < \delta$$
$$\ldots$$
$$|x_N - x_N^0| < \delta.$$

Make these coords. the same, the others very large.

$$\left(\frac{x_1^0}{M}, \dots, \frac{x_N^0}{M}, 1, 1, \dots\right),$$

and by these the point $(0, \dots, 0, 1, \dots, 1, \dots)$ is approxim.
A map always exists (but is not unique)



Original source details: GELFAND-P000212

Uncertain reading. The upper-left vertex is rounded: calligraphic $\mathcal{E}$ / ε. Candidate in the diagram: $\mathcal{E}$; the letter is undetermined. Both horizontal arrows point right, both vertical arrows down with labels $\mathbb{R}$.

$$\begin{array}{ccc} \mathcal{E} & \longrightarrow & E \\ \downarrow{\scriptstyle \mathbb{R}} & & \downarrow{\scriptstyle \mathbb{R}} \\ X & \longrightarrow & S \end{array}$$

S is constructed from a product of $\mathbb{R}$ of any cardinality (depends on X)
$25/\overline{\text{IX}}$.
A good formula (Feynman)

$$\frac{1}{ab} = \int_0^1 \frac{dt}{(at + b(1-t))^2}$$

(decomp. into partial fractions)

$$\frac{1}{abc} = \int_\Delta \frac{dt_1\, dt_2}{(at_1 + bt_2 + ct_3)^3},$$

Δ — a simplex

$$t_1 + t_2 + t_3 = 1, \quad t_i \geq 0.$$

Next time Fuchs and then logic.
There is a counterexample to the hypothesis of a common fixed point of commuting cont. maps of an interval, and it is proved that if they are differentiable, there is a point fixed for one and of finite multiplicity for the other.

GELFAND-P000213

Fuchs (continuation).
$\mathfrak{g} \subset gL(n; \mathbb{R})$

Original source details: GELFAND-P000213

Uncertain reading. The first letter before L has a lower loop: gL / GL; a semicolon follows n. Candidate in the line: gL. The group sign itself is the same as before: $\mathfrak{g}$ / G, candidate $\mathfrak{g}$; the letter case is undetermined.

principal bundles

$$\begin{array}{ll} (\xi) & p : E \longrightarrow X \\ (\xi^\#) & p^\# : E^\# \longrightarrow X \end{array}$$

(X — Hausdorff)

($\mathfrak{g}$ acts on E without fixed points]



Original source details: GELFAND-P000213

Uncertain reading. The right-hand entry about an action without fixed points. The closing sign is angular:] / ⟩. Candidate in the line:]; the reading is undetermined.

(

$$xg_1 = xg_2 \Rightarrow$$
$$\Rightarrow g_1 = g_2$$

Loc. triviality: $\forall x \; \exists$ a map $E^{\#} \longrightarrow \mathbb{R}^n$, an isom. at the point x, linear on the fibers.
(One cannot require 0 outside small nbhds, since then even $X \times \mathbb{R}^n$ may fail to qualify because of nonregularity)



Original source details: GELFAND-P000213

Diagram and typed description.

A morphism — a map

$$\begin{array}{ccc} E_1 & \longrightarrow & E_2 \\ \downarrow & & \downarrow \\ X_1 & \longrightarrow & X_2 \end{array}$$

, commuting with the action of $\mathfrak{g}$.

Examples of functors:

1) cohomology

2) H-bundles (H — another group)

correspondingly charact. classes.

$h_{\text{alg}}(\mathfrak{g})$ — the set (group) of all char. classes constructed from the functor h.

1) For any top. space

[Crossed out: an illegible sign.]

Original source details: GELFAND-P000213

Undeciphered passage. After “пр-ва” (space), before X, an additional sign is densely crossed out. The original grapheme is undetermined.

X, the sheaf $\mathbb{R}$ of germs of cont. real functions on X is defined.

Put

$$h(X) = H^q(X, \mathbb{R}).$$

(for [Crossed out: illegible.]

Original source details: GELFAND-P000213

Undeciphered passage. A fragment between “for” and “paracomp.” is crossed out; a descender is visible. The letters are undetermined.

paracomp. X this is 0)

There is defined

$$H^q_{\text{alg}}(\mathfrak{g})$$

Answer. For semisimple $\mathfrak{g}$ having finitely many connected components

$$H^q_{\text{alg}}(\mathfrak{g}) = H^q(\bar{\mathfrak{g}}/\hat{\mathfrak{g}}; R)$$



Original source details: GELFAND-P000213

Uncertain reading. Above the first right-hand group sign is a straight bar, above the second an angular hat; a slash separates them. Candidate in the line: $\bar{\mathfrak{g}}/\hat{\mathfrak{g}}$. A descender from the preceding line overlaps the upper strokes; the reading of the first superscript mark remains open. The whole right-hand side is underlined.

with coeffs. in a constant sheaf —
— real coeffs.

GELFAND-P000214

[source number: 4]

4

Here $\bar{\mathfrak{g}}$ — a compact form of $\mathfrak{g}$
$\hat{\mathfrak{g}}$ — a max. comp. subgroup
[Crossed out: $\bar{\mathfrak{g}}$?]

Original source details: GELFAND-P000214

Undeciphered passage. Before the final group sign an entry is densely crossed out. Candidate $\bar{\mathfrak{g}}$ from the visible upper bar and lower loop; the precise form beneath the strokes is undetermined.

$\mathfrak{g}$. (For $\mathfrak{g} = gL(n, R)$



Original source details: GELFAND-P000214

Uncertain reading. The initial letter before L matches the looped lowercase group sign: gL / GL. Candidate in the line: gL; the letter case is undetermined. The group sign itself is the same as before: $\mathfrak{g}$ / G, candidate $\mathfrak{g}$.

there will be $\bar{\mathfrak{g}} = U(n)$, $\hat{\mathfrak{g}} = O(n)$
$\bar{\mathfrak{g}}$ is obtained as a max. comp. subgroup of the complexification of $\mathfrak{g}$)
2nd order: as for S^2.
For a compact group everything is trivial.
For a nonsemisimple one, take $\mathfrak{g}/\hat{\mathfrak{g}}$ and differ. forms on $\mathfrak{g}/\hat{\mathfrak{g}}$ invariant under $\mathfrak{g}$.
d(invar.) — invar. And the homologies of this complex are isomorphic to $H^q_{\text{alg}}(\mathfrak{g})$.

$$H^q_{\text{alg}}(\mathbb{R}; \mathbb{R}) = \begin{cases} R & q = 0, 1 \\ 0 & q > 1. \end{cases}$$

Check! (there are 1 and dx)

2) X, H — a top. group

$EH(X)$ — the set of all loc. triv. (in the usual sense) bundles (principal) on X.

\

Theorem.

$$EH_{\text{alg}}(\mathfrak{g}) = \text{Hom}(\mathfrak{g}, H)$$

(cont. hom. [Crossed out: an illegible sign.]

Original source details: GELFAND-P000214

Undeciphered passage. After “cont. hom.” are doubled curved and oblique strokes: a cancelled) / the sign φ. The reading is undetermined.

, more precisely, classes of conjugate homom.)

The natural answer — a hom. $\mathfrak{g} \longrightarrow H$ corresponds to a char. class, naturally defined.

$$\varphi_1 \sim \varphi_2, \text{ if } \exists h \in H, \qquad \varphi_1(g) = h^{-1}\varphi_2(g)h$$



Original source details: GELFAND-P000214

Uncertain reading. The map signs have diverging upper strokes and a long stem: φ / ψ. Candidate in the line: φ, in both indexed names. The exact Greek letter is undetermined. The sign $\sim$, h^{-1}, and order of factors are readable.

GELFAND-P000215

Construction of a universal bundle.



Original source details: GELFAND-P000215

Uncertain reading. At the top is an elongated inclusion with a rightward arrowhead on the upper stroke. The precise reading as $\hookrightarrow$ / $\subset$ with an added arrow is undetermined. There is a downward arrow on the left and $\subset$ below; there is no right vertical arrow. The rounded upper letter is rendered by candidate $\mathcal{E}$.

$$\begin{array}{ccc} \mathcal{E}^I_{\mathfrak{g}} & \xhookrightarrow{\quad} & \mathcal{E}^J_{\mathfrak{g}} \\ \downarrow & & \\ S^I_{\mathfrak{g}} & \subset & S^J_{\mathfrak{g}} \end{array}$$

$I \subset J$ — arbitrary sets.

Any bundle maps into a universal one with I of sufficiently large cardinality.

Consider $\mathbb{R}^I \ni (x_i,\ i \in I)$.

The topology — Tychonoff.

and $\underset{n \text{ lin. indep. vect.}}{n\text{-frames}}$ in it — this is precisely $\mathcal{E}^I_{\mathfrak{g}}$.

$gL(n, \mathbb{R})$ and $\mathfrak{g}$ act there.



Original source details: GELFAND-P000215

Uncertain reading. The initial letter before L matches the lower looped group sign on the right: gL / GL. Candidate in the line: gL; the letter case is undetermined. The group sign itself is rendered by the same candidate $\mathfrak{g}$ as before.

The quotient space is precisely our $S^I_{\mathfrak{g}}$.
Observe that $\mathcal{E}^I_{\mathfrak{g}}$ does not depend on $\mathfrak{g}$.
Lemma. $\forall \mathcal{E}^I_{\mathfrak{g}}$ and a cont. function f on it $\exists$
$J \subset I$ such that $I \setminus J$ is at most countable, and
and $f|_{\mathcal{E}^J_{\mathfrak{g}}} =$ const.

GELFAND-P000216

[source number: 6]

2/X. Fuchs.
T — a space, $S \subset \mathrm{Map}(T, T)$, compact open top.
$\mathfrak{g}$ acts on T on the right



Original source details: GELFAND-P000216

Uncertain reading. The group sign is looped: lowercase fraktur-like $\mathfrak{g}$ / handwritten uppercase G. Candidate in the lines, subscripts, and diagrams: $\mathfrak{g}$. The element sign g in the next line is simpler; the letter case of the group sign is undetermined.

$$f \in S, \quad g \in \mathfrak{g} \Rightarrow fg \in S,\ gf \in S.$$

Examples.
1°. $\mathfrak{g} \subset gL(n; R)$,



Original source details: GELFAND-P000216

Uncertain reading. In the first example $gL(n; R)$ / $GL(n; R)$; the initial letter is looped. Candidate in the line: gL; the letter case is undetermined.

$T = \mathbb{R}^n$; S — all lin. maps (including zero maps).
2°. $\mathfrak{g}$ — a Hausdorff top. group, $T = C\mathfrak{g}$ — the cone over $\mathfrak{g}$

Diagram and typed description.

Original source details: GELFAND-P000216

$\mathfrak{g}$ acts naturally, S is generated by them and similarities

[Crossed out: растя... / растяже...? (dila...?)]



Original source details: GELFAND-P000216

Undeciphered passage. Before “contractions” a word or beginning of a word is crossed out; the opening “раст...” is distinguishable. The ending is undetermined.

contractions toward the vertex (and to a point).

Axioms.

1°. T is contractible by transformations in S to a marked point $*$.

2°. $\mathfrak{g}$ is closed in the group of all homeom. of T to itself.

3°. $*$ is fixed under all transf. in S.

4°. $\varphi_t : T \longrightarrow T$

$$\varphi_0 = \text{identity}, \quad \varphi_t \in S \quad —$$
$$\varphi_1(T) = *$$



Original source details: GELFAND-P000216

Uncertain reading. The Greek map sign has diverging upper strokes and a stem: φ / ψ. Candidate in the fourth axiom and following phrase: φ; the exact letter is undetermined. Subscripts 0, t, 1, identity, and image $*$ are readable.

— the homotopy of axiom 1°.

Then there exist φ_t such that φ_t for $t < 1$ are topological embeddings.

5°. S contains all transf. of $\mathfrak{g}$, and maps close to maps of $\mathfrak{g}$ in S are top. embeddings.

$U(1) \subset S$ consists of embeddings.

In this situation spaces are defined



Original source details: GELFAND-P000216

Diagram and typed description.

$$\begin{array}{c} \mathcal{E}_{\mathfrak{g}} \\ \downarrow \\ S_{\mathfrak{g}} \end{array}$$

, the action of $\mathfrak{g}$ on $\mathcal{E}_{\mathfrak{g}}$ — a universal principal bundle.

$\underbrace{T \times \cdots \times T}_{I \text{ times}}$ Tych. topology.

6°. $\mathfrak{g}$ acts effectively on T,

(otherwise [удвл. / удовл.?] point)



Original source details: GELFAND-P000216

Uncertain reading. The final parenthesis contains the abbreviation “удвл.” / “удовл.”. The reading and expansion of the word are undetermined.

An element of $\mathcal{E}_{\mathfrak{g}}$ — any embedding $T \subset T^I$ such that its compositions with all projections lies in S.



Uncertain reading. In the subscript of the rounded E and subsequently in $C\mathfrak{g}$, the action, and cohomology, the group sign is looped: $\mathfrak{g}$ / handwritten uppercase G. Candidate: $\mathfrak{g}$; the letter case is undetermined.

Original source details: GELFAND-P000217

1) $T = \mathbb{R}^n$ — all n-frames.

2) $T = C\mathfrak{g}$, $\mathcal{E}_{\mathfrak{g}} = C\mathfrak{g} \times \ldots \times C\mathfrak{g} \setminus \{*, \ldots, *\}$.

$\mathfrak{g}$ acts on $\mathcal{E}_{\mathfrak{g}}$ by multiplication by transf. in $\mathfrak{g}$.

I finite $\Rightarrow$ 1) the usual classif. space
2) Milnor's constr. with a not very substantial modification.

Diagram and typed description.

$\mathfrak{g} = \mathbb{R}$, $T =$ •————

Original source details: GELFAND-P000217

$\mathcal{E}_{\mathfrak{g}}$ — sequences of nonneg. numbers.

For each T its own definition of loc. triviality.



Diagram and typed description.

$$\begin{array}{c} E \\ \downarrow \mathfrak{g} \\ X \end{array}$$

Original source details: GELFAND-P000217

is loc. triv. if the induced bundle

Diagram and typed description.

$$\begin{array}{c} E^{\#} \\ \downarrow T \\ X \end{array}$$

Original source details: GELFAND-P000217

, has the property: $\forall x \; \exists$ a map $E^{\#} \longrightarrow T$, a homeom. on the fiber over x, and on $\forall$ fiber it is a transf. in S.

Theorem.

Every bundle maps into this one.

(X — all Hausdorff)

Defined $H^q_{\text{alg}}(\mathfrak{g};\mathbb{R})$

Theorem.

Whatever T and S may be, $H^q_{\text{alg}}(\mathfrak{g},\mathbb{R})$ does not depend on their choice

(Instead of $\mathbb{R}$ one may take a group A)

What will there be?

Uspenskii, Lectures on logic 2

Lidskii, Asymptotics of eigenfns. (after Hörmander)

Sinai, Conditions on diffeom. under which there is an invar. measure

Kazhdan, Discr. groups — solution of Selberg's problem

Kushnirenko, Analyt. action of a semisimple group in a nbhd. of a fixed point — linear

GELFAND-P000218

[source number: 7]

Tyurina and S. Gelfand survey of Pham's works.

Anosov and Maslov

I. Bernstein P^λ

Gelfand, Graev

S. G. Krein



Original source details: GELFAND-P000218

Uncertain reading. Интерполяции / Интерполяция (interpolation); the ending is uncertain.

Berezin
Kirillov' Grassmann analysis.

— • —

GELFAND-P000219

$16/\overline{\text{X}}$



Original source details: GELFAND-P000219

Uncertain reading. [Crossed out: illegible.]

S. G. Krein.

On interpolation of linear operators.



Original source details: GELFAND-P000219

Diagram and typed description.

$$\left.\begin{array}{l} E_0, \xrightarrow{A} F_0, \\ E_1, \xrightarrow{A} F_1, \end{array}\right\}$$ Banach spaces,



Uncertain reading. all embedded / all are embedded

Original source details: GELFAND-P000219

into one T. L. S. (the left and the right ones)

A is bounded.

E, F — an interpolation pair if, for $\forall$ A, boundedness at 0 and 1 implies boundedness of $A : E \longrightarrow F$.

All spaces will be spaces of summable functions.

A Banach space of summable functions [Inserted below the line: on $[0, 1]$.]



Uncertain reading. на / наз. (on / called)

Original source details: GELFAND-P000219

symmetric if

1) $y(t) \in E$

$$|x(t)| \le |y(t)| \quad \Longrightarrow \quad x \in E \qquad \text{and} \qquad \|x\| \le \|y\|$$

2) The norm does not change under transformations preserving measure (one may consider an equimeasurable monotone one)

Then $L_\infty \subset E \subset L_1$.

Examples. 1)

$$\int_0^1 x^*(t)\, d\psi(t), \qquad \psi(t) \text{ — monot.} \qquad \text{— of Lorentz type}$$



Uncertain reading. In the differential, the monotonicity label, and the denominator of the next example, the Greek sign has three upper arms and a lower stroke: ψ / Ψ. Candidate: ψ; the letter case is undetermined.

Original source details: GELFAND-P000219

$x^*(t)$ — a rearrangement of $|x(t)|$

2) Dual. $\sup\limits_e \dfrac{\int_e |x(t)|\, dt}{\psi(me)}$

3) and Orlicz spaces (these include L_p)

[At the left above the line:] 1st step.

Riesz–Thorin theorem.

GELFAND-P000220

2nd step.

Marcinkiewicz theorem.

(Less is required at the endpoints)

$$n_x(\tau) = \text{mes}\{t : |x(t)| \ge \tau\}$$

$$[n_{Ax}(\tau)]^{1/q_i} \le \frac{C}{\tau} \|x\|_{L_{p_i}}$$

— a less restrictive condition.

Most operators of analysis satisfy the Marcinkiewicz conditions at the endpoints

Matsaev and Dikarev — more precisely, from L_p into a space narrower than L_q (of Lorentz type)! — and it is already minimal (in the middle)

(Minimal for all operators under conditions both of Marcinkiewicz and of Riesz–Thorin) —

— this is for improving operators:

$$\begin{matrix} q_1 > p_1 \\ q_2 > p_2 \end{matrix} \quad \| \quad \text{— as in the Marcinkiewicz theorem.}$$

$p = q$ — maps into itself — then all the other scales do too.

Let $\begin{matrix} L_1 \longrightarrow L_1 \\ L_\infty \longrightarrow L_\infty \end{matrix}$ and $\|A\| \leq 1$

List all

Uncertain reading. [Crossed out: illegible.]

Original source details: GELFAND-P000220

spaces for which $\|A\| \leq 1$ as well.



Original source details: GELFAND-P000220

Diagram and typed description. The purpose and direction of the additional oblique strokes are undetermined.


into itself


into itself

[To the right of the figures:] linear oper. (2-dimensional case).

Док. [prove / proved], that these are all symmetric norms and only they.



Uncertain reading. The abbreviation “Док.” is readable; the full verb form is not written. Possible expansions: prove / proved.

Original source details: GELFAND-P000220

General theorem — B. S. Mityagin.

It is necessary and sufficient that the space be symmetric.

(also in the ∞-dimensional case)

$L_p \xrightarrow{A} L_p$ what then?

$p \neq 1, \infty$

(Marcinkiewicz case)

$$\| \underset{\substack{| \\ \text{char. fn. } e}}{\chi_e} \|_E = \varphi(me).$$

(symmetry is again necessary)

the resulting function $\varphi(t)$ — a characteristic of the space E.

$$\ell_E = \underline{\lim}_{t\to 0}\frac{\varphi(2t)}{\varphi(t)} \qquad u_E = \overline{\lim}_{t\to 0}\frac{\varphi(2t)}{\varphi(t)} \qquad 1 \le \ell_E \le u_E \le 2$$

GELFAND-P000221

[source number: 9]

For L_p they are both equal to $2^{1/p}$

Boundedness of all such A in $E \Longleftrightarrow 1 < \ell_E \le u_E < 2$

(Semyonov's 1st theorem)

Mityagin's theorem has not been generalized.

$$L_{1/\alpha} \longrightarrow L_{1/\alpha-\Delta}$$



Original source details: GELFAND-P000221

Uncertain reading. The right subscript is written as a diagonal fraction without parentheses: $1/\alpha - \Delta$ / $1/(\alpha - \Delta)$. The grouping is undetermined.

$0 < \Delta \le \alpha_0 < \alpha < \alpha_1$.

How can one list the spaces in which operators of this type are bounded?

$$2^{\alpha_0} < \ell_E \le u_E < 2^{\alpha_1} \quad \Longrightarrow \quad E \longrightarrow E_\Delta,$$

where

Original source details: GELFAND-P000221

Uncertain reading. After "where" there are two dense short signs; their exact reading and whether they are crossed out are undetermined.

$$\|x\|_{E_\Delta} = \|x^*(t)t^{-\Delta}\|_E$$

(This generalizes the theorem of Dikarev and Matsaev — the best space)

Applic.: Hausdorff–Young inequality

$$\sqrt[p]{|c_k|^p} \le \|x\|_{L_p} \qquad \text{— from Riesz's theorem}$$



Original source details: GELFAND-P000221

Uncertain reading. The first radicand visibly contains $|c_k|^p$; no separate summation sign is distinguishable. The root index is p, and the right-hand norm is in L_p.

Poia inequality:

$$\sqrt[p]{\sum k^{p-2}c_k^{*p}} \le C\|x\|_{L_p}$$

c_k^* — the monotone rearrangement of the $|\ |$ coefficients.

For monotone decreasing Fourier coefficients — two-sided inequalities (Hardy–Littlewood)

Between L_1 and $L_{1,5}$ there is no Hilbert interpolation space (Semyonov)

Gelfand's question: an abstract description of interpolation spaces. (it is unknown whether they are spaces of functions.)

Ya. Sinai.

Construction of invar. measures of smooth maps Markov partitions



Original source details: GELFAND-P000221

Diagram and typed description.

$T(x_1, x_2) = (ax_1 + bx_2,\ cx_1 + dx_2)$ — a map of the torus

and T_1. — another.

When does there exist a measurable map of the torus, $M \xrightarrow{U} M$, such that $UT_1 = T_2U$.



Original source details: GELFAND-P000221

Uncertain reading. First T, then T_1; in the equation, T_1 and T_2. The sign on the arrow and on both sides of the equation is looped: U / u; candidate: U, with letter case undetermined.

Irrational eigenvalues $\Rightarrow$ real $\Rightarrow$ ergodic, the spectrum is Lebesgue of countable multiplicity.

Entropy $h(T) = \ln \lambda \quad (\lambda > 1)$

GELFAND-P000222

If h agrees, this does not yet give linear conjugacy (there are other-inv.)

But metrically they are similar! (U — discontinuous, but measurable)

U — a homeom. $\Longrightarrow$ it is linear (one can prove this) (for any compact abelian groups)



Original source details: GELFAND-P000222

Uncertain reading. The looped map sign in both lines: U / u. Candidate: U; letter case is undetermined.

Ω_Π — the space of seq. $\omega = \{i_n\}$ — sequences infinite in both directions.

$i_n \in \{1, \ldots, S\}$

$$\underset{\text{of order } S}{\Pi} = \|x_{ij}\|, \quad x_{ij} = 1, 0 \qquad \pi_{i_n i_{n+1}} = 1$$

(only such sequences ω are admissible.)

We shall assume that Π^k consists of positive entries.

Consider the shift (the shift transformation on Ω).

Example. $\begin{pmatrix} 1 & 0 \\ 0 & 1 \end{pmatrix}$ — does not satisfy the cond., but Ω — sequences only of 1 or

Uncertain reading. [Crossed-out sign: illegible.]

Original source details: GELFAND-P000222

only of 2

$\begin{pmatrix} 1 & 1 \\ 1 & 1 \end{pmatrix}$ — anything may be put in

$\begin{pmatrix} 1 & 1 \\ 1 & 0 \end{pmatrix}$ — look into it.

on Ω_Π we would like to specify an invariant measure μ with max entropy:

Uncertain reading. [An illegible crossed-out entry to the left of the formula.]

Original source details: GELFAND-P000222

$$h = \max_{\mu} h_\mu(T)$$

(



Uncertain reading. [Crossed out: where / shift.]

Original source details: GELFAND-P000222

T — this is the shift).

One must consider e with positive coordinates. $\lambda e = \Pi^* e$, $\lambda > 0$

(unique.)

(G. If all entries and all minors of order 2 are > 0, then there exist 2 eigenvectors, the 1st with positive entries, the 2nd — with the 1st change of sign —

— the matrix of minors of order 2 — a representation of the matrix itself in the exterior product.)

Consider a Markov chain with probabilities $p_{ij} = \dfrac{e_j \pi_{ij}}{\lambda e_i}$ —

[At the right:] — entropy — $\ln \lambda$

[In general, the entropy of a Markov chain

$$h = \sum_i e_i \left(- \sum_j \ln p_{ij}\, p_{ij} \right)$$

the measure of max entropy is unique.

The measure in Ω_Π on the Σ-alg. generated by cylindrical sets.

GELFAND-P000223

[source number: 10]

a) $\{a_1^1, \dots, a_p^1;\ a_1^2, \dots, a_q^2;\ b_1^1, \dots, b_r^1;\ b_1^2, \dots, b_s^2\}$
Π

$$\text{from } \left.\begin{matrix}\alpha^1\\ \alpha^2\end{matrix}\right\} \longrightarrow \alpha^1 \text{ or } B^1$$

$$\text{from } \left.\begin{matrix}\beta^1\\ \beta^2\end{matrix}\right\} \longrightarrow \alpha^2 \text{ or } B^2$$



Uncertain reading. In the transitions the shapes $\alpha/a/A$ and $\beta/b/B$ are not uniquely established; the B-like signs on the right are larger. The alphabet above has a and b. The displayed candidates are α, β on the left and B on the right.

Original source details: GELFAND-P000223

[In the right margin:] ‖ a partition is constructed from an integer matrix of order 2.

$$\lambda^2 - (p+s)\lambda + (ps - qr) = 0, \qquad \boxed{\boxed{ps - qr = 1}}$$

condition.

b) Ω_{Π_1} $\pi_{ij} = 1$ and $\pi_{N1} = 0$ (only in the 1st position)

Prop. The shifts in a) and b) are isomorphic.

[Everything now reduces to proving that
an algebraic automorphism ⇒
⇒ a partition.

Proof of the proposition.

Alphabet b): $A_1, \dots, A_p$, $B_1, \dots, B_s$.

(Isomorphism of any 2 Ω_Π with the same entropy).

Different groups are encoded (using the symbols A_i, B_i).

The space with the 1st max measure passes into a space with another max measure.

Next time: Markov partitions and how invariant measures are constructed with their help.

$23/\overline{\text{X}}$. Leray. Singularities of Feynman integrals.

N. Nilsson, Arkiv för Math. (Swede) 1964–1965

(student of Gording)



Undeciphered passage. A short formula below "(student of Gording)" is crossed out. Possible beginning: $J(\dots)$; the remaining symbols are illegible.

Original source details: GELFAND-P000223

Original source details: GELFAND-P000223

Uncertain reading. A separate crossed-out sign below the formula: J / γ; its reading is undetermined.



Original source details: GELFAND-P000223

Uncertain reading. The cycle superscript is q / a; candidate: q. The coordinate sign in the argument of ω and below is ξ / ζ; candidate: ξ. The labels "cycle relative to $W(t)$", "homog. deg. 0", and "$= 0$ on $W(t)$" are readable.

$$J(t) = \int_{\gamma^q(t)} \omega(t,\xi)$$

cycle relative to $W(t)$ — homog. deg. 0 $= 0$ on $W(t)$

$t \in T = C^n$,

$\xi \in C^{\ell+1}$

$\omega(t,\xi)$ on P^ℓ, since it is homogeneous; the cycle is there too.

GELFAND-P000224

$W(t) = \bigcup_k W_k(t)$ — hyperplanes, algebraic functions of t, singularities may occur (not in general position)

$t \in S_0[W] \iff$ the dimension of the intersection of any number changes there.

Def:

$$\gamma^{q-m}(t) = \bigcap_{j=1}^{m} V_j(t),$$



Uncertain reading. Large sign: $\bigcap$ / $\bigwedge$; displayed candidate: $\bigcap$.

Original source details: GELFAND-P000224

$$V_j(t) = v_j(t,x) = 0$$

algebraic variety

One must assume

$$\frac{\omega(t,\xi)}{[v_1(t,\xi)]^{1+\beta_1}\dots[v_m]^{1+\beta_m}}$$ — defined on P



Uncertain reading. The coordinate signs in the argument of ω and first denominator: ξ / s; displayed candidate: ξ. The last factor is written $[v_m]^{1+\beta_m}$.

Original source details: GELFAND-P000224

[On the left:] Residue

$$J(t) = \int_{\gamma^{q-m}(\xi)} \frac{d^{\beta_1+\ldots+\beta_m}\omega}{[dv_1]^{1+\beta_1} \wedge \ldots \wedge [dv_m]^{1+\beta_m}}$$



Uncertain reading. Argument below the integral: ξ / s; displayed candidate: ξ.

Original source details: GELFAND-P000224

The singular support is also described in the general case

(On the covering space of the complement the form will be holomorphic)

Thm. Then $J(t)$ has algebraic singular support.

Uncertain reading. Right-margin note: “of type st. algebraic” / “of type sm. algebraic”; the first word and middle abbreviation are not uniquely established.

Original source details: GELFAND-P000224

(i.e. in T there exists an algebraic variety such that $J(t)$ is holomorphic on a covering of the complement.)

Leray described the singular support in the case of planes.

30/X Sinai.

U-diffeom.

characteristic exp growth of the distance between nearby points (separation)

either as $t \longrightarrow +\infty$, or as $t \longrightarrow -\infty$.

$$\frac{d(T^n x, T^n y)}{d(x,y)} \geq a e^{cn} \qquad \begin{matrix} n > 0 \\ \text{or } n < 0 \end{matrix} \qquad (x, y \text{ — nearby})$$

Consider the points $d(T^n y, T^n x) \leq a e^{-cn} d(y, x)$,

Suppose that $\forall\, x$ this is a k-dimensional submanifold.



Diagram and typed description.



Original source details: GELFAND-P000224

This is a contracting submanifold (hence the index c)

$$d(T^n y', T^n x) \leq a e^{+cn} d(y', x) \qquad (n \longrightarrow -\infty).$$

Similarly we obtain $\Gamma^{(p)}(x)$ — an expanding submanifold.
(ℓ-dimensional).
Then the choice does not depend on a and c.

GELFAND-P000225

[source number: 11]

U-system: $k+\ell=n$ and the tangent spaces to the submanifolds are uniformly transverse

1. $k+\ell=n$
2. transversality.
3. Smoothness (not written out explicitly).

We obtain 2 foliations $\gamma^{(c)}$ and $\gamma^{(p)}$.
Example: linear transformation of the torus $(x,y)\longrightarrow(ax+by, cx+dy)$.

$$\begin{vmatrix} a & b \\ c & d \end{vmatrix} = 1.$$



Original source details: GELFAND-P000225

Uncertain reading. Two families of inclined lines and axes with arrows upwards and rightwards. The number of coinciding lines and continuations within dense crossings are not uniquely established. Individual lines have no labels.



(parallel to the eigendirections).

A nonlinear perturbation (periodic and smooth) is also a U-diffeomorphism and the rotation number is the same.

Method of constructing U-diffeomorphisms.

g — a Lie group, Γ — a discrete subgroup.
g/Γ — compact.



Original source details: GELFAND-P000225

Uncertain reading. Lie-group notation: g / $\mathfrak{G}$; displayed candidate: g, distinct from the subsequent G.

T_{alg} — an algebraic automorphism of g, leaving Γ fixed $\quad(T_{\text{alg}}\Gamma=\Gamma)$

automorphism as a group

Then it acts on g/Γ.
Consider G — the Lie algebra; $\hat{T}_{\text{alg}}$ — the corresponding automorphism of G; if its
[At the left edge of the following line:] eigenvalues.
Among them there are no

Original source details: GELFAND-P000225

Uncertain reading. Crossed out: $\Longleftrightarrow$ / $\Longrightarrow$; endpoint directions are not established.

eigenvalues $= 1$ in mod

Original source details: GELFAND-P000225

Uncertain reading. Sign after mod: $\Leftrightarrow$ / a crossed-out sign.

$\Longleftrightarrow$ this is a U-diffeomorphism.
(They exist $\Longleftrightarrow$ G is nilpotent).



Original source details: GELFAND-P000225

Uncertain reading. Initial word in the parenthesis: “They exist” / “It exists”; the first candidate is displayed. The original fragment contains the entire parenthesis.

Further. A small nonlinear perturbation $T = T_{\text{alg}} + \Delta T$ is also a U-diffeomorphism.
Main problem: topological similarity to the algebraic one.
For small perturbations — from Anosov's general theorem
(A small perturbation of a U-diffeomorphism is topologically similar to the original).
Always.

$$M = M_1 \cup M_2$$

M_2 — wandering points
M_1 — nonwandering points. — the condition U holds on them
[In the right margin:]

| also a
| conjecture

GELFAND-P000226

An important construction:



Original source details: GELFAND-P000226

Diagram and typed description.



natural isomorphism of our pieces. of contracting leaves (along noncontracting leaves).

D_{c} — a contracting submanifold, dim $= k$.

(π — the canonical isomorphism.)

π is not always smooth (!), but it is absolutely continuous, i.e. the natural measures pass into one another.



Original source details: GELFAND-P000226

Uncertain reading. Two nearly vertical curved strokes and transverse curves; the number of coinciding strokes and their continuations at the dense middle crossings are not uniquely established. No labels or arrows are visible.

A parallelogram:



made of segments of foliations

(all its leaves are canonically isomorphic: both contracting and expanding.)

$$\Gamma(U) = \Gamma_{\mathrm{p}}(U) \cup \Gamma_{\mathrm{c}}(U)$$

Suppose there is a system of parallelograms U_i adjoining one another.

$$M = \bigcup \overline{U}_i$$
$$U_i \cap U_j \subset \Gamma(U_i) \cap \Gamma(U_j) \qquad (\Gamma \text{ — boundaries}).$$

α — such a partition into parallelograms. Consider the boundaries:

$$\Gamma_{\mathrm{p}}(\alpha) = \bigcup_i \Gamma_{\mathrm{p}}(U_i)$$
$$\Gamma_{\mathrm{c}}(\alpha) = \bigcup_i \Gamma_{\mathrm{c}}(U_i)$$

[Drawing on the right:]



Diagram and typed description.



Original source details: GELFAND-P000226

This α is called Markov if there exists an m such that

$$\boxed{\begin{array}{l}\Gamma_{\mathrm{p}}(T^{-m}\alpha) \subset \Gamma_{\mathrm{p}}(\alpha) \\ \Gamma_{\mathrm{c}}(T^{+m}\alpha) \subset \Gamma_{\mathrm{c}}(\alpha)\end{array}}$$

Thm. (technical) Markov partitions exist and there are many of them: $\forall$ α / partition into parallelograms, $\forall \varepsilon > 0$ $\exists m$ and a partition $\widetilde{\alpha}$, such that it will be at a distance of less than ε from the original.

[On the left:]



Original source details: GELFAND-P000226

Uncertain reading. A separate inclined quadrilateral and a narrow inclined strip with transverse quadrilaterals at its ends. The continuations of several superposed contours at the upper right end are not uniquely established. There are no arrows.



the ends cannot be in the middle.
(original parallelogram.)

— • —

If α is a partition with m, then one can make $m = 1$, taking the intersection

$$\alpha_1 = \alpha \cdot T^{-1}\alpha \cdot \ldots \cdot T^{-m+1}\alpha \text{ —}$$

— Markov with $m = 1$

GELFAND-P000227

[source number: 12]

— from

$$\Gamma_{\mathrm{p}}(\alpha_1) = \Gamma_{\mathrm{p}}(\alpha) \cup \Gamma_{\mathrm{p}}(T^{-1}\alpha) \cup \cdots \cup \Gamma_{\mathrm{p}}(T^{-m+1}\alpha)$$

Symbolic dynamics for a U-diffeomorphism.

(Suppose there is a Markov partition and with $m = 1$.)

$$\pi_{j_1 j_2} = \begin{cases} 1 & V_{j_1} \cap TV_{j_2} \neq \varnothing \\ 0 & \text{in the remaining cases} \end{cases}$$

Π

Ω_Π — the space of points

$$\omega = \{\dots\ j_{-n}, \dots, j_0, \dots, j_n, \dots\}$$
$$\pi_{j_n j_{n+1}} = 1.$$

Now associate

$$\omega \longrightarrow \bigcap_{-\infty}^{+\infty} T^n \overline{V}_{j_n} = x \in M \qquad (!)$$

(nonempty by the Markov property and, for a fine partition, consists of 1 point.)

We obtain a map $\varphi : \Omega_\Pi \longrightarrow M$

[A parenthesis begun on the right:] (from nonuniqueness.

it is not



Original source details: GELFAND-P000227

Uncertain reading. After the readable “not” a short entry is crossed out; possible “one-to-” is not established.

one-to-one because of the points — boundaries of parallelograms).

On a set of the 2nd category it is one-to-one.

Condition: Π^K consists of positive entries for some K.

(i.e. all leaves $\Gamma^{(c)}$ and $\Gamma^{(p)}$ are dense in M — this is necessary and sufficient.)

On each leaf $\Gamma^{(c)}$ a σ-finite measure λ_c is introduced,

where

[On the left:]



Original source details: GELFAND-P000227

Uncertain reading. The lines labelled $A, \widetilde{A}$ and connecting curves. Directed thickenings are visible at two lower right ends; the number of coinciding lower curves and character of the other ends are not uniquely established.



1) $\lambda_c(A) = \lambda_c(\widetilde{A})$

(measures of canonically isomorphic sets are equal.)

2) $\lambda_c(TA) = h\lambda_c(A) \quad (h < 1)$

(h — an algebraic number.)

— additional information.

(Reflects the homogeneous structure.)

(In an algebraic



Original source details: GELFAND-P000227

Uncertain reading. A word is crossed out, possibly “case”; its reading is not established.

[Inserted above:] U-automorphism everything is induced by Haar measure.)

Corollary:

there is an invariant measure, T is

Original source details: GELFAND-P000227

Uncertain reading. Crossed-out sign: Cyrillic “б” / “в”; its reading is not established.

a finite Markov chain.

Construction of this measure:

$(n = 2)$



Original source details: GELFAND-P000227

Uncertain reading. Two diagrams with V_i, leader stroke, transverse marks, and visible directed strokes. Connections of thick lines at the base of the right diagram and some endpoint directions remain undetermined. There is no arrow between the diagrams.



$$\lambda_i h^{-1} = \sum \lambda'_i = \sum \pi_{ii'} \lambda_{i'}, \quad \text{i.e.}$$



Original source details: GELFAND-P000227

Uncertain reading. In the first sum the prime is high: $\sum \lambda'_i$ / $\sum \lambda_{i'}$; the first candidate is displayed.

$$\boxed{h^{-1}\vec{\lambda} = \Pi\vec{\lambda}.}$$

— eigenvector.

(This is for our

Uncertain reading. A short crossed-out entry is illegible.

Original source details: GELFAND-P000227

parallelograms).

The values of the measure on a segment are given. Then from the 2nd property.

[Below the last line:] (on a smaller segment.)

GELFAND-P000228

Uncertain reading. Энтропия / Энтропии (entropy); the ending is not uniquely established.

Original source details: GELFAND-P000228

$$T = \begin{vmatrix} a & \cdot & b \\ c & & d \end{vmatrix}$$

$$h(T) = \ln \lambda \quad (\lambda > 1)$$

$$h(T) = \lambda$$

$\Rightarrow$ the transformations are metrically isomorphic.

Ω_{Π_1} maps onto Ω_{Π_0} (stand.) —



Uncertain reading. прежн. раз. / прим. раз. (prev. time / example, time); the first abbreviation is undetermined.

Original source details: GELFAND-P000228

And it remains to map the torus onto Ω_{Π_1}.

Π_1 is of a certain type: 4 groups of letters and properties of transitions — see earlier.



Uncertain reading. A nearly rectangular frame, oblique edges projecting above, to the right and below, and hatching. Continuations of lines at dense crossings and exact boundaries of the hatched parts are not uniquely established. There are no vertex labels or arrows.



Original source details: GELFAND-P000228

— a partition of the torus into 2 parallelograms (the sides ∥ the eigendirections)
The sides lie on a line through 0 in an eigendirection (and



Original source details: GELFAND-P000228

Uncertain reading. продолж. / проек. (cont. / proj.); the middle strokes of the abbreviation merge.

).
This is a Markov partition (the coarsest). It is because of it that one succeeds in solving the isomorphism problem.

$$\bigcap T^n V_{\omega_n}$$



Original source details: GELFAND-P000228

Uncertain reading. The subscript under V is ω_n / ω; a separate lower n is not established. No separate index is visible at the intersection sign.

may consist of a large number of points.
Consider first 4 parallelograms:

$$V_1 \cap TV_1$$
$$V_2 \cap TV_2$$
$$V_1 \cap TV_2$$
$$V_1 \cap TV_2$$



Original source details: GELFAND-P000228

Uncertain reading. The second intersection: $V_2 \cap TV_2$ / $V_2 \cap TV_1$. The right subscript is heavily retraced; the first candidate is displayed.

(



Uncertain reading. Уже (Already); the word is readable, but whether a transverse stroke crosses it out is undetermined.

Original source details: GELFAND-P000228

a disconnected partition. Form a partition — — its connected components. Their numbers, respectively — —

Uncertain reading. p, q, r, s; the second sign is heavily retraced and q remains a candidate.

Original source details: GELFAND-P000228

)

GELFAND-P000229

Year 1968.

12/II Question (Gelfand)

R — a countably normed ring:

$$\|xy\|_i \leq \|x\|_k \|y\|_\ell$$



Uncertain reading. The last subscript: ℓ / e; ℓ is displayed.

Original source details: GELFAND-P000229

Diagram and typed description.



Original source details: GELFAND-P000229

for

Original source details: GELFAND-P000229

Uncertain reading. [Superscribed sign: superposed loops and strokes; its reading is undetermined.]

normed rings:

$$f(x^*x) \geq 0 \Rightarrow f(x) = \int_{\mathcal{M}_0} x(M)\, d\sigma(M)$$

($\mathcal{M}_0$ — symm. ideals)



Original source details: GELFAND-P000229

Uncertain reading. In the lower limit and the explanation, the letter is M_0 / m_0 / $\mathcal{M}_0$; the lower zero is readable. Case and style are undetermined; $\mathcal{M}_0$ is displayed.

Extension — ? (Not always: one must characterize the class axiomatically).

$$x^*(M) = \overline{x(M')}, \quad M = M'$$

— symm.

L^1 with convolution, $\overline{x(-t)} = x^*(t)$

$\Rightarrow$ Bochner's theorem

$$\int_{-\infty}^{+\infty} e^{it\lambda}\, d\sigma(t)$$

I. Bernstein.

Original source details: GELFAND-P000229

Diagram and typed description.

Grothendieck topology.

T is the following collection:

1) The category Cat T is specified (objects — open sets).

2) Certain families $\{\alpha_i : U_i \to U\}$ are specified, called coverings

3) A system satisfying axioms is specified:

1. There exists an intersection — a product (fibered).



Original source details: GELFAND-P000229

Diagram and typed description.



(commut.).



Original source details: GELFAND-P000229

Diagram and typed description.

— given 3 objects

and 2 maps

$\boxed{V = V_1 \times_U V_2}$ — notation. Then there exists



Original source details: GELFAND-P000229

Diagram and typed description.



The universal property is required to hold:

$\forall X$, and $\forall$



Original source details: GELFAND-P000229

Uncertain reading. Four outer arrows: $X \to V_1$, $X \to V_2$, $V \to V_1$, $V \to V_2$. Wedge-shaped strokes are visible at both ends of the thick central connection; its direction and whether it was corrected are undetermined. The visible heads are retained but do not establish an unambiguous universal map. A leader points to “exists and is unique”.



Depends essentially on U (in Grothendieck top.)

(If V exists, it is determined uniquely by the properties of the category)

GELFAND-P000230

Original source details: GELFAND-P000230

Uncertain reading. At the upper right, 18 / 98; the first digit is thickened. The candidate 18 and angular frame are displayed.



2. $\{U \xrightarrow{\text{id}} U\}$ — a covering.

3. $\{V_i \to V\}$ — a covering.

$\{V_{ij} \to V_i\}$ — a covering.

$\Rightarrow \{V_{ij} \to V\}$ — a covering.

4. $\{U_i \to U\}$ — a covering

$\{V \to U\}$ — a morphism

Then $\{U_i \times_U V \to V\}$

Example: unramified topology.

X — an ordinary topological space.

An open set: $U \to X$ — a local homeomorphism

(U — a topological space)

(a covering over X or its open



Original source details: GELFAND-P000230

Uncertain reading. подмн-вом (subset) / мн-вом (set), with possible cancellation of the initial “под”; no separate crossing-out stroke is established.

).

A map



Original source details: GELFAND-P000230

Diagram and typed description.



(any continuous one with a commutative diagram)

$\{U_i \to U\}$ — a covering, if the images

Original source details: GELFAND-P000230

Undeciphered passage. [The crossed-out word is undeciphered.]

cover.

Axiom 1.

Original source details: GELFAND-P000230

Diagram and typed description.



U — a circle, U — also a circle, a map of degree 2 $U \to U$.

$$U \times_U U = U.$$

Original source details: GELFAND-P000230

Diagram and typed description.



$U_1 \times_X U_2$ —



Uncertain reading. перемн. и склеив. / пересеч. и склеив. (multipl. and gluing / intersect. and gluing); the first abbreviation is not uniquely established.

Original source details: GELFAND-P000230

— a disconnected union.

2 and 3 sheets $\Rightarrow$ 6 sheets

$$\mathbb{Z}_2 \times \mathbb{Z}_2 \neq \mathbb{Z}_4,$$
$$\mathbb{Z}_2 \times \mathbb{Z}_3 = \mathbb{Z}_6.$$

GELFAND-P000231

Presheaf: • a functor

$$\text{Cat}\, T \to \text{Ab} \qquad \text{(contravar.)}$$
$$u \to P(u)$$

$$v \to u \;\Rightarrow\; P(u) \to P(v)$$

A sheaf — a presheaf satisfying the axioms:

1. $\xi \in P(u)$

$\{u_i \to u\}$ — a covering

$$\xi \to \xi_i \qquad P(u) \to P(u_i)$$

ξ is uniquely determined by ξ_i

2. and is indeed determined, if ξ_i agree on intersections



Diagram and typed description.

$u_i \times_u u_j$

Original source details: GELFAND-P000231

Define Čech cohomology

$$C^0 = P(u)$$
$$C^1 = \prod P(u_i)$$
$$C^2 = \prod P(u_i \times_u u_j).$$
$$C^3 = \prod P(u_i \times_u u_j \times_u u_k)$$

d is defined naturally

$\mathcal{F} \to \Gamma(X, \mathcal{F})$ — a functor.

(Γ — an abelian group —
— a sheaf of groups)



Uncertain reading. Both lines of the parenthesis are retained. No separate symbol is visible before the dash in the second line; its implied subject is undetermined.

Original source details: GELFAND-P000231

$$0 \to \mathcal{F}_1 \to \mathcal{F}_2 \to \mathcal{F}_3 \to 0.$$

— an exact sequence of sheaves.

$$0 \to \Gamma(\mathcal{F}_1) \to \Gamma(\mathcal{F}_2) \to \Gamma(\mathcal{F}_3)$$

(left exact).

Derived functors exist. $R^i : S \to \text{Ab}$

S — arbit. sheaves (category).

$$\to R^1(\mathcal{F}_1) \to \ldots \to R^2(\mathcal{F}_2)$$

(R^i — determined uniquely).

$$R^i(\mathcal{F}) \underset{\text{def}}{=} H^i(X, \mathcal{F}).$$

Finite group. Grothendieck top. from representations.

Diagram and typed description. Separate icon on the source image.



Original source details: GELFAND-P000231

GELFAND-P000232

11/III Gelfand (and Kirillov)

$\mathfrak{g}$ — semisimple Lie algebra, (over C)

$U(\mathfrak{g})$ — its enveloping algebra

(polyn. in generators $e_1, \ldots, e_n$,

$$e_i e_k - e_k e_i = \sum C_{ik}^j e_j$$

$Z(\mathfrak{g})$ — centre of the enveloping algebra

(its elements — Laplace or Casimir operators).

Repr. of $G \Rightarrow$ diff. operators and commut.

$Z(\mathfrak{g})$ — commut. with the action of the



Uncertain reading. group

Original source details: GELFAND-P000232

Such a repr. of the enveloping alg. by diff. operators is not necessarily faithful.

On G itself — faithful (transform.)

For $Z(\mathfrak{g})$ it makes no difference, left or right.

$\mathfrak{g}$ — semisimple Lie algebra. (over C).

N_- — max nilpot.



Uncertain reading. [crossed out: group algebra] [inserted below the first word: group]

Original source details: GELFAND-P000232

(triang. matr.)

Uncertain reading. $N_- \backslash G$ [upper right symbol heavily overwritten]

Original source details: GELFAND-P000232

Theorem: in $N_-\backslash G$ the repr. of $U(\mathfrak{g})$ is faithful.



Uncertain reading. (simple).

Original source details: GELFAND-P000232

f on the group is regular if its translates — finite-dim. space

(sin on the line)

On a comp. group, functions are approx. by regular ones (completeness theorem)

Consider functions $f(g) \equiv f(n_- g)$ — invar. — ring.

Consider Spec of this ring. This is X.

$N_-\backslash G$ birat. equiv. to projective space.

Enveloping algebras are numerous, but division rings, of fractions are few

$$\underset{\substack{\text{division ring}\\ \text{of quotients}}}{D(\mathfrak{g})} \sim D_{n,k}$$

Nontriv. that embeds into a division ring (!) of quotients.

$$x_1, \dots, x_n; \quad \frac{\partial}{\partial x_1}, \dots, \frac{\partial}{\partial x_n}, \quad y_1, \dots, y_k$$



Uncertain reading. $\ell(x, \frac{\partial}{\partial x}, y)$

Original source details: GELFAND-P000232

$\underline{\underline{QP^{-1}}}$ $Q_1 P_1^{-1}$ and so on. Everything can be done in 2 steps.

(QP^{-1} suffices)

n — number of variables, k — number of parameters — invariants.

GELFAND-P000233

[source number: 23]

Diagram and typed description.

23

Original source details: GELFAND-P000233

For a semisimple group it is almost proved that $D(\mathfrak{g}) \sim D_{n,k}$.

(

Original source details: GELFAND-P000233

Uncertain reading. постр.

is valid)

For nilpotent proved, and probably for algebraic solvable.

Original source details: GELFAND-P000233

Diagram and typed description.

Adjoin to $Z(\mathfrak{g})$ (K) operators — virtual Laplace operators

New ring $\tilde{U}(\mathfrak{g})$ — with adjoined left translations



Original source details: GELFAND-P000233

Undeciphered passage. A short word or abbreviation is crossed out; its letters beneath the heavy strokes have not been established.

$$U(\mathfrak{g}) \otimes_{Z(\mathfrak{g})} \tilde{Z}(\mathfrak{g}) = \tilde{U}(\mathfrak{g}).$$

$\tilde{Z}$ — Z with adjoined virt. Laplace operators.

(this is an algebraic extens., Galois group — Weyl group).

Theorem. The division ring of fractions of $\tilde{U}(\mathfrak{g})$ is $D_{n,k}$.

(For U unknown; done for unimodular).

Alg. extens. of $D_{n,k}$ — ?.

In the commut. case, alg. varieties.



Original source details: GELFAND-P000233

Diagram and typed description.

Question. There are compact

compl. manif.

Describe regular differential operators

On the Riemann sphere $\frac{\partial}{\partial z}$, $z\frac{\partial}{\partial z}$, $z^2\frac{\partial}{\partial z}$

On Dixmier's work (Limanov).

$R_{1,0}$ — ring of quantum mech. — generators x, $\frac{d}{dx}$.

Original source details: GELFAND-P000233

Diagram and typed description.

Polynomials

in p and q.

$p, q, \quad [p, q] = 1.$

The autom. group is generated by triang. autom.



Original source details: GELFAND-P000233

Uncertain reading. $\begin{cases} p \to p \\ q \to q + f(p) \end{cases}$

and $\begin{cases} p \to p + g(q) \\ q \to q \end{cases}$

For the division ring $D_{1,0}$ unknown.

Or

Original source details: GELFAND-P000233

Uncertain reading. [crossed-out symbol: и? от?]

$\begin{cases} q \to q \\ p \to p + g(q) \end{cases}$

and $\begin{cases} q \to p \\ p \to -q \end{cases}$

(Fourier transform)

Is generated

GELFAND-P000234

Arnold: theor.

Let there be functions $f(p, q)$



Original source details: GELFAND-P000234

Uncertain reading. $[f_1(p,q), f_2(p,q)] = \frac{\partial f_1}{\partial p} \cdot \frac{\partial f_2}{\partial q} - \frac{\partial f_1}{\partial q} \cdot \frac{\partial f_2}{\partial p}$. [Index in the first factor after the minus: 1 or 2.]

Consider 2 polynomials

$$P = P(p, q)$$
$$Q = Q(p, q).$$

Substitute P and Q — will be 1.

They induce canon. transformations of quasiclassics.

But there is no connection, even with grading.

An element x is completely semisimple if the transformation ad X has a complete system of eigenvalues.

Then by an automorph. x is carried into $x \to pq$.



Original source details: GELFAND-P000234

Diagram and typed description.

$$\underbrace{x\frac{d}{dx}}_{\text{homog. polynomials.}} \quad \text{— eigenfunctions —}$$

$$p^a q^b \to (a-b)p^a q^b.$$

Result of

Original source details: GELFAND-P000234

Uncertain reading. Амицури or Амицура

:

x $C(x)$ — commuting — commut. subalgebra.
But these are not always polynomials.

$$\forall \alpha \; \exists X, Y, \qquad X^3 = Y^2 + \alpha, \qquad \alpha \in C.$$

Palamodov.
on Hörmander's work (on $\bar\partial$)
2 main results: existence theorem and approx. theorem.
1. $\Omega \subset C^n$, $\phi \in C^2(\Omega)$

$$L(\phi) = \frac{\partial^2 \phi}{\partial z_j \partial \bar z_k} \xi_j \bar\xi_k \geq 0$$

$$L_{p,q} = L_{p,q}(\Omega, \phi), \qquad \|f\|_\phi^2 = \int_\Omega |f|^2 e^{-\phi} dV$$

forms of type (p, q)
Let ϕ be plurisubh. in Ω



Original source details: GELFAND-P000234

Uncertain reading. [overlapping strokes before the parenthesis]

(therefore real) and
$\forall c \; \{\phi \leq c\}$ — compact. ($\Rightarrow \Omega$ — pseudoconvex)
Then $\forall f \in L_{p,q}$, $\bar\partial f = 0$
$\exists$

Original source details: GELFAND-P000234

Undeciphered passage. Crossed-out fragment; its initial symbol resembles g, the remaining letters have not been established.

g of type $p, q-1$

$$\bar\partial g = f \quad \overset{(q\geq 1)}{\text{and}} \quad g \in L_{p,q-1}(\Omega, \phi + 2\ln(1+|z|^2))$$

Here $\sqrt{q}\,\|g\| \leq \|f\|$ (assuming $q \geq 1$)

GELFAND-P000235

[source number: 24]

Diagram and typed description.

24



Original source details: GELFAND-P000235

2. Approx. theorem.

$\Omega = C^n$.



Original source details: GELFAND-P000235

Uncertain reading. The former second argument is crossed out: ϕ or ψ; $\phi + c\ln(1+|z|^2)$ is inserted below.

$f \in L_{0,0}(\Omega, [?])$ $\quad \bar{\partial} f = 0$ (holom. functions)

$\phi + c\ln(1+|z|^2)$

i.e. $|f| \le Ce^{\phi}(1+|z|^2)^k$, $(\exists C > 0)$.

This set is nonempty (nontriv. — $\Omega = C^n$). — and dense in the space of all [holom.] entire functions with unif. convergence on $\forall$ compact set:

ϕ — homog. along radii $\Rightarrow$ indicator of an entire function.

Hence Martino: the class of indicators — all radially homog. plurisubh. harm.

Original source details: GELFAND-P000235

Uncertain reading.

$$i(z) = \overline{\lim_{\tau\to\infty} \tau^{-k} \ln |f(z\tau)|}$$

The affiliation of the stroke above lim has not been established.

18/III

If $\phi = \phi(x)$ (only on the real parts), it is plurisubharm. if and only if it is convex.

In $\forall$ one-dim. complex space subharm.

Example:

$$\frac{\partial u}{\partial \bar{z}} = f, \qquad |f(z)| \le Ce^{a|\operatorname{Im} z|}(1+|z|^2)^k.$$

A solution in this class — nontrivial.
For bounded functions in the unit disk, the equation



Original source details: GELFAND-P000235

Uncertain reading. $\frac{\partial u}{\partial z} = f$ [denominator: z or $\bar{z}$]

is not necessarily solvable for bounded f.

For solvability it suffices
(f — measure)

Original source details: GELFAND-P000235

Uncertain reading.



The faint upper arc and dark strokes at the intersection are transcribed without an established meaning for the strokes.

S — disk. $|f(S\cap\Omega)| \le CR_S$.

Theorem 3. More precise theorem for fixed q.

Let $\partial\Omega \in C^3$ and the domain be bounded. Local condition on the boundary:

$\forall z \in \partial\Omega\ \exists \phi \in C^2$ such that $\Omega = \{\phi(z) < \phi(z_0)\}$ in a nbhd. of this point.

Condition a_q:

$$\sum \frac{\partial^2 \phi}{\partial z_j \partial \bar{z}_k} \xi_j \bar{\xi}_k \quad \text{on} \quad \sum \frac{\partial \phi}{\partial z_j} \xi_j = 0$$

has —

$$\begin{cases} q+1 \text{ negative} \\ \text{or } n-q \text{ positive} \end{cases} \quad \| \quad \text{eigen-values}$$

Gelfand: domains of regularity — ?

Palam. says nobody is working on this.

$\partial\Omega$ pseudoconvex if at $\forall$ point condition a_0 (at $\forall$ point $n-1$ positive eigenvalues)

In the tangent space, $n-q$-dim. surfaces along which the domain is pseudoconvex.

Let a_q hold at $\forall$ boundary point.

$$L_{p,q-1} \xrightarrow{\bar{\partial}} L_{p,q}(\Omega, \phi) \xrightarrow{\bar{\partial}} L_{p,q+1}$$

Cohomology



Uncertain reading. [crossed out below: kernel, ядро or ядра]

Original source details: GELFAND-P000235

is finite-dimensional and the image is closed.

Uncertain reading.



Isolated sign: E or $\exists$; its function has not been established.

Original source details: GELFAND-P000235

Existence of a function Ψ on the whole domain.

Ψ — real, defined inside Ω,



Uncertain reading. $\frac{\partial^2 \Psi}{\partial z_i \partial \bar{z}_k} \eta_j \bar{\eta}_k$ [first denominator index: i or j]

Original source details: GELFAND-P000235

satisfies all conditions

(1 more plus required, since in the whole space)

Then cohomology 0.

GELFAND-P000236

All these theorems for complex spaces — Andreotti and Grauert.

1. Runge-type theorem.

$\omega \subset \Omega$, $L(\Psi)$ at $\forall$ point of $\Omega \setminus \omega$ satisfies the condition

$$\begin{matrix} q+1 & - \\ \text{or} & \\ n-q+1 & + \end{matrix}$$

$\Psi \to \infty$ near $\partial\Omega$, $\{\Psi < 0\} = \omega$

Then the cohomology of Ω restricts monomorphically to the cohom. of ω.

A closed form f in Ω and the equation $\bar\partial u = f$ solvable in $\omega \Rightarrow$ it is solvable in Ω as well.

2. Approximation theorem.

Closed forms in ω are approximated by closed forms in Ω.

Existence theorem.

Let $\partial\Omega \in C^2$ and there exist ρ, $\{\rho < 0\} = \Omega$,



Original source details: GELFAND-P000236

Diagram and typed description.



It is proved simply, using the identity.

$$L_{p,q-1} \xrightarrow{\bar\partial=T} L_{p,q} \xrightarrow{\bar\partial=S} L_{p,q+1}$$

$$\|T^* f\|_\phi^2 + \|Sf\|_\phi^2 =$$

$$(u,v)_\phi = \int_\Omega u\bar v e^{-\phi} dV.$$

(adjoint with respect to this inner product)

$$= \sum_L \sum_{j,k} \left(\frac{\partial^2 \phi}{\partial z_j \partial \bar z_k} f_{jL}, f_{kL} \right)_\phi + \sum_J \sum_k \left\| \frac{\partial f_J}{\partial \bar z_k} \right\|_\phi^2 +$$

Take $p = 0$ (for simplicity — expansion in



Uncertain reading. dz [first symbol heavily overwritten; reading not established]

Original source details: GELFAND-P000236

).

$$f = \sum f_J d\bar z^J, \qquad J = j_1, \ldots, j_q.$$

f_J skew-symm. in the indices, jL — long index.

$$+ \sum \sum \int_{\partial\Omega} \frac{\partial^2 \rho}{\partial z_j \partial \bar z_k} f_{jL} \overline{f_{kL}} e^{-\phi} dS.$$

The identity — integration by parts.
First — Morri with $\phi = 0$.
grad, rot — known in mechanics.
Solvability follows from it.
Next time — Nirenberg (according to hearsay).

Chapter 4

GELFAND-P000237

Uncertain reading. [At the upper right: 1 / *l*.]

Original source details: GELFAND-P000237

Seminar of Gelfand. 1968-69.

1. Mumford. Moduli spaces. (Geronimus Sasha)

Uncertain reading. 2. [Cancelled: Kr.]

Original source details: GELFAND-P000237

Kirillov. Characters. (lectures)

3. Kazhdan Dwork ?

4. Griffiths Mixture of diff. eqs., geom., top., complex analysis

5. Spencer resolution. (Palamodov)

6. **Gromov**

7. Buslaev on eigenvalues (incl. Maslov's work)

8. Grauert and Remmert, p-adic analysis.

(old idea of L. G. Shnirelman about the Cauchy $\int$ and the like over an arbitrary field)

9. Nilson

10. Vershik on factors $\overline{\text{II}}$ and $\overline{\text{III}}$

Uncertain reading. or Sinai (and K^0 / K°)

Original source details: GELFAND-P000237

11. Hörmander work on Lie groups and diff. eqs. (hypoell.).

Idea of **Dwork** (Kazhdan)

If some series converges near 0 in a complex variable and at every p-adic one, then it is a rational function.

idea: represent the ζ-function using ([Above the line: in] p-adic variables) completely continuous operators.

[Wavy underlining: On Gromov:] 2 extreme cases which are unified.

Bundle techniques are transferred to foliations (sometimes). For foliations of dimension 1 — the question of a vector field.

[Wavy underlining on two lines:] A foliation of codim. ≥ 1 always exists if a family of planes exists (!)

The sheaf of germs and jets — a weak homotopy equiv.

(If there is a set of coeff. glob., then one can construct a function)



Original source details: GELFAND-P000237

Uncertain reading. Psych. experiment in an Eng. / Am. coll.

Tests ⇒ teachers secretly told about the giftedness of 20% of the pupils, selected by lot ⇒ after a year they are 1.5 times better than avg.! (not by marks, but by tests)

GELFAND-P000238

Geronimus on Mumford.

[Wavy underlining: Object of study] — compact Riem. surfaces.

$g = 0$ — all isomorphic (sphere).

$g = 1$ — complex elliptic curves.



Original source details: GELFAND-P000238

Diagram and typed description.

X — surface of genus 1.

$$\begin{array}{c} \overline{X} \\ \downarrow \\ X \end{array}$$

— universal cover. It is the plane (analytically)

$Z + Z$ acts without fixed points

$$z \to z + b \qquad (b_1, b_2)$$

When do we obtain different surfaces?



Original source details: GELFAND-P000238

Uncertain reading.

$$\begin{array}{ccc} \text{—} & lz+m & \text{—} \\ X & \longrightarrow & X' \\ \downarrow & & \\ X & \sim & X' \end{array}$$

[The attachment of the rules above the upper letters is not established.]



Original source details: GELFAND-P000238

Uncertain reading.

$$\begin{cases} b_1 = lb'_1, \\ b_2 = lb'_i. \end{cases}$$

[Final index in the second line: i / 2.]

One can assume ($b_i \neq 0$) that $b_1 = 1$.

$(1, z_2)$ an automorphism of $Z + Z$ also changes nothing.

$$(1, z) \qquad \operatorname{Im} z > 0$$

$$\mathrm{SL}(2, Z) = \Gamma$$



Original source details: GELFAND-P000238

Uncertain reading.

$$z_2 = \frac{dz_1 + b}{cz_1 + b} \qquad \begin{pmatrix} a & b \\ c & d \end{pmatrix} \in \Gamma$$

[First numerator coefficient: d / a; last denominator coefficient: b / d.]



Original source details: GELFAND-P000238

Diagram and typed description.

Thus, the quotient of the upper half-plane H by



of the unimodular group Γ

$$H \longrightarrow H/\Gamma = \Pi$$

On H there is a fund. domain



Original source details: GELFAND-P000238

Diagram and typed description.



this is a fund. domain

The plane — the analytic manifold of all elliptic curves.

General def. 1

There is a collection of analytic manifolds K.



Diagram and typed description.

Moduli space — an analytic manifold with a map

$$\begin{array}{c} X \\ \downarrow p \\ \underline{Y} \end{array}$$

Original source details: GELFAND-P000238

($X, \underline{Y}$ — manifolds and an analytic map). Points of $\underline{Y}$ in one-to-one corresp. with K ///

and, in addition, $p^{-1}(y) \cong$ the corresponding object of K

(objects of K cannot be analytically isom.)

GELFAND-P000239

[source number: 2]

$\underline{Y} = K$ with the structure of an analytic manifold

If the moduli space exists, it is unique up to analytic isom. (easy to prove).

Another def. takes account of possible automorphisms of objects of K.

Prelim. notion.



Original source details: GELFAND-P000239

Diagram and typed description.

Anal. Family of objects of K:

$$\begin{array}{c} X \\ \downarrow \\ Y \end{array}$$

all fibers isom. to objects of K

Induced family — analogous to an induced bundle (it always exists)



Original source details: GELFAND-P000239

Diagram and typed description.

$$\begin{array}{ccccc} X'' & \longrightarrow & X' & \longrightarrow & X \\ & \searrow & \downarrow & & \downarrow \\ & & Y' & \longrightarrow & Y \end{array}$$

This is a commut. diagram + univers.

Universality

Original source details: GELFAND-P000239

Diagram and typed description.

$$\begin{array}{ccc} & X' & \\ (& \downarrow & \text{univers.}) \\ & Y' & \end{array}$$

Diagram and typed description.



Original source details: GELFAND-P000239

A merely commut. diagram is insufficient (2 points and any one where a map $\exists$).



Diagram and typed description.

$$\begin{array}{ccc} Y' \times X & \longrightarrow & X \\ \downarrow & & \downarrow \\ Y' & \longrightarrow & \bullet \end{array}$$

Original source details: GELFAND-P000239

[Wavy underlining: Kirillov] (conjecture)

Representable functor. The representing object is the family of moduli

2 categ. — 1) all analytic spaces.



Uncertain reading. functor into the [Cancelled: 2) / 2] category of sets

Original source details: GELFAND-P000239



Diagram and typed description.

$Y \rightsquigarrow$ set of pairs

$$\begin{array}{c} X \\ \downarrow \\ \underline{Y} \end{array}$$

Original source details: GELFAND-P000239

— analytic families.

Repr. of the functor

$$C \xrightarrow{F} \text{Ens} \quad (\text{sets})$$

$$F_M = \text{Hom}(\bullet, M) \qquad M \text{ — analytic space.}$$



Original source details: GELFAND-P000239

Diagram and typed description.



— the family is called a moduli manifold if $\forall$ other family is obtained as an induced one.

GELFAND-P000240

A universal family for curves of a given genus does not exist (even for elliptic ones)

Exists for polarized ones (with a chosen homology basis)

Modification — final object of the category of families

If it does not exist, adjoin it formally.

An additional structure is introduced, allowing cohom. with coeff. in a sheaf to be considered, and so on.

There is no universal object for elliptic curves

Diagram and typed description.



Original source details: GELFAND-P000240

all points map unambiguously $\Rightarrow$ as a set — elliptic curves do not repeat.

Suppose there is a nontrivial family (base not a point) with identical fibers. [Above “fibers”: (bundle).]



Original source details: GELFAND-P000240

Undeciphered passage. [Cancelled fragment to the right of “fibers”: reading not established.]

(because there are automorphisms)



Original source details: GELFAND-P000240

Uncertain reading. Then the map must be into a point and one obtains triv. / nontriv.

Exists in a weaker sense — the plane

Original source details: GELFAND-P000240

Uncertain reading.



[Upper right mark: M? The lower mark is cancelled; its reading is not established.]

Most have one autom. ($x \to -x$) (with a marked point), and some have additional rotations.

Thus, the work consists in studying the properties of a nonexistent universal object.

Start precisely $6^{\underline{15}}$

GELFAND-P000241

[source number: 3]

$9/\underline{\overline{\text{IX}}}$. **Continuation of the talk by Geronimus.**

Nonexistence of the moduli space is overcome by fixing a homology basis (a more rigid object). This is not considered.

For elliptic curves only a point is fixed (and even that not immediately).

A way (a different one) to overcome this difficulty will be indicated.

Def. of a Grothendieck topology.



Diagram and typed description.

Fiber product over S — product in the categ.



Original source details: GELFAND-P000241

The axioms of a Grothendieck topology are obvious except: [Cancelled: $X_i \times Y$]

$$\left.\begin{array}{c} X_i \longrightarrow X \text{ — cover} \\ Y \longrightarrow X \end{array}\right\} \Rightarrow \begin{array}{c} X_i \times_X Y \longrightarrow X \\ \text{cover} \end{array}$$

A morphism of Grothendieck topologies —

— a functor $T_1 \to T_2$ preserving all structures.

Example 1. T_Γ — Γ-sets (Γ — a group).

Fiber products exist — pairs.



Original source details: GELFAND-P000241

Diagram and typed description.



(in $X \times Y$ take pairs (x, y) such that $p_1(x) = p_2(y)$).

$X_i \xrightarrow{f} X$ — a covering if $\bigcup f_i(X_i) = X$.



Uncertain reading. Final object [dense loop-shaped strokes; their purpose is not established] — a point.

Original source details: GELFAND-P000241

Cohomology of a point with coeff. in various sheaves. $H^q(\cdot, F)$

(F — an arbitrary sheaf)

[Cancelled: On]

All sheaves are constructed as follows.

If the value $F(\Gamma) = A$ is specified (Γ acts on Γ on the left), then on all the others it is uniquely determined by the group A. (if this really is a sheaf and not a presheaf).

$\Gamma \longrightarrow \Gamma/H$ a covering.

Apply the sheaf property to the covering of the open set Γ/H. We obtain

$$F(\Gamma/H) = A^H$$

(элем. A, инвар. отн. M)

Uncertain reading. (elements of A invariant under M / H)

Original source details: GELFAND-P000241

(Γ acts on A, because maps of sets induce maps of sections by the definition of a presheaf).

GELFAND-P000242

For an arbitrary Γ-set that is a union of disjoint orbits, one must consider the embeddings of all orbits, and there will be a direct sum.

Thus, everything is uniquely determined by the Γ-module A.

Here

$$H^q(\cdot, F) = H^q(\Gamma, A).$$

(another def. of $H^q(\Gamma, A)$).

A fact about group cohom.

$$H^2(\Gamma, Z) = \{\text{all complex one-dimensional representations of } \Gamma\}$$

Example 2. Topology C

Пример 2. Тополоия C откры analyt

Kateг. analyt. mn-зий и их отобр

мные

мj

бр. друг в друга.

Original source details: GELFAND-P000242

Diagram and typed description.



The categ. of analytic manifolds and their maps to one another.

Original source details: GELFAND-P000242

Undeciphered passage. The cancelled fragment to the left of “analytic” inside the enclosing stroke could not be deciphered.

There is a fiber product.

Coverings (!) X — an analytic manifold

$X_i \xrightarrow{f_i} X$ — a covering if

1) $\bigcup f_i(X_i) = X$

2) each f_i — an unramified covering of X_i over an open set of X

(f_i^{-1} a discrete set of points).



Original source details: GELFAND-P000242

Diagram and typed description.

$$X \quad \times \quad Y$$
$$\searrow \quad \swarrow$$
$$Z$$

— the collection of pairs projecting to the same point of Z

(an analytic structure is introduced on it)



Original source details: GELFAND-P000242

Diagram and typed description.

sheaf

↓ F

let F be given on this entire topology

$$H^q(X, F) = H^q(X, \widetilde{F})$$

$\widetilde{F}$ — a sheaf on the usual topology (restriction)

(ordinary cohomology)

(over a sufficiently small open set all coverings split).

GELFAND-P000243

[source number: 4]

Example 3. (the main one) Given K.



Original source details: GELFAND-P000243

Diagram and typed description.

$$\begin{array}{c} X \\ \downarrow \\ S \end{array}$$

— analytic families of objects of K (manifolds)

A map — induction,

Original source details: GELFAND-P000243

Uncertain reading. [A short word is cancelled: all / this / for; the reading is not established.]



Original source details: GELFAND-P000243

Diagram and typed description.

with an open map of bases

Fiber products exist



Original source details: GELFAND-P000243

Diagram and typed description.



One must take



and induce a family over it (from S_2 and S_1 one obtains the same thing)



Original source details: GELFAND-P000243

Diagram and typed description.

A covering



if the images cover all of S and each map —
— a covering (in the sense of Ex.2).

$H^q(\pi, F)$ equiv. to the preceding example $\cong$ cohom. of S in the preceding example.

(since the structures of open sets are the same and the topologies are isomorphic).



Original source details: GELFAND-P000243

Uncertain reading.

112

— a vertical sign between the two cohomology lines; the exact meaning of its form is not established.

$H^q(S, \widetilde{F})$ — ordinary cohomology.

If there is a terminal object.

Suppose there is no terminal object.

Example 4.

T_M — categ. — the old one + a formally adjoined terminal object M.

Its cohomology is computed as if it existed.

A fiber product exists.

$$\pi \times_M M = \pi$$

(M maps only to M)

The fiber product $X \times_M Y$ remains

In any category $\boldsymbol{X} \times_{\boldsymbol{M}} \boldsymbol{Y}$ — the direct product.

(a tautological fact).



Original source details: GELFAND-P000243

Uncertain reading. (it may also be empty [a sign resembling ξ, possibly cancelled])

— there is an empty family

GELFAND-P000244



Original source details: GELFAND-P000244

Uncertain reading. Existence of a direct product — a difficult [cancelled: category / construction?; inserted above the word: theorem] for the category of families.



Original source details: GELFAND-P000244

and one cannot take $S_1 \times S_2$ as the base.

Diagram and typed description.

$$\begin{array}{ccc} S_1 \times S_2 & \longrightarrow & S_2 \\ \downarrow & & \\ S_1 & & \end{array}$$

over $S_1 \times S_2$ different families are induced



Original source details: GELFAND-P000244

If $X_1 = X_2$ then the product — itself.
If $X_1 \neq X_2$, then empty.

Diagram and typed description.



Original source details: GELFAND-P000244

Uncertain reading. [Cancelled: But?]

If a point, then as a rule empty.
If close to universal, then usually nonempty.



Original source details: GELFAND-P000244

Diagram and typed description.



The base — a submanifold in S, with fibers isom. to Y.



Uncertain reading. if there are autom., then [cancelled: there is?] multiplicity etc.

Original source details: GELFAND-P000244

Set-theoretically — the base — points in S with fibers Y, multiplicity — the number of automorphisms.

This — an analytic manifold! (a difficult theorem)

(the number of ways of mapping Y into this family)

Def. of a covering of M:



Original source details: GELFAND-P000244

Diagram and typed description.

$\pi_i \longrightarrow M$ — a cover if $\pi \longrightarrow M$



Original source details: GELFAND-P000244

Diagram and typed description.

for any other

$\pi_i \times \pi \longrightarrow \pi$ — a genuine covering.

(one axiom is ensured by this def., the others — automatically)

All π_i — not a covering!



Uncertain reading. [Cancelled: But / To us?]

Original source details: GELFAND-P000244

Next time, continuation and or the Spencer resolvent or Dwork.

Diagram and typed description. Annotation icon in the lower margin.

[In the lower margin — a yellow annotation icon with three horizontal strokes.]

Original source details: GELFAND-P000244

GELFAND-P000245

[source number: 5]

16/IX Geronimus.



Undeciphered passage. (it is necessary that there exist [a cancelled word cannot be read beneath dense strokes] fiber products)

Original source details: GELFAND-P000245

Apologies: everywhere, not analytic manifolds, but analytic spaces.

Fiber product.



Original source details: GELFAND-P000245

Diagram and typed description.



and universally, i.e. if



Original source details: GELFAND-P000245

Diagram and typed description.



, then



Covering axioms

1) $X_{ij} \longrightarrow X_i \longrightarrow X$



Uncertain reading. 2) $X \xrightarrow{e\,/\,\varepsilon} X$ [the reading of the arrow label is not established.]

Original source details: GELFAND-P000245

3) $X_i \times_X Y \longrightarrow Y$

Presheaf: a contravariant functor F to the categ. of groups.

Sheaf.

$U_i \longrightarrow U$ — a covering

$g_i \in F(U_i)$



Original source details: GELFAND-P000245

Diagram and typed description.

$$U_i \longleftarrow U_i \times_U U_j \qquad g_i \in F(U_i) \longrightarrow F(U_i \times_U U_j)$$

$$U_j \longleftarrow U_i \times_U U_j \qquad g_j \in F(U_j) \nearrow$$

Compatible if the g_i map to the same element.

$$U_i \longrightarrow U \qquad F(U) \longrightarrow \underset{g_i}{F(U_i)}$$

Uncertain reading. [Cancelled: def. / exists / this?]

Original source details: GELFAND-P000245

a sheaf: if $g \in F(U)$ exists and is unique, mapping to the g_i.



Original source details: GELFAND-P000245

Uncertain reading.

$T^o \xrightarrow{F}$ Ab F — a sheaf.

categ. with reversed arrows. abel. groups

The first sign is written over an earlier form; T^o / T^0 / calligraphic T^0.

GELFAND-P000246

Cohomology — these are groups

Uncertain reading. $H^q(U,F)$ / $H^\nu(U,F)$,

Original source details: GELFAND-P000246

such that $H^0(U,F) = F(U)$. and if

$$0 \longrightarrow F' \longrightarrow F \longrightarrow F'' \longrightarrow 0, \quad \text{then}$$

(there is a procedure allowing one to construct a sheaf canonically from any presheaf — for any topology),

$$\longrightarrow H^q(U,F') \longrightarrow H^q(U,F) \longrightarrow H^q(U,F'') \longrightarrow H^{q+1}(U,F') \longrightarrow \dots$$

(they exist).

And for any injective sheaf cohom. 0

(and there are sufficiently many inj. sheaves)

Suppose there is a map compatible with all structures (a map of topologies)



Original source details: GELFAND-P000246

Diagram and typed description.

$$f: \quad T_1 \longrightarrow T_2$$

f^*F def. F

$$f^*F(U) = F(f(U)).$$

$$H^q(U, f^*F) \longrightarrow H^q(f(U), F).$$

$U \longrightarrow H^i(f(U), F)$ a presheaf and the constructed sheaf is zero,
then this map gives a canonical isom. (formal? criterion)

$$H^q(U, f^*F) \cong H^q(f(U), F).$$

Original source details: GELFAND-P000246

Uncertain reading. Abbreviation in parentheses before “criterion”: formal?



Original source details: GELFAND-P000246

Diagram and typed description.

Main example T. objects — analytic families

$$\begin{array}{c} X \\ \downarrow \\ S \end{array}$$

(X, S — analytic spaces)

It is necessary that

New category T_M with M. (a terminal object)

Existence of fiber products.

(topol. moduli spaces)



Uncertain reading. π_i — a covering [cancelled sign: φ / o?] of M if the properties hold

Original source details: GELFAND-P000246

1) each K occurs as a fiber in one of the families π_i

2) each K occurs only a discrete number of times

GELFAND-P000247

[source number: 6]

3) Extension axiom. $\forall X$.



Diagram and typed description.

Each Π_i satisfies the cond.

$$\begin{array}{cc} & X \\ \pi_i & \downarrow \\ & S \end{array}$$

Original source details: GELFAND-P000247



Diagram and typed description.



$$\begin{array}{cc} X' & X \\ \downarrow & \downarrow \\ S' & S \end{array}$$

Original source details: GELFAND-P000247

and a subfamily (base — a submanifold and [cancelled:

Uncertain reading. т.д. / т.е.; reading not established

Original source details: GELFAND-P000247

] induced restr.)
and ∀ map of the subfamily
∃ its extension (local)-
— to a tubular neighborhood S''.



Uncertain reading.



Original source details: GELFAND-P000247

The horizontal arrow $S' \to S$ is repeatedly crossed over; its final state is not established. The lower curved sign is reproduced by its shape, without an established meaning.

Next time — example with ellipt. curves.



GELFAND-P000248

Palamodov.
Spencer resolution.
Working on this
Sweeny

Uncertain reading. Holdschmidt / Heldschmidt / Goldschmidt

Original source details: GELFAND-P000248

Guillemin

Quillen
Sternberg
Singer

> presented by Sweeny in Acta math.

A method for solving the system $p(x, D)u = w$, where p is a matrix, u, w are vectors.



Original source details: GELFAND-P000248

Diagram and typed description.

M — a smooth manifold. $\mathcal{O}$ — the sheaf of germs of diff. fns.

$$\mathcal{O} \xrightarrow{j_\mu} J_\mu$$

jets of ord. μ

(jets)

(j_μ is even an embedding)

J_μ — vect. bundle (or the sheaf of its germs)



Original source details: GELFAND-P000248

Uncertain reading.

$$\mathcal{O} \xrightarrow{j_\mu} J_\mu \quad .$$

Retraced $\mathcal{O}$ / $\mathcal{O}$ with an upper sign; overlapping strokes not deciphered.

The Spencer resolution of the sheaf $\mathcal{O}$ begins with j_μ and continues so that the seq. of sheaves is exact.

$$0 \longrightarrow \mathcal{O} \xrightarrow{j_\mu} J_\mu \longrightarrow$$



Original source details: GELFAND-P000248

Uncertain reading. $\mu = 0$ — map to 0 / $\mathcal{O}$; final sign not established.

A collection is given (I. M. G.'s project)

$$\varphi_i \qquad i \text{ — multi-index}, \qquad |i| \le \mu.$$



Original source details: GELFAND-P000248

Diagram and typed description.

$$j_1 \qquad \varphi_0(x) = f(x)$$

$$f \longrightarrow \varphi_1(x) = \frac{\partial f}{\partial x_1} \qquad \varphi_i = \frac{\partial \varphi_0}{\partial x_i} \qquad \frac{\partial \varphi_0}{\partial x_i} - \varphi_i$$

$$\varphi_2(x)$$

$$\vdots$$

to a sp., isom. to the J's of 1st order

Cf.



Uncertain reading. псевдогр. / псевдооп. (pseudo-gr. / pseudo-op.)

Original source details: GELFAND-P000248

one order higher.



Original source details: GELFAND-P000248

Uncertain reading.

$$f \longrightarrow \{D^i f\}$$

Above the first f are short strokes; their meaning is not established.

GELFAND-P000249

[source number: 7]

notation $1_j = (0, \dots, \underset{j}{1}, \dots, 0)$

cf. φ_i with φ_{i+1_j}.

Need to

Uncertain reading. chk. (прв. / пров.)

Original source details: GELFAND-P000249

that

$$\frac{\partial \varphi_i}{\partial x_j} = \varphi_{i+1_j}, \qquad \underset{|i| \le \mu - 1}{\forall i}, \qquad j = 1, \dots, n.$$

Map to

Uncertain reading. Cancelled:

J / j; the beginning of the next word is also corrected.

Original source details: GELFAND-P000249

jets of order lower by 1.

$$\{\varphi_i\} \longrightarrow \left\{ \frac{\partial}{\partial x_j} \varphi_i - \varphi_{i+1_j} \right\}$$

$$|i| \le \mu - 1, \qquad j = 1, 2, \dots, n.$$

$$\sum \left(\frac{\partial}{\partial x_j} \varphi_i - \varphi_{i+1_j} \right) dx_j \qquad \text{(added).}$$



Original source details: GELFAND-P000249

Diagram and typed description.

$$(\mathcal{O}) \rightarrowtail J_\mu \xrightarrow{D} T^* \otimes_{\mathcal{O}} J_{\mu-1} \xrightarrow{D = d - \delta} \Lambda^2 T^* \otimes_{\mathcal{O}} J_{\mu-2}$$

cotang.

$$\left(\frac{\partial}{\partial x_j} \varphi_i - \varphi_{i+1_j} \right) = (d - \delta)\{\varphi_i\}$$

(difference of the operators of actual and formal diff.)

On $T^* \otimes J_{\mu-1}$ both ops. are also def.

d — exterior diff. in the 1st coord.

δ — formal diff.

$$\{\varphi_i^j(x)dx_j\} \overset{D=d-\delta}{\longrightarrow} d(\varphi_i^j(x)dx_j) - \varphi_{i+1_s}^j\, dx_j \wedge dx_s$$



Uncertain reading. In the second coefficient the lower index is corrected: $i+1_s$ / $i+1_j$; the final reading is not established.

Original source details: GELFAND-P000249

and so on.

The resolution will terminate (and it is exact)

Next time Geronimus, Palamodov and Kazhdan

GELFAND-P000250

$23/\overline{\text{IX}}$

Geronimus.



Diagram and typed description.

K — sp. of all tori with a compl. structure, and with a marked point. Let us construct Grothendieck's top. Category: families

$$\begin{array}{ccc} & & X \\ \pi & & \downarrow \\ & & S \end{array}$$

with a distinguished section $\sigma\colon S \to X$ (analyt. map)

Original source details: GELFAND-P000250



Original source details: GELFAND-P000250

Uncertain reading.



The precise right boundary and joins of the short vertical lines are not established.

set of all lattices S'

(moduli sp. in the coarse sense of the word)

(coarse)

Grothendieck top. — mod. sp. in the fine (fine) sense of the word.

Quotient H/Γ — H — upper half-plane

There is a family with base S', but this is not a fine moduli sp.

(does not induce nontriv. bundles with const. fiber)



Original source details: GELFAND-P000250

Diagram and typed description.

Another reason.

$$\begin{array}{c} H \\ \downarrow \\ H/\Gamma \end{array}$$

The family over H is not induced from a family over H/Γ.

(Under the action on H there are fixed points (3 of them)
there is branching there



Original source details: GELFAND-P000250

Uncertain reading.



Dense retracing at the node and stroke ends; arrowheads are not established.

and different struct. of the ellipt. curve are obtained)
Family over H $\quad H \times \mathbb{C} \quad z \in H \quad (z, 1)$ —
— a lattice.



Original source details: GELFAND-P000250

Diagram and typed description.



Problem: this family,

GELFAND-P000251

[source number: 8]

and there the group acts

$$z' = \frac{az+b}{cz+d}$$
$$\zeta' = \zeta(cz+d)^{-1}$$

Uncertain reading. Cancelled in the upper right margin: там (there) / так (so).

Original source details: GELFAND-P000251

Calculation of cohomology in this case.

The topology and everything else were defined earlier.

Uncertain reading. A separate word is cancelled:



Cohom. (?) / undeciphered word.

Original source details: GELFAND-P000251

~~$H^n(\pi, Z)$ — this is a sheaf~~

$$F(\pi) = \underbrace{Z + Z + Z}_{\text{by the number of conn. comp.}}$$

(so to speak, a const. sheaf).

It is easy to see that $H^n(\pi, Z) = H^n(S, Z)$

(π — ordinary) (Topological).

Cohom. of the final object.

1) T_Γ — another top.; Γ — a group of matrices with det 1.

2) T'_Γ — those Γ-sets where Γ does not act too triv.

(if the stabilizer of $\forall$ point — integral matr. with



Uncertain reading. The cancelled word has not been deciphered.

Original source details: GELFAND-P000251

1 mod 3.

$$\sigma x = x \to \sigma \in \Gamma_3.)$$

Map $T'_\Gamma \to T$

$$S \to (H \times S)/\Gamma \qquad (S \text{ — a discr. set}).$$

$$M' \to M.$$

It induces an isomorphism of cohomology.

(which is checked using the criterion stated last time).

Hence



Uncertain reading.

$$H^n(M, Z) = H^n(\Gamma, Z) = \begin{cases} 0 & n \neq 2 \\ Z_{12} & n = 2 \end{cases}$$

The sign in the second condition is heavily retraced: $n = 2$ / $n \equiv 2$; reading not established.

Original source details: GELFAND-P000251

(but if Γ acted without fixed points, would coincide with the cohom. of the ordinary moduli sp.).

The answer is valid over any field (Char $\neq 2$).

Families have an invar.

mod 12.

GELFAND-P000252

Shafarevich: an example of Grothendieck top.

A syst. of diff. eqns. (ordinary) is given on

Uncertain reading. мн-зии / мн-гии



Original source details: GELFAND-P000252

U — transv. patch

Map



Original source details: GELFAND-P000252

Uncertain reading.



The directions of all parts and exact joins are not established; the left-hand thickenings are retained by their shape.

$U \to V$

if from points of U

draw [cancelled:

Uncertain reading. по (along?) / undeciphered word

Original source details: GELFAND-P000252

] traject. into V

there is a fiber product



Original source details: GELFAND-P000252

Uncertain reading.



Three contours, paired links and internal strokes; labels and presence of arrowheads are not established.

If a fibration, then the cohom. of the base and the syst. are triv.

(then there is a final object).

On the plane diff. eqn. and const. sheaf of Groth. top.,

of numbers

then its Euler char. — the difference

Uncertain reading. прд. / пред.

Original source details: GELFAND-P000252

cycles and sing. points.
Next time Kazhdan. and Palamodov.

GELFAND-P000253

[source number: 9]

30/IX. Kazhdan.
Work of Ihara. (Jap.). (Ihara, Journ. Math. Soc. of J.



Undeciphered passage. Then two small strokes:11 / II; the subsequent bibliographic elements under dense cancellation cannot be read.

Original source details: GELFAND-P000253

107-121)
One-dimensional surf. over C are connected with discr. groups.
An attempt to transfer this to curves over finite fields.
$X = \Gamma\backslash M$ M — Lobach. pl.
Γ describes both X and unramif. coverings.
(The

Uncertain reading. congruence / conguence

Original source details: GELFAND-P000253

monodromy problem).
In [

Uncertain reading. Cancelled sign: C / k; reading not established.

Original source details: GELFAND-P000253

] $k[X, Y]$ consider the principal ideal (f)
$A = k[x, y]/(f)$ — ring of fns. on the curve, max. ideals — geom. points of the curve
A map $Y \longrightarrow X$ is a map of rings $A \longrightarrow B$

$$B \longleftarrow A$$

An unramif. map — unramif. at $\forall$ point.
$m \subset A$ Consider the image and B/mB
max. ideal.
if it does not contain nilpot. elems., then it is unramified at m.

There will be no seminar next Monday.

The time after next there will be...

GELFAND-P000254

$14/\overline{\text{X}}$ Palamodov.

X — manifold
O — sheaf of germs of diff. fns.



Original source details: GELFAND-P000254

Diagram and typed description.

$O \rightarrowtail J^k$
— sheaf of jets of order k.

presheaf $\{\varphi_i, \quad i = (i_1, \ldots, i_n), \quad |i| \leq k\}$ transition — as for derivatives.

Gelfand. Def.

Let k, m be integers.

Def. of (m, k)-jets.



Original source details: GELFAND-P000254

Uncertain reading. First letter of the pair overwritten: (m, k) / (n, k).

X — diff. manifold.
Consider fns. of the $(m+1)$-st variable.

Original source details: GELFAND-P000254

Uncertain reading. Retraced letter before $+1$: m / n.

(ordinary — $(1, k)$-jets).

$(1, k)$-jets.

$\varphi(x, y)$ — fns. on the square $X \times X$

Consider the diagonal $x = y$

Consider the collection of fns. $= 0$ on the diagonal

This is an ideal.



Original source details: GELFAND-P000254

Uncertain reading. After two vertical strokes: $m \neq 1$ and $(m+1)$ above; the final indices in the three lines look like $n+1, n+1, m+1$. The letter readings n / m are not fully established.

$m \neq 1$ $\overbrace{X \times \cdots \times X}^{(m+1) \text{ times}}$
diag. $x_1 = x_2 = \cdots = x_{n+1}$
$\mathcal{J}$ — ideal.
$\varphi(x_1, \ldots, x_{n+1}) = 0$ if
$x_1 = x_2 = \cdots = x_{m+1}$



Uncertain reading. Repeated symbol for the ideal: $\mathcal{J}$ / $\mathcal{I}$.

Original source details: GELFAND-P000254

Consider $\underline{\underline{\mathcal{J}^{k+1}}}$ (fns. of k-th order of smallness on the diag.)

We regard $\varphi_1 \sim \varphi_2$ if $\varphi_1 - \varphi_2 \in \mathcal{J}^{k+1}$

Diagram and typed description. Unlabelled square, thick rising diagonal and two dark lower corners; central protrusion: point / small arrowhead.



Original source details: GELFAND-P000254

$\varphi(x,y)$ — [

Original source details: GELFAND-P000254

]
$(1,0)$-jet. — fn. on the diagonal.

Original source details: GELFAND-P000254

$(1,1)$ — jet

Original source details: GELFAND-P000254

on the diag. with 1-st derivatives.

$$\varphi(x,y) = \varphi(x,x) + \left.\frac{\partial \varphi(x,y)}{\partial x}\right|_{y=x} (y-x)$$
$$\varphi(x,y) = \varphi(y,y) + \left.\frac{\partial \varphi(x,y)}{\partial y}\right|_{y=x} (x-y)$$



Original source details: GELFAND-P000254

There are 2 ways to define jets

$$a(x) + b(x)(y-x)$$
$$a(y) + b(y)(x-y)$$

These are different ways.

GELFAND-P000255

[source number: 10]

One can differentiate — this gives a jet of lower order.

$$\varphi(x_1,\dots,x_{n+1}) = \varphi(x,\dots,x) + \sum \left.\frac{\partial\varphi}{\partial x_i}\right|_{\dots}$$



Uncertain reading. Small dots or strokes are visible at the lower end of the bar; the entry ends here.

Original source details: GELFAND-P000255

$(1,m)$-jet — scalar fn. + diff. form

Palamodov.

The case of general m reduces to $m=1$.

$$\varphi(x,y) \sim \sum_{|i|\le m} \varphi_i(x)\frac{\xi^i}{i!}$$

$$O_Y \longrightarrow O_{X\times Y}/\mathcal{J}^{k+1}$$



Uncertain reading. Sign in the denominator: $\mathcal{J}^{k+1}$ / $\mathcal{I}^{k+1}$.

Original source details: GELFAND-P000255



Original source details: GELFAND-P000255

Diagram and typed description.

$$0 \longrightarrow O_X \xrightarrow{j} J^k \xrightarrow{d_x} T^*\otimes J^{k-1} \xrightarrow{d_x} \Lambda^2 T^*\otimes J^{k-2} \longrightarrow \dots$$

Spencer resol. (triv. case)

In the gen. case — O_X is replaced by the sheaf of germs of solns. of an arbitrary lin. syst. of eqns.

Sweeny

Acta Math., 120 $N = 3-4$.

and development by Malgrang

Quillen — a large article in proceedings...

Next time: Palamodov again.

10

GELFAND-P000256

[source number: 17]

27/X. Prof. Weinstein (USA).

on operators.

4/

Uncertain reading. XI / X

Original source details: GELFAND-P000256

Kirillov — Traces of operators !!

11/XI — skipped.

18/XI Kazhdan ζ-fns. following Dwork

25/XI ——— || ——— || ——— || ———

Kirillov.

$\mathcal{A}$ — operator.

M — comp. manifold, $\mathcal{L}_2(M, H)$ H — Hilbert.

μ — measure on it

(or a Hermitian bundle)

$$\mathcal{K}f(x) = \int_M K(x,y)f(y)\,d\mu(y)$$

(K — operator fn., $K(x,y)\colon H \longrightarrow H$)

jointly cont. in the weak oper. topology.

Existence of the trace

Necessary, and for $\overset{\text{oper.}}{>0}$ sufficient existence.

$$\underbrace{\operatorname{tr}\mathcal{K} = \int_M \operatorname{tr} K(x,x)\,d\mu(x) \qquad (\text{tr in the usual sense}).}$$

Scalar fns.: see Gohberg and Krein (Carleman theorem)

Nontriv.: if $\mathcal{K}$ has a trace, then $\operatorname{tr} K(x,x)$ exists almost everywhere.

Weinstein.

A — self-adj. oper. with discr. spectrum.

$$\mathbf{A}+\mathbf{B} \qquad \min R(u) \qquad R(u) = \frac{(Au,u)}{(u,u)}$$

The Euler eqn. gives $Au = \lambda u = 0$



Original source details: GELFAND-P000256

Uncertain reading. Heavily retraced sign: $Au = \lambda u = 0$ / $Au - \lambda u = 0$.

$u \perp \mathcal{R}$ infinite-dim.



Original source details: GELFAND-P000256

Uncertain reading. Overwritten letter: $\mathcal{R}$ / $\mathcal{P}$.

$$\mathcal{P} = \bigcup \mathcal{P}_n$$

$\min\limits_{u \perp \mathcal{P}_n} R(u)$ soln. exists: $\det \ldots = 0$

17

GELFAND-P000257

$$\min_{u \perp \mathcal{P}} \frac{(Au, u)}{(u, u)}$$



Uncertain reading. Retraced letter below the minimum: Φ / P / $\mathcal{P}$.

Original source details: GELFAND-P000257

exists for the oper. of Schrödinger

(not only completely cont.).

In general. classical theory — estimates of eigenvals., from one side.

Weinstein and Co. — from the other side.

Someone from Poland. Rolevich.

Periodic solns. of diff. eqns. with delay.

Reduces to solving a syst. of ordinary eqns. with periodic coeffs.



Original source details: GELFAND-P000257

Uncertain reading. The word below "periodic" at the double bracket: случ. / случая / случай [case]; ending not established.

periodic

A few more applications, etc.

Appl. to control problems.

Next will be Kirillov.

4/XI Kirillov.

G — simply conn. Lie group

T — irred. representation

$$T(\varphi) = \int_G \varphi(g) T(g)\, dg \quad \text{— operator}$$

tr as a generalized fn. sometimes exists.

$$\operatorname{tr} T(\varphi) = \int_G \varphi(g)\chi(g)\, dg$$

$\chi(g)$ — generalized fn.

In the examples it is no more complicated than a measure, but there is no general Theorem.

There are examples with no trace for any φ and even narrower than C_0^∞.

$$\begin{pmatrix} a & b \\ 0 & 1 \end{pmatrix}$$

for it one must narrow C_0^∞ to fns. with

$$\int \varphi(a,b)\, db \underset{a}{\equiv} 0$$

(over a conjugacy class of elems. — 0)

GELFAND-P000258

[source number: 18]

$\mathfrak{g}$ — Lie alg. (real) $\quad \mathfrak{g}^*$ — dual sp. (real).

G acts in $\mathfrak{g}$ and $\mathfrak{g}^*$.

$\chi(g)$ resembles another generalized fn.

$\mathfrak{g}^* \supset \Omega$, $\quad \Omega$ — orbit of G.

Ω — symplectic sp. (there is a nondegen. 2-form there).



Diagram and typed description.



Original source details: GELFAND-P000258

$B(\xi, \eta)$ $F \in \Omega$

functional on $\mathfrak{g}$.



Original source details: GELFAND-P000258

Diagram and typed description.





Diagram and typed description.



Original source details: GELFAND-P000258

One must take

$$\frac{1}{2\pi}\langle F, [X, Y]\rangle = B(\xi, \eta)$$

skew-symm.
nondegen.
form

(well-defined — independent of the choice [two symbols cancelled:



Uncertain reading. ξ, η / X, Y; neither cancelled symbol has an established reading.

Original source details: GELFAND-P000258

] representatives mod $\mathcal{H}$)

Inhomog. form.

$$\beta = e^B = 1 + B + \frac{B \wedge B}{2!} + \cdots + \frac{B \wedge \cdots \wedge B}{k!}$$

(it terminates).

In fact, only one term is needed for integr.

Thus, a measure is defined on each orbit.

generalized fns. $\begin{cases} \mathcal{J}_\Omega(x) = \int_\Omega e^{i\langle F, X\rangle} \beta(F) & \text{(Fourier transform of the measure on the orbit)} \\ \chi(\exp X) \end{cases}$



Uncertain reading. The left argument looks like x, while the exponent and $\chi(\exp X)$ have X; letter case is not fully established. The brace and complete right-hand explanation are retained.



Original source details: GELFAND-P000258

---

resemble one another.

the hypothesis that they coincide is false. But:

GELFAND-P000259

Their ratio $\in C^\infty$ and one can write a formula.

$\forall$ irred. repr.

$$\chi(\exp X) = p_\Omega^{-1}(x) \int_\Omega e^{i\langle F, X\rangle} \beta(F),$$



Original source details: GELFAND-P000259

Diagram and typed description.

where

$p_\Omega(x) =$

- 1 — for nilpot. groups
- $\underbrace{\sqrt{\rho(x)}}_{\text{inv. measure (if there is one)}}$ — for orbits in general position (for all groups)
- ~~for~~
- $\sqrt[4]{\rho_\ell(x)\rho_n(x)}$ — (if there is no inv. measure)



Original source details: GELFAND-P000259



Original source details: GELFAND-P000259

Uncertain reading. Symbol under the square root: $\rho(x)$ / $g(x)$; the lower arc leads to “inv. measure (if there is one)”.

Uncertain reading. Under the fourth root: $\rho_\ell(x)\rho_n(x)$ / $g_\ell(x)g_n(x)$ / $\rho_\Pi(x)\rho_\Pi(x)$ / $g_\Pi(x)g_\Pi(x)$; the indices remain unresolved. “For” is cancelled at the right.



Original source details: GELFAND-P000259

Diagram and typed description.

$p_\Omega(0) = 1$

smooth (proved)



Original source details: GELFAND-P000259

Uncertain reading. The arrow rises from beside “Nilpot. gr.” through the “comp.” line towards “always”; its reference to the formula or the orbit remark is not established.

(orbits do not always correspond to representations)

For an arbitrary comp. group all orbits are in general position.

Nilpot. gr.

Reduction theorems



Original source details: GELFAND-P000259

Uncertain reading. Provisional reading of the retraced word: theorems (теоремы); initial strokes remain undeciphered.

$$\operatorname{sth} x = \frac{\operatorname{sh} \frac{x}{2}}{x/2}$$



Original source details: GELFAND-P000259

Uncertain reading. Left notation: $\operatorname{sth} x$ / $\overline{\operatorname{sh}} x$ / $\operatorname{s}\bar{h} x$; the cross-stroke is not established as a separate t or bar.

$$p_\Omega(x) = \prod_\alpha \operatorname{sth}\langle \alpha, X\rangle \qquad \text{(conjecture)}$$

(where α — roots)



Original source details: GELFAND-P000259

Uncertain reading. Repeated notation: $\operatorname{sth}\langle \alpha, X\rangle$ / $\overline{\operatorname{sh}}\langle \alpha, X\rangle$ / $\operatorname{s}\bar{h}\langle \alpha, X\rangle$; the reading remains unresolved.

Unit. irred. reprs. of all Lie groups.

in $\mathfrak{g}^*$, orbits Ω.

Choose those for which $B \in H^2(\Omega, \mathbb{Z})$

($\int$ over $\forall$ cycle — an integer)

An integral orbit corresponds to a repr. [cancelled:



Original source details: GELFAND-P000259

]

Undeciphered passage. Short cancelled passage not deciphered; the historical candidate “по числу” [by the number] is not asserted. The number of words beneath the strokes is undetermined.

in a number

equal to the number of characters of the fund. group of the orbit.

(the fund. gr. is commutative in this case).

GELFAND-P000260

[source number: 19]

~~On~~ For $SU(2)$ (almost $SO(3)$)

2 form on the sphere $\frac{1}{2\pi}\frac{d\sigma}{r}$.

Integrality: $\boxed{2r = n}$ — such spheres.

$\int \ldots = \frac{\sin rx}{x}$. Obtain the usual characters.



Original source details: GELFAND-P000260

Uncertain reading. In all three formulas: r / τ; the repeated handwritten sign remains unresolved.

Universal Plancherel formula for all groups.

$$\int_G |f(g)|^2\, dg = \int \mathrm{tr}[T(f)T^*(f)]\, d\mu(T)$$

$$T(f) = \int_G f(g)T(g)\, dg$$

(T ranges over all [cont. / irred.] unit. reprs. up to equiv.)



Original source details: GELFAND-P000260

Uncertain reading. Abbreviation “непр.”: continuous / irreducible; its expansion remains unresolved. Complete parenthesis.

Abstr. theorem — true, the question is the calculation of the measure $d\mu$.

Problem. For a skew-symm. matrix, extract a polynomial sq. root from its det.



Original source details: GELFAND-P000260

Diagram and typed description.

(example $\det \begin{pmatrix} 0 & a \\ -a & 0 \end{pmatrix} = -a^2$).

One nontriv. duality:



Original source details: GELFAND-P000260

Diagram and typed description.

1) Product of matrices which $\overset{\text{(unit.)}}{> 0}$.
Find distrib. of eigenvalues
from distrib. of eigenvalues of factors.

2) the same for tensor
product of reprs. of the unit. group.

Perelomov and Popov —
— on a convex region.

$[(x^2-1)^n]^{(n)}$ — Legendre

$[(x-1)^{m_1}(x+1)^{m_2}]^{(m_3)}$ — Jacobi polynomials

m_3 — fractional — hypergeom. function

(or $x(x-1)$)

19

GELFAND-P000261

18/XI.

Original source details: GELFAND-P000261

Undeciphered passage. Heavily cancelled inscription to the right of the date not deciphered; two strokes below it.

Lit. on representation theory.

Minimum (0th level)

1. Kirillov lectures „Elem. theory of reprs. “, I, II

2. Gelfand, Minlos, Shapiro „Reprs. of the rotation group “

3. Zhelobenko, Lectures on theory of reprs.

4. Jacob Schwartz „Lie alg. and Lie groups “ (Engl)

5. Serre — "_____

6. Vinberg „Compact Lie groups “.

7. Sophus Lie Seminar „Reprs. of Lie algs.* reprs. of Lie groups “

and

1. general theorems on fin. and comp. grs.

2. detailed analysis for rotation gr. and matrices of 2nd order — illustr. and concr. for 1

3. useful for physicists

4. general theory of Lie groups and class. comp. and semisimple Groups

6. ... comp. groups and Lie algebras (Schwartz, but shorter)

7. modern exposition of theory of semisimple groups

1st level.

1. Gelfand, Naimark ~~Reprs.~~ „Unit. reprs. of class. groups “

(Acad. Sci. 1950)

(do not read the chapter on the Plancherel theorem,

read the introd. and article of Gelfand and Graev in Trans. Math. Soc. vol. 4.

(Plancherel theorem).

2. Godement Matem. 5:5

Simple proof of the Harish-Chandra theorem on existence of char.

Also there, description of fin.-dim. reprs.

3 Berezin Trans. + letter to ed.

vol. 6 vol. 12

[Cancelled: Given / For.] Description of reprs. of a semisimple group through the Laplace oper.

Existence of all reprs. proved.



Original source details: GELFAND-P000261

Uncertain reading. Cancelled word: Дан / Для [Given / For]; final joined strokes undeciphered. Both following lines in full.

4. Kirillov Reprs. of a nilpot. group.



Original source details: GELFAND-P000261

Uncertain reading. Circled number: 7 /4. Curve from the circle points upward at the left margin; precise attachment unresolved. Below the circle, “(in the 0th)”.



(in the 0th)

Mackey Addendum to Segal’s book (induc. reprs.)



Original source details: GELFAND-P000261

Uncertain reading. Abbreviation: индуц. / индук. [induc.]; last consonant crossed or overwritten.

5. $SL(2,C)$, ~~SL_2~~,



Original source details: GELFAND-P000261

Uncertain reading. Cancelled notation: SL_2 / $SL(2)$; position of 2 and parentheses unresolved.

(5th issue of generalized functions, Naimark, Unitary repr. of the Lorentz gr.)

GELFAND-P000262

[source number: 20]

$SL(2,R)$ (5th issue of generalized functions)

$SL(2,Q_p)$ (6th issue of gen. functions) ~~or Gelfand’s article)~~
to the next level.
1st level: no final theorems, except Berezin’s work + Harish-
-Chandra

6. J. Schwartz, C^*-algebras *; Naimark, UMN
(book)

2nd level.

1. $SL(2,Q_p)$. Gen. functions 6.
2. Karpelevich, Gindikin (Izv. AN) ~~Method~~ Plancher. theorem
for symm. spaces.
3. Method of horospheres $\rightarrow$ 1st level
(Gelfand, Graev — Trans. MMO, vol. 8
Serre
4. Exposition by ~~Harish-Chandra~~ ~~o~~ of **Borel-Weil!** work in

— Bourbaki sem. (exp 100 or 101)



Original source details: GELFAND-P000262

Uncertain reading. Separate cancelled sign: o / undeciphered sign. “Harish-Chandra” cancelled; “Serre” inserted above.

5. Exposition of Harish-Chandra at the Bourbaki sem. (Bruhat, ~~a~~ Cartier, Dixmier) —

— transl. in the journal „Matematika “, 6:5



Original source details: GELFAND-P000262

Uncertain reading. After “Bruhat”, separate altered sign: a / undeciphered sign. Complete names parenthesis and line with 6:5.

6. Groups and algs. of type 1, Glimm, Ferr, etc. —

— in Dixmier’s book „C^*-algebras and their reprs. “

7. Lie algebras and enveloping algebras.

Original source details: GELFAND-P000262

Uncertain reading. Heavily altered number before the heading: 7 /8. Wavy heading underline.

7. Enveloping algebras:

а) Sophus Lie; ch. I.

б) Harish-Chandra from 5)

в) Gelf., Kirillov; Fr. work and journal FA, vol. 3, issue 1

(Publ. Math.)

~~в)~~



Original source details: GELFAND-P000262

Uncertain reading. Separate cancelled label before г): в) /8. / undeciphered number.

г) Kostant, Amer. Journ., 85, pp. 327–404

д) Zhelobenko „Enveloping algs. “

е) Nelson „Anal. vectors “ (there is a transl. in the journal Matem.)

6:3

GELFAND-P000263

8. Kirillov and Kostent



Original source details: GELFAND-P000263

Uncertain reading. Surname: Kostant / Kostent; retraced ending and vowel unresolved.

Gen. theory of reprs. and characters.

(talk at Gelfand's sem.



Original source details: GELFAND-P000263

Uncertain reading. Dense mark to the left of "Gen." undeciphered; separate annotation or cancelled sign. No missing words established. Following parenthesis open.

9. Harish-Chandra — work of the latest series. (from. 1963 yr.)

10. Kazhdan — func. analysis and Fr. translation at the Bourbaki sem.

vol. I, issue 1.

(Kirillov's talk)

11. G/Γ — extensive lit. (conference Boulder)

Sommer Sicol

Proceed. — translation in preparation.



Original source details: GELFAND-P000263

Uncertain reading. Lower Latin note: Sommer Scool / Sommer Sicol / Sommer Sicool. Second word unresolved; no distinct h.

12. Other fields. Extensive lit.,

13. Other questions. — // —



Original source details: GELFAND-P000263

Uncertain reading. Altered number: 13 /14. Ditto sign at right consists of two slanting strokes between horizontal strokes.

13. List of questions.

Everything will be in „Uspekhi "

Gromov.

1. Invar. def. of diff. oper.



Original source details: GELFAND-P000263

Diagram and typed description.

M — manifold

fibre not necessarily a linear space

$\mathcal{L}$ — bundle

$\Gamma(\mathcal{L})$ — sections.

X — bundle space

Jets — equiv. class of sects. coinciding up to derivatives.

$\mathcal{L}^r$ — jet extension.

X^r — its space

Partial diff. equation —

— subset $A \subset \boldsymbol{X}^r$.

In appl. — a submanifold (not necessarily closed),

linear equation — a subbundle.

(add. to X of vect. spaces)

$$\mathcal{L}^r = \{M, X^r, \mathcal{F}^r, \rho^r\}$$



Uncertain reading. Last symbol of the quadruple: ρ^r / p^r; superscript r retained, the letter unresolved.

Original source details: GELFAND-P000263

Submanifold A in class. theory is usually closed.

But the equation $Lu \neq 0$ — an open set

$L(u) = 0$ — closed (if the func. does not satisfy, then

GELFAND-P000264

[source number: 21]

Or example.

$$f : \underset{g_1}{M_1} \longrightarrow \underset{g_2}{M_2} \qquad \text{with quad. forms.}$$

smooth map, inducing forms $f^*(g_2) = g_1$.



Diagram and typed description.



Original source details: GELFAND-P000264

map $M_1 \to M_2 \Leftrightarrow$ section

add an open cond. — so that it is an embedding.

General formulation:

solution exists or not.

$$d^r : \Gamma(\mathcal{L}) \longrightarrow \Gamma(\mathcal{L}^r)$$

(sect. has a jet at a point).

Solution:

$$\gamma \in \Gamma(\mathcal{L}), \quad \text{if} \quad \operatorname{Im}\gamma \subset A$$

(at any point)



Uncertain reading. Repeated letter: γ / δ. The line has membership in Γ(L) and Im of the same letter; no visible d^r before the second letter.

Original source details: GELFAND-P000264

1. Problem of existence.

Connection with others

2. Uniqueness. never occurs (almost never)
open sets

But one can speak of well-posedness.

3. Well-posedness.

A family A_N of diff. equations (A_N varies)



Uncertain reading. Right-hand index on A: N / n / α. First left-hand A_N read separately; the overwritten right-hand index unresolved.

Original source details: GELFAND-P000264

$$\Gamma(\mathcal{L}) \times N \longrightarrow N$$

Well-posedness — this is a Serre fibration!!!

of a family of problems.

(for ~~every~~



Original source details: GELFAND-P000264

Undeciphered passage. Following cancelled continuation unreadable; only elements resembling N and “и” are distinguishable. Complete words and number of hidden signs unknown.

every Γ, family N fixed)



Original source details: GELFAND-P000264

Uncertain reading. After Γ, a separate cancelled looped sign is undeciphered; lower stroke and following comma visible in the complete fragment.



Original source details: GELFAND-P000264

Diagram and typed description.

(one may, e.g., deform

with a finite number of param.)

Example:

M_1, M_2 a pair of forms defines an eq.
g_1 g_2

All pairs of forms — N,

Idea: as a rule, one assumes that locally everything is known,

and what is global — unknown.

Local part: Nash's implicit-function theorems.

in ex.

21

GELFAND-P000265

Stab. Corr. allows solving eqs.

Theorem C^1-Nash.

problem of C^1-imm. is posed correctly:

with a deform. of the metric one can deform the immersion.

With some metric an imm. exists — top. properties,

then deform it into any — obtain an emb. !!

Whitney–Smale princ. of contin. deformation. ⟹



Original source details: GELFAND-P000265

Uncertain reading. Abbreviation in the heading: “продолж.” / “продолже.” The upper of the two underlines has a right-hand point.



Original source details: GELFAND-P000265

Diagram and typed description.

Sol. over $U \subset M$,  deform the solution over a part

extend to the whole region

(if the boundary effect is ignored)

They proved it in a number of cases.

~~From corr. and this princ. one can~~

Microscopic realizability of these principles —

— this is the implicit-function theorem.

(contin. only at the 1st instant).



Original source details: GELFAND-P000265

Diagram and typed description.

Often:

Micro ⟹ Macro ↘

Narrowing the class of eqs.

If **[?]** a sol. after the action of diffeom. of some group remains
a solution, then Stability.



Original source details: GELFAND-P000265

Uncertain reading. Separate overwritten or cancelled sign before “реш.” undeciphered. The p of the following word is distinguishable at its right.

(invar. under the action
of the group of all diff., which acts there in X —
— if this is given)
example — tang. bundle.
(maps the eq. to itself)
~~Plateau prob.~~

Example: Plateau prob.

$$R^2 \longrightarrow R^3$$ minim. films invar. under diffeom.

Then (in the stable case) micro $\Rightarrow$ macro.
Another principle.

(Theorem ^{2}.)

a) M parall.
noncomp. conn.



Original source details: GELFAND-P000265

Uncertain reading. Abbreviation: “паралл.” / “парал.” Lower line: “noncomp. conn.”

в) A — submanifold
(subbundle)
and fibres nonempty.



Original source details: GELFAND-P000265

Uncertain reading. The letter before A has two loops: “в)” / “b)”. The order of the conditions does not determine its alphabet.

$\Rightarrow$

13-04 from 16-18 Tue.; sem. Arnold

GELFAND-P000266

[source number: 22]

c) there is Micro

d) there is stability

Then the eq. has a solution.

It contains Smale's immersion theory and so on.

Noncomp.: micro ⇒ macro.



Original source details: GELFAND-P000266

Diagram and typed description.

noncomp. ⇒

⇒ there is a fn. without

max

Example of a geom. character

M^n — Riemannian

$M^n \subset R^s$ loc. in $s = \frac{n(n+1)}{2}$

comp. of metr. tensor

one cannot, generally speaking, fit into a lower one.

~~But, [?]~~



Original source details: GELFAND-P000266

Undeciphered passage. After "But," the cancelled continuation is unreadable; looped and horizontal strokes are visible.

But: if $f_1, f_2 : M \to R^{?s}$.



Original source details: GELFAND-P000266

Uncertain reading. Obscured sign before superscript s: R^s with a cancelled preceding sign / R^{2s} / $R^{\lambda s}$. Its final shape is undetermined.

$0 < \lambda < 1$



Original source details: GELFAND-P000266

Undeciphered passage. Cancelled formula at the right; lower loop resembles g_0. Left-hand part and relation sign are unreadable.



Original source details: GELFAND-P000266

Diagram and typed description.



parametriz. (stable).

they are C^0-approxim. by maps φ_1, φ_2, such that the induced metrics are equal.

(Essentially there is no unique determination)
In large dim. $t \geq s$

$$t = ? + An$$



Uncertain reading. Sign after the equality resembles 3 or handwritten s: $t = 3 + An$ / $t = s + An$. The formula is doubly underlined.

Original source details: GELFAND-P000266

$$M \to R$$



Uncertain reading. No exponent discernible on R. Written: $M \to R$.

Original source details: GELFAND-P000266

any map is approxim. by a similar one



Undeciphered passage. Below “similar”, a cancelled word in a narrow outline is unreadable; the candidate “isometric” is unestablished.



Original source details: GELFAND-P000266





Uncertain reading. Separate overwritten sign: f / t. Order of the superimposed strokes undetermined.

Original source details: GELFAND-P000266

(with induced metric λg)
All this follows from theorem 2.

Next time: Gromov

GELFAND-P000267

25/XI

~~[?]~~

Uncertain reading. Dense cancelled sign at the right of the date is unreadable.

Original source details: GELFAND-P000267

Oleinik Radkevich's results on eqs.

$$Pu \equiv a^{ij} u_{x_i x_j} + b^i u_{x_i} + cu = 0.$$



Uncertain reading. Last index in $b^i u_{x_i}$ is overwritten: i / j.

Original source details: GELFAND-P000267

hypoell. — ?

Hörmander:

$$\sum_{i=1}^{n} X_i^2 u + X_0 u + cu = f$$

if at $\forall$ point there are n lin. indep. commutators, then hypoell., which is obtained from the est.:

$$\|u\|_\varepsilon \le C\big[\|u\|_0 + \|Pu\|_0\big]$$

~~+ weak norm[?]~~



Uncertain reading. Cancelled continuation: + weak norm (Russian "норм" / "норма"). Ending of the last word undetermined.

Original source details: GELFAND-P000267

$\boxed{\varepsilon > 0}$ (necessity not proved)

General case: without resorting to the concrete form



Original source details: GELFAND-P000267

Diagram and typed description.

for the estimate

cond. necessary

Radkevich:

$$Lu = a^{ij} u_{x_i x_j} + \delta u$$

$$P^0 = a^{ij} u_{ij}, \qquad P^{(j)} = a^{ij}(x) D_i,$$



Original source details: GELFAND-P000267

Diagram and typed description.

$P_{(j)}$ $\mathcal{E}_{-1}$

smooth. ellipt.



Original source details: GELFAND-P000267

Diagram and typed description.

Operators these and all commutators.

The condition is the same
($2n$ first-order oper.)

$$P_{(j)} = \sum_{i,k} \frac{\partial a_{ik}}{\partial x_j} \frac{\partial^2}{\partial x_i \partial x_k} (\mathcal{E}_{(-1)})$$

Rank n — one can select an elliptic system.
First order — the same
without pseudodiff. oper.

$$P^{(j)} \quad \text{and} \quad P_{(j)}$$

everywhere we keep the principal parts
It is necessary to be able to obtain an ellipt. system.
There is as yet no formulation incl. Hörmander's theorem.

GELFAND-P000268

[source number: 25]

25

Gelfand: for applications it is important to know: when is every solution a summable function?

Kazhdan

Work of Dwork: rat. of ζ-func. of $\forall$ alg. varieties over a fin. field.

k — a field.

$A = k[x_1, \dots, x_n]/\mathfrak{J}$ — an aff. scheme



Uncertain reading. Ideal sign: $\mathfrak{J}$ / $\mathfrak{a}$ / J; reading undetermined.

Original source details: GELFAND-P000268

Points — closed points (max ideals)

Hilbert's thm.:

$$K = A/I \quad \text{— a fin. ext. of } k.$$

Prime ideals — points. $K \supset k$.

Geom. point with values in K: a homomorphism $A \to K$.

(a max ideal corresp. to it)

$$A = \frac{R[x]}{x^2 + 1}$$

2 geom. points, although 1 scheme point

i and $-i$

Alg. variety — if there are no nilpot. elements

(this is the difference from a scheme)

[?]

Uncertain reading. At the left before F_{p^n} is a separate densely cancelled unreadable sign.

Original source details: GELFAND-P000268

F_{p^n} — a fin. field, ext. of Z_p by the eq.



Original source details: GELFAND-P000268

Uncertain reading. Height relation of p and $n-1$, and role of the heavy stroke, undetermined. Possible readings: $\frac{x^{p^{n-1}}-1}{x^p-1}=0$ / $\frac{x^{p^n-1}-1}{x^p-1}=0$; heavy stroke may be an underline or a raised minus. Glyph arrangement retained here.

$$f(x)=\frac{x^{p^{n-1}}-1}{x^p-1}=0.$$

Original source details: GELFAND-P000268

Diagram and typed description.

K

$\uparrow$

k

The autom. group of K is cyclic and has a canon. gen. — the Frobenius autom.

$$\sigma:\ x\to x^p.$$

$k=Z_p$.

[illegible].

Original source details: GELFAND-P000268

Uncertain reading. Interlinear mark above the following line: 3. / §.; reading and role undetermined.

A — an alg. variety. ζ-func. of it — ?

Consider a closed point of A — $x=I\subset A$

A/I — a finite field — an ext. of some degree.

Degree — degree of the closed point.

GELFAND-P000269

$$\zeta(t,A)=\prod_{x\in X}\frac{1}{1-t^{\deg x}}$$

(t — a formal variable)

Theorem. (Dwork)



Original source details: GELFAND-P000269

Diagram and typed description.

affine

∀ alg. variety — this is a rat. func. of t

(was Weil's conjecture, proved earlier for curves).

There are usually infinitely many points.

If A — the ring



Original source details: GELFAND-P000269

Diagram and typed description.

all

polynom. over Z_p, then

$Z_p[x]$

$$\zeta(t) = \frac{1}{1-pt}$$

(expansion inf. and all — poles at 1)



Original source details: GELFAND-P000269

Uncertain reading. "poles at 1" is clearly legible; the scope of the words is undetermined.

Degree 1 — exactly p points (x — Z_p).

Degree 2 — in (p^2-p) elem.

(so as not to fall among those counted

$\exists 1$ nontriv. autom.

$$\frac{1}{(1-t)^p} \quad \frac{1}{(1-t^2)^{\frac{p^2-p}{2}}} \quad \frac{1}{(1-t^3)^{\frac{p^3-p}{3}}} \quad \dots$$

$$(1-t^4)^{\frac{p^4-p^2}{4}}$$



Original source details: GELFAND-P000269

Uncertain reading. Separate entry $(1-t^4)^{(p^4-p^2)/4}$: corrected digits 4, and a cancelled unreadable sign after p^2. Possible cancelled reading: p? Earlier digits not recovered. No reciprocal fraction.

Uniqueness — ?

Idea

Degree chosen by the last chance to equate coeff. at the last.



Original source details: GELFAND-P000269

Uncertain reading. Russian “по посл. шансу” / “по посл. шагу” (“by the last chance” / “at the last step”): word after the abbreviation remains uncertain.

Hence $\forall$ can be expanded.

GELFAND-P000270

[source number: 26]

$$\zeta(t, A) = \sum c_k t^k \qquad c_k \text{ — integers} \qquad \text{(obv.)}.$$

The equality holds.

$$\zeta(t, A) = \exp\left(\sum N_e t^e / e\right),$$

where N_e — the number of geom. points with values in a field with deg $= e$.
(number of homom. from A to F_{p^e}).
This is a general equality.
But [?] it does not immediately follow from it that c_k — integers

Original source details: GELFAND-P000270

Uncertain reading. Cancelled word after “But”: possibly “immediately” (Russian “сразу”); reading undetermined.

Compute for $Z_p[x]$. $\quad N_e = p^e$.

$$\sum (pt)^e / e = -\ln(1 - pt) \qquad \text{and the rest is clear.}$$

Apply at $A = Z$. The usual ζ-func. results.

[? . . . ?]



Original source details: GELFAND-P000270

Undeciphered passage. Cancelled line not fully read. Possibly Russian “Идея ... Дворк” / “... Дворк” (“Idea ... Dwork” / “... Dwork”); content beneath the hatching undetermined.

Idea of proof. The series $\zeta(t, A)$ in a compl. variable — conv. in a disc.
Consider it in a p-adic variable. It will also conv. for a small norm.
Merom. p-adic (ratio of holom. p-adic) $\Longrightarrow$
$\Longrightarrow$ autom. rational (general theorem) —
— a simple theorem

$$\mathbb{Z}_p \text{ — ring} = \{x \in Q_p;\ |x| \le 1\}$$
$$M_p = \{x \in Q_p :\ |x| < 1\} \quad \text{— max. ideal}$$

$$\mathbb{Z}_p/M_p = Z_p \quad \text{— a field of } p \text{ elem.}$$

$$x_n \in Q_p. \qquad \sum_{\text{conv.}} x_n \iff x_n \to 0.$$

Banach sp. — the usual def. carries over.
Completely cont. oper.

GELFAND-P000271

Thm. In a Ban. sp. a compl. cont. oper. is nuclear,

~~[?]~~



Uncertain reading. Cancelled after “nuclear,”: Russian “то” / “по…” (“then” / “po…”); reading undetermined.

Original source details: GELFAND-P000271

and therefore there exists $\det(1 - tA)$
— an entire p-adic func. of a p-adic variable t.
Alg. extensions of Q_p.
~~Closure~~
Ω — alg. completion of the alg. closure of Q_p



Diagram and typed description.

$Z_\Omega/M_\Omega = F$ — field

max ideal

Original source details: GELFAND-P000271

Teichmüller representatives exist.
Every elem. $f \in F$ has a canon. representative in Z_Ω.

$F^* \longrightarrow Z_\Omega^*$ there is a canon. homomorphism.

Structure of analytic funcs. on the field of p-adic numbers.

$$f(t) = \sum c_k t^k, \qquad c_k \in \Omega.$$

Entire analytic, i.e. c_k sufficiently rapidly $\to 0$.

Then in $\forall$ disc ~~[?]~~ of finite radius there are finitely many zeros.



Uncertain reading. “disc” is inserted above a cancelled word and outlined with a lower point. Initial word undetermined.

Original source details: GELFAND-P000271

(Unit disc in the field Q_p is not compact)



Original source details: GELFAND-P000271

Uncertain reading. The source has Q_p and "not compact"; intended field notation and meaning of "disc" here undetermined.

(Shnirelman)

Proof: the max principle, Schwarz lemma ⇒ finitely many zeros.

$$f(z) = \frac{\prod(1-\alpha_i z)}{\prod(1-\beta_j z)} = 1 + \sum c_k z^k$$

c_k — integers

α_i, β_j — alg. $\Longrightarrow$ they are alg. integers.



Original source details: GELFAND-P000271

Diagram and typed description.

rat. func.

If not integers, a contradiction with the norms is obtained

$|\ |<1$ (on the left) on the right $=1$

(This is an example)

str[?] after $6/\overline{\text{II}}$

next mtg. on the 1st Mon. of next sem.)



Original source details: GELFAND-P000271

Uncertain reading. Above "Mon.": Russian "строго" / "стр." before "after 6/II"; full word or abbreviation undetermined.

10/II – 1969 **yr.**

Margulis. Integer points in a disc on the Lobachevsky plane.

Int. points — preimages on the univers. covering.



Original source details: GELFAND-P000272

Diagram and typed description.

Obtain area +

length of

term, proport. to boundary

of the same order

Remainder of order $\sqrt{\text{of the 1st terms}}$

Complete ergodicity of the horospherical flow is used.

There are works of Linnik: how many points on a sphere.

What will there be?

1. Kazhdan. 2. Margulis. 3. Kirillov.

Gelfand:

3-adic numbers (for schoolchildren)

$$121 \qquad 101$$

Inf. number of digits to the left, rather than to the right.

The rules and top. are introduced analogously.

Ordinary numbers are worse because of the identification of



Original source details: GELFAND-P000272

Diagram and typed description.

$0{,}999\ldots$ and 1 disconnected becomes connected



Original source details: GELFAND-P000272

Diagram and typed description.

$$\ldots 2222 = -1$$

$$\begin{array}{r} \ldots 2222 \\ \ldots 0001 \\ \hline \ldots 0000 \end{array}$$

$\frac{1}{2}$ — ?

$$\begin{array}{r} \times \quad \times \quad \times \quad \times \quad \times \quad \times \\ \hline 2 \\ \hline 0 \quad 0 \quad 0 \ldots 0 \quad 1 \end{array}$$

infinite (clear)

$$\begin{array}{r} \ldots 11112 \\ 2 \\ \hline 1 \end{array}$$

10-adic — no division (no $1/5$)

GELFAND-P000273

$31/\overline{\text{III}}$ Bleher's talk. On the spectr. func.

Acta Math. 121

$N = 3 - 4$, 1968 yr. (L. Hörmander)

$$(Pu, u) \geq c(u, u),$$

$$\hat{p} = \int \lambda \, dE_\lambda, \qquad e(x, y, \lambda) \in C^\infty(\Omega \times \Omega)$$

— the spectral function of the operator.

Asymptotics in λ — ?

Theorem.

$$\left|\lambda^{-n/m}e(x,x,\lambda)-(2\pi)^{-n}\int_{p^0(x,\xi)<1}d\xi\right|=O(\lambda^{-1/m})$$

Original source details: GELFAND-P000273

Uncertain reading. Second argument: final x over y / an earlier x; initial letter undetermined.

Original source details: GELFAND-P000273

Uncertain reading. Corrected sign before O: $=$ / $\leq$; reading undetermined.

Off the diagonal 0.

Avakumovich's example.

Δ on $S^n \subset R^{n+1}$



Original source details: GELFAND-P000273

Uncertain reading. Axes with upward and rightward arrows, four horizontal steps and three rises. Sloping strokes have no assigned formulas; their number as distinct comparison lines and their role are undetermined. No axis labels.



λ of large multiplicity.

the jump magnitude is of just this order.

Large multiplicities due to invariance of the sphere under rotations.

The worst situation for asymptotics is a **multiple spectrum.**

$$e(x,x,\lambda_k+0)-e(x,x,\lambda_k-0)=\frac{C^k_{n+k}-C^{k-2}_{n+k}}{V_n}.$$



Original source details: GELFAND-P000273

Uncertain reading. Both lower indices read $n+k$, and the second upper index is $k-2$: $C^k_{n+k}-C^{k-2}_{n+k}$.

$$\frac{(2\pi)^{-n}}{V_n}\lambda^{n/2}$$

Jump $\sim \lambda^{(n-1)/2}$ and $C\lambda^{(n-1)/2}$ cannot be written.

There are averages:

$$\frac{1}{\lambda}\int_0^{\lambda} e(x,x,\nu)\,d\nu = (2\pi)^{-n}\lambda^{n/m}\int_{p^0(x,\xi)<1} d\xi + \lambda^{(n-1)/m} \quad ?$$



Uncertain reading. The leading coefficient is written $(2\pi)^{-n}$; a question mark is outlined after the second power term.

Original source details: GELFAND-P000273

This has not been done. It has been done for Laplace on a square.

GELFAND-P000274

[source number: 38]

See Dikii, UMN, 1957 on traces.

and earlier in 1954 Gelfand.

38

There are 2 problems.

1) obtain the subsequent terms of the asymptotics.

2) obtain a **formal asympt. expansion** (a subtle problem).

$$A = \hat{P}^{1/m} \quad \text{— a pseudodiff. operator.}$$

$$A = a_1 + a_0 + a_{-1} + \cdots$$

$$a_1 = p^{1/m}(x,\xi).$$

It suffices to do everything for the operator A. (pseudodiff., first order)

$$G(t) = \int e^{it\lambda}\,dE_\lambda = \exp(itA).$$

E_λ — spectr. decomp. of A: $A = \int \lambda\,dE_\lambda$.

$$(D + A)G(t) = 0, \qquad \text{where} \quad D = i\frac{\partial}{\partial t}$$

$$G(0) = I$$

A hyperb. problem results and is therefore solved.

Generalized Huygens principle: singularities propagate at finite speed.

$$G(t)u = \iint e^{i\varphi(x,t,y,\xi)}q(x,t,y,\xi)u(y)\,dy\,d\xi + Ku;$$

$\varphi(x,t,y,\xi) = \psi(x,y,\xi) - ta_1(y,\xi).$

$$q \sim q_0 + q_1 + \cdots$$

Only this is important for the asymptotics.
We need small t. ($|t| < \varepsilon$).

$$\psi(x, y, \xi) = (x - y, \xi) + O(|x - y|^2 |\xi|).$$

One can then refer to Marchenko's Tauberian theorem.
$E(x, y, t)$ — kernel of $G(t)$
$Q(x, y, t)$ — approx. kernel (regulariz.)

$$E - Q \in C^\infty \quad \text{in } x \text{ and } y \text{ for } |t| < \varepsilon$$

$$\hat{\varrho}(t)(E - Q) \in C^\infty_{0t}$$



Uncertain reading. The signs 0 and t are below and to the right of C^∞; t is lower and farther right than 0. Strict index hierarchy undetermined.

Original source details: GELFAND-P000274

cut off



Uncertain reading. Horizontal axis with a rightward arrow, vertical stroke with $\hat{\varrho}$, rounded rise and lower tails. Whether lower strokes belong to the graph or are pen flourishes is undetermined. No $\pm\varepsilon$ labels.



Original source details: GELFAND-P000274

GELFAND-P000275

$$\int \varrho(\lambda - \mu)\, de(x, y, \mu) - \int e^{i\psi(x,y,\xi)} R(x, \lambda - a_1(y, \xi), y, \xi)\, d\xi$$

$$R(x, \lambda, y, \xi) = F^{-1}_{t\to\lambda}\big(q(x, t, y, \xi)\hat{\varrho}(t)\big)$$

Diagram and typed description.

Original source details: GELFAND-P000275

GELFAND-P000276

$14/\overline{\text{IV}} - 69$ yr.

Uncertain reading. An illegible short mark is crossed out before the date.

Original source details: GELFAND-P000276

I. M. Gelfand.

On the work of Yik-Hoi Au-Yeung (Proceed. of Amer. M. S. February 1969)

If two quadr. forms are not simult. 0, then they can be

simult. reduced [Crossed out: to normal form / to diagonal form.]



Uncertain reading. The middle word of the cancelled phrase is undetermined: “to normal form” / “to normal form” with a longer abbreviation / “to diagonal form”.

Original source details: GELFAND-P000276

to a sum of squares.

(Greg / Grech / Grel “Lin. algebra”)

Uncertain reading. The surname’s final letters are undetermined: Greg / Grech / Grel.

Original source details: GELFAND-P000276

$\xi^* A\xi, \qquad \xi^* B\xi$ — corresp. quadr. forms

a pair of numbers — a vector of the plane.

[Above the line: Normalize.]

If $\forall \xi$ this is $\neq 0$, then it runs through no more than a semicirc.

After this rotate and one will be pos. definite.



Original source details: GELFAND-P000276

Uncertain reading. The upper axes have upward and rightward arrows. Below are axes without arrows and an open, nearly circular curve, heavier at the upper right. Short strokes occur at the ends of the heavy arc; their role as arrows or boundary marks is undetermined. There are no labels.



[Crossed out: in R / in R^3.]

Original source details: GELFAND-P000276

Uncertain reading. A possible superscript at R is obscured by hatching; the digit 3 is undetermined.

Davis (Toronto)

Davis, Acta Sci. Math. (1968)

H — compl. Hilb.



Original source details: GELFAND-P000276

Uncertain reading. Under the beginning of "Hilb." is a small correction group resembling Cyrillic "и"; its role is undetermined.

y^*x — scalar product, $(x, y) \in H \oplus H$.

$$A : H \to H, \qquad \underset{y=Ax}{(y,x)} \quad \text{— graph}$$

More gen. def. — a relation — a set $\alpha = \{(y,x)\} \subseteq H \oplus H$.



Original source details: GELFAND-P000276

Uncertain reading. The first letter after $\subseteq$: H / M; the final H is clearly legible.

1°

$$\|A\| \le a \quad \Rightarrow \quad \left\{ \frac{\|Ax\|^2}{\|x\|^2} : x \neq 0 \right\} \subseteq [0, a^2]$$

2°. Range of values of the form.

$$w(A) = \left\{ \frac{x^* Ax}{\|x\|^2} : x \neq 0 \right\}.$$

3°.

$$\sigma_p(A) : \{\lambda \in C : (\exists x) \quad Ax = \lambda x\}$$



Uncertain reading. No condition $x \neq 0$ is written at $\exists x$.

Original source details: GELFAND-P000276

([Crossed out: Numerical?] Numerical sets of the operator)



Uncertain reading. The cancelled word: Numerical?; some letters are obscured.

Original source details: GELFAND-P000276

Univers. inform. about the operator.
Indicatrix.
4°.

$$\{(\|Ax\|^2,\ x^* Ax,\ \|x\|^2) : x \neq 0$$

$$R \times C \times R$$



Uncertain reading. After $x \neq 0$ there is no visible closing brace.

Original source details: GELFAND-P000276

cone

GELFAND-P000277

[source number: 41]

Diagram and typed description.



Original source details: GELFAND-P000277

A convenient section:

$$(\xi, h) = \left(\frac{2x^* Ax}{\|Ax\|^2 + \|x\|^2}, \frac{\|Ax\|^2 - \|x\|^2}{\|Ax\|^2 + \|x\|^2} \right)^{=s(A)} \subseteq \mathbb{C} \times \mathbb{R}$$

$$\|\xi\|^2 + h^2 \le 1, \qquad s(A) \subseteq \text{ball}.$$



Original source details: GELFAND-P000277

Uncertain reading. Above the right parenthesis is $= s(A)$; on the main line is $\subseteq \mathbb{C} \times \mathbb{R}$. There are no set braces or quantifier over x.

Eigenvector — when it belongs to the sphere.
eigenval. — stereogr. projection



Original source details: GELFAND-P000277

Uncertain reading. A circle, a vertical line, two horizontal lines and a sloping stroke with three marked points. Labels $\frac{a^2-1}{a^2+1}$, λ, $\tau(\lambda)$, (ξ, h). Short strokes at the lower-right point have no established arrow direction; the exact boundaries of the densely marked points are undetermined.



Norm — if it does not go above the line $\frac{a^2-1}{a^2+1}$, then a — the norm.

Th. 1. Let $\mu(\lambda) = \frac{a\lambda+b}{c\lambda+d}$. $ad - bc \neq 0$.
$\forall$ relation α there is defined $\mu(\alpha)$,

$$s(\mu(\alpha)) = \varrho_\mu(s(\alpha))$$



Original source details: GELFAND-P000277

Uncertain reading. The symbol before index μ: ρ_μ / g_μ / ϱ_μ. A closed upper loop and a curved lower tail; the letter identity is undetermined.

[Under the transformation symbol:]
fractional? / analytic?-lin. transf.



Original source details: GELFAND-P000277

Uncertain reading. The first abbreviation is undetermined: “дроб.” (fractional) / “анал.” (analytic).

[Crossed out: **[?]**]



Original source details: GELFAND-P000277

Uncertain reading. A short cancelled word before “If”: Для? (For?); reading undetermined.

If A — an oper., then as usual
(if there exists $\mu(A) = (aA + b)(cA + d)^{-1}$).

$$(y, x) \in \alpha \iff (ay + bx, cy + dx) \in \mu(\alpha).$$

def.:

$$X \text{ — a spectr. set of } A \iff$$

(**[Cancelled illegible mark]** $\forall$ rat. funcs. f: $f(X) \subseteq D \Rightarrow \|f(A)\| \leq 1$.)

Original source details: GELFAND-P000277

Uncertain reading. After the opening parenthesis, before $\forall$, a single mark is densely crossed out and unread.

$$D = \{\lambda : |\lambda| \leq 1\}.$$

Th. 2 description of spectr. sets
provided that $\underset{\text{(on the sph.)}}{\tau(X)}$ — a segment (spherical).

$$\boxed{X \text{ — spectral}} \iff s(A) \subseteq \text{konv}(\tau(X)).$$

GELFAND-P000278

V. Buchstaber.

$$T^n = \underbrace{S^1 \times \ldots \times S^1}_{n}.$$

Thm. There are finitely many smooth manifolds of homotopy type torus.
(up to diffeom.)
For simply conn., it is proved: everything is determined by Pontryagin classes.
and the hom. type
(up to finitely many possibilities)

Milnor: for spheres $\underset{\text{unknown}}{(\text{except } 4 \text{ and } 3)}$

Novikov: For simply conn. manifolds: they are determined by the homot. type and charact. classes of the tangent bundle — then finitely many possibilities remain.

M^n — a manifold.

Smale:

Let $\partial W^{n+1} = M_1^n \cup M_2^n$

$M_1^n \subset W^{n+1}$ — a deform. retract



Original source details: GELFAND-P000278

Diagram and typed description.

$M_2^n \subset W^{n+1}$ ——————||——————

Then W^{n+1} — h-cobordism of the pair (M_1^n, M_2^n).

Smale's theorem.

h-cobordism (film) is completely (up to diffeom.) determined by a boundary (one of M_i^n) and an invar.



Original source details: GELFAND-P000278

Uncertain reading. The beginning of the final word "одним" (one) is overwritten over an illegible earlier entry.

$$\alpha \in \underset{\text{(Whitehead gr.)}}{\mathrm{Wh}}(\pi_1(M_1^n)).$$



Original source details: GELFAND-P000278

Diagram and typed description.

\

expressed through

$K_1(Z(\pi))$

||

see the talk of

Novikov.



Original source details: GELFAND-P000278

Diagram and typed description.

$Z[\pi]$

$GL(Z(\pi))$

| |

lim ind

group det D'ëdone / D'ëdonne $K_1(Z(\pi))$.

Uncertain reading. The number of repeated middle strokes in the surname is undetermined: Дьёдоне / Дьёдонне (D'ëdone / D'ëdonne).



Original source details: GELFAND-P000278

(noncommut.)

(quotient by the commutator subgroup).

Wh is obtained by taking a further quotient.

The element α is obtained through Smale's func. (nice-function).

In the Smale-Novikov case [crossed out: this?] h cobordisms $\Longleftrightarrow$ diffeom., and a cobord. is already a homot. [cancelled illegible mark] concept. (There $W^{n+1} = M_1^n \times I$)

Original source details: GELFAND-P000278

Uncertain reading. A short word between "Smale-Novikov" and "h cobordisms" is cancelled: это? (this?); reading undetermined.

Original source details: GELFAND-P000278

Uncertain reading. Between "homot." and "concept", a mark or beginning of a word is cancelled; reading undetermined.

GELFAND-P000279

[source number: 42]

42

Tori could be classif. because of Bass's theorem:

$$K_1(Z + Z + \ldots + Z) = 0.$$

(of the group ring of the group).

(algebr. fact)



Original source details: GELFAND-P000279

Uncertain reading. The entry reads K_1, ordinary plus signs and $= 0$.

For Z it is obvious.



Original source details: GELFAND-P000279

Uncertain reading. Left of "For Z", a narrow loop-like mark with a stroke; reading undetermined.

Matrices of polynomials ~~det~~ invertibility $\Longleftrightarrow$ det $= \pm 1$.

Uncertain reading. Cancelled: det and a following sign: $det =$ / $det \neq$; the sign is undetermined.

Original source details: GELFAND-P000279

(see Artin's book "Geometrical algebra"— it has the det of D'edonné).
Whitehead det. 1 — if reducible by elem. transformations to 1
(and increase of order)
The quotient is commutative — this is a remarkable theorem! (Whitehead).
Bass — it suffices to restrict to

sufficiently high
~~[?]~~ order.



Uncertain reading. An illegible word is crossed out below the outlined "sufficiently high".

Original source details: GELFAND-P000279

$$M^n \overset{\nu_n}{\subset} R^N$$

ν_n — normal bundle



Uncertain reading. Initial letter: ν_n / V_n; the first lower index is n, and M is used below.

Original source details: GELFAND-P000279

(stable) (does not depend on embedding, like the tangent bundle)

Equivalence — of manifolds with a bundle.
(is induced...)



Uncertain reading. In "индуцируется" (is induced), the middle letters are heavily overwritten; the earlier entry is undetermined.

Original source details: GELFAND-P000279

Let us calculate for the torus.
From Adams's theorem on the J-funct.

spher.

for $M^n \sim T^n$ everything is completely determined by the Pontryagin classes of M^n.

Pontryagin classes — an infinitely valued invar.

Novikov: for tori, Pontryagin classes are a homot. invariant.

There $\nu_M = 0$.

But: on $S^2 \times S^4$ there are infinitely many smooth structures.

Again everything works for tori, since it is parallelizable and $\nu_M = 0$.

$$\{M_1^n\} \qquad f : M_1^n \longrightarrow M_2^n, \quad f^*\nu_{M_2} = \nu_{M_1}.$$

How many such classes? If there are finitely many here, then everything is in order. Then for tori everything is unique.



Original source details: GELFAND-P000279

Diagram and typed description.

$M^n \subset R^N$

$R^N \longrightarrow T_{\nu_M}$ (Thom compl.)

$E_{\nu_M} \subset R^N$ (tube)

$S^N \longrightarrow T_{\nu_M}$.

GELFAND-P000280

An elem. of $\pi_N(T_{\nu_{M_1}})$ is obtained.

The space T_{ν_M} does not depend on the manifold (!) — they are all homot. equiv., since on the base they are homot. equiv.

We obtain an element of $\pi_N(T_{\nu_M})$.

We need to consider the Hurewicz homom.



Original source details: GELFAND-P000280

Diagram and typed description.

$$H: \quad \pi_N(T_{\nu_M}) \longrightarrow H_N(T_{\nu_M}) = Z$$

$$\downarrow$$

$$\alpha$$

If α is realized in this way, then $H(\alpha) \longrightarrow +1$.

(on the interior of the tube it is the identity).

(by the Excision theorem).

There is a map

$$\{M_i\} \longrightarrow H^{-1}(1)$$

finite group

$\forall$ manifolds



Uncertain reading. Below the rectangular bracket, the entry reads “finite group $\forall$ manifolds”.

Original source details: GELFAND-P000280

$$T_\nu(T^n) = \Sigma^{N-n} T^n = S^N \vee \left(\vee_{i<N} S^i\right).$$



Uncertain reading. The line uses equality signs; below the final part is $i < N$. No additional sign is visible after T^n.

Original source details: GELFAND-P000280

Everything follows from Serre’s finiteness theorem.

It remains to show that Ker is finite.



Original source details: GELFAND-P000280

Uncertain reading. The horizontal arrow f_{M_1} points right. There are thickened strokes at the ends of the slanting f_{M_2} line; whether there is a second arrowhead is undetermined.



Suppose they are homotopic.

$$\partial W^{n+1} = M_1^n \cup M_2^n$$

and there exist retractions and with bundles

Everything is in order.



Original source details: GELFAND-P000280

Diagram and typed description.

$$\begin{array}{ccc} F : S^N \times I & \longrightarrow & T_\nu \\ & & \cup \\ & & M^n \end{array}$$

We need to classify ~~[?]~~ films which deform. retract.



Original source details: GELFAND-P000280

Uncertain reading. A long word crossed out repeatedly: кобордизмы (cobordisms)? The reading is undetermined.

A class of finite index, for which a film exists.
This is the same as saying that $i : M_1 \subset W$ induces an isom. of all homot. groups.
Obstruction theory for the modification of the film.

GELFAND-P000281

[source number: 43]

21/IV Kirillov. Borel–Weil theorem. (in a new form).

43

$G \supset K$ K — compact subgr. (max).
It is assumed that rank G = rank K (dimension of a max. torus).
$K \supset H$ — Cartan subgr. (common to K and G).

e.g. $GL(2,R)$

G — a real semisimple group.

for matrices —

— unit circle.



Original source details: GELFAND-P000281

Uncertain reading. The example reads $GL(2,R)$; below, G is called a real semisimple group. The example has a frame open on the left; the right-hand matrix note has a frame open on the right.

$D = G/H$ — complex manifold (always)

The number of complex structures — the number of elements of the Weyl group.

$\mathcal{L}_\lambda$ — 1-dimensional bundles over D(fiber $\mathbb{C}$)

$$\mathcal{L}_\lambda \xrightarrow{\mathbb{C}} D$$

1-dimensional representation — a character of the Cartan subgroup

$A_0^i(\mathcal{L}_\lambda)$ — smooth $(0,i)$-forms with values in $\mathcal{L}_\lambda$.

(and with compact support)

$$\bar\partial : A_0^i \longrightarrow A_0^{i+1}$$

$$\square = \bar\partial\bar\partial^* + \bar\partial^*\bar\partial.$$

(Laplace–Beltrami)

The space of L^2-cohomology. (with coefficients in the sheaf)

A one-dimensional bundle
is given by a character of the group H!
(the principle of Frobenius
reciprocity)

G — compact $\Rightarrow$ this is the Borel–Weil theorem.

On D there is an invariant measure $\Rightarrow$ there is ~~[?]~~ a Hilbert space L^2. (completion of smooth ones)



Uncertain reading. Before “a Hilbert space L^2”, a densely crossed-out entry in a rectangle; its reading is undetermined.

Original source details: GELFAND-P000281

$\bar{\partial}$ on a dense set.

$$\mathrm{Ker}\,\Box = \mathcal{H}^i(\mathcal{L}_\lambda)$$

— i-dimensional L^2-cohomology.

In the compact case they are finite-dimensional. In the general case they are not.

If with decay at infinity — there will be the same cohomology.



Uncertain reading. The beginning of “Если” (If) is heavily overwritten; the earlier letters are undetermined.

Original source details: GELFAND-P000281

A partial answer to 2 conjectures of Langlands

Theorem 1. λ — a weight, $|(\lambda, \alpha)| > b \quad \forall$ simple root α.

sufficiently nondegenerate.

Then

$$\mathcal{H}^i(\mathcal{L}_\lambda) = \begin{cases} 0, & i \neq k(\lambda \text{ ~~[?]~~} + \rho), \\ \pi_{\lambda+\rho}, & i = k(\lambda + \rho). \end{cases}$$



Uncertain reading. Immediately after λ in the first row, a loop-shaped sign is crossed out: ρ / β. Its reading is undetermined; after the cancellation, the entry is $k(\lambda + \rho)$.

Original source details: GELFAND-P000281

Theorem 2.

$$K(\mu) = \text{number of compact roots } \alpha : (\alpha, \lambda) < 0 \quad + \\ + \text{number of noncompact roots } \beta : (\beta, \lambda) > 0.$$



Uncertain reading. In Theorem 2, the left side is $K(\mu)$ and both pairings on the right use λ; Theorem 1 uses lowercase k. There are two plus signs at the line break. Theorem 2 is set off by an angular rule.

Original source details: GELFAND-P000281

For the usual Bor.–Weil theorem see Demazur

GELFAND-P000282

Uncertain reading. Two small crossed-out loop-shaped signs above and to the left of the surname. Possible reading: B.; undetermined.

Original source details: GELFAND-P000282

Buchstaber.

Manifolds of the homot. type of a torus are divided by h-cobordisms into a finite number of classes

Problem: to show that in $\forall$ class there is a finite number

Next, the simplest films are classified by Morse modifications.



Uncertain reading. At bottom right, a curved vertical stroke with a separate short mark above it:) / 1. The reading is undetermined.

Original source details: GELFAND-P000282

GELFAND-P000283

15.9.69 yr.

B. Vainberg on results of Hörmander. (see Vishik seminar). on singularities of fund. sol.
General sol. of homog. eqn.: (homog. polynomial)

$$\int_{P(\xi)=0} f[(x,\xi)]A(\xi)\,d\xi \qquad \text{(Borovikov)}$$

f, A — arbitrary functions.
Singularities in the homog. case are described by Borovikov.
For example:

$$\int_{P(\xi)=0} \frac{(x\cdot\xi)^\lambda}{\Gamma(\lambda+1)} A(\xi)\,d\xi$$



Uncertain reading. A short crossed stroke between x and ξ: dot /plus /comma. The parentheses and superscript λ are visible; the dotted reading is undetermined.

Original source details: GELFAND-P000283

— proposal of Borovikov.

$$\boxed{R_0^+ \text{ (stand. fund. sol.)}}$$

Grushin:

$$\sum_j \int \frac{\alpha_j(\xi)e^{i(x,\xi)}}{P(\xi)\pm i0}\,d\xi$$

α_j — partition of unity on the sphere.
The Bernstein problem is solved.

$$\left\{\begin{array}{l} z=f(x_1,\dots,x_{n-1}) \text{ — min. surf.} \\ (x\text{-arbitrary}) \implies \text{it is a plane.}\end{array}\right\}$$



Uncertain reading. The final variable index: $n-1$ /$n+1$; the short strokes merge. The reading is undetermined.

Original source details: GELFAND-P000283

true for $n \le 8$; for $n \ge 9$ false.

De Giorgi, Simons and Bombieri.

Kazhdan and Bernstein.

Convergence of the spectrum as the domains expand.



Diagram and typed description.



Original source details: GELFAND-P000283

A — self-adj. op. on the manifold X.

$\Lambda \subset R$.

[Below Λ:] interval.

The continuous functions contained in E_Λ are dense in it.

(required) — so for elliptic op.

$x_0 \longrightarrow$ a Plancherel measure on the spectrum of A.

$$M_{x_0}(\Lambda) = \max_{\substack{f\text{-continuous in } E_\lambda,\ \|f\|=1 \\ \text{(over all of } X\text{)}}} |f(x_0)|^2.$$



Uncertain reading. Below max: E_λ; possibly E_Λ. Above are E_Λ and $M_{x_0}(\Lambda)$; the cases have not been made uniform.

Original source details: GELFAND-P000283

[At right:] This is a measure (possibly infinite).

GELFAND-P000284

[source number: 53]

$K_\Lambda(x, y)$ — the kernel of E_Λ.

? 53

Kazhdan. M. Artin in the Bourbaki seminar.

$$f_i(x_1, \ldots, x_n) = 0, \qquad 1 \le i \le k.$$

f_i — convergent power series.

When does a sol. exist $\psi_j(t_1, \dots, t_\tau)$



Uncertain reading. The function letter: ψ /Y; the final index: τ /r. The reading is undetermined.

Original source details: GELFAND-P000284

Answer: if and only if there is a sol. in formal power series.
(arbitrarily close to the formal one)
[Below the parenthesis:] can be completed

———— • ————

22.9.69 yr.
Fikera on unilateral bound. problems.



Diagram and typed description.



Original source details: GELFAND-P000284

An elastic body on a surface Σ rigid and frictionless.
And the stress tensor $\equiv 0$.
A — natural volume of the body.
On the free part of the boundary, a force $\underbrace{\varphi}_{\text{density}}$ on $\partial A - \Sigma = \Sigma^*$.
Inside there are also certain forces f — volume forces.
Let the body move to a position of equil.
It may separate from Σ.



Uncertain reading. Contact is visible at the left. At the right, overlapping strokes and a narrow light strip; exact contact or separation and the length of contact are undetermined. There are no labels or arrows.



Original source details: GELFAND-P000284

This is an analytic problem (formulation A. Signorini, 1959)
σ_{ik} — the stress tensor.
Inside the body
[Crossed out:] ~~$(\sigma_{ik})_k - f_i \equiv 0$~~

[Written at the right:]

$$\sigma_{ik/k} - f_i = 0.$$

$(\operatorname{div}\sigma = f)$.

$$\sigma_{ik}\nu_k - \varphi_i = 0.$$

— bound. conditions.
(ν — normal vector)



Uncertain reading. The normal sign in the formula and caption has the form V /ν; the choice of letter is not established from the shape alone.

Original source details: GELFAND-P000284

GELFAND-P000285

On Σ.

u_i — the displacement vector.

Condition	$u_i\nu_i = 0$ (on Σ)	
Normal reaction	$\sigma_{ik}\nu_i\nu_k \geq 0$	
	$\sigma_{ik}\nu_i\tau_k = 0$	— tang. comp.



Uncertain reading. The conditions are joined by an open stepped line. The normal sign has the form ν /V; the shape alone does not establish the letter.



Original source details: GELFAND-P000285

At a point of the free surface:

$$\begin{cases} u_i\nu_i > 0, \\ \sigma_{ik}\nu_i\nu_k = 0, \\ \sigma_{ik}\nu_i\tau_k = 0. \end{cases}$$

But it is unknown where which occurs.
We have not yet taken into account that the body is elastic.

$$\underline{\underline{W(x,\varepsilon)}}$$
potential

$$\varepsilon = \{\varepsilon_{ik}\} \qquad \varepsilon_{ik} = 2^{-1}(u_{i/k} + u_{k/i})$$

Strain tensor.

Relation:

$$\sigma_{ik} + W_{\varepsilon_{ik}} = 0 \qquad \text{on } A.$$

Problem of exist. and uniqueness.

$$I(u) = \int_A W[x, \varepsilon(u)]\, dx - \underbrace{\int_A f_i u_i\, dx}_{\text{work of } f} - \underbrace{\int_\Sigma \varphi_i u_i\, d\Sigma}_{\text{work of } \varphi}.$$

(Total energy)



Original source details: GELFAND-P000285

Uncertain reading. The first surface integral is written with Σ, without a star.

In the class of admissible displacements $\mathcal{W}_\Sigma$.



Original source details: GELFAND-P000285

Uncertain reading. The heavily retraced letter: $\mathcal{W}_\Sigma$ /$\mathcal{U}_\Sigma$; it is not made uniform with the model-class notation below.

If a minimum exists in $C^1(\Sigma)$, then it is a solution.
conversely, a solution is a min.



Original source details: GELFAND-P000285

Uncertain reading. Written $C^1(\Sigma)$; there is no bar over Σ.

But: in this class min does not exist.

$$I(u) = \frac{1}{2}\int_A a_{nk}(x)u_{/n}u_{/k}\,dx - \int_A fu\,dx - \int_{\Sigma^*}\varphi u\,d\sigma.$$

$$a_{nk}(x)\mu_n\mu_k \geq \rho_0\mu_n\mu_n.$$

$$\mathcal{U}_\Sigma: \quad u|_\Sigma \geq 0.$$

(Model problem)



Original source details: GELFAND-P000285

Uncertain reading. The upper arc: Σ^*; at lower left: Σ. Two ringed junction marks; the left one is retraced, with an oblique stroke. Its role and an orientation of traversal are undetermined.



GELFAND-P000286

[source number: 54]

From this we obtain the problem.

$$\boxed{u = 0, \quad a\frac{\partial u}{\partial \lambda} \geq 0} \quad \text{or} \quad \begin{cases} u > 0, \\ a\dfrac{\partial u}{\partial \lambda} = 0. \end{cases}$$

$$\boxed{(a_{nk}u_{/k})_{/n} = f.} \quad \boxed{54}$$

Necessary:

$$\int_A f\,dx + \int_{\Sigma^*}\varphi\,d\Sigma \leq 0.$$

Original source details: GELFAND-P000286

Uncertain reading. The first integral differential: $dx\ /d\Sigma$; possibly Σ is changed to x. The strokes overlap.

Original source details: GELFAND-P000286

Uncertain reading. The final A below the first integral is traced over earlier strokes. A possible earlier Σ is undetermined.

Let $f \leq 0$ on A and $\varphi < 0$ on Σ^*.
By the min principle, u cannot have a min. in A.
There is no sol. in $C^1(\bar{A})$.

(deduced from Green's formula)
an immediate contradiction — a discontinuity of the derivative is obtained.

29.9.69

Kazhdan Formulation of results of M. Artin. (1968).
(in the USSR independently Pokornii and Rybkin)

Original source details: GELFAND-P000286

Uncertain reading. The first surname: Pokornii /Pokornyi (Покорний /Покорный); the joined ending does not establish иогы.

UMN, vol. 15, $N = 4$ (1960) p. 169
and Melamed
Sib. math. journal

$$f_i(x_1, \ldots, x_k) = 0, \qquad 1 \leq i \leq n.$$

a collection of convergent power series (in a nbd. of 0
We try to find

$$\boxed{x_j = x_j(y_1, \ldots, y_\ell)} \quad \boxed{j = 1, \ldots, k.}$$

so that the equalities hold upon substitution.
It is sufficient to find such functions in formal power series.

Example.	Then a sol. in analytic functions will be found, arbitrarily close. (with any number of derivatives)
$x_1^2 - x_2^3 = 0$ $\quad x_1 = y^3,$ $\quad x_2 = y^2.$	

the problem is handled by induction on the number of x_j.
and a more complicated ind.
Reformulation.
These are equations of an analytic set and 2 rings

$A = C\{y_1, \ldots, y_\ell\}$	convergent series.
$B = C[[y_1, \ldots, y_\ell]]$	formal series.

If the manif. has a point with values in B, then there is also a point with values in A.

GELFAND-P000287

Induction also on conn. components. (their number)

Irreduc. — a subpiece has smaller dimension.

1) If for irreduc. varieties (of the given dim.) proved, then also always proved. (given dim.)

Choose eqns. lying in the ideal, **[crossed out: ?]** corresp. to this component.

Original source details: GELFAND-P000287

Uncertain reading. A word between “ideal,” and “corresp.” is densely crossed out. Its initial stroke resembles Cyrillic “к”; the complete reading is undetermined.

Adding eqns. Consider a prime ideal.

Original source details: GELFAND-P000287

Diagram and typed description.



$\mathcal{J} =$ (Intersect. of primes).

Original source details: GELFAND-P000287

Uncertain reading. The symbol before the equality has a long lower hook: $\mathcal{J}$ / $\mathcal{I}$; the letter identity is undetermined.

We obtain 2 systs. of eqns. $\forall$ solution satisfies one of these systems.

(If a geom. point lies on **[crossed out: ?]** a variety, then it lies on one of the components.)



Original source details: GELFAND-P000287

Uncertain reading. A short word or word beginning between “on” and “a variety” is covered by several lines; no reliable sequence of letters is established.

[Cancelled mark in the left margin: ?]

Original source details: GELFAND-P000287

Uncertain reading. A compact repeatedly crossed-out mark with loops. Whether it is a letter, number or nontextual mark is undetermined.

The rest — next time.
L. Faddeev.

On the results of a computational experiment, **[crossed out: ?]** rel. to Kirillov’s programme

descr. of reprs.

Original source details: GELFAND-P000287

Uncertain reading. A word after “experiment,” before “rel.” is cancelled. Its beginning resembles “ре”; the alternatives “реал.” / “рез...” remain unestablished.

Representation — quantization of class. mechanics.

Examples and probls. on quantization rules.

M_{2n} — a sympl. manifold, possess.? Ω — a 2-form (nondeg.). $\Omega = d\omega$.



Original source details: GELFAND-P000287

Uncertain reading. The source abbreviation after “sympl. manifold” is “обл.” / “обал.”; the intermediate stroke is ambiguous. “possess.?” is a provisional abbreviated rendering; the full source word is not established.

$d\mu = \Omega^n$ — a measure.

$$f \longrightarrow X_f \qquad \text{(a field from a fn.)}$$



Original source details: GELFAND-P000287

Diagram and typed description.

$\Omega(X_f, Y) = Yf$

Hamiltonian fields X_f form a Lie algebra

$$[X_f, X_g] = X_{\{f,g\}},$$

where $\{f, g\}$ — the Poisson bracket (it is defined by this).

Oper. X_f is antisymm. in L^2 with measure $d\mu = \Omega^n$. (It is preserved by Liouville's theorem.)

To the Lie-algebra elem. $X_f \longrightarrow$ corresponds an oper. in L^2.

1951 Van Hove found a 1-param. family of representations.

$$Z_f = X_f + \alpha\big(\omega(X_f) - f\big)$$

GELFAND-P000288

[source number: 55]

55

Then the representation condition holds

$$\omega(X_f) - f = \ell_f$$

Van Hove's assertion: This is again a repr., not equiv. for any α

$$[Z_f, Z_g] = Z_{\{f,g\}}$$

But this is not yet a passage to quantum mechanics, since everything is still in the space of all variables, rather than half of them.

Consider now $SO(3)$ with its nat. repr. in $\mathbb{R}^3$. On the orbits (S^2) there is a natural compl. structure.

Result of computing Z_f, when X_f — a gener. of the rotation group.

Diagram and typed description.

~~X_1, X_2, X_3~~

Original source details: GELFAND-P000288

$$x_1^2 + x_2^2 + x_3^2 = a^2 \quad \text{— orbit}$$

Functions x_1, x_2, x_3. Corresp. Van Hove opers.:

Quantization problem.



Diagram and typed description.



Original source details: GELFAND-P000288

Hamiltonian $f = \dfrac{p^2}{2m}$ (free particle).
An operator must be assigned to it.

$f = x_1$.

Uncertain reading. A rounded contour touches a nearly horizontal line; four sloping strokes extend from its upper region. The rightmost ends above the lower line. A small left hook may be a leftward arrow or a line irregularity; its direction and the exact upper-stroke junctions are undetermined. There are no labels.



Original source details: GELFAND-P000288

After stereogr. projection (coord. z) — ω is not single-valued.

$$\Omega = a\frac{dz \wedge d\bar{z}}{(1+|z|^2)^2}$$

$$X_i = X_f \quad \text{for } f = x_i$$

$$\omega = \frac{a}{i}\frac{1}{1+z\bar{z}}(z\,d\bar{z} - \bar{z}\,dz)$$



Uncertain reading. The entry for Ω has a before the fraction and denominator $(1+|z|^2)^2$. The next entry has factor a/i, denominator $1+z\bar{z}$ and parenthesis $z\,d\bar{z} - \bar{z}\,dz$; all these signs are retained.

Original source details: GELFAND-P000288

No sing. on the plane, but a sing. at ∞ (north pole before projection).

$$X_1 = \frac{1}{2i}\left((1-z^2)\frac{\partial}{\partial z} - (1-\bar{z}^2)\frac{\partial}{\partial \bar{z}}\right)$$

$$Z_1 = X_1 + \frac{\alpha a}{2}(z+\bar{z}).$$

The analyt. and antianal. parts commute!

Therefore we take

$$Y_1 = \frac{1}{2i}(1-z^2)\frac{d}{dz} + \frac{\alpha a}{2}z$$

Y_2, Y_3 analogously. This is a basis of the Lie alg., satisfying commutation rels.

GELFAND-P000289

They give a repr. of the rotation gr.

A measure where they are self-adj. exists only for integral a!

$$\frac{1}{(1+\bar{z}z)^a}$$

Square-integrable ones — a finite number — polynomials. Therefore a finite-dimensional representation.

Next time: Kazhdan;

(Schmid on L^2-cohomology (Vezantini, Raghunathan)).

Uncertain reading. The first surname in parentheses: Vezantini / Vezantin / Vezentini; the crowded final strokes do not establish a definitive reading.

Original source details: GELFAND-P000289

Starts at 18^{30}. (end 20^{30})

6/X-69 yr.

Uncertain reading. A narrow, densely cancelled mark precedes the date: 1 / 2 / a nontextual mark. Its reading is undetermined.

Original source details: GELFAND-P000289

Dusa mc Duff

Uncertain reading. Dusa mc Duff / Дуса mc Duff / Дуза mc Duff. The first name admits mixed or Cyrillic lettering; the written case of "mc" is retained.

Original source details: GELFAND-P000289

On factors of type II_1.

(in English and a woman).

see Naimark.

A subring of the ring of all opers. in Hilb. space is called a factor, if

1) [crossed out: $\forall$?] $X \in M \Longrightarrow X^* \in M$.



Uncertain reading. After "1)" the sign beneath slanting strokes may be the quantifier $\forall$; it has not been recovered.

Original source details: GELFAND-P000289

2) M is weakly closed (for $\forall$ seq. X_n the weak limit belongs).

3) The centre consists of opers. proportional to I.

Example. In the fin.-dimensional case:



Diagram and typed description.

X	0
0	X

Original source details: GELFAND-P000289

Every factor in the fin.-dimensional case is like this: in $H_1 \otimes H_2$ consider opers. $X \otimes 1$ (X — arbitrary).

A vect. — a matrix ξ_{ik}. An oper. — acts on the 1st coordinate.

Every weakly closed ring (with involution) decomposes into a direct integral of factors.

Von Neumann 1935–36

Let M — a factor; then $\frac{X+X^*}{2}, \frac{X-X^*}{2i}$ generate them.

(self-adj.) $a = \int \lambda \, de_\lambda$, $e_\lambda \in$ the factor, and generate the factor.

A factor is generated by projections with $e^2 = e$, $e^* = e$.

GELFAND-P000290

[source number: 56]

56

partial

If [crossed out: illegible] there exists an isometry from M, joining the subsp. corresponding to the projections, then the 2 opers. are called equivalent.
(subsp.)

Uncertain reading. After "If" and before "there exists", tall signs are densely crossed by diagonals; the underlying signs have not been separated or read.

Original source details: GELFAND-P000290

If equiv. ones are identified, then an ordering results (by inclusion).

Equiv. classes of projection opers. can be added.

Hence subsp. can be measured (assign numbers to a subsp.).

(No Archim. axiom — ∞ is present).

Thm. If there is a min subsp., then it is isom. to the ring of all opers. in Hilb. space.

$$R = M \otimes M' \qquad (M' \text{ — commutant factor}).$$

No min $\Longrightarrow$ either II_1, II_∞ or III.
II_1 — there is never a min, but everything is meas. by numbers in $(0, 1]$ (there is a max) and the Archim. axiom.



Diagram and typed description.

II_1.

Original source details: GELFAND-P000290

[cancelled sign: ∀?] ∀ oper. has a trace and det; the minimax theory of eigenvalues holds (everything that holds for matrices).

Uncertain reading. Before the legible ∀, a small sign with two slanting strokes and a crossbar is cancelled. Its possible reading as ∀ is not established.

Original source details: GELFAND-P000290

$$\mathrm{Tr}(a) = \int \lambda \, d(\dim e_\lambda) \qquad (\dim \text{ from } 0 \text{ to } 1)$$

The space itself has not yet been discovered.

Which factors of type II_1?

1) hyperfinite Murray and Neumann — there is only one

2) J. Shvarts

3) Ching

4) Sakai

5–6) Dixmier, Lance

7–8) Zeller-Meier

$7, 8'$) Stepin, Golodets

Diagram and typed description.

Continuum of factors ‖ Dusa Mc Duff

Original source details: GELFAND-P000290

GELFAND-P000291

13/X-69 yr. Next time Minlos and Sinai.

Gelfand.

On Araki's work.

Question: Let

$$\begin{pmatrix} \alpha(t) & \beta(t) \\ -\bar{\beta}(t) & \overline{\alpha(t)} \end{pmatrix} = u(t)$$

a unit. matrix with det 1,

$$|\alpha(t)|^2 + |\beta(t)|^2 = 1, \qquad t \in [0, 1].$$

Find all irred. unit. representations of this group. This has not been done.

supp of repr. F — the smallest closed set for which the condition holds

$$u(t) \equiv 1 \quad \forall t \in U(F) \Longrightarrow T_{u(t)} = I$$

Problem: does an irred. unit. representation exist with supp — an interval.

———— • ————

supp — a point — the operator $u(t_0)$ (2-dim. repr.).

This is the repr. $\delta(t - t_0)$.

$$e: \; u(t) \longrightarrow T^e_{u(t_0)} \qquad \delta_e(t - t_0)$$



Uncertain reading. Before the colon, above T and below δ is a looped sign: e / ℓ. The typeset line shows the visual candidate e; the letter is undetermined.

Original source details: GELFAND-P000291

$$u(t) \longrightarrow u(t_1) \otimes u(t_2)$$

an irred. repr. with supp — a pair of points.
(a repr., in effect, of a direct sum of 2 [crossed out: matr.?] groups of matrices).



Original source details: GELFAND-P000291

Uncertain reading. The parenthetical insertion is on the right. After "2", a short word is cancelled, possibly "matr."; below it is the separate entry "groups of matrices". The cancelled word's reading is undetermined.

One can take n points.

For a countable set this can no longer be done (it can be done for a convergent seq.).

Araki.

Idea:

$$e^K = \bigoplus_{n=0}^{\infty} S^n(K)$$

(K — Hilb. space)

$$e^{\varphi} = \bigoplus_{n=0}^{\infty} \frac{1}{\sqrt{n!}} \varphi \otimes \varphi \otimes \cdots \otimes p$$



Original source details: GELFAND-P000291

Uncertain reading. The last factor after $\otimes$ has a descending stroke and an upper-right loop: p / ρ; its possible identification with the preceding φ signs is not established. The formula shows the visual candidate p.

$\sqrt{n!}$, so that $(e^{\varphi}, e^{\psi}) = e^{(\varphi,\psi)}$.

$K \to e^K$ — a functorial passage

$$K_1 \oplus K_2 \longrightarrow e^{K_1} \otimes e^{K_2}$$

At $\forall$ point t we specify a representation in the space $K(t)$ (e.g. 2-dimensional)

$$\int_0^1 K(t)\, dt$$

GELFAND-P000292

[source number: 57]

57

Consider $e^{\int_0^1 K(t)\, dt}$.

A repr. is obtained in it (from funct.) which is reducible.

The gr. of matrices of order 1 $\alpha(t) = e^{x(t)}$.
"Nepr." repr.

Original source details: GELFAND-P000292

Uncertain reading. The source abbreviation "Непр." before "repr." is retained as "Nepr." without expansion; continuous/irreducible has not been selected from context.

$$e^{x(t)} \longrightarrow C, \qquad e^{x_1(t)} e^{x_2(t)} \longrightarrow C_1 C_2, \qquad C = e^a$$
$$x(t) \longrightarrow a$$

a — a lin. funct. of $X(t)$ — a generalized func. or distribution.

Original source details: GELFAND-P000292

Uncertain reading. In the line about the linear functional, the letter $X(t)$ / $x(t)$ is larger than the nearby x signs; its case is undetermined. The candidate $X(t)$ is shown.

$$\delta(t - t_0): \qquad e^{x(t)} \longrightarrow e^{x(t_0)}$$

$$x(t) \longrightarrow e^{\int_0^1 a(t)x(t)\,dt}$$

On the circle an integrality condition is added.

— • —

A repr. here is a generalization of a distribution.

GELFAND-P000293

[source number: 60]

60

17/XI-69 yr. Hewitt.
One result (sharp for all comp. groups)
as for the circle.
[crossed out: illegible]

Original source details: GELFAND-P000293

Uncertain reading. Dense crossing strokes precede the heading "On s-numbers"; the underlying letters or signs have not been read.

On s-numbers:

Gantmakher;
Wielandt
Berezin, Gelfand Trudy M. M. O. —
— ∀ semisimple Lie groups.
from repr. theory for a compl. func.

H. Weyl and Ky Fan.

[crossed out: illegible] All this is for an arbitrary group and a class of representations:

Original source details: GELFAND-P000293

Uncertain reading. Before “All this”, joined vertical and slanting strokes are cancelled; the underlying sequence is undetermined.

$$\|\hat{f}\|_p = (\sum_{\sigma\in\Sigma} d_\sigma \|\hat{f}(\sigma\|_p^p)$$



Original source details: GELFAND-P000293

Uncertain reading. After σ in the argument are two vertical strokes without a separate closing round parenthesis. No exponent is read after the large right parenthesis. The σ next to d may be a subscript or on the line; the candidate d_σ is shown.

Peter–Weyl–Plancherel thm.

$$\|\hat{f}\|_2^2 = \int_G |f|^2 \, d\lambda;$$

$$\|\hat{f}\|_\infty = \sup\{\|\hat{f}(\sigma)\|_{\mathfrak{S}_\infty} : \sigma \in \Sigma\}.$$



Original source details: GELFAND-P000293

Uncertain reading. Before ∞ is an S-shaped sign with a long crossing stroke: $\mathfrak{S}_\infty$ / S_∞. This line shows the blackletter candidate; the following lemma retains ordinary S.

Riem.–Lebesgue lemma:

$$\forall f \in L_1(G), \quad \forall \varepsilon > 0 \quad \{\sigma : \|\hat{f}(\sigma)\|_{S_\infty} > \varepsilon\}$$

— a finite set.

Kunze's thm. $1 < p < 2$

$$\|\hat{f}\|_{p'} \le \|f\|_p.$$

(Hausd.–Yun.).



Original source details: GELFAND-P000293

Uncertain reading. After “Hausd.-”, the abbreviation is Yun. / Yung.; the final hooked stroke before the full stop is not established as part of н or a separate г.

Thm. of Hardy–Littlewood — equality only for $f(x) = \alpha e^{inx}$;

For a general group things are not so simple: there, for funcs. of the form

χ — a cont. func. on an open subgroup G_0, $\chi(e) = 1$, $\chi(xy) = \chi(x)\chi(y)$,

$\chi = 0$ outside G_0.

There are analogues of the Riesz–Thorin theorems.

GELFAND-P000294

23.2.70 yr.

Kazhdan on Griffiths's work.

Original source details: GELFAND-P000294

Uncertain reading. On the left is an oval contour with an interior point and six long curves above it. A small loop and nearly parallel lower strokes occur at the left edge. The short-stroke connections and curve continuations are undetermined; there are no labels or definite arrows.



$$T:\ H^i(V_s) \longrightarrow H^i(V_s)$$

(on going around a puncture)

$$\exists N, \text{ such that } \quad (T^N - 1)^{i+1} = 0$$

(T is unipotent).



Uncertain reading. The formula is followed by the separate entry "(T is unipotent)", with no N on T and no "quasi" prefix; the entry is retained.

Original source details: GELFAND-P000294

Diagram and typed description.

W

$\downarrow$

S

Original source details: GELFAND-P000294

an algebraic bundle

base — a 1-dim. alg. variety (a Riem. surface with punctures).

$$\pi_1(S):\ H^K(V_s) \longrightarrow H^K(V_s) \qquad \text{(coeffs. } C\text{)}.$$

and defines a vect. bundle [crossed out: an illegible sign] (analytic)

Uncertain reading. A narrow cancelled sign occurs between “bundle” and “(analytic)”; the underlying letter is undetermined.

Original source details: GELFAND-P000294

Diagram and typed description.

$$\begin{array}{c} E \\ \downarrow \\ S \end{array}$$

Original source details: GELFAND-P000294

$O(E)$ — the sheaf of germs of analyt. sects.

There is a canon. connection from parallel transports on the universal cover $\tilde{S}$. (There it is a direct product.)

We shall study it near a puncture.

Write the connection in the form of an eqn.

$$\begin{array}{l} f_1(z) \text{ — sections} \\ \dots \\ f_n(z) \end{array} \qquad \text{(a basis near } z\text{)}.$$

Picard–Fuchs eqn. $\dfrac{\partial}{\partial z} = A(z)$



Uncertain reading. This line literally reads $\partial/\partial z = A(z)$, with no $f(z)$ on either side. A separate equation with $f(z)$ occurs below; both entries are retained.

Original source details: GELFAND-P000294

Transport $f_1(z)$ horizontally to $z + \delta z$ and expand in the basis [crossed out: $z + \delta z$, followed by illegible signs] $f_1(z + \delta z), \dots$



Uncertain reading. After “basis”, the cancelled sequence $z + \delta z$ has an illegible ending; there may be another z on the right. The uncancelled $f_1(z + \delta z), \dots$ is read separately.

Original source details: GELFAND-P000294

Consider any flat sect. of the bundle. it satisfies the eqn.

$$\frac{\partial}{\partial z} f(z) = A(z) f(z)$$

and all flat sects. are solutions of this eqn.

Example of flat sections.

Let Φ_z — a cycle in the fibre (K-dimensional).

Original source details: GELFAND-P000294

Uncertain reading. After "Let", a large heavily retraced letter reads Φ_z / ϕ_z; its original form and whether it was retraced or corrected are undetermined. The candidate Φ_z is shown.

$$\Phi_z \subset V_z, \qquad \Phi_{z'} \subset V_{z'}.$$

GELFAND-P000295

[source number: 62]

62

— an example of a flat section. —



Original source details: GELFAND-P000295

Uncertain reading. The first entry has two pairs of round parentheses; the outer ones extend downward toward the explanation. The retraced sign after f admits $f_i(z)$ / $f^i(z)$. Subscript i is shown; the parentheses' relation to the explanation below is undetermined.

$$\left(\begin{array}{c} (f_i(z), \phi_z) \\ \text{value of cohom. on hom.} \end{array} \right)$$

— a vector func.

Thm. (Griffiths)

$\exists$ a basis $f_i(z)$, such that the eqn. has a reg. singular point,

i.e. $zA(z)$ extends holomorphically to 0. (regular).

(Allows one to infer the behaviour of periods on approaching a singular point).

Corollary

Consider any flat section — a sol. of the eqn. Then it expands in a series

$$\sum_{n \le 0} z^{n/N} \left(\underline{C_{n0}} + \underline{C_{n1}} \ln z + \ldots + \underline{c_{nk}} \ln^k z \right)$$



Original source details: GELFAND-P000295

Uncertain reading. The index n / ν is heavily retraced. The bound sign resembles $\le$; $n \le 0$ is shown, with no established upper limit. The last initial letter is smaller than the earlier C signs and c-/e-shaped; its case and reading are undetermined, with candidate c_{nk} shown. Three coefficients are underlined.

Lemma $\forall$ flat sect. ϕ_z

$$|\Phi_z| \le C|z|^{-a}|\ln z|^b$$



Uncertain reading. The exponent on $|\ln z|$ has two crowded loops: b / β. The candidate b is shown. The bound has a large Φ, while the preceding line has a lighter ϕ; the distinction is retained.

Original source details: GELFAND-P000295

Diagram and typed description.

Original source details: GELFAND-P000295

GELFAND-P000296

7/IX-1970 yr. Seminar of Gelfand.

Seminar programme.

1. Kazhdan on the relation between formal and algebraic geometry.
2. Arnold: Griffiths's works.
3. Mityagin and Henkin on their works.

[cancelled number: 4.?] 1′. Moishezon on Artin's works.

Uncertain reading. Before the separate uncancelled 1′, a number or sign is densely cancelled, possibly 4.; the number has not been recovered.

Original source details: GELFAND-P000296

?. K-theory of finite groups

Brown, Tate, Tomson, Swan, Katz.

(Kazhdan, Bernstein, etc.)

4. Hironaka.

For next semester.

ζ-func. (p-adic harm. analysis).

Finite groups.

Kazhdan.

Where is this expounded?

part III, $N = 1$.



Original source details: GELFAND-P000296

Diagram and typed description.

Cohomology of aff. and proj. schemes.
1. Serre, "Coherent alg. sheaves".
2. More modern, but less pleasant Dieudonné Mat. 9:1
3. Lectures of Yu. I. Manin (part 1) Alg. geometry.
4. 3rd volume of Grothendieck I. H. E. S., vol. 12

Gelfand's remark: learn Serre's books "Finite groups" and "Lie gr. and Lie alg.".
(Part of the minimum in lin. algebra)



Original source details: GELFAND-P000296

Diagram and typed description.

↘
1 and 2nd part.

Part 1: Cohomology of coherent sheaves.

§1. Definition of a scheme.

A scheme — a ringed space of a special kind

Top. space, equipped with a sheaf of rings. O (structure sheaf).
X

Affine scheme. A — a comm. ring with 1.

Spec A Points — prime ideals $\wp \subset A$.

Original source details: GELFAND-P000296

Uncertain reading. The looped ideal sign admits $\wp$ / $\mathfrak{p}$ / p. Both occurrences show the nearest available glyph $\wp$; the letter's identity is undetermined.

Topology: $\forall$ I $\subset A$ assign the set of prime ideals $U_I \subset$ Spec A,
ideal
consisting of prime ideals

$$\wp \not\supset I.$$



Original source details: GELFAND-P000296

Uncertain reading. Between the prime-ideal sign and I is a rounded inclusion sign opening to the left, crossed by a slanting stroke. No separate lower equality bar is visible, and none is added. The precise inclusion convention is undetermined.

The sets U_I are called open.

GELFAND-P000297

[source number: 67]

Problem: check that a topology results.

A basis of open sets:

$$f \in A \rightsquigarrow U_f \subset \operatorname{Spec} A \quad \text{from} \quad \wp \ni f.$$



Original source details: GELFAND-P000297

Uncertain reading. The looped ideal sign admits $\wp$ / $\mathfrak{p}$ / p; the candidate $\wp$ is shown. The following sign has a rounded outline, a middle crossbar and a crossing stroke; $\ni$ is shown.

Problem: U_f — a basis.

Problem: the weakest separation ax. holds (of 2 points, 1 can be separated by a nbhd.)

Localization.

Let S — a multipl. set in A, not containing 0 (closed under mult.)

The ring A_S consists of pairs $\frac{a}{s}$:

$$\frac{a}{s} = \frac{a'}{s'} \iff \exists s'' \in S \qquad s''(s'a - sa') = 0.$$

Problem: this is an equivalence rel.

Later this will be needed for modules.

Struct. sheaf on Spec A:

$$\Gamma(U_f, O) = A_{\substack{\{f^n\},\\ n \geq 0}} \qquad S = \{f^n\}.$$

Reminder.

Def. of a sheaf.

A presheaf and $\forall U \subset X$ and a cover $\{U^*_\alpha\}$ of the set U the sequence is exact.

$$\{U^*_\alpha\} \subset U \qquad \left(\bigcup U^*_\alpha = U\right).$$



Original source details: GELFAND-P000297

Uncertain reading. Both signs are circles with a plus, shown as $\oplus$; beneath the first expression is "product of sets". The signs' meaning is undetermined.

$$F(U) \longrightarrow \underbrace{\bigoplus_{\alpha} F(U_\alpha)}_{\text{product of sets}} \rightrightarrows \bigoplus_{\alpha,\beta} F(U_\alpha \cap U_\beta).$$

$$F(U_\alpha) \longrightarrow F(U_\alpha \cap U_\beta)$$

$$F(U_\alpha) \longrightarrow F(U_\beta \cap U_\alpha)$$



Original source details: GELFAND-P000297

Uncertain reading. Three indices in the second line are heavily overwritten. The candidate $F(U_\alpha) \to F(U_\beta \cap U_\alpha)$ is shown; the left index admits α / β. The original strokes have not been recovered.

Question: why are these different arrows?

Exactness:

$$\operatorname{Im} i = \{\cdot \mid \varphi_1 = \varphi_2\}.$$

The stalk of a sheaf (presheaf) at pt. x etc.

Problem: prove that $\forall$ presheaf $\exists$ a sheaf with the same stalks (and unique)

Remark: to define a sheaf, it suffices to know the presheaf on a basis.

Original source details: GELFAND-P000297

Diagram and typed description.

End of reminder.

$$U_f \subset U_g \iff \exists n: \quad f^m = gh.$$

Uncertain reading. The sign between U_f and U_g is heavily overwritten; the outer contour $\subset$ is shown. The original sign is undetermined.

Original source details: GELFAND-P000297



Uncertain reading. After $\exists$, n is legible; the exponent on f has several joined arches: m / an overwritten n. The candidate f^m is shown; agreement with the quantifier is undetermined.

Original source details: GELFAND-P000297

(Equiv. to the thm. that $\bigcap$ of all prime ideals is the radical)

GELFAND-P000298

$$A_{\{g^n\}} \longrightarrow A_{\{f^n\}}.$$

$$\frac{a}{g} \longrightarrow \frac{ah}{f^m}, \qquad \frac{a}{g^k} \longrightarrow \frac{ah^k}{f^{mk}}.$$

Original source details: GELFAND-P000298

Diagram and typed description.

Prescheme: a ringed space, loc. isom. to an aff. scheme.

Problem. $\forall f \in A$, $(U_f, O) =$ an aff. scheme

Product of preschemes. Spec A, Spec B

$$\text{Spec}\, A \times \text{Spec}\, B = \text{Spec}(A \otimes B)$$

Problem: determine def. of two preschemes.



Uncertain reading. After “determine”, the short source word admits “опред.” (def.) / “произв.” (prod.); “def.” is shown. The repetition has not been removed.

Original source details: GELFAND-P000298



Original source details: GELFAND-P000298

Diagram and typed description.

example.
(Z_2 and Z_3).
Spec Z_2 × Spec Z_3 —
— the empty set.



Original source details: GELFAND-P000298

Diagram and typed description.

Improvis.
of Kirillov

$$\begin{array}{cc} X, & Y \\ \| & \| \\ \bigcup X_\alpha & \bigcup Y_\beta \end{array}$$

— preschemes



Original source details: GELFAND-P000298

Uncertain reading. The Y in the cover and the Y signs in the right-hand intersection are heavily retraced with extra strokes; the final Y signs are legible, but the original letters are undetermined.

in $\bigcup\limits_{\alpha}(X_\alpha \times Y_\beta)$



Original source details: GELFAND-P000298

Uncertain reading. The small darkened union index has a loop and several rays: α / $*$ / an overwritten sign. The candidate α is shown; no second index is added.



Original source details: GELFAND-P000298

Diagram and typed description.

$$\begin{array}{cc} X_\alpha \times Y_\beta & X_{\alpha'} \times Y_{\beta'} \\ X_\alpha \cap X_{\alpha'} & Y_\beta \cap Y_{\beta'} \\ \| & \| \\ \bigcup X_\gamma & \bigcup Y_\delta \end{array}$$

Lemma: $X_\alpha \subset X_{\alpha'}, Y_\beta \subset Y_{\beta'} \Rightarrow X_\alpha \times Y_\beta \subset X_{\alpha'} \times Y_{\beta'}$.

See Serre.

A prescheme X is called a scheme if $\Delta \subset X * X$ is closed.



Original source details: GELFAND-P000298

Uncertain reading. Between X and X is a small many-rayed sign with a dark centre: $*$ / a retraced $\times$. The star-shaped form is shown as $*$.

Problem: prove that an aff. scheme is a scheme.

Let X — an arbitr. prescheme, $\mathcal{F}$ — a sheaf of $\mathcal{O}$-modules over [cancelled sign: x?] X.

Original source details: GELFAND-P000298

Uncertain reading. Between "over" and X, one sign is densely cancelled, possibly x; the original letter is undetermined.

It is called quasicoherent if it is loc. isom.

GELFAND-P000299

[source number: 68]

to the cokernel of the map:

$$\underbrace{O^R}_{\text{direct sums.}} \xrightarrow{\varphi} O^T.$$

S, T — arbitrary sets.



Uncertain reading. The first exponent is heavily retraced: R / an overwritten S. The candidate $O^R \to O^T$ is shown; the following line separately has S, T. Beneath the first O is "direct sums.".

Original source details: GELFAND-P000299

Problem: give an example of a nonquasicoherent sheaf.

Theorem. Let A — a comm. ring and Spec A — an aff. scheme.

The map from the categ. of quasicoherent sheaves of modules

$$\mathcal{F} \longrightarrow \Gamma(\text{Spec}\, A, \mathcal{F})$$

to the categ. of modules is an isomorphism.

I.e. the categ. of q.-c. sheaves of mod. over the aff. scheme A is isom. to the categ. of modules over A.

(The module of glob. sections.)

(This is equivalent to saying that for aff. spaces the cohom. are zero)



Uncertain reading. No cohomological degrees or coefficients are specified in this separate phrase.

Original source details: GELFAND-P000299

A quasicoherent sheaf of modules is determined by its glob. sections.

28/IX.

Direct and inv. image of sheaves.

$$X \xrightarrow{f} Y, \qquad X, Y \text{ — top. spaces,}$$

$\mathcal{F}$ — a sheaf on X,

$$\Gamma(U, f_*\mathcal{F}) := \Gamma(f^{-1}(U), \mathcal{F}), \qquad U \subset Y$$

a presheaf on Y results.

Exercise (easy) — this presheaf is a sheaf

Example: if Y — a point, then $f_*\mathcal{F}$ — the group of sections of the orig. sheaf,

($f^{-1}(U)$ may also be empty, then the set of sections is empty).



Uncertain reading. The source twice says “empty”: “may also be empty, then the set of sections is empty”; both words are rendered literally.

Original source details: GELFAND-P000299

A very important concept.

Inverse image.

$$X \xrightarrow{f} Y$$

$\mathcal{G}$ — a sheaf on Y

GELFAND-P000300

The sheaf $f^*\mathcal{G}$ is defined as follows:

$\forall \mathcal{F}$ on X the equality holds:



Original source details: GELFAND-P000300

Uncertain reading. The number with a closing parenthesis above the frame's right edge is heavily retraced: 1) / an overwritten number. The candidate 1) is shown. Below the left Hom, a vertical stroke leads to "set of morphisms over X".

$$\boxed{\mathrm{Hom}(f^*\mathcal{G},\mathcal{F}) = \mathrm{Hom}(\mathcal{G}, f_*\mathcal{F})}^{1)}$$

set of morphisms over X

I.e. $\forall$ sheaf $\mathcal{F}$ a one-to-one corr. between these sets is given, compatible under morphisms of $\mathcal{F}$ into one another.

(An isomorphism of functors on the cat. of sheaves).

Construction, proving the existence of $f^*\mathcal{G}$

[A short expression is cancelled: ?]

Original source details: GELFAND-P000300

Uncertain reading. Beneath several diagonals are a Γ/F-shaped letter, rounded outlines and a U-shaped sign: $F(U)$ / $\Gamma(U,\mathcal{G})$; the expression is undetermined.

$$\Gamma(U, \overline{f^*\mathcal{G}}) = \varinjlim_{V \supset \overrightarrow{f(U)}} \Gamma(V, \mathcal{G})$$



Original source details: GELFAND-P000300

Uncertain reading. The first argument of the final Γ is heavily overwritten: V / U / a retraced V. The candidate V is shown; the original strokes are undetermined.

this equality defines a presheaf $(V \subset Y)$

Exercise: the sheaf assoc. to it is the inverse image



Original source details: GELFAND-P000300

Diagram and typed description.

Example.



When $U \subset X$ is a point, then $\mathcal{G}$, $U = X$ — also $\mathcal{G}$. Not a sheaf.

---

1) Definition of Hom:

A map $\mathcal{F}_1 \longrightarrow \mathcal{F}_2$ over X is called [cancelled word: ?] a collection of maps

Uncertain reading. After “is called” and before “a collection”, a short word is cancelled; a lower loop and right-hand vertical strokes are visible, but no reliable letters are established.

Original source details: GELFAND-P000300

$$\varphi_U : \Gamma(U, \mathcal{F}_1) \longleftrightarrow$$
$$\longrightarrow \Gamma(U, \mathcal{F}_2)$$
$$\forall U \subset X.$$



Uncertain reading. At the first line's end, the arrow has a right head and short left-hand strokes resembling a second head; the two-headed form is shown. A separate arrow on the next line points right. Whether the left strokes are a correction is undetermined.

Original source details: GELFAND-P000300

and commute with the restriction opers. (A morphism of functors)

GELFAND-P000301

[source number: 69]

69



Original source details: GELFAND-P000301

Uncertain reading. The cancelled line has a frame open at the top; bars are visible above both G signs. Bars over F cannot reliably be separated from upper loops and cancellation strokes; the candidate $\mathrm{Hom}(\overline{G}, \mathcal{F}) = \mathrm{Hom}(\overline{G}, \overline{\mathcal{F}})$ is shown.

~~$\mathrm{Hom}(\overline{G}, \mathcal{F}) = \mathrm{Hom}(\overline{G}, \overline{\mathcal{F}})$~~

— def. of the sheaf corr. to a presheaf

$$\mathrm{Hom}(\mathcal{F}, G) = \mathrm{Hom}(\overline{\mathcal{F}}, G)$$

$\overline{\mathcal{F}}$ — a presheaf, $\mathcal{F}$ — the assoc. presheaf.



Uncertain reading. The right-hand entry literally says "the assoc. presheaf."; the word "presheaf" is repeated.

Original source details: GELFAND-P000301

$\overline{\mathcal{F}} \longrightarrow \mathcal{F}$ — a map (of presheaves) must be given



Diagram and typed description.

Next time is skipped.

Original source details: GELFAND-P000301

Reminder, § 2.

Cohomology.



Original source details: GELFAND-P000301

Uncertain reading. Before “general-categ.” is a darkened multiline sign resembling a star or an overwritten A-shaped letter; its meaning is undetermined. Two vertical rules appear at the left; both captions have lower frame strokes.

X — a top. space,		$H^i(\mathcal{F})$,	$\check{H}^i(\mathcal{F})$.
$\mathcal{F}$ — a sheaf	☆	general-categ.	Čech.

$H^i(\mathcal{F})$ — a deriv. functor of the sections functor.

Consider the category C of sheaves of ab. groups over the space X

Lemma 1. — this is an abelian category.

Inject. sheaves are important.

Lemma 2. There are enough inject. objects (any sheaf embeds in an inject. sheaf).

Functor to a sheaf $\longrightarrow$ sections over all of X.

$$0 \longrightarrow \Gamma(\mathcal{F}') \longrightarrow \Gamma(\mathcal{F}) \longrightarrow \Gamma(\mathcal{F}'')$$

Γ — a semiexact functor (on the left), and since there are enough inject. objects, the derived functors are defined.

Let X — a top. space $\{U\}$ — a basis of the topology in X, such that

$$\check{H}^i(\mathcal{F}, \{u_i\}) = 0, \qquad i > 0.$$

Then the actual cohom. [cancelled: calc.?] agree with the Čech calc.



Original source details: GELFAND-P000301

Uncertain reading. After “actual”, a short word beginning with a в-shaped loop is cancelled: “выч.” / “вычисл.” (calc.); its ending is undetermined.

And one can calc. them in acycl. covers.



Original source details: GELFAND-P000301

Uncertain reading. Slanted quadrilateral outlines, inner frames, dark triangular regions and short edge strokes. The reconstruction follows the visible contours; labels, exact internal-stroke junctions and mathematical purpose are undetermined.



GELFAND-P000302

An ellipt. syst. of order 2 — on a manif. without lower-order terms. Does it have solutions?

For the Laplace oper. it is known that there are none

The number of solns. $(\text{mod } 2)$.

In principle max is topology

(The Dirichlet prob. has a 0-th solution)

Kazhdan on one specific work.

G — a compl. semis. group (A_n or D_n).

A reg. elem. — if the centralizer has rank $n-1$.

Subreg. — if dim of the centralizer is $n-2$,

(two coincident eigenvals.)



Original source details: GELFAND-P000302

Uncertain reading. The underlined entries are $n-1$ and $n-2$; a separate small sloping stroke beneath the first minus is shown separately. “rank” and “dim” are distinct; the role of n is unspecified.

Consider

$$G \xrightarrow{\varphi} H/W \qquad \begin{array}{l}(W \text{ — the Weyl gr.}\\ H \text{ — a Cartan subgroup})\end{array}$$

An elem. [cancelled: sub / not?] is reg. $\Longleftrightarrow$ the map is reg. there.

Original source details: GELFAND-P000302

Uncertain reading. Before the clean entry “reg.”, several letters are cancelled: “суб” (sub) / “не” (not); the original prefix is undetermined.

$12/\overline{\underline{X}}$.

Original source details: GELFAND-P000302

Diagram and typed description.

Rota’s conjecture.

Fix a finite field F_q.

Let there be given ℓ and $k > \ell$. Then $\exists N$ [above the line: such?], that if one partitions the ℓ-dimensional subspaces in an N-dimensional subspace,



Original source details: GELFAND-P000302

Uncertain reading. Above the line after N is the candidate “такое” (such), with dense crossing strokes; the underlying lettering and possible cancellation of part of the word are undetermined.

[cancelled: that?]



Original source details: GELFAND-P000302

Uncertain reading. Before the clean entry “then”, a short word is cancelled: “что” (that) / “то” (then); crossing lines obscure the middle and the reading is undetermined.

then $\exists$ k-dimensional one, such that all subspaces of this k-dimensional one fall into one of the classes.

$$F^N \supset E \qquad \dim E = k$$

and all its ℓ-dim. subsp. are in one class.

For $\ell = 1$ it is proved.

One can use proj. terms (there a line is a point).

If P^N is partitioned into 2 classes, there is a line in one class.

GELFAND-P000303

[source number: 70]

Kazhdan.

A quasicoherent sheaf — a sheaf loc. isom. to the cokernel of a map of free sheaves.

Example. A — a ring, M — a module, $\mathcal{F}_M$ — a sheaf of modules on Spec A.

$(\dot{S}) \subset A$ (multipl. syst.) $\qquad M_S \qquad \frac{m}{s} = \frac{m'}{s'}$ if $s''(s'm - sm') = 0$.



Original source details: GELFAND-P000303

Uncertain reading. Small separate strokes are visible above the parenthesized S; no definite additional symbol, index or prime mark is established.

$$M_f = M_{(f^n)}.$$

Sect. on U_f are M_f.

$$\Gamma(U_f, \mathcal{F}_M) = M_f.$$

The check is left to the listeners.

Lemma: this is a sheaf.

Another def. of a quasicoherent sheaf.

Def. 2. Quasicoherent sheaves — sheaves loc. isom. to a sheaf of the form $\mathcal{F}_M$.

Problem: prove equiv. of the definitions.



Original source details: GELFAND-P000303

Uncertain reading. At the right, beyond two nearly vertical rules, a short word is cancelled: “изом.” / “изом.:” (isom.); M follows. Cancellation obscures the middle of the word; its reading is undetermined.

// [cancelled: isom.?] M

Main theorem.

Spec A

$\forall$ quasicoherent sheaf $\mathcal{F}$ on an aff. scheme has the form $\mathcal{F}_M$, where M is an A-module.

Problem (sol.)



Original source details: GELFAND-P000303

Diagram and typed description.

$$M = A^n \Rightarrow \mathcal{F}_M = \mathcal{O}^n, \qquad \begin{array}{l} A^m \longrightarrow A^n \longrightarrow M \\ \mathcal{O}^m \longrightarrow \mathcal{O}^n \longrightarrow \mathcal{F}_M. \end{array}$$

In the reverse direction:

$$\mathcal{O}^m \longrightarrow \mathcal{O}^n \longrightarrow \mathcal{F} \quad \text{loc.}$$

[overwritten: and?] then sect. $A^m \longrightarrow A^n \longrightarrow M$.

Uncertain reading. Before "then sect." is a dark overwritten sign: "и" (and) / "не" (not), with an extra right-hand loop; original and later strokes cannot be separated.

Original source details: GELFAND-P000303

Proof of the theorem.

$$\mathcal{F} \qquad M = \Gamma(X, \mathcal{F}).$$

$$\forall f \in A \qquad \Gamma(U_f, \mathcal{F}) = M_f.$$

$\forall$ aff. scheme is quasicompact (no separation). From $\forall$ open cover select a finite one.

GELFAND-P000304

$$\mathcal{F}|_{U_{f_i}} = \mathcal{F}_{M_i}, \qquad M_i \quad A_{f_i}\text{-module.}$$

There is a nat. map



Diagram and typed description.

$$M_f \longrightarrow \Gamma(U_f, \mathcal{F}).$$

Original source details: GELFAND-P000304

$1/f \in \Gamma(U_f, \mathcal{O}_X)$, and $\mathcal{F}$ — a sheaf of modules.

Tomson as expounded by Gelfand I. M.

(G, M) — a pair.

G — a group, $F_p = \overline{Z}/pZ$.



Uncertain reading. A separate short horizontal stroke appears above the first Z; it is shown as an overbar, but its mathematical function is undetermined.

Original source details: GELFAND-P000304

M — a module over F_p, and faithful irred. a repr. of G in M.

Require that [cancelled sign: M?] G be generated by a collection $\langle Q \rangle$, of such elems.:

Uncertain reading. Before the clean G, a tall sign with several nearly vertical strokes is cancelled, possibly M; its letter is undetermined.

Original source details: GELFAND-P000304

~~if~~ if $g \in Q$, then $M(g-1)^2 = 0$.

(Example: a matrix group generated by elems. with Jordan blocks of order 2).

It is proved that over the finite field F_p with $p > 5$ G can only be a class. group: S, O etc. (except E_8).



Uncertain reading. The entry says “can only be a class. group: S, O etc.” and separately “(except E_8)”. The qualification’s scope is undetermined; no further hypotheses are written in this paragraph.

Original source details: GELFAND-P000304

Characteristics 2 and 3 remain.

Diagram and typed description.

Original source details: GELFAND-P000304

Kirillov from Tomson's account.

Another finite simp. group (Conway) —

— belonging to no series.

The automorphism gr.

[margin: в]

[Cancelled: $R^{24} \supset Z^{24}$?; then an illegible cancelled word.]



Uncertain reading. The cancelled line has R^{24}, an inclusion sign and Z^{24} / L^{24}, then an illegible word; the candidate Z^{24} is shown. Later loops prevent separating the original letter.

Original source details: GELFAND-P000304

$$R^{24} \supset \underset{\text{lattice}}{L} .$$

1) unimodular — the fund. domain has unit volume.

2) ~~(λ_i, λ_j) — integers.~~



Uncertain reading. In the cancelled pairing, the first index admits i / c and the second resembles j; (λ_i, λ_j) is shown. Cancellation obscures the first index's dot and lower stroke; "— integers" is cancelled with the pair.

Original source details: GELFAND-P000304

(λ, μ) is always an integer, and (λ, λ) is even.

GELFAND-P000305

[source number: 71]

3) $\min(\lambda, \lambda) = 4$.



Original source details: GELFAND-P000305

Uncertain reading. The range of $\min(\lambda, \lambda)$ and a condition $\lambda \neq 0$ are not written.

[Cancelled: 4)?]

Original source details: GELFAND-P000305

Uncertain reading. Before "Such a lattice", a short sign with a parenthesis is cancelled, possibly 4); its original and cancelling strokes cannot be separated.

Such a lattice is uniquely det. up to autom.

The signature is div. by 8 for pos. def. forms.



Original source details: GELFAND-P000305

Diagram and typed description.

To read on alg. geom. ‖ 1) Serre, 2) Manin 3) Dieudonné 9:1?

Original source details: GELFAND-P000305

Uncertain reading. After Dieudonné there is a looped sign with a lower tail, followed by : 1; the candidate 9:1 is shown, with "Э:1" also possible. The note's function is undetermined.

19/X. I. M. Gelfand.

Let a sheaf of modules be given on X.

A, $X = \operatorname{Spec} A$, M — a module, $\mathcal{F}_M$ — the corresp. sheaf (sheafification of the module M).

Example of a non-quasi-coh. sheaf over Spec A:

fibre A at the point x and 0 at the other points.

$$\Gamma(U,\mathcal{F}) = \begin{cases} A & \text{if } x \in U, \\ 0 & \text{if } x \notin U. \end{cases}$$



Original source details: GELFAND-P000305

Uncertain reading. The first argument of Γ is heavily overwritten: U is shown, possibly over X or another sign. Both U signs in the conditions at the right are clear; the original and correcting letters at the left cannot be recovered separately.

Original source details: GELFAND-P000305

Uncertain reading. A quadrilateral frame with crossing strokes, an upper angle, a dark right-hand junction with a slanting trace, and a short upper-left trace. The visible lines are encoded; their purpose and the composition of possible arrowheads are undetermined. No labels are visible.





Original source details: GELFAND-P000305

Diagram and typed description.



Example (I. Bernstein).

$\mathbb{C}^n$, I — an ideal in the polynomial ring; to it there corresp. a subvariety, $\underset{M}{\frac{P}{Q}}$ is def. at every point of the subvariety.

Original source details: GELFAND-P000305

Uncertain reading. The ideal's letter admits I / J: an upper wavy stroke, a right stem and a lower left hook. The candidate I is shown in the first entry and in mod; lower J-shaped signs are shown as J, including the indices. This is not an established distinction of notation; the exact letter remains uncertain.

Then to it there corresp. a polynomial R such that

$$\boxed{\frac{P}{Q} = R \pmod{I}} \text{ (on it)}$$



Original source details: GELFAND-P000305

Diagram and typed description.

More prec. thm.: if it is locally such.

$A = \mathbb{C}[x_1, \ldots, x_n]$, $\mathcal{O}_X$ — the struct. sheaf on $\underline{X = \operatorname{Spec} A}$.

$$\underline{\operatorname{Spec} A \supset \mathbb{C}^n}.$$

(not only on $\mathbb{C}^n$).

$$\underline{\underline{J \subset \mathcal{O}}}$$
subsheaf

J — the ideal $(f_1, \ldots, f_n)$, a module over A.
$\mathcal{F}_J$ — the corresp. sheaf, $\mathcal{F}_J \subset \mathcal{O}_X$.

$$(J \subset A \Rightarrow \mathcal{F}_J \subset \mathcal{F}_A).$$

GELFAND-P000306

$$0 \longrightarrow I \longrightarrow A \longrightarrow M \longrightarrow 0, \qquad \underline{M = A/I}.$$

$$0 \longrightarrow \mathcal{F}_I \longrightarrow \mathcal{O}_X \longrightarrow \mathcal{F}_M \longrightarrow 0.$$



Original source details: GELFAND-P000306

Uncertain reading. The ideal's letter in the sequence, denominator and index admits I / J; the provisional candidate I is shown. The upper wavy stroke and lower hook do not establish the exact letter.

[Cancelled: $\mathcal{F}_M$ — rat. f-n?]

Original source details: GELFAND-P000306

Uncertain reading. After the cancelled $\mathcal{F}_M$, "рац. ф-" is legible; the final letter admits а / я / и. The candidate "ф-а?" is shown as "rat. f-n?"; the later clean "rat. f-n" does not resolve the cancelled entry.

Sections of the sheaf $\mathcal{F}_M$:

1) constr. from M

2) from the exact seq.

Let Y — the set of zeros of the ideal I.

P/Q — a rat. f-n, $Q \neq 0$ on Y.

$$P/Q \in \Gamma(X, \mathcal{F}_M) \qquad \text{from exactness of the sequence.}$$

Consider X_Q [a small sign is cancelled] and $X \setminus Y$.

Original source details: GELFAND-P000306

Uncertain reading. Between X_Q and "and", a small sign with crossing strokes is cancelled; its original letter is undetermined.



Original source details: GELFAND-P000306

Diagram and typed description.

here P/Q in $\mathcal{O}_X$.

Over $X \setminus Y$ consider the section $\equiv 0$.

$$0 \in \Gamma(X \setminus Y, \mathcal{F}_M).$$

$$i\left(\frac{P}{Q}\right) \in \Gamma(X_Q, \mathcal{F}_M).$$

Construct a section of the sheaf on X.

On the intersection they agree, since sections of $\mathcal{F}_M$ on $X \setminus Y$ are ident. 0, since $\mathcal{F}_M$ is supported on Y.

But! a section of this sheaf is an elem. of M — a polynomial.

[A sign is cancelled at the left: $\mathcal{O}$?]

Original source details: GELFAND-P000306

Uncertain reading. Before the first $\mathcal{O}_X$ is a dark corrected sign with a long loop and a rising right stroke, possibly $\mathcal{O}$; the upper-right stroke cannot be separated from the cancellation.



Original source details: GELFAND-P000306

Diagram and typed description.

$$\mathcal{O}_X^I \longrightarrow \mathcal{O}_X^J \longrightarrow \mathcal{F} \longrightarrow 0 \qquad U_f$$

$$A^I \longrightarrow A^J \longrightarrow M \longrightarrow 0.$$



Original source details: GELFAND-P000306

Uncertain reading. The superscript pair is provisionally shown as I, J: the first has a hook without a closed lower loop, the second has a loop and a cross-stroke. The same pair recurs on A; the names of the indexing sets are undetermined.



Original source details: GELFAND-P000306

Diagram and typed description.

$\mathcal{F} = \mathcal{F}_M$



Original source details: GELFAND-P000306

Diagram and typed description.

For home:

GELFAND-P000307

[source number: 72]

72

Ya. Sinai. Noncommut. probability theory.

H — finite-dimensional Hilbert. dim $H = 2$ already nontriv.

$\ldots, H_{-1}, H_0, H_1, H_2, \ldots$ with a fixed isom. onto H (basis).

I — a finite subset,

$$H_I = \bigotimes_{i \in I} \text{[a sign is cancelled]}\, H_i. \qquad \dim H_I = 2^k, \quad \text{where } k = |I|.$$



Original source details: GELFAND-P000307

Uncertain reading. Between $\otimes$ and the clean H_i is a dark cancelled sign with several vertical strokes; an earlier H is possible, but the original entry is undetermined.

$\alpha(I)$ — the algebra of matrices over H_I. [Cancelled: “Всем” (to all)?]

Original source details: GELFAND-P000307

Uncertain reading. After the full stop following H_I, a short looped word is cancelled, resembling “Всем” / “всем” (to all); crossing strokes prevent the complete word from being established.



Original source details: GELFAND-P000307

Diagram and typed description.

$$I_1 \subset I_2 \implies \alpha(I_1) \subset \alpha(I_2).$$

$(\ldots \otimes 1)$.

Elems. of $\alpha(I)$ — local observations.

Close $\bigcup \alpha(I)$ in the uniform metric.

$$[-n, n].$$

$$\alpha([-n, n]) \subset \alpha([-n-1, n+1]).$$

closed in norm (completion) (uniform).

Obtain the algebra $\underline{\alpha}$ quasilocal observations. (with invol.).

Probability th. — Ω — a space (compact), on $C(\Omega)$ positive functionals (probability distrs.).
α plays the role $C(\Omega)$.

A state φ on α [a sign is cancelled: φ?] — a positive normalized functional (probability distr.).

Original source details: GELFAND-P000307

Uncertain reading. After α, a looped sign with a long lower stroke and several oblique strokes is cancelled; φ is possible, but original and cancelling lines cannot be separated.

$$\varphi(a) \geq 0 \quad \text{when } a \geq 0; \qquad \varphi(e) = 1.$$

$\varphi(a^*)$ — real when $a^* = a$.

1. State of measure type.

Consider the values of the functional on $\alpha(I)$.

$$\varphi(a) = \operatorname{tr}(\rho_I \cdot a), \qquad \text{where } \rho_I \geq 0, \quad \operatorname{tr} \rho_I = 1.$$

State of measure type — the eigenv. of ρ_I agree in the following sense:

in H_i there exists a basis $(e_1^{(i)}, e_2^{(i)})$ — a basis in H_i (depends on φ).



Original source details: GELFAND-P000307

Uncertain reading. In the first H_i, the subscript has upper and lower bars with a separate dot above; i / I are possible. The candidate i is shown; the second H_i has a shorter sign. The case of the first index is undetermined.



Original source details: GELFAND-P000307

Diagram and typed description.

$\bigotimes_{i_s \in I} e_{k_s}^{(i_s)}$ — a basis in H_I

They — eigen.
for ρ_I

GELFAND-P000308

$$\varphi\left(\bigotimes e_{k_s}^{(i_s)}\right) = \mu(k_1, \ldots, k_s). \qquad \sum \mu(\,) = 1.$$

probability distr.

A measure on the space of seqs. taking the values 1 and 2.

2. States generated by a Hamiltonian.

$A \in \alpha((0,1)), \qquad H((I))$.

On $[-n, n]$ consider



Original source details: GELFAND-P000308

Diagram and typed description.

$$H_n = \sum_{i=-n}^{n-1} A_i$$

A_i — shifted A.

$$\varphi_n(a) = \frac{\operatorname{tr} e^{-\beta H_n} \cdot a}{\operatorname{tr} e^{-\beta H_n}}.$$



Uncertain reading. In the numerator, a separate dot precedes a after $e^{-\beta H_n}$; no round parentheses enclose the expression under the trace. The scope of tr relative to a is unspecified.

Original source details: GELFAND-P000308

$$\varphi(a) = \lim_{n\to\infty} \varphi_n(a) \text{ exists} \quad \forall A. !$$

This is called a state, generated by the Hamiltonian A.

(from the quantum Gibbs distr.)

A noncommut. analogue of Markov chains.

Let φ — a state. A weakly closed ring of opers. in Hilbert space is constructed.

In the alg.

$$\langle a_1, a_2 \rangle = \varphi(a_2^* \cdot a_1).$$

Quotient by the ideal ...

H_φ — Hilbert space.

[Crossed out: $h \in H_\varphi$]

Uncertain reading. At the left, $h \in H$ with a small looped index resembling φ is cancelled. Oblique cancelling strokes cross the index; the candidate H_φ is shown without recovering its earlier strokes.

Original source details: GELFAND-P000308

$$h \in H_\varphi \implies L_a = ah.$$

Weak closure — M_φ.

when is it a factor?
Mainly of type 3.

GELFAND-P000309

[source number: 73]

26/X. Kazhdan.

73

Triviality of the cohom. of a quasicoher. sheaf on an aff. scheme.

Original source details: GELFAND-P000309

Uncertain reading. Between A^n and Spec is a dark overwritten sign with two horizontal regions and a rounded left portion. The candidates $=$ / an inclusion or membership sign remain unresolved.



Original source details: GELFAND-P000309

Diagram and typed description.

A^n [a sign is cancelled] Spec $\mathbb{C}[x_1, \ldots, x_n]$

$\downarrow$

X closed — a subvar. (alg.).



Original source details: GELFAND-P000309

Diagram and typed description.

A^n — the space of max. ideals

$Q|_X \neq 0$, then P/Q — a func. on X, $\forall P$.
Then $\exists R$ — a polynomial, $(\forall P \exists R)$.

$$\left.\frac{P}{Q}\right|_X = R|_X.$$

Consider the ideal corresp. to X (0 on X),
$F_1, \ldots, F_k$ — a basis of this ideal.
Then $(F_1, \ldots, F_k, Q) = k[x_1, \ldots, x_n]$.
[A sign is cancelled: H / R?]

Original source details: GELFAND-P000309

Uncertain reading. Before the opening parenthesis is a cancelled short sign with several upright and oblique strokes; H / R are possible, but its original letter is undetermined. No closing parenthesis is visible in the following phrase.

(this ideal is not contained in any maximal
$\exists$ polynomials $L_0, \ldots, L_k$.

$$L_0 Q + L_1 F_1 + \ldots + L_k F_k = P;$$

Hence one can take $R = L_0$.
(Hilbert's thm. — description of max. ideals)
This proof is analogous to the proof of triviality of cohomology
(this is triviality of 1-dimensional cohomology).
$X = \operatorname{Spec} A$, A [a sign is cancelled: $=$?] $(f_1, \ldots, f_n)$.

Original source details: GELFAND-P000309

Uncertain reading. Between A and $(f_1, \ldots, f_n)$, horizontal strokes are heavily overwritten, with an additional oblique line below. A cancelled $=$ is shown as a candidate; the exact earlier sign is undetermined.

Consider $X_i = X_{f_i}$.

$$A = (f_1, \ldots, f_n) \Longleftrightarrow X = \bigcup X_i.$$

Let M — A-module, $\mathcal{F}_M$ — the corresp. sheaf.
Čech complex:
q-chain: $\forall$ index collection $1 \leq i_0$, [two overwritten signs: $<$?] $\ldots, i_q \leq n$ is given

Original source details: GELFAND-P000309

Uncertain reading. A separate comma descends immediately after i_0. Two dark overwritten signs lie between it and the ellipsis; the candidate $<$ remains unresolved. A comma is also visible before i_q.

$$m_{i_0\dots i_q} \in \Gamma(X_{i_0} \cap \dots \cap X_{i_q}), \mathcal{F}_M) = \\ = M_{f_{i_0}\dots f_{i_q}}.$$



Uncertain reading. After the last X_{i_q} and before the comma is a tall curved stroke, shown as). It is followed by $\mathcal{F}_M)$ and an equals sign; on the next line an equals sign repeats before $M_{f_{i_0}\dots f_{i_q}}$. Identification of the curved stroke as a closing parenthesis remains provisional.

Original source details: GELFAND-P000309

GELFAND-P000310

$$(dm)_{i_0\dots i_q} = \sum_{0\le j\le q+1} (-1)^j m_{i_0\dots\widehat{i_j}\dots i_{q+1}}.$$

$d : C^q \longrightarrow C^{q+1}$.
$d^2 = 0$ and the cochains form the Čech complex



Uncertain reading. After M, before the comma, a tall looped letter is cancelled. The formula provisionally shows the candidates F/φ; the original sign is undetermined.

Original source details: GELFAND-P000310



Original source details: GELFAND-P000310

Diagram and typed description.

$$C^*(M\,[F/\varphi?], \{f_i\})$$

$$\cup$$

antisymm. cochains — $C(M, \{f_i\})$

(subspace)

Prop.: the cohomologies coincide (the isom. is induced by inclusion).
For convenience — sometimes C^*, sometimes C.
Theorem: $H^q(\{X_i\}; \mathcal{F}_M) = 0$ for $q \neq 0$.
Proof: Let $m_{i_0\dots i_q} \in M_{f_{i_0}\dots f_{i_q}}$ — cycles.

There we had $A = (f_1, \dots, f_m, Q)$,

$$m_{i_0 i_1} \in M_{f_{i_0} f_{i_1}},$$
$$(dm)_{i_0 i_1 i_2} = m_{i_0 i_1} - m_{i_0 i_2} + m_{i_1 i_2} = 0.$$

Need to prove:

$$\exists n_i \in M_{f_i}$$
$$m_{i_k i_\ell} = n_{i_k} - n_{i_\ell}.$$



Original source details: GELFAND-P000310

Uncertain reading. The letter before i after $\exists$ is heavily overwritten; the candidate n_i is provisional. The small subscripts on m are also overwritten; the reading $i_k i_\ell$ is not final.

Ex.: $(M_f)_g = M_{fg}$.

[Cancelled; provisional reading: $(\sum L_{ijk} f_i f_j f_k = 1)$.]



Original source details: GELFAND-P000310

Uncertain reading. Oblique strokes cancel the sum, coefficient, and product. The candidate L_{ijk}, the small subscripts on f, and the final $= 1$ remain uncertain; the right parenthesis is visible.

$m_{1,i} = n_1 - n_i$.

Put $n_1 = 0$, [a sign is cancelled: m?]

Original source details: GELFAND-P000310

Uncertain reading. Before $n_i = -m_{1,i}$, a short sign is densely crossed out; m is possible, but the original reading is undetermined.



Original source details: GELFAND-P000310

Diagram and typed description.

$n_i = -m_{1,i}$ $\quad i > 1$

False, since $m_{1,i}$ has the form

$$\frac{m}{f_1^k f_i^\ell},$$
$$\frac{m}{f_2 f_i^\ell},$$
$$\vdots$$

and combine, using the fact that this is a cover.

[source number: 74]

[Cancelled: “Consider.”?] For simplicity, let $q = 1$.

Original source details: GELFAND-P000311

Uncertain reading. After the initial R-shaped letter, several horizontal strokes obscure the middle letters. The candidate “Consider.” remains provisional.

Given $m_{i_0 i_1} - m_{i_0 i_2} + m_{i_1 i_2} = 0$. $\quad 1 \le i_k \le n$.

Original source details: GELFAND-P000311

Uncertain reading. Before $m_{i_0 i_2}$ is a dark overwritten sign with two horizontal regions and a short lower extension. A minus is shown as a candidate; the earlier sign is unrecovered.

Need to find $n_i \in M_{f_i}$: $\quad m_{i_0 i_1} = n_{i_0} - n_{i_1}$.

$m_{i_0 i_1} =$ [a cancelled fraction: $\bar m / f_{i_0}$?] $\dfrac{\bar m_{i_0 i_1}}{f_{i_0}^N f_{i_1}^N}$, $\quad \bar m \in M$.

Original source details: GELFAND-P000311

Uncertain reading. Oblique strokes cross the old numerator and fraction bar. The reading $\bar m / f_{i_0}$ is provisional; a second denominator factor in the old expression is unrecovered.

Find $L_i \in X_i$;

$$\sum L_i f_i^N = 1.$$

Define

$$\bar n_{i_0} = \sum_{i_1} L_{i_1} \bar m_{i_0 i_1} / f_{i_0}^N \in M_{f_{i_0}}.$$



Original source details: GELFAND-P000311

Uncertain reading. The digits in the summation index and on L are heavily overwritten. The candidate i_1 is shown; some surviving strokes also resemble 2. The reading remains provisional.

$$\bar n_{i_0} - \bar n_{i_1} = \sum_i \left(\frac{L_i}{f_{i_0}^N} \bar m_{i_0 i} - \frac{L_i}{f_{i_1}^N} \bar m_{i_1 i} \right) =$$

$$= \frac{1}{f_{i_0}^N f_{i_1}^N} \sum L_i f_i^N \underbrace{\left(\frac{\bar m_{i_0 i}}{f_{i_0}^N f_i^N} - \frac{\bar m_{i_1 i}}{f_{i_1}^N f_i^N} \right)} =$$

$$[\text{a sign is cancelled}] \quad = \sum L_i f_i^N \underbrace{(m_{i_0 i} - m_{i_1 i})}_{m_{i_0 i_1}} = m_{i_0 i_1}.$$



Uncertain reading. In the first line, the last subscript on the first $\bar{m}$ is overwritten; the candidate i is provisional. A small expression before the last line's equality is cancelled. The difference of fractions has a long unlabelled angular bracket below it; the last difference has a curve labelled $m_{i_0 i_1}$.

Original source details: GELFAND-P000311

This is not all, since the eq. is in the sense of a twisted



Undeciphered passage. Before "module", a short word is cancelled. An initial n-shaped stroke and a small final curve are visible; the text is unrecovered.

Original source details: GELFAND-P000311

module, (more precisely, in the sense of
[Cancelled; candidate: $M_{f_{i_0}^N \dots f_{i_n}^N}$?]



Original source details: GELFAND-P000311

Uncertain reading. Several long strokes cancel the old localization expression. The final subscript in the candidate $f_{i_n}^N$ remains uncertain; i_1 is also possible. At the right, the new expression $M_{f_1^N \dots f_n^N}$ has lower and side strokes. No closing parenthesis is visible after it.

$M_{f_1^N \dots f_n^N}$

The eq.: $\bar{n}_{i_0} - \bar{n}_{i_1} = m_{i_0 i_1}$ holds if it is multiplied by some power.
Bernstein's proof: let all $m_{i_0 i_1}$ not contain f_{i_0} in the denom.



Uncertain reading. The two small subscripts on m are heavily overwritten. The candidate $i_0 i_1$ is provisional.

Original source details: GELFAND-P000311

and eqs. to 0 do not require multiplication by f_{i_0}. Then everything goes through.
Consequence:

$f_{i_0}^N m_{i_0 i_1}$ — a boundary. The same for $f_{i_1}^N$ and so on.

Since $(f^N_{i_0}, \dots, f^N_{i_n}) = 1$, everything is all right.

GELFAND-P000312

[Cancelled: "Let" and a sign $\dagger$]



Original source details: GELFAND-P000312

Uncertain reading. After "Let" is a tall vertical stroke with a short cross-stroke. The candidate φ is undetermined: no closed loop is visible.

Sinai. H_i — 2-dimensional, $-\infty < i < +\infty$.
$I =$ any finite set.

$$H_I = \bigoplus_{i \in I} H_i;$$

basis $\bigotimes e^i_{t_n}$



Original source details: GELFAND-P000312

Uncertain reading. The small subscript on e is provisionally shown as t_n; t_i and i_n are also possible. The product has a bracket with a straight lower stroke and short sides.

$\alpha(I)$ — all matr. in H_I.
In $\alpha(I)$ introduce the operator norm in Hilb. space.

$$I \subset I_1 \Rightarrow \alpha(I) \subset \alpha(I_1). \qquad (\otimes 1).$$

$$\alpha(I_1) = \alpha(I) \otimes \alpha(I_1 \setminus I).$$

This gives a normed ring (completion) α.
(algebra of quasiloc. observables).
New operators added:
$\varphi(a)$ — a functional (lin.), $\varphi(a) \geq 0 \; \forall$ positive matr. a.
In $\alpha(I)$ we have $\varphi(a) = \mathrm{Sp}(a\rho) = \mathrm{Tr}(a\rho)$.

$$\varphi(a) \geq 0 \Longleftrightarrow \rho \geq 0.$$

$\varphi(e) = 1$ — a noncommut. analogue of a probability distrib.; a state in QFT.

$\alpha(I)$ — a ring of matrices [cancelled: “on”?], $\varphi(a) = \mathrm{Tr}(a\rho_I)$, $\mathrm{Sp}\,\rho_I = 1$.

Uncertain reading. After “matrices”, a short word is densely crossed out. The candidate “on” remains provisional.

Original source details: GELFAND-P000312

On ρ_I the compatibility cond.:

$$\mathrm{Tr}_{I_1-I}(\rho_{I_1}) = \rho_I.$$

$$\alpha(I_1) = \alpha(I) \otimes \alpha(I_1 - I).$$

φ — a state of measure type. $\longrightarrow$ [Cancelled: let ρ_i corresp. to a point;]
[Cancelled: then require $\rho_i\rho_j = \rho_j\rho_i$?]
if ρ_I for different I commute (in a larger space).
[At the left, two signs are cancelled; candidates $\rho_{I_1}\rho_i$?]
(one-point ρ_i and ρ_j always commute.)



Uncertain reading. In the upper cancelled line, “let” is followed by a rho-shaped letter with a small subscript, then “corresp. to a point;”. In the next line, a condition with four rho-shaped letters is crossed out; the subscripts i, j are provisional. Below at the left are two separately cancelled letters whose small subscripts also remain uncertain.

Original source details: GELFAND-P000312

GELFAND-P000313

[source number: 75]

75

ρ_i — a matrix in H_i,
Let e_1^i, e_2^i — a basis of eigenvectors of ρ_i,

$$e_{\alpha_1}^{i_1} \otimes e_{\alpha_2}^{i_2} \otimes \ldots \otimes e_{\alpha_n}^{i_n}.$$

Then $\rho(I)$ is diagonal in it, since it commutes with all ρ_i (obvious if the spectrum is nonrepeated) ($\exists$ such a basis).
$2^{|I|}$ eigenvectors. $\mu(\alpha_1, \ldots, \alpha_n)$ — an eigenvalue.
It characterizes a distrib. of measure type. Its compatibility cond.:

$$\sum_{\alpha_n} \mu(\alpha_1, \ldots, \alpha_n) = \mu(\alpha_1, \ldots, \alpha_{n-1})$$

and so on.
Consider an infinite seq. of 0 and 1.

$\ldots, \varepsilon_{-n}, \varepsilon_{-n+1}, \ldots, \varepsilon_0, \ldots$

a group (addition mod 2). A measure is defined on cylinder sets $\alpha_1, \ldots, \alpha_n$ — fixed $\mu(\alpha_1, \ldots, \alpha_n)$.

The condition is compatibility of these measures.

$\prod \mathbb{Z}_2^i$. One can take Haar measure.

[A sign is cancelled; candidate φ?]



Original source details: GELFAND-P000313

Uncertain reading. Before (a, b), oblique strokes cross a looped letter; a lower vertical extension is visible. The candidate φ remains provisional. The uncancelled formula has a bracket with a straight lower stroke and short sides.

$$(a, b) = \varphi(b^* a)$$

$$(a, a) = \varphi(a^* a) \geq 0.$$

Now quotient and complete — a Hilb. space.

$xa = X_a$ — a lin. operator — continuous in this inner product.

Our ring consists of lin. operators.

(see the supplement to the book by Gelfand, Shilov, Raikov)

(Naimark et al.)

The ring generated by the state φ.

Factors of type **3**. — they are important — these are shifts.

GELFAND-P000314

2/XI. I. M. Gelfand.

Results of the speaker and V. Ponomaryov (not the Mechanics and Mathematics Faculty one).

[The upper margin has a yellow annotation icon with three black horizontal strokes; no readable text appears inside.]

P — a finite-dimensional space, $E_1, \ldots, E_4$ — 4 subspaces (the order matters).

$$S = \{P; E_1, E_2, E_3, E_4\}.$$

This is a category (morphisms carry into).

Equivalent to studying the category of diagrams



Original source details: GELFAND-P000314

Diagram and typed description.



in the category of finite-dimensional spaces.

The methods give information about modules and submodules.

$S \sim S'$, if $\exists$ a lin. isom.

Direct sum is naturally introduced.

The permutation group acts.

Example. E; $A : E \to E$. Graph $\{(x, Ax)\} \subset E \oplus E$.

A — graph, $P = E \oplus E$, E_3 — the graph of A.

To describe the system $E \oplus E$ one must specify

$E_1 = E \oplus 0$, $E_2 = 0 \oplus E$ and the diagonal $E_4 = \{(x, x)\}$.

Pairs



Original source details: GELFAND-P000314

Undeciphered passage. After “Pairs”, several letters before the final tall looped sign are crossed out. Their text is unrecovered.

Original source details: GELFAND-P000314

Uncertain reading. Horizontal and oblique strokes cross the final tall sign; the candidates φ / b remain unresolved.

of maps

$$A : E \longrightarrow F,$$
$$B : F \longrightarrow E.$$



Original source details: GELFAND-P000314

Uncertain reading. The beginnings of both arrows are heavily overwritten. The final reading $A : E \to F$, $B : F \to E$ is discernible; the earlier space letters are unrecovered.

(problem

are also described.

Kronecker’s problem — in the same direction.

Relation — any graph.

Invariants:

4 lines.



Original source details: GELFAND-P000314

Diagram and typed description.



Invariant — a number λ (one).

2 are coordinate axes.

The 3rd is diagonal.

The 4th is a graph — $y = \lambda x$.

Change the numbering: $\lambda \to 1 - \lambda, \quad \lambda^{-1}, \quad \lambda/(\lambda - 1)$.

Result (the proof is long).

GELFAND-P000315

[source number: 76]

76

Original source details: GELFAND-P000315

Undeciphered passage. Before “Let”, a short expression with several dense strokes and a large rounded final loop is cancelled. Its text is unrecovered.

Let there be given P, E_1, E_2, E_3, E_4, then [cancelled: “syst.”?] [inserted above: syst.] decomposes as a direct sum of the following formations



Original source details: GELFAND-P000315

Uncertain reading. “syst.” is clearly written above the line. The earlier short expression below is densely crossed out; the candidate “syst.” remains provisional.

systems with defect $0, \pm 1, \pm 2$.

$\rho(S) = 0, \pm 1, \pm 2.$



Original source details: GELFAND-P000315

Uncertain reading. The defect symbol in the line and frame has a loop and a lower curved tail; the candidates ρ / g remain unresolved. The text provisionally uses ρ. A left and a lower rule frame the definition and “defect”, with no top or right rule.

$$n(S) = \dim P,$$

$$\rho(S) = 2\dim P - \sum_{i=1}^{4} \dim E_i$$

defect

Irreducible (not decomposable as a direct sum)



Original source details: GELFAND-P000315

Uncertain reading. After the opening brace of E_3, a narrow tall sign is cancelled; the candidate ξ is shown with a question mark. The last e_k is heavily overwritten; the earlier strokes are unrecovered.



Original source details: GELFAND-P000315

Diagram and typed description.

1) for $n(S) = 2k$.

Basis in P $\{e_1 \dots e_k\ f_1 \dots f_k\}$.

$E_1 = \{(e_1, \dots, e_k)\}$.

$E_2 = \{(f_1, \dots, f_k)\}$.

$E_3 = \{[\xi?]\ e_2 + f_1, \dots, e_k + f_{k-1}\}$.

$E_4 = \{e_1 + f_1, \dots, e_k + f_k\}$.

$S_3(2k, -\underline{1})$

2) $S_3(2k, 1)$.

$$E_1 = (e_1, \ldots, e_k).$$
$$E_2 = (f_1, \ldots, f_k).$$
$$E_3 = (e_1, e_2 + f_1, \ldots, e_k + f_{k-1}, f_k\}.$$
$$E_4 = \{e_1 + f_1, \ldots, e_k + f_k\}.$$

3) E_1, E_2 — the same.



Original source details: GELFAND-P000315

Uncertain reading. The right-hand addition has 1 below S, with 3 farther right and higher, followed by $(2k, 0)$. Their positions are represented separately; the compact reading S_{13} is provisional. The frame has a left, a lower, and a short right stroke.

$S_{1\ 3}\ (2k, 0)$

$$E_3 = \{e_1, e_2 + f_1, \ldots, e_k + f_{k-1}\}.$$



Original source details: GELFAND-P000315

Uncertain reading. In the second position, the final e_2 is written over an earlier letter. A separate residual upright stroke resembles f, but the old letter is unrecovered.

$$E_4 = \{e_i + f_i\}.$$

GELFAND-P000316

$S(2k; 0, \lambda)$.

$$E_1 = \{e_i\},$$
$$E_2 = \{f_i\},$$
$$E_4 = \{e_1 + f_1, \ldots, e_k + f_k\},$$
$$E_3 = \{e_1 + \lambda f_1, e_2 + f_1 + \lambda f_2, \ldots, e_k + f_{k-1} + \lambda f_k\}.$$

$\lambda \neq 0, \quad \lambda \neq 1.$

σ — a permutation. $1 \longrightarrow i$, $3 \longrightarrow k$

$$\sigma(S_{13}) \xrightarrow{\text{def}} \sigma(S_{ik}).$$

$\sigma\lambda$. λ transforms as an anharm. quadruple of points.

$$\sigma(\lambda) = \left\{\lambda, 1 - \lambda, \frac{1}{1 - \lambda}, \frac{\lambda - 1}{\lambda}, \frac{1}{\lambda}\right\}.$$

Odd-dimensional spaces.



Original source details: GELFAND-P000316

Uncertain reading. In the first line, near the initial subscript 1, a tall f-shaped sign is cancelled; [f?] marks it provisionally. In the second line, the old brace after f_{k-1} is heavily overwritten, with a loop above it. An added e_k stands at the right before the final brace; no separate comma is visible before it.



Original source details: GELFAND-P000316

Diagram and typed description.

$S(2k-1,2)$. $E_1 = \{e_1\,[f?], \dots, e_k\}$, $E_2 = \{f_1, \dots, f_{k-1}\,[\text{overwritten}]\,e_k\}$, $E_3 = \{e_1, e_2+f_1, \dots, e_k+f_{k-1}\}$, $E_4 = \{f_1, e_1+f_2, \dots, e_{k-2}+f_{k-1}, e_{k-1}+e_k\}$.	$S(2k-1,-2)$, orthog. to the preceding one.	def. $=0 \Rightarrow$ — the graph of a lin. transformation (relation).

def 0 does not occur in odd dimension.

def(-1) occurs for relations.

general position — without a parameter, and degenerate — with a parameter.

GELFAND-P000317

[source number: 77]

77

These trajectories.

Example. $S(5,2) \oplus S(1,2)$.

$S(5,2)$ is stable (i.e. deform. gives an isom. syst.).

(Indecomp. systs. without parameters are always stable).

$S(5,2)$ and $S(1,2)$ are stable, but $S(5,2) \oplus S(1,2)$ is unstable and under deform. passes into the stable syst.

$$S(3,2) \oplus S(3,2).$$

It is interesting to find a simple proof.

(The decomp. into irreducibles is unique if they are distinct, and the number is always the same)

Kazhdan.

Let $m_{ij} \in M_{f_i f_j}$, $\quad m_{ij} + m_{jk} + m_{ki} = 0 \in M_{f_i f_j f_k}$.

Need to prove: $\exists m_i \in M_{f_i}$, $\quad m_{ij} = m_i - m_j$.



Original source details: GELFAND-P000317

Uncertain reading. The letters before i after $\exists$ and before i, j in the difference are heavily reinforced. The visible final reading is rendered as m_i, m_j; earlier strokes cannot be separated.



Original source details: GELFAND-P000317

Uncertain reading. Before “Choose”, a short word with loops and a lower tail is crossed out. The candidate “Будем” (we shall) remains uncertain; the complete earlier reading is undetermined.

Choose m_1, the others are determined uniquely and without contradiction.

Suppose the denominators of all elems. do not contain f_1 and all rels. hold without multiplication by f_1.

Then one must put $n_1 = 0$.

Let $m_{1i} \in M_{f_i}$,

$$0 = m_{1i} + m_{ij} + m_{j1} \in M_{f_i f_j}.$$

Put $n_i = m_{1i}$.

Lemma.

$$\exists \text{ cocycles } m_{ij}^{(k)}, \qquad \sum_k m_{ij}^{(k)} = m_{ij};$$

$$m_{ik}^{(k)} \in M_{f_i}, \qquad m_{ij}^{(k)} + m_{jk}^{(k)} + m_{ki}^{(k)} = 0 \in M_{f_i f_j}.$$



Original source details: GELFAND-P000317

Uncertain reading. The k in the second subscript jk, the final i in the third term and the last j in $M_{f_i f_j}$ are reinforced. Their visible final forms are rendered provisionally; earlier strokes are unrecovered.

Proof. Consider:

$$m_{ij}^{(N,k)} = f_k^N m_{ij} \quad \text{— cocycles, for sufficiently large } N$$

GELFAND-P000318

satisfy all conditions.

$$\exists N: \quad m_{ki}^{(N,k)} \in M_{f_i}.$$



Original source details: GELFAND-P000318

Uncertain reading. The first letter of the lower index is heavily reinforced, with an upper loop; the visible final form is rendered as ki. Earlier strokes within k cannot be separated.

The 2nd property is proved similarly.

$$m = 0 \text{ in } M_{f_i f_j f_k} \quad \Longleftrightarrow \quad f_k^N m = 0 \text{ in } M_{f_i f_j}.$$

Choose N common to all k.

Let $\sum g_k f_k^N = 1$. Put

$$m_{ij}^{(k)} = g_k m_{ij}^{(N,k)};$$

they satisfy all conditions of the lemma. ■

Now it suffices to consider $m_{ij}^{(k)}$.

$$n_i^{(k)} = m_{ik}^{(k)} \in M_{f_i} \text{ by assumption.}$$

$$m_{ij}^{(k)} = n_i^{(k)} - n_j^{(k)} \in M_{f_i f_j},$$



Original source details: GELFAND-P000318

Uncertain reading. The sign before the final M has three horizontal endings and several reinforced oblique and curved strokes. The visible form is rendered as $\in$; earlier lines are unrecovered.

from the last condition of the lemma.

Example. The sheaf O^*, $X = \operatorname{Spec} A$.

$$\Gamma(U, O^*) = \{\gamma \in \Gamma(U, O) \mid \gamma \notin p,\ \forall p \in U\}.$$

(a subsheaf of the structure sheaf)
Consider the simplest alg. variety —
— a torus with a point removed.

$$P = y^2 - x^3 + 1; \qquad A = \mathbb{C}[x, y]/p.$$

[Reinforced before the heading: “Упр” (Ex.).]
Exercise: $H^1(\operatorname{Spec} A, O^*) \neq 0$.



Original source details: GELFAND-P000318

Uncertain reading. Before the full heading “Упражнение” (Exercise), the short “Упр” is superimposed on earlier loops; the earlier letters are undetermined. A dark reinforced loop also occurs within the full heading; the final word is rendered as “Упражнение”, without reconstructing earlier strokes.

$S = A^n - \{0\}$.

$$H^i(S, O) = 0 \text{ for } i \neq n-1 \text{ and } i \neq 0.$$

For $i = n - 1$ it is infinite-dimensional and easily described. $H^0 = A$.

Original source details: GELFAND-P000318

Uncertain reading. At the start of the final sentence, the letter before $= n - 1$ is heavily reinforced and has a separate dot above it. It is rendered as i; earlier strokes within the lower loop are undetermined.

GELFAND-P000319

[source number: 78]

78

Theor. of de Linya.
X — a complete variety,
Y — a subvariety, locally

Diagram and typed description.

Original source details: GELFAND-P000319

a direct prod. of transverse planes.

$f \quad = 0$ on the variety (codim. 1).
(may)

$$\left\{\frac{df}{f}\right\} \quad \text{— generating diff. forms.}$$

Resolution of sing. reduces everything to this case.
The ring does not depend on the method of resolution.

Sinai.
α — the alg. of quasilocal observ., φ — a state (functional),
$L^2_\varphi \longleftarrow$
— Hilb. space



Uncertain reading. The reinforced initial letter has a right loop and a descending vertical stroke. Its visible form is rendered as φ; the positivity condition and the subscript on L^2 provide adjoining forms. Earlier strokes in the reinforced letter cannot be separated.

Original source details: GELFAND-P000319

$$\varphi(a) \geq 0, \text{ if } a \geq 0, \qquad \varphi(1) = 1.$$

M — a weakly closed ring of opers.
Powers's theorem. Let $\forall x \in \alpha, \quad \forall \varepsilon > 0, \quad \exists y$:



Uncertain reading. Before $\varepsilon > 0$, a $\forall$ is written over dark earlier strokes; a separate $\exists y$ is clearly written at the right. The earlier sign beneath the reinforced $\forall$ is unrecovered.

Original source details: GELFAND-P000319

$$|\varphi(xy) - \varphi(x)\varphi(y)| \leq \varepsilon \|y\|,$$



Diagram and typed description.

$\underbrace{y \in \alpha([-n,n])'}$
(asympt. commut.)

Original source details: GELFAND-P000319

— the commutant (commuting matrices).
Then M — a factor.

φ — of measure type



Original source details: GELFAND-P000319

Undeciphered passage. Between “of measure type” and the dash, an entire local passage is enclosed and crossed out; its verbal or mathematical content is unrecovered.

— this is the cond.



Original source details: GELFAND-P000319

Diagram and typed description.



(a cond. of asympt. independence type)



Original source details: GELFAND-P000319

Uncertain reading. The ending of “независимости” (independence) has a dark overlap with a long lower stroke and an upper horizontal line. The upper-right curved stroke is provisionally rendered as a closing parenthesis; the earlier ending is unrecovered.

B, [a short word is cancelled; candidate “зав.” (depends)?]



Original source details: GELFAND-P000319

Uncertain reading. After B and before “не зав.” (does not depend), several horizontal and oblique strokes cross a short entry. The candidate “зав.” (depends) remains uncertain.

does not depend on variables numbered $\leq n$.



Original source details: GELFAND-P000319

Uncertain reading. The sign before n is heavily reinforced; an upper angle and two lower strokes are visible. Its final reading is rendered as $\leq$; earlier strokes are undetermined.

(the first n coords. take $\forall$ values)

Products of measures with prob. $\geq c > 0$ satisfy this cond.

State obtained from a Hamiltonian — a factor.

GELFAND-P000320

Original source details: GELFAND-P000320

Uncertain reading. Cancelled earlier date: candidate $2\ldots$/XI; the complete day is undetermined.

$16/\overline{\text{XI}}$. Kazhdan.

Original source details: GELFAND-P000320

Uncertain reading. In the left margin below the cancelled date and to the left of “Consider”, an isolated dense mark has no established verbal reading.

Consider $A^n \setminus \{0\} = X$.

$$H^i(X, O) = ?$$

$$A^n = \text{Spec}\, A[x_1, \ldots, x_n].$$

$\{0\} = (x_1, \ldots, x_n)$ and all prime ideals containing it.

(A — a field [$\leftarrow$ / —?] it is max and, hence, only itself)

Original source details: GELFAND-P000320

Uncertain reading. The short, almost double horizontal mark between “A — a field” and “it is max” has candidates $\leftarrow$ and a dash; the thickened left end does not establish an arrowhead.

Removing a closed subset — an open one remains.

Restr. of a sheaf to any open set is defined.

(Open sets in X — those that are open in A^n).

An open set in X — (basis)

$$U_f \cap (U_{x_1} \cup \ldots \cup U_{x_n}).$$

$(\mathbf{C}[x_1, \ldots, x_n])$.

Open sets U_f correspond to those f, for which $f(0) = 0$.



Original source details: GELFAND-P000320

Uncertain reading. The letter before $(0) = 0$ is reinforced and crossed by additional strokes; the final loop is provisionally rendered as f. Earlier strokes cannot be separated.

$$X = \bigcup_{i=1}^{n} X_i, \qquad X_i = U_{x_i} = \operatorname{Spec} \mathbf{C}[x_1, \ldots, x_n, x_i^{-1}].$$

$$X_{k_0,\ldots,k_m} = \operatorname{Spec} \mathbf{C}[x_1, \ldots, x_n, x_{k_1}^{-1}, \ldots, x_{k_m}^{-1}].$$

m-dim. chains — sections on $X_{k_0,\ldots,k_m}$.

$$a_{k_0,\ldots,k_m} = \frac{P(x_1, \ldots, x_n)}{(x_{k_0} \ldots x_{k_m})^N};$$

H^0:



Original source details: GELFAND-P000320

Uncertain reading. After H^0, a cancelled entry resembles a_{k_0}; the lower rounded sign and the strokes beneath the cancellation do not establish the reading conclusively.

$$a_k = \frac{P_k(x)}{x_k^{e_k}}.$$

$$(da)_{kj} = \frac{P_k(x)}{x_k^{e_k}} - \frac{P_j(x)}{x_j^{e_j}} = 0 \qquad \forall k, j.$$



Original source details: GELFAND-P000320

Uncertain reading. The second sign in $(d \ldots)_{kj}$ has a loop and a right stroke close to the closing parenthesis; candidates are $(da)_{kj}$, $(dd)_{kj}$, $(dg)_{kj}$. The first candidate is provisionally shown in the formula.

Hence a_k — a polynomial for all k.



Original source details: GELFAND-P000320

Diagram and typed description.

True for $n \neq 1$!

GELFAND-P000321

[source number: 79]

79

H^1:

$$a_{kj} = \frac{P_{kj}(x)}{(x_k x_j)^N}.$$



Uncertain reading. Earlier separate powers above x_k and x_j are cancelled; candidates e_k, e_j and n_k, n_j remain undetermined. The common exponent N at the right is clear.

Original source details: GELFAND-P000321

Boundary:

$$\frac{P_{kj}}{(x_k x_j)^N} + \frac{P_{js}}{(x_j x_s)^N} + \frac{P_{sk}}{(x_s x_k)^N} = 0.$$

$$\boxed{P_{kj}x_s^N + P_{js}x_k^N + P_{sk}x_j^N = 0}.$$

Bound.

$$a_{kj} = \frac{Q_k}{x_k^N} - \frac{Q_j}{x_j^N} \quad \#;$$

Need: $P_{kj} = Q_k x_j^N - Q_j x_k^N$.

Concretely. there are 3 polyns. in 3 vars.

$$P_{12}x^N + P_{23}y^N + P_{31}z^N = 0.$$

Then $\exists Q_1, Q_2, Q_3$

$$P_{12} = Q_1 y^N - Q_2 z^N, \quad \text{and so on.}$$

$\Downarrow$



Uncertain reading. Between the P_{23} and P_{31} rows, a short entry with subscript 31 and an equals sign is cancelled. The candidate $P_{31} =$ is rendered provisionally; long strokes cross its initial loop.

Original source details: GELFAND-P000321



Original source details: GELFAND-P000321

Diagram and typed description.

$$P_{23} = \underbrace{Q_{23}}_{\text{in } x,y,z}\, x^N + \Big(\underbrace{L_{N-1}}_{\text{in } y,z}\, x^{N-1} + \ldots \Big)\, y^N$$

$$\cancel{P_{31} =}\quad P_{31} = Q_{31}x^N + (M_{n-1}x^{N-1} + \ldots)\, z^N$$

$$0 \quad \text{cancel.}$$

$$P_{23}y^N + P_{31}z^N = x^N(Q_{23}y^N + Q_{31}z^N).$$

$$\Downarrow$$



Original source details: GELFAND-P000321

Uncertain reading. The initial looped sign with a lower crossbar resembles f_{12} or P_{12}. In the following formula, P_{12} is shown provisionally; the letter remains uncertain.

$$P_{12} = Q_{23}y^N + Q_{31}z^N;$$



Diagram and typed description.

$Q_{23} = Q_1, \quad Q_{31} = -Q_2.$

Original source details: GELFAND-P000321

Prove $Q_{12} = 0$.

Subtract the corresponding cobound. Cocycles with 2 terms remain.

And it now suffices to consider the problem with $\boxed{P_{12} = 0}$.

GELFAND-P000322

H^1 is also easy in the general case.

H^2 is harder. (for $n > 3$).

Uncertain reading. An isolated reinforced letter above H^{n-1}: candidate a; additional upper and lower loops prevent recovery of the earlier letter.

Original source details: GELFAND-P000322

H^{n-1}

$$X = \bigcup_{i=1}^{n} X_i, \qquad a = \frac{P(x)}{(x_1 \dots x_n)^N}.$$

$$a \stackrel{?}{=} \text{[cancelled sign]} \frac{\sum P_i(x) x_i^N}{\prod x_i^N}.$$



Uncertain reading. Between $a \stackrel{?}{=}$ and the fraction, a large sign with two horizontal ends is cancelled: candidates $\prod$ and $\sum$ remain undetermined. Above the equality, a separate dot below the upper curved stroke forms a question mark.

Original source details: GELFAND-P000322

$$\frac{1}{(x_1 \dots x_n)^N} \quad \text{— not representable} \quad \forall N.$$

Answer:



Diagram and typed description.

$\dfrac{1}{x_1 \dots x_n} \mathbb{C}\left[\dfrac{1}{x_1}, \dots, \dfrac{1}{x_n}\right]$

(module)

Original source details: GELFAND-P000322

A module over $\mathbb{C}[x_1, \dots, x_n]$ (over H^0).

$$a_{1\dots n} = \frac{P(x)}{(x_1 \dots x_n)^N}.$$

---

n comm. opers. — the resolv. gives nothing (as for one) —
— localiz. in 1 var. is simple, but not here.



Original source details: GELFAND-P000322

Uncertain reading. In the underlined source phrase “n комм. опр.”, the middle strokes of the final abbreviation merge; “опр.” and “опер.” cannot be distinguished confidently. The text provisionally translates the first candidate as “opers.”

Original source details: GELFAND-P000322

Uncertain reading. Above $\Longleftrightarrow$, a small enclosed sign is crossed by oblique strokes and the preceding paragraph’s line. The inner glyph is unrecovered; the displayed ? is only a candidate.

$a_{1\ldots n}$ — bound. $\not\Longleftrightarrow$ [unreadable sign] $P(x) = \sum P_i(x) x_i^N$.

Original source details: GELFAND-P000322

Uncertain reading. After $\Longleftrightarrow$ and before $P(x)$ is a dense oblique sign with a loop and a separate small stroke at the right. Candidates are a,“ф.”, or a cancelled letter; reinforcement cannot be distinguished from cancellation.

Those with degree $< N$ in every variable remain in the quotient.



Original source details: GELFAND-P000322

Diagram and typed description.

$$\frac{C + c_i x_i + \ldots + \prod_i x_i^{N-1}}{\prod x_i^N}$$ and



There remains $\dfrac{1}{x_1 \ldots x_n}$ — the highest term. N — arbitrary.



Original source details: GELFAND-P000322

Uncertain reading. In the first lower index of the denominator $x_1 \ldots x_n$, a reinforced 1 has an additional loop and lower strokes; the final index is rendered as 1, while earlier strokes are unrecovered.

hence the answer:

$$\frac{1}{x_1 \dots x_n} \mathrm{C}\left[\frac{1}{x_1}, \dots, \frac{1}{x_n}\right].$$

GELFAND-P000323

[source number: 80]

80

A module over H^0 — mult. by a polyn. and discard integer powers;

$$\left(\text{in } \mathrm{C}\left[\frac{1}{x_1}, \dots, \frac{1}{x_n}\right]\right).$$

$$H^{n-1} = \mathrm{Hom}_{\mathrm{C}[x_1,\dots,x_n]}(\mathrm{C}[x_1, \dots, x_n], \mathrm{C}).$$

C is a $\mathrm{C}[x_1, \dots, x_n]$-module (mult. by $f(0)$).

$$\mathrm{Hom}_{H^0}(H^0, \mathrm{C}).$$

Need to construct a map

$$H^0 \times H^{n-1} \longrightarrow \mathrm{C}.$$

(product and coeff. of $\dfrac{1}{x_1 \dots x_n}$, i.e. the residue)

$(P, R) = \mathrm{Res}\, PR$ — — the constant term in what remains.

(It no longer depends on the covering)

---

i

Uncertain reading. Above the line on duality, an isolated vertical stroke with a dot is provisionally rendered as i; its role and final reading are undetermined.

Original source details: GELFAND-P000323

connection — Serre's duality theorem.

Theorem.

$$A^n = \mathrm{Spec}\, A[x_1, \dots, x_n], \qquad \{0\} = (x_1, \dots, x_n).$$

A — a module over $A[x_1, \dots, x_n]$.

$$H^0(X, O) = A[x_1, \dots, x_n],$$

$$H^{n-1}(X, O) = \text{Hom}_{H^0}(H^0, A),$$

$$H^i(X, O) = 0 \text{ for } i \neq 0, n-1.$$

Next time — project. space.
(the Kashul [Koshul?] complex).

Original source details: GELFAND-P000323

Uncertain reading. The surname after "complex" has readings "Кашуля" (Kashul) and "Кошуля" (Koshul). The joined vowel after К has an a-like shape, but remains uncertain; the first candidate is provisionally shown in the line.

GELFAND-P000324

22/XI. Plan for next semester.

1) Arnold — [cancelled: new?] Griffiths.

Original source details: GELFAND-P000324

Uncertain reading. Between Arnold and Griffiths, a cancelled word resembles "новый" (new); its dense ending remains undetermined.

($\int$ of rat. funcs. on various cycles — many vars.)

$$\int \frac{P(z_1, \ldots, z_n)}{Q(z_1, \ldots, z_n)} \, dz_1 \wedge \ldots \wedge dz_n$$

over n-dim. cycles (in $\mathbb{CP}^n$).
(Annals, $N = 1$ or 3 for 1969)
2) and Gabrielov — new Griffiths.
3) S. Gelfand — Brauer theory.
4) Sinai, Factors.



Original source details: GELFAND-P000324

Uncertain reading. The labels of items 3 and 4 contain reinforcement and earlier intersecting strokes; the final digits are shown, while earlier forms are undetermined.

5) A new proof of Grauert's theor. (Knorr).
6) New work of Atiyah (Skew Fredholm opers. and
[cancelled: "work, opr." / "work, oper."?]



Original source details: GELFAND-P000324

Uncertain reading. Below "Skew Fredholm opers. and","раб." (work) and a continuation resembling "опр." or "опер." are cancelled; the continuation's letters remain uncertain.



Original source details: GELFAND-P000324

Diagram and typed description.

parallel ‖ works of Gohberg and Krupnik ⇒

⇒ Gorin

Gorin.

$$\alpha \xrightarrow{\varphi} \mathbb{C} \quad \text{(hom.)};$$

α — a noncommut. Ban. algebra.

$$J = \bigcap_{\varphi} \ker \varphi,$$



Diagram and typed description.

$\boxed{\alpha/J = A}$ — the algebra of symbols.

Original source details: GELFAND-P000324

Example. α — the alg. of all bounded opers. $\Rightarrow J = \alpha$ (no symbols).

$\mathcal{E}(A)$ — the gr. of invertible elements in A.

$$\alpha \xrightarrow{\psi} A, \qquad \psi^{-1}(\mathcal{E}(A)) \ni T \text{ — f-operators.}$$

$$\psi(T) \in \mathcal{E}(A), \qquad \mathcal{E}_1(A) \text{ — the conn. comp. of the identity,}$$

$$\operatorname{ind} T \in \mathcal{E}(A)/\mathcal{E}_1(A) = H^1(\mathfrak{M}_A, \mathbb{Z}).$$

(this is not a number).

GELFAND-P000325

[source number: 81]

81

On works of Gohberg and Krupnik.

Example. $|\zeta| = 1$, $|\zeta| < 1$. (the $+$ ones).

$$a \longrightarrow T_a, \qquad (T_a f) = (af)_+.$$

Consider $\alpha = \{T_a\}^?$ generated by these operators.

Original source details: GELFAND-P000325

Uncertain reading. At the upper end of the closing brace in $\{T_a\}$, an additional curl and separate dots are visible. The displayed superscript ? is only a candidate; an independent sign and earlier strokes remain undetermined.

Δ — the unit disc. Opers. on $H_2(\Delta)$ (holom. inside).

$$\sum_{n=0}^{\infty} c_n z^n, \qquad \sum |c_n|^2 < \infty.$$

a — a piecewise cont. func.

T_a is Fredholm $\iff$ $\widetilde{a}$ does not vanish at 0.

(at discontinuities, join by line segments).
The index — the number of turns.



Original source details: GELFAND-P000325

Diagram and typed description. An irregular contour with an almost straight top, curved sides and a lower gap; the round and triangular strokes are rendered by their visible shapes. Below the gap is the candidate 0. The directions of all small strokes are not established; the gap is not joined.



it does not pass through 0.

Arnold. On vector fields in general position.

Kazhdan. $A^{n+1} - \{0\}$.

A^* acts.

$$P^n = A^{n+1} - \{0\}/A^*.$$



Original source details: GELFAND-P000325

Diagram and typed description.



$$A^* = \{x, y \in A^2,\ xy = 1\}.$$

$$A^* \times A^* \underset{\text{alg.}}{\longrightarrow} A^* \quad \text{(alg. groups)}$$

schemes

A^* — a scheme (aff.).

$$A^* = \text{Spec}\, A[x, y]/(xy - 1).$$

A precise definition of P^n.

$$A^{n+1} = \text{Spec}\, A[x_0, \ldots, x_n].$$

$P^n \in A^{n+1}$ — homogeneous prime ideals, not contained in the ideal $(x_0, \ldots, x_n)$.
Or:



Original source details: GELFAND-P000325

Uncertain reading. Under "Or" and before P^n, a long narrow mark is densely hatched. The strip and hatching are rendered; earlier content and any possible direction are unrecovered.

$$P^n \longleftarrow A^{n+1} \setminus \{0\}.$$

homog. ideals. — invariant under similarity transformations.
(the set of lines — they are points, but not closed)
A basis of open sets: $f \in A[x_0, \ldots, x_n]$ — a homog. func.,
P_f — prime homog. ideals not containing this func.:

$\Gamma(P_f, O_P) = (A[x_0, \ldots, x_n]_f)_0$ — elems. of 0 degree of homogeneity.

GELFAND-P000326

Assert:

Original source details: GELFAND-P000326

Uncertain reading. Before the final U_i, a cancelled parenthesized entry is provisionally rendered as (U_i); crossing strokes obscure the lower sign, which remains uncertain.

$$P_{x_i} \cong A^n \stackrel{\text{def}}{=} \cancel{(U_i)}\ U_i.$$

On P there are sheaves $O(k)$: ($k \in$ Z).

Original source details: GELFAND-P000326

Uncertain reading. In the first $O(k)$, the parenthesized letter is heavily reinforced; its final form is rendered as k, while earlier strokes cannot be separated.

$$\Gamma(P_f, O(k)) = (A[x_0, \ldots, x_n]_f)_k \quad \text{— homog. degree } k \text{ funcs.}.$$

$O(1)$ — the Hopf sheaf; $O(0)$ — the struct. sheaf.

A coherent sheaf: loc. finitely

$$O^J \longrightarrow O^I \longrightarrow \mathcal{F} \longrightarrow 0, \qquad J, I \text{ — finite.}$$

$\mathcal{F}$ — a coherent sheaf on P^n,
Consider



Original source details: GELFAND-P000326

Diagram and typed description.

$$\mathcal{F}(k) = \mathcal{F} \otimes_O O(k) \qquad O = O(0).$$

Serre's theorem:

1) $\forall i \quad H^i(P, \mathcal{F})$ — A-modules of finite type;

2) (obvious). $H^i(P, \mathcal{F}) = 0$ for $i > n$;

3) $\exists k_0$, such that for $k > k_0$ $H^i(P, \mathcal{F}(k)) = 0$ for [cancelled sign] $i \neq 0$.

Original source details: GELFAND-P000326

Uncertain reading. Before the clear $i \neq 0$, a small sign is densely crossed by horizontal and diagonal strokes; the earlier glyph is undetermined.

Let A — a field. Define

$$\chi(F) = \sum_i (-1)^i \dim H^i(\mathcal{F}).$$

Theorem: $\forall$ coherent $\mathcal{F}$, $\chi(\mathcal{F}(k))$ — a polynomial in k.
(Serre).
(Hilbert: $\dim H^0(\mathcal{F}(k))$).



Original source details: GELFAND-P000326

Uncertain reading. Inside the parentheses after H^0 are a calligraphic $\mathcal{F}$ and a tight loop merging with the closing parenthesis. Candidates are $\mathcal{F}(k)$ and $\mathcal{F}_k$; the first is provisionally shown in the line.

(starting from certain k.)

The main lemma for Serre's theor.:
$\forall \mathcal{F}\ \exists k_0$: for $k \geq k_0$ $\mathcal{F}(k)$ is generated by its global sections
(over O).
Explanation. $P^n \supset P_{x_0}$ — aff. space.
Consider [cancelled: $\mathcal{F}|_{P_{x_0}}$?].



Original source details: GELFAND-P000326

Uncertain reading. After "Consider", $\mathcal{F}$, a vertical stroke and a lower P with a dense x_0-like subscript are cancelled. The candidate $\mathcal{F}|_{P_{x_0}}$ is provisional; part of the subscript beneath the strokes cannot be separated.

$$\alpha \in \Gamma(P_{x_0}, \mathcal{F}). \qquad \exists k: \quad \alpha \in \Gamma(P_{x_0}, \mathcal{F}(k)).$$

GELFAND-P000327

[source number: 82]

that α extends to a sect. over the whole ring.



Original source details: GELFAND-P000327

Uncertain reading. Before "extends", a loop has a tall ascending stroke. It is provisionally rendered as α; d and "2" remain among the recorded readings. The glyph is not established unambiguously.

Idea: the sections are simply related
sects. of $\mathcal{F}(k)$ — sects. of $\mathcal{F}$, with an additional pole of order k.
(mult. by x_0 — extension to global sections).
Transition to the proof of Serre's theorem.
$H^i(O(k))$ have already been computed.



Original source details: GELFAND-P000327

Uncertain reading. After $\{0\}$, the closing mark is heavily overwritten: a tall loop and an oblique stroke cross the underline. The earlier content of these strokes is unrecovered.

$$\sum_{k\in\mathbb{Z}} H^i(O(k)) = H^i\left(\sum_k O(k)\right) = \underline{H^i(A^{n+1}-\{0\},O)}$$

homog. comp. of degree k

This is obvious.



Original source details: GELFAND-P000327

Uncertain reading. The initial "Э" in "Это" (This) is heavily reinforced by transverse and looped strokes; the earlier short sign beneath them is undetermined.

Diagram and typed description.



$\sum = \oplus$.

Original source details: GELFAND-P000327

$P^n = \bigcup U_i$ and the Čech complex. One obtains homog. funcs. of all degrees.

$\mathcal{F}(k)$ is generated by global sects., i.e. $\exists$ an epimorphism

Original source details: GELFAND-P000327

Uncertain reading. A separate dot is visible below the start of the final arrow to 0; its punctuation value is undetermined. The dot and double underline are retained.

$$O^N \longrightarrow \mathcal{F}(k) \longrightarrow 0.$$

For O^N Serre's theorem is checked, and now $O^N \longrightarrow \mathcal{F}(k) \longrightarrow 0$.

From this follows Serre's theorem in the general case.

item 2 is obvious (there are no chains).



Diagram and typed description.

see Serre's article.

Original source details: GELFAND-P000327

Next, induction downwards in dimensions. (simult. 1 and 3).

$i > n$ is proved.

Suppose proved for $i > i_0$.

$$0 \longrightarrow \mathcal{G} \longrightarrow O^N(-k) \longrightarrow \mathcal{F} \longrightarrow 0.$$

write the exact sequence.



Original source details: GELFAND-P000327

Diagram and typed description.



1) proved.

$$0 \longrightarrow \mathcal{G}(k') \longrightarrow O^N(-k+k') \longrightarrow \mathcal{F}(k') \longrightarrow 0.$$



Original source details: GELFAND-P000328

Uncertain reading. The middle term is written $\mathcal{F}(k)$; no separate prime is visible on k, unlike k' above and at the right. The reading is retained with this uncertainty.

$$\begin{array}{ccccc} H^{i_0}(O^N(-k+k')) & \longrightarrow & H^{i_0}(\mathcal{F}(k)) & \longrightarrow & H^{i_0+1}(\mathcal{G}(k')) \\ \| & & \| & & \| \\ 0 & \Longrightarrow & 0 & \Longleftarrow & 0 \end{array}$$

by ind. hyp.

Corollary: ind. on dim of proj. sp.

$$0 \longrightarrow \mathcal{F} \longrightarrow \mathcal{F}(1) \longrightarrow \overline{\mathcal{F}} \longrightarrow 0.$$

$\overline{\mathcal{F}}$ concentr. on a hyperplane,



Original source details: GELFAND-P000328

Diagram and typed description.

(depends on the emb. of $\mathcal{F}$ in $\mathcal{F}(1)$)

mult. by x_i

$$0 \longrightarrow \mathcal{F}(k) \longrightarrow \mathcal{F}(k+1) \longrightarrow \overline{\mathcal{F}}(k) \longrightarrow 0.$$

$$\chi(\mathcal{F}(k+1)) - \chi(\mathcal{F}(k)) = \overline{\mathcal{F}(k)} \quad \leftarrow \quad \text{polynomial.}$$



Original source details: GELFAND-P000328

Uncertain reading. After the equality there is no visible χ before $\mathcal{F}(k)$; a long upper stroke extends over this notation. The overlined notation and the left-pointing arrow from "polynomial" are retained.

hence $\chi(\mathcal{F}(k))$ — a polynomial.

For a point everything is trivial. (initial — 0th dim.)

GELFAND-P000329

[source number: 83]

83

8/II-71 I. M. Gelfand.

Bott. Tang. bund. to X, integr. subbund. in TX;



Original source details: GELFAND-P000329

Undeciphered passage. At the left, before "Suppose", a short word with tall oblique strokes is crossed out. The text of this cancelled word is unrecovered.

Suppose there is a bundle: $\exists$ an integrable foliation homotopic to it?

Bott: example of one not homotopic to an integrable one.



Original source details: GELFAND-P000329

Uncertain reading. In the “Bott: example” line, the provisional reading is “не гомотопного интегрируемому” (not homotopic to an integrable one). The stem “гомотопн” (homotop-) is visible, but the final word ending is heavily overwritten; earlier and latest strokes are not confidently separated. The historical alternatives “не гомотопн...” and “интегрируемых” are retained in the reading records.

There is already an example on $\mathbb{C}P^2$ — obtained using Pontr. cls.
Thm.: if there is an integr. foliation, then their

$$\text{Pontr}_i^k(\dots) = 0 \qquad \text{for } k > 2\,\text{dim bund.}$$

(and their products)



Original source details: GELFAND-P000329

Uncertain reading. The upper index is shown as k, and the small lower mark provisionally as i. At the upper right of the zero is a densely overwritten area and small strokes; the earlier writing beneath them is undetermined. The written bound $k > 2\,\text{dim}$ and abbreviation are retained.

Idea: if the integr. syst. were not from a foliation, but a bundle,
then $\text{Pontr}^k(\,) = 0$ for $k > \dim T/E$

(E — our bund.,
T — tang. bund.).

Original source details: GELFAND-P000329

Undeciphered passage. After $H^k(X) = 0$, a short looped word is crossed out. The text of this cancelled word is unrecovered.

for $k > \dim X$;

$$0 \longrightarrow E \longrightarrow T \longrightarrow \pi^* TX \longrightarrow 0.$$

and everything from naturality of Pontr. classes.



Original source details: GELFAND-P000329

Diagram and typed description.

$$\begin{array}{ccc} Y & & \\ \downarrow{\scriptstyle \pi} & & H^k(X) = 0 \\ X & & \end{array}$$

(Work in the seminar on global analysis, vol. 16).

Sinai.

Seminar plan.

Sinai 3 times.
with const. coeffs.:





Original source details: GELFAND-P000329

Diagram and typed description.

Gabrielov

Bernstein — fund. sol. ∀ eqns.

1) analytic.

Original source details: GELFAND-P000329

Uncertain reading. After “analytic.” is a crossed entry beginning with shapes resembling “во”; its remaining letters are covered by horizontal strokes. They are not reconstructed from the phrase’s meaning.

outside fin. codim.

2) analyt. cont. to the whole complex $\mathbb{C}^n$.

3) finite dimensionality. (branches — a fin.-dim. sp.)

GELFAND-P000330

Original source details: GELFAND-P000330

Uncertain reading. The encircled, struck-out and underlined name is shown only as the candidate “Берн...штейн” (Bern...shtein). “Бернштейн” (Bernstein) and other readings of earlier strokes remain possible; historical attribution is not established.

~~Bern...shtein~~ — study analytically ord. analyt. eqns.

~~Др.... ра~~

Original source details: GELFAND-P000330

Uncertain reading. A shortened entry before the equation is crossed out. The beginning “Др.” (Dr.) and ending “ра” (ra) are shown provisionally; its middle and complete reading are undetermined.

$$-y'' + x^2 y + \beta x^4 y = \lambda y.$$

As $\beta \to 0$, a ctbl. number of 2nd-order branch pts., tending to a 3rd-order branch point.



Original source details: GELFAND-P000330

Uncertain reading. Before “number” are two short letters and a dot; “сч.” is shown provisionally, with “сл.” also possible. The Russian abbreviation is not expanded; English “ctbl.” represents only the first candidate. The written orders 2 and 3 are retained.

Original source details: GELFAND-P000330

Uncertain reading. At the right, in an oval, is a 2-like mark with a separate dot below. Both are shown; their combined meaning or reading as a question mark is not established.

Semiphys. work.

Original source details: GELFAND-P000330

Uncertain reading. Below the rule at the right is a connected underlined entry. Only candidates are shown:“Пре...ств...”, a separate tall A/1-like sign, and an ending “ур.”/“пун...”. The complete phrase is unread.

Пре...ств... А/1 ур./пун...

Fedosov.



Original source details: GELFAND-P000330

Diagram and typed description.

1965, 66 Michig.

Bott's result:



Original source details: GELFAND-P000330

Uncertain reading. In the right margin,"reference in Atiyah–Singer" is marked by an angular frame. Above is a separate box, provisionally "UMN, 1969, 6.1"; the small figures and marks after the year are not entirely certain. The bibliographical entry is not completed.

UMN, 1969, 6.1

reference in Atiyah–Singer

M — comp. complex manif., X — holom. vect. field on M.

Let $\exists$ a fin. number of points p, where it is 0 (and nondegenerately).



Original source details: GELFAND-P000330

Diagram and typed description.

Using it, one can compute all Chern cls.

$$\Theta(X)Y = [X, Y].$$

Y — another vect. field.

At pt. p a lin. transformation in the fibre.



Original source details: GELFAND-P000330

Uncertain reading. After "on", the upper Y is heavily overwritten; below it is a separate Y_p. Earlier strokes at the upper letter and the value of the closing curve on the right are undetermined. The candidate Y, lower notation and curve are shown.

(depends only on Y)

Y_p.

Θ_p — a lin. transf. of the tang. sp.

Nondeg.: Θ_p is nondegenerate. $\forall p$.

Let dim $M = m$,



Original source details: GELFAND-P000330

Uncertain reading. The index on the final X is heavily overwritten; it is provisionally shown as m. At the right, the degree, also resembling m, is overwritten and circled. Earlier indices are unrecovered.

$\psi(X_1, \ldots, X_m)$ — a homog. polynomial of degree (m)

The corr. Chern number $\overline{\psi}$

(expr. through elem. symm. and subst. ξ and take integrals on "м.")



Original source details: GELFAND-P000330

Uncertain reading. After "subst." is a tall shaped sign with an upper loop and lower tail; ξ is shown provisionally, with $\mathcal{F}$ also possible. After "on" is an m-shaped sign and dot, provisionally retained as "м." without normalization to M. The full reading of these signs is undetermined.

$$\overline{\psi} = \sum_p \frac{\psi(\Theta_p)}{\det \Theta_p}.$$

(if the degree $< m$, then one gets 0).

$$\psi(\Theta_p) = \psi(\lambda_1, \ldots, \lambda_m),$$

λ_i — the eigenvalues of Θ_p.

GELFAND-P000331

[source number: 84]

This is an infinites. analogue of the Atiyah–Bott thm.

$$(e^{\text{field}} = \text{transf. of a manif. into itself})$$

~~Ka...dan~~

Original source details: GELFAND-P000331

Uncertain reading. Before “There is”, a surname is crossed out; it is provisionally shown as “Ка...дан” (Ka...dan). “Каждан” (Kazhdan) and “Каздан” (Kazdan) remain possible; its middle and ending are hidden by dense horizontal strokes.

There is an analogue for the real case.



Original source details: GELFAND-P000331

Diagram and typed description.

Exact values of the numbers, rather than estimates as in Morse theory.

Next time Sinai and the main res. of Brouwer.

15/II. I. M. Gelfand (work with Kazhdan).

Some notions of diff. geom. and their appl. to questions of



Original source details: GELFAND-P000331

Uncertain reading. The compressed line ending has the candidate “когом. со анал. м...”. Its small abbreviations and final signs at the right edge are uncertain; the full title is unrecovered.

Fedosov. References 1. Michigan Math. J., 1967, v.14, $N = 2$, 231–244.

2. J. Diff. Geometry, 1967, v.1 $N = 4$, 311–330.

3. Matem., 14:2, 1970.

4. Baum, Bott, vol. dedicated to de Rham, Springer 1970, 29–47.

(Steklov)

M m-manif., where X becomes in a nondeg. way.



Original source details: GELFAND-P000331

Uncertain reading. Between the references and the line about M, above “m-manif.”, the parenthesized entry reads “Стеклова” (Steklov). It is retained at this position; its attachment to the references or following line is undetermined.

X — a holom. vect. field.

Bernstein. Formula for merom. vect. fields.

V — a merom. vect. field on a comp. analyt. manif. X.

It has a fin. number of nondeg. zeros.
Poles at codim $= 1$, in general, singular.
It has a corr. cycle in X.



Original source details: GELFAND-P000331

Diagram and typed description.

At nonsing. pts. $f(z)\frac{\partial}{\partial z_1}$ where $f(z)$ has a pole, the order is computed.

Y — the poles, $Y = Y_1 \cup Y_2 \cup \ldots \cup Y_k$ — irred. comps.
Y_i — cycles.

Cycle of the field: $\sum_{i=1}^{k} \alpha_i Y_i$, where k — the order of the pole of W.



Original source details: GELFAND-P000331

Uncertain reading. The final letter after "pole of" resembles W, possibly a rewritten V. The upper limit k, lower limit $i = 1$, coefficients α_i and following written "k is the order of the pole" are retained.

GELFAND-P000332



Original source details: GELFAND-P000332

Diagram and typed description.

$$\frac{\sum f_i(z)\frac{\partial}{\partial z_i}}{\text{max deg. of } z_1 \text{ occurring in the denom.}}$$

$z_1 = 0$ — eqn. of the manif.

Cycles A_V.
p —

Original source details: GELFAND-P000332

Uncertain reading. The looped sign before the dash has a long descending stroke. p is shown provisionally; ρ is also possible.

~~ВХОД~~



Original source details: GELFAND-P000332

Uncertain reading. The first crossed-out word is provisionally shown as "вход" (vkhod, entry); dense strokes cross its visible letters. Its complete reading remains unsettled.

Undeciphered passage. A separate second word follows, heavily crossed out; its text is unrecovered.

Original source details: GELFAND-P000332

by Poincaré duality, 2-dim. cycles.

The right-hand side is the same.

The left-hand side:



Original source details: GELFAND-P000332

Uncertain reading. After a_1, the overwritten two-stroke sign is shown as $\Rightarrow$; a rewritten equality sign is also possible. The letter on the right is shown as p, with ρ also possible. The shared brace, all three rows and right-hand label are retained.

$$\begin{cases} a_1 \Rightarrow c_1 + p; \\ a_2 = c_2 + c_1 p + p^2; \\ \\ a_i = c_i + c_{i-1}p + \ldots + p^i \end{cases}$$

— regularized Chern classes (from the zeros).

$\psi(a_1, \ldots, a_m)|_X$.

Fedosov. The real case.

M — Riem., oriented, dim $m = 4k$.



Original source details: GELFAND-P000332

Uncertain reading. The initial M has a capital form; the sign after dim resembles a small m and is provisionally shown that way. The dimensional notation is retained as dim $m = 4k$.

X — a vect. field; $\forall Y, Z$: (vect. fields).

$$([X,Y],Z) + (Y,[X,Z]) = X(Y,Z).$$

Displ. along traj., up to ∞ small isometries.

Then Θ_p is skew-symm. at sing. pts.

$\psi(p_1, \ldots, p_m)$,



Uncertain reading. Between the closing parenthesis and the frame is a heavily overwritten small looped sign, resembling p. Earlier strokes are unrecovered.

Original source details: GELFAND-P000332



Original source details: GELFAND-P000332

Diagram and typed description.

$\overline{\psi} = \sum \frac{\psi(\Theta_p)}{\operatorname{pf}\Theta_p}$

$\operatorname{pf}\Theta_p = (\det\Theta_p)^{1/2}$ with the required sign.

One-param. group of isometries.

GELFAND-P000333

[source number: 85]

22/II Sinai.

Factors — Naimark.

Next time — Gabrielov.

Arnold.

$A(\lambda)$ — a holom. family of matrices.

(or a matr. over the ring of germs of holom. fns.).

A_0 — a fixed matr., $A(\lambda)$ — its deform., $A(0) = A_0$.

Versal family: if obtained under a mapping.

$$B(\lambda) = C(\lambda)A(\varphi(\lambda))C^{-1}(\lambda); \qquad C(0) = 1, \quad \varphi(0) = 0,$$



Original source details: GELFAND-P000333

Diagram and typed description.

holom.

$(\exists\varphi : \mathbb{C}^k \longrightarrow \mathbb{C}^n$ k — any (!) incl. $> n$ works).

for any

With the least no. of parameters. (Universal, but not unique.)



Original source details: GELFAND-P000333

Uncertain reading. The abbreviation “наим.” (least) is shown provisionally; its last letters are heavily overwritten and the earlier entry is unrecovered. The wavy underline of the whole phrase and separate right-hand parenthetical note are retained.

Answer. Versal deform. of A_0.

Let A_0 have 1 eigenval. (otherwise separate.)

$n_1 \geq n_2 \geq n_3 \geq \dots$



Original source details: GELFAND-P000333

Diagram and typed description. The outer contour, two internal vertical dividers, the upper n_1, n_2 and left n_1 labels, horizontal bands, left diagonal hatching and two dense L-shaped bands at the lower right are retained. The exact cell count and earlier strokes at dense intersections are undetermined.



Insert free params. in the marked cells.

Versal deform.

Row numbered n_1, 1st column down.



Original source details: GELFAND-P000333

Diagram and typed description. The rectangular contour, two interrupted internal vertical dividers, common dense horizontal band, two lower right hatched bands, left and internal vertical shading, slanted pointer below and label “if 3 cells” are retained. Dense intersections and the exact cell count remain unclear; no distinct arrowhead is visible on the slanted stroke.



$A_0 + \Lambda$,
Λ — free parameters.



Original source details: GELFAND-P000333

Diagram and typed description.

Transversals — normals in the matrix

Sp

GELFAND-P000334

Sing. in a 3-param. family of matrices in general pos.

Gelfand: question:

the action of $GL(n, \mathbb{C})$ is triv., if locally — a fibration.

Let there be an action (here XAX^{-1}).



Original source details: GELFAND-P000334

Uncertain reading. The last letter in “здесь” (here) is heavily overwritten; the word is shown according to the current entry and the earlier letter is unrecovered.

Original source details: GELFAND-P000334

Uncertain reading. At the left margin, an oval encloses four slanted strokes, with a dense crossbar at the two inner strokes. The sign resembles (H) or (H); its meaning is undetermined.

cannot split — essential.

Precisely here — a versal family

describe all types of actions (tensors of rank 15, etc.).



Original source details: GELFAND-P000334

Uncertain reading. A short entry before Ad is crossed out. The left B and small 1,“об” below are shown only as candidates from visible fragments; the full reading is undetermined. The intersecting cancellation strokes are retained.



Ad — the worst action.

Hypothesis: locally there is a fibration without sing.,

in the remainder — Ad — Jordan form.

~~Near...~~

Original source details: GELFAND-P000334

Uncertain reading. After “form”, a word is crossed out; its visible beginning is “Близк...” (near...). A line crosses its middle and the ending is unrecovered. The ellipsis marks the unrecovered remainder of the word.

A nearby probl.: a generalized fn., inv. under the action of matrices.

Ordinary eqns. — traject. — not one-param., but a gr. of matrices.



Uncertain reading. The middle contraction is provisionally shown as “траект.” (traject.); the historical candidate “трансв.” is also retained in the full apparatus. Its final vertical letter and join remain uncertain. The separate following contraction is “однопар.” (one-param.).

Original source details: GELFAND-P000334

Chapter 5

GELFAND-P000335

[source number: 1]

Gelfand sem.

1/III — 71

Gabrielov on the art. of Griffiths (Griffits).

On the periods of certain rational integrals

Ann. Math., v. 90, $N = 3$.

I. Bernstein.

Milnor and ..., Topology, vol. 9, $N = 4$, 1970.

Generalization of Brieskorn's work.

$P(z)$ — a polynomial, $z \in \mathbb{C}^n$.

0 — a sing. point (isol.) of the surf. $\{P(z) = 0\} = Y$.

Topology of $S \setminus S \cap Y$ (S — a sphere of small rad.).



Original source details: GELFAND-P000335

Diagram and typed description.

$(S \setminus S \cap Y) \longrightarrow S^1$

$(\arg P(z))$.

We study the fibres and the circuit.

(homeomorphism of the fibre: $T : F \longrightarrow F$).

Diagram and typed description.



Original source details: GELFAND-P000335

Fibre F: $P(z) = \varepsilon$, ε — a small complex number.

Let $w_1, w_2, \ldots, w_n$ — a collection of rational numbers ($w_i > 1$).

$$z_1^{i_1} z_2^{i_2} \ldots z_n^{i_n}; \qquad \frac{i_1}{w_1} + \ldots + \frac{i_n}{w_n} = 1.$$



Original source details: GELFAND-P000335

Uncertain reading. The handwritten Latin letter in the list and denominators is provisionally shown as w; its form does not securely distinguish w from W. The degree condition retains only the written first and last terms, with the ellipsis between them.



Original source details: GELFAND-P000335

Diagram and typed description.

$$\left(\sum \frac{z_i \frac{\partial}{\partial z_i}}{w_i} P(z) = P(z) \right)$$

quasi-homog. polyn. $P(z)$.



Original source details: GELFAND-P000335

Diagram and typed description.

Then homotopically F — a bouquet of spheres S^{n-1} in the number

$$\underbrace{(w_1-1)\dots(w_n-1)}$$

(homotopy equiv.)

(It is an integer if an isol. sing. point).

GELFAND-P000336

The characterist. polynomial of the transfor. T has been computed
(Example: $z_1^2+\ldots+z_n^2=\varepsilon$. — one sphere — real coord. and everything retracts onto it).



Original source details: GELFAND-P000336

Uncertain reading. The last compressed abbreviation after “real” is provisionally read as “coord.”; its ending is not secure and also permits the Russian reading “котор.”. The provisional abbreviation is not expanded.

Brieskorn's case:

$$z_1^{i_1}+\ldots+z_n^{i_n}=\varepsilon.$$

(I. Bernstein: the poles and residues of P^λ are connected with these cycles.)

$$H^{n-1}(F)=\mathbb{Z}^{(w_1-1)\dots(w_n-1)}.$$

Consider the group ring $\mathbb{Q}(\mathbb{C}^*)$.

$$\sum r_i\langle z_i\rangle, \qquad \langle z_i\rangle\cdot\langle z_j\rangle=\langle z_iz_j\rangle.$$

Instead of $\mathbb{C}^*$ only $\sqrt{1}$ occurs, so алг. $\subset\mathbb{C}$.



Original source details: GELFAND-P000336

Uncertain reading. The short abbreviation before the inclusion sign is provisionally shown as the literal Russian “алг.”; the initial loop and following joined strokes permit other readings, including “ан.” and “они”. The abbreviation is not expanded. No index is supplied to the root of one.

$$\operatorname{div}(t-d_1)\dots(t-d_k)=\langle d_1\rangle+\ldots+\langle d_k\rangle \quad \text{(divisor)}.$$

Divisor of the char. polynomial $\chi(T)$

$$E_k = \frac{\langle 1\rangle + \langle \xi\rangle + \ldots + \langle \xi^{k-1}\rangle}{k},$$

Original source details: GELFAND-P000336

Uncertain reading. The averaging fraction's denominator is provisionally shown as k. Its larger angular form also permits K; the handwritten form does not establish its case.



Original source details: GELFAND-P000336

Diagram and typed description.

$$\underset{\text{prim.}}{\xi} = \sqrt[k]{1}, \qquad E_k^2 = E_k.$$

Let $w_i = \dfrac{u_i}{v_i}$ — irreduc.

$$\operatorname{div}\chi(T) = (w_1 E_{u_1} - 1)(w_2 E_{u_2} - 1)\ldots(w_n E_{u_n} - 1).$$

This gives an integral posit. divisor.

2nd work: Connection between Reidemeister tors. and ζ-funct. of the corresp. Laplace oper. on a Riem. manif.

Singer and someone else;

Original source details: GELFAND-P000336

Undeciphered passage. The crossed-out line after "Singer and someone else;" and before "Preprint": overlapping letters and long strokes; the complete text has not been recovered.

Preprint.

GELFAND-P000337

[source number: 2]

I. M. Gelfand.

$$\alpha = \begin{pmatrix} A & B \\ C & D \end{pmatrix}, \qquad A, B, C, D \text{ — matrices.}$$

$$\det \begin{pmatrix} A & B \\ C & D \end{pmatrix} \text{ — ?}$$

AD cannot be mult., in diff. spaces, AB, AC do not occur in det.

$$A - B \cdot C. \qquad D \text{ only in the middle.}$$

$A - BD^{-1}C$.

$$\det \alpha = \det[A - BD^{-1}c] \cdot \det D. \qquad (?)$$



Original source details: GELFAND-P000337

Uncertain reading. The last letter in $BD^{-1}c$ is smaller than the neighbouring capitals C and is provisionally retained as lowercase c. The question mark at the right belongs to this line.

Cond. for posit. definiteness: $D \geq 0, \quad A - BD^{-1}C \geq 0.$

$A - BD^{-1}C.$

S. P. Novikov. On det

Original source details: GELFAND-P000337

Undeciphered passage. A short word between det and “(commut.)” is crossed out; the earlier letters overlap and have not been recovered.

(commut.).



Original source details: GELFAND-P000337

Diagram and typed description.

$$\begin{array}{ccc} \mathbb{C}^n & \xrightarrow{\quad A \quad} & \mathbb{C}^n \\ e_1 & & e'_1 \\ \vdots & \det A & \vdots \\ e_n & & e'_n \end{array}$$



Original source details: GELFAND-P000337

Uncertain reading. The last $\mathbb{C}$ has n_k above and a separate k-shaped sign below. Both are retained; the meaning of the lower sign is not established. Braces enclose the chain, with $= C$ at the right.

$$\left\{0 \longrightarrow \mathbb{C}^{n_1} \xrightarrow{A_1} \mathbb{C}^{n_2} \xrightarrow{A_2} \dots \xrightarrow{A_{k-1}} \mathbb{C}^{n_k}_{k} \longrightarrow 0.\right\} = C.$$

Classical det is defined for exact sequences.

In all $\mathbb{C}^{n_i}$ their own bases $e_1^{(i)}, \dots, e_n^{(i)}$.

(dat. bivector $e_1^{(i)} \wedge \dots \wedge e_n^{(i)}$ — vol. elem.).



Original source details: GELFAND-P000337

Uncertain reading. The compressed first word is provisionally shown as “dat.” (Russian “дат.”); the ending of “бивектора” also permits “бивекторы”. The last $e_n^{(i)}$ has only n below, without an additional i. These provisional words and this index are retained.

$$0 \longrightarrow \mathbb{C}^n \xrightarrow{A} \mathbb{C}^n \longrightarrow 0. \qquad \det A.$$



Original source details: GELFAND-P000337

Diagram and typed description.

$$\begin{array}{ccccccccc} 0 & \longrightarrow & \mathbb{C}^{n_1} & \xrightarrow{A_1} & \mathbb{C}^{n_2} & \xrightarrow{A_2} & \mathbb{C}^{n_3} & \longrightarrow & 0 \\ & & e' & & e & & e'' & & \end{array}$$

Compute the det of the transition from e to $(A_1 e', A_2^{-1} e'')$. This is $\det C$.

GELFAND-P000338



Original source details: GELFAND-P000338

Uncertain reading. The circled object's denominator has a dense subscript; it is provisionally shown as n_4, with n_1 also possible. Two arrows at the right end without labelled objects. The written Im A_2, both labels A_2, the label A_3, the oval and both zeros are retained; the exact index and connections are not established.





Original source details: GELFAND-P000338

Uncertain reading. The crossed-out sign before $(-1)^i$ is provisionally shown as $\prod$; two uprights and an upper stroke are visible, but the whole sign is not established. A three-sided bracket is below the entire expression.

$\not\Pi\ (-1)^i$ det of triples

does not depend on the choice of bases in the intermediate spaces.

Lens spaces.



Original source details: GELFAND-P000338

Diagram and typed description.

$$A = \begin{pmatrix} \xi^{\alpha} & 0 \\ 0 & \xi^{\beta} \end{pmatrix}, \qquad \xi = \sqrt[p]{1}.$$

prim.

Without fixed points.

$$q = \frac{\alpha}{\beta};$$

$\underline{\underline{A_{1,\beta}}}$.



Original source details: GELFAND-P000338

Uncertain reading. The looped sign with a descending stroke to the left of α/β is provisionally shown as q; φ is also possible. The separate $A_{1,\beta}$ below is double-underlined.

Quotient of the sphere — lens space.

$$L^3_p = S^3/A_{1,\beta}.$$

|| как пр-ва с дейст. кон. гр.

Original source details: GELFAND-P000338

Diagram and typed description.

|| as spaces with an action of a finite group.

Are they homeom. or not? The homologies are the same.

$\xi^p = 1$. The fund. gr. of a lens manif. is a cyclic group.

— цикл. группа

— как у проект. пр-ва

	σ^3	σ^2	σ^1	σ^0
Гран.	0	$p\sigma^1$	0	0.

Original source details: GELFAND-P000338

Uncertain reading. The coefficient below σ^2 is provisionally shown as p; the form also permits ρ. A horizontal line separates the rows, with short vertical strokes above the four lower entries. The comparison with project. space is written at the right.

	σ^3	σ^2	σ^1	σ^0
Bound.	0	$p\sigma^1$	0	0.

— as for project. space.

Univ. cover.

$$\xi\sigma^3$$
$$\xi^2\sigma^3$$
$$\vdots$$

Module

Over the group ring $\mathbb{Z}[\pi_1]$, $\pi_1 = \mathbb{Z}_p$.

Uncertain reading. The last $\mathbb{Z}$ has a subscript provisionally shown as p; its looped form also permits ρ.

Original source details: GELFAND-P000338

GELFAND-P000339

[source number: 3]

The cochain complex is exact.

$$\sigma^3 \xrightarrow{\partial} \text{[unreadable crossed-out expression]} \quad (1-\xi^{\beta})\sigma^2_{\not k}$$



Undeciphered passage. A whole expression after the first arrow and before $(1-\xi^{\beta})\sigma^2$ is crossed out. Overlapping loops, sloping strokes and long horizontal strokes do not permit recovery of the entire expression.

Original source details: GELFAND-P000339

$$\sigma^2 \xrightarrow{\partial} (1+\xi+\ldots+\xi^{p-1})\sigma^1_{\not k}.$$



Uncertain reading. The two right-hand occurrences of σ have dense cancelled lower signs, provisionally shown as crossed k; their earlier readings are not established. The looped upper sign on the first ξ is provisionally shown as β, with 3 also possible. Neither lower sign is recovered as a secure index.

Original source details: GELFAND-P000339

$\partial\sigma^1 = (1-\xi\ )\sigma_0$. exact.



Undeciphered passage. The exponent of ξ inside $(1-\xi\ )$ is a solid dark cancelled sign. The blank preserves its position; the earlier exponent has not been recovered.

Original source details: GELFAND-P000339

Exact sequence.

The last ones — the 0th operator.

$$\det = (1-\xi)(1-\xi^{\beta}).$$



Original source details: GELFAND-P000339

Diagram and typed description.

General def. — to understand invariance.

any fund. group.

A repres. such that the complex on the covering is exact.

V. I. Arnold. $\Lambda = \mathbb{C}^k$.



Original source details: GELFAND-P000339

Diagram and typed description.

$A : \Lambda \longrightarrow \mathrm{End}(\mathbb{C}^n)$ $\qquad A(0) = A_0.$

germ.

They are a category. The final object is a vers. deform.

$C(\lambda)$ — a deform. of the identity.

$$C(\lambda)A(\lambda)(C(\lambda))^{-1} = B(\lambda), \qquad C(0) = 1.$$

$\varphi : M \longrightarrow \Lambda$, $\varphi^* A$ — induced deform.



Original source details: GELFAND-P000339

Uncertain reading. The map sign is looped, with a descending stroke; it is provisionally shown as φ, with ψ also possible. The signs before the star and inside $A(\varphi(\mu))$ are also looped; the same provisional candidate is retained at all three sites.

Original source details: GELFAND-P000339

Undeciphered passage. A small solid cancelled mark is above and after A. The blank preserves its position; the mark's content has not been recovered.

A versal deform. A — every deform. B of the matr. $A_0 \sim$ induced.

A.

$$(B(\mu) = C(\mu)A(\varphi(\mu))c^{-1}(\mu)).$$



Original source details: GELFAND-P000339

Uncertain reading. The first letter in the final inverse factor is smaller than the neighbouring capital C and open, with a small middle curl. The provisional $c^{-1}(\mu)$ is retained; e and C are also possible.

$\exists$ a vers. fam. with 9 params.



Original source details: GELFAND-P000339

Uncertain reading. The rectangular boundary, internal vertical and horizontal lines, and the written λ, 1 and $\alpha_1, \ldots, \alpha_9$ are encoded. The label near $\lambda + \alpha_3$ intersects the lines; the exact cells and overlaps are not established. Lower labels are close to the border. Empty places remain empty, without supplied zeros.

λ	1			
	λ	1		
α_1	α_2	$\lambda + \alpha_3$	α_4	α_5
α_6			λ	1
α_7			α_8	$\lambda + \alpha_9$

α_i — free parameters.

GELFAND-P000340

Dim. of the space of variations:

$$\sum_{\lambda}(n_1 + 3n_2 + 5n_3 + \ldots)$$

$$n_1(\lambda) \geq n_2(\lambda) \geq \ldots$$

Through A_0 draw a manif. transvers. to the orbit.

Deformations of the identity — n^2 params.



Original source details: GELFAND-P000340

Uncertain reading. An unlabelled rectangular sketch with a broad left region and two narrower right regions. Below are two horizontal divisions and several wavy bands; the outer boundary has a small gap at the upper left. The visible band positions are encoded, but the exact cells, block order and meaning of the waves are not established; no labels or entries are supplied.



Vazov — dimension count, formul. of the question.



Original source details: GELFAND-P000340

Uncertain reading. The word before the dash is provisionally shown as “Vazov” (Russian “Вазов”); the first letter and vowel also permit “Базов” or “Вызов”. No identity or meaning of this word is established.

Versality $\Leftrightarrow$ transversality (to the orbit) —

— a normal to the orbit.
Normal — almost centralizer.



Original source details: GELFAND-P000340

Uncertain reading. The word is provisionally read as “almost” (Russian “почти”): its beginning is overwritten by dense strokes, and the ending “ти” is readable. The earlier initial letters are not established. “Centralizer” has a wavy underline.

For quadr. forms — the canon. form of quadr. forms.

GELFAND-P000341

15/III L. Faddeev.

$$u_t + 2u_{xxx} + 6u_x u = 0.$$



Original source details: GELFAND-P000341

Uncertain reading. Before u_{xxx} is a visible 2 with a dense earlier looped stroke above it; before $u_x u$ is 6 with an overwritten top. The candidates 2 and 6 are retained; the earlier coefficients are not established. Both written signs before these terms are pluses.

$u(x,\delta) \longrightarrow 0$ as $|x| \longrightarrow \infty$.



Original source details: GELFAND-P000341

Uncertain reading. The second argument of u, with a hooked upper stroke and lower loop, is provisionally shown as δ; t is also possible. The same form in the following equation for ψ is also retained as δ.



Original source details: GELFAND-P000341

Diagram and typed description.

There are no shock waves here.
(many 1st integrals).

Consider $\psi'' + k^2\psi = u(x,\delta)\psi$.

Spec. solution:

$$\psi|_{x\to-\infty} = e^{ikx} + a(k)e^{-ikx}$$
$$\psi|_{x\to+\infty} = e^{ikx} \cdot b(k).$$

One derives $|a(k)|^2 + |b(k)|^2 = 1$.

Known fact: $a(k)$ determines $u(x)$

$u(x) \longleftrightarrow a(k)$ (up to the discr. spectrum).

Recipe: $|a(k,t)| = |a(k)|$

$\arg a(k,t) = \arg a(k) + ck^3t$.

Original source details: GELFAND-P000341

Uncertain reading. The coefficient before k^3t is provisionally shown as lowercase c; the form with a small upper curl also permits e or C. The entire line has a wavy underline.

$u(x,t) \longleftrightarrow a(k,t)$.

And with a discr. spectrum A, $-æ^2$ — these are solitons,

Original source details: GELFAND-P000341

Uncertain reading. After A, is a negative number with exponent 2; the letter made of two joined loops is provisionally represented as æ. The alternative κ is possible, but is not substituted for the visible form.

when $a(k) \equiv 0$.



Uncertain reading. The letter before $(k) \equiv 0$ is dense, with an overlapping stroke; the candidate a is retained, and the earlier form is not established.

Original source details: GELFAND-P000341

GELFAND-P000342

Conclusion: resembles a Hamilton. eq. in action — angle variables.
$a(k,t)$ — a solution of a classical Hamilton system



Original source details: GELFAND-P000342

Uncertain reading. At the right is a crossed-out entry with an H-shaped sign and a small k-shaped lower stroke. The crossed H_k is provisional; the exact earlier expression is not established.

$$\begin{cases} \dfrac{\partial |a|}{\partial t} = 0 \\ \dfrac{\partial \varphi}{\partial t} = Ck^3. \end{cases}$$

Assertion: — the equation is an ∞-dimensional completely integr. Hamilton. eq. The solution of the scattering problem is its canonical transfor. to an explicitly solvable form.
Symplectic structure in the space of functions $u(x)$.



Original source details: GELFAND-P000342

Uncertain reading. Between the minus sign and the second integral are crossed parentheses, u, v and a horizontal sign. The crossed $(u \to v)$ is provisional; $(u \leftrightarrow v)$ is also possible, with the direction obscured by cancellation.

$$\langle u|v\rangle = \int_{-\infty}^{\infty} u(x)\,dx \int_{-\infty}^{x} v(y)\,dy - \cancel{(u \to v)} \int_{-\infty}^{\infty} v(x)\,dx \int_{-\infty}^{x} u(y)\,dy.$$

a nondeg. skew-symm. form.

Hamiltonian:

$$Q(u) = \int_{-\infty}^{\infty} (u^3 + u'^2)\, dx$$

$$\frac{\partial u}{\partial t} = \left(\frac{d}{dx}\right)\left(\frac{\delta Q}{\delta u(x)}\right).$$

In general form, for (Jx, x) and $H(x)$ the eq.



Original source details: GELFAND-P000342

Uncertain reading. Both letters in the introductory pair resemble x: (Jx, x). The next pair is (Jx, y); the difference is retained. Below the equation with J^{-1} is a line with upright sides; no upper side is visible.

$$\langle x, y\rangle = (Jx, y); \qquad \dot{x} = J^{-1}\frac{\partial H}{\partial x}.$$

Or:



Original source details: GELFAND-P000342

Diagram and typed description.

$$\left\langle v \middle| \frac{du}{dt} \right\rangle = (dQ(u))(v).$$ — correct form.

In the кокас. bundle — 2 eqs. for p and q.



Original source details: GELFAND-P000342

Uncertain reading. The abbreviation before “bundle” is provisionally shown as the literal Russian “кокас.”; “клас.” and “коас.” are also possible. An initial k-shaped stroke, rounded o and second k-shaped transition are visible. The abbreviation is not expanded.

Pass from u to $a(k)$.



Original source details: GELFAND-P000342

Uncertain reading. Below Q in the final equality is a separate short, dense, sloping stroke. Its position is encoded; its reading and meaning are not established.

$$Q(u) = \int_{-\infty}^{\infty} (u^3 + u'^2)\, dx = \int_{-\infty}^{\infty} \ln(1 - |a|^2) k^4\, dk.$$

(Trace f-la: L. D. Faddeev and Buslaev,



Original source details: GELFAND-P000342

Undeciphered passage. A small sign with remnants of a loop is densely crossed out between “Buslaev,” and “DAN”; the earlier entry has not been recovered.

DAN, 1960 (2)).

GELFAND-P000343

[source number: 6]

Express any $\int$ of this type (a local functional) through moments of the logarithm $\ln(1 - |a|^2)$. Image of the differential form $\longrightarrow$ in the canonical space (the transition is nonlinear).

$$\langle \delta u_1, \delta u_2 \rangle_u = i \int_{-\infty}^{\infty} \frac{k}{1 - |a|^2} \delta_1 a_k(k)\, \delta_2 a_k(-k)\, dk =$$



Original source details: GELFAND-P000343

Uncertain reading. The small lower signs after both occurrences of a are overwritten, with dark loops. The k in $a_k(k)$ and $a_k(-k)$ is provisional; the original indices are not established, and a reading without a subscript is also possible.



Original source details: GELFAND-P000343

Uncertain reading. Before $\ln(1-|a|^2)$ is an opening brace; no closing brace or trailing dk is visible in this row. An arc labelled dp is below the left part; below $\delta_2 \arg a$ are a three-sided bracket labelled "2nd var." and a lower arc labelled dq. Unseen completions are not supplied.

$$= \int_{-\infty}^{\infty} k\delta_1\{\ln(1-|a|^2) \qquad \delta_2 \arg a$$

dp 2nd var. dq

When eigenvalues are present, there are additional terms.

The three-dimensional inverse scattering problem.

$$-\Delta\psi + v(\vec{x})\psi = k^2\psi, \qquad \vec{x} \in \mathbb{R}^3,$$

$v(\vec{x})$ decays sufficiently rapidly as $|\vec{x}| \longrightarrow \infty$

Scattering amplitude.

The natural solution:



Original source details: GELFAND-P000343

Uncertain reading. A plus is written after f at the end of the first row, and another before $o(1/r)$ in the next row. Both are retained, and o is lowercase. A stepped line is below the fraction and formula ending, with $r \longrightarrow \infty$ at the lower left.

$$\psi(\vec{x},\vec{k}) = e^{i(\vec{k},\vec{x})} + \frac{e^{ikr}}{r}\cdot f\left(\vec{k},\frac{\vec{x}}{r}\right) +$$

$$r \longrightarrow \infty \qquad +o(1/r).$$

f — the scattering amplitude, a function of 5 variables (since $\vec{x}/r$).

Relations on the scattering amplitude have been found, eliminating 2 parameters.

Original source details: GELFAND-P000343

Uncertain reading. The crossed beginning of the line contains a tall f-shaped form and (k). The crossed $f(k)$ is provisional; the dense initial form is not definitively established.

$$f\left(k\left|\frac{\vec{k}}{k},\frac{\vec{x}}{r}\right.\right)\longrightarrow f(k|\vec{\alpha},\vec{\beta})$$

in $L_2(S^2)$ a unitary operator! — this is a condition;
analogous.

Original source details: GELFAND-P000343

Undeciphered passage. A short expression between "analogous" and $a^2+b^2=1$ is crossed out; the overlapping letters have not been recovered.

$a^2+b^2=1$.
$S(k)=I+f$, f — $\mathcal{B}L_2(S^2)$ if



Original source details: GELFAND-P000343

Undeciphered passage. After "if" and before "operator with a kernel", a word is crossed out by overlapping strokes; the word has not been recovered. Before this is a B-shaped sign directly before the space notation, without a supplied membership sign or new parentheses.

an operator with a kernel.

GELFAND-P000344



Original source details: GELFAND-P000344

Uncertain reading. After $Q_\gamma^{(+)}$ are a dot and a long slant near the opening of the next parenthesis. Both strokes retain their positions. A product is only a candidate; the slant's role and possible earlier division are not established. No argument k is visible on the first Q, and none is supplied.

$$S(k)=Q_\gamma^{(+)}\cdot/(Q_\gamma^{(-)}(k))^{-1},$$

где Q вольтерровские, γ — ед. вектор
по углу θ, отсчит. от γ.

Original source details: GELFAND-P000344

Diagram and typed description.

where Q are Volterra, γ — a unit vector.

|

in the angle θ, measured from γ.

$$h_\gamma(k;\alpha,\beta)\Theta[\pm(\alpha-\beta,\gamma)] = f\left(k\left|\frac{\vec{k}}{k},\frac{\vec{x}}{r}\right.\right)$$

When $(\alpha,\gamma)=(\beta,\gamma)$ there is a function analytic in k in the upper half-plane.
The Green function and factorization were written down (several years ago).
There was no inverse problem because of the discrete spectrum.
A. Gabrielov.
Griffiths's work on periods of rational integrals. Annals of Math.

$$\omega = \frac{P(z)}{Q(z)}\,dz_1\wedge\ldots\wedge dz_n, \qquad P,Q \text{ — polynomials in } \mathbb{C}^n.$$

V — the zeros of $Q(z)$.
Γ — n-dimensional cycles in $\mathbb{C}^n\setminus V$.
$\int_\Gamma \omega$ — the periods.
1 variable: $\omega = \frac{P(z)}{Q(z)}\,dz$
Γ reduces to a standard collection of paths



Original source details: GELFAND-P000344

Uncertain reading. Two small closed contours enclose points; both upper arrowheads point left. The label above the first contour is provisionally shown as p_i; the form also permits uppercase P_i. The label γ_i is at the right of the first contour. No other labels or directions are supplied.



$$\Gamma = \sum \mu_i\gamma_i; \qquad \int_\Gamma \omega = \sum \mu_i \int_{\gamma_i}\omega.$$

Reduction to 1st order — subtract an exact differential.
And now $\sum$ of residues.

Regard the form as defined on $\mathbb{CP}^n$.

$P_n \supset V$ — the manifold of poles.

There exists Q — a homogeneous form of degree m, minimal.

GELFAND-P000345

[source number: 7]

$$\Gamma \subset P_n \setminus V, \qquad \Gamma \in H_n(P_n \setminus V, \mathbb{Z}).$$



Original source details: GELFAND-P000345

Diagram and typed description.

Notice that Γ in P_n is 0;

$$n \text{ — odd} \Rightarrow H_n = 0.$$

$$n = 2k+1 \Rightarrow H_n(P_n) = 0.$$



Original source details: GELFAND-P000345

Diagram and typed description.

n — even $= 2m$, $\qquad H_n(P_n) \neq \mathbb{Z}$



Original source details: GELFAND-P000345

Undeciphered passage. The earlier word after "Then" is crossed out by dense horizontal strokes; the whole word has not been recovered. The inserted "plane" is enclosed, with a downward arrow at its right towards the earlier entry. An initial loop and a long lower stroke are visible; "alg." remains only a candidate.



section P_m — the only generator. It suffices to compute the intersection index of Γ with P_m. Consider $W = P_{m+1} \cdot V = q \cdot P_m$, q — the degree of the polyn. defining V.

This follows from $W \cdot P_m = V \cdot P_1$ (Bézout's thm.),

$$(z_1^2 + z_2^2 + z_3^2 = 0 \sim 2P_1).$$

Original source details: GELFAND-P000345

Uncertain reading. After ΓP_m and before the comma is a raised small crossed sign with a loop and a lower stroke. A crossed 2 is provisional; the earlier sign is not established. Its position is not expanded as a secure exponent.

$$0 = \Gamma \cdot W = q\Gamma P_m^{\not 2},$$

hence



Original source details: GELFAND-P000345

Diagram and typed description.

$\Gamma P_m = 0,$ as required

Сущ. цепь R, такая что $\partial R = \Gamma$.
в P_m

Original source details: GELFAND-P000345

Uncertain reading. Below R is the insertion "in P_m". Its lower letter is dense, with joined strokes; m is provisionally retained, with n also possible. The insertion stays below R.

There is a chain R, such that $\partial R = \Gamma$.

in P_m

Assume R and V in general position, $\gamma = R \cdot V$, $\gamma \in H_{n-1}(V, \mathbb{Z})$.
Take $T_\varepsilon(\gamma)$ — an ε-neighbourhood of the cycle γ in P_n.



Original source details: GELFAND-P000345

Uncertain reading. In the first argument of T_ε the letter with a lower loop is strongly reinforced and provisionally shown as γ; earlier strokes cannot be securely separated.



Original source details: GELFAND-P000345

Diagram and typed description.

$$\tau_\varepsilon(\gamma) = \partial T_\varepsilon(\gamma).$$
$$\partial(R - T_\varepsilon(\Gamma)) = \Gamma - \tau_\varepsilon(\gamma)$$

Hence $\tau_\varepsilon(\gamma) \sim \Gamma$. We obtain:

$$\tau : H_{n-1}(V, \mathbb{Z}) \longrightarrow H_n(P_n \setminus V, \mathbb{Z}).$$



Original source details: GELFAND-P000345

Uncertain reading. The letter before the colon has an upper wavy stroke separate from its curved lower leg. It is provisionally shown as τ: ordinary τ_ε on the same leaf has a similar crossbar. A separate tilde above the letter is not established; $\tilde{\tau}$ is also possible.

This gives a map [crossed out] of homologies.



Original source details: GELFAND-P000345

Undeciphered passage. Between “map” and “of homologies” a word is covered by several horizontal strokes. Joined loops are visible beneath them; the whole earlier word has not been recovered, including the candidate Russian “когомол.”.

$$\tau_\varepsilon(\partial\gamma) = \partial(\tau_\varepsilon(\gamma)).$$

$$\tau : H_k(V, \mathbb{Z}) \longrightarrow H_{k+1}(P_n \setminus V, \mathbb{Z}).$$



Original source details: GELFAND-P000345

Uncertain reading. The final map has the same letter form: a separate upper wavy stroke and a curved lower leg. τ is provisionally retained without an added separate tilde; $\tilde{\tau}$ is not excluded.

Original source details: GELFAND-P000345

Diagram and typed description.

GELFAND-P000346

Arnold. Let $P_n(x, y) = 0$ be a plane nonsingular alg. curve.



Original source details: GELFAND-P000346

Uncertain reading. The subscript on the first P is strongly reinforced; n is provisionally retained. Dense overlapping strokes do not securely separate the earlier form.

$$\underline{n = 2k}.$$

Harnack’s thm.: ovals $\leq g + 1$, $g = \dfrac{(n-1)(n-2)}{2}$.

4th degree.



Original source details: GELFAND-P000346

Diagram and typed description.



6th degree. — 50 cases (Gudkov). Let the max. number of ovals be 11 (for $n = 6$).

Original source details: GELFAND-P000346

Diagram and typed description.



and another 2 cases,

Posit. ovals — lie in an even number of others.

Petrovsky: $|2(p-m)-1| \leq 3k^2 - 3k + 1$. Hence not all 11 are outside one another.

Gudkov: $p - m \equiv k^2 \pmod 8$.

Arnold and Varchenko: proof mod 4 because of integral forms.

$$(x, x) = (u, x) \pmod 2$$

— the quad. form is linear mod 2.

Lemma.



Original source details: GELFAND-P000346

Diagram and typed description.

$\underset{\text{an actual integer.}}{(u,u)} \quad \equiv \quad \text{sgn} \quad \underset{\text{quad. form.}}{(\quad)} \quad \text{mod } 8$

Proof:

$$(u+2x, u+2x) = u^2 + 4ux + 4x^2,$$

and ux and x^2 have the same parity by the formula.

———— . ————

$z^2 = f(x,y)$, z, x, y; $(p-m)$ — the Euler char. of the manif. of smaller values.

GELFAND-P000347

[source number: 8]

22/III. A. Gabrielov.

$$\int_\Gamma \frac{P(z)}{Q(z)}\, dz_1 \wedge \cdots \wedge dz_n, \qquad \Gamma \text{ — a cycle in } P^n \setminus V.$$

$$V = \{Q(\xi) = 0\}, \qquad \deg Q = q.$$

The cycle Γ in P_n is homologous to zero.

$$\Gamma \in H_n(P_n \setminus V, \mathbb{Z}).$$

The map $H_n(P_n \setminus V, \mathbb{Z}) \longrightarrow H_n(P_n, \mathbb{Z})$ is zero.
Let $\Gamma \in H_n(P_n \setminus V, \mathbb{Z})$, $n = 2m$.



Original source details: GELFAND-P000347

Uncertain reading. Before V in the repeated group are dense crossed oblique strokes. The resulting complement is retained as \; the earlier sign is not recovered.

Intersec. no.

$\langle P_m, P_m \rangle = 1$ — direct check.

$$\langle P_{m+1} \cdot V, P_m \rangle = q.$$

$$\langle P_{m+1} \cdot V; P_m \rangle = \langle V, P_{m+1} \cdot P_m \rangle = V \cdot P_1 = q.$$

(Bézout's thm.).

$$0 = \Gamma \cdot (P_{m+1} \cdot V) = q(\Gamma, P_m), \qquad \text{hence } (\Gamma, P_m) = 0.$$

Thus, $\Gamma = \partial R$, $R \cdot V = \gamma \in H_{n-1}(V, \mathbb{Z})$.

$T_\varepsilon(\gamma)$ — a bundle of discs over γ.

$$\partial T_\varepsilon(\gamma) = \tau_\varepsilon(\gamma).$$
$$\partial(R - T_\varepsilon(\gamma)) = \Gamma - \tau_\varepsilon(\gamma).$$



Original source details: GELFAND-P000347

Diagram and typed description.

$\tau_\varepsilon(\gamma)$ — the canon. form of the cycle $\mathbf{\Gamma}$.

fibred over γ into circles normal to V.

A map has been constructed:



Original source details: GELFAND-P000347

Uncertain reading. The map symbol has an upper wavy stroke separated from its lower part. τ is provisionally retained; a separate tilde, $\widetilde{\tau}$, is also possible.

$\tau : H_k(V, \mathbb{Z}) \longrightarrow H_{k+1}(P_n \setminus V, \mathbb{Z})$,

$\gamma \in H_{n-1}(V, \mathbb{Z})$.

How ambiguous is this?

$$\operatorname{Ker} \tau\big|_{H_k} - ?$$



Uncertain reading. After Ker the symbol has a wavy upper stroke. τ is provisionally retained; $\widetilde{\tau}$ is not excluded.

Original source details: GELFAND-P000347

GELFAND-P000348

This is part of the exact seq. of the pair:

$$H_{n+1}(P_n, \mathbb{Z}) \xrightarrow{\cdot V} H_{n-1}(V, \mathbb{Z}) \xrightarrow{\tau} H_n(P_n \setminus V, \mathbb{Z}) \xrightarrow{0} H_n(P_n, \mathbb{Z}).$$



Uncertain reading. Several map symbols have an upper wavy stroke separated from the lower part; in the following equality it is straight. τ is provisionally retained; $\tilde{\tau}$ is not excluded for the wavy forms.

Original source details: GELFAND-P000348



Uncertain reading. A word before “It is exact” is crossed out. “otsyuda” (“hence”) remains a possible reading beneath the diagonal strokes.

Original source details: GELFAND-P000348

It is exact. Usually mod torsion, but here everything is fine.



Original source details: GELFAND-P000348

Diagram and typed description.

It was proved that

τ is an epimorphism.

Hence exactness at that term.

From exactness: Ker τ is described.

$$\operatorname{Ker}\tau = H_{n+1}(P_n, \mathbb{Z}), \quad \begin{cases} n \text{ — even — this is } 0, \\ n \text{ — odd — } \mathbb{Z} \text{ with gen. } P_{m+1}. \end{cases}$$

Exactness is proved in the standard way.

Alternatively: the pair P_n, P_n, — a tubul. neighb. of V. Apply to the pair and the Thom isom.:



Uncertain reading. A small sign after “Thom isom.” is densely crossed out. In the right subscript the last digit is reinforced over other strokes; $n+1$ is provisionally retained.

Original source details: GELFAND-P000348

$$H_{n-1} \longrightarrow H_{n+\mathbf{1}}.$$

Proof of exactness: Let $\tau(\gamma) = \partial R$, $\partial(T(\gamma) - R) = 0$ and hence $T(\gamma) - R$ is the bdry. of something, intersect with V and precisely γ.

Uncertain reading. Before the final R in $T(\gamma) - R$ is a dense correction with a vertical stroke and diagonals. The earlier sign is not recovered; R is readable.

Original source details: GELFAND-P000348

[In the left margin: $\Gamma \cdot V = \gamma = \partial R'$.]

$$\partial T(R) = \tau(R) + T(\gamma);$$



Original source details: GELFAND-P000348

Diagram and typed description.

$\Gamma - \partial T(R) = \underline{\quad}(\mathbf{\Gamma} - T(\gamma)) \underline{\quad} -\tau(R);$

Let there be a rat. diff. form on P_n. In homogeneous coord.

$$\mathbb{C}^{n+1} \setminus \{0\} \underset{\varphi}{\longrightarrow} P_n.$$



Uncertain reading. Below the arrow is a small looped sign with a descending oblique leg. φ is provisionally retained; π remains a historical candidate.

Original source details: GELFAND-P000348

The induced form

$$\Omega = \sum (-1)^j \xi_j \, d\xi_0 \cdots \widehat{d\xi_j} \cdots d\xi_n.$$



Uncertain reading. Earlier signs above ξ_j, after $d\xi_0$, at $\widehat{d\xi_j}$ and above the final $d\xi_n$ are reinforced or crossed out. The earlier indices are not recovered.

Original source details: GELFAND-P000348



Original source details: GELFAND-P000348

Diagram and typed description.

$$\frac{P(\xi)}{Q(\xi)}\Omega, \qquad \boxed{\deg P(\xi) = \deg Q(\xi) - (n+1)}$$

then the form is defined on P_n.

$$\varphi = \frac{1}{B(\xi)}\left\{\sum_j (-1)^{|j|}\left[\sum_{\alpha=1}^{\ell}(-1)^{\alpha}\xi_{j_\alpha}A_{j_1\cdots\widehat{j_\alpha}\cdots j_\ell}(\xi)\right]\right.$$
$$\left.(d\xi_0\wedge\cdots\widehat{d\xi_{j_1}}\cdots\wedge\widehat{d\xi_{j_\ell}}\wedge\cdots\wedge d\xi_n)\right\}; \qquad \deg B = \deg A + (n+\mathbf{2}-\ell).$$

GELFAND-P000349

[source number: 9]

Everything is nonsingular.
This is the type of forms that are pullbacks from P_n.

Uncertain reading. The end of "podnyatiyam" is reinforced by overlapping strokes. This reading is provisional; the earlier ending is not recovered.

Original source details: GELFAND-P000349

$$\frac{P(\xi)}{Q^{\ell}(\xi)}\Omega.$$

We lower the order of poles by subtracting coboundaries.

$$\frac{1}{Q(\xi)^{\ell}}\left\{\sum_{i<j}(-1)^{i+j}[\xi_i A_j(\xi) - \xi_j A_i(\xi)]\right.$$
$$\left.(d\xi_0\wedge\cdots\wedge\widehat{d\xi_i}\wedge\cdots\wedge\widehat{d\xi_j}\cdots\wedge d\xi_n)\right\}.$$

$$P = \ell\left(\sum A_j\frac{\partial Q}{\partial\xi_j}\right) - Q\left(\sum\frac{\partial A_j}{\partial\xi_j}\right),$$
$$\deg P(\xi) = \deg Q(\xi) - (n+1).$$

Annals, v. 90, n. 3, 1969.

Palamodov.

On the characteristics of systems of lin. eqns.

$$\text{system}\begin{cases} a_1 u = f_1 \\ \quad\vdots \\ a_t u = f_t \end{cases} \qquad a_1, \dots, a_t \text{ — diff. operators}$$

Example

$$\begin{cases} D_x u = f, \\ (D_y + \lambda) u = g. \end{cases} \qquad \text{princ. part — ?}$$

Not $\begin{pmatrix} D_x \\ D_y \end{pmatrix}$, since a consequence of the system is: $u = h = D_y g - D_x f$.

One must write out all consequences and deal with them.

Char. — ? $D_x u + D_y v = f$.

Holmgren's thm. does not apply in any direction, whereas the thm. of **C**auchy-**K**oval. in any direction.

GELFAND-P000350

29/III. Rolewicz.

A — a lin. operator in a fin.-dim. space.

$\{x, Ax, A^2 x, \dots\}$ — closure.

Limit points: 0, $+\infty$ or



Undeciphered passage. An entire crossed-out word between "or" and "a compact set" is unreadable.

Original source details: GELFAND-P000350

a compact set not containing zero.

Let it be defined in a Hilbert space, ℓ^p or c^0. It can be dense everywhere. — a shift with multiplication.

$$S(x_1, \dots, x_n, \dots) = (x_2, \dots, x_n, \dots).$$



Diagram and typed description.

$A = aS$, $a > 1$.

Original source details: GELFAND-P000350



Original source details: GELFAND-P000350

Diagram and typed description.

$x^{(n)} = \{x_1^{(n)}, \dots, x_{k_n}^{(n)}, 0, 0, \dots\}$ — a lin. set

rat. numbers $n = 1, 2, \dots$.



Original source details: GELFAND-P000350

Uncertain reading. After “large no. of zeros —” is a short abbreviation. “schit.” is provisionally retained; “ochit.” remains a candidate. A short arc is below the first denominator.

$$\boldsymbol{x} = \{x^1, 0, 0, \ldots, 0, \underbrace{\frac{x^2}{a^{\alpha_1}}}, 0, \ldots, 0, \frac{x^3}{a^{\alpha_2}}, \ldots\}.$$

large
no. of zeros — schit.

$$x^{(1)} = (x_1^{(1)}, x_2^{(1)}, \ldots, x_{k_1}^{(1)}).$$

Topol. equiv. of lin. opers.: $\exists$ a homeom. U: $A = UBU^{-1}$.

Exist. opers. not equiv. — density of an orbit — a topol. prop.



Original source details: GELFAND-P000350

Uncertain reading. Before “opers. not equiv.” a word is crossed out, with “Exist.” inserted above. The earlier word is not recovered; “Eti” (“These”) remains a candidate.



Original source details: GELFAND-P000350

Undeciphered passage. An entire line between “topol. prop.” and “One can construct” is crossed out with horizontal lines and repeated loops. Its original words are unreadable.

One can construct an oper. unbounded in $\forall$ norm.

Arnold.

Milnor — the theory of unimod. quad. integral forms.

$$\varphi : \mathbb{Z}^n \times \mathbb{Z}^n \longrightarrow \mathbb{Z}.$$

Unimod.: $\tilde{\varphi} : \mathbb{Z}^n \longrightarrow \mathbb{Z}^{n*}$ is an isomorphism.

Invariants: r — rank; sgn — signature; type, I, II.



Original source details: GELFAND-P000350

Uncertain reading. Before “rank” is a sign with a curved upper part and a lower hook. Latin r is provisionally retained; the form also resembles τ.

If the form is not definite, then the system is complete.

Consider the quad. form $\hat{\varphi}_2 : \mathbb{Z}_2^n \longrightarrow \mathbb{Z}_2$, reduced mod 2. It is linear.



Original source details: GELFAND-P000350

Diagram and typed description.

Write it in the form ~~(u, x)~~

$$\varphi(u, x) = \varphi(x, x).$$

GELFAND-P000351

[source number: 10]

or $\varphi(x, x) \equiv \varphi(u, x) \bmod 2 \quad \forall x$

Type I — $\exists$ an elt. whose square is odd.

Lemma: 1) $\varphi(u, u) \bmod 8$ does not depend on u. (u is defined mod $2\mathbb{Z}^n$).

2) $\varphi(u, u) \equiv \operatorname{sgn} \varphi \bmod 8$.

(from Fresnel's $\int$).

Classif.: Not definite.

$$\text{odd} \quad \sum x_i^2 - \sum y_i^2$$

Original source details: GELFAND-P000351

Uncertain reading. After $\sum x_i^2 - \sum y_i^2$ a small term is densely crossed out with oblique and horizontal strokes. Its notation is not recovered.

Diagram and typed description.



from K-theory.

Original source details: GELFAND-P000351

$$\text{even} \quad kU \oplus \ell\Gamma_8, \qquad \Gamma_8 \text{ — the Zolotarev form,}$$

related to E_8.

$$U = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}.$$

Posit. def. — a finite number in $\forall$ dimension.

Serre — a textbook of arithmetic.



Original source details: GELFAND-P000351

Diagram and typed description.

Stably only rank and signature.

Dear Misha you are wrong.

GELFAND-P000352

[source number: 12]

5/IV Kirillov Presentation following Geronimus.

Based on the notion of a Grothendieck topology (“Topó”).

C — a category, for $\forall A \in C$ covers are specified $\{U_\alpha \xrightarrow{\varphi_\alpha} A\}$.

Axioms:



Original source details: GELFAND-P000352

Diagram and typed description.

1) $\{U_{A_\alpha} \xrightarrow{\varphi_\alpha} U_\alpha\} \implies \{U_{\beta_\alpha} \xrightarrow{\varphi_\alpha \circ \varphi_{\beta_\alpha}} A\}$

covers $\forall\alpha$ a cover



Original source details: GELFAND-P000352

Diagram and typed description.

$$\begin{array}{c} B \\ \| \end{array}$$

2) $\{U_\alpha \times_A B \overset{\varphi_\alpha \times_A 1}{\longrightarrow} A \times_A B\}$ also a cover

A morphism $B \overset{\varphi}{\longrightarrow} A$ is given here.



Original source details: GELFAND-P000352

Diagram and typed description.

Def. $X_0 = B \times_A C$.



A universal object, i.e. $\forall X$,



there exists a unique morphism



8) $U \longrightarrow U$ a cover.



Original source details: GELFAND-P000352

Uncertain reading. Before $U \to U$ is a densely reinforced number with two loops. The visible 8 is provisionally retained; 3 remains a candidate, and the earlier number is not recovered.

(see **Mumford.**)

A sheaf — a functor $F : C \underset{\text{contravar.}}{\longrightarrow} K$ — another category. And the sheaf ax. holds.

$$U_\alpha \xrightarrow{\varphi_\alpha} A.$$



Original source details: GELFAND-P000352

Diagram and typed description. The first arrow from $F(A)$ is reinforced; beneath its strokes at the left is a remnant of a left-facing arrowhead, while the right arrowhead is clear. The order of alteration is not established. At the left of the lower parallel arrow are thickened strokes. After $F(\varphi_\beta)$ is a dense sign with two crossbars and a loop; its meaning is not established. Below $F(A)$ are two lines; below $\prod F(U_\alpha)$ is a bracket.

$$0 \longrightarrow F(A) \overset{F(\varphi_\alpha)}{\longleftarrow} \prod F(U_\alpha) \underset{F(\varphi_\beta)}{\overset{F(\varphi_\alpha)}{\rightrightarrows}} \prod F(U_{\alpha\beta})$$

A — an arbitrary object.

If the images agree, then

$$A \longleftarrow U_\alpha \longleftarrow U_\alpha \times U_\beta.$$

Polutop. exists everywhere.

Полутоп. есть всюда

Uncertain reading. “Polutop.” is a provisional reading of the final abbreviated term; its expansion has not been established.

Original source details: GELFAND-P000352

GELFAND-P000353

$\mathcal{U} = \{U_\alpha \to A\}$. Cohomology $H(\mathcal{U}, F)$ (Čech).

Nontriv. theorem. (!) By the preceding one can construct a sheaf.

Original source details: GELFAND-P000353

Undeciphered passage. The entire crossed-out heading to the left of "from a group" is not read in full. "Predstavleniya" ("Representations") remains an uncertain candidate.

from a group G construct "Topó". and from a repr. — a sheaf over this "topó".

Geronimus's idea — cohomology and its relation to the old reprs.

G — a (Lie) group. C — the G-manifolds. Morphisms — G-maps, and moreover regular,



Original source details: GELFAND-P000353

Uncertain reading. Between M and "tang. map" a small sign is crossed out with several oblique strokes. Neither its letter nor its direction is established. Below M is written $M \to N$.

i.e. at $\forall$ point M the tang. map is an epimorphism.

$$M \longrightarrow N$$

2nd ex.

G — a fin. group — categ. — arbitrary G-sets. (Finite). Cat. K — the category of lin. spaces. Sheaves $\leftrightarrow$ representations. Let a repr. T_g in E be given.

[Crossed out: ~~Repr.~~ $\longrightarrow$]



Original source details: GELFAND-P000353

Undeciphered passage. The crossed-out word at the right after the readable "Repr." and arrow is unreadable.

commuting with the action of G.



Original source details: GELFAND-P000353

Diagram and typed description.

If X is a G-space, then one must consider maps from X to E,

of 5 points.

$$\xi_{g(i)} = T_g \xi_i.$$

The five-tuples — a lin. space.

From X and T_g construct a space of fns. $\xi(x)$.

$$T_g\xi(xg^{-1}) = \xi(x), \qquad \xi(x) \in E.$$

There are sheaves that are not obtained from representations.
Elementary-particle theory



Original source details: GELFAND-P000353

Uncertain reading. Before “not constructed” is a short crossed-out word with an e-shaped first loop and following shch-shaped strokes. “eshchyo” (“yet”) and “eshch.” remain uncertain candidates; the dots over yo and the ending are not established.

is not constructed, since not all reprs. are known. (cf. spinors and electrons.) (For a fin. group everything is obtained from here).

Sometimes one obtains the cohom. of a topol. space and cohom. as in Gelfand–Fuchs.

GELFAND-P000354

[source number: 13]

I. M. Gelfand on the Weil conjecture.



Original source details: GELFAND-P000354

Diagram and typed description.

$$Q: \quad y^3 = x^3 - g_1 x - g_2.$$

g_1, g_2 — rat. numbers. — an ell. curve T. Over the compl. numbers.

There is a discr. group of matrices $\begin{pmatrix} \alpha & \beta \\ A\gamma & \delta \end{pmatrix}$, $\alpha, \beta, \gamma, \delta$ — integers, $\det = 1$.

$A \in \mathbb{Z}$,



Original source details: GELFAND-P000354

Uncertain reading. Between $A \in \mathbb{Z}$, and “will be chosen” a small word is crossed out with a horizontal stroke and diagonals. “pozd.” (“later”) remains an uncertain candidate.

will be chosen. Group mod A.

They define fractional-lin. transf. of the upper half-plane into itself.

$$z' = \frac{\alpha z + A\gamma}{\beta z + \delta}.$$

Fund. domain — the modular manifold X_A.

The group $\Gamma_0(A) = \begin{pmatrix} \alpha & \beta \\ A\gamma & \delta \end{pmatrix}$.

Original source details: GELFAND-P000354

Diagram and typed description. Four arcs above a slanted nearly horizontal line with a small left arrowhead. The two outer branches rise; the third arc has an upper gap, and the first inner foot has a loop. The loop is not identified as a label.





Original source details: GELFAND-P000354

Diagram and typed description.



$A = 1.$



Original source details: GELFAND-P000354

Diagram and typed description.



The Weil conjecture — ∃ an anal. map $\varphi : X_A \longrightarrow T$

(There are finitely many maps; from ∀ curve to a torus)

Diagram and typed description.

$p \neq 2, 3$



Original source details: GELFAND-P000354

Replace T mod p. A curve over $\mathbb{F}_p$ results. It



Original source details: GELFAND-P000354

Uncertain reading. After “It” at the start of the next line before “can” is a dense overlap of letters resembling “on” (“he/it”). It is not established whether this is a cancelled repetition of the pronoun.

can become singular. (I.e. the partial derivs. mod p equal 0).

1) No sing. points.

2) Sing. points with distinct tangents.

2a — real



Original source details: GELFAND-P000354

Undeciphered passage. An entire crossed-out word between “real” and “tang.” is unreadable.

tang.

2b — imaginary tangents.

3) The tangents coincide.

$$\begin{array}{lll} A_p = 1 & p & \text{type 1} \\ A_p = p & p & \text{type 2} \\ A_p = p^2 & p & \text{type 3} \end{array}$$

GELFAND-P000355

$A = \prod_p A_p$ — the conductor of the curve.

$$L_p(\zeta) = (1 - c_p p^{-s} + p^{1-2s})^{-1}, \qquad p \text{ — of type 1.}$$



Original source details: GELFAND-P000355

Uncertain reading. The first argument has a curved Greek sign, provisionally ζ; ξ is also possible. The later arguments and exponents use s.

[Crossed out before the sign “+”:]



Original source details: GELFAND-P000355

Undeciphered passage. The initial entry before “+ number of points of the curve” is densely overwritten and crossed out. The whole earlier sign or short entry has not been recovered.

$+$ number of points of the curve:

$$1 - c_p + p.$$

$$L_p(s) = (1 - \varepsilon_p p^{-s})^{-1}, \qquad \text{case 2);} \qquad \begin{matrix} \varepsilon_p = +1 & \text{2a,} \\ \varepsilon_p = -1 & \text{2b.} \end{matrix}$$

$L_p(s) = 1$, case 3.

$$\zeta(s) = \prod_p L_p(s).$$

Expand $\zeta(s)$ in a series:

$$\zeta(s) = \sum_1^\infty \frac{c_n}{n_s}.$$



Uncertain reading. The small s in the denominator is below n. The visible n_s is retained without replacing it by a power n^s.

Original source details: GELFAND-P000355

Now consider

$$\sum_z c_n e^{inz} = \omega(z).$$



Uncertain reading. The lower summation sign has two horizontal strokes and an oblique middle, resembling z. The coefficient and exponent use n; the lower z is provisionally retained.

Original source details: GELFAND-P000355

Assertion: $\int \omega(z)\, dz$ — the sought fn..

It is str. in the upper half-plane. (and analyt.)



Uncertain reading. The abbreviation after “It” is provisionally read “str.”; “opr.” remains a candidate. Before “upper” are overlapping and crossed strokes; the earlier prefix has not been recovered. The abbreviation is not expanded.

Original source details: GELFAND-P000355

Maps the upper half-plane into the compl. line.

The Weil conjecture:

I. $\exists$ a lattice $\Gamma \subset \mathbb{C}^1$ such that $\forall g \in \Gamma_0(A)$

$$\int_z^{gz} \omega(z)\, dz \in \Gamma.$$

[Crossed out at lower left:]

Undeciphered passage. The short entry in the lower left margin is covered by horizontal and oblique strokes. A complete reading is not established.

Original source details: GELFAND-P000355

[Crossed-out line at the bottom:]



Original source details: GELFAND-P000355

Uncertain reading. The crossed line is provisionally read “otsyuda vse” (“from here all”); “vsyo” (“everything”) is also possible. The last ending and possible dots over yo are obscured by horizontal strokes.

~~from here all~~

[Crossed out above the continuation of this line:]



Original source details: GELFAND-P000355

Uncertain reading. The crossed entry $\Gamma_0(A) \to \Gamma$ is shown provisionally. The letter in parentheses is reinforced over other strokes; A remains a candidate, and the earlier argument has not been recovered. The oblique strokes and two upper horizontal lines are rendered typographically.



GELFAND-P000356

[source number: 14]

12/IV. Perelomov.

V — a $2N$-dim. real space,



Original source details: GELFAND-P000356

Diagram and typed description.

B — skew-symm. nondeg. bilin. form on V.

A B-lattice $L \subset V$,

Original source details: GELFAND-P000356

Undeciphered passage. The short crossed-out entry between $L \subset V$, and the following dash has not been read in full.

— on L, B takes integer values. $J^2 = -1$, J is compatible with B: $J^T B J = B$.



Original source details: GELFAND-P000356

Uncertain reading. The crossed row is provisionally read v_0 fix. vector. Middle strokes of "fix." are covered by horizontals; the abbreviation is not expanded. After the word, a dash, comma and long horizontal stroke are retained.

~~v_0 fix. vector~~ —, ———

Gelfand on Pauli's book:

$$P^2 = P, \qquad \lambda^2 = \lambda, \qquad \lambda = 0, +1, -1.$$

$\underline{-1}$ discarded for phys. reasons.

Volume of the fund. parallelotope $= 1$. (principal lattice). Let $BJ > 0$.



Original source details: GELFAND-P000356

Uncertain reading. The sign after BJ is reinforced over earlier strokes, with an additional horizontal line. $>$ is shown provisionally; $\geq$ remains a possible reading.

A compl. structure on V. $z \in \mathbb{C}^N$.

$H(z, z') = B(z, Jz') + iB(z, z')$ — a Hermitian form.



Original source details: GELFAND-P000356

Undeciphered passage. Between the equals sign and the current $B(z, Jz')$, an earlier formula with a B-like beginning is covered by repeated cancellation. Its arguments and signs are unreadable.

Consider a fn. F: — integer-valued.

$$F(\alpha + \beta) \equiv F(\alpha) + F(\beta) + B(\alpha, \beta) \pmod 2.$$

A lin. form may be added to F. Choose a basis in L.

$$v \in L \mapsto \kappa_1, \ldots, \kappa_N, \ell_1, \ldots, \ell_N.$$

Assume:

$$B = \begin{pmatrix} 0 & I \\ -I & 0 \end{pmatrix}.$$



Original source details: GELFAND-P000356

Undeciphered passage. The short crossed-out word before $F(\alpha)$ has not been read in full. An initial loop and a lower stroke are visible, but a complete reading is not established.

$$F(\alpha) = \sum \kappa_i \ell_i + \sum \varepsilon_i \kappa_i + \sum \tilde{\varepsilon}_i' \ell_i \qquad \text{(there exist } 4^N \text{ solutions)}.$$



Original source details: GELFAND-P000356

Uncertain reading. Above the last coefficient is a separate oblique stroke below the right part of the tilde. It is provisionally rendered as an additional prime on $\tilde{\varepsilon}_i'$; its exact position remains uncertain.

A Θ-fn. — a solution of the eqn.



Original source details: GELFAND-P000356

Uncertain reading. The current $H(\alpha, z)$ has no separate upper bar on z; below it is a remnant of an overlapped curve, not separated into a secure sign. Below the whole formula is a three-sided bracket without a top, with "(entire fn.)" underneath.

$$\Theta(z+\alpha) = (-1)^{F(\alpha)} e^{\frac{\pi}{2} H(\alpha,\alpha) + \pi H(\alpha, z)} \Theta(z).$$

(entire fn.).

There exists only one solution of the functional eqn. up to const. (It is important that the lattice is principal — $\det B = 1$). This is written in Cartier (although known before him).

GELFAND-P000357

Phys. problem (see von Neumann). Let a — annihil. oper., $a|\alpha\rangle = \alpha|\alpha\rangle$ — eigenvectors.

$$e^{-\frac{(x-\lambda)^2}{2}}.$$

Spectrum — the whole compl. plane. The system is overcomplete. Problem: select a complete system.

~~Reasonabl~~[?]



Original source details: GELFAND-P000357

Uncertain reading. The crossed word has a legible beginning "Razumn-"; its ending is covered by a horizontal stroke. "Reasonable" and "Reasonableness" remain candidates.

Overcomplete — if discarding $\forall$ finite number leaves a complete system. (if λ has an accumulation point, then ...) For which seq. λ_n is this a complete system? Let λ — a lattice on the compl. plane C.

cell area $> \pi$ — incomplete,
— " — $< \pi$ — overcomplete.

Let the cell area $= \pi$.

vyb. 1 point — complete.

vybr. 2 points — incomplete.



Original source details: GELFAND-P000357

Uncertain reading. Before “2 points”, “vybr.” is shown provisionally; “vyb.” remains a candidate. After the b there is a loop and a descending r-like stroke, but the earlier entry is not securely separated. The abbreviation is left unexpanded. The first line has a wavy underline, the second two horizontal underlines.

I.e., there is exactly 1 relation.

$$f(z) = \sum (-1)^{mn+m+n} e^{-\frac{1}{2}|\lambda_{mn}|^2 + \lambda_{mn} z} = 0.$$



Original source details: GELFAND-P000357

Uncertain reading. The exponent ends in z with an internal crossing stroke. No separate upper bar is discernible; the preliminary reading $\bar{z}$ is not adopted.

$\lambda_{mn} = m\omega_1 + n\omega_2$. (already in F_2) — everything is divisible. or

$$\sum (-1)^{m\boldsymbol{n}+m+n} e^{-\frac{(x-\lambda_{mn})^2}{2}}.$$



Original source details: GELFAND-P000357

Diagram and typed description. In the initial mn of the sign exponent, the second letter is thickened and overwritten. A separate earlier reading is not established.

$$|\langle \alpha | \beta \rangle|^2 = e^{-|\alpha - \beta|^2}.$$

(Neumann and Schoenberg — pos. def. fns.). Von Neumann’s question: consider a lattice with area π and fns. $|\alpha_{mn}\rangle$. In this state determine the variances of X and p. $\delta_x\, \delta_p$ usually grows for an orthog. system.

GELFAND-P000358

[source number: 15]

Von Neumann’s question. Will $\delta_x\, \delta_p$ after orthogonalization of these vectors be bounded on this system? Gelf. considers this unlikely. The gen. question for an orthog. system is unclear.



Original source details: GELFAND-P000358

Undeciphered passage. Legible fragments of the two crossed-out lines are retained. The end of the first line and beginning of the second, including part of a parenthesis, are unrecovered.

~~Perelomov can prove this for an orthog. lattice [?]~~

~~[?] (from the Jacobi ident. $(z = 0)$).~~

π The gen. ident. is not deduced from the Jacobi ident..



Original source details: GELFAND-P000358

Uncertain reading. The current preposition is provisionally read “from”; it is rewritten in dark strokes. The earlier entry underneath is not securely separated.

This carries over to the N-dim. case. Obtain $2^{N-1}(2^N-1)$ identities. Thus, an elem. problem:

$$\sum(-1)^{mn+n+m}e^{-\frac{1}{2}|\lambda_{mn}|^2+\lambda_{mn}z}=0,$$



Original source details: GELFAND-P000358

Uncertain reading. The exponent ends in a crossed z. The upper stroke belongs to the letter; a separate bar above it is not discernible. The preliminary reading $\bar{z}$ is not adopted.

if the lattice area $=\pi$. Proof: consider a Hilb. space with

$$\int \bar{f}(z)g(z)e^{-|z|^2}\,dz\,d\bar{z}.$$

$|\boldsymbol{\lambda}_{mn}\rangle$
Consider $|\lambda\rangle$ and $|\psi\rangle\in\mathcal{H}$.

$$\langle\psi|\lambda\rangle=e^{-\frac{|\lambda|^2}{2}}\,\psi(\lambda)\cdot$$

entire analytic.

Orthog.

$$\langle\psi|\lambda_{mn}\rangle=e^{-\frac{|\lambda|^2}{2}}\psi(\lambda_{mn}).$$



Original source details: GELFAND-P000358

Uncertain reading. The second formula has λ without mn in the norm; the ket and the argument of ψ have λ_{mn}. No subscripts are added to the norm.

Entire with 0s at the prescribed set of points. Need to prove that it does not exist in F_2. (see Levin, standard theorem).

Original source details: GELFAND-P000358

Undeciphered passage. The isolated crossed-out mark before G is not recovered in full.

$$G = \begin{pmatrix} 1 & \alpha & \delta \\ 0 & 1 & \beta \\ 0 & 0 & 1 \end{pmatrix},$$

α, β, δ — real.



Original source details: GELFAND-P000358

Diagram and typed description. The current α and β in Γ are heavily overwritten; earlier strokes are unrecovered. The upper right entry is provisionally shown as $k\pi$. The note below has a capital K. Below L is a short detached vertical stroke towards the two underlined words “Our lattice”; its exact connection is not established.

$$\Gamma = \begin{pmatrix} 1 & \boldsymbol{\alpha} & k\pi \\ 0 & 1 & \boldsymbol{\beta} \\ 0 & 0 & 1 \end{pmatrix}. \qquad \alpha + i\beta \in L \;|\; \underline{\text{Our lattice.}}$$

K — integer.

GELFAND-P000359

Consider the operators.

$\underline{D = e^{i\varphi} e^{i(\alpha^* a - \alpha a^*)}}$ — a 3-param. group.

Lie alg. — a, a^+ and 1; $[a, a^+] = 1$, other commutators 0. Γ — the α-points of the lattice; φ — 0 and π. Then the repr. induced by the repr. $(-1)^{mn+m+n}$ of the discrete group Γ is irreducible. There is an extension to an arbitrary group.

Kazhdan.



Original source details: GELFAND-P000359

Uncertain reading. “Kazhdan.” is shown provisionally; compressed middle strokes also permit the literal “Kamdan.”.

G — a polupr. group,

Original source details: GELFAND-P000359

Uncertain reading. After G — “polupr.” is shown provisionally; “polugr.” remains a candidate. The abbreviation is not expanded.



Original source details: GELFAND-P000359

Diagram and typed description.

Hilb. space

T — its repr. in H,

h_0 — a distinguished vector in H. $T(g)h_0 \in H$. $\Gamma \subset G$ a discrete subgroup, $T(\gamma)h_0 \in H$. For a reasonable subgroup Γ the system is complete and satisfies a finite number of relations. Here — a unipotent group.

$$f(z) = \sum_{\alpha} (-1)^{F(\alpha)} e^{-\frac{\pi}{2}H(\alpha,\alpha)+\pi H(\alpha,z)} = 0 = c\Theta(z).$$

Original source details: GELFAND-P000359

Uncertain reading. The exponent has $H(\alpha, z)$. No separate upper bar is discernible above the crossed z; the preliminary $H(\alpha, \bar{z})$ is not adopted.



Original source details: GELFAND-P000359

Uncertain reading. The source literally writes $= 0 = c\Theta(z)$. The last argument of Θ is repeatedly retraced, with overlapping upper and lower strokes. z is shown provisionally; the earlier sign and any separate upper bar are not established.



Original source details: GELFAND-P000359

Diagram and typed description.

— of them $\underline{4^N}$

for some $F(\alpha)$ $\quad c = 0$.

$c \neq 0$ — A new repr. of the Θ-fn. For half of the $F(\alpha)$ this is 0. $\Theta(z)$ — the standard fn., $\neq 0$.
Next meeting 1st Mon. of September.

GELFAND-P000360

[source number: 22]

Kirillov on quantization. (Kostant etc.) Trivial part. A symplectic manifold — X^{2n} — even-dimensional with a nondeg. closed 2-form ω ($d\omega = 0$).



Original source details: GELFAND-P000360

Diagram and typed description.

Locally there exist coords. 

such that

$$\omega = \sum_{i=1}^{n} dp_i \wedge dq_i.$$

(see Rashevskii, “Geom. theory of diff. eqns.”, Sternberg, “Lectures on diff. geom.”). Volume

$$\Omega = \frac{1}{n!}\omega \wedge \omega \wedge \cdots \wedge \omega = \frac{1}{n!}\omega^n \quad \text{(exterior power)}.$$

Identify tang. space with cotang. using the form ω.

$$\omega(\xi, \eta) :— \quad \omega : T_x X \to T_x^* X \quad \text{(isomorphism)}.$$



Original source details: GELFAND-P000360

Uncertain reading. The lower index of the first T is heavily overwritten. x with overlapping upper strokes is shown provisionally; $*$ remains a candidate.

$$\xi \to \alpha_\xi;$$

$$\alpha_\xi(\eta) = \omega(\xi, \eta).$$

$$\left(\text{in those coords. } \frac{\partial}{\partial q_i} \to dp_i, \quad \frac{\partial}{\partial p_i} \to -dq_i\right).$$

Closed 1-forms $\leftrightarrow$ vector fields preserving the form ω.

in the sense of the Lie derivative L_ξ.

L_ξ acts on all geom. objects on the manifold. φ_t — the corresponding one-param. group, corresponding to the field ξ. ($\dot{x} = \xi(x)$).

$$\left.\frac{d}{dt}\right|_{t=0} = L_\xi.$$

It commutes with differentiation of diff. forms: $L_\xi d = dL_\xi$. $L_\xi f = \xi f$, $L_\xi \eta = [\xi, \eta]$.

$$\boxed{L_\xi \omega = 0 \;\Leftrightarrow\; d\alpha_\xi = 0}$$

— a short formulation. Such fields — Hamiltonian, forms — gradient. ξ — loc. Hamiltonian $\Leftrightarrow \alpha_\xi = df$. f is defined up to const and is multivalued.

GELFAND-P000361

Uncertain reading. Beside the first ξ_F is a dense round overwritten mark. It is shown as a round mark without assigning a mathematical meaning; the exact earlier sign is not established.

$F \longrightarrow \xi_F$

|

fn.

Original source details: GELFAND-P000361

dF — a form $\longleftrightarrow$ Hamiltonian field; $dF = 2\alpha_{\xi_F}$. Poisson bracket.

$$\{F_1, F_2\} = \xi_{F_1} F_2 = -\xi_{F_2} F_1 = 2\omega(\xi_{F_1}, \xi_{F_2}).$$

Identity:

$$\xi_{\{F_1,F_2\}} = [\xi_{F_1}, \xi_{F_2}].$$

Remark:



Original source details: GELFAND-P000361

Uncertain reading. Between $(dp \wedge dq)$ and the parenthesis with vectors is a dense crossed hash-like mark. Its strokes are shown without a mathematical interpretation.

$(dp \wedge dq)$ ## $\left(\frac{\partial}{\partial p}, \frac{\partial}{\partial q}\right) = \frac{1}{2}$ (one may take 1).

$$\frac{1}{2}[\alpha_1(\xi)\alpha_2(\eta) - \alpha_2(\xi)\alpha_1(\eta)] = \alpha_1 \wedge \alpha_2.$$

A new object is constr. when $[\omega] \in H^2(X, Z)$. Constr. a complex 1-dim. bundle and a map C.



Diagram and typed description.

$C \longrightarrow L$

$\downarrow$

X

Original source details: GELFAND-P000361

$\{U_j\}$ — a covering, $\omega = d\alpha_j$ in U_j. On $U_j \cap U_k$ constr. $\alpha_j - \alpha_k = df_{jk}$. ~~$\alpha$~~[?]



Undeciphered passage. After df_{jk}, the beginning of the crossed entry is provisionally shown as α. Small signs, subscripts and the continuation are not recovered in full.

Original source details: GELFAND-P000361

on $U_j \cap U_k \wedge U_\ell$ we have $d(f_{jk} + f_{k\ell} + f_{\ell j}) = 0$ and hence



Uncertain reading. The second sign between the sets is pointed: $\wedge$ is shown provisionally, without replacing it by the usual intersection.

Original source details: GELFAND-P000361

Original source details: GELFAND-P000361

Diagram and typed description.

$f_{jk} + f_{k\ell} + f_{\ell j} = \underset{\text{const}}{\underline{C_{jk\ell}}}$ — a 2-dim. Čech cocycle,

corresponding to the form $\underline{\underline{\omega}}$. Integer-valued — $\exists \alpha_j, f_{jk}$ such that $C_{jk\ell}$ — integer-valued.

$g_{jk} = e^{2\pi i f_{jk}}$ — a set of bundle transition fns. (1-dim.).

$$\boxed{g_{jk} \cdot g_{k\ell} \cdot g_{\ell j} = 1.}$$

GELFAND-P000362

[source number: 23]

Choose other α, ~~[?] const [?]~~



Undeciphered passage. In the cancelled continuation a const-like fragment is shown provisionally. Other words and signs among long looping cancellation strokes are not read in full.

Original source details: GELFAND-P000362

The equiv. class of the constr. bundle depends on choosing an element of

$$\boxed{H^1(X, \mathbb{C}^*).}$$

$H^1(X, \mathbb{C}^*)$ acts simply transitively on the set of bundles. ($\mathbb{C}^*$, rather than

Undeciphered passage. The small crossed-out token before “sheaf” is wholly unreadable.

Original source details: GELFAND-P000362

the sheaf of continuous fns.) s_j in U_j, $s_j = g_{jk} s_k$ — a section of the bundle.

along a vector field.



Original source details: GELFAND-P000362

Diagram and typed description.

Connection — derivative of sections



Original source details: GELFAND-P000362

Uncertain reading. The small upper mark on the first Γ is thickened. $\Gamma^1(L)$ is shown provisionally; $\Gamma\prime(L)$ remains a candidate. Below ∇_ξ is a curved underline.

$$\nabla_\xi : \quad \Gamma^1(L) \to \Gamma(L).$$



Original source details: GELFAND-P000362

Diagram and typed description.

Choice

of α_j defines the connection.

$$(\nabla_\xi s)_j = \xi s_j - 2\pi i \alpha_j(\xi) s_j.$$

This acts as an oper. on the space of sections. (checking left to the reader).



Original source details: GELFAND-P000362

Uncertain reading. The first word is provisionally read “checking”; “to check” remains a candidate. The following Russian abbreviations are “predost. chit.”, with a separate o-like loop after d. The abbreviations remain unexpanded in the Russian text.

Check:

$$(\nabla_\xi s)_j = g_{jk}(\nabla_\xi s)_k.$$

Define a Hermitian bundle with a connection and a generalized Fourier transform in it. Consider an arbitrary 1st-order diff. oper. in the bundle L.

$$D : \Gamma(L) \to \Gamma(L) \quad \text{(ordinary in local coords.)}.$$

Its gen. form: $D = \nabla_\xi + \varphi = D_{\xi,\varphi}$ (φ — multiplication by a fn.).



Original source details: GELFAND-P000362

Undeciphered passage. The earlier adjective is crossed out and not recovered in full. Above it is the legible inserted and outlined word “compatible”.

D is called compatible ~~[?]~~ with the connection if



Original source details: GELFAND-P000362

Diagram and typed description. An arc starts at the right of the commutator, bows to the right beside the remarks in square brackets, and ends down-left above the lower frame. No additional mathematical relation is assigned to the arc.

$[D_{\xi,\varphi}, \nabla_\eta] = \nabla_{[\xi,\eta]}$.

[ω — the curvature form of this connection.
It is always closed, but not always nondeg.]

[Connection — a 1-form with values in L.]

Or

$$\boxed{\xi = \tfrac{1}{\pi i}\xi_\varphi}$$



Original source details: GELFAND-P000362

Uncertain reading. The frame literally reads $\xi = \frac{1}{\pi i}\xi_\varphi$.

(in particular, ξ is actually Hamiltonian.)

GELFAND-P000363

~~$D_{\overline{\varphi}}$~~

Original source details: GELFAND-P000363

Uncertain reading. The crossed initial sign is provisionally shown as D_φ; overlapping strokes do not permit a secure reading.

The operator $D_\varphi = \nabla_{\xi_\varphi} + \pi i\varphi : \Gamma(L) \to \Gamma(L)$. Fund. theorem:

$$[D_\varphi, D_\psi] = D_{\{\varphi,\psi\}}.$$

(obtain a repr. of the Lie algebra) compatible with the connection. (Van Hove repr.: fns. $\to$ opers. on bundle sections) compatible with the connection. This is called prequantization.



Original source details: GELFAND-P000363

Diagram and typed description. Before the note at right is a short left arrow with a shaft on its right. Its exact endpoint is not established; no additional logical connection is assigned.

← acts on too large a space.

(~~This.~~ consider 200 pp. of the 3rd issue of Lectures on Modern An., Lecture Notes, Lectures on Modern Analysis, III). A Lagrangian distribution (isotropic space) — — at $\forall$ point a Lagr. subspace is given. $\frac{1}{2}$ the dimension.

$$F : F_x \subset T_*X, \qquad \omega|_{F_x} = 0, \qquad \dim F_x = n = \frac{1}{2}\dim X.$$

Complex distributions will be considered:

$$F_x \subset T_x^C X, \qquad \omega|_{F_x} = 0, \qquad \dim_C F_x = n = \frac{1}{2}\dim X.$$

The choice of an integr. Lagr. distrib. — polarization.

It is considered integrable (Frobenius cond.) — see Dieudonné. (Locally exists — because of $\sum dp \wedge dq$) take the p-subspace.



Original source details: GELFAND-P000363

Diagram and typed description.

The complex case is hard.

Example: a sphere with its usual volume. Globally impossible. Special cases (extreme).

1) $\overline{F}_x = F_x$ — a real distribution. (real polarization)



Original source details: GELFAND-P000363

Uncertain reading. The first F and its bar in the first equality are heavily thickened or rewritten. The current reading is provisionally shown as $\bar{F}_x = F_x$; earlier strokes are not separated.

2) $F_x \cap \bar{F}_x = 0$. (Kahler polarization).

$$\dim(F_x + \bar{F}_x) = k \quad (= \text{const}) \quad (\text{and an integr. bundle}).$$

There is a mixed-mfd. structure there (a bundle with a real base and complex fibres; transitions — holom. transformations of the fibres).

GELFAND-P000364

[source number: 24]

F — a distrib., $\Gamma(L,F)$ — sections constant along the leaves, i.e., $\nabla_\xi s = 0$ if $\xi_x \in F_x$. Now consider the action of opers. on $\Gamma(L,F)$.



Original source details: GELFAND-P000364

Diagram and typed description.

$A(F)$ — fns. φ constant along the leaves.

|

algebra of
such fns.

($\xi f = 0, \forall$



Uncertain reading. The crossed sign is provisionally shown as $\forall$; overlapping diagonal strokes cross it.

Original source details: GELFAND-P000364

if $\xi_x \in F_x$). $\varphi \in A(F) \Rightarrow D_\varphi$ preserves the space of sections (D_φ acts on $\Gamma(L,F)$ as multiplication by φ). $A(F)$ — a max. commutative subalg. with the Poisson bracket (locally). Now consider operators (also preserving $\Gamma(L,F)$)

$$A_1(F) = \text{normalizer of } A(F) \text{ in the Poisson-bracket alg.} = \\ = \{\varphi : \{\varphi, A(F)\} \subset A(F)\}.$$

Thm. Operators D_φ with $\varphi \in A_1(F)$ preserve $\Gamma(L,F)$ and act there as 1st-order opers. This is already quantization, and the fns. — quantizing. (Other quant. are already nonunique). There are many of them.



Uncertain reading. The current word “ikh” (“of them”) is readable, but its first letter is rewritten. Earlier strokes are not separated.

Original source details: GELFAND-P000364

p, q; $dq = 0$ — subspace, fns. — of q only. Opers. — fns. of q — multiplication opers., linear fns. of p — 1st-order opers.

Next time: Kirillov.

GELFAND-P000365

13/IX-71. I. M. Gelfand on the work of Springer (comput. char. for semisimple groups over a finite field). 1. Consider the group $SL(n, C)$ and unipot. matrices. [?]



Original source details: GELFAND-P000365

Uncertain reading. A separate dark overwritten sign precedes the first matrix. Neither U nor an equals sign has been established securely.

$$\begin{pmatrix} 1 & & & 0 \\ & 1 & & \\ & & \ddots & \\ \dots & & & 1 \end{pmatrix}$$

~~U~~[?]



Original source details: GELFAND-P000365

Undeciphered passage. The beginning of the short cancelled entry is provisionally shown as a U-like sign. The remaining signs under horizontal strokes have not been read in full.

(reduced to this form). $(1 + a,$ where $a^n = 0)$. At 1 — sing. points.

$$\begin{pmatrix} a & b \\ c & d \end{pmatrix}, \quad ad - bc = 1, \qquad \text{unipot. } a + d = 2, \quad \text{in } R^3 \text{ a cone}, \quad 1 \text{ — a singularity.}$$

Nonsingular — one Jordan block. Several Jordan blocks — **singular**. Answer: R — the set



Original source details: GELFAND-P000365

Undeciphered passage. Beneath the outlined insertion “all unipot. matrices”, the earlier phrase is cancelled. Its remainder between and after the provisionally legible fragments has not been recovered.

all unipot. matrices

~~matr.[?] [?] sing.[?] [?],~~



Original source details: GELFAND-P000365

Uncertain reading. The contractions “matr.” and “sing.” are provisionally rendered in the cancelled line. Endings and intervening writing are covered by strokes; the contractions are not expanded.

$g \in R$.



Original source details: GELFAND-P000365

Uncertain reading. Between $P =$ and $B\backslash G$ a sign is heavily cancelled, provisionally P. The exact earlier sign has not been recovered. Beneath it is a short vertical stroke and the caption “project. space.”.

$P =$ ~~P~~[?] $B\backslash G$

project. space.

B — triangular matrices

$$\begin{pmatrix} \lambda_1 & & 0 \\ & \ddots & \\ \dots & & \lambda_n \end{pmatrix}.$$

Consider pairs (p, g) with actions

$$pgp^{-1} \in U = \left\{ \begin{pmatrix} 1 & & 0 \\ & 1 & \\ & & \ddots \\ \dots & & 1 \end{pmatrix} \right\}, \qquad p \in P.$$

(This does not depend on the chosen representative elem. from p.) $\bar{R}$ — the set of pairs.

$$(p, g) \longrightarrow g.$$

This is $\bar{R} \to R$, a resolution of singularities (all). Over a point in gen. position one element. $\bar{R}$ — a nonsingular variety. (This is for an arbitrary reductive group over $\forall$ field.)

Original source details: GELFAND-P000365

Uncertain reading. The Russian word “nad” (“over”) is readable, but its last letter is heavily rewritten, with a separate arc above it. Earlier strokes are not separated.

2. Geom. interpretation of Hall polynomials. Consider G [?]



Original source details: GELFAND-P000365

Undeciphered passage. After G is a short overwritten and cancelled group of strokes. An equals sign remains a candidate; no secure earlier reading has been established.

— the group of matrices, B — the group of triangular matrices.

$$G = GL(n, F_q), \qquad B\backslash G \text{ — flags.}$$



Original source details: GELFAND-P000365

Diagram and typed description. A sloping four-sided outline has a roughly middle bent line with a large dot on it. The small detached dot above its upper middle join, short trace at upper left and thickened upper right join are encoded without assigning additional nodes or mathematical meaning.



The number of flags — a polynomial in q, whose degree depends on n.

GELFAND-P000366

[source number: 25]

A coset class is determined by a partition $n = n_1 + \cdots + n_k$, $u \in U$ — an elem. of this class.

$$|P^u| = P_{n_1,\ldots,n_k}(q) \text{ — a Hall polynomial}$$

(the number of fixed points of this element). $u = 1$ — obtain the Poincare polynomial. This allows one to determine the Poincare polynomial for any split group.



Original source details: GELFAND-P000366

Uncertain reading. The abbreviation after “This” has a first sign resembling Russian п, then a rounded sign and a z-like descending movement. “Pozv.” (“allows”) is provisionally rendered; the earlier reading “nazv.” is not secure. The Russian abbreviation remains unexpanded.

J. A. Green, Trans. A. M. S., 1955 — recommended.

There are bounds on the dim. of the variety lying over a point here.

$$\pi : \bar{R} \longrightarrow R,$$

$$\dim \pi^{-1}(g) \leq \frac{\dim Z_g - (n-1)}{2}$$

Z_g — the centralizer of g.

B. Rosenfeld. On notes by Rego, C. R., t. 272 (1971). ~~In the tang. space.~~



Original source details: GELFAND-P000366

Diagram and typed description.

Given a distribution (integrable) on M with it Frobenius cond.

are assoc. certain cohomologies.



Original source details: GELFAND-P000366

Uncertain reading. Above “diff. forms” a word is inserted, provisionally “kompleksno.”, rendered as “complex...”. The ending and contraction are doubtful; “kompleksna.”, “kompleksn.” and “kompleksa.” also remain candidates. Grammar has not selected a reading.

Every diff. of the graded ring complex...[?] diff. forms on M has the form

$$d_{L_1} + i_{L_2}$$

(i_{L_2} — interior multiplication by a vector-form).

– – – – – – – – – – – – – – – – – –

$\omega(X_1, \ldots, X_q)$ — a scalar form.

$L(X_1, \ldots, X_p)$ — a form (vector-valued).

$(i_L\omega)(X_1, \ldots, X_{p+q-1})$ substitute and antisymmetrize.

$$d_L\omega = (d \circ i_L + (-1)^p i_L \circ d)\omega.$$

L — a form of degree 0 (vector field) — d_L — the Lie derivative. ~~$d_L^2 = 0$~~[?]

Original source details: GELFAND-P000366

Uncertain reading. Before “integrability” a short formula is cancelled. $d_L^2 = 0$ is provisionally shown; the index and exponent on d are hidden by overlapping strokes and not established securely.

Integrability. (square $= 0$)

GELFAND-P000367

Prof. Ptak.

$$\dim E \leq \infty, \qquad E \text{ with a norm.}$$



Uncertain reading. Between dim E and ∞ several oblique and horizontal strokes overlap. $\leq$ is provisionally shown; $<$ and $\neq$ remain candidates.

Original source details: GELFAND-P000367

q — an exponent (crit.) if

$$1^\circ. \quad A \in L(E), \quad 1 = |A| = |A^{\boldsymbol{q}}| \Rightarrow |A|_\sigma = 1 \quad \text{(sp. radius)}.$$

Uncertain reading. The exponent on the second A is heavily thickened or rewritten. q is shown provisionally; the earlier exponent is unestablished.

Original source details: GELFAND-P000367

$$2^\circ. \quad \exists B, \quad 1 = |B| = |B^{q-1}|, \quad \text{but } |B|_\sigma < 1.$$

$$\ell^\infty \quad |x| = \max |x_i|, \qquad q(n) = n^2 - n + 1.$$

$$\ell_1 \quad \sum |x_i|,$$

$$\ell_2 \qquad q(n) = n.$$

There exists a 2-dim. space in which $q = \infty$. (The norm gives poor estimates of convergence; eigenvalues are needed).



Original source details: GELFAND-P000367

Diagram and typed description.



A — rotation by a small angle (Danzer's example). ℓ_p — unknown whether it exists, except for $p = 2^m$. A useful problem for computational mathematics.

$$M(n) = \text{min over all ban. } \leq n.$$



Original source details: GELFAND-P000367

Uncertain reading. The abbreviation after "over all" is provisionally shown as "ban.". Its middle letters are heavily thickened and rewritten; earlier strokes are not separated. The abbreviation is not expanded.

$\exists$ those for which $< n$! There exists a seq. $M(n_k) \sim \sqrt{n_k}$. It is unknown whether $\liminf M(n) = \infty$ is true.

$$\ell_4^2 \underset{\ell_1}{\oplus} \ell_8^2$$



Original source details: GELFAND-P000367

Uncertain reading. Above the cancelled earlier word is the legible outlined insertion "here". The earlier "eto" ("this") is shown provisionally; the covered letters do not establish its complete reading.

— here ~~this~~[?] dim $= 12$, and crit. exponent $= 11$.

$$C(E, r, \rho) = \max\{|T^r|,\ |T| \leq 1,\ |T|_\sigma \leq \rho\}.$$

$$0 < \rho < 1.$$

GELFAND-P000368

[source number: 26]

I. M. Gelfand.

C Radon formula over a finite field.



Original source details: GELFAND-P000368

Uncertain reading. Before "formula" is a separate C-shaped sign, shown as "C". Its meaning and relation to the following abbreviation are unestablished.

Over F_q an n-dim. space. $(x_1, \ldots, x_n)$. q^n points.

Integrals over all planes are known.

$$\varphi(p) = \int_{x \in p} f(x) \quad \text{(sum)}.$$

p — a plane.



Original source details: GELFAND-P000368

Diagram and typed description.

$\sum_{p \ni x_0} \varphi(p) =$ number of points of $(n-1)$-dim. project. space $= \frac{q^n - 1}{q - 1}$ $\cdot f(x_0)$ this many times counted x_0

$$+ \frac{q^{n-1} - 1}{q - 1} \sum_{x \neq x_0} f(x).$$



Original source details: GELFAND-P000368

Uncertain reading. In the cancelled term the angular sign before (x_0) is provisionally shown as A. f remains a candidate; the crossing cancellation strokes prevent a unique reading. The entire term is cancelled; an equals sign follows it.

~~$+ \frac{q^{n-1} - 1}{q - 1} A(x_0)$[?] $=$~~

$$\sum_x f(x) = \sum_{p \| p_0} \varphi(p) \quad [?] \quad \equiv C.$$



Undeciphered passage. Between the sum over $p \parallel p_0$ and $\equiv C$ several signs are cancelled. Their reading is unestablished.

Original source details: GELFAND-P000368

(does not depend on p_0) — a cond. on $\varphi(p)$ — an analogue of the Paley–Wiener theorem.



Original source details: GELFAND-P000368

Diagram and typed description. The sum $\sum_x f(x)$ is circled; beneath it "C — known." is underlined. The lower index has overlapping strokes and a small loop; x is retained provisionally.

$$= \frac{q^n - 1}{q - 1} f(x_0) + \frac{q^{n-1} - 1}{q - 1} \left(\sum_x f(x) \right) - \frac{q^{n-1} - 1}{q - 1} f(x_0).$$

C — known.

Rota — as $q \to 1$ one obtains a passage to simple theorems. $C_k^n(q)$ — the number of k-dim. subspaces of an n-dim. space.

$$\lim_{q \to 1} C_k^n(q) = C_k^n \text{ — combinations.}$$

GELFAND-P000369

Kirillov.

Consider an arbitrary generalized function A on a manifold M (e.g. R^n). For it a wave front is defined

$$WF(A) \subset T^*M.$$

A smooth function — zero wave front (empty). Let $\xi \in T^*M$.

$$\xi \notin WF(A), \quad \text{if}$$
$$\langle A, \varphi e^{it\psi} \rangle = o(t^{-n}), \quad \forall n \quad \text{as } t \to +\infty.$$



Uncertain reading. The phase sign after it is heavily thickened or rewritten. ψ is shown provisionally; the earlier strokes are not separated.

Original source details: GELFAND-P000369

(here $d\psi = \xi$ at the point π_ξ and $\varphi \in C_0^\infty$ is arbitrary).

It is convenient to study functions for which the wave front $\in$ a Lagr. manifold.

$$N \subset M \longrightarrow \underline{\text{norm. bundle over } N}$$

(tangent covectors perpend. to N).

This is a Lagr. subman. of $1/2$ dimension.

~~[?]~~ P. D. O. — a generalized function on $M \times M$ (kernel) with a wave front constructed in this way from the diagonal.

Original source details: GELFAND-P000369

Uncertain reading. Before “P. D. O.” a short word is heavily cancelled. “Napr.” (“e.g.”) remains a candidate; the complete reading is unestablished.

~~$A(p,q) =$~~

$$\langle A[?]u\rangle = \int e^{i\psi(x,\xi)} a(x,\xi) u(x)\, dx\, d\xi.$$



Original source details: GELFAND-P000369

Uncertain reading. Between A and u is a reinforced vertical sign with an upper loop or dot and a lower bend; beside it is a separate lower stroke. i, a comma, a semicolon and a cancelled sign remain possible readings.

(Value of A on the test function u).
Every A ~~[?]~~ with wave front defined this way is given by this formula.



Original source details: GELFAND-P000369

Undeciphered passage. After “Every A” a separate sign is heavily cancelled. Its reading is unestablished.

Original source details: GELFAND-P000369

Uncertain reading. After “Wave front” a rounded sign is cancelled. φ is shown provisionally; another reading is not excluded. The following $\in \Lambda$ is retained separately from the cancellation.

$$\text{Wave front } \varphi[?] \in \Lambda = \left\{ \begin{matrix} x, \xi \\ x \in M \\ \xi \in T^* M \end{matrix} \;\middle|\; d\psi = \xi\, dx \right\}.$$

GELFAND-P000370

[source number: 27]

20/IX '

Uncertain reading. To the right of 20/IX is a separate short vertical 1-like stroke. Its meaning is unestablished.

Original source details: GELFAND-P000370



Original source details: GELFAND-P000370

Diagram and typed description.

A. Cartan, Cartier (?), Kuiper, Deligne. — guests.

Atiyah.

I. Bernstein. on work of Godbillon, Vey. Comptes rendus. M — a compact manifold. On M is given a form ω (a foliation S of codim. 1), which is integrable.

$$d\omega = \omega \wedge \omega_1.$$

— [?]



Undeciphered passage. After the formula an earlier word is heavily cancelled; its reading is unestablished.

Original source details: GELFAND-P000370

[?] To it is associated $\alpha_s \in H^3(M, R)$, it



Undeciphered passage. Before "To it is associated" an entire phrase is heavily cancelled; its reading is unestablished.

Original source details: GELFAND-P000370

[?] $= 0$ if this is a fibration and is stable under deformations,

Undeciphered passage. After "it" and before $= 0$ a short word is heavily cancelled. No confident reading of its letters is established.

Original source details: GELFAND-P000370

[?] $\neq 0$.

Undeciphered passage. Between "under deformations" and $\neq 0$ a short word is crossed out; its reading is unestablished.

Original source details: GELFAND-P000370

Construction: there exist forms ω_1, ω_2:

$$d\omega = \omega \wedge \omega_1;$$
$$d\omega_1 = \omega \wedge \omega_2.$$

Consider $\underline{\Omega = \omega \wedge \omega_1 \wedge \omega_2}$

— closed, and the cohom. class does not depend on the choice of ω_1 and ω_2. There is a connection with the cohomology of algebras.



Original source details: GELFAND-P000370

Uncertain reading. After $SL(2, R)$ is a reinforced M-like sign. M is shown provisionally; the overlapping strokes are unestablished.



Original source details: GELFAND-P000370

Diagram and typed description.

Example: $SL(2, R)\,M$[?]

Γ — compact.

discr. subgr.

and $\begin{pmatrix} a & 0 \\ c & b \end{pmatrix}$ dense trajectories —

— always.

Then it is $\neq 0$.

Foliation:

$\varphi_i : U_i \longrightarrow R,$
$\varphi_j\varphi_i : U_i \cap U_j \longrightarrow R.$

on an interval of the line

Since the leaves are the same, one obtains $\Psi_{ij} : R \to R$ (an interval). If $\Psi_{ij} \in$ a group, then a cocycle with coeff. in the group $\longrightarrow$ a bundle and from it cohomology classes. But this is a pseudogroup. But consider a Lie algebra isom. to W_1 — formal vector fields on the line, $f(x)\frac{d}{dx}$. They are $= 0$, except there exists $H^3(W_1, R) = R$. This is precisely that class.

Atiyah. On the spectrum of a selfadj. elliptic operator. X — a compact manifold, D — an elliptic diff. operator, selfadj. $D^* = D$. Discr. spectrum; eigenvalues are divided into positive and negative. Let $D = D_t$, t — a param.; the spectrum changes with t.



Original source details: GELFAND-P000370

Diagram and typed description. An inclined nearly vertical line with twelve distinguishable transverse strokes of different lengths and short overlapping strokes. One stroke in the middle is thickened. Exact intervals and separation of all overlapping strokes are unestablished; there are no numerical labels.



Let $D_{t+1} = D_t$ — periodicity, or



Original source details: GELFAND-P000370

Uncertain reading. The first U stands on the main line; a small cancelled earlier sign is above and to its right. “na” remains a candidate; the exact reading is unestablished. The order of insertion is undetermined.

$$D_{t+1} = U \overset{[?]}{} D_t U^{-1}$$

— general!

($U =$ const).

$$\operatorname{Spec} D_{t+1} = \operatorname{Spec} D_t.$$

The spectrum moves (eigenvalues may shift by q[?]).

Original source details: GELFAND-P000371

Uncertain reading. After "by" is a reinforced q-like sign. q is shown provisionally; a question mark remains a candidate.

One can define an integer characterizing this shift. (Place an observer at 0 and see what mass has passed to the left and to the right.)



Original source details: GELFAND-P000371

Diagram and typed description. Upper drawing: axes λ, t, marks $0, 1$, two verticals and three wavy curves. Thick dots occur at endpoints and on the axis; the lower right dot has a light centre. Below are six distinguishable inclined segments between nearly vertical lines. Exact separation of overlapping strokes and joins is unestablished.





Original source details: GELFAND-P000371

Undeciphered passage. In the middle of the lower drawing a short caption is cancelled, distinct from the inclined lines. No complete word or formula has been recovered.

Example. Spectral flow $\in Z$.

$$X \text{ — a circle}, \qquad D_t = -i\frac{d}{dx} + t, \qquad Uf = e^{ix} f.$$

Flow $= \pm 1$ $(n \to n+1)$. This is a top. invariant under deformations of the family. Problem: compute spectral flow from the geom. data of the problem: manifold, operator, U. Connected with the index. Let the operator D be of 1 st order (a system). Consider

$$P \equiv D_t + \frac{\partial}{\partial t}$$

on functions $f(x,t)$, $f(x,t+1)=f(x,t)$, $x\in X$, $(U=1)$. (if $U\neq 1$, adjust $U\otimes 1$). This is an elliptic operator on $X\times S^1$ (or in a bundle, base S^1, fibre X). (D_t — Hermitian, $\frac{\partial}{\partial t}$ — skew-Hermitian). Theorem.



Original source details: GELFAND-P000371

Uncertain reading. Near the right family brace an upper 1-like stroke and a lower 0-like loop join the reinforced brace strokes. Possible limits 1 and 0 are not confidently separated; no definite interval is assigned.

Spectral flow $\{D_t\}=$ $\sqrt{\pm}$ index P

$=$ the index formula.

A direct proof is difficult. It is easier to express spectral flow by a formula. Heuristic considerations. Let D_t depend real-analytically on t. ~~[?]~~



Original source details: GELFAND-P000371

Undeciphered passage. After “real-analytic” a short word is entirely crossed out. Its reading is unestablished.

~~[?]~~



Original source details: GELFAND-P000371

Uncertain reading. At left an entry is cancelled: an initial t-like form and at right a t_0- or 0-like ending. $t\dots t_0$, $t=t_0$, $t=0$, $t\dots 0$ remain candidates; the relation sign is unestablished.

$$\lambda_1(t),\ \lambda_1(t),\ \lambda_2(t), \dots$$

— analytic functions!; defined for all t. (Roots of char. polynomials; real $\Rightarrow$ no branching).

Original source details: GELFAND-P000371

Diagram and typed description. A nearly vertical line and two groups of branches at different levels: upper crossing curves, below a right rising branch and a downward-bent branch, and oblique strokes at left. Exact joins of thick strokes and endpoints are unestablished.



GELFAND-P000372

[source number: 28]

Periodicity $\Rightarrow$ a permutation σ of them.

$$-i\frac{d}{dx} + t, \qquad \sigma(n) = n + 1.$$

These σ are not arbitrary. Orbits of σ — 4 classes are possible. 1) finite — an eigenvalue that returns. 2) bounded on one side (from $-\infty$ to $-\infty$ or from $+\infty$ to $+\infty$). 3) unbounded on either side.

Original source details: GELFAND-P000372

Diagram and typed description. To the right of case3 is a descending zigzag and several wavy or angular strokes with solid and interrupted parts; in the middle is a downward arrow-like stroke. Exact joins and geometric meaning are unestablished.



$$(|\lambda'(t)| < C|\lambda(t)|.)$$

Increasing and decreasing — the numbers of orbits of ob.[?] classes p and q are finite.

Original source details: GELFAND-P000372

Uncertain reading. The abbreviation after “orbits” is provisionally shown as “ob.”. The first letter has a gap; “sb.” remains a candidate. The abbreviation is not expanded.

Functions $\underline{\underline{\lambda(t)}}$ on the cylinder. 3) — spirals go upward or downward.



Original source details: GELFAND-P000372

Diagram and typed description. Two drawings between verticals: at left overlapping loops, solid and interrupted parts, an upper rightward arrow and a lower dot at right. At right are several arcs with solid and interrupted parts. Additional directions and hidden joins are unestablished.



The number of orbits of class3) is finite. (intersection with a <u>horizontal</u>) <u>Spectral flow</u> $\Rightarrow p - q$. (obvious from this). <u>Assumption:</u> let the eigenvectors be independent of t. Then ~~[?]~~ ~~[?]~~ exact solution



Undeciphered passage. After “Then” and before “exact solution” two short words are crossed out. Neither reading is established.

Original source details: GELFAND-P000372



Original source details: GELFAND-P000372

Uncertain reading. The first operator before the plus is reinforced over an earlier sign. D_t is shown provisionally; earlier strokes with a possible ∂ are not separated. Below the plus is a separate $(-)$; this insertion does not replace the main plus.

$\left(\underset{(-)}{D_t}[?] + \frac{\partial}{\partial t}\right) u = 0$ write it thus:

$$u_n = C_n \exp\left(-\int \lambda_n(t)\,dt\right), \qquad u = \sum u_n e_n, \quad e_n \text{ — an eigenvector.}$$

$$\lambda_n(t+1) = \lambda_{\sigma(n)}(t).$$

$$\sigma(n) \longrightarrow \infty \iff \text{finite } n \text{ and large } t.$$

$$u_n(t) = C_n \exp\left(-\int_0^t \lambda_n(s)\,ds\right).$$

p — the number of solutions of the equation with $+$,



Original source details: GELFAND-P000372

Diagram and typed description.

q ——————— // ——————→ $-$, adjoint to the equation with $+$.

Finite orbits $\int_0^N \lambda_n(t)\,dt = 0$, N — the period.

Index $= p - q$. In the general case (vectors move), the equation $D_t + \frac{\partial}{\partial t}$ contains an additional term expressing the motion of eigenvectors. A direct analytic proof cannot be used here.

GELFAND-P000373

Examples. ①. $T : X \longrightarrow X$ — a diffeom. Define a bundle.



Original source details: GELFAND-P000373

Diagram and typed description.



Let there be a functorial situation (X, g, D), g — a Riem. metric, D — a selfadj. operator. (The case of a spectrum unbounded on both sides is interesting). One then obtains:

$$X_t, g_t, D_t.$$

Original source details: GELFAND-P000373

Uncertain reading. After "when" a separate sign is cancelled; A remains a candidate. Above it "this" is readable. The earlier sign is not confidently recovered.

(E.g.: $d + \delta$, when this ~~[?]~~ is selfadj.).

Spectral flow does not depend on the choice of Riem. metric. If T is an isometry, then $D_t =$ const and spectral flow $= 0$. The invariant is an obstruction to the existence of a metric preserved by T. ②. $X \times S^1$, the operator $(d + \delta)_t$ on forms. Twisted using this map. Suppose given

$$\pi_1(X) \longrightarrow Z \longrightarrow S^1$$
character.

$$X^{4k+1} \times S^1$$

— a Novikov invariant using the Hirzebruch L-polynomial. Deligne, in Manin's translation. On the theory of motives. Different cohomology theories of alg. varieties. 25/X-71 | S. Gelfand. Schubert cells. Horrocks, Proc. Lond. Math. Soc., 7, $N°$[?] 26, 1957.



Original source details: GELFAND-P000373

Uncertain reading. Between 7 and 26 is an N-like entry with a short upper or horizontal stroke. $N°$ is shown provisionally; $N =$ remains a candidate.

$G(N,n)$ — the complex Grassm.

(n-planes in C^N)
$\shortparallel$
E



Original source details: GELFAND-P000373

Diagram and typed description. The tuple is framed. At right a line leads to “points where the func. jumps”; below is the insertion “dim.” joined by an oblique stroke to the end of the caption. Its exact attachment to the lower line is unestablished.

$a_1 \le a_2 \le \dots \le a_n \le N$ — tuple — — points where the func. jumps

dim.

A fixed flag is chosen.

$$E_1 \subset E_2 \subset \dots \subset E_N = E,$$
$$\dim E_i = i.$$
$$F \in \Omega(a_1, \dots, a_n), \quad \text{[?]}$$

Undeciphered passage. After $F \in \Omega(a_1, \dots, a_n)$ an entire word is cancelled by several thick horizontal strokes. Its reading is unestablished.

Original source details: GELFAND-P000373

$$\Updownarrow$$
$$\dim(F \cap E_{a_i+i}) = i.$$

$$\varphi(i) = \dim(F \cap E_i).$$

$\underline{\underline{a_i + i}}$ — the growth points of this function.

GELFAND-P000374

[source number: 29]

This is a cell decomposition of the Grassm. manifold. Problem. Find all invariant diff. forms (Chern classes). Connection between the cohom. basis and rings.

$$(*) \quad U(N)/(U(n)\times U(N-n)) = G(N,n) = G/F.$$

The form can be lifted to $U(N)$. Construction of forms: de_{ij}. $U = (e_{ij})$, (e_{ij}) — a matrix-element function on $U(N)$.

$$\theta_{jk} = \sum_{p=1}^{N} \bar{e}_{kp}\, de_{jp}, \qquad j = 1,\dots,n, \quad k = n+1,\dots,N.$$

Uncertain reading. In the index on $\bar{e}$, after k, is a heavily reinforced p-like sign. p is shown provisionally; ρ remains a candidate.

Original source details: GELFAND-P000374

$j,k = 1,\dots,n$.



Original source details: GELFAND-P000374

Uncertain reading. In the last factor, beneath the bar, is a rounded sign with a horizontal stroke. Θ is shown provisionally; lowercase θ is not excluded. Its case is not established by mathematical consistency.

$$\Theta_{jk} = -\frac{1}{2\pi i}\sum_{s=n+1}^{N} \theta_{js}\wedge\bar{\Theta}_{ks}$$

curvature form of the bundle $(*)$.



Original source details: GELFAND-P000374

Diagram and typed description. Above ω is "form on G"; separately at right is G/F. The abbreviation after "skew" is not completely established:"tensor" remains a candidate; its initial t is retained in the line.

The condition that ω — form on G — skew t[?]. G/F

1) $\omega(X_1, \dots, X_k) = 0$, $X_i \in T(F)$ — tangent to F. 2) ω — invariant under F. All Θ_{jk} satisfy condition1). Invariant under $U(N-n)$; under $U(n)$ it transforms by conjugation (adjoint action).

$$GL(n) \ni (x_{ik})_{i,k=1}^{n}.$$

Construct polynomials in the matrix elements with the property

$$p(x) = p(gxg^{-1}).$$

Coefficients of the char. polynomial — elementary symm. functions. A basis of the linear space is needed. Let $\lambda_1 \geq \lambda_2 \geq \dots \geq \lambda_n \geq 0$ be integers. x — a matrix, $\alpha_1, \dots, \alpha_n$ — eigenvalues. One must take

GELFAND-P000375

symm. fns.



Original source details: GELFAND-P000375

Uncertain reading. The small faint note above the first determinant is provisionally rendered "symm. fns."; a longer final contraction remains possible.

$$\{\lambda\} = \frac{\begin{vmatrix} \alpha_1^{\lambda_n} & \alpha_1^{\lambda_{n-1}+1} & \dots & \alpha_1^{\lambda_1+n-1} \\ \vdots & \vdots & & \vdots \\ \alpha_n^{\lambda_n} & \alpha_n^{\lambda_{n-1}+1} & \dots & \alpha_n^{\lambda_1+n-1} \end{vmatrix}}{\begin{vmatrix} 1 & \alpha_1 & \dots & \alpha_1^{n-1} \\ \vdots & \vdots & & \vdots \\ 1 & \alpha_n & \dots & \alpha_n^{n-1} \end{vmatrix}} = \{\lambda\}(\chi_{ij}) \text{ — a polynomial.}$$



Original source details: GELFAND-P000375

Uncertain reading. Above the first numerator entry is a separate heavily overwritten entry. An α-like form and neighboring short strokes are visible; the earlier index is not securely recovered.

This is the character of a representation.



Original source details: GELFAND-P000375

Undeciphered passage. The outlined insertion “determ. by numbers” lies above the cancelled earlier phrase. Its initial Russian “so” and separate final strokes are visible; the words under the dense horizontal strokes are not established in full.

determ. by numbers

~~so [?]~~

$$\lambda_1 \geq \lambda_2 \geq \cdots \geq \lambda_n \geq 0[?].$$



Original source details: GELFAND-P000375

Uncertain reading. The last small oval has an attached lower stroke. 0 is provisionally shown; a remains a candidate.

$\{\lambda, \textcircled{H}\} = \textcircled{H}^{\{\lambda\}}$ — notation.



Original source details: GELFAND-P000375

Uncertain reading. The elevated entry after the enclosed letter contains λ and two curly strokes. Braces $\{\lambda\}$ are provisionally rendered; not all overlapping strokes have been separated.

$\textcircled{H}$ — a matrix of diff. forms (they have degree 2 and commute).



Original source details: GELFAND-P000375

Uncertain reading. Within the circular enclosure is a short transverse bar with two side strokes. H inside a circle is provisionally typeset; its case is not established. The forms in the notation line and the definition line are retained separately.

Put $a_i = N' - n - \lambda_i$.



Original source details: GELFAND-P000375

Uncertain reading. Between N and the minus is a separate thin rising stroke above the line. N' is provisionally rendered; the meaning of the stroke is not established.

Then



Original source details: GELFAND-P000375

Diagram and typed description.

$\int \textcircled{H}^{\lambda} = 1$, and on the others 0.

$\Omega(a_1, \ldots, a_n)$ degree = dim. of the Schubert cell.

Problem (I. M. Gelfand)

$$g \in SL(2, F_q).$$

Group ring $\sum_g a(g)g$. $(a(g) \leftarrow$ alg. closure $F_q)$.



Original source details: GELFAND-P000375

Uncertain reading. After $a(g)$ is a separate leftward sign with upper and lower oblique strokes. $\leftarrow$ is rendered; a membership reading is not securely accepted.

Describe it. A. Vinogradov. Global aim — to expel analysis from the theory of linear diff. operators.



Original source details: GELFAND-P000375

Diagram and typed description.

K — a ring, (arbitr.)

$M \longrightarrow N$

2 modules over K

Classical situation



Original source details: GELFAND-P000375

Diagram and typed description.

$K = C^{\infty}(L)$ (L — manifold)

$C^{\infty}(E_1) \xrightarrow{\mathcal{D}} C^{\infty}(E_2)$

K may be noncommutative.

GELFAND-P000376

[source number: 30]

$$M \xrightarrow{\mathcal{D}} N.$$

$k \in K$,



Original source details: GELFAND-P000376

Undeciphered passage. The right-hand side after $k\mathcal{D} =$ is crossed by horizontal and oblique strokes. Its earlier signs have not been read in full.

$k\mathcal{D} =$ [?] $\qquad (k\mathcal{D})f = k(\mathcal{D}f)$

$k^{+}\mathcal{D} = \mathcal{D}k.$ $\qquad (k^{+}\mathcal{D})f = \mathcal{D}(kf).$

$$\delta_k = k^{+} - k.$$

Basic definition. A diff. operator — an additive map



Original source details: GELFAND-P000376

Undeciphered passage. After the visible n an earlier sign is densely cancelled. Curly strokes lie to the left of n, with a wavy line below "ord.". The complete earlier reading is not established.

$\mathcal{D}$:

ord. n [?] $\qquad \delta_{k_0}\delta_{k_1}\cdots\delta_{k_n}\mathcal{D} = 0$

$\forall k_0, \ldots, k_n$

In the classical case this agrees with the usual one. In this way one algebraically constructs the theory of de Rham homology and so on. (Spencer.[?] and oth.)



Uncertain reading. After “Spencer” are faint separate strokes before “and oth.”. A period after the surname is provisional; a reading without it is not excluded. The final contraction remains unexpanded.

Original source details: GELFAND-P000376

$\mathrm{Diff}_n^+(M,N)$ — all these operators. a module with multiplication $\underline{k^+}$.



Original source details: GELFAND-P000376

Diagram and typed description.

$\mathrm{Diff}_n^+(M,N)$ $\quad$ $\mathrm{Diff}_n(M,N)$

$\|\ def$ $\quad$ $\|\ def$

$\searrow$ $\quad$ $\downarrow$

$\mathrm{Hom}_K(M,\ \mathrm{Diff}_n^+ N\ )$ $\quad$ $\mathrm{Hom}(J^n(M),N)$



Original source details: GELFAND-P000376

Diagram and typed description.

$\mathrm{Diff}_n^+(N) = \mathrm{Diff}_n^+(K,N) \quad \Longrightarrow$

$\mathrm{Diff}_n^+(N)$

$\diagdown$

cojets.

$\Longrightarrow$ existence theorem, see $J^n(K)$ [?] — an existence theorem also exists.



Undeciphered passage. After $J^n(K)$ is a separate small sign with overlapping cancellation strokes. Its whole reading is not recovered.

Original source details: GELFAND-P000376

In Diff$_n$ K consider the algebra of operators generated by k, k^+.



Uncertain reading. Beneath the last k is a separate lower N/n-like sign. N is provisionally rendered; lowercase n and a reading without an independent index remain candidates. The upper plus is retained separately.

$$J^n(K) = \{k, k_N^+\}$$

Original source details: GELFAND-P000376

GELFAND-P000377

D_i — ~~[?]~~ functors $D_i(M)$ (de Rham homology).



Undeciphered passage. The word before "functors" is cancelled by several horizontal strokes. It has not been recovered in full.

Original source details: GELFAND-P000377

Define inductively. $D = D_1$ — derivations of K into N — denoted $D(N)$. $K \xrightarrow{\nabla} N$ is a derivation if



Original source details: GELFAND-P000377

Uncertain reading. After the first k inside the argument is one lower, nearly vertical stroke. k_1k_2 is provisionally rendered; k, k_2 remains a candidate. No separate comma after a lower 1 has been inserted.

$$\nabla(k_1k_2) = k_1\nabla k_2 + k_2\nabla k_1$$

This is a diff. op. of order 1. $(-k_1k_2\nabla(1))$.

This is $D(N)$ (vector fields with values in N). D — ordinary vector fields.

$$D_2(N) = D\{D(N) \subset \mathrm{Diff}_1^+ N\}.$$



Diagram and typed description.

$D \hookrightarrow \mathrm{Diff}_1^{(+)}$

Original source details: GELFAND-P000377



Original source details: GELFAND-P000377

Uncertain reading. The old adjective before “left” is densely cancelled. “right” is rendered as a candidate; the overlapping strokes do not yield an indisputable whole reading.

D — ~~right[?]~~ left module,

Diff_1^+ — right; D — a subset, and not a submodule

In $\mathrm{Diff}_1^{(+)}$ it is not a submodule, and the inclusion — a diff. operator of order 1. $D_2(N)$ — derivations of K into $\mathrm{Diff}_1^+ N$ which go into $D(N)$.

$$D_i(N) = D\{D_{i-1}(N) \subset (\mathrm{Diff}_1^+)^{i-1}(N)\}.$$

(by induction).



Original source details: GELFAND-P000377

Diagram and typed description.

1/XI-71 Hamilton-Jacobi equation:

$\delta_{k_1} \cdots \delta_{k_1} \mathcal{D}$ — left side of the Hamilton-Jacobi eq.



Uncertain reading. The last lower index contains thick overlapping strokes. k_1 is provisionally rendered; k_n is retained among the candidates.

Original source details: GELFAND-P000377

(calculate) (k_1 — the same everywhere). Existence theorem for $J^n(M)$:

Uncertain reading. The heading has n; the following quotient and Π_s have s. Both source indices are retained.

Original source details: GELFAND-P000377

$$K \otimes_{\mathbb{Z}} M/\Pi_s = J^s(M).$$

Π_s — the submodule in $K \otimes_{\mathbb{Z}} M$ generated by the required relations.

$$k(k' \otimes m) = kk' \otimes m,$$
$$\bar{k}(k' \otimes m) = k' \otimes km.$$

GELFAND-P000378

[source number: 31]

$$\Delta_{k_0 \ldots k_s} = (\bar{k}_0 - k_0) \cdots (\bar{k}_s - k_s).$$

Consider the submodule generated by these Δ.

$$K \otimes_{\mathbb{Z}} M = \underline{A} \supset \Delta(A) = \underline{\Pi_s} \quad \text{(the usual definition of jets).}$$

~~In the simplest[?] case simply Diff$_s^{(+)}(K, N[?])$~~ [?]



Undeciphered passage. The whole line is cancelled. “In the simplest[?] case simply” and formula strokes can be distinguished. The adjective ending and final overlapping signs are not recovered in full.

Original source details: GELFAND-P000378



Uncertain reading. In the cancelled Diff$_s^{(+)}(K, N[?])$ the target sign is N/M-like. N is provisionally rendered; M remains a candidate.

Original source details: GELFAND-P000378

$J^s(K)$ is simpler than in the general case.

$D_1(M)$ — diff. operators without a constant term. $D_1(M) = D(M)$ (derivations of K with values in M). $D(M) \subset \mathrm{Diff}_1 M$.

$$A \in D_1(M) \overset{def}{\iff} A(k, k_2) = A(k_1)k_2 + k_1 A(k_2).$$



Original source details: GELFAND-P000378

Uncertain reading. After the first k in the argument is one lower curved stroke, provisionally rendered as a comma. A lower 1 without a separate comma remains a candidate. No additional second sign has been inserted.



Original source details: GELFAND-P000378

Diagram and typed description.

$D_0(M) = M$;

$D_k(M)$ — a left module. (w.r.t. multiplication by k).

$$D_2(M) = D_1(D_1(M) \subset \mathrm{Diff}_1^+(M)).$$



Original source details: GELFAND-P000378

Diagram and typed description.

$D_{k+1}(M) = D_1(D_k(M) \subset \mathrm{Diff}^+_{\underbrace{1\ldots1}_{k\text{ times}}}(M))$

/

the k-fold application of the functor $\mathrm{Diff}_1^+(M)$.

Original source details: GELFAND-P000378

Undeciphered passage. Above the uncancelled “not a submodule” is a cancelled entry with visible parts “not” and “submod...”. The other letters are not recovered in full. Above the entry is a separate short vertical stroke.

$D_1(D_1(M) \subset \text{Diff}^+(M))$.

|

~~not a submod~~[?]

not a submodule

in the structure $\text{Diff}^+(M)$.



Original source details: GELFAND-P000378

Undeciphered passage. After “Diff.” before K a word is densely cancelled. It has not been read in full.

Diff. ~~[?]~~ of K into $\text{Diff}_1^+(M)$,

~~[?]~~ whose values lie

in the subset $D_1(M)$.

Original source details: GELFAND-P000378

Undeciphered passage. Before “whose” is a separate short fragment beneath cancellation strokes. It has not been deciphered in full.



Original source details: GELFAND-P000378

Diagram and typed description.



$0 = 1$ with ends identified.

M — functions.

$\underline{\underline{M = K}}$.

$$D_1(M) = \left\{ a \text{[?]} \frac{\partial}{\partial x} + b \frac{\partial}{\partial y} \right. .$$



Original source details: GELFAND-P000378

Undeciphered passage. After the legible a its argument is densely overwritten and cancelled. It has not been deciphered in full. An opening curly brace is visible; no closing brace has been added.

$$\text{Diff}_1^+ : a \frac{\partial}{\partial x} + b \frac{\partial}{\partial y} + c.$$

$$K(x) \longrightarrow \text{[?]}\, a_k \frac{\partial}{\partial x} + b_k \frac{\partial}{\partial y}.$$



Original source details: GELFAND-P000378

Undeciphered passage. Immediately after the arrow a short prefix is cancelled. It cannot be read in full. The line lies at the lower edge of the frame.



Original source details: GELFAND-P000378

Uncertain reading. Beside a and b are compact k-like strokes. Lower indices a_k, b_k are provisionally rendered; $a(k), b(k)$ remain candidates. Complete parentheses are not recovered.

$$a(k_1k_2)\frac{\partial}{\partial x}+b(k_1k_2)\frac{\partial}{\partial y}=a(k_2)\frac{\partial}{\partial x}k_1+b(k_2)\frac{\partial}{\partial x}k_1+$$
$$+a(k_1)\frac{\partial}{\partial x}k_2+b(k_1)\frac{\partial}{\partial x}k_2;$$



Uncertain reading. In the four right-hand terms the denominators read ∂x, including those with b. These source signs are retained.

Original source details: GELFAND-P000379

Hence $a(k_1k_2)=a(k_2)k_1+a(k_1)k_2$ and b — a derivation, and also the condition:

$$a(k_2)\frac{\partial k_1}{\partial x}+a(k_1)\frac{\partial k_2}{\partial x}$$
$$+b(k_2)\frac{\partial k_1}{\partial x}+b(k_1)\frac{\partial k_2}{\partial x}\quad =0\ldots=0.$$



Uncertain reading. After the sum, $=0$ is crossed by a separate oblique stroke. Separate dots and a faint lower stroke follow; then there is an uncancelled $=0$.

Original source details: GELFAND-P000379

$$\left(a(k_2)\frac{\partial}{\partial x}+b(k_2)\frac{\partial}{\partial y}\right)k_1+\sim=0.$$
$$D_1(k_2)k_1+D_1(k_1)k_2=0.$$

Uncertain reading. The first lower 1 is densely overwritten. D_1 is provisionally rendered; the earlier overlapping strokes are not recovered in full.

Original source details: GELFAND-P000379



Original source details: GELFAND-P000379

Diagram and typed description.

$k \longrightarrow D_1(k)$.

$D_1(k_2)k_1 + D_1(k_1)k_2 = 0.$ — requirement.



Original source details: GELFAND-P000379

Undeciphered passage. At the left margin before $D_k(M)$ a separate sign is cancelled. It has not been deciphered in full.

~~[?]~~ $D_k(M)$ —k-forms on the ~~[?]~~ manifold with values in M.

~~[?]~~

~~Def.-e.[?]~~

Original source details: GELFAND-P000379

Undeciphered passage. Between “on” and “manifold” a sign is densely cancelled. It has not been recovered in full.

Original source details: GELFAND-P000379

Uncertain reading. Below the line at left is a cancelled contraction, provisionally “Def.-e.”; “Def.-o.” and “Def.” are retained as alternatives. The ending is not expanded.



Original source details: GELFAND-P000379

Undeciphered passage. Below “forms” is a separate cancelled entry. It has not been recovered in full.



Original source details: GELFAND-P000379

Diagram and typed description.

$$\underbrace{\mathrm{Diff}^+_{1,1,\dots,1}}_{k\text{ times}} = (\mathrm{Diff}^+_1)^k = \underbrace{\mathrm{Diff}^+_1(\cdots \mathrm{Diff}^+_1 \cdots)}_{k\text{ times}}.$$

$$(\mathrm{Diff}^+_1)^2(M) = \mathrm{Diff}_1(K, \mathrm{Diff}^+_1 M).$$

Definition of exterior differential forms. (the de Rham complex over the ring K)

Original source details: GELFAND-P000379

Diagram and typed description.

$$D_i(M) \overset{def}{=} \mathrm{Hom}_K(\ \Lambda_i\ , M);$$

$$\Lambda_i = \Lambda_i(\cancel{M}[?]\, K).$$

Uncertain reading. In the argument before the legible K an M/N-like sign is cancelled. M is provisionally rendered; N remains a candidate.

Original source details: GELFAND-P000379

Theorem: representing objects exist. $K = \mathbb{Z}_2$ will have $D_2 \neq 0$! (the 2-dimensional classical de Rham).

GELFAND-P000380

[source number: 32]

Consider the group ring $\Gamma_2(\mathbb{Z}_2)$ (with coefficients in $\mathbb{Z}_2$).



Uncertain reading. The first capital is Γ/Γ-like and is provisionally rendered as Γ. F remains among the candidates. The lower 2 s are retained.

Original source details: GELFAND-P000380

All de Rham cohomology groups —$\mathbb{Z}_2$. For group rings, de Rham cohom. — group cohom.!



Original source details: GELFAND-P000380

Uncertain reading. At the upper right of J in the sequence is a separate dense sign with overlapping strokes. Its whole reading and meaning are not established; it is rendered as [?].

$\Lambda_1^{\text{old}}(K)$

$$0 \longrightarrow J^{[?]} \longrightarrow K \otimes K \xrightarrow{\text{mult.}} K \longrightarrow 0$$

$J^1/J^2 = \Lambda_1$, the rest — exterior powers.



Original source details: GELFAND-P000380

Uncertain reading. At the upper right of the numerator are dense overwritten strokes. J^1 is provisionally rendered; J without an independent power and J with an unidentified earlier power remain candidates. The denominator J^2 is legible.

For a field these cohomologies will be 0, and the Vinogradov ones $\neq 0$. This definition is unnatural in the categorical sense. They are not defined for noncommutative rings. This is the only natural definition in the category of rings. The differential d.



Original source details: GELFAND-P000380

Undeciphered passage. Below the map is a separate small sign with overlapping cancellation strokes. It has not been recovered in full.

$D_k \longrightarrow D_{k-1}(\mathrm{Diff}_1^+)$ morphism of functors.

(in other terms, d).

i.e. $D_k(M) \longrightarrow D_{k-1}(\mathrm{Diff}_1^+(M))$. natural map.

~~[?]~~

$$D_1 = D \underset{\text{incl.}}{\longrightarrow} \mathrm{Diff}_1^+ \quad (= D_0(\mathrm{Diff}_1^+)).$$



Uncertain reading. The first lower index is densely overwritten, with a loop-like component. 1 is provisionally rendered; 0 remains a visual candidate.

Original source details: GELFAND-P000380

$$D_1 \longrightarrow D_0(\mathrm{Diff}_1^+).$$

(not a module inclusion, but a differential operator of order 1).

$\mathrm{Diff}_n \longrightarrow \mathrm{Diff}_n^+$
(a differential operator of order n).

Induction:

$$D_k = D_1\{D_{k-1} \subset (\mathrm{Diff}_1^+)^{k-1}\}.$$



Original source details: GELFAND-P000380

Diagram and typed description.

$$D_{k-1}(\mathrm{Diff}_1^+) = D_1\{$$

$$D_{k-2}(\mathrm{Diff}_1^+) \subset (\mathrm{Diff}_1^+)^{k-2}(\mathrm{Diff}_1^+)\ \}.$$

$$\| \|$$

$$(\mathrm{Diff}_1)^{k-1}$$

Assume inductively that $D_{k-1} \subset D_{k-2}(\mathrm{Diff}_1^+)$, and then we obtain:

GELFAND-P000381

$D_k \subset D_{k-1}(\mathrm{Diff}_1^+)$. This is an ~~[?]~~ injective morphism of functors, that is

Undeciphered passage. Before “injective” a short sign or fragment is cancelled. It has not been deciphered in full.

Original source details: GELFAND-P000381



Original source details: GELFAND-P000381

Diagram and typed description.

$\forall$ module M: $D_k(M) \subset D_{k-1}(\mathrm{Diff}_1^+(M))$
submodule

Express this in the language of differential forms:



Original source details: GELFAND-P000381

Uncertain reading. In the diagram the lower $i-1$ at left and i at right are written over reinforced strokes. The current pair is provisionally rendered; the earlier lower signs are not recovered in full.

$$\begin{array}{ccc} \Lambda_{i-1} & \xrightarrow{\ \nabla\ } & \Lambda_i \\ & & \downarrow{\scriptstyle h} \\ & & M \end{array}$$

$$\boxed{\nabla \in \mathrm{Diff}_1^+(\Lambda_{i-1}, \Lambda_i)}$$

$$D_i(M) = \mathrm{Hom}(\Lambda_i, M).$$



Original source details: GELFAND-P000381

Uncertain reading. Above “ordinary” is a separate thick, nearly vertical stroke. An independent lower dot is not established; no complete exclamation mark has been supplied.

$\Lambda_i = \Lambda_i(K)$. — universal object. (a module over K).

ordinary diff. forms.

$$D_i(M) \overset{\alpha_i}{\longleftrightarrow} D_{i-1}(\mathrm{Diff}_1^+(M)).$$

$$h \in \mathrm{Hom}(\Lambda_i, M) \overset{\alpha_i}{\longleftrightarrow} \text{[?]}\,\mathrm{Hom}(\Lambda_{i-1}, \mathrm{Diff}_1^+(M)).$$

Undeciphered passage. Before the right-hand Hom a short fragment is densely cancelled. It has not been recovered in full.

Original source details: GELFAND-P000381

Let a differential operator of order 1 be given, $\Lambda_{i-1} \xrightarrow{\nabla} \Lambda_i$. Then to each $h : \Lambda_i \longrightarrow M$ assign the composition $h \circ \nabla \in \mathrm{Diff}_1^+(\Lambda_{i-1}, M)$.



Original source details: GELFAND-P000381

Diagram and typed description.

$$\forall \nabla \Longrightarrow D_i \overset{\alpha_i(\nabla)}{\longrightarrow} D_{i-1}(\mathrm{Diff}_1^+)$$

will be constructed.



Original source details: GELFAND-P000381

Diagram and typed description.

$$h \longrightarrow h \circ \nabla \in \mathrm{Diff}_1^+(\Lambda_{i-1}, M) \quad \Longrightarrow$$

$$\Longrightarrow \qquad \mathrm{Hom}(\Lambda_{i-1}, \mathrm{Diff}_1^+ M)$$

$$\mathrm{Hom}(J^1\Lambda_{i-1}, M)$$

And conj. on M



Original source details: GELFAND-P000381

Undeciphered passage. The first cancelled entry lies under the strokes of a reinforced rightward arrow; its whole reading is not recovered. At right, “diff.” is separately cancelled. Both parts and the arrow are retained.

~~[?]~~ ⟶ ~~diff.~~

a homomorphism $J^1\Lambda_{i-1} \longrightarrow \Lambda_i$, i.e. a differential operator $\Lambda_{i-1} \longrightarrow \Lambda_i$. Taking $M = \Lambda_i$ and the identity map gives what is needed.

GELFAND-P000382

[source number: 33]

$$\mathrm{Hom}(\Lambda_i, M) \overset{\alpha_i}{\longleftrightarrow} \mathrm{Hom}(\Lambda_{i-1}, \mathrm{Diff}_1^+(M)).$$

$M = \Lambda_i$ and id on the left. An element of $\mathrm{Hom}(\Lambda_{i-1}, \mathrm{Diff}_1^+(M))$ is by definition a differential operator of order 1 from Λ_{i-1} to M. (We find ∇, which exists and is unique). We must prove that



Diagram and typed description.

$$d^2 = 0.$$

Original source details: GELFAND-P000382

Consider



Original source details: GELFAND-P000382

Diagram and typed description.

$$\begin{array}{ccccc} D_{i+1} & \longrightarrow & D_i(\mathrm{Diff}_1^+) & \longrightarrow & D_{i-1}(\mathrm{Diff}_{1,1}^+) \\ & \searrow & & & \downarrow \\ & & & & D_{i-1}(\mathrm{Diff}_2^+) \end{array}$$

An aside: The ring $F_2(\mathbb{Z}_2)$—does not coincide with the classical ones. $0, 1, x$, ~~[?]~~, $1 + x$, $(x^2 = 1)$.

Undeciphered passage. After x and before $1 + x$ a separate element is cancelled. Its whole reading has not been recovered.

Original source details: GELFAND-P000382

$y = x + 1$, then $y^2 = 0$. $0, 1, y, 1 + y$, where $y^2 = 0$.

The Spencer operator (boundary) will be constructed.



Original source details: GELFAND-P000382

Diagram and typed description. At upper left is $D_{i+1}(\mathrm{Diff}_k^+)$, at upper right $D_i(\mathrm{Diff}_{1,k}^+)$, and below at right $D_i(\mathrm{Diff}_{k+1}^+)$. A horizontal arrow bears $\alpha_{i+1}(\mathrm{Diff}_k^+)$; at right is a downward arrow. A short diagonal down-right arrow stops before the lower expression; its Spc label is crossed out. A curved pointer from below at left approaches the start of the upper horizontal arrow. Under the diagonal is a curved vertical bracket to "This is the Spencer hom."; "Spencer" is underlined. Above the right expression are $\mathrm{Diff}_1(\mathrm{Diff}_k)$ and two short slanted strokes; the composition annotation is at right.





Uncertain reading. The sign after i has discontinuous vertical portions. Provisionally D_{i+1}; possibly D_{i-1}.

Original source details: GELFAND-P000382

Uncertain reading. After the left k a linking mark and a 2-like sign are cancelled. The earlier reading may be -2, $+2$, or another index ending in 2.

Original source details: GELFAND-P000382

Original source details: GELFAND-P000382

Undeciphered passage. After the right k an additional index fragment is cancelled. Its whole reading has not been recovered.

The Spencer complex:



Original source details: GELFAND-P000382

Diagram and typed description.

$$M \xleftarrow{\Delta} \mathrm{Diff}^{+}_{k} M \xleftarrow{Spc} D(\mathrm{Diff}^{+}_{k-1} M) \xleftarrow{Spc} \cdots \xleftarrow{Spc} \not{D}_{\bar{i}}$$

Original source details: GELFAND-P000382

Uncertain reading. The cancelled expression at the far right is provisionally D_i; the lower hook also admits D_1.



Original source details: GELFAND-P000382

Uncertain reading. All four labels have a third sign resembling c/e or a lower e-like sign. Provisionally Spc; possibly Spe. The diagonal label is crossed out; the three lower labels are current.

GELFAND-P000383

$$\longleftarrow D_i(\mathrm{Diff}^{+}_{k-i} M) \longleftarrow \cdots$$

This is the Spencer resolution (coresol. Sm.)



Original source details: GELFAND-P000383

Uncertain reading. In parentheses, “coresol. Sm.”; the final two joined Cyrillic letters admit “См.” or “Сп.”. The abbreviation is left unexpanded.



Original source details: GELFAND-P000383

Uncertain reading. The tiny word is provisionally “там”(“there”); possibly “тан” or “точ”. It is followed by “for J”. A separate short vertical stroke is above the area of “for”.

there for J.

$$M \longleftarrow \mathrm{Diff}^{+}_{\infty}\{M\} \longleftarrow D_1(\mathrm{Diff}^{+}_{\infty}\{M)$$
$$\longleftarrow \cdots \longleftarrow D_i(\mathrm{Diff}^{+}_{\infty} M) \longleftarrow \cdots$$



Original source details: GELFAND-P000383

Uncertain reading. The first M has braces with reinforced strokes. Before the second M is a brace-like sign, and after it a closing round parenthesis. Provisionally $D_1(\mathrm{Diff}^{+}_{\infty}\{M)$; the earlier form of the reinforced strokes is not established in full. All arrows point left.

$$\mathrm{Diff}^{+}_{\infty} M = \varinjlim \mathrm{Diff}^{+}_{i} .$$



Original source details: GELFAND-P000383

Diagram and typed description.

$$(\mathrm{Diff}^{+}_{i} \hookrightarrow \mathrm{Diff}^{+}_{i+1})$$

This is a complex. And a map (not yet defined)

$$\mathrm{Diff}_k^+ M \longrightarrow M.$$

$$\mathrm{Diff}_s^+(M,N) \stackrel{def}{=} \mathrm{Hom}_K(M, \mathrm{Diff}_s^+ N).$$

Let $\mathrm{Diff}^+ N \xrightarrow{\Delta} N$; Δ — an operator of order s. Then from the hom. $h : M \longrightarrow \mathrm{Diff}^+ N$ construct the composition. (we must take $\mathrm{Diff}_s^+ N$ as M and the identity map

$$id \in \mathrm{Hom}(M, \mathrm{Diff}_s^+ N).$$

we obtain $\mathrm{Diff}_s^+ N \longrightarrow N$.

This defines the 1 st morphism.



Original source details: GELFAND-P000383

Diagram and typed description. The map $M \longrightarrow \mathrm{Diff}^+ N$ following h is doubly underlined. Below Hom a separate thin diagonal stroke runs down to the right, without an arrowhead, towards the start of the next arrow. Before "we must" is an opening round parenthesis; no separate overall closing parenthesis is visible after the lower N.

$$\Delta \in \mathrm{Diff}_s^+(K,M) \longrightarrow \Delta(1).$$

Headings: All Spencer resolutions in non-coordinate form (a distinction from Spencer). The index over any ring. The Hamiltonian formalism for $\forall$ ring. Next time—continuation.

GELFAND-P000384

[source number: 34]

[ ]



Diagram and typed description.

8 XI Lemma 1.

Original source details: GELFAND-P000384

Diff$_n^+(M, N)$ for fixed N —a functor of M (contravar.).

Diagram and typed description.



Original source details: GELFAND-P000384

(and if we take Diff$_n(M, N)$, then this is a functor of N for fixed M (covar.)). Proof: $\mathcal{F}^+_{N,n}(M) =$ Diff$_n^+(M, N)$. If $f : M_1 \longrightarrow M_2$ a module hom. $\Longrightarrow$

$$\mathcal{F}^+_{N,n}(f) : \text{Diff}_n^+(M_2, N) \longrightarrow \text{Diff}_n^+(M_1, N).$$



Original source details: GELFAND-P000384

Uncertain reading. The right-hand inset reads $D \circ f : M_1 \longrightarrow M_2$; the final M_2 is retained. Its frame is open above, with a long lower stroke and short side bends.

$D : M_2 \longrightarrow N \rightsquigarrow D \circ f : M_1 \longrightarrow M_2$

And this is a module homomorphism, since



Original source details: GELFAND-P000384

Undeciphered passage. Before $D(kf)$ is a separate short, densely cancelled fragment. Its whole reading has not been recovered.

[?] $D(kf) = (Dk)f = (k^+D)f = Dfk = k^+(Df)$

$$\Longrightarrow (k^+D)f = k^+(Df).$$

Similarly, if we consider $\mathrm{Diff}_n(M, N)$ as a functor of N, then f must be sent from the left, and this also gives a module homomorphism. [ ] Lemma 2. Let $A \in \mathrm{Diff}_1(K, M)$. Then

$$A(k_1k_2) = k_1A(k_2) + k_2A(k_1) - k_1k_2A(1). \qquad (1)$$

and conversely, if $A : K \longrightarrow M$ —an additive map satisfying (1), then $A \in \mathrm{Diff}_1(K, M)$. Proof: The general situation $A \in \mathrm{Diff}_1(N, M) \Longleftrightarrow$

$$Ak_0k_1 = k_0Ak_1 + k_1Ak_0 - k_0k_1A \quad (\forall k_0, k_1). \qquad (2)$$

For $N = K$ this means that

$$A(k_0k_1k) = k_0A(k_1k) + k_1A(k_0k) - k_0k_1A(k). \qquad (3)$$

Setting $k = 1$ gives (1). Conversely, let (1) vyp.



Uncertain reading. After "let (1)" is the small "вып."; possibly "выч.". The abbreviation is unexpanded.

Original source details: GELFAND-P000384



–

Original source details: GELFAND-P000384

Uncertain reading. The digit 3 is densely reinforced over earlier ink; an overwritten 2 is possible. At left are two close opening parentheses; at right one closing parenthesis. Above is the small insertion $(\forall k_0, k_1, k)$.

$$(\forall k_0, k_1, k)$$

We prove $((3)$.



Original source details: GELFAND-P000384

Uncertain reading. The whole $k_1kk_0A(1)$ is crossed out; the final argument is reinforced and also admits $A(k)$. The final term $-k_0k_1kA(1)$ is crossed out separately.

$$A(k_0k_1k) = A(k_0(k_1k)) = k_0A(k_1k)+k_1(kA(k_0))-k_0k_1kA(1) =$$

$$\big(kA(k_0) = A(kk_0) + kk_0A(1) - k_0A(k)\big)$$

$$= k_0A(k_1k)+k_1A(k_0k) + \cancel{k_1kk_0A(1)} - k_1k_0A(k)\cancel{-k_0k_1kA(1)}.$$

$$= k_0Ak_1k + k_1Ak_0k - k_0k_1Ak,$$

as required.

Corollary: $A \in \mathrm{Diff}_1(K, M) \Longrightarrow A - A(1)$ —a derivation from K to M. Lemma 3. Let $A_1 \in \mathrm{Diff}_m(M_1, M_2)$, $B \in \mathrm{Diff}_n(M_2, M_3)$.

Original source details: GELFAND-P000384

Uncertain reading. In the hypothesis, the first A has an extra reinforced 1-like lower index. Provisionally A_1; the earlier lower sign is not established.

Then $B \circ A \in \mathrm{Diff}_{m+n}(M_1, M_3)$. Proof: induction on $m+n$. For $m+n = 0 (m = n = 0)$ everything is evident. Assume it proved for $m+n \leq d-1$. Let $m+n = d$.

$$\begin{aligned}\delta_k(B \circ A) &= kBA - BAk = (kB - Bk)A + B(kA - Ak) \\ &= (\delta_k B)A + B(\delta_k A) \quad \blacksquare\end{aligned}$$

GELFAND-P000385

Lemma 4. There exists a canon. diff. operator of ord. n:



Original source details: GELFAND-P000385

Diagram and typed description.

$$\mathrm{Diff}_n^+(K, N) \longrightarrow N$$

$$C: \quad A \longmapsto A(1)$$

Proof.

$$\begin{aligned}(\delta_k C)(A) &= (kC - Ck)(A) = kA(1) - CAk \\ &= kA(1) - Ak(1) = (\delta_k A)(1).\end{aligned}$$

hence

$$(\delta_{k_0}\delta_{k_1}\ldots\delta_{k_n}C)(A) = (\delta_{k_0}\delta_{k_1}\ldots\delta_{k_n}A)(1) = 0$$

and C is a diff. op. Consequence: a canon. homomorphism exists



Original source details: GELFAND-P000385

Diagram and typed description.

$$\mathrm{Hom}_K(M, \mathrm{Diff}_n^+(K, N)) \longrightarrow \mathrm{Diff}_n^+(M, N)$$

$$f \longmapsto [?] \quad C \circ f$$



Original source details: GELFAND-P000385

Undeciphered passage. Before $C \circ f$ a formula is crossed repeatedly by horizontal and oblique strokes. Its whole earlier reading has not been recovered.

(Check that this is a module hom.:

$$kf \longmapsto C \circ kf = C \circ fk = k^{+}(C \circ f), \quad \text{ch.[?] and so on})$$



Original source details: GELFAND-P000385

Uncertain reading. Before “and so on” is a short ч-like beginning with a separate period. Provisionally “ч.”(ch.); possibly “и.”(i.). The abbreviation is unexpanded.

Lemma 5. A canon. homomorphism exists:



Original source details: GELFAND-P000385

Diagram and typed description.

$$\mathrm{Diff}_n^{+}(M,N) \longrightarrow \mathrm{Hom}_K(M, \mathrm{Diff}_n^{+}(K,N))$$

$$A \longrightarrow \{m \longmapsto A(km)\}$$

Proof. 1) Check that $A(km)$ (m is fixed) $\in \mathrm{Diff}_n^{+}(K,N)$ — — this is a diff. op. on a submodule (restrict. of the larger diff. op.) $=$



Original source details: GELFAND-P000385

Diagram and typed description.

$$K \longrightarrow M \longrightarrow N$$

$$k \longrightarrow km \xrightarrow{A} A(km)$$

canon. hom. and diff. op. of ord. n.

2) Check that $g : m \longmapsto A(km)$ is $\mathrm{Hom}_K(M, \mathrm{Diff}_n^{+}(K,N))$.



Original source details: GELFAND-P000385

Uncertain reading. The letter before m is densely overwritten, with a loop and lower crossing strokes. Provisionally g; its earlier form is not established.

$g \ldots$

Original source details: GELFAND-P000385

Uncertain reading. Before the additivity line is a cancelled earlier prefix with a g-like beginning. Its argument strokes overlap; the complete earlier expression has not been recovered.

$$g(m_1+m_2)(k) = A(km_1+km_2) = A(km_1)+A(km_2) = g(m_1)(k)+g(m_2)(k).$$



Original source details: GELFAND-P000385

Uncertain reading. After m_2 the right argument boundary and the following (k) are densely reinforced and intersect. Provisionally $g(m_1+m_2)(k)$; possibly $g(m_1+m_2,k)$.

$$\begin{aligned} g(k_0m)(k) &= A(kk_0m) = A(k_0km) = (Ak_0)(km) \\ &= (k_0^+A)(km) = k_0^+g(m). \end{aligned}$$

3) Check that



Original source details: GELFAND-P000385

Diagram and typed description.

$A \longrightarrow \{m \longmapsto A(km)\}$ is a homomorphism.

$$k^+A \longrightarrow \{m \longrightarrow k^+A(km)\} = k\{m \longrightarrow A(km)\}, \quad \text{ch.[?] and so on}$$



Original source details: GELFAND-P000385

Uncertain reading. At the end of check 3, before “and so on” is another short ч-like beginning with a period. Provisionally “ч.”(ch.); possibly “и.”(i.). The abbreviation is unexpanded.

Lemma 6. The constructed maps (the consequence of lemma 4 and lemma 5) are mutually inverse and give a module isom.

$$\mathrm{Diff}_n^+(M,N) \simeq \mathrm{Hom}_K(M, \mathrm{Diff}_n^+(K,N)).$$

Proof. [?]



Original source details: GELFAND-P000385

Undeciphered passage. Between “Proof” and “Let” a word is repeatedly cancelled by long horizontal strokes. The whole word has not been recovered.

Let $A \in \mathrm{Diff}_n^+(M,N)$, construct $A' \in \mathrm{Hom}_K(M, \mathrm{Diff}_n^+(K,N))$:

$$(A'm)(k) = A(km).$$

Now from A' construct $A'' \in \mathrm{Diff}_n^+(M,N)$ by the formula

$$A''_m = C \circ A'm = (A'm)(1) = A(m), \quad \text{i.e. } A'' = A$$



Original source details: GELFAND-P000385

Uncertain reading. Below the first A'' is a small reinforced m-like entry. Provisionally a lower m; the earlier strokes are not established. The following $A'm$ is rendered without adding a lower index.

Conversely, let $A' \in \mathrm{Hom}_K(M, \mathrm{Diff}_n^+(K,N))$. Construct $A'' \in \mathrm{Diff}_n^+(M,N)$



Original source details: GELFAND-P000385

Uncertain reading. In the final $\mathrm{Diff}_n^+(M,N)$ the first argument is densely reinforced. Provisionally M; the complete earlier form underneath has not been recovered.

GELFAND-P000386

[source number: 35]

by the formula $A''m = (A'm)(1)$ and then $A''' \in \mathrm{Hom}_K(M, \mathrm{Diff}_n^+(K,N))$ as

$$(A'''m)(k) = A''(km) = (A'(km))(1) = k^+ A'(m)(1) = (A'(m)k)(1)$$
$$= A'(m)(k), \quad \text{i.e. } A''' = A'.$$

~~[?]~~



Original source details: GELFAND-P000386

Undeciphered passage. After $A''' = A'$ and before the black square, a short word is cancelled by several horizontal strokes. The whole earlier word has not been recovered.

■

Thus, it is proved that $\boxed{\mathrm{Diff}_n^+ N = \mathrm{Diff}_n^+(K,N).}$

GELFAND-P000387

15/XI. I. M. Gelfand.

G is a Lie group, X a sp., G acts transitively on X (X is a homogeneous sp.).

Principal homog. sp.: G acts on X without fixed pts. ($xg = y \Rightarrow g$ is unique).

The same in terms of the Lie algebra:

Let a Lie algebra $\mathfrak{g}$ act on X.

$$\xi \in \mathfrak{g} \rightsquigarrow \text{a vector field on } X; \quad a(\xi),$$
$$\xi_1 + \xi_2 \rightsquigarrow a(\xi_1) + a(\xi_2);$$
$$[\xi_1, \xi_2] \longrightarrow [a(\xi_1), a(\xi_2)].$$

Homogeneous sp.: if $\mathfrak{g} \longrightarrow TX_x$ epim. $\forall x$ ($a(\xi)_x$ generate all of X).

(One can prove that sometimes this means ordinary homogeneity)

very rarely.
When can one dog.[?] to a group:



Original source details: GELFAND-P000387

Uncertain reading. The abbreviation has a clear do-like beginning and an uncertain final cursive stroke with a period. Provisionally “дог.”(dog.); possibly “дот.”(dot.). It is unexpanded.

when $\mathfrak{g}$ is finite-dimensional.
Principal homog. sp.: map $\mathfrak{g} \longrightarrow TX_x$ isomorphism.
Ordinary case:
fix x_0, one gets $x_0 g = y$. $g \leftrightarrow y$, $X \cong G$ and the transf. is a right translation.
If there is no group, there may be many of them and different ones!
(All of them are candidates for the title of group)
Principal homog. sp. is now understood in this[?] sense.



Original source details: GELFAND-P000387

Uncertain reading. In the word before “sense,” the final letters are densely reinforced and intersect earlier strokes. Provisionally “этом”(this); the whole earlier form has not been recovered.

Example.
W_n — formal vect. fields;

$$\sum_{i=1}^{n} a_i(x) \frac{\partial}{\partial x_i}$$
$$X = (x_1, \ldots, x_n)$$



Original source details: GELFAND-P000387

Uncertain reading. The initial cross-shaped sign on the coordinate line is noticeably larger than the components x_i. Provisionally X; possibly a large handwritten x. The case distinction is not finally established.

$a_i(x)$ — formal series (power series).

GELFAND-P000388

[source number: 36]

The group does not exist: one cannot move.
In W_n there is a subalgebra $L_0 \subset W_n$, $a_i(0) = 0$ — const. term $= 0$.



Original source details: GELFAND-P000388

Diagram and typed description.

$\dim(L_0 \backslash W_n) = n.$

Original source details: GELFAND-P000388

Uncertain reading. After the equals sign, the letter is densely reinforced, especially at left. Provisionally n; the complete earlier strokes have not been recovered.

The algebra L_0 can be brought to a group.

Original source details: GELFAND-P000388

Diagram and typed description. A circled mark: two roughly parallel oblique strokes and a dark spot in the middle. Its number or symbol is not established.

$y = \varphi(x)$ — formal automorphisms, 0 stays in place.
Its Lie alg. ~~then~~[?] is L_0.



Original source details: GELFAND-P000388

Uncertain reading. Between “Its Lie alg.” and “is L_0” a word is cancelled by several strokes. Provisionally “тогда”(then); the complete earlier reading is not finally established.

Consider W_n, its gr. of automorphisms, its Lie alg. is L_0.
Thm: the Lie alg. of the automorphism gr. of W_n is L_0.
(In the classical case one gets the quotient gr. ~~[?]~~

Original source details: GELFAND-P000388

Undeciphered passage. Between “quotient gr.” and “alg.” is a short densely cancelled fragment. Its whole content has not been recovered.

of the alg. by the centre).
~~[?]~~



Original source details: GELFAND-P000388

Undeciphered passage. A long line above the lower cancelled heading is covered by repeated loops and horizontal strokes. The complete earlier line has not been recovered.

~~Other gr.~~[?]



Original source details: GELFAND-P000388

Uncertain reading. In the separate lower cancelled heading, “Other” is clear; the second abbreviated word is crossed by a stroke. Provisionally “гр.”(gr.), unexpanded.

Consider W_n and sympl. transf. (Hamiltonian), volume-preserving and so on.
Construction of a principal homog. sp. for W_n.
M — a sp. (arbitrary) — a finite-dimensional manifold, $x \in M$.

Consider at pt. x jets of coordinate systems (a coord. syst. is a map of a nbd. U_x into R^n, $x \longrightarrow 0$). 2 coord. systs. are called equiv. if $\tau_1^{-1}\tau_2$ has at 0 all derivs. equal to 0.



Original source details: GELFAND-P000388

Diagram and typed description. Two separate arrow starts: the upper arrow points right with label τ_1 to R^n; the lower arrow slopes down and right with label τ_2 to a second R^n. Above the upper start is provisionally U_1, with a circled digit 1 below. A cursive stroke crosses the upper letter; no connection between starts is supplied.



$\xi \in W_n$ acts there.
$\xi\tau(x)$ — another formal coord. syst.

Original source details: GELFAND-P000388

Diagram and typed description. An earlier cancelled scheme: provisionally $\tau(x)$, then A, a rightward arrow and R^n. Long loops and oblique strokes cross the labels and arrow. The exact earlier beginning has not been recovered.

$X = S(M)$ — the sp. of all jets of coord. systems (at all points of M).
Theorem: $S(M)$ — a principal homog. sp. for W_n.
dim M = ~~def[?]~~ defect W_n (by how much it falls short).



Original source details: GELFAND-P000388

Uncertain reading. After dim M = a short earlier beginning is cancelled by horizontal and oblique strokes. Provisionally “деф”(def); the complete earlier form has not been recovered.

Original source details: GELFAND-P000388

Uncertain reading. In the current word “дефект”(defect), the middle letters are densely overwritten. The word itself is legible; all earlier strokes underneath are not established.

It is unclear whether there are other substantive principal homog. spaces.

GELFAND-P000389

Let G act on X, ω — an invar. diff. form.

It suffices to specify it at the 1st point. Right-inv. forms correspond to forms on G. Differential $=$ diff. in the cohomology of the Lie algebra $\mathfrak{g}$.

W_n — a Lie alg., $X = S(M)$.

$f(\xi_1, \ldots, \xi_q)$ — a multilin. skew-symm. form on $W_n \rightsquigarrow$

$\rightsquigarrow$ an invar. form on $S(M)$.



Original source details: GELFAND-P000389

Uncertain reading. The subscript of the last ξ in the first f is densely reinforced and crossed by earlier strokes. Provisionally q; possibly n. The whole earlier subscript form has not been recovered.

x, $D_1, \ldots, D_q$ — vectors at the point $x \in X$.

corresponding to them are vectors $\xi_1, \ldots, \xi_q \in W_n$. One gets $f(\xi_1, \ldots, \xi_q)$ — a form on $S(M)$.

Right-invar. one can give a definition.

Original source details: GELFAND-P000389

Uncertain reading. Several initial letters in "Right-invar." are densely overwritten. The current reading is provisionally retained; the whole earlier strokes are not established.

$$(df)(\xi_1, \ldots, \xi_{q+1}) = \sum_{s<t} (-1)^{s+t=1}$$

$$f([\xi_s, \xi_t], \xi_1, \ldots, \hat{\xi}_s, \ldots, \hat{\xi}_t, \ldots, \xi_{q+1}).$$



Original source details: GELFAND-P000389

Diagram and typed description. In the exponent, after $s + t$ and before 1, there are two separate horizontal strokes. They are encoded as $=$.



Original source details: GELFAND-P000389

Diagram and typed description.

$f \longrightarrow \omega$

$df \longrightarrow d\omega$

($d\omega$ — the ordinary de Rham diff.

from ~~left[?]~~ invar. forms

Tricks of diff. geometry — lowering to M.



Original source details: GELFAND-P000389

Uncertain reading. Before “invar. forms” is a cancelled joined beginning with a tall loop. Provisionally “лево”(left); the whole earlier entry is not established.



Original source details: GELFAND-P000389

Uncertain reading. At right are two joined curves: the upper is beside the de Rham line; the lower is shorter, beside the invar. forms and lowering lines. Below and right is a separate period. The exact semantic attachment of the curves is not established.

(classes and so on).

see note in DAN, I. M. Gelfand and Kazhdan.

I. Bernstein.

Original source details: GELFAND-P000389

Diagram and typed description. At right in the source raster is a digital yellow comment icon with a black outline, a lower tail and three horizontal bars.

Consider ∞-dimensional manifolds.

Definition:

An ∞-dim. manifold is a proj. limit of finite-dimensional ones



Original source details: GELFAND-P000389

Diagram and typed description.

$$M_1 \longleftarrow M_2 \longleftarrow M_3 \longleftarrow \cdots \quad M$$

Original source details: GELFAND-P000389

Uncertain reading. After the last arrow are a short point-like stroke and a separate low wavy stroke. The exact continuation mark is not established; it is not normalized to three dots.

All maps are onto maps.

Ring of functions on M: ~~A[?]~~



Original source details: GELFAND-P000389

Uncertain reading. After the ring-of-functions heading, a single letter-like sign is cancelled. Provisionally A; the whole earlier form is not established.

$$A(M) = \bigcup A(M_i) \qquad (\varinjlim A(M))$$

GELFAND-P000390

[source number: 37]

C^∞ — vector fields, C^∞ — diff. forms and ktogda[?] one constructs the de Rham compl.

Original source details: GELFAND-P000390

Uncertain reading. After "and," the next word has an extra k-like beginning before a togda-like continuation. Provisionally "ктогда"(ktogda); possibly overwritten "когда"(when) or "тогда"(then). The whole original reading is not established.

ω — a form; $\omega(\xi_1, \dots, \xi_i)$,



Original source details: GELFAND-P000390

Uncertain reading. Two argument letters are reinforced over earlier strokes. Provisionally $\xi_1, \dots, \xi_i$; possibly $\eta_1, \dots, \eta_i$. The complete earlier outlines have not been recovered.

ξ_i — a tangent vect., extended to vector fields η_i.



Original source details: GELFAND-P000390

Uncertain reading. The initial letter with subscript i in the tangent-vector phrase is reinforced. Provisionally ξ_i; possibly η_i. The clean final η_i is rendered separately; the earlier strokes of the initial letter are not established.

$$(d\omega)(\xi_1, \dots, \xi_{i+1}) = \sum_{j=1}^{q+1} (-1)^{j+1} \xi_j \omega(\xi_1, \dots, \hat{\eta}_j, \dots, \eta_{i+1}) + \\ + \sum_{j<k} (-1)^{j+k} \omega([\eta_j, \eta_k], \eta_1, \dots, \hat{\eta}_j, \dots, \hat{\eta}_k, \dots, \eta_{i+1}). \qquad (1)$$



Original source details: GELFAND-P000390

Uncertain reading. In the first row of (1), the two letters at left, the upper summation limit, the letter before ω and the first argument of ω are reinforced. Provisionally $\xi_1, \dots, \xi_{i+1}$ at left, $q+1$ above, then ξ_j and ξ_1; the corresponding η and $i+1$ are possible. The clean η entries in the tail and second row are retained. The complete earlier strokes have not been recovered.

Using, $S(M)$ we shall construct the Chern classes of M.

$\mathfrak{g}$ — an inf.-dimensional Lie alg. (proj. lim of finite-dimensional ones with the corresp.

topol.).

X — a principal homog. sp.

Construct the complex $C(\mathfrak{g})$

$C(\mathfrak{g}) = \{C^i(\mathfrak{g})\}$. — the standard complex of the algebra $\mathfrak{g}$.

$C(\mathfrak{g}) \longrightarrow \Omega(X)$ — the de Rham compl. of X.

A homomorphism (commuting with d) — by formula (1).

The 1st terms will cancel

One gets a map.

$$H^i(\mathfrak{g}) \longrightarrow H^i(X)$$

How does one constr. Chern classes?

~~Def[?]...~~



Original source details: GELFAND-P000390

Uncertain reading. Before the new heading is a cancelled earlier beginning. Provisionally “Опр...”(Def...); possibly “Однор...”(Homog...). The ending has not been recovered or completed from the following heading.

Definition.

$\mathfrak{g} \supset \mathfrak{p}$ — a subalgebra.

A homog. sp. of $\mathfrak{g}$ with isotropy subalg. $\mathfrak{p}$.



Original source details: GELFAND-P000390

Diagram and typed description. To the left of the current vertical projection from S to X is a cancelled earlier X; beside it are an open hook-like stroke and a separate upper-right crossing resembling a plus. The exact earlier sign is not established. ι^+-, τ^+-or t^+-like forms are possible; the earlier $\mathfrak{g}/\mathfrak{p}$ hypothesis is not confirmed by a clear fraction bar.



a fibration (∞-dim. manifolds)

On tangent spaces the maps are onto

S — a princ. homog. $\mathfrak{g}$-sp. and if $s \in S$,



Uncertain reading. In the abbreviations “главн.”(princ.) and “однор.”(homog.), final and middle letters are overwritten and crossed by earlier strokes. The current reading is provisionally retained; the complete earlier outlines are not established.

Original source details: GELFAND-P000390

GELFAND-P000391

$\mathcal{F}_s$ — the fibre of S at pt. s, then $\xi \in \mathfrak{p}$ passes to vector fields, tangent to the fibre, and at the same time $\mathcal{F}_s$ — a principal homogeneous $\mathfrak{p}$-space.



Uncertain reading. The letter before “-space” is densely overwritten. Provisionally $\mathfrak{p}$; possibly $\mathfrak{g}$. The complete original outline is not established.

Original source details: GELFAND-P000391

X — a principal homog. sp.

Chain complex $C(\mathfrak{g})$

Rel. chain compl. $C(\mathfrak{g}, \mathfrak{p})$.

$$C^i(\mathfrak{g}, \mathfrak{p}) \subset C^i(\mathfrak{g})$$

$\omega(\xi_1, \ldots, \xi_i)$ — a form on $\mathfrak{g}$, belonging to $C^i(\mathfrak{g}, \mathfrak{p})$, if

1) $\omega(\xi_1, \ldots, \xi_i) = 0$ for $\xi_1 \in \mathfrak{p}$.

2) $d\omega(\xi_1, \ldots,) = 0$, if $\xi_1 \in \mathfrak{p}$.

(ω invar. with respect to ~~elem[?]~~ the adjoint repr. of elem. of $\mathfrak{p}$).

Uncertain reading. The cancelled word after “invar. with respect to” is provisionally “элем”(elem.). The full earlier reading is not established.

Original source details: GELFAND-P000391

The forms ω — a complex.

Cohomology — cohom. of the quotient gr. (in the classical case).

Let there be a homog. $\mathfrak{g}$-space, $\mathfrak{p}$ — an isotropy subalg.

$\exists$ a map

$$C(\mathfrak{g}, \mathfrak{p}) \longrightarrow \Omega(X).$$

Construction:

$\eta \in T_x(X)$,



Original source details: GELFAND-P000391

Diagram and typed description. The current vertical projection is from S down to X. At left is an earlier horizontal right arrow to X with its beginning and small label crossed out. The beginning resembles s; the complete earlier letter and label are not established.

$\eta' \in T_s(S)$, $\eta' \longrightarrow \eta$.

Original source details: GELFAND-P000391

Uncertain reading. The letter before $\in T_s(S)$ is densely overwritten; the separate upper-right stroke is read as a prime. Provisionally η'; possibly ξ'. The original letter is not established.

$\omega \in C(\mathfrak{g}, \mathfrak{p}) \longrightarrow$

$$\longrightarrow$$

$$\tilde{\omega}(\eta_1, \ldots, \eta_n) = \omega(\bar{\eta}'_1, \bar{\eta}'_2, \ldots, \bar{\eta}'_n)$$



Original source details: GELFAND-P000391

Uncertain reading. Above the second argument $\bar{\eta}_2$ is a dense crossing with a loop-like stroke. The prime in $\bar{\eta}'_2$ is provisional; $\bar{\eta}^*_2$ or a reinforced or overwritten upper stroke is possible. The exact upper mark is not established.

$\bar{\eta}'_i$ — the corresp. elements of the Lie alg. $\mathfrak{g}$.

GELFAND-P000392

[source number: 38]

There is arbitrariness, but $\tilde{\omega}$ does not depend on it — on the choice of $\bar{\eta}'_i$.



Original source details: GELFAND-P000392

Uncertain reading. The horizontal stroke immediately below page number 38 lies above η'_i. Provisionally $\bar{\eta}'_i$; possibly η'_i with only page number 38 underlined. The attachment of the horizontal stroke is not established.

It does not depend on the choice of point either.

These are continuous skr.[?] forms on X.



Original source details: GELFAND-P000392

Uncertain reading. The abbreviation before “forms” is provisionally “скр.”(skr.); possibly “сим.”(sim.). The abbreviation is not expanded.

M — a manifold, $S(M)$ — a princ. W_n-space (see above).

gl(n) — a subalg. of linear transformations

It acts on $S(M)$ and the action extends to the group

$V_x \longrightarrow V_0 \subset \mathbb{R}^n$, rotates.

Consider $S(M)/GL(n,R)$ corresp. to the pair $(W_n, \mathrm{gl}(n))$.

This is already homotopy equiv. to M.

(in contrast to $S(M)$, which is homotopy equiv. to 1-frames).

~~[...]~~



Original source details: GELFAND-P000392

Undeciphered passage. The short cancelled word before "There is a map" has not been recovered.

There is a map.

[word?] — a map $M \longrightarrow S(M)$.



Original source details: GELFAND-P000392

Uncertain reading. In the right margin before "— map" is an unidentified word. The earlier provisional candidates "Искусство"(Art) and "Выгодно"(Advantageous) are not asserted as readings.



Original source details: GELFAND-P000392

Diagram and typed description. Below the quotient is a separate curved vertical stroke and the label M. In the right margin above the formula are two vertical strokes, one with an upward arrow. Their position is retained; the mark below the quotient is not replaced by an equality assertion.

$$C(W_n, \mathrm{gl}(n)) \longrightarrow \Omega(S(M)/GL(n,R))$$

M

Description of the cohom. of this alg:

$\psi_1, \psi_2, \ldots, \psi_n$[...ymi?] — generators of degree $2n$.



Original source details: GELFAND-P000392

Uncertain reading. After ψ_n are faint letter strokes. The earlier provisional ending "-ыми"(-ymi) is qualified; the whole word is not established.

degrees $> 2n \Rightarrow$ one gets 0.

Map to the cohomology of M —



Original source details: GELFAND-P000392

Uncertain reading. The linked lines contain “Chern,” “geometr...ification” and “tangent bundle (Pontryagin cl.).” The joined word is provisionally “геометрификации”(geometrification); the earlier division “геометр. модификации”(geometr. modifications) is also not established. A brace-like stroke and arrowed lines link the left and right parts. The whole word remains unidentified.

~~this[?]~~ image of ψ_i — classes

Chern { geometr...ification[?] of the tangent bundle

(Pontryagin cl.)



Uncertain reading. Before “image of ψ_i — classes” is a cancelled word, provisionally “это”(this). The full earlier reading is not established.

Original source details: GELFAND-P000392

A form on $S(M)/GL(n,R)$ is det. uniquely (invar.), nonuniqueness (choice of connection) appears, when we try ~~not[?]~~ to constr. forms on M.

Uncertain reading. Before “constr.” is a short cancelled beginning, provisionally “не”(not). The crossings prevent recovery of the complete original reading.

Original source details: GELFAND-P000392



Original source details: GELFAND-P000392

Diagram and typed description. Above the following heading and line are a separate horizontal arrow with heads at both ends, a small open c-like stroke and a separate long sloping stroke above the foliation sign. Their meanings are not established.

Bott thm. M — a manifold, $\mathcal{F}$ — a foliation, codim $= n$.

GELFAND-P000393

$S_{\mathcal{F}}(M)$. $x \in M$, $U_x \overset{\text{form.}}{\longrightarrow} U_0 \subset R^n$, having the properties

1) const. on the leaves; 2) an isom. on a transverse sect. (nondeg.)

(A formal germ of a map).



Original source details: GELFAND-P000393

Uncertain reading. The ending of the first framed word is not established: “локальный”(lokalnyi) / “локальная”(lokalnaya) / “локальн…”(lokaln…). The small raised terminal strokes do not decide the ending. “coord. syst. in the quotient.” is retained without expansion.

lokaln…[?]
coord. syst.
in the quotient.

Consider $S_{\mathcal{F}}(M)/GL(n, R)$.

On $S_{\mathcal{F}}(M)$ no algebra acts.

Consider ~~dim $M \longrightarrow N$~~ $\mathbb{R}^N_n$, in it a standard foliation of codim n.



Original source details: GELFAND-P000393

Uncertain reading. After the cancelled dim $M \longrightarrow N$ stands $\mathbb{R}^N$ with a small n lower right. The provisional positional notation is $\mathbb{R}^N_n$; the n may be separate. Its role is not established.

$W_{N,n}$ — the Lie alg. of vector fields preserving the foliation



Original source details: GELFAND-P000393

Diagram and typed description. A row of nearly vertical strokes of different lengths and thicknesses, with dark thickenings. Intertwined reinforced strokes are rendered schematically. The exact number of separate lines and the attachment of the thickenings are not established; no points or particular leaves are assigned.



Linear transf.: :



Original source details: GELFAND-P000393

Diagram and typed description.



$S'_{\mathcal{F}}(M)$, $x \in M$, $U_x \overset{\text{form.}}{\longrightarrow} U_0 \subset R^N$

leaves of the foliation $\longrightarrow$ leaves of the form. foliation.

$S'_{\mathcal{F}}(M)$ — a princ. homog. $W_{N,n}$-space. !



$W_{N,n} \supset L$ — preserving each leaf

Diagram and typed description. Between the quotient and W_n are two reinforced wavy upper strokes and a lower nearly straight stroke. The form is rendered as separate strokes; a standard relation is not imposed.

$$W_{N,n}/L \underset{\sim}{\approx} W_n.$$

Original source details: GELFAND-P000393

$$\begin{array}{c} S'_{\mathcal{F}}(M) \\ \downarrow \\ S_{\mathcal{F}}(M) \end{array} \qquad \text{const. along the leaves.}$$

The pair $(S'_{\mathcal{F}}(M), S_{\mathcal{F}}(M))$ — a homogeneous $(W_{N,n}, L)$-space.

GELFAND-P000394

[source number: 39]

~~(Formally[?]~~



Original source details: GELFAND-P000394

Uncertain reading. At the beginning an opening parenthesis and a word are cancelled, provisionally “Формально”(Formally). The complete earlier reading and superimposed strokes are not established.

(the quotient group does not act on the quotient space)

$$C(W_n) = C(W_{N,n}, L) \longrightarrow \Omega(S_{\mathcal{F}}(M))$$

$S = S_{\mathcal{F}}(M)/GL(n,R)$ — homotopy equiv. to M.
$(S'_{\mathcal{F}}(M), S)$ — a homog. princ. sp. relative to $(W_{N,n}, L + \mathfrak{gl}(n))$

$$\underline{C(W_n, \mathfrak{gl}(n))} = \underline{\underline{C(W_{N,n}, L + \mathfrak{gl}(n)) \longrightarrow \Omega_M(S).}}$$

/

these are known (generators) $\psi_1, \ldots, \psi_n$ — Izv. A. N., 1971, Gelfand, Fuks.
$T(M)/T(\mathcal{F})$ — Chern classes — images of the cl. $\psi_1, \ldots, \psi_n$.

$$\prod \psi_i \quad (\text{deg. } > 2n) = 0.$$

Hence for $\overleftarrow{\overleftarrow{T(M)/T(\mathcal{F})}}$ a product of Chern cl. deg. $\geq 2n$ must be 0!! — this is Bott’s thm. —

Original source details: GELFAND-P000394

Uncertain reading. In this sentence the sign before $2n$ has a separate lower slanting stroke. Provisionally $\geq 2n$; $> 2n$ with a separate lower stroke is not excluded. The preceding formula clearly has $> 2n$.

— an obstruction to being homotopically integrable ~~[...]~~



Original source details: GELFAND-P000394

Undeciphered passage. The densely cancelled word after “integrable” has not been recovered.

. . .

Arnold.

$$\frac{dw}{dz} = \frac{P(z,w)}{Q(z,w)} \quad \text{on } \underline{\underline{CP^2}} \setminus \text{several singular points.}$$

One gets an invariant of the foliation. (on 3-dimensional complex manifold: point — vector)

Arnold’s question — characterize geometrically, prove integrality (rationality)

(a generalization of Poincaré rotation numbers).



Original source details: GELFAND-P000394

Uncertain reading. The current "Exercise" is reinforced over earlier strokes. The complete earlier outlines have not been recovered. The two lines beneath the heading with left ends are rendered separately.

Exercise:

define rotation numbers as such an invariant.

GELFAND-P000395

[source number: 43]

14 February.

L. Vaserstein.

———— . ————

A — an assoc. ring with 1. (not necessarily commut.). V — a module over A. (right).

A quadr. form over a comm. ring — in A^n — is $A^n \longrightarrow A$, written in the form $\sum a_{ij}x_ix_j$. The matrices are det. nonuniquely.

$\exists\, 2^{-1} \Rightarrow$ there is a one-to-one corresp. with symm. matrices.

———— . ————

An involution on A: $A \longrightarrow A$.



Original source details: GELFAND-P000395

Undeciphered passage. Below the arrow a short word is cancelled by horizontal and slanting strokes. Separate loops are visible; the full reading is not established.

$$(x-y)^* = x^* - y^*; \qquad (xy)^* = y^* x^*; \qquad (x^*)^* = x.$$

A sesquilin. form: $f(u,v) \in A$, $u, v \in V$; additive in all variables;

$$f(u\mu, v\lambda) = \mu^* f(u,v)\lambda.$$

(see Bourbaki). (There are no bilin. forms over a noncomm. ring)

$\mathrm{Hom}(V, V^*)$ — these are 1,5-lin. forms.
$V^* = \mathrm{Hom}_A(V, A)$ (of two right modules).

(Hom is always over A).



Original source details: GELFAND-P000395

Uncertain reading. Two earlier abbreviations are cancelled. Provisionally “left.; right.”; the complete earlier strokes are not established. Above the second, “left.” is clearly inserted and circled; its pointer crosses the earlier word.

left.

V^* ~~left.[?]~~ ~~right.[?]~~ module.

(generally speaking).

But the involution makes it poss. to consider V^* as



Original source details: GELFAND-P000395

Uncertain reading. Before “module” an earlier abbreviation is cancelled, provisionally “left.”. The complete earlier strokes are not established. Above it “right.” is clearly inserted and circled, with a pointer down and left.

right.

~~left.[?]~~ module.

$$a \longmapsto f(a); \qquad \lambda f(a); \qquad a \longmapsto \lambda f(a).$$

$L \in \mathrm{Hom}(V, V^*)$ (a hom. of right A-modules).

$$f(u,v) = L(u)v.$$

GELFAND-P000396

A quadr. form — not quite that.

Undeciphered passage. At left before the ring line a word is densely cancelled. A large initial stroke and separate loops are visible; the complete word is not established.

Original source details: GELFAND-P000396

A — a ring, $*$ — an invol., $\varepsilon \in$ the centre of A, $\varepsilon \cdot \varepsilon^* = 1$. ($\varepsilon$ — the symmetry of the quadr. form). (most often one encounters $\varepsilon = 1$ or -1).
Λ — a subgroup of the additive gr. of the ring, having the properties:

$$\{x - \varepsilon x^*\}_{x \in A} \subset \Lambda \subset \{x = -\varepsilon x^*\}_{x \in A};$$
$$a^* \lambda a \in \Lambda \quad \text{for } \lambda \in \Lambda \text{ and } a \in A.$$

Original source details: GELFAND-P000396

Uncertain reading. At right below “properties” are a separate open bracket-like stroke and a small looped sign. “э” or “д” is possible; no verbal reading is established.

The extreme cases occur most often.



Original source details: GELFAND-P000396

Diagram and typed description. The slanting stroke beside "on V" descends to the left towards the conditions on X.

~~I.e.~~ Quadr. forms $\equiv$ sesquilin. on V / subgroup:

$$X(v,v) \in \Lambda; \qquad X = -\varepsilon X^*,$$
$$\text{i.e. } X(u,v) + \varepsilon X(v,u)^* = 0.$$

From a quadr. form q one constr. a scalar product.

$$(u,v)_q = Q(u,v) + \varepsilon Q(v,u)^* \qquad \text{(linearization)}.$$

$Q \in q$; (does not depend on the choice of representative). It is a $1/2$-lin. form.



Original source details: GELFAND-P000396

Diagram and typed description. At right are two lines with a frame open at the top; in the lower line the left subscript is ε and the right pair has no subscript.

$(u,v)_q$ — an ε-symmetric form.

$$\varepsilon(v,u)^*_\varepsilon = (u,v)$$



Original source details: GELFAND-P000396

Uncertain reading. The first letter of the right pair in the lower line is reinforced by dense strokes. Provisionally u; the complete earlier strokes are not established.

Length map: $V \longrightarrow A/\Lambda$.

$$|u|_q = Q(u,u) + \Lambda.$$

(also does not depend on the representative)

Λ max $\Rightarrow$ ~~[q?] [...] sesquilin. reconstr. from quadr[...]~~



Original source details: GELFAND-P000396

Undeciphered passage. After the arrow a short expression with a q-like sign and a phrase are cancelled. Parts reading “sesquilin.”, “reconstr.” and “from quadr...” are distinguishable; the complete earlier expression and ending have not been recovered.

quadr. is reconstr. from its $|v|_q$ (linear.) and there is no sense in distinguishing.

GELFAND-P000397

[source number: 44]

Example: (Hamiltonian or hyperbolic quadr. forms)



Original source details: GELFAND-P000397

Diagram and typed description. At right the parameters and the word “fixed” are circled.

$A, *, \varepsilon, \Lambda$ — fixed.

U — an A-module (any). $H(U) = U \oplus U^*$ with the quadr. form corresp. to

$$Q(u + f, u' + f') = fu'.$$



Undeciphered passage. In parentheses before “1,5 lin.” a short sign is densely cancelled. Its complete initial reading is not established.

Original source details: GELFAND-P000397

(1,5 lin.).

Undeciphered passage. Below fu' a separate formula with vertical, horizontal and slanting strokes is cancelled. The complete expression is not established.

Original source details: GELFAND-P000397

$\begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix}$, and the scalar prod. will be $\begin{pmatrix} 0 & 1 \\ -1 & 0 \end{pmatrix}$.

Witt group: from nonsing. forms: i.e. $(u, v)_q = (L(u)v)$, $L : V \longrightarrow V^*$, ~~corresp. scalar product~~, L is an isomorphism.

Uncertain reading. Immediately before (u, v) a sign with a tall f-like stroke is densely overwritten. Its complete earlier outline and reading are not established; a separate initial f is not asserted.

Original source details: GELFAND-P000397

Witt gr.: $(V, q) \perp (V', q')$ — the orthog. direct sum of two modules with quadr. forms ($A, *, \varepsilon, \Lambda$ fixed).

Nonsing. quadr. forms on finitely gener.

Original source details: GELFAND-P000397

Undeciphered passage. Between “gener.” and “projective” a short fragment is densely cancelled. Its complete reading is not established.

projective modules. (dir. summ.[?],



Original source details: GELFAND-P000397

Uncertain reading. The start of the parentheses is provisionally “прям. слаг.” (dir. summ.); the joined middle letters and the ending of the second abbreviation allow other readings. The abbreviations are not expanded.

Original source details: GELFAND-P000397

Undeciphered passage. After the first two abbreviations in parentheses a word is densely cancelled. The whole earlier word has not been recovered.

finite-dimensional free ones).

They are a semigroup. From it one constr. a group (Grothendieck’s), this is the Witt gr. Over a field there is a cancellation law (Witt’s thm.).
$K_0O(A)$; O — orthog.



Original source details: GELFAND-P000397

Diagram and typed description. The line has O incl. $(A * \varepsilon\Lambda)$; below the parameters is the label “param.”.

O incl. $(A * \varepsilon\Lambda)$
param.

Witt—Grothendieck. Witt, quotient by Hamilton.

Original source details: GELFAND-P000397

Diagram and typed description. At right of these lines are two separate nearly vertical strokes.

Ex. A — a division ring $\Rightarrow$ the fund. cancellation thm.

Thm. 1. $\forall$ finitely gener. projective module with a quadr. form is a direct summand in a Hamilton. (finite-dim.).

$$(V, q) \perp \underbrace{(V', q')}_{\exists} = H(A^n).$$

Remark: if cancellation by $\forall$ modules is allowed, then the Witt gr. $= 0$. $(a + b + a + b + \ldots)$.

GELFAND-P000398

Examples: 1 A — a field, $*$ the identity, $\varepsilon = 1, -1$ (the theory of symm. and



Undeciphered passage. Between "and" and the following abbreviation a short word is densely cancelled. Its complete reading has not been recovered.

Original source details: GELFAND-P000398

sympl. forms.) W.-G. gr. $= Z$.

2 $A = Z$, $*$ — the identity; $\varepsilon = +1, -1$; 1) $\Lambda = 0$ for $\varepsilon = 1$;



Original source details: GELFAND-P000398

Uncertain reading. Between the equals sign and 0 is a separate tall corrected or cancelled sign: a left slanting side, a right stem and a cross-stroke. 4, a cancelled one, or an earlier A- or Λ-like letter are possible. Its reading is not established.

$\Lambda =$ 0



Original source details: GELFAND-P000398

Diagram and typed description. Below Z is the label “2)”, and below $2Z$ is “3)”.

$$\Lambda = \underset{2)}{Z} \text{ or } \underset{3)}{2Z} \quad \text{for } \varepsilon = -1.$$

1) classif. of quadr. forms: invariants — rank and signature (for nonsing. ones). the cancellation thm. is false.

2) symplectic: they are isom. to Hamilton.

3) — an addit. invariant — the Arf invariant.

3 The group ring of a group. $A = Z[g]$. Answers in some cases are unknown. $g = Z_p \times Z_q$; K_0 is unknown.

Original source details: GELFAND-P000398

Uncertain reading. The last subscript in $Z_p \times Z_q$ is densely overwritten, with a loop and a lower tail. Provisionally q; the complete earlier strokes are not established.

This is of interest for topology (there Λ is minimal and sometimes maximal).

Taking Matrices over A does not change $K_0, K_1 \ldots$

Remark. (there are $80 \cdot 10^6$ nonisom. quadr. forms in 32 variables) with det $= 1$.

$K_1 O(A)$; $O = (A, *, \varepsilon, \Lambda)$. $O(H(A^n))$.



Original source details: GELFAND-P000398

Uncertain reading. In A below the superscript n are two parallel left strokes and a dense apex. The current A is readable; reinforcement and an earlier A- or Λ-like layer cannot be separated confidently. The earlier letter is not established.



Original source details: GELFAND-P000398

Diagram and typed description. Within parentheses the blocks a, b, c, d are separated by horizontal and vertical lines; n stands above both columns and to the left of both rows.

$$\begin{array}{cc} n & n \\ \left(\begin{array}{c|c} a & b \\ \hline c & d \end{array}\right) & \begin{matrix} \\ n \\ n \end{matrix} \end{array}$$

$$a^* d + \varepsilon c^* b = 1; \qquad a^* c \in \Lambda_n \quad (?).$$

(the scalar product $= 1$, and the length 0).

$$O(H(A^n)) \subset O(H(A^{n+m})).$$

~~$O(H(A^\infty))$.~~ $O(A)$ — their union.

GELFAND-P000399

[source number: 45]

$$O(A)/\underline{[O(A),O(A)]} = K_1O(A).$$

Lemma (Whitehead): $[O(A),O(A)]$ is gener. by elem. matrices

$$\begin{pmatrix}1 & b\\ 0 & 1\end{pmatrix}, \qquad \begin{pmatrix}1 & 0\\ c & 1\end{pmatrix}.$$



Original source details: GELFAND-P000399

Diagram and typed description. At left is $EO(A)$; a slanting arrow from "(Steinberg)" points to the underlined $StO(A)$. Below $K_2O(A)$ is "kernel", and below $StO(A)$ are two lines of caption. The cancelled loops after the kernel are rendered separately.

$$0 \longrightarrow \underset{\text{kernel}}{K_2O(A)} \longrightarrow \underset{\substack{\text{univ. centr. cover}\\ \text{extension of the gr. } EO(A)}}{StO(A)} \longrightarrow EO(A) \longrightarrow 0$$

(Steinberg) ↙ over $StO(A)$; $EO(A)$ over $EO(A)$

Undeciphered passage. After $K_2O(A)$ before the arrow two small loop-like signs are crossed by strokes. Their complete original expression has not been recovered.

Original source details: GELFAND-P000399

$$H_2(G,Z) \longrightarrow \widetilde{G} \longrightarrow G \qquad ([G,G]=G).$$



Uncertain reading. Below the line is provisionally "неприв. система." (nepriv. system); "нетрив. система." (netriv. system) is possible. The middle letters of the abbreviation and its connection with the separate slanting stroke at left are not established. The abbreviation is not expanded.

Original source details: GELFAND-P000399

/

nepriv.[?] system.

Abstr. simplicial scheme. A simplex — a finite subset. a set and finite subsets and so on.



Original source details: GELFAND-P000399

Diagram and typed description. Below the words about a set and finite subsets is a stepped bracket-like line: a short upper horizontal at left, a descent, a long horizontal, a slanting descent, a lower horizontal, a rise at right and a short continuation to the right. There are no labelled vertices or arrows; the role of the steps is not established.

$$K_n O(A) = \pi_{n-1}(O(A)).$$

Simpl. str.[?] in $O(A)$.



Original source details: GELFAND-P000399

Uncertain reading. The abbreviation after "Simpl." is densely overwritten. Provisionally "стр." (str.); the longer "структ." (strukt.) is possible. The complete earlier strokes are not established.

On finite $O(H(A^n))$.



Original source details: GELFAND-P000399

Diagram and typed description. At right the formula is underlined by a long stroke with a left-pointing head at its left end.

$$K_n(A) = \pi_{n-1}(GL(A))$$

Matrices of order $(2n)$.



Original source details: GELFAND-P000399

Diagram and typed description. Within parentheses a, b, c, d are separated by horizontal and vertical lines.

$$\left(\begin{array}{c|c} a & b \\ \hline c & d \end{array}\right)$$

Which finite set is a simplex?



Original source details: GELFAND-P000399

Diagram and typed description. Within parentheses are three diagonal ones, $*$ at upper right, 0 at lower left and two small separate strokes between the middle and lower ones.

$$\begin{pmatrix} 1 & & * \\ & 1 & \\ & \cdot & \\ 0 & & 1 \end{pmatrix}$$

Any finite subset in this subgr. is a simplex. and right and left translations are also a simplex. (All simult. reduced to Δ form). K_1 and K_2 defined earlier agree with these.

Original source details: GELFAND-P000399

Undeciphered passage. At left before the lower line a short fragment is cancelled. The large initial stroke resembles “Э”; the whole word is not established.

Comm. relations. — relns. of elem. matrices. Triv. relns. — also conn. with π_2.

GELFAND-P000400

21/II. Ka[?]dan.

Original source details: GELFAND-P000400

Uncertain reading. After “Ka” is a narrow joined stroke and an open c-like curve before a tall д. Possible readings are “Каждан.” (Kazhdan), “Каздан.” (Kazdan), “Кацдан.” (Katsdan) or “Касдан.” (Kasdan); the exact surname is not established.

Let A be a ring. Then $K_0(A)$ is the Groth. gr. of proj. A-modules fin. gener.; $K_1(A) = GL(\infty, A)/E(A)$.



Original source details: GELFAND-P000400

Diagram and typed description. Within braces is a matrix schematic: three diagonal ones, $*$ at upper right, three small diagonal strokes and an overwritten lower-left sign. Its provisional candidate 0 is qualified separately; no finite size is specified.

$$E(A) = \left\{ \begin{pmatrix} 1 & & * \\ & 1 & \\ & \cdot & \\ 0 & & 1 \end{pmatrix} \right\}$$

. subgr.

Original source details: GELFAND-P000400

Uncertain reading. The lower-left sign is densely overwritten: a loop is crossed by vertical strokes. The candidate is 0; the earlier sign is not established.

Undeciphered passage. After “subgr.” is a separate short densely cancelled fragment; its initial entry has not been recovered.

Original source details: GELFAND-P000400

$$K_2(A) = \text{Ker}\{St(A) \longrightarrow E(A)\}.$$

(Gr. of Helmholtz—Grothendieck — Helmholtz when changing colours — subtract.) green — yellow = blue.



Original source details: GELFAND-P000400

Diagram and typed description. Within parentheses are three visible ones with intervening dots on a descending diagonal, 0 at lower left; a at upper right, short dotted guides to the left of and above a. At left is i, above a a small j-like label. Below $E_{ij}(a)$ is a separate $i \neq j$. The full matrix size is not specified.

$$E_{ij}(a) = \quad i \neq j$$



The gr. gener. by them, $\underline{\underline{E(A)}}$.

1)



Original source details: GELFAND-P000400

Uncertain reading. The current candidate is $E_{ij}(a) \cdot E_{ij}(b) = E_{ij}(a+b)$. Earlier square brackets are crossed out, and a comma-like stroke near the dot is cancelled. The indices of the second and right-hand E are overwritten; their earlier strokes have not been recovered. Beneath the line is a long rule with a rightward head at the old right bracket and a continuation below the right-hand side.







Original source details: GELFAND-P000400

Uncertain reading. Below at left a cancelled unfinished prefix E has overwritten i-/j-/k-like lower strokes and an opening parenthesis. After it is a blank interval. No written argument or closing parenthesis is visible; the exact indices are not established.



$$(1+ae_{ij})(1+be_{jk})(1+ae_{ij})(1+be_{jk}) = 1.$$



Original source details: GELFAND-P000400

Uncertain reading. In the first two factors the signs after 1 are densely overwritten; the candidates are plus and minus. Plus candidates are provisionally retained in the line; the final two plus signs are separately visible. The result 1 is written lower down at right after the equals sign.



Original source details: GELFAND-P000400

Undeciphered passage. Below the product before the separately written 1 a short entry with u- or v-like and index-like strokes is cancelled; the complete earlier result has not been recovered.

2) $[E_{ij}(a), E_{jk}(b)] = E_{ik}(ab)$. and these are all the relations for now.

In $GL(4, C)$ the gr. of matrices with $\underline{\det = 1}$ will be gener. by elementary ones. i.e. $K_1(A) = C$ for $A = C$;



Original source details: GELFAND-P000400

Uncertain reading. Above and to the right of the final C is a small upper i-like or stroke-like sign, a separate dot below and further below a dot with a tail. The main C is readable; the upper sign is not identified.



and this holds for any field.

GELFAND-P000401

[source number: 47]

Consid. $\{E_{ij}(a)\}$ with the indicated relns. (commut. $a^{-1}b^{-1}ab$).



Original source details: GELFAND-P000401

Uncertain reading. Above the final a and b two exponents with minus-like and one-like strokes are cancelled. The current first two exponents $-1, -1$ are clear; the complete earlier final exponents are not established.



The gr. gener. by them is called $St(A)$ (an abstr. group). (Relns. in the ring, apart from the standard ones, are called $K_2(A)$) Unkn. whether these generate all relns. valid in any ring. (all Steinberg's relns.).



Original source details: GELFAND-P000401

Undeciphered passage. Before the new problem heading a line is cancelled. Parts of "Задача" (Problem) and the final word are distinguishable; the entire earlier formulation has not been recovered.



Original source details: GELFAND-P000401

Diagram and typed description. At left a brace joins the new heading, the question and the following “Triv. case”. Two rules are beneath the word “Problem”; the exclamation marks are to its right.

Problem!! (unsolv.) — will a reln. valid in any ring follow from the Steinberg ones?

The triv. case is conn. with an unsolv. problem of the theory of discrete groups.

A, $B = A[t, t^{-1}]$.



Original source details: GELFAND-P000401

Diagram and typed description. In the second line two short nearly vertical ditto strokes are between two horizontal rules. They are reproduced without expanding the repeated words.

$K_0(A)$ — direct summ. $K_1(B)$

$K_1(A)$ — " — $K_2(B)$.

1) $K_0(A) \longrightarrow K_1(B)$. $K_1(B)$ — autom. of a free module. Shall we specify an autom. of a proj. module? $L \in \mathrm{Aut}\, P$; $P + Q = A^n$.

Original source details: GELFAND-P000401

Uncertain reading. At right the formula $L \oplus 1 \in \mathrm{Aut}\, A^n$ is underlined. After 1 is a small dot; two more small marks are below and to the right of A^n. Their role is not established; they are rendered as separate strokes and dots.

$$L \oplus 1 \in \mathrm{Aut}\, A^n$$

This is a well-defined def. in K_1.

$$P[t, t^{-1}] \overset{\text{def}[?]}{=} P \otimes_A B.$$

Original source details: GELFAND-P000401

Uncertain reading. Above the equals sign is a short underlined Latin label: provisionally def; the first two letters are de, the final tall crossed stroke with a lower hook is t-/f-like. Its exact letter reading is not established.

de t



Original source details: GELFAND-P000401

Diagram and typed description. Below the equation at left is a separate short vertical stroke. The words “proj. over B.” are underlined by a long rule with a leftward head.

proj. over B.

$P[t, t^{-1}]$ has an autom. — mult. by t! From it we construct

Original source details: GELFAND-P000401

Undeciphered passage. After “construct” a short word is crossed out. Provisionally “авто” / “авто...” (avto / avto...) can be distinguished; dense correction covers the end. The exact whole word and ending are not established.

an element of $K_1(B)$.

GELFAND-P000402

Inverse construction:

$$A^n \longrightarrow (B^n, t) \simeq (B, t^n).$$

An elem. of $K_1(B)$ is a matrix



Original source details: GELFAND-P000402

Diagram and typed description. Within parentheses are four asterisks in two outer columns with dots between top and bottom. Its size is separately stated as $r \times r$; the schematic does not specify the number of intervening rows.

$$L = \begin{pmatrix} * & * \\ \vdots & \vdots \\ * & * \end{pmatrix} = t^{-n} L'$$

of order $r \times r$. The elems. of L' are polynomials! It is invertible in B.

$$L' : A[t]^r \longrightarrow A[t]^r.$$

Original source details: GELFAND-P000402

Uncertain reading. Inside the first square brackets the letter is densely overwritten, with B-like loops; provisionally t. The exponent after the bracket is r-/n-like; the line uses the candidate r. The earlier strokes are not established.



Original source details: GELFAND-P000402

Uncertain reading. Before the current right-hand $A[t]^r$ a B-like expression with a densely cancelled upper exponent is crossed out; the candidates are B^r, B^n. The drawn exponent is provisional.



Coker $L' = A[t]^r$-mod. $\Rightarrow$ A-modules.

Original source details: GELFAND-P000402

Uncertain reading. In $A[t]^r$ after Coker the letter inside the brackets is overwritten; the exponent is r-/n-like. The line provisionally uses t, r; the equals sign and abbreviation "-mod." are written in the source.

It is fin. gener. and projective over A. (like a Fredholm oper. — finite cokernels).

Original source details: GELFAND-P000402

Diagram and typed description. At left is an arrow $K_2(B) \to K_1(A)$. At right in parentheses is the opposite direction $K_1(A) \to K_2(B)$; below its arrow is a short downward arrow to "exercise".

$$K_2(B) \longrightarrow K_1(A) \qquad (K_1(A) \longrightarrow K_2(B)) \downarrow \text{exercise}$$



Original source details: GELFAND-P000402

Diagram and typed description. Within parentheses is a descending diagonal row of dots; beside it are separate arrows upwards-left and downwards-right.

$M =$ 

infinite in both directions. In each row and col. a finite number of elems. $\neq 0$. $M^+ \subset M$, infinite in one dir.



Original source details: GELFAND-P000402

Diagram and typed description. Within parentheses the upper-left corner is filled: a vertical line is to the right of the hatching and a horizontal below it; inside are slanting strokes. The rest is unfilled, and no finite size is specified.



only one corner is filled (not fixed). $M_0 \subset M^+$.



Original source details: GELFAND-P000402

Undeciphered passage. After $M_0 \subset M^+$ a phrase is cancelled. An initial б-like sign and separate letter loops are visible; the whole phrase has not been recovered.



Original source details: GELFAND-P000402

Diagram and typed description. The label Ψ is above the arrow from M to M^+/M_0; "ring" is doubly underlined, and "homomorphism." is lower at right. Beneath is a long underlining rule.

$$M \xrightarrow{\Psi} M^+/M_0$$

ring, homomorphism.

M_0 — a finite number of elems. different from 0.

Original source details: GELFAND-P000402

Uncertain reading. At M with lower 0 there is an additional densely corrected upper sign with loops, resembling 0; its precise initial position and reading are not established.

M_0

An embedding.



Original source details: GELFAND-P000402

Uncertain reading. A horizontal arrow labelled φ goes from B to M; at right "exists." is doubly underlined. From M a slanting arrow downwards-right labelled Ψ points to a caption, provisionally "якобиева матрица" (yakobieva matrix, Jacobian matrix); the beginning of the first word is densely overwritten.

$$B \xrightarrow{\varphi} M$$

exists.

Ψ

Jacobian[?] matrix

(exercise on a Laurent series)

$$E_{ij}(b_1)\ldots = 1$$

— a reln. of elem. matrices — an element of K_2 — — a certain reln. (not a Steinberg one).

$$E_{ij}(\Psi(\varphi(e_2)))\ldots = 1.$$



Original source details: GELFAND-P000402

Uncertain reading. In the last line inside φ is a looped e-like letter and a small lower sign with a bend and lower rule. The current candidate is e_2; the historical candidates e_i, b_i are not excluded. The preceding argument b_1 has not been copied here.

GELFAND-P000403

[source number: 48]

$\ldots M^+/M_0$ “all oper. po vn. nepr.”

Original source details: GELFAND-P000403

Uncertain reading. Within quotation marks is “все опер. по вн. непр.” (all oper. po vn. nepr.). The abbreviations “вн. непр.” are left unexpanded; their full sense is not established.

$$E_{ij}(\varphi(b_1))\ldots = L.$$
$$\Psi(L) = 1.$$



Original source details: GELFAND-P000403

Diagram and typed description. The upper arrow $M \to M^+/M_0$ is labelled Ψ; at left an arrow downwards-right labelled Ψ_1 goes to M^+, and from there an arrow upwards-right labelled Ψ_2.



Ψ_2 — a ring hom.; Ψ_1 — trunc. — not a ring hom..



Diagram and typed description. The correction at right is separated by two long nearly vertical rules; its heading is underlined.

Correction:

Original source details: GELFAND-P000403

we must consid. matrices,



Undeciphered passage. After “matrices” a word with distinguishable в-like and p-like strokes is cancelled; its complete reading has not been recovered.

Original source details: GELFAND-P000403

which fit in a finite number of diagonals parall. to the principal one. Otherwise not a ring hom.



Diagram and typed description. Within parentheses are four one-like signs: two beside each other below, one higher, and one still higher at right; at both ends are separate diagonally positioned dots. Full rows, band boundaries and the remaining entries are not labelled.

Original source details: GELFAND-P000403



Consider $E_{ij}(\Psi_1(\varphi(b_1)))\ldots = L$. $L \neq 1$, since Ψ_1 is not a ring hom.

Uncertain reading. The sign after the inequality is densely overwritten: a one-like stem with a lower rule and superimposed loops is visible. The current candidate is 1; the earlier sign is not established.

$L \neq$

Original source details: GELFAND-P000403

But $\Psi_2(L) = 1$. L is a matrix over M^+, hence it is over M^0 — a finite matrix, def. an elem. of $K_1(A)$.

Bourbaki Sem., report by Delinya[?];



Original source details: GELFAND-P000403

Uncertain reading. The surname after “report” is densely overwritten and underlined. The candidate is “Делиня” (Delinya), possibly “Делинь” (Delin); the final strokes and earlier letters cannot be confidently separated.



Original source details: GELFAND-P000403

Diagram and typed description. At right $N = 180$ is within a shaped frame, with Lect. Notes. below it. The frame edge bends downwards at right.



UMN, 1970, $N = 3$, Griffiths.

Gabrielov. Work of Griffiths on var. Hodge structure.

X — a nonsingular complex[?] alg. projective variety; dim $X = d$.

Original source details: GELFAND-P000403

Uncertain reading. The abbreviation after “nonsingular” is provisionally “компл.” (complex); its middle joined strokes and ending are not fully separate. The complete word is not written out here.

$$H^n(X, Z), \qquad H^n(X, C) = H^n(X, Z) \otimes_Z C.$$

X is Kähler. On it there is an integral form η of second pr.[?] of type $(1, 1)$.

Original source details: GELFAND-P000403

Uncertain reading. After “second” is a short abbreviation with п-like and p-like strokes, provisionally “пр.” (pr.); a compressed middle о in “пор.” (por., order) is possible. Its exact complete letter reading is not established.

$$H^n(X, C) = \bigoplus_{p+q=n} H^{p,q}.$$

$\eta \in H^{1,1}$, closed and def. a cohom. class. it is given a priori. η is called a polarization.

GELFAND-P000404

$L : H^n(X, C) \longrightarrow H^{n+2}(X, C)$ — the oper. of mult. by η.

$$\text{Put } H_0^n = \text{Ker}(L^{d-n+1}; H^n \longrightarrow H^{2d-n+2}).$$

primitive cohomology. In cohom. there is a natural scalar product. One can prove that H_0^n is the orthog. complement of the image of L.

$$H^n(X, C) = \bigoplus L^i H_0^{n-2i}.$$

(decomp. of Hodge, Le Pazha, Lert[?], and so on)



Original source details: GELFAND-P000404

Uncertain reading. After “Ходжа” (Hodge) is written “Ле Пажа” (Le Pazha), then a surname or abbreviation beginning “Лер” and ending in a t-like stroke. Provisionally “Лерт” (Lert);“Лерэ” (Lere) and “Лефт” (Left) are possible. A full name is not expanded here.

(i.e. everything decomposes into primitives). $x, y \in H_0^n$. Consid.

$$\Psi(x, y) = (-1)^{\frac{n(n+1)}{2}} \int_X \eta^{d-n} \Lambda x \Lambda y.$$



Original source details: GELFAND-P000404

Uncertain reading. Between η^{d-n} and x, and between x and y, are two tall Λ-like signs. The line retains Λ; a reading as large wedge signs remains possible.



Original source details: GELFAND-P000404

Diagram and typed description. Below the word “form” is an insertion “on H_0^n” within a curved enclosure connected above to the line.

This is a bilin. form — the Hodge form.

on H_0^n

Properties:

1) $\Psi(x, y) = (-1)^n \Psi(y, x)$.

2) $x \in H_0^{p,q}$, $y \in H_0^{p',q'} \Rightarrow \Psi(x,y) \neq 0$ only when $p = q'$, $q = p'$.



Uncertain reading. After $p =$ the q' is densely overwritten; after $q =$ the letter p' has repeated strokes. The current candidates are $p = q'$, $q = p'$; earlier letters have not been recovered.

Original source details: GELFAND-P000404

3) $0 \neq x \in H_0^{p,q} \Rightarrow i^{p-q}\Psi(x,\overline{x}) > 0$. (in cohom. there is complex conjugation, $\overline{x}$ is the complex conjugate) Let C be the Weil autom. — mult. by i^{p-q} in $H^{p,q}$. (mult. by i in the tangent space). $\Psi(x,y)$ is inv. under the Weil autom.

1) and 3) $\Longleftrightarrow$



Original source details: GELFAND-P000404

Diagram and typed description. The formula with $C\overline{y}$ is doubly underlined; the lower rule has a leftward head. At right "pos. def. Hermitian form" is underlined by one long rule.

$\Psi(x, C\overline{y})$ — pos. def. Hermitian form

GELFAND-P000405

[source number: 49]

The basic idea of Deligne — one can forget about manif. and retain one Hodge struct. Cohom. — lin. spaces. A problem of lin. algebra.

$H_{\mathbb{Z}}$ — a finite-type $\mathbb{Z}$-module,

$H_{\mathbb{R}} = \mathbb{R} \otimes H_{\mathbb{Z}}$; $\quad H_{\mathbb{C}} = H_{\mathbb{Z}} \otimes \mathbb{C}$.



Original source details: GELFAND-P000405

Diagram and typed description. At right beside a double vertical rule:

// in applic. these will be primit. cohomology.



Original source details: GELFAND-P000405

Uncertain reading. [Crossed out above the formula:] “Real struct.[?]” (“Вещ. стр.”); the ending “стро” is possible. Strokes obscure the end of the abbreviation.

$\psi(x,y)$ — a bilin. form in $H_{\mathbb{C}}$ (integral — takes integer values on $H_{\mathbb{Z}}$).



Original source details: GELFAND-P000405

Diagram and typed description. Below the line,“of weight n” is inserted within a curved enclosure.

A real Hodge struct. on $H_{\mathbb{C}}$

of weight n — a decomposition

$$H_{\mathbb{C}} = \bigoplus_{p+q=n} H^{p,q}, \qquad H^{p,q} = \overline{H^{q,p}}.$$

A polarization of a real Hodge struct.: specifying an integral $\psi(x,y)$, inv. under the Weil autom. C ($\psi(Cx,Cy) = \psi(x,y)$) and $\psi(x,C\bar{y})$ — a pos. def. Hermitian form.

$$C: \quad H^{p,q} \xrightarrow{\times i^{p-q}} H^{p,q},$$
$$\psi(H^{p,q}, H^{p',q'}) = 0 \quad \text{when } p \neq q',\ q \neq p'.$$

This is called a polarized Hodge structure.

27/II. Kirillov. — repetition of Konsdana/Konstana[?].



Original source details: GELFAND-P000405

Uncertain reading. The surname after “repetition” has joined middle letters and a tall stroke returning below; provisionally “Консдана/Констана” (Konsdana/Konstana), with “Костана” (Kostana) and “Кансдана” (Kansdana) also possible. The full reading is not established.



Original source details: GELFAND-P000405

Diagram and typed description. From B a short slanted stroke leads to the underlined caption; no head is visible.

$A \longrightarrow A[t, t^{-1}] = B$

fns. on the suspension.

$$K_1 = GL(A)/E(A).$$

Original source details: GELFAND-P000405

Diagram and typed description. Two separate horizontal arrows: the upper one points right, the lower one left.

$K_0(A) \rightleftarrows K_1(B)$

$M \in GL(B)$, $\quad M = t^{-k}$[crossed-out sign]M_1,

Original source details: GELFAND-P000405

Uncertain reading. Between t^{-k} and M_1 a separate sign is densely crossed out. Its earlier shape cannot be separated; candidates are a crossed-out multiplication sign or another separate symbol.

M_1 — a polyn. matrix mstr.[?] $k \times k$.



Original source details: GELFAND-P000405

Uncertain reading. Below “polyn. matrix” the abbreviation is provisionally read “мстр.” (mstr.); “матр.” (matr.) is possible. The middle letter cannot be separated reliably.

$$A[t]^k \xrightarrow{M_1} A[t]^k, \qquad \ker = 0.$$



Original source details: GELFAND-P000405

Diagram and typed description. At right of the line beside a double vertical rule:

// Coker $M_1 = A$-module, which is already finite-dimensional.

(actually one needs the difference between kernel and cokernel) Elem. transformations do not change the cokernel.

GELFAND-P000406

$$M = t^{-k}M_1 = t^{-\ell}M_2.$$

Original source details: GELFAND-P000406

Diagram and typed description. In the margin — a long lower rule and an additional short one at left:

one must subtract the excess.

Original source details: GELFAND-P000406

Diagram and typed description. Crossed out:

~~N~~

The inverse map.

$$N \longrightarrow N[t, t^{-1}] = N \otimes_A B.$$

Original source details: GELFAND-P000406

Uncertain reading. The sign has two horizontal bars and a separate small downward stroke; provisionally the equality sign is retained. The meaning of the lower mark is not established.



Original source details: GELFAND-P000406

Diagram and typed description. A long horizontal rule is drawn below the next line.

$$N \otimes_A B \xrightarrow{t} N \otimes_A B$$

complete to a free module (otherwise one does not obtain a matrix).

$$\underline{N + M = A^k}, \qquad M \otimes_A B \xrightarrow{1} M \otimes_A B.$$

One obtains a map $B^k \longrightarrow B^k$. multiply by t^ℓ to obtain a polynomial one? [At right:] One need not multiply.



Original source details: GELFAND-P000406

Diagram and typed description. $A^k[t]$ is above the left-hand $M[t] \oplus N[t]$; between them are two vertical rules.

$A^k[t]$

$||$

$M[t] \oplus N[t] \qquad \xrightarrow{\quad t^\ell \oplus t^{\ell+1} \quad} \qquad M[t] \oplus N[t]$



Original source details: GELFAND-P000406

Diagram and typed description. At right the equality is underlined and has two exclamation marks.

$N[t] \xrightarrow{\times t} N[t]$ $\qquad\qquad$ $\underline{\text{Coker} = N!!}$

And the ends have met.

$$1 \longrightarrow K_2(B) \longrightarrow St(B) \longrightarrow E(B) \longrightarrow 1.$$

Swan, Tate. Two talks in Nice from [crossed out: an unreadable word]

Undeciphered passage. The word after "Two talks in Nice from" is entirely covered by dense crossing-out; its reading is not established.

Original source details: GELFAND-P000406

different points of view.

Gelfand.

$$K_0(A) \longrightarrow K_1(B).$$

N — a proj. module.



Original source details: GELFAND-P000406

Diagram and typed description. Below N and M are written t and 1; a downward arrow leads from the equality to the caption.

$$B \otimes_A (\underset{t}{N} \oplus \underset{1}{M}) = A^k$$

$$\downarrow$$

a matrix — an elem. of $K_1(B)$.

$B^k \longrightarrow B^k$ multiply by $t^{-\ell}$; one obtains $A[t]^k \longrightarrow A[t]^k$.



Original source details: GELFAND-P000406

Diagram and typed description. The concluding words are doubly underlined.

and Coker.

GELFAND-P000407

[source number: 50]

$$0 \longrightarrow K_1A \longrightarrow K_1A[t] \oplus K_1A[t^{-1}]$$
$$\longrightarrow K_1A[t,t^{-1}] \longrightarrow K_0A\,; \longrightarrow 0.$$

Original source details: GELFAND-P000407

Uncertain reading. Immediately after K_0A are a detached upper dot and a lower comma-like stroke; provisionally ";" in the line. The exact nature of the mark is not established.

K_0A ;

$$K_1A[t] = K_1A \oplus \text{Nil}\, A.$$

$M:\ A[t]^k \longrightarrow A[t]^k$ an invertible matrix up to elem. transformations. For regular rings Nil $A = 0$. K_1A — the constant term elem. transf. equiv. to the identity matrix. Now $M = 1 + tN(t)$; and invertible. one can make N independent of t; t^2 is broken up by increasing the order of the matrix (reduction to an equation of the first order).

$$1 + tN \text{ invertible in polynomials} \quad \Longrightarrow \quad N^k = 0.$$

Nil$A$ — nilpotent matrices.

Original source details: GELFAND-P000407

Diagram and typed description. Two horizontal segments with a detached dot between them.

———— . ————

The K-functor in Quillen's sense. Morava. (Kalumb.[?] Univ.).

Original source details: GELFAND-P000407

Uncertain reading. The first vowel in the abbreviation before "Univ." is a-/o-like. Provisionally "Калумб." (Kalumb.); "Колумб." (Kolumb.) is possible. The abbreviation is not expanded from an assumed university name.

Quillen's lemma. (d...na[?] by[?] one of the first in topology).



Original source details: GELFAND-P000407

Undeciphered passage. The first parenthetical word is not read in full. The beginning д and ending на are distinguishable; "должна" (dolzhna, a feminine form of "must/should") remains conjectural. The historical Т...сина/Г...сина (T...sina/G...sina) are not asserted as a name.

Original source details: GELFAND-P000407

Uncertain reading. After the first word,"бы" (by) is distinguishable; the joined ending is not established. The candidates "быть" (to be),"была" (was, feminine) and "было" (was, neuter) are retained without choosing by grammar.

X — a space, H — a normal subgroup of $\pi_1(X)$, with



Original source details: GELFAND-P000407

Diagram and typed description. Below the condition are two small separate vertically placed strokes/dots and a caption; no arrowhead is visible.

$H = [H, H]$
:
commutator



Original source details: GELFAND-P000407

Diagram and typed description. Between "unique" and X_H, "space" is inserted in a curved enclosure with a lower tip.

Then $\exists$ a unique 

X_H:

(up to homotopy),

$$X_H = X \cup e^2 \cup e^2 \cup \cdots \cup e^3 \cup \cdots \cup e^3,$$
$$\text{such that} \quad \pi_1(X_H) = \pi_1(X)/H,$$
$$\text{and} \quad H_*(X, Z) \simeq H_*(X_H; Z).$$

(the homology ring with integer coeffs.) Corresp. functorially in X. Proof by means of

obstruction theory.

GELFAND-P000408

Let $X = BGL(R)$ — the classif. space of $GL(\infty)$. [Below $GL(\infty)$, crossed out: ned...naya.]



Original source details: GELFAND-P000408

Uncertain reading. In the crossed-out word the beginning “нед...” (ned...) and ending “...ная” (...naya) are distinguishable; the middle is covered by a line. The candidate “недискретная” (non-discrete) is not established in full.

(R — any ring). everything without topology — a discr. group. (has nothing in common with Grassm.).

$$E(R) = [E(R), E(R)].$$

the subgroup generated by elem. matrices.

$$\pi_1(BGL(R)) = GL(R),$$
$$\pi_1(X_{E(R)}) = GL(R)/E(R) \text{ — its fund. group } K_1(R).$$

Now $K_i(R) = \pi_i(X_{E(R)})$. [Crossed out: It is unknown, true



Original source details: GELFAND-P000408

Undeciphered passage. The middle words of the crossed-out line are not recovered; the surviving beginning and end are given in the line.

for K_0.] K_0: the def. must be changed, since $\pi_0(\ ) = \{1\}$. Quillen: if R is a field, then

$$K_2^{\text{Quillen}} = k_2^{\text{Milnor}}.$$



Original source details: GELFAND-P000408

Uncertain reading. On the right, the letter before the subscript 2 is distinctly smaller than the left K and has a k-like form. Provisionally typeset as k_2; its case is not inferred from the expected group notation.

There is also Volodin's definition. There exists a theory applicable to top. groups. Then for R and C one obtains the usual K-functor.



Original source details: GELFAND-P000408

Diagram and typed description. The $\wedge$ sign is lowered below the main line. Below the formula is a lower bracket with a short stroke to the caption "suspension"; the exact scope of the caption is not established.

$$K_i(R)(Y) \stackrel{\text{def}}{=} [S^i_{\wedge} Y; X_{E(R)}]$$

suspension

Novikov's problem: define the Chern char. in alg. K-theory. Here this reduces to computing $H_*(X_{E(R)}; Q)$.

GELFAND-P000409

[source number: 51]

A. Gabrielov. X — an alg. projective manifold.

$$H^n(X, \mathbb{C}) = \bigoplus_{p+q=n} H^{p,q},$$

$$F^p = \bigoplus_{\substack{p'>p \\ p'+q=n}} H^{p',q} \text{ — the Hodge filtration.}$$

It moves holomorphically! The behaviour of this filtr. will be studied when X depends on a parameter. $X_s \subset Y$ — an analytic nonsing. manifold.



Original source details: GELFAND-P000409

Diagram and typed description. The family diagram and a separate short vertical stroke with a hook below X_s; below it, nearby, $s \in S$.



[Before the following words, crossed out:]

Original source details: GELFAND-P000409

Undeciphered passage. The crossed-out word before “analytic map” is not recovered in full. The candidates “гладкое” (smooth) and “полное” (complete) are not fully confirmed.

analytic map (loc. project.). S — a nonsing. alg. project. manifold. smooth — local triviality in the analytic sense. O_S — the sheaf of analytic functions on S;



Original source details: GELFAND-P000409

Diagram and typed description. The underlined definition, “image” inserted below, and a curved arrow to the margin.

Without tensor mult. by O_Y.

f^*O_S — set-theor. inv. image.

Uncertain reading. In the first f^*O_S the superscript is overwritten into a dark blot. Provisionally $*$; $\circ$ is possible. The later clear f^* and f° do not establish this written sign.

Original source details: GELFAND-P000409

$R^n f_* f^\circ O_S$ —



Original source details: GELFAND-P000409

Diagram and typed description. The enclosed insertion “holom.” attached to “bundle”; below to the right is a separate vertical stroke.

loc. triv. bundle

holom.

with fibre



Original source details: GELFAND-P000409

Uncertain reading. After X_s, before the separator, are crossed-out vertical and loop-like strokes. The previous signs are not read; the strokes are shown without asserting a letter Z. Below the left part of the formula is a double underline.

$H^n(X_s; \mathbb{C})$

Original source details: GELFAND-P000409

Uncertain reading. Below the formula to the right is a crossed-out fragment ending “...оем” (...oyem); “слоем” (with fibre) is possible, but not established in full. Above it is a short vertical stroke.

~~with fibre[?]~~

in the fibres, a holom. filtration by subbundles. The relative de Rham complex:

$$\Omega^*_{Y/S},$$

$$\Omega^1_{Y/S} = \Omega^1_Y / f^*\Omega^1_S; \qquad \Omega^p_{Y/S} = \bigwedge_p \Omega^1_{Y/S},$$

$$0 \longrightarrow f^\circ O_S \longrightarrow O_Y \longrightarrow \Omega^1_{Y/S} \longrightarrow \dots.$$

($f^*O_S = O_Y$, $f^\circ O_S$ — constant along the fibres). (a resolution of the sheaf f°). N. m. $H^{p,q}$ forms in $dz, d\bar{z}$ move non-analytically, since $d\bar{z}$ transforms non-analytically. $H^{0,q}$ is clear (dz does not enter).

Original source details: GELFAND-P000409

Diagram and typed description. The last line of the leaf, with an unclosed parenthesis: $d\bar{z}$ remains, the number does not increase. (the holom. part increases.

GELFAND-P000410

S — a point, $f^\circ O_S$ — the sheaf of constants, $R^n f_* f^\circ O_S$ — cohom., depending holom. on the parameter.



Original source details: GELFAND-P000410

Diagram and typed description. Two separate horizontal segments below words in parentheses.

(functions const on $\forall$ fibre, but on S analytically).

Consider the Leray spectr. seq.:

$$E_1^{p,q} = R^q f_* \Omega^p_{Y/S} \longrightarrow R^n f_* f^\circ O_S.$$

they induce a filtration



Original source details: GELFAND-P000410

Diagram and typed description. The filtration and exact sequence.

$$R^n f_* f^\circ O_S \supset \mathcal{F}^p \quad \text{(sheaves)},$$
$$\mathcal{F}^n = R^n f_* \Omega^0_{Y/S},$$
$$0 \longrightarrow \mathcal{F}^{p-1} \longrightarrow \mathcal{F}^p \longrightarrow E_\infty^{p,n-p} \longrightarrow 0.$$

The spectr. seq. degenerates (all differentials are zero). In the bundle $R^n f_* f^\circ O_S$ there is a filtration by holom. bundles with fibres F^p.



Original source details: GELFAND-P000410

Diagram and typed description. A short arrow from the formula to the lower line about sections.

$$R^n f_* \mathbb{C} \longrightarrow R^n f_* f^\circ O_S = R^n f_* \mathbb{C} \otimes O_S$$
$$\downarrow$$

loc. constant sections arise $\Rightarrow$ a connection

(Gauss-Manin)



Original source details: GELFAND-P000410

Diagram and typed description. The connection formula and several nearly coincident horizontal strokes below it.

$$\nabla : \quad R^n f_* f O_S \longrightarrow \Omega^1_S \otimes R^n f_* f^{\circ} O_S$$

GELFAND-P000411

[source number: 52]

6/III. M. Sh. Birman.



Original source details: GELFAND-P000411

Diagram and typed description. A tilted solid oval inside a wider broken contour; Ω at the upper right, R at the lower left, and the condition at the right. The exact assignment of the region Ω to the contours is not established.



$u_{tt} = \Delta u$.

Original source details: GELFAND-P000411

Diagram and typed description. A phrase with a wavy underline.

Suppose Huygens' principle holds.

$\int_\Omega (|\nabla u|^2 + |u_t|^2)\, dx$ — is conserved.

Original source details: GELFAND-P000411

Diagram and typed description. Incoming and outgoing solutions — do not exhaust the subsp. with finite energy.

$K_+ \oplus K_- = \mathcal{H} \ominus K_0$; (consider the initial data of solutions). K_0 — solutions decaying exp. in time, but concentrated near the boundary. f, $\frac{\partial f}{\partial t}\Big|_{t=0} = f_1$. Initial data — pairs (f, f_1) in the energy metric. K_+ — outgoing waves and at $t = 0$ already concentrated outside the sphere of radius R.

Original source details: GELFAND-P000411

Diagram and typed description. A line with two separate underline segments and a dot between them.

see Lax and Phillips.

Words. (key)

1. Characteristic functions. — part 2 of the book by Gohberg and Krein.
2. Scattering.
3. “the second sheet of the resolvent”
4. S-matrix theory.
5. complex poles of

Original source details: GELFAND-P000411

Diagram and typed description. Two separate segments below the words and a dot between them.

self-adjoint oper.

H is close to H_0 if $\forall f\ \exists g_\pm$:

$$\|e^{-iH_0t}f - e^{-iHt}g_\pm\| \longrightarrow 0 \quad \text{as } t \longrightarrow \pm\infty.$$

On the abs. cont. spectrum there is a def. $g_+ = U_+ f$; U_+ — a partial isometry.



Original source details: GELFAND-P000411

Diagram and typed description. A phrase with a wavy underline.

Suppose the whole spectrum is abs. cont.

Then U_+ is semi-unitary



Original source details: GELFAND-P000411

Uncertain reading. After the underlined identity is a separate densely crossed-out sign; its previous form is not established. The visible horizontal and oblique strokes are reproduced without choosing ⇒.

$$U_+H_0 = HU_+.$$

H contains a part unitarily equiv. to H_0. Problem: when does the range of U_+ exhaust the whole abs. cont. subsp. of H? This is single-channel scattering (in physical language). (i.e. $\exists$ complete wave operators). multichannel: To describe H one needs



Original source details: GELFAND-P000411

Diagram and typed description. A list of operators with a lower horizontal stroke turned upward at the right.

$$H_0^{(1)}, \ldots, H_0^{(n)}$$

so that the ranges of U^+ cover the whole space and are orthogonal. $H_0^{(i)},\ i = 1, \ldots, n$ — a collection of operators; H is called admissible if $U_+^{(i)}$ are defined

such that their ranges $U_+^{(i)}$ are pairwise orthogonal. and gen.[?] the abs. cont. spectrum of H.

Original source details: GELFAND-P000412

Uncertain reading. The abbreviation after "and" has a dense beginning and a distinguishable ending "...рожд." (...rozhd.). Provisionally "порожд." (gen.); it is not expanded into a full verb.



Original source details: GELFAND-P000412

Diagram and typed description. "3 particles" is underlined; below the middle of the line are two separate segments and a dot.

3 particles Faddeev embedded in the scheme of Lax and Phillips.



Original source details: GELFAND-P000412

Diagram and typed description. Below the name and date is a line ending in a point to the right.

Kato (1957). $H - H_0$ nuclear.

$\varphi(H) - \varphi(H_0) \in$ nuclear. Birman, 1962.

Original source details: GELFAND-P000412

Uncertain reading. The second function sign, before (H_0), is heavily overwritten. Provisionally φ; a ψ-like form is not excluded. The clear signs in the later formula do not recover the previous strokes.

$S = U_+^* U_-$ — the scattering oper.,

$S(\lambda)$ — the scattering matrix (corresp. decomp. of H_0),

$S(\lambda) - I_\lambda \in$ nuclear. Birman — Krein,

$$\det S(\lambda) = e^{-2\pi i \xi(\lambda)},$$

$$\mathrm{Sp}[\varphi(H) - \varphi(H_0)] = \int \frac{d\varphi(\lambda)}{d\lambda} \xi(\lambda)\, d\lambda.$$

(this defines $\xi(\lambda)$)

Original source details: GELFAND-P000412

Diagram and typed description. A dividing line.

$$D(H) = D(H_0);$$



Original source details: GELFAND-P000412

Uncertain reading. A tall loop-like letter with a forked top and subscript 1. Provisionally $\mathcal{J}_1$; the candidate γ_1 remains. The two separate underline segments and dot are retained.

$(H - H^0)E^0(\Delta) \in \mathcal{J}_1 \qquad \forall$ bounded Δ

— sufficient for the existence of wave operators. The proper abstract formulation — gradually separate the spectrum of different dimensions (see



Original source details: GELFAND-P000412

Diagram and typed description. Two underline segments with a dot between them.

theory of coupled forms

— different Laplace operators). On a more general def. of wave operators.

$$U_\pm = \lim_{t \to \pm\infty} e^{iHt} J e^{-iH_0 t}.$$

Corresp. to different spaces and classical scattering.

$$1) \quad D(H) = D(H_0),$$

$$2) \quad (JH_0 - HJ)E^0(\Delta) \in \mathcal{J}_1,$$



Original source details: GELFAND-P000412

Uncertain reading. In condition 2 is the same loop-like letter with subscript 1. Provisionally $\mathcal{J}_1$; γ_1 is possible. The letter is not established from the expected operator ideal.

$$3) \quad (J^*J - I)E^0(\Delta) \in \mathcal{J}_\infty.$$



Original source details: GELFAND-P000412

Uncertain reading. In condition 3 is a loop-like letter with a lower horizontal loop. Provisionally $\mathcal{J}_\infty$; the candidate is γ_∞. The letter and reading of the lower loop remain qualified.

$J = U_+$ — trivially exists. One must ≈ guess U_+.

GELFAND-P000413

[source number: 53]

L. Vaserstein. Different K-theories. 1) A — an assoc. ring. $K_n = \pi_{n-1}(GL(A))$.



Original source details: GELFAND-P000413

Diagram and typed description. A double vertical stroke and a caption to the right.

Volodin's def.

def. of an abstr. simpl. scheme in $GL(A)$. K_1 coincides with Whitehead's; K_2 with Milnor's.



Original source details: GELFAND-P000413

Diagram and typed description. A long dividing line.

2) Derived functors (Swan; Gershtein) of GL. $K_n^{GS} A$. Consider a free resolution of the ring A:



Original source details: GELFAND-P000413

Uncertain reading. Below A' is a crossed-out expression, provisionally K_0. Its meaning is not recovered from context.

$$A'' \longrightarrow A' \longrightarrow A$$

~~K_0~~



Original source details: GELFAND-P000413

Diagram and typed description. A double vertical stroke; “assoc.” in an enclosure with an insertion tip; ditto strokes in the second line.

assoc.

|| A' — a free ring, generated by A as a set.

A'' — || — || — the kernel of the map.

$$GL(A'') \longrightarrow GL(A') \longrightarrow GL(A)$$

is no longer exact.. K_1 coincides (

Original source details: GELFAND-P000413

Uncertain reading. Before the following K_1 is a separate densely inked mark. The previous sign is not determined.

K_1 of a free ring $= 0$).



Original source details: GELFAND-P000413

Diagram and typed description. A separate vertical stroke above the marginal explanation.

a matrix invertible over a free ring
(∼ over any) is a product of elementary matrices.

(For simplicity the rings are taken without identity).



Original source details: GELFAND-P000413

Diagram and typed description. Below $[A]$ is a short stroke to the lower caption.

$A' = Z[A]$
|
all elem.

— noncommut. polynomials without a constant term; The derived functor is defined using simplicial constructions.

Original source details: GELFAND-P000413

Diagram and typed description. Two horizontal segments with a detached dot between them.

$$1 \longrightarrow A'' \longrightarrow A' \longrightarrow A,$$
$$K_{n+1}(A) = K_n(A'').$$

(an inductive formula): define everything through K_1. The problem of the Steinberg relations was done by L. V. and follows from the coincidence of these K-functors with Volodin's. A — a ring. MA — matrices over A. ℓA — in $\forall$ row and column there are only finitely many nonzero elements. $MA \longrightarrow \ell A$.



Original source details: GELFAND-P000413

Uncertain reading. In the first ring notation and in the adjacent arrow is a loop-shaped lowercase letter. Provisionally ℓ in both places; the candidate e remains. Similarity of the forms does not establish the choice of letter.

GELFAND-P000414

and $K_n \ell A = 0$! (contractible). (according to V. or GS). (A — any ring) Proof $\sim$ Kuiper's theorem.



Original source details: GELFAND-P000414

Diagram and typed description. A horizontal line.



Original source details: GELFAND-P000414

Uncertain reading. At the end of the sequence is an inked sign with a rounded lower loop; 0 is only a candidate. Below MA are crossed-out strokes.

$$MA \longrightarrow \ell A \longrightarrow \mu A \longrightarrow$$

analogue of compact.

Original source details: GELFAND-P000414

Undeciphered passage. The crossed-out word immediately below MA is not read in full. The candidates “матр.” (matr.) and “комп.” (compact.) are not asserted.

(matrices with finitely many nonzero elements)

$$\underline{\underline{K_n A = K_n M A}},$$

$$\underline{\underline{K_n A = K_{n+1}\mu A}} \quad \text{(from the exact sequence)}.$$

From this one obtains K_0 ($= K_0$ [crossed out:



Original source details: GELFAND-P000414

Undeciphered passage. The phrase before “ordinary” inside the parenthesis is not recovered in full.

] ordinary) — full (a free module $\neq 0$).

$$K_0 A = K_1 \mu A.$$



Original source details: GELFAND-P000414

Uncertain reading. The subscript on the second K is reinforced/overwritten. Provisionally 1; the former form is not established from the shift formula.

From this, K_n ($-\infty < n < \infty$). This coincides with Bass's K_n.

$$\boxed{\mathrm{Nil}_n\, A = K_n\, tA[t].}$$



Original source details: GELFAND-P000414

Diagram and typed description. Two separate horizontal segments, the right one higher, with a dot between them.



Original source details: GELFAND-P000414

Diagram and typed description. Below "hom." is the inserted line $A \longrightarrow B$.

To $\forall$ ring hom. corresp. an exact seq. of K_n,

$A \longrightarrow B$

and a new ring, so that relative K_n = absolute of the new ring.

$$A \xrightarrow{f} B,$$
$$\cdots \longrightarrow K_nA \longrightarrow K_nB \longrightarrow K_nF \longrightarrow K_{n-1}A \longrightarrow \dots.$$



Original source details: GELFAND-P000414

Diagram and typed description. A square with circled F, four arrows and an arc to “universal”. Before the lower arrow is a crossed-out mark; the former sign is not recovered. The upper-right letter is μ-/m-like: provisionally μB; mB and MB are not excluded. The notation is not replaced from the expected inclusion.



(fibred product; inverse image) pullback. In L. V.’s opinion, Quillen’s theory coincides with these. Karoubi’s theory does not coincide. $tA[t]$ is considered contractible.



Original source details: GELFAND-P000414

Diagram and typed description. A lower caption for $t(t-1)A[t]$ and the label $t=1$ at the right arrow.

$$t(t-1)A[t] \longrightarrow tA[t] \xrightarrow{t=1} A$$

loop space ΩA

GELFAND-P000415

[source number: 54]

$K_{n+1}A = K_n \Omega A$. According to Karoubi.

In the present K-theor.



Original source details: GELFAND-P000415

Diagram and typed description. Below the formula are two separate horizontal strokes and a small mark between them.

$K_n\, tA[t] = Nil$

On Quillen's theorem:

Let G be any group, $E = [G, G]$ and $E = [E, E]$. Consider the universal classif. space BG with a cell structure. Publ. Math., 34. $\pi_1 BG = G$, the others 0. $(BG = K(G, 1))$.

Make minimal cell attachments, turning it into a group (H-space). Homology does not change. E is killed.



Original source details: GELFAND-P000415

Diagram and typed description. Below the end of "For the new complex" is a separate stroke, then a dot and a stroke below π_n.

For the new complex $\pi_n = K_n$.



Original source details: GELFAND-P000415

Diagram and typed description. Below the line are two separate strokes and a dot between them; the left stroke has a point toward the left.

Everything carries over to the unitary case.

Theor. Valonera/Vagonera[?] on Laurent extensions.

Original source details: GELFAND-P000415

Uncertain reading. The underlined surname is provisionally “Валонера/Вагонера” (Valonera/Vagonera); the middle letters are joined. The full reading is not established.

$$K_2A[t,t^{-1}] = K_2A \oplus K_1A \oplus \textcircled{2}.$$



Original source details: GELFAND-P000415

Uncertain reading. The upper curve of the last circled sign is 2-like, with a separate dot below. The visible strokes are reproduced; “?” remains a candidate, and no numeric summand is asserted.

the theor. holds $\forall n$, but from this case all the others follow.

Proof.



Original source details: GELFAND-P000415

Diagram and typed description. The first caption is below its arrow, the second above its arrow.

$$A \xrightarrow[\text{constant term.}]{} A[t,t^{-1}] \xrightarrow{t=1} A$$



Original source details: GELFAND-P000415

Diagram and typed description. At right is an enclosure with upper, left and lower sides; the right side is open. There are two strokes below the following words.

K_2 relative is trivial

Mult. by $t \in$ the centre.



Original source details: GELFAND-P000415

Undeciphered passage. Between the diagram and the matrices is a row of eleven small separate dots/short strokes. Their purpose and any earlier inscription are not established.

$$\begin{pmatrix} a & 0 \\ 0 & a^{-1} \end{pmatrix} = \begin{pmatrix} 1 & a-1 \\ 0 & 1 \end{pmatrix} \begin{pmatrix} 1 & 0 \\ 1 & 1 \end{pmatrix} \begin{pmatrix} 1 & \cdot \\ 0 & 1 \end{pmatrix} \begin{pmatrix} 1 & 0 \\ \circ & 1 \end{pmatrix}.$$

(Whitehead's formula). (the dots are recovered uniquely).



Original source details: GELFAND-P000415

Uncertain reading. The upper-right entry of the third matrix is a dot. The lower-left entry of the fourth is a thick 0-like dot with a small opening; its contour is reproduced, but its value is unwritten.

g is a matrix over A. (defines an elem. of K_1)

$$\begin{pmatrix} gt & 0 \\ 0 & g^{-1}t^{-1} \end{pmatrix} \qquad \begin{pmatrix} t & 0 \\ 0 & t^{-1} \end{pmatrix} \qquad \begin{pmatrix} g & 0 \\ 0 & g^{-1} \end{pmatrix}.$$

Original source details: GELFAND-P000415

Uncertain reading. The upper-left entry of the middle matrix is overwritten; provisionally t, with the earlier strokes unrecovered. There are no equality signs between the three matrices.

Now decompose them into elem.

Original source details: GELFAND-P000415

Uncertain reading. After the abbreviation "элем." (elem.) is a faint slanted chain of broken strokes with two darker spots. Its connection to the inscription and the punctuation are not established.

one obtains relations —

— an elem. of K_2

GELFAND-P000416

The converse: An elem. of $K_2A[t,t^{-1}]$.

Original source details: GELFAND-P000416

Diagram and typed description. The underlined “Laurent series” and a horizontal arrow with a wavy beginning.

Laurent series. ⇝ Mult. by it — an infinite matrix

Original source details: GELFAND-P000416

Undeciphered passage. Before “One obtains relations” is a separate densely crossed-out formula. K-like, a lower 2-like and A-like fragments are distinguishable; the full inscription is unrecovered.

One obtains relations between infinite matrices. Cut off ⇒ relations $\ell A/\mu A$. (mod. finite matrices).



Original source details: GELFAND-P000416

Uncertain reading. The numerator is overwritten: provisionally ℓA, with MA possible beneath the dense earlier sign; the denominator is μA. The earearlier strokes are unrecovered.

~~ℓA~~$/\mu A$

We need $\ell A/\mu A$. Lift.

Kazhdan/Kazdan[?].



Original source details: GELFAND-P000416

Uncertain reading. The doubly underlined heading is provisionally “Каждан/Каздан” (Kazhdan/Kazdan); the join after “Ка” is ambiguous.

Original source details: GELFAND-P000416

Uncertain reading. The crossed-out heading is provisionally “Let there be[?] 2 formal power series”; “Let 2 formal power series be given” is also possible. The second word merges with the crossing stroke.

~~Let there be[?] 2 formal power series~~



Original source details: GELFAND-P000416

Diagram and typed description. A parenthetical caption is inserted below “power series”.

K is the field of formal power series over k (a field).

(Laurent)

A is power series (Taylor). $k \subset K \supset A$.

Let



Original source details: GELFAND-P000416

Diagram and typed description. To the right of the three conditions are two separate vertical rules and a caption.

$$\begin{aligned} p_1 + p_2 &= 1, \\ p_1 A &= 0, \\ p_2 K &\subset A. \end{aligned}$$

p_i — maps of K.

Let $f, g \in K$. The residue of $\underline{f\,dg}$ — ?

Original source details: GELFAND-P000416

Uncertain reading. The parenthetical note is provisionally “(без парам.!)” (without param.!); the abbreviation is unexpanded. The readings “без лоран.!” (without Laurent.!) and “без полюса!” (without a pole!) remain candidates; the joined middle strokes are not fully determined.

Consider $Sp[p_1 f, p_1 g]$.



Uncertain reading. In both arguments after p are small lower signs, provisionally $1,1$; $2,1$ and $1,2$ are possible. The first sign especially merges with p.

Original source details: GELFAND-P000416



Original source details: GELFAND-P000416

Diagram and typed description. Below the commutator are two long lower contours with short raised ends. There is a separate dot at the left end of the outer contour; below is a caption with a wavy underline.

$Sp[p_1 f, p_1 g]$

oper. of finite rank.

GELFAND-P000417

[source number: 55]

$13/\overline{\text{III}}$. Prof. Morava. Work by G. Segal and K^0.

C is a categ., BC the simpl. set corresponding to this category. the points of the set are the objects of this category.



Original source details: GELFAND-P000417

Diagram and typed description. At the left above the beginning of the C_0 line is an underlined surname.

Gelfand.

C_0: $[n] = \{0, 1, \ldots, n\}$ — objects of an auxiliary categ.

Morphisms: $[k] \underset{\varphi(i)}{\longrightarrow} [n]$, $\varphi(1) \leq \ldots \leq \varphi(k)$.

Original source details: GELFAND-P000417

Uncertain reading. In the first argument of φ is a thick 1; an earlier overwritten 0 is possible underneath.

(see Gabriel, Tsisman[?])



Original source details: GELFAND-P000417

Uncertain reading. The second surname is provisionally “Цисман” (Tsisman); the joined middle letters are ambiguous, and “Зисман” (Zisman) is possible.



Original source details: GELFAND-P000417

Diagram and typed description. Above the beginning of the next line, “Contravar.” is outlined; the lower contour has a narrow projecting pointer.

A functor A from C_0 to the categ. K is called a simplicial object in the cat. K. A_k is the image of the object $[k]$. $A_0, A_1, \ldots, A_k, \ldots$ and a system of morphisms. If K is the cat. of sets, then this is

Original source details: GELFAND-P000417

Undeciphered passage. An earlier short word is densely crossed out; its original letters are not fully recovered. A lower loop is visible.

a simplicial set.

The system A_0 is a set of points. The system A_1 — $-\|-$ of segments. and so on.



Original source details: GELFAND-P000417

Diagram and typed description. Three product lines; below are two short strokes and a dot. Under the last triangle are a short vertical stroke and a caption.

$A_0 \times \cdot$

$A_1 \times \Delta_1$

$A_2 \times \Delta_2$

stand.
simpl.

and glue in the natural way. Obtain an actual complex.



Original source details: GELFAND-P000417

Diagram and typed description. Under the line is a long leftward arrow; to the right of its left part is a gap with a separate dot, then the stroke continues.

From a categ. — a simpl.



Original source details: GELFAND-P000417

Diagram and typed description. There is a wavy stroke beneath the equality. The next line is "morphisms in C".

objects $C = BC_0$.

morphisms in C.



Original source details: GELFAND-P000417

Diagram and typed description. Three lines with captions at the left. In the first, BC_1 is above the arrow; the right letter is provisionally b, possibly an e-like letter. Below a is a small closed contour, and below the right letter a separate thick stroke; the meanings of the lower signs are undetermined. In the second are two round marks and an arrow to c; the middle letter is also provisionally b, possibly e-like. In the third are four marked positions, the third and fourth merging with arrowheads; after the fourth is a further rightward arrow, with no added endpoint.

1-simplices BC_1 a b

2-simpl. a b c

3-simpl.

GELFAND-P000418



Original source details: GELFAND-P000418

Diagram and typed description. At the right is the chain $a \to b \to c$, with a separate densely crossed-out a-like sign after c. Three oblique arrows point left to the lines $a \to b$, $b \to c$, $a \to c$. Beneath the right chain, "3 maps" is doubly underlined. The earlier overlapping strokes of the last sign are not fully recovered.



Example. If C has one object,

Original source details: GELFAND-P000418

Undeciphered passage. After "object" an earlier short inscription is crossed out; its letters are unrecovered. Below it an outlined e is inserted.



$\forall$ morphism — isomorphism.



Original source details: GELFAND-P000418

Uncertain reading. Below the parenthetical inscription "$C =$ group" is the caption "set of morph. ob[?]". The final joined sign is provisionally read "об" (ob); the abbreviation is unexpanded and the reading is undetermined.

$C =$ group

set of
morph. ob[?]



Original source details: GELFAND-P000418

Diagram and typed description. After $BC_1 = G$, $Mor(e,e)$ is written separately. Below are three short faint marks and a separate dot.

$BC_1 = G$ $\qquad\qquad$ $Mor(e,e)$

$$BC_n = G \times G \times \ldots \times G.$$

def. $\Rightarrow$ Milnor's def. of the classifying space of the group G.

Original source details: GELFAND-P000418

Undeciphered passage. Before "of the group", an earlier short word is densely crossed out and not fully recovered.

since $BC_n \times \Delta_n$ and gluing. G a top. gr. $\Rightarrow$ one may equip with a topology.



Original source details: GELFAND-P000418

Diagram and typed description. Below the R-modules is a parenthetical insertion; between "modules" and "and" is a small angular stroke.

Let C be the category of R-modules and isomorphisms in the cat. Mod.

(projective; finitely generated.)

Original source details: GELFAND-P000418

Uncertain reading. The category name is provisionally "Мод." (Mod.); the initial letter merges with dense earlier strokes, and the earlier inscription is unrecovered.

BC.



Original source details: GELFAND-P000418

Diagram and typed description. Two lines of arrows; in the lower one the sign between M and N is overwritten on earlier strokes.

$$C \times C \longrightarrow C$$

$$(M \times N) \longrightarrow M \oplus N$$

Original source details: GELFAND-P000418

Uncertain reading. In the lower left argument the sign is provisionally $\times$; one diagonal stroke is very thick, and the earlier sign is unrecovered.

Lemma. α, β are 2 categories $\Rightarrow B(\alpha \times \beta) = B\alpha \times B\beta$.

Original source details: GELFAND-P000418

Diagram and typed description. In the left margin,"Proof" is crossed out.

~~Proof~~

Original source details: GELFAND-P000418

Undeciphered passage. At the right after the product formula an earlier phrase is densely crossed out and not fully recovered. A separate lower loop is visible beneath the stroke.

$BC \times BC \longrightarrow BC$; i.e. BC is an H-space.

Original source details: GELFAND-P000418

Undeciphered passage. After the doubly underlined heading a short inscription is densely crossed out; its letters are unrecovered. At the left is a separate angular mark.

Remark:

$M \oplus N \neq N \oplus M$ (isom.,but not $=$ as objects of the categ.)



Original source details: GELFAND-P000418

Diagram and typed description. The top and oblique arrows of the triangular diagram are labelled $\oplus$; the vertical arrow points downward and is labelled T. Below T is a separate short curved rightward arrow; at the left is a faint broken stroke.





Original source details: GELFAND-P000418

Diagram and typed description. The right-hand insertion has two left vertical rules and an oblique lower boundary. Above the arrows of the upper line are the labels a_1, a_2, a_5; below the outer arrows of the second, b_1, b_7, with the final lower index overwritten and provisionally read 7. Next is written $a_1b_1 \to a_2b_1 \to \cdots \to a_5b_1 \to a_5b_2$, with a_5b_3 below, an arrow and dots. The caption is “12 in all”. At the lower right margin are two further rules, an upward arrow and “homot. commut.”.



GELFAND-P000419

[source number: 56]

Remark. If $X \times X \longrightarrow X$ is commut. and associat.



Original source details: GELFAND-P000419

Diagram and typed description. Above the line,“exactly, and not up to homot.” is outlined with a lower projecting pointer; to the right are a separate frame and the sign ⇒.



Original source details: GELFAND-P000419

Diagram and typed description. The sign between X and the product has a wavy upper stroke and two lower horizontal strokes.

$\Rightarrow X \cong \prod_n K(\pi_n, n)$

Theorem. Let $X \times X \longrightarrow X$

Original source details: GELFAND-P000419

Uncertain reading. The first word is provisionally “ассоц.” (assoc.); the initial letters are overwritten and the earlier strokes cannot be separated.

~~a~~ssoc.[?]

commut. and assoc. in a canonical way. Then ∃ a classif. space;

Original source details: GELFAND-P000419

Uncertain reading. The overwritten word is provisionally “оно” (it); “это” (this) is possible. The initial strokes merge.

~~it~~[?]

is also an H-space with a canonically homot. commut. and assoc. law. BX is this classif. space. $B(BX) \underset{def}{=} B^2X$.

Original source details: GELFAND-P000419

Diagram and typed description. At the left is a vertical sequence with two groups of continuation dots.

C

BC

B^2C

$\vdots$

B^kC

$\vdots$



Original source details: GELFAND-P000419

Diagram and typed description. The definition has two lower contours. Two short vertical strokes cross the long contour; beneath is a separate bracketed expression. The cancelled intermediate inscription is provisionally $[Y]$; the small right-hand sign is rendered by separate strokes.

$$K_C^{-k}(Y) = \cancel{[Y]} \lim_{i\to\infty} [Y, \Omega^i B^{k+i} C]$$

$$[S^i \wedge Y, B^{k+i} C]$$

Original source details: GELFAND-P000419

Uncertain reading. Between the equality and lim is an earlier crossed-out bracketed inscription; square brackets and a Y-like letter are visible, provisionally $[Y]$. A fuller inscription is undetermined.

Original source details: GELFAND-P000419

Uncertain reading. After the right bracket is a small sign with a loop, a long rightward stroke and a separate upper dot; below is a further separate mark. An i-like inscription is possible, but its meaning and index position are undetermined.

In fact



Original source details: GELFAND-P000419

Uncertain reading. At the right after the exponent $k+1$, the letter C is unwritten. The relation sign has a wavy stroke above two horizontal strokes.

$$B^k C \cong \Omega B^{k+1}$$



Original source details: GELFAND-P000419

Diagram and typed description. The condition at the left is doubly underlined; at the right the entire phrase, including the initial “and”, is underlined.

$\underline{\underline{k \geq 2.}}$ and the limit is unnecessary.

Example 1. $Y = \{*\}$, C the cat. of projective R-mod. $\Rightarrow$ the K-functor according to Quillen.
Example 2. C is the categ. of finite sets.

$$BC = \coprod_n B\Sigma_n$$

(disj. union of all classif. spaces of the symm. groups Σ_n).



Original source details: GELFAND-P000419

Diagram and typed description. The whole line is underlined; below are two additional short strokes with a dot between them.

An H-space all together

For projective modules also



Original source details: GELFAND-P000419

Diagram and typed description. The index $M \in$ Proj mod. is written on a separate line under the union sign.

$BC = \coprod K(GL(M), 1)$

$M \in$ Proj mod.

GELFAND-P000420

For the cat. of finite sets it is known that



Original source details: GELFAND-P000420

Uncertain reading. The lower index at Π is overwritten and 3-like; provisionally s, possibly 3. The upper k is read separately.

$K_C^{-k}(Y) = \Pi_s^k(Y)$

(stable cohomotopy groups.)



Original source details: GELFAND-P000420

Diagram and typed description. Two lines of arrows. Above the upper arrow are two separate horizontal strokes with a small mark between them. Beneath the left category are four separate small marks, a brace with a gap in its right half and the caption k; the lower arrow leads to R^k.

$C = \{\text{finite sets}\} \longrightarrow \{R\text{-modules}\} = \mathcal{R}$

$k \longrightarrow R^k$



Original source details: GELFAND-P000420

Uncertain reading. After the equality is a florid R-like letter with large left and upper loops; provisionally $\mathcal{R}$, with the precise font and overlapping strokes undetermined.

$$\Pi_s^k(Y) \longrightarrow K(R)^k(Y).$$

Y a point $\Rightarrow$ or stable homot. groups of spheres. One obtains their

Original source details: GELFAND-P000420

Undeciphered passage. Before "homom." an earlier separate word is densely crossed out and not fully recovered.

homom. into the K-functor of any ring. $R = F_p$, Y a point (p prime).



Original source details: GELFAND-P000420

Uncertain reading. Between $K(R)^kY$ and "image" is a small dense sign with two widened parts and a connecting stroke; its exact reading is undetermined.

$K(R)^kY$ ⊃ image of the j-homomorphism



Uncertain reading. Before "-homomorphism" is a letter with a lower loop and a separate upper dot, provisionally j; the case j/J is undetermined.

Original source details: GELFAND-P000420

Next time — cobordisms. (in the same exposition).

Vasershtein. (for Povzner[?]).



Uncertain reading. The first join after "П" (P) merges; "Повзнера" (Povzner) and "Певзнера" (Pevzner) remain candidates.

Original source details: GELFAND-P000420



Original source details: GELFAND-P000420

Undeciphered passage. An earlier beginning and a line with K_1, K_0 and the words “new operation” are crossed out. The initial E-like fragment is provisionally rendered “E…”; the whole earlier assertion is unrecovered.

~~E…~~

~~K_1 — K_0 … new operation~~

Simpl. scheme — a set with marked simplices (finite subsets) (together with $\forall$ set all its subsets are included). A topol. space is assigned to it. (see Godeman) homot. groups can be defined combinatorially.

A any ring; (noncommut.)



Original source details: GELFAND-P000420

Diagram and typed description. Above “finite” is a short curved stroke; the parenthetical caption is placed beneath the line.

MA — finite matrices. ($\forall$ finite order.)

(analogue of compact oper.)

ℓA — row-finite (in $\forall$ row and col. a finite number of elements $\neq 0$) (analogue of bounded oper.) $\mu A = \ell A / MA$ — the ring of Fredholm oper. $K_i A$. $GL(A)$ —



Original source details: GELFAND-P000420

Undeciphered passage. The earlier definition is crossed out; the beginning “invert…” and the final MA are visible, while the middle phrase is unrecovered. A faint oblique stroke descends from the middle part.

~~invert … MA~~

Original source details: GELFAND-P000420

Diagram and typed description. At the right is a new inscription with $1 + MA$ doubly underlined.

invertible elem. of the form $\underline{\underline{1 + MA}}$

A simplex — a finite subset in upper triang. matrices λ and

GELFAND-P000421

[source number: 57]

any conjugate of it (suffices by means of permutations) $a_1, \ldots, a_n$ — simpl., if $\exists f, g$ — invertible: fa_ig — upper triang. (with 1 on the diagonal).



Original source details: GELFAND-P000421

Diagram and typed description. A small matrix schematic: three 1-like diagonal entries, an upper-right star, short diagonal strokes and a lower-left $C/0$-like sign open on the right. The full size and lower-left sign are undetermined.





Original source details: GELFAND-P000421

Diagram and typed description. The formula is inside a three-sided enclosure with no top side.

$$K_iA = \pi_{i-1}GL(A)$$



Original source details: GELFAND-P000421

Diagram and typed description. At the right are two vertical rules, two lines of a marginal note, a separate short oblique stroke lower down at the left and a wavy underline beneath “see Volodin.”.

Suffices to take conj. symmetric[?]
and integral matrices.

see Volodin.



Original source details: GELFAND-P000421

Uncertain reading. The adjective before “and” is provisionally “symmetric”; “singular” remains a candidate, and the joined middle is not confidently read.

Original source details: GELFAND-P000421

Undeciphered passage. Before “integral matrices.” a short word is densely crossed out and not fully recovered.

Exercise:

Original source details: GELFAND-P000421

Uncertain reading. find the arrows. The second word is provisional: its middle letters merge.

Theorem.

Original source details: GELFAND-P000421

Diagram and typed description. The formula and final period are inside the frame.

$$K_i A = K_{i+1} \mu A.$$

In particular,



Original source details: GELFAND-P000421

Diagram and typed description. The formula is framed; the explanations are outside at the right, with separate periods.

$$K_1 \mu A = K_0 A$$

(index). (def. of index).

The theor. generalizes to a Banach ring ⇒ the usual theor. holds. Question for Quillen's K-functor.

Undeciphered passage. And th
A short unfinished beginning after the question; the continuation is unwritten.

Original source details: GELFAND-P000421

This follows from contractib. of ℓA. Sufficient is $K_i(\ell A) = 0$. Contractibility of $\ell A \Leftrightarrow$ contractib. of the complex $GL(\ell A)$. (even in the strong sense)

Original source details: GELFAND-P000421

Uncertain reading. On the left margin is a separate slanting $1/i$-like mark and a tall curved stroke; the reading and function are undetermined.



Original source details: GELFAND-P000421

Undeciphered passage. "Proof of contraction" and a following separate inscription are crossed out; the last inscription is not fully recovered.

~~Proof of contraction~~



Original source details: GELFAND-P000421

Diagram and typed description. The formula is inside a closed slightly sloping frame.

$$K_i(\text{free ring}) = 0$$

—

Original source details: GELFAND-P000421

Undeciphered passage. Before “but contractib.” is a separate short crossed inscription, not fully recovered.

but there is no contractib. of a free ring.



Original source details: GELFAND-P000421

Diagram and typed description. The arrow chain has a two-line caption below L. Its last round sign is open on the right.

$$0 \longrightarrow L' \longrightarrow L \longrightarrow A \longrightarrow C$$

free
ring.

Uncertain reading. The final sign after the arrow from A has an open right edge; $0/C$ remain candidates. Its contour is rendered without selecting a value.

Original source details: GELFAND-P000421

Original source details: GELFAND-P000421

Diagram and typed description. The formula is framed; the parenthetical explanation is at the right.

$K_i A = K_{i-1} L'$ (shift in the other direction)

There is a long exact seq. (everything follows from it) Hence follows a connection with the K-functors of Swan and Gershtein. (K_0, K_1 coincide, and further inductively).



Original source details: GELFAND-P000421

Diagram and typed description. The whole line is enclosed by a bottom rule with short vertical ends; there is no top side.

K_i with negative i occurs in Bass — also coincide.

Original source details: GELFAND-P000421

Undeciphered passage. A separate densely crossed beginning of the final line, not fully recovered.

For regular rings all $K_i = 0$ with $i < 0$.

GELFAND-P000422

Karoubi's theor.: $i > 0$ differs from Bass No zero divisors — Karoubi also coincide Quillen's theor.:

Original source details: GELFAND-P000422

Undeciphered passage. After the heading and before G is a separate densely crossed earlier fragment, not fully recovered.



Original source details: GELFAND-P000422

Uncertain reading. After $E(A)$ are two horizontal strokes, with an oblique stroke descending from the lower one. An overwritten equality and a remnant of an earlier $\neq$ are possible; the sign is rendered as strokes without a choice.

$G = GL(A), \quad E = E(A) \quad [E,E] = [G,G].$



Original source details: GELFAND-P000422

Diagram and typed description. I and two numbered marks. The upper arrow leads from BG to BG^+; beneath it is the map on π_1. From "2)" a separate arrow points to the words about homology isomorphism; the last word is underlined.

I. $BG \longrightarrow BG^+$ (Quillen's constr.) and an isom. on all homology.

1) on π_1: $G \longrightarrow G/E$ 2)

(universal in this sense!).

II. ∃ such a BG^+, which is an H-space and universal, i.e. for ∀ other map into an H-space



Original source details: GELFAND-P000422

Diagram and typed description. Three arrows: $BG \to X$, $BG \to BG^+$ and from the lower BG^+ up to X.



(Morava: and even without H-spaces,if it induces an isom.

Original source details: GELFAND-P000422

Undeciphered passage. Before “of homology” a short earlier word is crossed out and not fully recovered.

~~[illegible]~~

of homology)

Рассмотрим теперь $GL(\mu A)$

Original source details: GELFAND-P000422

Diagram and typed description. Beneath the line are two separate horizontal strokes and a small separate dot between them.

Consider now $GL(\mu A)$

Quillen’s constr.: $K_i^Q A = \pi_i BG^+$, $i \geq 1$. Theorem: $K_i A = K_i^Q A$.

$K_i^Q A = K_i^{S, G, Bol_1, Bol_2, Bac}$

Original source details: GELFAND-P000422

Diagram and typed description. After the equality is just one K_i with the upper list S, G,“Vol” with lower $1, 2$ and “Vas”; the S is dense. No additional A is written on the right.

$K_i^Q A = K_i^{\mathbf{S},G,\mathrm{Vol}_1,\mathrm{Vol}_2,\mathrm{Vas}}$

Proof.



Original source details: GELFAND-P000422

Diagram and typed description. The five nodes with BGL and the lower BG^{+} are provisional: the initial B s are heavily blackened and the upper-left ℓ is overwritten; earlier signs are unrecovered. All six arrows, the $GL(MA)$ action, captions and two exclamation marks are retained. At the upper right the bar covers $BGL(\ell A)$, at the middle right only the numerator, and at the bottom the whole quotient.



GELFAND-P000423

[source number: 58]

Assertion:



Original source details: GELFAND-P000423

Undeciphered passage. Above $GL(\mu A)$ is an earlier short crossed inscription; separate loops are visible, but it is not fully recovered.





Original source details: GELFAND-P000423

Diagram and typed description. After $\oplus$ are three separate marks: a dot, a short horizontal stroke, a dot.

$GL(\mu A) = K_0 A \oplus \quad . \; - \; .$



Original source details: GELFAND-P000423

Diagram and typed description. Two inscriptions with oblique quotient strokes. In the first, the upper bar covers only $GL(\ell A)$, and $G = GL(MA)$ is written beneath. In the second, the bar covers the entire quotient.

$$BG = \overline{GL(\ell A)} \,/\, G = GL(MA)$$

$$BG^{+} = \overline{GL(\ell A) \,/\, GL(MA)}$$



Original source details: GELFAND-P000423

Uncertain reading. At the right is a frame with no right side. The small overwritten mark before "component" has two horizontal and crossing strokes with a separate 1-like inscription; its meaning is undetermined.

simpl. scheme

$GL(\ell A)/GL(MA)$ — component of the identity in $\overline{GL(\mu A)}$.



Original source details: GELFAND-P000423

Diagram and typed description. The heading is outside the sloping closed frame; the formula is inside.

Theorem

$$K_i A = \pi_i GL(\mu A)$$



Original source details: GELFAND-P000423

Uncertain reading. Inside the frame is the upper equality; beneath $GL(MA)$ are a bracket and two short vertical strokes, with $GL(A)$ below. The link's meaning and scope of H_i are undetermined. Separate captions at the right and below have leader strokes.





Original source details: GELFAND-P000423

Diagram and typed description. A long slightly curved transverse rule.



Original source details: GELFAND-P000423

Diagram and typed description. The date has rules above and below III; at the left is an underlined name, and below it a doubly underlined heading.

20/III.

Gelfand.

Quillen's theor.

(proved nonelementarily) F_q — a finite field; $K_i(F_q)$ — ?

$$K_0(F_q) = \mathbb{Z},$$
$$K_1(F_q) = F_q^*.$$

It is easy to show that $K_2(F_q) = 0$.

Original source details: GELFAND-P000423

Undeciphered passage. After the equality to zero is a separate small crossed inscription, not fully recovered.



Original source details: GELFAND-P000423

Uncertain reading. The first index is provisionally $2i+1$: $2i$, a dense $+$ and 1 are visible, but an earlier overwritten layer is unrecovered. The range $i = 1, 2, \ldots$ is retained.

$$K_{2i+1}(\overline{F}_q) = \overline{F}_q^*, \quad K_{2i}(\overline{F}_q) = 0, \quad i = 1, 2, \ldots.$$

$\overline{F}_q$ — the (alg.) closure of the field F_q. (like the periodicity theor.)

$$K_{2i}(F_q) = 0,$$



Original source details: GELFAND-P000423

Uncertain reading. Between $2i$ and 1 is a dense overwritten mark, rendered by its contour; $+$ and $-$ remain candidates.

$K_{2i \bullet 1}(F_q) =$ $F^*_{q\ i}$, $i = 1, 2, \ldots$.



Uncertain reading. At the right of F is a lower q, a small i above and to its right, and an upper star. A candidate is $F^*_{q^i}$; the exact two-level placement remains uncertain.

Original source details: GELFAND-P000423

GELFAND-P000424

As i increases, the K-functor approaches elementary K in



Uncertain reading. The final word:“замке” (lock/castle) / “записи” (notation); the joined middle strokes remain ambiguous.

Original source details: GELFAND-P000424

Uses the Frobenius automorphism. Kazhdan: Proof. Consider

Original source details: GELFAND-P000424

Uncertain reading. The first lower index at G is overwritten; provisionally n, with the earlier sign unrecovered.

$GL(n, F_q) = G_n$

and its classifying space $\underline{K(G_n,1)}$. $GL(n,F_q) \supset SL(n,F_q) = G_n^0$.



Original source details: GELFAND-P000424

Diagram and typed description. After the inclusion is a separate dash; the next line begins with a dash and ends with an equality, with another equality at the start of the bottom line.

$$K(G_n,1) \subset B_n —$$

— «Quillenization» $K(G_n,1)$ has homot. groups $=$

$=$ the K-functors of the ring.

Aim: make the fund. group commutative, without changing homology groups. We fill in the commutator subgroup and the resulting 2-dimensional cycles. One can restrict to attaching 3-cycles.

$\underline{\underline{\text{Fuchs. Existence theor.}}}$ X — a cell complex,



Original source details: GELFAND-P000424

Diagram and typed description. On the right, the outer first argument is $\pi_1(X)$ and the second argument is the inner commutator; all brackets are retained.

$$[\pi_1(X),\pi_1(X)] = [\pi_1(X),[\pi_1(X),\pi_1(X)]]$$

This condition is necessary and sufficient for the existence of



Original source details: GELFAND-P000424

Diagram and typed description. Above Y is the inserted “cell.” in a curved contour with a pointed lower end.



and a map $f : X \longrightarrow Y$, an isom. of all homology and



Original source details: GELFAND-P000424

Diagram and typed description. At the right is condition1), a rightward arrow with a wavy stroke above it. At the left is an angular bend and below a long rule; there are no right side or upper side above the formula.

$$1)\ f_* : H_*(X, \mathbb{Z}) \xrightarrow{\sim} H_*(Y, \mathbb{Z})$$

in Y

Original source details: GELFAND-P000424

Undeciphered passage. Before “2)” a short earlier inscription is crossed out and not fully recovered.

2) $\pi_1(Y)$ is commutative. Hence $\pi_1(Y)$ is computed, namely



Original source details: GELFAND-P000424

Diagram and typed description. The formula has an oblique quotient stroke: the numerator is higher at the left, and the commutator lower at the right.

$$\pi_1(Y) = \pi_1(X) \,/\, [\pi_1(X), \pi_1(X)].$$

This is an existence theorem. Such a Y is not unique. (E.g., when $\pi_1(X)$ is commutative.) 2a) let Y be simple (the fund. group acts on $\pi_n(Y)$ trivially) Such a Y is unique ($\Rightarrow$ commutative fund. group, since π_1 acts on itself by conj.) — Whitehead’s theor.. It is known that H-spaces are simple.

GELFAND-P000425

[source number: 59]

Kazhdan — B_n — H-space. (but this is for this G, not for every G).

$$K_i(G_n) = \pi_i(B_n).$$

Quillen found a topological realization for B_n.

Consider the category // of topological spaces of cell complexes, $X \longrightarrow K^0(X) = [X, BU]$. \ quotient by trivial



Original source details: GELFAND-P000425

Diagram and typed description. Two slanting strokes before the inserted lines; a slanting stroke leads to the annotation under the formula.

Define the Adams operations on the functor $K(X)$.

On U_n consider the function: $u \longmapsto$ eigenvalues $\lambda_1, \ldots, \lambda_n$.

Original source details: GELFAND-P000425

Uncertain reading. The short sign between the arrow and “eigenvalues” is crossed out; the underlying letter is illegible.

$$\widetilde{\psi}^k(u) = \sum_{i=1}^{n} \lambda_i^k(u)$$

— the character of a virtual representation (difference of characters).



Original source details: GELFAND-P000425

Uncertain reading. Crossed-out subscript beneath the tilded ψ^k; the original index is illegible.



Original source details: GELFAND-P000425

Uncertain reading. The subscript of λ is a dot above a short curved stroke: i or j. The sum limit $i = 1$ is legible.

This representation $\widehat{\psi}^k$: Sp $\widehat{\psi}^k = \widetilde{\psi}^k(u)$.

Construct, for $\forall$ bundle, another with a U action, using the representation $\widehat{\psi}^k$. This is an operation in the K-functor: $\psi^k(d^\dagger)$.

$$\exists \text{ a map } \psi^k : BU \longrightarrow BU,$$

inducing the Adams operation in K. $d^\dagger \in [X, BU]$,

Original source details: GELFAND-P000425

Undeciphered passage. The crossed-out writing after $[X, BU]$ has a ψ-like beginning and a rounded stroke near the end; the remainder is illegible.

$$(\psi^k - 1) : BU \longrightarrow BU.$$



Original source details: GELFAND-P000425

Uncertain reading. The horizontal stroke before 1 has been retraced; the lower stroke merges into it. Reading: $-$ or $=$.





Original source details: GELFAND-P000425

Undeciphered passage. Under the insertion "turns into", the crossed-out fragment before "bundle" is illegible.



Original source details: GELFAND-P000425

Diagram and typed description. Two BU labels and a down arrow. At left $\psi^k - 1$; at right $E\psi^k$ with no separate arrow. A crossed-out mark is at the left of the upper BU.

$$\begin{array}{ccc} & BU & \\ \psi^k - 1 & \downarrow & E\psi^k \\ & BU & \end{array}$$

$E\psi^k$ — fiber of the map $\psi^k - 1$.

Claim: $E\psi^q = B_n = B$ for large n.



Original source details: GELFAND-P000425

Uncertain reading. The exponent on $E\psi$ has been retraced: k or q. The equality is underlined twice.

Frobenius automorphism $\sim$ Adams operation in topology.

Another def.

Original source details: GELFAND-P000425

Uncertain reading. A looped mark above the line: “e” (the end of the Russian abbreviation) or a separate k.

Let $[K(X)]^k \subset K^0(X)$,

$$[K(X)]^k = \{d^\dagger \in K^0(X) \mid \psi^k d^\dagger = d^\dagger\}.$$

Original source details: GELFAND-P000425

Uncertain reading. Crossed-out sign after ψ^k; the original reading is undetermined.



Original source details: GELFAND-P000425

Uncertain reading. † In every occurrence on this frame, d is provisional; α is also possible.

it is representable and

$$[K(X)]^k = [X, E\psi^k]$$

easy to check.

GELFAND-P000426

$K(G,1) \subset B$. Identify B with $E\psi^q$.

Uncertain reading. Crossed-out traces of $[K(X)]$, a superscript (k or q), and a separate illegible sign to the right.

Original source details: GELFAND-P000426

Consider $GL(n, F_q)$ and fix a homomorphism $\mu : \overline{F}_q^* \longrightarrow C^*$.

On $GL(n, F_q)$ construct a function — the character of a representation.

$\varphi_\mu(g) = \sum \mu(\lambda_i)$, where λ_i — eigenvalues of the matrix g.

We must construct a map $K(G_n, 1) \longrightarrow E\psi^q$ or an element of $[K(G_n, 1), E\psi^q]$, i.e. an element of the K-functor of $K(G_n, 1)$, invariant under ψ^q, =



Undeciphered passage. After the invariance clause, the short crossed-out fragment is illegible.

Original source details: GELFAND-P000426

It suffices to give a representation of the group G_n (then we obtain an element of $K(K(G_n, 1))$.

From Brauer's thm. $\varphi_\mu^\dagger(g)$ character of a virtual representation,



Original source details: GELFAND-P000426

Uncertain reading. † In the outlined insertion the reading is $\varphi_\mu(g)$ or $\psi_\mu(g)$; the first letter is overlaid. A wavy line underlines "Brauer".



Undeciphered passage. The heavily crossed-out inscription below the insertion is illegible.

Original source details: GELFAND-P000426

The set λ_i^q — eigenvalues too — the same ones $\Rightarrow$ invariance.

On $E\psi^q$ there is an H-space structure $\Rightarrow$ the map extends to a map into B_n (onto the filled-in disks).

Another way: SL is generated by unipotent matrices, and these are the ones to kill $\Rightarrow$ and on them $\varphi_\mu = 1$.



Original source details: GELFAND-P000426

Diagram and typed description. The source reads $\varphi_\mu = 1$.

Homotopy groups of $E\psi^q$ from



Original source details: GELFAND-P000426

Diagram and typed description. Three arrows; the sign $\sim$ and its caption are by the descending arrow.





Original source details: GELFAND-P000426

Diagram and typed description. Two BU labels, a down arrow, and $E\psi^q$ at right without a separate connection.



For $E\psi^q$ the homology is computed, and for B_n — ?

The homology groups of $K(G_n, 1)$ are computed. (Quillen too). using étale topology (see Annals).

$$\varphi : G \longrightarrow G$$
$$\varphi(g) = g^{-1} g^\sigma$$

(σ — Frobenius automorphism).

Now write the spectral sequence of the fibration and compute. // Next time: cobordisms.



Original source details: GELFAND-P000426

Diagram and typed description. Two near-vertical slanting strokes separate the marginal note; its opening is underlined twice.

GELFAND-P000427

[source number: 60]

M. Sh. Birman. Kato's theorem.

$H - H_0 \overset{=}{} V \in \gamma_1$ (nuclear operator).

Original source details: GELFAND-P000427

Uncertain reading. Between $H - H_0$ and V are several overlapping horizontal strokes: $=$ or $\equiv$.

Original source details: GELFAND-P000427

Uncertain reading. An isolated mark below the page number 60 has two loops and a slanted cross stroke. Possibly f. Its connection to the formulas is undetermined.

Prove that the absolutely continuous parts of H and H_0 are unitarily equivalent. H, H_0 — self-adjoint.

Question (I. M. Gelfand): how can one determine from the collection of spectral types whether they can be realized so that the difference is a nuclear operator?

Spectrum in the quotient ring modulo the nuclear operators — ?

2 facts used:

1) $D_1, D_2 \in \gamma_2$; E_λ — resolution of the identity $\Rightarrow$

$$\Rightarrow \quad \frac{d}{d\lambda} D_1 E_\lambda D_2$$

exists almost everywhere and is nuclear ($\sim$ rigging theorem).

(see Gelfand, diff. formula, strongly bounded var.)

2) $D_1 R_z D_2 \longrightarrow D_1 R_{\lambda+i0} D_2$ almost everywhere in γ_2.



Uncertain reading. Each of the three marks has a loop and two upper branches. The letter may be γ or $\mathcal{J}$. The subscripts $1, 2, 2$ are legible.

Original source details: GELFAND-P000427

Operator implementing the unitary equivalence:

$$\int_{-\infty}^{\infty} \frac{d}{d\lambda}(E_\lambda(I + VR_z^0)f, g)\Big|_{z=\lambda\pm i0} d\lambda = (W_\pm f, g).$$

(V is split into 2 Hilbert–Schmidt operators.)

Next time.

27/III Kazhdan.

Artin–Mazur theorem.

If X — set over a field k. any!! From it one can construct a complex C_X



Diagram and typed description. “Any!!” is written above k, with a slanted leader.

Original source details: GELFAND-P000427

If $k = C \Rightarrow C_X = \hat{X}_C$ — completion



Diagram and typed description. A wavy line underlines “completion”.

Original source details: GELFAND-P000427

Algebraic construction. $\longrightarrow$

$\longrightarrow$ (autom. of the field k, preserving X $\overset{\text{act on}}{\rightsquigarrow}$ C_X)



Original source details: GELFAND-P000427

Undeciphered passage. Before C_X there is a crossed-out inscription whose beginning resembles “не” (“not”). The remainder is illegible. “Act on” is inserted below.

If X is defined over Q, then $\mathrm{Gal}(C \mid Q)$ acts on C_X.

Original source details: GELFAND-P000427

Uncertain reading. Before “then”, below the line, a short mark has a faint slanted continuation. It is unclear whether the continuation is part of the comma.

GELFAND-P000428

Let X — top. space.



Original source details: GELFAND-P000428

Undeciphered passage. Horizontal strokes conceal the crossed-out abbreviation. Traces resembling “мн-” or “мн-ие” remain. “Top. space.” was added in the outline above it.

Consider the functor $\| \; \overset{\text{category}}{X \longrightarrow X_i}$



Original source details: GELFAND-P000428

Diagram and typed description. Two vertical strokes precede the arrow diagram. A wavy stroke and a caption are below it.

the images of all $\pi_n(X)$ — finite groups

$\forall \underline{Y}$ consider the set $\underline{Y} \longrightarrow X_i \qquad \prod_i \mathrm{Hom}(\underline{Y}, X_i)$

and compatible $\underline{h_{\widehat{X}}(Y)}$ — a functor.

It is representable and $\widehat{X}$ — the representing object.

———— · ————

I. M. Gelfand.

Standard language.

1°. Category and functor (Grothendieck, "On some questions of hom. alg." — chapter 1).

2°. Topos (topó). + theorem on descent

Uncertain reading. "Descent" is provisional. The middle strokes of the Russian word merge.

Original source details: GELFAND-P000428

(the definition is in Manin's preface to the article by Mumford)

M. Artin — Grothendieck,

———— · ————

M. Sh. Birman. Theorem of Kato.

$\mathfrak{H}$ — Hilbert space. H, H^0 — operators, $H - H^0 \in \Upsilon_1$.



Uncertain reading. The ideal sign may be γ_1 or $\mathfrak{S}_1$. The subscript 1 is legible.

Original source details: GELFAND-P000428

$$e^{iHt}e^{-iH^0t}P^0$$

P^0 — projection onto the absolutely continuous subspace of H^0

$$\underset{t\to\pm\infty}{s\text{-}\lim} e^{iHt}e^{-iH^0t}P^0 = W_\pm$$



Diagram and typed description. The t under the limit is heavily retraced, followed by an arrow to $\pm\infty$.

Original source details: GELFAND-P000428

Then both W_+ and W_- give an isomorphism of the absolutely continuous spectra of H and H^0 (symmetry of the assumptions!)

$W_\pm H^0 = HW_\pm$ || $P^{0\mathfrak{H}}$ — domain of isometry of $W_\pm$ (on the complement it is 0),



Diagram and typed description. A horizontal bracket with two short upstrokes is below the equality.

Original source details: GELFAND-P000428



Diagram and typed description. At right, two vertical strokes and a bracket open to the right surround the isometry note.

Original source details: GELFAND-P000428

Range: does it coincide with the subspace

$P^{\mathfrak{H}}$?

Diagram and typed description. There is a bracket below the subspace symbol, with the question mark outside it.

Original source details: GELFAND-P000428



Uncertain reading. All three occurrences show a looped sign with a long lower tail. $\mathfrak{H}$, $\mathcal{H}$, and Ψ are possible readings. The shape is represented by an outline.

Original source details: GELFAND-P000428

GELFAND-P000429

[source number: 61]

Prop. The range of W_+ coincides with $P^{\mathcal{Y}} \Leftrightarrow \exists$ wave oper. W_+ with the roles of H and H_0 interchanged.

Uncertain reading. The ornamental glyph after P has several loops, including a closed lower loop. $\mathfrak{H}$, $\mathcal{H}$, and Ψ are possible readings.

Original source details: GELFAND-P000429

Hence existence $\Rightarrow$ completeness, from the symmetric relation.

$$W_\pm(H_3, H_2)W_\pm(H_2, H_1) = W_\pm(H_3, H_1).$$

Proof of thm.

$$\int_{-\infty} \frac{d}{d\lambda}\left(E_\lambda(I + VR_z^0)f, g\right)\Big|_{z=\lambda\pm i0} d\lambda = (W_\pm f, g)$$



Uncertain reading. A narrow vertical crossing-out stands after f and before the comma. The underlying sign is illegible.

Original source details: GELFAND-P000429



Original source details: GELFAND-P000429

Diagram and typed description. The integral has $-\infty$ below it. No upper limit is visible.

This is the definition of the bilinear form of this operator; One must be able to [find]: $\frac{dE_\lambda g}{d\lambda}$, and this is possible with $\frac{dDE_\lambda g}{d\lambda}$, where D — a Hilbert–Schmidt oper.

The derivative [constitutes?] directly the absolutely continuous part of the spectrum.

Uncertain reading. The word begins with two open rounded letters. A provisional literal reading is “сставляет”. Alternatives are “составляет” (constitutes) and “оставляет” (leaves).

Original source details: GELFAND-P000429

Factor V into 2 Hilbert–Schmidt oper.

Almost everywhere there exists the derivative of $(E_\lambda f, g)$

$$\frac{d(E_\lambda f, g)}{d\lambda} + \left(D_1 R^0_{\lambda + i0} f, \frac{dD^* E_\lambda g}{d\lambda} \right)$$

$V = D_\bullet D_1; \qquad D_i, D$ — Hilbert–Schmidt oper.



Original source details: GELFAND-P000429

Uncertain reading. The first subscript in the product is heavily overwritten. 2 is possible. The second factor's subscript 1 is legible.

The oper. $W_\pm$ is independent of the decomposition of V as a product.

$$R^0_z - R^0_{\bar z} = Q^*_z (R_z - R_{\bar z}) Q_z; \qquad Q_z = I + V R^0_z;$$

Further,

$$\frac{d(E^0_\lambda f, g)}{d\lambda} = \frac{d}{d\lambda} \left(E_\bullet Q_{\mu \pm i0} f, Q_{\mu \pm i0} g \right) \Big|_{\mu = \lambda}$$



Original source details: GELFAND-P000429

Uncertain reading. The overwritten subscript on E at right resembles λ; μ is possible. Both Q subscripts read $\mu \pm i0$.

GELFAND-P000430

All D — the required riggings,
see the article in “Izvestiia”, 1967.

$$\int_{-\infty}^{\sigma} \frac{d}{d\lambda}\left(E_\lambda(I+VR_z^0)f,g\right)\Big|_{z=\lambda\pm i0} d\lambda = (E_\sigma W_\pm f, g)$$

More gen. variant:

$$E(\Delta)(H-H^0)E^0(\Delta) \in \gamma_1.$$



Uncertain reading. A looped sign with subscript 1. Possible readings are γ_1 and $\mathfrak{S}_1$.

Original source details: GELFAND-P000430

$\mathcal{D}(f(H)) \dot{=} \mathcal{D}(f^c(H^0))$, f, f^0 grow at infinity.



Uncertain reading. The second f in the equality has an open, c-shaped superscript. The later f carries an oval superscript, set here as 0. A separate dot appears to the left of the equality sign.

Original source details: GELFAND-P000430

3/IV-72 Minimum.

1. Grothendieck topol. and derived functors.
2. Descent.
3. Simplic.

Uncertain reading. “Simplic.” is a provisional reading of “Симплиц.” The middle strokes run together.

Original source details: GELFAND-P000430

Exam: work through Artin's article on the relation between formal and algebraic objects.

Geronimus.



Original source details: GELFAND-P000430

Diagram and typed description. A narrow, diagonally hatched band underlines the name.

Def. Grothendieck topology. —

cat. T to each $X \ni T \overset{\text{assigns}}{\rightsquigarrow} \mathrm{Cov}_T X$ — a set,



Original source details: GELFAND-P000430

Diagram and typed description. The labelled arrow begins with a wavy stroke. It follows $X \ni T$ as written.

its elements $\{f_\alpha : X_\alpha \longrightarrow X\}$. (a family of morphisms). ($\alpha \in A$ — a set).

1) $f : Y \longrightarrow X$ an isom. in cat. T. Then $\{f : Y \longrightarrow X\}$ is a covering.

2) $\{f_\alpha : X_\alpha \longrightarrow X\} \in \mathrm{Cov}_T X$ and $\forall \alpha$ given $\{f_{\alpha\beta} : \boldsymbol{X}_{\alpha\beta} \longrightarrow X_\alpha\} \in \mathrm{Cov}_T \boldsymbol{X}_\alpha$



Original source details: GELFAND-P000430

Diagram and typed description. Two X glyphs are heavily retraced, in the last family and after Cov_T.

Then

$$\{f_\alpha \circ f_{\alpha\beta} : X_{\alpha\beta} \longrightarrow X\} \in \mathrm{Cov}_T X$$

Mumford, Matematika 13:2

3) $\{f_\alpha : X_\alpha \longrightarrow X\} \in \mathrm{Cov}_T X$, $f : U \longrightarrow X$ — arbitrary morphism.

GELFAND-P000431

[source number: 62]

Then

Original source details: GELFAND-P000431

Uncertain reading. Diagonal strokes cover a single sign. φ and 0 are possible readings.

3.1 $X_\alpha \underset{X}{\times} U$ exists (fibre prod.)

3.2 $\{p_2 : X_\alpha \underset{X}{\times} U \longrightarrow U\} \in \mathrm{Cov}_T\, U$.

Def. of fibre prod.:



Original source details: GELFAND-P000431

Diagram and typed description. The diamond has arrows p_1, p_2, f, g. The note on Z is to its right.



Z univ. — fibre prod.

T — the starting category.

Let A be a fixed abelian category (with infinite direct sums)

Presheaf: ~~a~~ contravar. functor from T to A:

$$\boldsymbol{F} : T^0 \longrightarrow A.$$

Original source details: GELFAND-P000431

Undeciphered passage. Heavy crossing-out covers a short fragment before “contravar.”



Original source details: GELFAND-P000431

Diagram and typed description. The strokes of F are reinforced. The small oval above T is set as 0.

P_T — the category of presheaves.

It is called a sheaf if $\forall$ coverings the seq.

$$0 \longrightarrow F(X) \xrightarrow{\bigoplus F(f_\alpha)} \bigoplus_\alpha F(X_\alpha) \underset{F(p_2)}{\overset{F(p_1)}{\rightrightarrows}} \bigoplus_{\alpha,\beta} F(X_\alpha \underset{X}{\times} X_\beta)$$



Original source details: GELFAND-P000431

Diagram and typed description. Two direct sums are written. The first labelled arrow reads $\bigoplus F(f_\alpha)$; the parallel arrows read $F(p_1)$ and $F(p_2)$.

S_T — the full subcat. of sheaves in the cat. of presheaves

Morphism of functors

$$F : \mathcal{C} \longrightarrow \mathcal{D} \qquad F \xrightarrow{t} G$$
$$G : C \longrightarrow \mathcal{D}$$

Original source details: GELFAND-P000431

Diagram and typed description. Two rows point to $\mathcal{D}$. At right, an arrow from F to G carries the label t.

$\alpha : C_1 \longrightarrow C_2$



Original source details: GELFAND-P000431

Uncertain reading. The inner glyph at lower right has an inward stroke resembling G. The reading $G(G_2)$ is provisional. $G(C_2)$ is also possible.

$$\begin{array}{ccc} F(C_1) & \xrightarrow{F(\alpha)} & F(C_2) \\ {\scriptstyle t(C_1)}\downarrow & & \downarrow{\scriptstyle t(C_2)} \\ G(C_1) & \xrightarrow{G(\alpha)} & G(G_2) \end{array}$$

This is a deep concept. Nontriviality: there are many different α, and exactly 2 components $t(C_i)$.

GELFAND-P000432

Hence the functors themselves form a “category”.

(up to the fact that morphisms may fail to form a set)



Original source details: GELFAND-P000432

Diagram and typed description. The crossing-out leaves a Y-like left label, a rightward arrow, and an A-like right label visible. A further looped stroke is at the right edge.

Theorem: the category S_T is abelian.



Original source details: GELFAND-P000432

Diagram and typed description. A vertical line without an arrowhead and two underlined rows are below $\mathcal{P}_T$.

$i : S_T \longrightarrow \mathcal{P}_T$ (functor).

|

cat. of presheaves

Idea of proof:

$\exists$ a functor $\# : \mathcal{P}_T \longrightarrow S_T$, adj. to i.

(associated sheaf).

Functors:

$$F : T_1 \longrightarrow T_2$$
$$G : T_2 \longrightarrow T_1$$

are called adjoint if $\forall X \in T_1$ and $\forall Y \in T_2$ a nat. isomorphism is given

$\mathrm{Hom}(X, GY) \cong \mathrm{Hom}(FX, Y)$.

isom. of 2 functors
from the product of their categories
from the cat. of sets.

Def. using a
univ. morphism from a
presheaf to a sheaf
also works



Original source details: GELFAND-P000432

Diagram and typed description. An arc and an arrow run from below each Hom expression toward the shared caption.



Original source details: GELFAND-P000432

Diagram and typed description. Both of the last two lines begin with “from” in the source. The final line is underlined.



Diagram and typed description. The note is at the right of two vertical strokes.

Original source details: GELFAND-P000432

(isom. of functors — see ch. 1 of Grothendieck).

∃ 2 morphisms of functors whose compositions are identities.



Original source details: GELFAND-P000432

Diagram and typed description. The abbreviation “isom.” is underlined and a separate stroke leads downward to the next line.

(for the proof see Artin).

GELFAND-P000433

[source number: 63]

Definition. Let T, $X \in T$, $F \in S_T$

$$H^q(T, X, F) \stackrel{\text{def}}{=} R^q i(F)(X).$$

$R^q i$ — a new functor. (also from S_T to $\mathcal{P}_T$).

~~Take its value on the object X~~



Uncertain reading. The crossed-out sentence is provisional. There are further slanting strokes and a low mark after X, possibly “, A”.

Original source details: GELFAND-P000433

Its value on F — a presheaf (i.e. also a functor)

A presheaf on X — ~~is~~

Uncertain reading. The crossed-out Russian “это” is a provisional reading.

Original source details: GELFAND-P000433



Diagram and typed description. A row of dots and small strokes follows the crossing-out.

Original source details: GELFAND-P000433

Definition.

$f : T_1 \longrightarrow T_2$ morph. of topol. $\underset{\text{def}}{\Leftrightarrow}$ covering $\longrightarrow$ cov.

$f^* : S_{T_2} \longrightarrow S_{T_1}$ (also a functor).



Original source details: GELFAND-P000433

Uncertain reading. The subscript on the right-hand T is heavily retraced. 1 and traces of 2 are possible. The shape is represented by an outline.

$$f^*F(X) = F(f(X)), \quad \text{where } X \in T_1,\ F \in S_{T_2}.$$

Easy to check that this is a sheaf.

Leray spectr. seq.

$f : T_1 \longrightarrow T_2$; $X \in T_1$; $F \in S_{T_2}$.

Then a spectr. seq. exists with second term

$$E_2^{p,q} = H^p(T_1, X, R^q f^*(F)) \Rightarrow H^*(T_2, f(X), F)$$

Let A, B, C be ab. categories

$$A \xrightarrow{F} B \xrightarrow{G} C.$$

Then (under certain cond.) there exists a spectr. seq.

$$R^pG \circ R^qF(X) \Rightarrow R^*(G \circ F)(X)$$

Leray's thm. is a special case of this situation: $\Rightarrow$

GELFAND-P000434



Uncertain reading. The crossed-out formula is provisional. Horizontal strokes obscure the middle relation.

Original source details: GELFAND-P000434

$i_{T_2} f_s^* F = f_p^* \circ i_{T_1} F$ — an identity (tautology)

Uncertain reading. The right-hand index on T is heavily retraced where it meets the bracket. 1 and 2 are possible. The left-hand T_2 is clear.

Original source details: GELFAND-P000434



Original source details: GELFAND-P000434

Diagram and typed description. The horizontal line under the equality has two raised ends. The caption is at right.

f_p^* — the same morph. on presheaves

Leray's thm. is a special case because f_p^* is exact in the cat. of presheaves.



Uncertain reading. A separate entry is heavily crossed out. φ is possible.

Original source details: GELFAND-P000434

Classifying topology.

Definition.

Let T be a Grothendieck topol.,

Uncertain reading. "Topol." is the provisional reading of a retraced Russian abbreviation. A wavy line runs below the phrase.

Original source details: GELFAND-P000434

G is a group in cat. T.

$$X \in T \rightsquigarrow h_X : T^0 \longrightarrow \text{Ens} \qquad \text{(contravar.)}$$



Original source details: GELFAND-P000434

Diagram and typed description. The first arrow starts with a wave. The oval above T is set as 0.

$$h_X(Y) = \mathrm{Hom}(Y, X).$$

Together with G there must be given a group structure on $h_G(Y)$,

functorial in Y and

$$h_G(Y_1) \overset{h_G(\alpha)}{\longrightarrow} h_G(Y_2) \qquad (\alpha : Y_2 \longrightarrow Y_1).$$



Original source details: GELFAND-P000434

Diagram and typed description. The arrow from $h_G(Y_1)$ to $h_G(Y_2)$ is labelled $h_G(\alpha)$. At right is $\alpha : Y_2 \longrightarrow Y_1$.

is a group hom.

Another def.: a collection of 3 morphisms

$$G \times G \longrightarrow G$$
$$G \longrightarrow G$$
$$e \longrightarrow G$$



Original source details: GELFAND-P000434

Diagram and typed description. Three separate unlabelled arrows point rightward, all to G.

(e — terminal object in the cat.)

related by several commut. diagr.

G acts on X if $\forall Y \in T$:

X — G-object on the left

$h_G(Y)$ acts on $h_X(Y)$.

funct. in Y



Original source details: GELFAND-P000434

Uncertain reading. Dense strokes obscure the argument of the first h and the subscript of the second. Y and X, respectively, are possible.



Original source details: GELFAND-P000434

Diagram and typed description. A stepped line runs below the formula, with the caption on the lower step.



Original source details: GELFAND-P000434

Diagram and typed description. The outline at left has a point at its lower-left end. “On the left” is in a separate outline.

TG — a new Grothendieck topol. Category —

GELFAND-P000435

[source number: 64]

— G-sets (G-objects).

$X \in T$ and on it an action of G.

Objects [...] of cat. TG — G-objects.

Undeciphered passage. The short crossed-out entry between “Objects” and “cat.” is unreadable.

Original source details: GELFAND-P000435

Morph. — commute with the action (G-morphisms).

Coverings — those cov. $\underbrace{\{f_\alpha : X_\alpha \to X\}}_{\text{in the orig. cat.}}$, which consist of G-morph.

This is the classifying topology.

[...] Classif. space: final object, if it exists.

Undeciphered passage. The first sign in the cancelled entry before “Classif. space” resembles M. Two long strokes extend below it. The full reading is unresolved.

Original source details: GELFAND-P000435

Interesting: иссл.[?] $TG \longrightarrow T$ (forgetf.).



Uncertain reading. The two curves before the last ascending stroke favour «иссл.». «исл.» and «исх.» remain possible.

Original source details: GELFAND-P000435

This is an analogue of a principal bundle (univ. гл.[?] with base the classif. space).



Uncertain reading. The circled insertion provisionally reads «гл.» (principal); «им.» is possible.

Original source details: GELFAND-P000435

Theorem. A const. sheaf is def. in the obvious way by a group A (abelian).

Aim: cohom. of TG from the cohom. of T.

For Quillen's theor. a const. sheaf is needed.



Original source details: GELFAND-P000435

Diagram and typed description. Two rules separate the note on the right. An arrow from the line "(abelian)" points down to the first row; its rightward arrow starts with a wavy stroke. Both closing lines have wavy underlines.

$X \in T \rightsquigarrow A$

morph. $\longrightarrow$ ident. map

Const. sheaf assoc.
with this presheaf

$I : TG \longrightarrow T$.

[...] The Leray spectr. seq., with some addit. restrictions, is arranged thus:

Original source details: GELFAND-P000435

Undeciphered passage. The cancelled entry before "Spectr." has a C-shaped initial curve and loops below the line. The full reading is unresolved.



Original source details: GELFAND-P000435

Diagram and typed description. Below TG is a U-shaped stroke with a middle bar, above X. A blot lies to the left of A; a short rule extends down to the two-line label. The direction of the U-shaped mark is unresolved.

$I : \quad TG \longrightarrow T$

X $\qquad$ A

const.
sheaf

Original source details: GELFAND-P000435

Undeciphered passage. Dense ink covers the entry immediately to the left of the lower A.

$$E_2^{p,q} = H^p(TG, X, A^*) \otimes H^q(T, G, A) \Rightarrow$$
$$\Rightarrow H^*(T, IX, A).$$

Original source details: GELFAND-P000435

Uncertain reading. The coefficient is provisionally typeset as A^*. An overlapping vertical stroke with crossbars is visible below the star; the order of the layers is unresolved.



Original source details: GELFAND-P000435

Diagram and typed description. The sign $\Rightarrow$ closes the first line and is repeated at the start of the next.

X — point.

$$H^p(BG) \otimes H^q(G) \Rightarrow H^*(E).$$

GELFAND-P000436

Quillen's theor.

$G = GL(n, F_q)$

Then

$$H^*\Big(G, \underset{\substack{\uparrow \\ \text{triv. module}}}{F_\ell}\Big) = S[c_1, \ldots, c_n] \otimes \Lambda[c_1', \ldots, c_n']$$



Diagram and typed description. Below the first F_ℓ is a short stroke with an upward point and the label "triv. module".

Original source details: GELFAND-P000436

$$c_i \in H^{2i}(G, F_q)$$
$$c_i' \in H^{2i-1}(G, F_\ell)$$



Diagram and typed description. The subscript of F reads q on the first line and ℓ on the second.

Original source details: GELFAND-P000436

Where does this come from?



Original source details: GELFAND-P000436

Diagram and typed description. Below the first arrow is "faithf. irred.". Two short strokes above $K(G,1)$ are below BG.

If $G \longrightarrow U$ (faithf. irred.) ; $BG \longrightarrow BU$. (BG = $K(G,1)$)

hence in the alg. cohom. of G a fin. number of generators

(this is kn.). (from the spectr. seq.)

(we have a finite number of gen.)

We need to know this map explicitly.

There is none among Lie groups!

Quillen's rem.: take matr. over the closure of the field F_q

$GL(n, F_q)$.



Original source details: GELFAND-P000436

Diagram and typed description. An arc under the right-hand term connects it to the three lines below.

$BGL(n, F_q) \longrightarrow BGL(n, \overline{F}_q)$

This must be understood prop. and then it $= BU. = BGL(n, \mathbb{C})$. (the cohom. will be the same).

Original source details: GELFAND-P000436

Uncertain reading. The separate low mark after BU and before the reinforced equals sign is set as a dot. Its function is unresolved.

Theor. of Ma[n/m]ford — coincid. of cohom.

Original source details: GELFAND-P000436

Uncertain reading. The connected middle strokes allow «Манфорда» (Manford) and «Мамфорда» (Mamford).

Grothend. theor.

Rem. of I. Bersht./Bernsht.[?]: repres. of $\overline{F}_q$ and $\mathbb{C}$ are descr. in terms of high. weights.

Original source details: GELFAND-P000436

Uncertain reading. After «И.» the joined strokes allow «Бершт.» (Bersht.) and «Берншт.» (Bernsht.).

GELFAND-P000437

[source number: 65]

1[0/8]/IV Geronimus.

Original source details: GELFAND-P000437

Uncertain reading. The second date digit is overwritten. Both 10/IV and 18/IV remain possible. There are rules below and to the right, with rules above and below IV.

Derived category.

Let A — an abelian category.

$K(A)$ — category of complexes with val. in A;

Original source details: GELFAND-P000437

Undeciphered passage. Two fragments resembling «морф» (morph.) survive the crossing-out. The slanted arrow points down and left.



$$C = \{0 \longrightarrow C_0 \xrightarrow{d_0} C_1 \xrightarrow{d_1} C_2 \xrightarrow{d_2} \dots\}$$

$$H^q(C) = \operatorname{Ker} d_q / \operatorname{Im} d_{q-1}.$$

Original source details: GELFAND-P000437

Uncertain reading. Both subscripts of d are darkened. In the denominator the sign before -1 is provisionally q.

$$D = \{0 \longrightarrow D_0 \xrightarrow{d'_0} D_1 \longrightarrow \dots\}$$

map of degree τ:



Original source details: GELFAND-P000437

Diagram and typed description. Both vertical arrows are labelled on the right. Each horizontal arrow is labelled above.

$$\begin{array}{ccccc} \cdots & C_n & \xrightarrow{d_n} & C_{n+1} & \cdots \\ & \downarrow f_n & & \downarrow f_{n+1} & \\ \cdots & D_{n+\tau} & \xrightarrow{d'_{n+\tau}} & D_{n+\tau+1} & \cdots \end{array}$$

Let f and g — 2 maps of degree τ.

They are called homotopic, if $\exists$ a map α of deg. $\tau - 1$:

$$\forall n: \quad f_n - g_n = d_n\alpha_n + \alpha_n d'_n \qquad (f - g = d\alpha + \alpha d').$$

Original source details: GELFAND-P000437

Diagram and typed description. The second α_n is more heavily retraced. Both subscripts on d and both on α read n.

Homot. maps induce the same cohom. morph..

Morphisms in $K(A)$, — morphisms of degrees τ (all) —

— direct sum — quotient by morphisms, homotopic to zero.

~~Derived~~ Category of complexes — is not abelian!



Original source details: GELFAND-P000437

Diagram and typed description. "Derived" is crossed out before "Category".

(because of homot. equival.)

Deriv. categ. for an ab. categ. A, — is the cat. $D(A)$, and

$\exists$ —: $K(A) \xrightarrow{\text{functor}} D(A)$, and $\forall$ morph. of compl. inducing a cohomology isom. is assigned an isom. in cat. $D(A)$.



Original source details: GELFAND-P000437

Diagram and typed description. "Functor" is written above the arrow. A wavy line runs below $K(A)$, the arrow and $D(A)$.

f induces a cohom. isom. $\iff$ $\bar{f}$ isom. in $D(A)$



Original source details: GELFAND-P000437

Diagram and typed description. The two-headed arrow is heavily retraced. A bar is above f.

and $D(A)$ is univ. in this sense.

Construction:

consider morphisms the same for morph. inducing cohom.

$D(A)$ is def. by 2 prop.

1) f^* isom. $\Rightarrow \bar{f}$ isom.

2) Let



Original source details: GELFAND-P000438

Diagram and typed description. A rule and caption sit below $D'(A)$. To the right of the diagonal arrow, a separate pointer from ∃ points left.



another cat. with the same prop.

$D(A)$ — deriv. category for A

one can pr. (this is a theor.) that then in $D(A)$ f^* isom. $\Leftrightarrow \bar{f}$ isom.

This is not the same as the categ. C with morph. $f \sim g$, if $f^* = g^*$.

In $D(A)$ there are more morphisms.

To maps inducing cohom. isom., inverses are added formally.

It suffices to have a map $C_1 \longrightarrow C_2$, inducing a cohom. isom. — then it is an isom.

Construction. Objects — complexes

Let C, D — complexes.

~~For...~~ [?] To an object C' associate a diagr.

Original source details: GELFAND-P000438

Undeciphered passage. An opening resembling «Для» (For) and a tall loop survive before “To an object”. Crossing strokes cover the right end.



Original source details: GELFAND-P000438

Diagram and typed description. Two arrows start at C' inside the braces. Only the upper one is labelled f.

$$\mathcal{M}_{C'} = \left\{ \begin{array}{ccc} C' & \xrightarrow{f} & C \\ & \searrow & \\ & & D \end{array} \right\}$$

morph. f^* — isomorph. — set of such diagr.

With resp. to the map C' a proj. system, indexed by objects of the category $C^{[?]}$; ...

Original source details: GELFAND-P000438

Uncertain reading. The joined strokes above C resemble an H or M. A separate prime is unresolved.

Original source details: GELFAND-P000438

Undeciphered passage. Horizontal strokes cover the entry after the category name. Separate lower loops survive.

(contravar. functor of C').

Proj. lim.it[?] of this syst. — set of maps[?] from C to D.

Original source details: GELFAND-P000438

Uncertain reading. A gap and a small dot occur before the letter д. «предел» (limit) and a contracted reading remain possible.

Original source details: GELFAND-P000438

Uncertain reading. An interrupted round stroke precedes б. «отобр.» is provisional, with «отбр.» also possible. Both are abbreviations for maps.

$$f : A \longrightarrow A'$$

Deriv. functor:

$$D(f) : D(A) \longrightarrow D(A').$$

Original source details: GELFAND-P000438

Diagram and typed description. Two separate lengthwise traces run near the right edge.

GELFAND-P000439

[source number: 66]

Ka[z/zh]dan.

Uncertain reading. The joined strokes after “Ka” allow «Каздан» (Kazdan) and «Каждан» (Kazhdan). The surname is doubly underlined.

Original source details: GELFAND-P000439

Let A — an ab. categ. with a suff. number of inj. obj.

Consider the full subcategory of inj. objects. Inj(A)

Consider there the categ. of complexes.

Categ. of compl. in Inj$(A) \cong$ the deriv. category of A.

Original source details: GELFAND-P000439

Diagram and typed description. The sign between Inj(A) and “deriv.” has a wave over two strokes.



Original source details: GELFAND-P000439

Diagram and typed description. Two long rules bound the three lines above and below. Two oblique strokes cross out the block.



Morava.

Cobordism.

M, N — manif.[?], compact[?], C^∞, $\partial M = \partial N = \varnothing$.

Uncertain reading. The abbreviation has a loop with a descender after the hyphen. «мн-зия» is provisional, with «мн-гия» also possible.

Original source details: GELFAND-P000439

Uncertain reading. The final rounded stroke favours «компактные»; «компактны» is still possible. Both readings mean “compact”.

Original source details: GELFAND-P000439

$$\dim M = \dim N = n.$$

$$M \sim N \quad \text{cobordant} \quad \Longleftrightarrow \quad \exists\, \text{manif. } W, \quad \partial W = M \cup N$$

(W comp., C^∞).

$$N_n = \{\text{set of this cl. equiv.}\}. \quad = \{\text{cobord. cl.}\}.$$

1) $N_n = \{\text{semigroup}\}$

$$[M] + [N] = [M \cup N] \qquad \text{(disjoint)}$$
$$[M] + [\varnothing] = [M].$$

In | fact

Diagram and typed description. A tall slanting rule separates “In” from “fact”.

Original source details: GELFAND-P000439

$N_n =$ group, because $[M] + [M] = [\varnothing]$

$$\partial(M \times [0,1]) = (M \times 0) \cup (M \times 1).$$

Spec. case: 1) M oriented

2) M complex

$$(M^{2n}, N^{2n}) \qquad W^{2n+1} - ?$$



Uncertain reading. After the dash, the upper part of the sign resembles a 2. There is a separate dot below. “?” is a possible reading.

Original source details: GELFAND-P000439

GELFAND-P000440

Weak compl. manif.

$(M, \xi) = \{M$ — manif.; ξ — compl. vect. bundle over $M\}$.

Undeciphered passage. Below the pair is a short stroke and a crossed-out sign with a loop. Its lettering is unresolved.

Original source details: GELFAND-P000440



Original source details: GELFAND-P000440

(T_M — tang. bundle).

k, k' — trivial real bundles.

α is fixed.

Diagram and typed description. A wavy line is below the isomorphism. At left a long curved arrow points down to the underlined condition.

($\tau(\xi)$ — real ... sous-jacent bundle).



Original source details: GELFAND-P000440

Uncertain reading. Both signs before ξ have a cross stroke and a curved stem. They are provisionally set as τ; r is possible.

Original source details: GELFAND-P000440

Undeciphered passage. A single sign after "real" is crossed out. An oblique stroke extends below it.

$[M, \xi, \alpha] \longrightarrow M$ ...

class of equiv. three objects

Original source details: GELFAND-P000440

Undeciphered passage. A short crossed-out entry remains to the right of M. Parts of loops show through the strokes.



Original source details: GELFAND-P000440

Diagram and typed description. The lower line connects two ovals. The slanted uprights are labelled ξ and η. Two of the five inner strokes reach the right upright. The third has a small loop at left. The role of the angular ends is unresolved.



S^1 — weak complex manif.

$T_{S^1} =$ triv.

Every W. c. m. is cobord. to compl. man.).

Ω_n^U — group | cobord. n-dim man. (w-compl.).

Film and conn. bundle. $\dots$ Σ.

Original source details: GELFAND-P000440

Undeciphered passage. Overlapping strokes cover a loop and diagonals before Σ. The earlier sign is unreadable.

$(W, \Sigma, \dots)$ — also W. c. m.



Original source details: GELFAND-P000440

Uncertain reading. Three separate groups of strokes follow the comma after Σ. An ellipsis remains a tentative reading.



Original source details: GELFAND-P000440

Diagram and typed description. A brace gathers two lines. Two short vertical strokes sit between the product of classes and the expression below.

$$\left.\begin{array}{l}[M] \in \Omega_m^U \\ [N] \in \Omega_n^U\end{array}\right\} \Rightarrow [M] \times [N] \in \Omega_{m+n}^U$$
$$||$$
$$[M \times N]$$

GELFAND-P000441

[source number: 67]

$$\Omega_*^U = \bigoplus_{n \geq 0} \Omega_n^U$$

This | is a graded ring.

Original source details: GELFAND-P000441

Diagram and typed description. A short vertical stroke stands between “This” and “is”. The phrase has a wavy underline.

Th. $\Omega_*^U \cong \mathbb{Z}[t_0, t_1, \dots, t_n, \dots]$.



Original source details: GELFAND-P000441

Diagram and typed description. The enclosure is open at the top.

$\deg t_i = 2i$

(Ord$[M] \neq 2$ — compl. structure!).

Ω_n^U is group

Proof: $-[M] = [M \overset{\text{opposite}}{\text{orientation}}]$.

for orient cobord.

Compl. case — something similar.

X — topological space.

$X \mapsto \Omega_n^U(X)$ — group (functor of X).

$[M, \xi, \sqrt[\alpha]{} f]$ ~~[bord...?]~~



Original source details: GELFAND-P000441

Uncertain reading. The letter above the deep insertion mark reads α. The left end of the mark hooks back. A comma sits below it.

Original source details: GELFAND-P000441

Undeciphered passage. Strokes resembling “bord” or “cobord” remain under the cancellation. The full reading is unresolved.



Original source details: GELFAND-P000441

Diagram and typed description. A short slanted stroke leads from the map notation to the caption below.

$f : M \longrightarrow X$

\ cont. map



Original source details: GELFAND-P000441

Diagram and typed description. The upper line is separated from the left oval. Both lines stop before the right oval. A separate arc from the right of N points to X, as does the middle arrow. The lower arrow labelled f stops just short of the edge of the oval X.



$\Omega_n^U(X)$ — equivalence classes
(group of Bordism of X).
$[M, \xi, \alpha, f] \sim [N, \eta, \rho, g]$



Original source details: GELFAND-P000441

Uncertain reading. The sign before g in the upper line has one loop and is provisionally read as ρ or p. β is possible. The β in the lower line has two bends.

iff ~~map [?] f and g~~ $[M, \xi, \alpha] \sim [N, \eta, \beta]$



Original source details: GELFAND-P000441

Uncertain reading. "map" and "f and g" are visible under the cancellation. The sign between them resembles $=$ or a dash.

and equiv. prolong. over W
$\bigoplus \Omega_n^U(X) = \Omega_*(X)$ — graded group (mult. abs.)
GELFAND-P000442

This is a Ω_*^U-module.

Original source details: GELFAND-P000442

Uncertain reading. A separate dark spot appears below "a". Its function is unresolved.

...

Original source details: GELFAND-P000442

Undeciphered passage. Horizontal and oblique strokes cover the short entry. The letters are unreadable.

Problem: describe Ω_*^U-module structure. (in Ω_*^U)
$\Omega_*^U = \mathbb{Z}[t_0, t_1, \ldots]$ = coordin. ring of a big affine space $\mathbb{A}$.
Module $\Omega_*^U(X)$ — sheaf over $\mathbb{A}$.



Original source details: GELFAND-P000442

Diagram and typed description. The slanting outline almost closes on the left. Inside it is $\mathbb{A}$, with a double left stroke.



graduir. ignored
$\bigoplus \Omega^U_{2n}(X)$ and $\bigoplus \Omega^U_{2n+1}(X)$ —
— from graduir. (forgets the rest)



Uncertain reading. The abbreviation in both lines reads “graduir.”.

Original source details: GELFAND-P000442

Theor. $\exists$ dens. open set in the Zar. topol. $\mathbb{A}$, such that
Morava and Quillen,
the fibre at $\forall$ point is the gr. $K^\bullet(X)$ $\big(= K^0(X) \oplus K^1(X)\big)$!!



Diagram and typed description. “Morava” and “and Quillen” appear below the heading. There are two separate lines under the names.

Original source details: GELFAND-P000442

Uncertain reading. The Russian is provisionally read as “пл.” and translated as “dens.”. The second letter more closely resembles “л” than the “н” of “мн-во” to the right.

Original source details: GELFAND-P000442

Diagram and typed description. The Russian “в” is written above the line before $\mathbb{A}$, inside a loop-shaped insertion mark.

Original source details: GELFAND-P000442

Uncertain reading. The heavily circled sign with intersecting strokes is provisionally set as $\oplus$. $\otimes$ is possible.

Original source details: GELFAND-P000442

$\mathbb{Z}[t_0, \ldots, t_n, \ldots][t_1^{-1}]$ — this is that very open set.

$t_1 = \mathbb{P}_1$ — compl. proj. bundle



Uncertain reading. A separate U-shaped mark with an inner stroke stands above $\mathbb{P}_1$. A detached rising stroke to the right may be a prime. No continuous arrow shaft is visible.

Original source details: GELFAND-P000442

R — commutative; $\Gamma(R) = \left\{ \sum_{i=1}^{\infty} a_i t^i \;\middle|\; a_i \in R \right\}$

$a_1 \in R^*$ invert.



Diagram and typed description. A short oblique stroke lies between R^* and "invert.". No separate arrowhead is visible.

Original source details: GELFAND-P000442

gr. under compos. of maps.

GELFAND-P000443

[source number: 68]

$\Gamma(R)$ — inf. dim alg. group. (compos. — polinomial)

Γ acts on A

Sheaf Ω_*^U is an equivariant sheaf (const on orbits).

Uncertain reading. There is a dark patch of ink at the left of Ω. Any earlier writing underneath is unreadable.

Original source details: GELFAND-P000443

Γ: {Rings} ⟶ {groups}.

Diagram and typed description. The arrowhead at right is clear. At left is a short lower hook whose role is unresolved.

Original source details: GELFAND-P000443

The actual theor. should consist in the descr. of the orbits.

~~Orb.[?]~~ over $\mathcal{D}$ — fibers $K^\bullet(X)$.
$\mathcal{D}_{(p,h)}$ p prime — orbits,
$1 < h < \infty$, $h \in \mathbb{Z}$.
$\mathcal{D}_\infty$ = fibers $H^*(X, \mathbb{Z})$.

orbits.

Original source details: GELFAND-P000443

Undeciphered passage. An initial loop, a tall loop and a dot show through the cancellation. “Orb.” is a provisional reading.



Original source details: GELFAND-P000443

Diagram and typed description. The strict inequality $1 < h < \infty$ is written below “p prime”. The top stroke of 1 meets the wavy underline.



Original source details: GELFAND-P000443

Diagram and typed description. Two near-vertical strokes set off the doubly underlined caption on the right.

$K(h)$ — functor $K(h)^+(X, \mathbb{Z}_p)$ — $\mathbb{Z}_p$-module.



Original source details: GELFAND-P000443

Uncertain reading. The superscript of $K(h)$ has a crossbar and one slanted stroke. It is provisionally set as $+$. $*$ is possible, though the stars in Ω^U_* and H^* show extra arms.

Bott periodicity in dim $2(p^h - 1)$

$\exists$ Adams oper. $\psi^\alpha \colon K(h)$

Original source details: GELFAND-P000443

Diagram and typed description. The arc at the right of $K(h)$ runs from the lower end to the upper end. Its arrowhead points left.

$\alpha \in$ units of p-adic division algebra of ranke h^2.

Original source details: GELFAND-P000443

Uncertain reading. The sign before $\in$ resembles the superscript of ψ. It is provisionally set as α, with λ possible. The final "e" is visible in "ranke".

This is station. subgroup of a point on the orbit.

Next time — continuation

Formal groups

Original source details: GELFAND-P000443

Uncertain reading. An angular loop, a hooked stem and a separate dot lie within the outlined shape. The glyph remains unidentified.

$\mathbb{A}$ — moduli space for 1-dimensional commut. form. groups.

F — form. gr. over a ring R, if an elem. is given $F \in R[[X, Y]]$,

Original source details: GELFAND-P000443

Uncertain reading. The inner opening mark is rounded, almost like a C. Two closing brackets are visible. The double opening bracket is provisional.

1) $F(X,Y) = F(Y,X)$; 2) $F(0,X) = X$; 3) $F(X, F(Y,Z)) = F(F(X,Y),Z)$

(the inv. exists automatically). X, Y — form. var. — letters.

GELFAND-P000444

$f \in \Gamma(R)$ $\Rightarrow$ s'

Original source details: GELFAND-P000444

Uncertain reading. A separate slanting stroke sits below the right end of the underline. The small adjacent sign and its raised stroke are provisionally read as s', with $5'$ possible.

$$f = a_1 t + a_2 t^2 + \dots$$
$$a_1 \in R^*$$

Change of var. —



Original source details: GELFAND-P000444

Diagram and typed description. A long line with raised ends encloses the formula from below.

$F^f(X,Y) = f^{-1}\big[F\big(f(X), f(Y)\big)\big).$

Uncertain reading. The slanted sign with a short lower hook after f^{-1} is provisionally set as [. Two round parentheses and a stop follow Y. No separate outer closing delimiter is visible.



Original source details: GELFAND-P000444

f acts on the set of form. groups.

R — ring $\rightsquigarrow$ {form. groups $A(R)$ — set.}

$$A\colon (\text{Rings}) \xrightarrow{\text{Functor}} (\text{Sets})$$

it is representative



Original source details: GELFAND-P000444

Diagram and typed description. The frame is open at the top. Two vertical strokes below Ω_u cross its lower line. The polynomial ring is written below them.

$A(R) \cong \mathrm{Hom}_{(\text{Rings})}(\Omega_u; R).$

$\mathbb{Z}[t_0, t_1, \dots]$

Uncertain reading. The sign after Ω is lowered in both occurrences. It is provisionally set as Ω_u. A capital U in the subscript is possible.



Original source details: GELFAND-P000444

Hom determ. by values on t_i. which form. gr.

~~$\Omega_u \longrightarrow R$[?] ...~~



Original source details: GELFAND-P000444

Undeciphered passage. At left under the cancellation are an omega-like loop and lower sign, followed by a rightward arrow-like stroke and R. The beginning may read $\Omega_u \to R$ or contain $\forall$. A C-like sign is visible farther on. The full inscription is unresolved.

$$\forall R: \qquad \Gamma(R) \times A(R) \longrightarrow A(R);$$
$$\Gamma \times \mathbb{A} \longrightarrow \mathbb{A}.$$

(Γ acts on A as an alg. gr. on an alg. set).

$$A(R) \underset{\text{def}}{=} \text{Hom}(\Omega_u, R).$$

Γ — form. substitutions

Original source details: GELFAND-P000444

Uncertain reading. The Russian is provisionally read as “подстановки”. Joined strokes between “д” and “т” obscure the reading.



Original source details: GELFAND-P000444

Diagram and typed description. Two short arrows point up from the vicinity of $\Gamma(R)$ to f and from the first $A(R)$ to F. Both long arrows point right.

f — subst. $\qquad$ F — form. group

$\Gamma(R)\times \qquad A(R) \longrightarrow A(R)$

$(f, F) \longrightarrow F^f$



Original source details: GELFAND-P000444

Uncertain reading. The caption is provisionally read as “подст.”. It has a tall medial loop, a final cross stroke and a stop. The earlier alternatives “индив.” and “модиф.” remain possible.

Original source details: GELFAND-P000444

Uncertain reading. The first lower A is heavily overwritten. The earlier strokes cannot be separated.

GELFAND-P000445

[source number: 69]

Kazhdan.



Diagram and typed description. Two vertical strokes stand between the beginning of the line with $\mathbb{Z}$ and Ω. The statement about R is to their right.

$\mathbb{Z}[t_0, t_1, \ldots]$ and form. group ... over R.
$\|$ R — ring of char. 0.
Ω.

Original source details: GELFAND-P000445

Undeciphered passage. The short cancelled inscription before "over" is undeciphered.

Original source details: GELFAND-P000445

Constr. of an inv. diff. on a form. group — uniquely determ.

$$\omega = \sum c_i x^i \, dx;$$

Map: $t_i \longrightarrow C_i \in R$.

Uncertain reading. Both variable signs are heavily overwritten. They are provisionally set as x. Their case and earlier strokes are unresolved.

Original source details: GELFAND-P000445



Uncertain reading. The coefficient in the differential is set as c_i. The taller letter in the map is set as C_i. The distinction in case is provisional.

Original source details: GELFAND-P000445

Obtain a map $\Omega \longrightarrow R$.

14/IV I. M. Gelfand.

On Dyson's talk "Unrealized possibilities".

Anecdote about a tunnel.



Diagram and typed description. The reference to an anecdote sits in the right margin beneath the title.

Original source details: GELFAND-P000445

Aim: to convince math. and phys. how much they lost by failing to listen to one another.

Example 1.

(Dyson's amusement)

$$\prod_{m=i}^{\infty}(1-x^m)^{24}=\eta^{24}(x)=\sum_{n=1}^{\infty}\tau(n)x^n \quad \text{(Ramanujan fn.)}$$



Original source details: GELFAND-P000445

Uncertain reading. The lower product index is provisionally read as $m=i$. A short stroke with a small mark above it follows the equals sign. The reading $m=1$ remains possible. No separate factor is visible before the product.

Identity:

$$\tau(n)=\sum_{\substack{a,b,c,d,e\equiv 1,2,3,4,5 \pmod 5,\\ a+b+c+d+e=0\\ a^2+b^2+c^2+d^2+e^2=10n}}\frac{(a-b)(a-c)(a-d)(a-e)(b-c)(b-d)(b-e)(c-d)(c-e)(d-e)}{1!\,2!\,3!\,4!}.$$

Original source details: GELFAND-P000445

Uncertain reading. The first letter in the penultimate parenthesis is overwritten. The factor is provisionally set as $(c-e)$.

$\eta(x)$ — Dedekind fn..

Another amateur physicist discov. an analog. fmla. $\eta^{10}(x)$.



Original source details: GELFAND-P000445

Uncertain reading. The joined writing after the underlined words is provisionally read as "откр.". The abbreviation before the power of η is provisionally read as "ф-лу".

Dyson: for $\eta^d(x)$,



Original source details: GELFAND-P000445

Diagram and typed description. Short slanted strokes lead from 3 and 8 toward the labels. A comma and a small stroke are visible after 36.

$d=$ 3, 8, 10, 14, 15, 21, 24, 26, 28, 35, 36,

3 — Jacobi

8 — Klein, Fricke

These are dimensions of simple Lie algebras.

$$\begin{array}{ccccccc} A_1 & A_2 & Sp(4) & - & - & \cdot & A_4 = SL(5) \\ 3 & 8 & 10 & - & - & \cdot & 24 \end{array}$$

Prod. — over all simple roots (pos.) of gr. $SL(5)$.

Произв. — по всем простым корням (положит.) гр. $SL(5)$

Original source details: GELFAND-P000445

Uncertain reading. The wording is “простым корням (положит.)”, rendered here as “simple roots (pos.)”.

26 — drops out — unclear

GELFAND-P000446

2. $c \to 0,\ c \to \infty,\ R \to \infty$ — lim. transitions in the kinem. group.

в кинем. группе.

Original source details: GELFAND-P000446

Uncertain reading. The last word reads “группе” (“group”). Joined strokes in the middle obscure the reading slightly.

Morava.

Kirillov (recapitulation).

$X \longrightarrow \Omega_n(X)$ — group, $\underset{[?]}{}$ $\Omega_n(*)$ — module.

Original source details: GELFAND-P000446

Uncertain reading. A separate small sign with two upper strokes is visible beneath the dash after $\Omega_n(X)$. Its reading is unresolved.

~~Triple.~~ (M, ξ, α, f)

Original source details: GELFAND-P000446

Uncertain reading. “Тройка.” (“Triple.”) is the provisional reading beneath the two cancellation strokes.

(M, ξ, α) — weakly compl. set

$$\left(\cdots \quad \underbrace{\tau(M) + [k] = \xi + [k']}_{\alpha}, \quad \xi \text{ — already a compl. bundle} \right)$$

Original source details: GELFAND-P000446

Undeciphered passage. The short sign just inside the left parenthesis is cancelled. The earlier strokes are unresolved.

α — fixed decomp..

$f\colon M \longrightarrow X$

Equiv. relation.



Original source details: GELFAND-P000446

Diagram and typed description. Three arrows point right toward the hatched region X. The upper label is provisionally g, and the label beneath the middle of the left cylinder is provisionally w. Two arrows in the separate right cylinder point inward from its ends.



Theorem. $\Omega_*(*) = \mathbb{Z}[t_1, t_2, \ldots]$

$$\deg t_i = 2i$$

$t_1 \leftrightarrow CP^1$

A — cobord. ring of a point $\Omega_*(*)$.

M — module over A $(\Omega_*(X))$.

Spec $A = \mathbb{A}$.

M determ. a sheaf over $\mathbb{A}$.

Description of M_x — ? $(x \in M)$
fiber of the sheaf

$\mathbb{A}$ has points of 3 types.



Original source details: GELFAND-P000446

Uncertain reading. The right slanting stroke is doubled in three signs. The sign before the equals sign is written more simply. The three signs are set as $\mathbb{A}$.



Original source details: GELFAND-P000446

Uncertain reading. The letter following the membership sign in the margin reads M. The heavily overwritten subscript of M_x is provisionally read as x.

GELFAND-P000447

[source number: 70]

What matters is the traj. of a point under the action of an infin. group.



Uncertain reading. The opening reads “Важна траект.”. Some joining strokes are faint.

Original source details: GELFAND-P000447

Orbits:

1) one open dense — gen. pos.
2) one closed
3) count. number of interm. orbits

Uncertain reading. The first letters of the abbreviation are overwritten. The provisional reading is “промежут.” (“interm.”).

Original source details: GELFAND-P000447

1) fiber $K(X)$. (at $\forall$ point) (open dense)
2) p, n (p — prime, n — natur.) $K^{n,p}(n)(X, \mathbb{Z}_p)$.



Diagram and typed description. A stepped bracket runs beneath “of the sp. X”.

— new char.
of the sp. X.

Original source details: GELFAND-P000447



Uncertain reading. A short inscription above (n), following K, is cancelled. It is provisionally read as n, p.

Original source details: GELFAND-P000447

3) $H^*(X, \mathbb{Z})$ at $\forall$ point.

Clarification

$$(a_1, \ldots, a_n, \ldots) \in \mathbb{A}$$

max id.

$$J = (t_1 - a_1, \ldots, t_n - a_n, \ldots)A \subset \mathbb{A}$$

M/MJ — vect. sp. (more precisely A/J — module).



Original source details: GELFAND-P000447

Diagram and typed description. “It” is written separately on the left. “Grows” is inserted beneath the cancelled “over”.

it ~~it grows~~ ~~over~~ grows the point J.

Partition $\mathbb{A}$ into pieces.



Uncertain reading. The right stroke of A is doubled after $\in$ and to the right of $\subset$. The letter in the “Partition” heading is also set as $\mathbb{A}$. The sign immediately after the closing parenthesis in the J line is plain A.

Original source details: GELFAND-P000447

~~$\mathbb{A}$ [...] one-dimension... form.~~ G — gr. of form. substitutions of variables

Undeciphered passage. Under the wavy cancellation the initial A, the stem “одномерн” (“one-dimension”), and the final “форм.” (“form.”) are visible. The reading of the horizontal stroke and the ending of the first word is unresolved.

Original source details: GELFAND-P000447



Original source details: GELFAND-P000447

Diagram and typed description. Two vertical strokes separate the W_1, W_1' entries from the substitution g. The subscript on the first a is overwritten and reads as 1.

W_1 — alg. of form. vect. fields
W_1' — dual alg. of differentials.

$g\colon x \longrightarrow$
$a_1 x + a_2 x^2 + a_3 x^3 + \dots$
$a_i \in \mathbb{Z}$ and invertible
$(a_1 = 1)$



Original source details: GELFAND-P000447

Uncertain reading. The text reads “двойств. алг. дифференциалов” (“dual alg. of differentials”). A separate stroke is visible above “й”.

Possible for $\forall$ rings. —
— in particular from A.
(a_1 — inv. el. of the ring)
Form. 1-dim. group:

$$x * y = x + y + \alpha xy + \beta x^2 y + \delta x y^2 + \dots \qquad (\alpha, \beta \in \text{the ring})$$

associativity. — sole req.
They are equiv. if one law of mult. $\longrightarrow$ the other by a form. subst. of var.

$$\varphi(x) = \lambda_1 x + \lambda_2 x^2 + \dots, \qquad \lambda_1 \text{ — inv. el. of the ring}$$



Original source details: GELFAND-P000447

Diagram and typed description. Two vertical strokes separate the right marginal note. Its abbreviation is provisionally read as “одноморф.” (“same-form”).

$F_1(x,y) = \varphi^{-1}\big(F_2(\varphi(x), \varphi(y))\big)$

These are same-form groups



Original source details: GELFAND-P000447

Uncertain reading. The coordinate sign is set as φ in all four places. A right loop is visible, especially in the lower formula. The first sign is less clear. The two overwritten coefficients are provisionally read as λ_1, λ_2.

GELFAND-P000448



Original source details: GELFAND-P000448

Diagram and typed description. A loop encloses the insertion “1-dim.”. The left arrow leads down to “Proof”.

Thm.

Over a Field of char. 0 — 1-dim. form. gr. $\sim$ addition. $\underline{x+y}$. !

Commut. follows.

Descr. by means of form. diff.

Proof. $\varphi^{-1} = \int \frac{dx}{f}$, where $\underline{f(x) = \frac{\partial F}{\partial y}(x,0)}$.

(simple check).

Outside char. 0 — the integral does not exist.

$\int x^{p-1}\,dx$ does not exist over a field of char. p.

$$\dot{\varphi}^{-1} = \int a\,dx = \int \frac{dx}{f}$$



Uncertain reading. A separate dot is visible above the left part of φ in the second occurrence. It is set as a dot above the letter. It may be a spot.

Original source details: GELFAND-P000448

$\underline{a\,dx}$ — form. diff., ~~reconstr.~~ determ. the group

Uncertain reading. The cancelled abbreviation is provisionally read as “восстан.” (“reconstr.”).

Original source details: GELFAND-P000448

$$a(x) = 1 + a_1 x + a_2 x^2 + \dots$$

Action of the group (in diff.)

$$a(x) \longrightarrow a(\varphi(x))\varphi'(x)$$



Uncertain reading. Both signs have a right loop. They are set as φ and φ'.

Original source details: GELFAND-P000448

$a(x)$ — any series. To it corresp. a form. group (theorem on existence of the univ. group) Morava.



Original source details: GELFAND-P000448

Diagram and typed description. The labels under a_1 and a_2 are in square brackets. The letter C has an additional stroke inside.

$$a(x) = 1 + \underset{[\mathbb{C}P(1)]}{a_1}\, x + \underset{[\mathbb{C}P(2)]}{a_2}\, x^2 + \dots$$

— Kirillov's prop.

(Mishchenko's thm. — … here one obtains $\mathbb{C}P(n)$).

Undeciphered passage. The short inscription after the dash is heavily cancelled. The letters cannot be separated.

Original source details: GELFAND-P000448

Theorem, G — gr. scheme. $X_{[?]}$ — G-scheme (over $\mathbb{Z}$).

Uncertain reading. A single slanting stroke follows "Theorem". It is provisionally set as a comma.

Original source details: GELFAND-P000448

Uncertain reading. A small looped mark and an adjacent stroke appear below and to the right of X. The reading is unresolved.

Original source details: GELFAND-P000448

Let X be smooth, G be flat and all be Noetherian

Uncertain reading. Two diagonal strokes overwrite the sign before "smooth". It is provisionally set as X. The earlier loop-like stroke cannot be separated from the overwriting.

Original source details: GELFAND-P000448

… K — (alg. closed field) and $G(K)$ acts transitively on $X(K)$



Uncertain reading. A separate sign with two slanting sides is heavily cancelled before K. One possible reading is $\forall$.

Original source details: GELFAND-P000448

Original source details: GELFAND-P000448

Uncertain reading. The letters in parentheses after G and X are smaller than the standalone K, but have a similar angular form. They are provisionally set as K.

GELFAND-P000449

[source number: 71]



Original source details: GELFAND-P000449

Diagram and typed description. A short slanted stroke links S to its label.

$\exists\ S \subset G \qquad X \cong G/S$

subgr.

(stabiliz.)

Original source details: GELFAND-P000449

Diagram and typed description. Ten dots form a separator.

. . . . . .

GELFAND-P000450

25/IX-72 yr. Gabrielov.

Fam. of Hodge structures over S (nonsingular analyt. set)



Original source details: GELFAND-P000450

Uncertain reading. Two rounded strokes are joined after “б”. The reading is “неособое” (“nonsingular”).

1) $\mathcal{H}_{\mathbb{Z}}$ — loc. free sheaf of $\mathbb{Z}$-modules of fin. type.

~~2)~~ From it constr. a loc. triv. compl. bundle $H_{\mathbb{C}}$.

Original source details: GELFAND-P000450

Uncertain reading. The cancelled beginning of the line is provisionally read as “2)”.



Original source details: GELFAND-P000450

Diagram and typed description. An arrow from the complex scalar extension points to the note. The lower line of the note turns up at its left end.

$H_{\mathbb{C}} = H_{\mathbb{Z}} \otimes_{\mathbb{Z}} \mathbb{C}, \quad H_{\mathcal{O}} = H_{\mathbb{Z}} \otimes_{\mathbb{Z}} \mathcal{O}_S.$

and $H_{\mathbb{R}}$ — real bundle. loc. system (Deligne) —

— bundle with connection.

2) in $H_{\mathbb{C}}$ a decreasing filtration by holom. bundles

$$H_{\mathbb{C}} = F^0 \supset F^1 \supset \ldots \supset F^n$$

Original source details: GELFAND-P000450

Diagram and typed description. A loop encloses the inserted “есть” (“there is”).

3) in $H_{\mathcal{O}}$ (there is) nat. connection (Gauss–Manin)



Original source details: GELFAND-P000450

Uncertain reading. The middle letters of the first name are joined. The pair is read as “Гаусса—Манина” (“Gauss–Manin”).



Original source details: GELFAND-P000450

Diagram and typed description. The note on the kernel is to the right of the formula. The mark before the dash is provisionally a comma.

$\nabla\colon H_{\mathcal{O}} \longrightarrow \Omega^1 \otimes_{\mathcal{O}_S} H_{\mathcal{O}}$ (diff. oper. with kernel, — sect. of $H_{\mathbb{C}}$).

(there are loc. const. sections $\mathbb{Z}$ — image of the sheaf $H_{\mathbb{C}}$)



Original source details: GELFAND-P000450

Uncertain reading. The sign between “sections” and the dash is provisionally read as $\mathbb{Z}$. It has a loop and a long lower stroke. The exact reading is unresolved.

The connection must satisfy the cond.:

$$\nabla(\mathcal{F}^p) \subset \Omega^1_S \otimes \mathcal{F}^{p-1} \qquad (\mathcal{F}^p = F^p \otimes_{\mathbb{C}} \mathcal{O}_S)$$

4) ψ — bilin., loc. const. form on $H_{\mathbb{C}}$, giving on restriction to $\forall$ fiber a genuine Hodge struct.

———— • ————

Classifying sp. of Hodge structures.
Consid.

———— • ————

$$F = \{F^0 \supset F^1 \supset \ldots \supset F^n\} \qquad \text{— flags of fixed dim.}$$

in a fixed sp., $\mathbb{C}^n$ (dim can have gaps).

———— • ————



Original source details: GELFAND-P000450

Diagram and typed description. Two vertical strokes separate the right marginal note.

list of dim —
— is given.

D — sp.;
Points of the sp. ~~D~~ — flags.



Original source details: GELFAND-P000450

Uncertain reading. The heavily overwritten sign before the dash resembles D. The reading of the cancelled letter is provisional.

Take a lin. sp. $H_{\mathbb{C}}$ with a bilin. form $\psi(x, y)$ (nondeg.; skew or symm.)



Original source details: GELFAND-P000450

Diagram and typed description. Two lines under $H_{\mathbb{C}}$ sit below its lowered subscript.

$\bar{D}$ — set of all flags ~~in~~ in $H_{\mathbb{C}}$ with a fixed list of dim

Original source details: GELFAND-P000450

Uncertain reading. A separate stroke is visible above the heavily retraced D.

Original source details: GELFAND-P000450

Uncertain reading. The small cancelled sign before “в” (“in”) is provisionally read as a repeated “в”.

GELFAND-P000451

[source number: 72]

... with condition 1) $\psi(F^p, F^{n-p}) = 0$.

Original source details: GELFAND-P000451

Undeciphered passage. The short cancelled sign before “with” is undeciphered.



Original source details: GELFAND-P000451

Uncertain reading. The first formula clearly reads $n - p$. The next formula separately reads $n - p + 1$.

This is an algebraic subs. $\bar{D}$.

ψ either symm. or skew-symmetric (def).

$$2) \quad F^p \oplus \bar{F}^{n-p+1} \cong H_{\mathbb{C}}$$



Original source details: GELFAND-P000451

Uncertain reading. The sign before $H_{\mathbb{C}}$ has a wave above two horizontal strokes. A slanted mark joins the lower strokes. The reading $\cong$ is provisional. The letter H is heavily retraced.

$H_{\mathbb{Z}} \subset H_{\mathbb{R}} \subset H_{\mathbb{C}}$ also given

The nondeg. flag determ. the grading and the Weil autom.

$$H^{p,n-p} = F^p \cap \bar{F}^{n-p}$$

Weil autom.:

$$C\xi = i^{2p-n}\xi \quad \text{when } \xi \in H^{p,n-p}$$

These conds. pick out in $\bar{D}$ the open subs. D.

... Another condition: $\psi(x, C\bar{x}) > 0$ when $x \neq 0$.



Original source details: GELFAND-P000451

Undeciphered passage. Several horizontal strokes cover the earlier writing before “Another condition”. The ending has a loop and a stop. The text is unresolved.

Define on D the structure of a homog. sp..

G — group of all real transf. of $H_{\mathbb{R}}$, preserv. ψ

$$\big(\psi(gx, gy) = \psi(x, y)\big).$$



Original source details: GELFAND-P000451

Uncertain reading. The left outer parenthesis is heavily retraced. Two round closing parentheses are distinguishable on the right.

Then G acts on D



Original source details: GELFAND-P000451

Diagram and typed description. Before G is a short inscription provisionally read as “яв.” (“expl.”) and a heavily retraced sign. A 1 is inserted in the loop above it. The beginning of the line provisionally reads 1).

Theorem: 1) expl. ...$\overset{1}{\bigcirc}$$G$ acts transitively

2) stab. Subgroup H (preserv. the flag) is compact.

Proof: from explicit computation of G and H.

$K \subset G$ — max. comp. subgroup

$G/H \longrightarrow G/K$ it is not holomorphic

In G/K there is a compl. structure

GELFAND-P000452

Original source details: GELFAND-P000452

Undeciphered passage. Closely spaced wavy strokes cover the underlined heading. A stop is visible to the right. The letters are unresolved.

Manin’s 1st lecture on p-adic numbers. (retelling)

K — loc. field, (...

Original source details: GELFAND-P000452

Undeciphered passage. After the comma are a left parenthesis and a short, heavily cancelled inscription. The right parenthesis in this line is unclear.

(fin. ext. of the p-adic numbers) ~~or form. pow. series over a fin. field~~)



Original source details: GELFAND-P000452

Undeciphered passage. The cancelled lines are provisionally read as “or form. pow. series over” and “a fin. field”. The closing parenthesis near “adic numbers” is heavily retraced.



Original source details: GELFAND-P000452

Diagram and typed description. A short vertical stroke connects m with the label below.
A — ring of integers, $m \subset A$
max. ideal

$P^1(K)$ — proj. line.

$$G = \text{its motions} \quad \left\{ z \longrightarrow \frac{az+b}{cz+d} \;\middle|\; a,b,c,d \in K,\ \det \neq 0 \right\} =$$
$$= \mathrm{GL}(2,K)/K^*$$



Original source details: GELFAND-P000452

Uncertain reading. The notation before the right brace reads det $\neq 0$. The sign is heavily retraced. Two horizontal strokes immediately after the brace read as $=$. The next line also starts with $=$.

$U \subset G$; $U = \mathrm{GL}(2,A)/A^*$.

Constr. G/U — graph Δ — analog of the Lobachevsky pl..

Def.: a lattice in K^2 — a free A-module with 2 gen.

$$L = Ae_1 \oplus Ae_2.$$

Lemma. If L_1 and L_2 — 2 latt., then $\exists$ a basis e_1, e_2 in K^2, such that

$$L_1 = Ae_1 \oplus Ae_2; \qquad L_2 = m^{\nu_1} e_1 \oplus m^{\nu_2} e_2 =$$
$$= A\pi^{\nu_1} e_1 \oplus A\pi^{\nu_2} e_2$$

(π — generator [?] of the max. ideal)



Original source details: GELFAND-P000452

Uncertain reading. A looped mark with a lengthwise stroke stands between “generator” and “max.” in the Russian. Its reading is unresolved.



Original source details: GELFAND-P000452

Diagram and typed description. The inscription $\nu_1, \nu_2 \in \mathbb{Z}$ sits at the right between the two parenthetical lines.

(analog. to the lin. alg. theor. on simult. reduction) $\nu_1, \nu_2 \in \mathbb{Z}$

Def. $L_1 \sim L_2$, if $L_1 = \alpha L_2$, where $\alpha \in K^*$.

There is an analog of distance — as in symm. sp.. ... — see A. Weil

Undeciphered passage. The small sign before the dash is cancelled. Its reading is unresolved.

Original source details: GELFAND-P000452

Vertices of graph $\Delta^{(0)}$ — equiv. classes of lattices

Undeciphered passage. A small cancelled sign appears below and to the right of the first Δ. Its reading is unresolved. Above it is (0).

Original source details: GELFAND-P000452

G acts on $\Delta^{(0)}$.

GELFAND-P000453

[source number: 73]



Diagram and typed description. The arrow by $\Delta^{(0)}$ points down and left toward the first entry.

$\Delta^{(0)}$

$\swarrow$

$\Lambda_1 = \{L_1\}, \quad \Lambda_2 = \{L_2\}$ — classes of lattices.

Original source details: GELFAND-P000453



Diagram and typed description. The frame under $L_2 \subset L_1$ is open at the top. Two vertical strokes set off the residue field on the right. The left stroke of F is doubled.

$L_2 \subset L_1 \quad \| \quad A/m = k = \mathbb{F}_q$

Original source details: GELFAND-P000453

$$L_1 = Ae_1 \oplus Ae_2$$
$$L_2 = Ae_1 \oplus A\pi^\nu e_2$$

— thus choose the representatives, $\nu > 0$.



Uncertain reading. The end of the last word is faint. The reading is “представители” (“representatives”).

Original source details: GELFAND-P000453

ν is called distance $\underline{\underline{\nu = d(\Lambda_1, \Lambda_2).}}$



Diagram and typed description. Three strokes frame the formula below and at the sides. The inscription after the equals sign is heavily cancelled. Its reading is unresolved.

$L_1/L_2 = \dots A/m^\nu$

Original source details: GELFAND-P000453

Thm. This is a corr. def. and is a distance.

Variant:

$$L_1/L_2 \simeq A/\pi^{\nu_1}A \oplus A/\pi^{\nu_2}A$$



Uncertain reading. A single straight stroke lies under the wave. It is set as $\simeq$.

Original source details: GELFAND-P000453

$$d(\Lambda_1, \Lambda_2) = |\nu_1 - \nu_2|$$

Λ_1, Λ_2 — neighbors in Λ^0, if $d(\Lambda', \Lambda^2) = 1$.

Uncertain reading. The set has a Λ with a small raised circle. In the arguments of d, a raised stroke follows the first Λ and a raised 2 follows the second.

Original source details: GELFAND-P000453

Join them by an edge. We obtain a graph Δ.

Theorem: Δ — a tree (conn. graph without cycles), and from $\forall$ vertex there issue exactly $q+1$ edges

Δ is the Lobachevsky pl. — there acts G etc.



Diagram and typed description. The outer boundary has a gap at the upper right. The inner arcs and chain follow the visible strokes. A fine mark by the lower left arc resembles an oval. Some joins in the upper right remain uncertain.



Original source details: GELFAND-P000453

GELFAND-P000454

D. Kazhdan. Tate's art., Matematika, 13 : 2, §3.

(on the field $\mathbb{C}_p$ — completion of the alg. closure $\overline{\mathbb{Q}}_p$ or $\mathbb{Q}_p$ — p-adic numbers)



Original source details: GELFAND-P000454

Uncertain reading. The connecting word reads "or."

K — finite ext. of the field $\mathbb{Q}_p$.



Original source details: GELFAND-P000454

Diagram and typed description. There is a curved stroke between the two entries. Its meaning is uncertain. Two short vertical strokes sit below the second entry.

$\mathcal{O}_K$ — integers in K.

$\smile$

m_K — max. ideal

$k = \mathcal{O}_K/m_K$. (π).

L — finite ext. of K, $\ldots$ $\mathcal{O}_L$ — integers in it

Original source details: GELFAND-P000454

Uncertain reading. The crossed-out marks before $\mathcal{O}_L$ are illegible.

$m_L = (\tau)$, $\quad \ell = \mathcal{O}_L/m_L$,

$$G = \mathrm{Gal}(L : K)$$

Introduce a filtration in G and prove that G is solvable.

On L and K $\ldots$ define a norm so that $|\pi| = (\mathrm{Card}\, k)^{-1}$

Original source details: GELFAND-P000454

Uncertain reading. A crossed-out sign sits between K and "define." Its reading is uncertain.

Def. $\ldots$.

Original source details: GELFAND-P000454

Undeciphered passage. A short entry is crossed out after "Def." Its reading is uncertain.

$$g \in G_i \Longleftrightarrow \forall x \in \mathcal{O}_L \quad x^g - x \in m_L^i$$

$$G = G_0 \supset G_1 \supset \ldots \supset G_n = \{e\}.$$

G_i — normal subgroup in G.

Theorem: G_i/G_{i+1} — ab. group

1) $i = 0$. $G \xrightarrow{\varphi}$ Gal$(\ell : k)$ (natural map)

Construction of φ: $\bar{x} \in \ell,\ g \in G$

$x \in L$ $\quad \bar{x}^g \overset{\text{def}}{=} \overline{x^g}$

Uncertain reading. The manuscript reads $x \in L$.

Original source details: GELFAND-P000454

$g \in \ker \varphi \iff \bar{x} \in \ell,\ \bar{x}^g = \bar{x}$, i.e. $\bar{x}^g - \bar{x} = 0$, i.e.



Uncertain reading. The equivalence sign is followed by $\bar{x} \in \ell$. No explicit quantifier is visible.

Original source details: GELFAND-P000454

GELFAND-P000455

[source number: 74]

~~i.e. ...~~ $x^g - x \in m_L$, i.e. $g \in G_1$.

Uncertain reading. The start of the crossed-out entry provisionally reads “i.e.”.

Original source details: GELFAND-P000455

Undeciphered passage. The remainder of the crossed-out entry is illegible.

Original source details: GELFAND-P000455

$$0 \longrightarrow G_0/G_1 \xrightarrow{\varphi} \text{Gal}(\ell : k)$$

Exercise: φ — an isomorphism.

2) G_1/G_2 — ?



Uncertain reading. A question mark follows the dash.

Original source details: GELFAND-P000455

$$G_1 \xrightarrow{\psi_1} \ell^* \qquad g \sim\!\!\!\longrightarrow \overline{\tau^g/\tau} \qquad \text{(indep. of the choice of } \tau\text{)}$$

Uncertain reading. The first arrow is labelled ψ_1.

Original source details: GELFAND-P000455

Its kernel is G_2.

Uncertain reading. The word following "kernel" reads «ero» ("its").

Original source details: GELFAND-P000455

$$G_i/G_{i+1} \longrightarrow \ell^+ \qquad \text{(addit. group of the field } \ell\text{)}.$$
$$g \xrightarrow{\psi_i} \overline{\left(\frac{\tau^g/\tau - 1}{\tau^{i-1}}\right)}$$

Uncertain reading. The arrow from g is labelled ψ_i.

Original source details: GELFAND-P000455

Thm. $G_{i+1} = \operatorname{Ker} \psi_i$.



Uncertain reading. The domain on the upper line is written G_i/G_{i+1}. The line below has $G_{i+1} = \operatorname{Ker} \psi_i$.

Original source details: GELFAND-P000455

G_1 is called the inertia subgroup of the Galois grp.

Unramified extension $\underset{\text{def}}{\iff} G_1 = \{e\}$;

weakly ramif. $G_2 = \{e\}$.

Uncertain reading. The second letter is overwritten. The abbreviation reads «слаборазветвл.» ("weakly ramif.").

Original source details: GELFAND-P000455

purely ramified $G_0 = G_1$



Uncertain reading. The last subscript is overwritten. It provisionally reads 1.

Original source details: GELFAND-P000455

GELFAND-P000456

The seminar will start at $18^{\underline{00}}$.

2/X-72. A. Gabrielov.

S — compl. analytic set

$H_{\mathbb{Z}}$ — loc. free $\mathbb{Z}$-sheaf

($\mathbb{Z}$ — const. sheaf; a section over a conn. region is a const. integer; $H_{\mathbb{Z}}$ — loc. free sheaf of $\mathbb{Z}$-modules.

Uncertain reading. Overlapping strokes follow "modules." Their reading is uncertain.

Original source details: GELFAND-P000456

At $\forall$ point $\exists$ nbhd., in which it is isom. to $\mathbb{Z} \oplus \cdots \oplus \mathbb{Z}$).

~~H...~~

Uncertain reading. The first crossed-out sign provisionally reads H.

Original source details: GELFAND-P000456

Undeciphered passage. The rest of the short entry before the parenthesis is illegible.

Original source details: GELFAND-P000456

($\mathbb{Z}$-sheaf assoc. with the presheaf which ~~... ...~~

$F(U) = \mathbb{Z}$).



Undeciphered passage. Two entries after "which" are crossed out. Below them is $F(U) = \mathbb{Z}$.

Original source details: GELFAND-P000456

The space is loc. connected $\Rightarrow$ fiber $= \mathbb{Z}$.

The space of the sheaf $\mathbb{Z}$ is homeom. to $S \times \mathbb{Z}$.

Loc. $H_{\mathbb{Z}}|_U \simeq U \times \mathbb{Z}^n$

$$\Gamma(U, H_{\mathbb{Z}}) \cong \mathbb{Z}^n$$

S is connected $\Rightarrow$ n is the same everywhere.

Cover by neighborhoods and fix isomorphisms over the neighborhoods (up to $GL(n, \mathbb{Z})$)



Original source details: GELFAND-P000456

Diagram and typed description. Two overlapping ovals with four strokes in their intersection. There is an angular mark on the left arc.



transition functions from $GL(n, \mathbb{Z})$.

One can construct a loc. triv. bundle with such transition functions.



Original source details: GELFAND-P000456

Diagram and typed description. A slanted stroke links $H_{\mathbb{C}}$ to the caption.

This is $H_{\mathbb{R}}$ (or $H_{\mathbb{C}}$ depending on the fiber)

compl. vector bundle



Original source details: GELFAND-P000456

Diagram and typed description. A vertical stroke leads to the wavy-underlined caption. The rectangle at right is crossed out.



sheaf of holom. sections of $H_{\mathbb{C}}$

Original source details: GELFAND-P000456

Uncertain reading. The crossed-out entry may start with H and a subscript.



Original source details: GELFAND-P000456

Undeciphered passage. The crossed-out entry inside the rectangle is illegible.

$$H_{\mathcal{O}} = H_{\mathbb{Z}} \otimes_{\mathbb{Z}} \mathcal{O}_S.$$

There is a natural connection (Gauss–Manin)

$$\nabla \colon H_{\mathcal{O}} \longrightarrow \Omega^1_S \otimes_{\mathcal{O}_S} H_{\mathcal{O}} \qquad (\mathbb{C}\text{-lin. homom.})$$

Ω^1_S — holom. diff. forms of order 1

GELFAND-P000457

[source number: 75]

def. of connection.

1. $\mathbb{C}$-linearity.

2. $\varphi \in \mathcal{O}_{S,s}$ (germs), $f \in H_{\mathcal{O},s} \Rightarrow$

$$\Rightarrow \nabla(\varphi f) = \varphi \nabla f + d\varphi \otimes f$$

Our connection.

Take a loc. trivialization
and a basis of const. sections (bundle $H_{\mathbb{Z}}$) u_i

$$f = \sum \varphi_i u_i, \qquad \varphi_i \in \mathcal{O}_S$$

Then

$$\nabla f = \sum d\varphi_i \otimes u_i$$

This def. is well-defined and satisfies all the axioms.

The curvature of this connection equals 0.

Uncertain reading. The last sign reads 0.

Original source details: GELFAND-P000457

Requirement on the G.-M. connection (or on the ... filtration)

$$\nabla(\mathcal{F}^p) \subset \Omega^1_S \otimes \mathcal{F}^{p-1}.$$

(Griffiths)

Uncertain reading. The crossed-out sign after "or on the" is illegible.

Original source details: GELFAND-P000457

(Given a filtration $H_{\mathbb{C}} = F^0 \supset F^1 \supset \cdots$)
by holom. subbundles

$\mathcal{F}^p$ — sheaves of sections of F^p

There is a loc. constant bilin. form $\psi(x,y)$ on $H_{\mathbb{C}}$

Uncertain reading. The letter before (x,y) reads ψ.

Original source details: GELFAND-P000457

...

Undeciphered passage. The short crossed-out entry before “and” is illegible.

Original source details: GELFAND-P000457

and at $\forall$ point $s \in S$ this is a Hodge structure.

———— . ————

Let $0 \leq p \leq n$, $k_p \geq k_{p+1}$ — a seq. of numbers

$$k_0 \geq k_1 \geq \cdots \geq k_n.$$

Z — space with elem. $F = \{F^0 \supset F^1 \supset \cdots \supset F^n\}$,
where dim $F^p = k_p$.

Uncertain reading. The superscript p on F is overwritten.

Original source details: GELFAND-P000457

This is a proj. alg. set.

GELFAND-P000458

$$H_{\mathbb{C}} = F^0, \qquad H_{\mathbb{Z}} \subset H_{\mathbb{R}} \subset H_{\mathbb{C}}.$$

Let there be on $H_{\mathbb{C}}$ a given bilin. form ψ (nondeg.),

Uncertain reading. The sign after “form” reads ψ.

Original source details: GELFAND-P000458

symm. for odd n and skew for even n; integral



Original source details: GELFAND-P000458

Uncertain reading. The manuscript reads “symm. for odd n and skew for even n.”

$\overline{D}$ — subset in Z of those flags for which



Diagram and typed description. A line encloses the formula from below and at both sides.

$$\psi(F^p, F^{n-p+1}) = 0$$

Original source details: GELFAND-P000458

Add. cond.
on the flags 1) $F^p \oplus \overline{F^{n-p+1}} \cong H_{\mathbb{C}}$



Uncertain reading. The end of the exponent $n-p+1$ is overwritten beside the sign $\cong$.

Original source details: GELFAND-P000458

2) From it are constr. the grading and the Weil autom. C and then

$\psi(x, C\bar{y})$ pos. def. Herm. form on $H_{\mathbb{C}}$.

Uncertain reading. After C the manuscript reads «и тогда» (“and then”).

Original source details: GELFAND-P000458

These conditions single out $\underset{\text{(open).}}{D} \subset \overline{D}$.

D is called the classify. space of Hodge structures.

Depends on the set of dimensions and the form ψ.

Next time: homogeneity.

grp. of the compl. space $H_{\mathbb{C}}$, preserv. ψ, transit. on $\overline{D}$

Conn. comp. $_1$ grp. of the real space $H_{\mathbb{R}}$, preserv. ψ, transit. on D



Uncertain reading. The left addition provisionally reads «Св. комп.» (“conn. comp.”) with a lowered sign resembling 1.

Original source details: GELFAND-P000458

Manin's 2nd lecture.

D: Kazhdan. More on Tate's work.



Original source details: GELFAND-P000458

Uncertain reading. Two dots sit one above the other after the initial.



Original source details: GELFAND-P000458

Diagram and typed description. A narrow mark of several strokes crosses the divider. No definite letter or arrow is visible.



Chapter 6

GELFAND-P000459

V. Buchstaber.

Formal groups.

The def. of a formal group was given.



Original source details: GELFAND-P000459

Diagram and typed description. The abbreviation "commut." is added in a bubble above "ring."

commut.

A — arbitrary ring with 1;

$$\sum_{i=0}^{\infty} a_i x^i, \qquad a_i \in A$$

Form. group:

$$F(x,y) = x + y + \sum_{i+k\geq 2} a_{ik} x^i y^k$$

— form. power series.

Conditions: associativity, commutativity (it follows from assoc.). Exist. of an inv. elem. from the implicit func. thm.



Uncertain reading. The last words read «неявной ф-и» (“implicit func.”).

Original source details: GELFAND-P000459

Isomorphism:

$$z = \varphi(x) = x + a_1 x^2 + \ldots; \qquad \varphi^{-1}(x) = z - a_1 z^2 + \ldots$$

Uncertain reading. The sign in the first formula reads φ.

Original source details: GELFAND-P000459



Uncertain reading. The same sign φ appears before the exponent -1.

Original source details: GELFAND-P000459

Uncertain reading. The parentheses contain x. The right-hand side uses z.

Original source details: GELFAND-P000459

... and one is obt. from the other by a change of variables.



Undeciphered passage. The entry before “and one” is crossed out. A full reading is uncertain.

Original source details: GELFAND-P000459

Form. groups will be classified (but not up to isom. — that is a separate problem)

The series $g(x) = x + \dots$ is called a logarithm of the grp. F, if

$$F(x, y) = g^{-1}(g(x) + g(y))$$

Lazard's lemma. If A is a $\mathbb{Q}$-module, then any form. group $F(x, y)$ over A has a logarithm.

Original source details: GELFAND-P000459

Uncertain reading. The name provisionally reads «Лазара» (Lazard). The vowel after «з» may be «у».

Proof. (see Mat., $13 : 6$)

GELFAND-P000460

Consider in place of A the ring $A[[t]]$; t — time.

Then def. the shift $x \mapsto F(x, t)$ (shift of the form. var. by time t).

Differential:

$$\omega(x) = \psi(x)\, dx$$

Original source details: GELFAND-P000460

Uncertain reading. The first coefficient sign is set as ψ. The same letter recurs in the formulas below.



Original source details: GELFAND-P000460

Diagram and typed description. A thin line marks off the addition above the formula.

can be consid. as an elem.

$\psi(x) \in A[[t]][[x]]; \quad A \subset A[[t]]$

Inv. form (differential):



Original source details: GELFAND-P000460

Diagram and typed description. Two vertical strokes and "or" stand between the formulas.

$\psi(F(x,t))\, dF(x,t) = \psi(x)\, dx.$

$\|$ or

$$\psi(F(x,t))\, \frac{\partial F(x,t)}{\partial x}\, dx$$

$$\psi(F(x,t))\,\frac{\partial F(x,t)}{\partial x} = \psi(x)$$

(t is a parameter; the differential is taken only in x)

Set $x = 0$:

$$\psi(t)(1+\ldots)|_{x=0} = \psi(0),$$
$$\psi(t) = \psi(0)\,\frac{1}{\left.\dfrac{\partial F(x,t)}{\partial x}\right|_{x=0}}.$$

These are the series that are coeffs. in the inv. differential.

Canonical form:

$$\omega(x) = \frac{1}{\left.\dfrac{\partial F(x,y)}{\partial y}\right|_{y=0}}\,dx$$

is an ... invar. differential (simple exercise).

Uncertain reading. A heavy vertical sign lies between the words. Its reading is uncertain.

Original source details: GELFAND-P000460

This gives a characterization.

Consider the form. series

$$g(x) = \int_0^x \omega(x) = x + \ldots$$

(it is important that A is a $\mathbb{Q}$-module! — integer denominators arise during integration)

Uncertain reading. An exclamation mark follows “module.”

Original source details: GELFAND-P000460

Uncertain reading. The first word after the dash reads «появляются» (“arise”).



Original source details: GELFAND-P000460

Integrate the relation:

$$\psi(F(x,t))\,dF(x,t) = \psi(x)\,dx$$
$$g(F(x,y)) = g(x) + C;$$

Here integration is in x (t — param.), therefore $C = C(y)$.

Set $x = 0$. We obtain: $C = g(y)$ ...

Undeciphered passage. The entry after $C = g(y)$ is crossed out and illegible.

Original source details: GELFAND-P000460

$$g(F(x,y)) = g(x) + g(y)$$
$$F(x,y) = g^{-1}(g(x) + g(y)). \quad !! \qquad \blacksquare$$

Corollary Over $\mathbb{Q}$-mods. all form. laws are strictly isom.

Univ. law: consid. $g(x) = x + \sum g_i x^{i+1}$ — a series, its ring is $\mathbb{Q}[g_i]$.

$$F(x,y) = g^{-1}(g(x) + g(y));$$

Over $\overset{\downarrow}{\mathbb{Q}}[g_i]$ one obtains a univ. law. (for all $\mathbb{Q}$-modules)

Original source details: GELFAND-P000460

Uncertain reading. The letter $\mathbb{Q}$ below the arrow is overwritten. The earlier strokes cannot be separated.

We shall classify over arbitrary rings A (commut. and with 1)

Original source details: GELFAND-P000460

Uncertain reading. The first word reads «Будем» (“we shall”).

Original source details: GELFAND-P000460

Diagram and typed description. A curved arrow leads from the universal law to the bracket before “Universality.”

[Universality:

any series $F(x,y)$ over the $\mathbb{Q}$-mod. A is obt. from such a series by replacing its coefficients by their homomorphic images under a ring homom. $\mathbb{Q}[g_i]$ into A, sending g_i to the coeffs. of the series $g(x)$, found above]



Original source details: GELFAND-P000460

Uncertain reading. The two words for “homomorphic images” have plural endings.

GELFAND-P000461

Now consid. the general case: A is not necess. a $\mathbb{Q}$-module.

Consid. the series $F(x,y) = x + y + \sum a_{i,j} x^i y^j$

$a_{i,j}$ — alg. indep. variables.

Consid. $\mathbb{Z}[a_{i,j}]$, $\deg a_{i,j} = i + j - 1$

A form. group is obt. from it

$$F(F(x,y),z) = x + y + z + \sum a_{i,j,k} x^i y^j z^k, \quad a_{i,j,k} \in \mathbb{Z}[a_{i,j}].$$
$$F(x,F(y,z)) = x + y + z + \sum a'_{i,j,k} x^i y^j z^k \qquad a'_{i,j,k} \in \mathbb{Z}[a_{i,j}]$$

Consid. in $\overset{\mathbb{Z}[a_{i,j}]}{\overline{\ldots}}$ the ideal J, gen. by the homog. elems. $\{a_{i,j,k} - a'_{i,j,k}\}$ and by the elems. $\{a_{i,j} - a_{j,i}\}$.

Undeciphered passage. $\mathbb{Z}[a_{i,j}]$ is inserted above the cancellation. The earlier entry is illegible.

Original source details: GELFAND-P000461

Uncertain reading. There are crossed-out strokes above the second coefficient $a_{j,i}$.

Original source details: GELFAND-P000461

Now replace $a_{i,j}$ in $F(x,y)$ with $a_{i,j}$ mod J — $\overline{\ldots}$ we obtain the series $F \in \Lambda[[x,y]]$.



Undeciphered passage. The entry before “we obtain” is crossed out and illegible.

Original source details: GELFAND-P000461

$$\Lambda = \mathbb{Z}[a_{i,j}]/J$$

This is the univ. group. (clear).

Lazard’s thm., Λ — a polynomial ring on generators, one in each dimension:

$$\Lambda = \mathbb{Z}[a_i], \quad i \geq 1, \quad \deg a_i = i.$$

Uncertain reading. The penultimate letter of «одной» (“one”) is heavily overwritten.

Original source details: GELFAND-P000461

By Lazard's lemma:



Original source details: GELFAND-P000461

Diagram and typed description. Two pairs of strokes with dots lie above and below the equality.

$$\Lambda \otimes_{\mathbb{Z}} \mathbb{Q} = \mathbb{Q}[g_i], \ \deg g_i = i.$$

1. How many mult. generators has Λ?

Consid. $\widetilde{\Lambda} = \Lambda/(\text{decomposable elements})$.

Original source details: GELFAND-P000461

Uncertain reading. The word in the denominator provisionally reads «разложимым» (“decomposable”).



Original source details: GELFAND-P000461

Diagram and typed description. A short vertical stroke links the first ring to the explanation.

$\mathbb{Z}[a_{i,j}] \longrightarrow \Lambda \longrightarrow 0.$

here there is an ideal gen. by decomp. elems. (prod. of 2 of nonzero degree)

We have: $\widetilde{\Lambda} = \sum_{i \geq 0} \widetilde{\Lambda}_i$;
multiplication is zero except when one of … is an elem. of degree 0.

Decomp. elems. are elems. of the form $a \cdot b$, where a and b *
* are noninvertible. Take the ideal they generate, and $\widetilde{\Lambda}$ — the quotient ring.
Grading $\Rightarrow$ only elems. of degree 0 are invertible.
Hence this ideal is the image of the ideal of decomp. elems. from $\mathbb{Z}[a_{i,j}]$.



Original source details: GELFAND-P000461

Diagram and typed description. Two vertical strokes separate the marginal note at right.



Original source details: GELFAND-P000461

Uncertain reading. The left-hand sign probably reads $\widetilde{\Lambda}$ with a joined tilde. Another possible reading is χ.



Original source details: GELFAND-P000461

Undeciphered passage. The short entry after “of” is crossed out and illegible.

Original source details: GELFAND-P000461

Uncertain reading. The marginal note reads «необратимы» (“are noninvertible”).



Original source details: GELFAND-P000461

Uncertain reading. «Берется» (“take”) follows «необратимы».

$\widetilde{\Lambda}_n$ — an abelian grp. under add. with gens. — gens. of the mult. grp. Λ in dimension n.

$$F(F(x,y),z) = F(x,y) + z + \sum a_{i,j} \dddot{} (x+y)^i z^j$$

Original source details: GELFAND-P000461

Undeciphered passage. The entry before $(x+y)^i$ is crossed out and illegible.



Original source details: GELFAND-P000461

Diagram and typed description. The bubble above the line contains “of different $a_{i,j}$.”

of different $a_{i,j}$

(in $\widetilde{\Lambda}$ the product already equals 0).

$$F(x,F(y,z)) = x + F(y,z) + \sum a_{i,j} x^i (y+z)^j$$

$\widetilde{\Lambda}$ is obt. from the free ab. group gen. by $a_{i,j}$, by quotienting by the rels. ...

Let $h(x,y) = \sum h_{i,j} x^i y^j = F(x,y) - x - y$.

$$h(x,0) = 0, \quad h(0,y) = 0.$$

GELFAND-P000462

Lazard's rel.:

$$h(x,y)+h(x+y,z)=h(y,z)+h(x,y+z). \qquad (*)$$

It suffices to take homog. polynomials h.

In Lazard: methods of number theory.

Problem: find all solutions of $(*)$ [homog. polys.] over some ring K.

All solutions — a group L, Everything over the ring K

$$L \longrightarrow \mathrm{Ext}^{2,n}_{K[x]}(K,K) \longrightarrow 0.$$

Introduce on $K[x]$ a Hopf struct.: a mult. homomorphism

$$\Delta : K[x] \longrightarrow K[x]\otimes_K K[x] \qquad \text{(comultiplication)}.$$
$$x \longrightarrow x\otimes 1 + 1\otimes x$$

A Hopf alg. has cohomology. The alg. is graded $\Rightarrow$ the cohom. is bigraded. Hence 2 indices for Ext.

Next:

$$\text{on the left and on the right} \quad (x+y+z)^n - x^n - y^n - z^n$$
$$\downarrow$$
$$0 \longrightarrow \{c((x+y)^n - x^n - y^n),\ a\in K\} \longrightarrow L \longrightarrow \mathrm{Ext}^{2,n}_{K[x]}(K,K) \longrightarrow 0.$$

Original source details: GELFAND-P000462

Diagram and typed description. The arrow from the addition points down toward the first term of the sequence.



Original source details: GELFAND-P000462

Uncertain reading. The sign before the parentheses provisionally reads c. The separate entry reads $a \in K$. Both signs are overwritten.

$n=2$. Polyn. of degree 2 cxy.



Original source details: GELFAND-P000462

Uncertain reading. The sign above "Polyn." is crossed out and illegible.

$\underline{\underline{n=3}}$ $h(x,y) = C_1x^2y + C_2xy^2$

$$\widetilde{\Lambda} = \mathbb{Z} + \mathbb{Z}_3.$$

Uncertain reading. The line reads $\widetilde{\Lambda} = \mathbb{Z} + \mathbb{Z}_3$.



Original source details: GELFAND-P000462

1 sol. by Lazard's lemma: $c((x+y)^n - x^n - y^n)$

$h(x,y) = x^2y + xy^2$ for all rings

$h(x,y) = x^2y$ for rings that are $\mathbb{Z}_3$-modules

Uncertain reading. The subscript on $\mathbb{Z}$ in this line is 3.

Original source details: GELFAND-P000462

x^2y

Consid. comodules over a Hopf alg. A — this is an ab. grp. N, for which there is a map $N \longrightarrow A \otimes N$ with nat. conds.

Choose the resolution correctly: there will be all cycles without boundaries (min. resolution). ~~by~~

Uncertain reading. The crossed-out word after the parenthesis may read «по» (“by”).

Original source details: GELFAND-P000462

~~H...~~

Uncertain reading. The start of the crossed-out heading shows the Cyrillic «Н».

Original source details: GELFAND-P000462

Undeciphered passage. The rest of the crossed-out heading is illegible.



Original source details: GELFAND-P000462

Calculation of the group Ext^2.

1°. K — ... a comodule over the Hopf alg. $K[x]$.

Original source details: GELFAND-P000462

Uncertain reading. A heavy rectangular mark is crossed out between the dash after K and "comodule."

... $x \longrightarrow x \otimes 1 + 1 \otimes x$

Original source details: GELFAND-P000462

Uncertain reading. A heavily crossed-out sign appears before x in the addition.

$$K \longrightarrow K \otimes K[x] \quad \longleftarrow\!\!\!

GELFAND-P000463

Consid.

$$K_*[x] = \mathrm{Hom}_K(K[x], K).$$

("diff. operators").

$$(x_*^n, x^m) = \delta_{n,m}$$

Multiplication:

$$\underline{x_*^n \cdot x_*^m = C_{n+m}^n x_*^{n+m}} \qquad \text{— table.}$$

Here K plays no role.

It suffices to take $K = \mathbb{Z}_p$ or $\mathbb{Q}$.

$$K_*[x] = \prod_{q=1}^{\infty} B_q, \qquad B_q = \mathbb{Z}_p[y_{p^i}]/(y_{p^i}^p)$$



Uncertain reading. The left side reads $K_*[x]$. The product has lower limit $q = 1$ and upper limit ∞.

Original source details: GELFAND-P000463

$y_1, \ldots, y_i, \ldots, y_{p^i}$ — generators.



Uncertain reading. In three places the i next to p is raised. This is set as y_{p^i}. In the denominator the separate outer exponent p on y is visible.

Original source details: GELFAND-P000463

GELFAND-P000464

30/X̄-72. Gelfand sem..

I. Bernstein

И.М.Г.



Original source details: GELFAND-P000464

Diagram and typed description. The two arrows at left point to the same vertex. From the middle vertex arrows lead left, right and down to the right. The bent line at right has arrowheads. The small strokes at vertices have no established reading as letters.



There is a directed graph. This is a category.

Ꝑ Consid. some diagrams, with at the points — vect. spaces, on the arrows maps (functoriality is not required).

Original source details: GELFAND-P000464

Uncertain reading. A loop survives at the start of the crossed-out sign. Possibly Cyrillic «Р».

Original source details: GELFAND-P000464

Uncertain reading. The words before “diagrams” provisionally read «какие л.» (“some”).

Prob. — to classify.



Original source details: GELFAND-P000464

Diagram and typed description. A slightly curved rightward arrow joins the two points.

Prob. of classif. of maps. The only invs. are dim Ker and dim Coker. Reduces to an embedding.

Original source details: GELFAND-P000464

Diagram and typed description. One loop. Its arrowhead on the left side points upward.

one transformation.

Original source details: GELFAND-P000464

Diagram and typed description. Two loops share the left vertex. The top of the outer loop is faint. Overlapping arrowhead strokes are visible near the vertex.



— the prob. is unsolvable (a pair of arbitrary lin. operators). ~~...~~

Original source details: GELFAND-P000464

Uncertain reading. The short entry before “it” is crossed out and illegible.

It reduces to the prob. of commuting ones (Gelf. and Ponomarev).



Original source details: GELFAND-P000464

Uncertain reading. The first letter is overwritten. The abbreviation reads «Гельф.» (Gelf.).

~~Reduc....~~



Original source details: GELFAND-P000464

Uncertain reading. The crossed-out line may begin «Свод.» (“reduc.”).

Original source details: GELFAND-P000464

Undeciphered passage. The remainder of the crossed-out line is illegible.

Space and subspace.
Space and 2 subspaces } triv.

Can be done: Space and 3 lin. subspaces.



Original source details: GELFAND-P000464

Uncertain reading. The start of the line provisionally reads «Делается» (“can be done”).

There are 9, invariants, not 8!

Diagram and typed description. Three arrows point toward the upper vertex. Their arrowheads partly merge.



Original source details: GELFAND-P000464

(problem).

Diagram and typed description. Four edges meet at the heavily inked central vertex. Overlapping strokes obscure the direction of two edges.



Original source details: GELFAND-P000464

Space and 4 subspaces classified (Gelf. and Ponom.) — ... already an inf. number of indecomp.

Undeciphered passage. The word after the dash is crossed out and illegible.



Original source details: GELFAND-P000464

Gabriel: in which graphs are there finitely many indecomp. systems?

Answer: draw a Dynkin diagram! — these and only these are such graphs.

Exceptions: diagrams with double (generally multiple) arrows.

GELFAND-P000465

Theorem (Roytov or Nazarovy).
from Kyiv



Uncertain reading. The names provisionally read «Ройтов» and «Назаровы». The addition below reads “from Kyiv.”

Original source details: GELFAND-P000465

A class of diagrams is descr. with a classific. as in Gelf. and Ponomarev.

Connection ... with singularities! — see Artin, Tyurina, Brieskorn.

Undeciphered passage. The word between “Connection” and “with singularities” is crossed out and illegible.



Original source details: GELFAND-P000465

И.Б. Category of vect. spaces over points and maps over arrows.
(The graph is fixed). Def. direct sum. This is Cat(Γ) (Γ — graph)
Morphisms — maps over each point with commut. diagrs.

- category of linear spaces.

Important: no need to ident. isomorphic ones.

Original source details: GELFAND-P000465

Uncertain reading. The abbreviation before “isomorphic” provisionally reads «отожд.» (“ident.”).

It is easy to see that $\forall$ object $= \sum$ indecomp. ones. (uniquely up to isom.).

1) Classif. Γ, with finitely many indecomp. objects.

Restrict to connected ones:

Original source details: GELFAND-P000465

Diagram and typed description. A small angular stroke rises above the third vertex from the left.

A_n (n points)



Original source details: GELFAND-P000465

Diagram and typed description. There is a small leftward arrowhead on the segment between the third and fourth vertices.

D_n $n \geq 4$

Original source details: GELFAND-P000465

Diagram and typed description. There are six vertices on the horizontal chain. A branch descends from the third vertex from the left.

E_k

$k = 6, 7, 8$ (necessarily 2 segments on the left).

Place the arrows arbitrarily!!

D_4 — space and 3 subspaces.

Idea: no cycles (one obt. eigenvalues), no

Original source details: GELFAND-P000465

Uncertain reading. The abbreviation in parentheses may read «получ.» (“obt.”).

Original source details: GELFAND-P000465

Diagram and typed description. Four segments meet at the black dot. No separate vertices are visible at the ends.



— there will be an inf. number.

Original source details: GELFAND-P000465

Diagram and typed description. The chain has a fork at each end. Five vertices are marked on the chain itself.



— also impss., since ident.

Original source details: GELFAND-P000465

Uncertain reading. The last abbreviation provisionally reads «отожд.» (“ident.”).

2) The no. of indecomp. objs. does not depend on the dir. of the arrows.
It is characterized by the set of dimensions!!
one should consid. the root syst.
γ — pos. root, α_i — simp. roots.
To each root — an indecomp. object

$$\gamma = \sum n_i \alpha_i, \qquad n_i \text{ — dimensions!!}$$

Original source details: GELFAND-P000465

Uncertain reading. Both signs have a lower loop and two upper strokes. They are provisionally set as γ.

No. = no. of simple roots.

Original source details: GELFAND-P000465

Uncertain reading. The line reads «простых корней» (“simple roots”).



Original source details: GELFAND-P000465

Diagram and typed description. Six rows of dimensions stand below the chain with two rightward arrows.

1	0	0
0	1	0
0	0	1
1	1	0
0	1	1
1	1	1

Original source details: GELFAND-P000465

Uncertain reading. The middle 1 in row two is overwritten. A remnant of a loop survives to its right.

GELFAND-P000466

3) Consid. the Γ, for which Cat(Γ) is solvable.

Original source details: GELFAND-P000466

Diagram and typed description. The two loops share a vertex. Inside the upper loop there is a short slanted stroke separate from its arrowhead.



C

Unsolvable categ. — if there is an embedding $C \longrightarrow \mathrm{Cat}(\Gamma)$, taking nonisom. objects to nonisom. ones.

They are classif. and correspond to extended Dynkin diagrams!

Original source details: GELFAND-P000466

Diagram and typed description. Three arrows leave one vertex, upward, rightward and down to the left.



Original source details: GELFAND-P000466

Diagram and typed description. Seven points lie on a straight chain. An arc joins the endpoints.



$\widehat{A}_n$



Original source details: GELFAND-P000466

Diagram and typed description. Seven points lie along the chain, with two branches at each end.



Original source details: GELFAND-P000466

Diagram and typed description. Seven points lie along the horizontal chain. Two segments with points descend from the third point from the left.



(appear in the theory of ~~grp.~~ groups generated by reflections.)

Original source details: GELFAND-P000466

Uncertain reading. The crossed-out insertion above the line may read «гр» (“grp.”).

These are all the graphs for which the prob. is solvable.

V. Buchstaber.

Lazur's thm.



Original source details: GELFAND-P000466

Uncertain reading. The name provisionally reads «Лазура» here. The middle vowel may be «а».

$$\Lambda = \mathbb{Z}[a_1, \ldots, a_n, \ldots], \qquad \deg a_n = n \geq 1.$$

Proof.

$$\Lambda \longrightarrow \bar{\Lambda} = \Lambda/(\text{decomp.})$$



Original source details: GELFAND-P000466

Uncertain reading. A horizontal stroke stands above the second Λ. The denominator reads «разл.» (“decomp.”).

$\bar{\Lambda}$ — univ. ring for such polynomials $h(x, y)$,



Original source details: GELFAND-P000466

Diagram and typed description. “Such” is inserted in a bubble before “polynomials.”

that ↓ $h(x,y) = h(y,x), \quad h(x,0) = 0,$

$$h(y,z) + h(x,y+z) = h(x,z) + h(y,x+z).$$



Diagram and typed description. "That" is inserted in a separate bubble before the conditions.

Original source details: GELFAND-P000466

This is cohomology: $\underset{\text{(cycles)}}{dh} = 0$ (in the bar construction for polynomials)



Uncertain reading. Below dh is the word "cycles."

Original source details: GELFAND-P000466

$$\mathrm{Ext}^{*,*}_{A[x]}(A,A) = H^{*,*}(A[x])$$



Original source details: GELFAND-P000466

Uncertain reading. The subscript on Ext reads $A[x]$. There are two stars above the symbol on each side.

$$A[x] \longrightarrow A[x] \otimes \bar{A}[y]$$
$$x \longrightarrow x + y$$

Uncertain reading. Below the first arrow the manuscript reads $x \longrightarrow x + y$.

Original source details: GELFAND-P000466

Cohom. is calc. using resolutions.

The bar constr. is one of the resolutions.

$$\mathcal{A}: \quad A[x] \xrightarrow{\Delta} A[x] \otimes \bar{A}[y] \longrightarrow A[x] \otimes \bar{A}[y] \otimes \bar{A}[z] \longrightarrow \dots$$

$\bar{A}[y]$ — polynomials with no const. term.

We obt. an acyclic complex which is used to compute cohomology

$$(\text{put everywhere} \underset{h(x,y)}{} — \tilde{a} \Rightarrow a \otimes 1 + 1 \otimes a) = \Delta a).$$



Original source details: GELFAND-P000466

Uncertain reading. A wavy stroke stands above a. The following sign provisionally reads $\Rightarrow$. Both closing parentheses are visible.

One must classif. cycles in a particular resolution.

$$0 \longrightarrow B \longrightarrow Z \longrightarrow H^2(A[x]) \longrightarrow 0$$

Original source details: GELFAND-P000466

Uncertain reading. The term after B is Z, and H has superscript 2.

$x^n \longrightarrow (x+y)^n - x^n - y^n$ (these are boundaries)

GELFAND-P000467

Passage to the obt. resol. by means of the functor $\mathrm{Hom}(\cdot, A)$

Original source details: GELFAND-P000467

Uncertain reading. The abbreviation before "resol." reads «получени.» ("obt.").

In the acycl. resol.

$$x \longrightarrow x + y$$
$$x^n \longrightarrow (x+y)^n.$$

We must consid. $\mathrm{Hom}_{A[x]}(\mathcal{A}, A)$ (from the 1st factor est. the struct. of an $A[x]$-mod.).

Original source details: GELFAND-P000467

Uncertain reading. The subscript on Hom is $A[x]$. The arguments are $\mathcal{A}, A$.

Uncertain reading. The abbreviation after “factor” reads «уст.» (“est.”).

Original source details: GELFAND-P000467

$$A \xrightarrow{d} A[y] \xrightarrow{d} A[y] \otimes A[z] \xrightarrow{d} \dots$$

Original source details: GELFAND-P000467

Uncertain reading. On this line $A[y]$ and $A[z]$ have no overbars.

$$\Delta \longrightarrow d: \qquad x^n \longrightarrow (x+y)^n - x^n - y^n$$



Original source details: GELFAND-P000467

Uncertain reading. Both subtracted terms, x^n and y^n, are visible on the next line.

$$\Delta: \quad h(x,y) \longrightarrow h\big(\underset{\|}{\Delta x}, y\big) - h\big(x, \underset{\|}{\Delta y}\big)$$
$$\qquad\qquad\qquad\quad x+z \qquad\qquad\quad y+z$$

Uncertain reading. There is a heavily inked horizontal sign between the terms. It is provisionally set as minus.

Original source details: GELFAND-P000467

$\mathcal{A}$ — a seq. of $A[x]$-modules,

Uncertain reading. A short low stroke at the end of the line resembles a comma.

Original source details: GELFAND-P000467

$A[x] \otimes y^k$ — submodules

Because of $\overline{A[y]}$:

$$x^n \longrightarrow (x+y)^n - x^n \qquad \text{(since there is no const. term)}$$



Diagram and typed description. A long line runs along the right edge of the frame. It begins with a small bend and ends just below the divider.

Original source details: GELFAND-P000467

GELFAND-P000468

13/XI-72. Gelfand sem..

L. Vaserstein.

A — assoc. ring (not necessarily with 1).

iA — ring with a formally adjoined unit.

$iA/A = \mathbb{Z}$, A — two-sided ideal in iA.

GA — mult. group of the ring.

$GA \subset A$

$(a,b) \longrightarrow a+b+ab$ This is a binary assoc. oper.

$$\| \qquad (e+a)(e+b) - e = a+b+ab$$

~~iA~~ GA — set of invertible elements with respect to this operation.

Uncertain reading. The short crossed-out entry before GA may read iA.

Original source details: GELFAND-P000468

$$a \longrightarrow 1 + a, \qquad A \longrightarrow 1 + A$$

homomorphism. into the ordinary invert. elems.

$$f : A \longrightarrow B$$
$$f(GA) \subset GB$$

Uncertain reading. The sign before GB is overwritten. It is provisionally set as $\subset$.

Original source details: GELFAND-P000468

i, G — functors to the cat. of rings with 1 and the cat. of groups.

$M_k A$ — matrices $k \times k$ with ordinary multiplication.

$\widetilde{\Omega} A = \{a = (a_{ij})\}$, in $\forall$ row and column a finite no. of elems. $\neq 0$, (this is a ring)

MA — subring of finite matrices (a finite number of elems. $\neq 0$). (two-sided ideal in $\widetilde{\Omega} A$).

$\Omega A = \widetilde{\Omega} A / MA$



Uncertain reading. The letter before A on the left is overwritten. It reads Ω.

Original source details: GELFAND-P000468

$M, \widetilde{\Omega}, \Omega$ — functors.

$$\underline{\Theta A} \subset MA$$

upper triangular $a = (a_{ij})$: $\quad a_{ij} = 0$ when $i \leq j$ ...

Diagram and typed description. A short vertical stroke is drawn below the double underline under ΘA.

Original source details: GELFAND-P000468



Uncertain reading. The manuscript has “upper triangular” and $a_{ij} = 0$ when $i \leq j$.

Original source details: GELFAND-P000468

Undeciphered passage. Several signs one above another are crossed out after the inequality.

Original source details: GELFAND-P000468

Remark. If $N \xrightarrow{\sim} N$ is a bijection, there is a map of the matrix ring (~~th.~~ autom.) — simultaneous perm. of rows and columns.

Uncertain reading. The crossed-out abbreviation before “autom.” may read «эт».

Original source details: GELFAND-P000468

(inner autom. perm. of rows and columns)



Uncertain reading. The parenthesis reads «внутр. автом.» (“inner autom.”).

Original source details: GELFAND-P000468

Even if $N \longrightarrow N$ is any map, it is assigned an endomorphism.

Uncertain reading. The first word reads «Даже» (“even”).

Original source details: GELFAND-P000468

Uncertain reading. The last word is underlined and reads “endomorphism.”

Original source details: GELFAND-P000468

GMA — mult. group, MA, $GMA \subset MA$.

Simplicial structure in MA.

$X \subset GMA$ is called a simplex, if by a left shift and conjugation by a permutation matrix it can be taken into ΘA



Uncertain reading. The manuscript reads «левым сдвигом» (“by a left shift”).

Original source details: GELFAND-P000468

Note that $G\Theta A = \Theta A$ as a set (they are nilpotent)



Uncertain reading. The last letters are overwritten. The word reads “nilpotent.”

Original source details: GELFAND-P000468

Undeciphered passage. A crossed-out mark before the first line with a short stroke to its right. The reading is unresolved.

Original source details: GELFAND-P000469

In fact

Diagram and typed description. The line under the inclusion turns up at both ends.

$\llcorner GMA \supset \Theta A \lrcorner$

Original source details: GELFAND-P000469

Mark the vertex 0 — the identity of the group GMA.

SA — the corresponding simplicial scheme.

(Historical remark: Volodin used SA to define the functors $K^n_{\mathbb{C}}$)

in essence



Uncertain reading. The subscript reads $\mathbb{C}$, with an extra stroke inside the letter.

Original source details: GELFAND-P000469

Suppose the ring A has a unit. Then put.

$$K_n A = \pi_{n-1} SA, \qquad n \geqslant 1.$$

For $n \geqslant 2$ there is a group structure, commutative for $n \geqslant 3$.

Another def. of the group structure (commutative).

Whitehead's lemma

Consider the spheroid $s\colon Z^n \longrightarrow SA$. The group of permutations acts on SA $f\colon N \longrightarrow N$. We obtain a new spheroid s^f:



Diagram and typed description. The top arrow is unlabelled.



Original source details: GELFAND-P000469

They are always homotopic.

Idea of the proof:

Im $s \subset M_k A$.

$$s = \left(\begin{array}{c|c} sz & 0 \\ \hline 0 & 0 \end{array}\right).$$

Everything reduces to the case

$$s^f = \left(\begin{array}{c|c} 0 & 0 \\ \hline 0 & sz \end{array}\right).$$



Uncertain reading. The final sign in sz has a cross-stroke and is provisionally set as a lowercase letter. Both matrices have two dividing rules.

Original source details: GELFAND-P000469

(f of a special form: $fi = i + k$, we adjust it at ∞).

$$\begin{pmatrix} a & 0 \\ 0 & 0 \end{pmatrix} \quad \begin{pmatrix} a & a \\ 0 & 0 \end{pmatrix} \quad \begin{pmatrix} 0 & a \\ -1 & 0 \end{pmatrix} \quad \begin{pmatrix} 0 & 0 \\ -1 & a \end{pmatrix} \quad \begin{pmatrix} 0 & 0 \\ 0 & a \end{pmatrix}$$



Original source details: GELFAND-P000469

Uncertain reading. The upper left zero in the third matrix is heavily retraced.

These are 5 spheroids. This is a homotopy. Each 2 neighbours are elementarily homotopic:

$$s_1, s_2 \colon S' \longrightarrow S'$$

are called elem. homotopic if $\forall$ simplices $X \subset S$, $s_1 X \cup s_2 X$ is a simplex in S'.



Uncertain reading. A short stroke is visible above the first S. The next line has $X \subset S$ without a prime.

Original source details: GELFAND-P000469

Let all a lie in one simplex X. Then $\begin{pmatrix} a & 0 \\ 0 & 0 \end{pmatrix}$ and $\begin{pmatrix} a & a \\ 0 & 0 \end{pmatrix}$ lie in one simplex.

Let $a_0^{-1} \in X$. Multiply by a_0. Then they become upper triang. If all a are upper triangular, then all 5 matrices lie in one simplex.

The commutative group structure on K_nA.

$$MA \times MA \xrightarrow{\oplus} MA$$

$fi = 2i$	$f, g\colon \mathbb{N} \longrightarrow \mathbb{N}$	noncommut., nonassoc., with no identity elem.
$gi = 2i+1$	$a \oplus b = a^f + b^g$	



Diagram and typed description. A vertical rule separates the note about the operation.

Original source details: GELFAND-P000469

Uncertain reading. Outside the left edge of the text are a slanting stroke and a mark resembling a closing parenthesis. Their purpose is unresolved.

Original source details: GELFAND-P000469

GELFAND-P000470

it induces the map $SA \times SA \longrightarrow SA$, which gives operations on all K_i, $i \geqslant 0$. (corr. verif. by Whitehead's lemma)



Uncertain reading. The second abbreviation after «корр.» is provisionally read as «прв.».

Original source details: GELFAND-P000470

They are commutative and agree with those introduced earlier by mutual distributivity, which is verified by Whitehead's lemma.

One can define a sum — H-space. On $\widetilde{\Omega}A$ one can even add an inf. number of matrices! Hence it will have trivial K-functors.

Uncertain reading. A long wavy mark is written over Ω. It is set as $\widetilde{\Omega}$.

Original source details: GELFAND-P000470

$K_1 A = \pi_0 SA.$

This is the set of connected components in GMA.

EA — the connected component of the identity. (products of elem. matrices),

pseudotriangular



Diagram and typed description. "Pseudotriangular" is written under "elem." and connected to it by a stroke.

Original source details: GELFAND-P000470



Diagram and typed description. The stepped outline encloses both hypotheses. The arrow starts level with the first one.

$A \ni 1$ $\Longrightarrow$

or

$AA = A$ (in ring mult.)

Original source details: GELFAND-P000470

$$EA = [GMA, GMA] = [EA, EA].$$

$K_2 A$ — homot. classes of loops. Loops — relations of elem. matrices.

ΘA has generators a^{ij}

Undeciphered passage. The entry after a^{ij} is heavily crossed out. A short leftward arrow is visible below "Loops".

Original source details: GELFAND-P000470

(at position i, j stands $a \in A$).

Relations: Steinberg

$$a^{ij} * b^{ij} = (a+b)^{ij},$$
$$[a^{ij}, b^{jk}] = (ab)^{ik}$$

and for some the commutator is 0.

These are the defining relations.

Let StA — be the group gen. by these generators and relations.

$$0 \longrightarrow K_2 A \longrightarrow StA \longrightarrow EA \longrightarrow 0$$

$$|$$

homot. classes of paths from 0 to somewhere
(with fixed start and end)



Original source details: GELFAND-P000470

Diagram and typed description. The annotation is connected by a vertical stroke to StA.

Uncertain reading. There is a single retraced mark to the left of the formula. Its reading is unresolved.

Original source details: GELFAND-P000470

$$K_2A = \underbrace{H_2EA}_{\text{(group homology)}} \sim StA = \text{the universal central extension of } EA.$$

Problem: suppose there are 3 matrices in GMA. All segments are simplices. Then all 3 form a simplex.

Generalization: if any pair is a simplex, then all form a simplex. (space of tolerance)

D. A. Kazhdan. Derived category.

C — an abelian category. Consider the category of complexes K_C.



Original source details: GELFAND-P000470

Diagram and typed description. The arrows point up in both columns. Two arrows point right between the columns.



Original source details: GELFAND-P000470

Uncertain reading. A fragment before “with morphisms” is struck out. A possible reading is «с сост. об.».

with morphisms f the homot. classes of morphisms of complexes.

Original source details: GELFAND-P000470

Uncertain reading. A single mark after “morphisms” is struck out. Its reading is unresolved.



Original source details: GELFAND-P000470

Diagram and typed description. A continuous stepped underline runs beneath the two lines.

$S \subset \operatorname{Hom} K_C$

|

morph. inducing an isomorphism of homologies



Original source details: GELFAND-P000470

Diagram and typed description. The annotation is connected by a vertical stroke to S.

GELFAND-P000471

Lemma. Let $f; g\colon K \longrightarrow K'$ be two morphisms.



Original source details: GELFAND-P000471

Uncertain reading. Two strokes appear between f and g, here set as a semicolon.

The following statements are equivalent:

1°. $\exists K_1, s_1 \in S$:



Original source details: GELFAND-P000471

Diagram and typed description. The first diagram with the equality written below it.

$$K_1 \xrightarrow{s_1} K \underset{g}{\overset{f}{\rightrightarrows}} K'$$

$$fs_1 = gs_1$$

2°. $\exists K_2, s_2 \in S$



Original source details: GELFAND-P000471

Diagram and typed description. The second diagram with the equality written below it.

$$K \underset{g}{\overset{f}{\rightrightarrows}} K' \xrightarrow{s_2} K_2 \ ,$$

$$s_2 f = s_2 g.$$

L_C — the same objects, and the morphisms: allow inverting s^{-1} and Ore relations.



Original source details: GELFAND-P000471

Diagram and typed description. “Ore relations” is written below the first line, with a stepped rule.

The lemma makes it poss. to define the product correctly.

Original source details: GELFAND-P000471

Uncertain reading. The manuscript has «возможно» immediately before «корректно».

See Hartshorne. Residues and duality.

Uncertain reading. A short cross-shaped mark appears above «См.» (“See”).

Original source details: GELFAND-P000471

V. Buchstaber.

References:

	C.–E.	213–223	(Cartan and Eilenberg)
	M.	358–370	(Mac Lane)
	Adams	Mat. 3 : 4	pp. 7–19.



Uncertain reading. The parenthesis reads «Маклейн» (“Mac Lane”).

Original source details: GELFAND-P000471

$$A = \sum_{n \geqslant 0} A_n \qquad \text{— grad. ring.}$$

A_n — an A_0-module for every $n \geqslant 0$.

$$0 \longleftarrow A_0 \xleftarrow{\varepsilon} A \longleftarrow C_1 \longleftarrow C_2 \longleftarrow \cdots \longleftarrow C_s \xleftarrow{d_{s+1}} C_{s+1} \longleftarrow \cdots$$

(ε assigns A zeroth comp. to each $a \in A$).

Original source details: GELFAND-P000471

Uncertain reading. A separate A is written immediately after «сопост.» (“assigns”).

Complete to a grad. free resolution.

The functor $\mathrm{Hom}_A(\cdot, A_0)$. takes d_s to $(d_s)^*$.



Uncertain reading. A small zero is visible below and to the right of the second argument A, against the parenthesis.

Original source details: GELFAND-P000471

$$H^s(A) = \mathrm{Ker}(d_{s+1})^* / \mathrm{Im}(d_s)^*$$



Diagram and typed description. The numerator has d_{s+1} and the denominator d_s.

Original source details: GELFAND-P000471

Theorem: 1) A free resolution exists

2) The groups $H^s(A)$ are independent of the resolution.

$$H(A) = \sum_{s=0}^{\infty} H^s(A) \qquad \text{— a graded ring.}$$

A def. will be given for the multiplication of Yoneda.

$$f \in H^i(A), \quad g \in H^j(A), \quad fg \in H^{i+j}(A),$$
$$\widetilde{f}\colon C_i \longrightarrow A_0; \qquad \widetilde{g}\colon C_j \longrightarrow A_0.$$

GELFAND-P000472



Original source details: GELFAND-P000472

Diagram and typed description. The node C_1 is heavily retraced. The arrow from C_i to A is dashed, and the arrow from C_{i+j} to C_j has a single break.



We have obtained a homomorphism $C_{i+j} \longrightarrow A_0$.

Original source details: GELFAND-P000472

Uncertain reading. The first word is read as «Получили» (“we have obtained”). Its last two letters run together.

This gives

$$A \underset{\text{assigns}}{\rightsquigarrow} H(A) \qquad \text{(a ring)}$$

$H(A)$ is generally noncommutative (!) in a genuine sense. The classification of multivalued groups rests on this.



Original source details: GELFAND-P000472

Uncertain reading. The manuscript abbreviates “multivalued” as «многозн.».

(So far in topology only commut. rings have occurred — there one always has Hopf algebras).

Standard resolution or B-resolution.

$$\overline{A} = \sum_{n>0} A_n$$

$$C_1 = A \underset{A_0}{\otimes} \overline{A} \qquad \text{Henceforth } A_0 \text{ is omitted}$$

(The starting rings are commutative!)

$$C_s = A \otimes (\overline{A})^s.$$
$$d_{s+1} \colon A \otimes (\overline{A})^{s+1} \longrightarrow A \otimes (\overline{A})^s$$

$$d_s\big(a_0[a_1|a_2|\dots|a_s]\big) = (-1)^{\varepsilon(0)} a_0 a_1 [a_2|\dots a_s] + \sum (-1)^{\varepsilon(n)} a_0 [a_1|\dots|a_n a_{n+1}|\dots a_s]$$



Uncertain reading. Two indices in the product are retraced. The reading is $a_n a_{n+1}$.

Original source details: GELFAND-P000472

$\varepsilon(n)$ — certain functions of the index, ~~For even grading $\varepsilon(n) = n$.~~

$\varepsilon(n) = n$, if all elems. are even.



Diagram and typed description. The condition on even elements is added below the deleted line and set off by a rule.

Original source details: GELFAND-P000472

$$\mathrm{Hom}_A(C_s, A_0) \simeq (\overline{A}^*)^s, \qquad \overline{A}^* = \mathrm{Hom}_{A_0}(\overline{A}, A_0)$$
$$d_s^* \colon [\alpha_1|\alpha_2|\dots|\alpha_{s-1}] = \sum (-1)^{\varepsilon(n)} [\alpha_1|\dots|\overline{\Delta}\alpha_n|\dots|\alpha_{s-1}].$$
$$\varepsilon(n) = n, \quad \text{if } \deg \alpha_i = 2k_i$$

Def. $\overline{\Delta}$.



Diagram and typed description. The top arrow has a clear right head. Its retraced left end also resembles a head.



Original source details: GELFAND-P000472

In fact

$$\operatorname{Im}\overline{\Delta} \subset \overline{A^*}.$$



Uncertain reading. The bar on the right extends over both A and the star.

Original source details: GELFAND-P000472

This gives another definition of multiplication,

$$\begin{array}{ll} C_s^* & f = [\alpha_1|\dots|\alpha_s] \\ C_{s'}^* & g = [\alpha'_1|\dots|\alpha'_{s'}] \end{array} \qquad f \cdot g = [\alpha_1|\dots|\alpha_s|\alpha'_1|\dots|\alpha'_{s'}]$$



Original source details: GELFAND-P000472

Uncertain reading. The last index in g reads s'. The separator after the first primed term in the product is heavily retraced.

GELFAND-P000473

20/XI-72. Gelfand sem..

Kostyuchenko. One example.



Diagram and typed description. The month is given as a Roman numeral. The name and title are double-underlined.

Original source details: GELFAND-P000473

$$\begin{aligned} v'' + 2a\lambda v' + b\lambda^2 v &= 0 \\ v(0) = v(\pi) &= 0. \end{aligned} \qquad \text{in } L_2[0,\pi].$$



Diagram and typed description. A line under the equation turns up at both ends.

$$\frac{\partial^2 u}{\partial x^2} + 2a\frac{\partial^2 u}{\partial x \partial t} + b\frac{\partial^2 u}{\partial t^2} = 0,$$

Original source details: GELFAND-P000473

$$0 < x < \pi$$
$$0 \leqslant t < +\infty$$

Uncertain reading. The second inequality sign is retraced. The provisional reading is $0 \leqslant t < +\infty$.

Original source details: GELFAND-P000473

Suppose the eq. is elliptic.

Uncertain reading. The first word reads «Пусть» (“Suppose”).

Original source details: GELFAND-P000473

$$a^2 < b; \qquad b > 0.$$

$$v_k(x) = e^{\gamma kx} \sin kx, \qquad \gamma = \frac{-a}{\sqrt{b-a^2}}; \qquad k = \pm 1,\ \pm 2,\ \ldots.$$



Diagram and typed description. A rule with upturned ends is drawn below the formula for γ.

Original source details: GELFAND-P000473

1. The system is complete, but it is unknown how to find the coefficients. This is the question of finding the biorthog. system.



Uncertain reading. The end of “system” is retraced. A separate mark is crossed out after the period.

Original source details: GELFAND-P000473

(found in terms of the inverse fn. of the Christoffel–Schwarz integral)

(a biorthog. system exists)

2. This is not a basis! (not every vector expands into a conv. series in this system)

~~Even~~ Moreover: if there is an expansion in L^2, then the limit — an analytic fn.! — and satisfies inf. many boundary conditions (the converse holds too).



Uncertain reading. The crossed-out word may read «Даже» (“Even”).

Original source details: GELFAND-P000473

It cannot be summed by the Abel method of the first order.

if

$$\sum_{\lambda_k > 0} e_k e^{\lambda_k t} v_k(x)$$

Uncertain reading. The coefficient is heavily retraced. The provisional reading is e_k.

Original source details: GELFAND-P000473

Undeciphered passage. Two short entries after $v_k(x)$ are heavily struck out. Their readings are unresolved.

Original source details: GELFAND-P000473

has a limit as $t \to 0$, then the limiting fn. is analytic.



Diagram and typed description. A wavy stroke runs above “fn.” and below “limiting”.

Original source details: GELFAND-P000473

(Discrediting the Fourier method for the elliptic eq.)

With certain nonseparated conditions one can solve it.

Uncertain reading. The adjective before “conditions” is abbreviated as «неразд.».

Original source details: GELFAND-P000473

Undeciphered passage. Two marks before “Reason” are crossed out. Their readings are unresolved.

Original source details: GELFAND-P000473

Reason for the poor behav.: the resolvent grows exp in the angles

Diagram and typed description. Two intersecting lines, broken strokes on the left, a dot at their crossing, and a circle and arrow on the right.



Original source details: GELFAND-P000473

On $[0, \pi - \varepsilon]$ it is overdetermined.

On $[0, \pi + \varepsilon]$, $0 < \varepsilon < \pi$ it remains complete !!! (I. Bernstein)



Uncertain reading. The lower bound is heavily retraced and is provisionally set as zero.

Original source details: GELFAND-P000473

On $[0, 2\pi]$ many orthog. fns. arise.

A problem in the theory of entire fns..

$$\int_0^\pi f(x) e^{\gamma k x} \sin kx \, dx = 0 \quad \Longrightarrow \quad F(\lambda) = \int_0^\pi f(x) e^{\gamma \lambda x} \sin \lambda x \, dx$$

$F(\lambda)$ is an entire fn. of exp type. It is 0 at integer points $F(n) = 0$, $n > 0$.

The specific features must be taken into account.

On $[0, \pi - \varepsilon]$ the type and indicator diagram work.

Uniqueness — ?

It is unknown what happens if one replaces k by λ_k.

GELFAND-P000474

I. M. Gelfand on Arnold's work.

Original source details: GELFAND-P000474

Diagram and typed description. The name and topic are double-underlined.

$$(\mathbb{R}^n, 0) \longrightarrow (\mathbb{R}, 0)$$

$f(x) = 0$ — hypersurf.

How does the hypersurf. behave in a neighbourhood of 0 — ?

$f \in C^\infty$; $f(0) = 0$, $df(0) = 0$. (crit. point).

(In fact consider $\mathbb{C}^n \longrightarrow \mathbb{C}$)

Equiv. hypersurfaces — differ by a change of variables

$$(\mathbb{R}^n, 0) \longrightarrow (\mathbb{R}^n, 0) \qquad \text{(diffeom.)}.$$

Simple hypersurf.: $f(x) = 0$

if one perturbs it, there will be finitely many orbits in jets of order N (the bound on the number of orbits does not depend on the index N).

Enumeration of the simple orbits:



Original source details: GELFAND-P000474

Diagram and typed description. Two chains are drawn at left. The lower chain forks at its end.





Original source details: GELFAND-P000474

Diagram and typed description. The right-hand chain has a downward branch at the third vertex. Its last links are broken.



E_6, E_7 and E_8

Next: Most orbits are simple (as a rule, the orbit is simple).

Original source details: GELFAND-P000474

Undeciphered passage. A short fragment after the opening parenthesis is struck out. Its reading is unresolved.

Nonsimple ones of codimension 6.

$$x_1^{n+1} + x_2^2 + \cdots * = 0$$

— corr. to the first type.

Uncertain reading. The first letter of the exponent $n+1$ is retraced. A separate star-like mark follows the ellipsis. A rule with upturned ends is drawn below the formula.

Original source details: GELFAND-P000474

Versal deformation.

$$F(x,\lambda) = 0, \qquad F(x,0) = f(x),$$
$$\lambda = (\lambda_1, \lambda_2, \ldots, \lambda_k)$$

Every other def. is equiv. to a def. induced from this one as follows:

$$G(x,\mu) = F(X(x,\mu), \Psi(\mu)) \quad \text{and} \quad X(y,0) = y, \quad \Psi(0) = 0$$

Original source details: GELFAND-P000474

Uncertain reading. The first arguments of G and X are heavily retraced and provisionally read as x. The right side clearly has $X(y,0) = y$.

Rule for constructing a vers. family: Take an orbit and a set transverse to the orbit.

Diagram and typed description. A curved line and a short transverse segment with a point at their intersection.

Original source details: GELFAND-P000474

$$F(x,\lambda) = f(x) + \sum a_i \left.\frac{\partial F}{\partial \lambda_i}\right|_{\lambda_i=0} = f(x) + \sum c_i \varphi_i(x) + O(\lambda^2).$$



Uncertain reading. The multiplier in the first sum is provisionally read as a_i. The evaluation subscript is $\lambda_i = 0$.

Original source details: GELFAND-P000474

φ_i give an infinitesimal versal deformation: if $\forall$ fn. $a(x)$ is repr. in the form



Original source details: GELFAND-P000474

Uncertain reading. The first fragment is heavily retraced and double-underlined. The provisional reading is φ_i «зад» (“give”).

$$a(x) = \sum \frac{\partial f}{\partial x_i} \cdot h_i(x) + \sum_{i=1}^{k} c_i \varphi_i(x)$$

$a(x)$ defines an infinitesim. vers. deform.

(φ_i gen. the local ring of smooth maps)



Undeciphered passage. A separate crossed-out entry precedes the parenthesis about Taylor expansion. Its reading is unresolved.

Original source details: GELFAND-P000474

(from the Taylor exp. of that fn.)

Important: the quotient ring by the Jacobian ideal $\left(\left\{\frac{\partial f}{\partial x_i}\right\}\right)$.

The quotient — a finite-dimensional space of dimension k.

GELFAND-P000475

$$f = z_1^{k+1} + z_2^2 + \cdots + z_n^2.$$

Then

$$\frac{\partial f}{\partial z_1} = z_1^k, \qquad \frac{\partial f}{\partial z_2} = z_2, \ \ldots,$$



Uncertain reading. The right-hand sides are written as monomials without numerical factors.

Original source details: GELFAND-P000475

hence the quotient ring is a space of dimension k.

$$\varphi_i = 1, z_i, z_i^2, \ldots, z_1^{k-1}$$



Uncertain reading. The first two powers after 1 have subscripts resembling i. The last has 1.

Original source details: GELFAND-P000475

Vers. deformation:

$$\underline{\lambda_0 + \lambda_1 z_1 + \cdots + \lambda_{k-1} z_1^{k-1} + z_1^{k+1} + z^2} \quad \text{— vers. deformation}$$



Original source details: GELFAND-P000475

Diagram and typed description. A rule with upturned ends is drawn below the polynomial. The final term is written z^2.

$\underline{F(z,\lambda) = 0.}$ The bifurc. diagram — the set of those λ, for which sing. points remain (in the vers. deformation).



Diagram and typed description. Four segments meet at a common point to the left of the theorem.



Original source details: GELFAND-P000475

Thm.: on an open set (bifurc. diag.) the sing. points will already be simple (Morse).



Diagram and typed description. "Bifurc. diag." is written in a bubble below "set".

Original source details: GELFAND-P000475

$z_1^{k+1} + z_2^2 = 0 \quad \| \quad \longrightarrow$ the bifurc. diag. of this point — Swallowtail.

$$z_1^{k+1} + z_2^2 + \lambda_{k-1} z_1^{k-1} + \cdots + \lambda_0$$

$$z_2^2 = -p_{k+1}(z_1); \qquad z_2 = \sqrt{-p_{k+1}(z_1)}.$$

sing. points $(z_2, P'(z_1)) = 0$, i.e.

$$\underline{P(z_1) = 0 \text{ and } P'(z_1) = 0}$$

(P has multiple roots)



Diagram and typed description. A single rule with upturned ends surrounds the two equalities below.

Original source details: GELFAND-P000475

Consider the complement of the bifurc. diagram and its fund. group. It is the braid group of the Coxeter group.

Consider the eq.

$$P(z,\lambda)=0, \quad |z|<\varepsilon \qquad \lambda \text{ such that there are no singularities}$$



Original source details: GELFAND-P000475

Uncertain reading. The first letter is heavily retraced. The provisional reading is P.

the homology of this space is $\neq 0$ only in ~~dim.~~



Original source details: GELFAND-P000475

Undeciphered passage. Traces remain after the struck-out "dim.". A full reading is unresolved.

half-dimension $n-1$.

It is a bouquet of μ spheres.

Original source details: GELFAND-P000475

Diagram and typed description. Four loops with a common point depict the bouquet.





Original source details: GELFAND-P000475

Undeciphered passage. The entry to the left of H^{n-1} is heavily struck out. Its reading is unresolved.

H^{n-1} has generators $e_1\ e_2 \dots\ e_\mu$.

The intersection index defines a scalar prod. (e_i, e_k).

$$n-1 \equiv 2 \pmod 4 \qquad \| \qquad \begin{matrix}\text{neg. def.}\\ \text{semidef.}\\ \text{indef.}\end{matrix} \qquad e_i^2=-2 \quad \text{(always)}$$



Original source details: GELFAND-P000475

Undeciphered passage. One line between "semidef." and "indef." is crossed out. Its reading is unresolved.

monodromy: rep. of the fund. gr. in



Original source details: GELFAND-P000475

Undeciphered passage. An entry after “in” is crossed out and followed by an ellipsis. Its reading is unresolved.

...

———— • ————

~~Atiyah~~



Original source details: GELFAND-P000475

Uncertain reading. The struck-out name may read «Атья» (“Atiyah”).

There are works by Atiyah, Bott,...: how to get rid of derivatives in Singer’s calculations? How can one study the topology of the world while sitting at one point? Finding explicit asymptotics for eqs. of the 2nd order (considerations of I. M. Gelfand, V. I. Arnold and others)

(will be in the next semester)

A. Shnirelman on Maslov’s work.

GELFAND-P000476

V. M. Buchstaber. (continuation).

$$A \overset{\text{addit.}}{=} \Lambda[[X]], \qquad X_n \text{ — addit. generators}$$
$$X_n \cdot X_m = C^n_{n+m} X_{n+m}$$

Original source details: GELFAND-P000476

Uncertain reading. Two short parallel strokes under “addit.” read as an equals sign.

$$\begin{array}{c}\mathrm{Ext}_A^{2,*}(\Lambda,\Lambda)\\ \|\\ \mathrm{Ker}\, d_3^*/\,\mathrm{Im}\, d_2^*\end{array}$$ in terms of the B-construction

1°.

$$d_3^*\colon \overline{A}^*\otimes\overline{A}^*\longrightarrow \overline{A}^*\otimes\overline{A}^*\otimes\overline{A}^*$$

$$A^*=\mathrm{Hom}_\Lambda^c(\Lambda[[X]],\Lambda)\overset{\text{add.}}{\simeq}\Lambda[x]$$



Original source details: GELFAND-P000476

Uncertain reading. The upper index of Hom reads c and the lower one Λ.

compact (nonzero val. on a finite number).

Diagram and typed description. "Compact" is written below Hom and connected to it by a stroke.

Original source details: GELFAND-P000476

$$\Delta\colon A^*\longrightarrow A^*\otimes A^*$$
$$\Delta x_n\longrightarrow x_n\otimes 1+1\otimes x_n+\sum d_{i,j}x_i\otimes x_j^*$$



Uncertain reading. A star is visible after x_j. It is absent from the later formula for Δx_n.

Original source details: GELFAND-P000476

$$\begin{array}{c}(\Delta x_n, x_i\otimes x_j)=d_{i,j}\\ \|\\ (x_n, x_i\cdot x_j)=(x_n, C_{i+j}^i x_{i+j})=C_{i+j}^i\delta_{n,i+j}\end{array}$$



Original source details: GELFAND-P000476

Diagram and typed description. A vertical equals sign joins the two lines of the pairing.

$$\Delta x_n = x_n \otimes 1 + 1 \otimes x_n + \sum C_n^i x_i \otimes x_{n-i}$$

And put $x_n = x^n$

$$\Delta x^n = (x \otimes 1 + 1 \otimes x)^n$$
$$d_3^*\colon \overline{\Lambda[x,y]} \longrightarrow \overline{\Lambda[x,y,z]}$$

$$d_3\left(\begin{array}{c} h(x,y) \\ \| \\ \sum h_{i,j}x^i y^j \end{array}\right) = \sum h_{ij}(\overline{\Delta}x^i)z^j - \sum h_{i,j}x^i\overline{\Delta}y^j =$$

Uncertain reading. The calculation has d_3 without a star before $h(x,y)$. The preceding line has d_3^*.

Original source details: GELFAND-P000476

$$\overline{\Delta}x^n = \begin{array}{c} \Delta x^n \\ \| \\ (\Delta(x))^n \\ \| \\ (x+y)^n \end{array} - x^n - y^n.$$



Diagram and typed description. Below Δx^n, vertical equals signs connect $(\Delta(x))^n$ and $(x+y)^n$.

Original source details: GELFAND-P000476

$$= h(x+y,z) - \cancel{h(x,z)} - h(y,z) - h(x,y+z) + h(x,y) + \cancel{h(x,z)}.$$



Original source details: GELFAND-P000476

Diagram and typed description. Both instances of $h(x,z)$ are crossed out. The minus and plus signs in front remain visible.

Ker d_3^*:

$$\boxed{h(x+y,z) + h(x,y) = h(x,y+z) + h(y,z)}$$

Denote these cycles by L.



Original source details: GELFAND-P000476

Diagram and typed description. The equality is enclosed in a rectangular box.

This is precisely the Lazard relation.

Original source details: GELFAND-P000476

Uncertain reading. The adjective before "relation" reads «лазаровское» ("Lazard").

$$\underline{\operatorname{Im} d_2^*} = \Lambda\{d_2^* x^n\}$$

$$0 \longrightarrow \operatorname{Im} d_2^* \longrightarrow L \longrightarrow \operatorname{Ext}_A^{2,n}(\Lambda, \Lambda) \longrightarrow 0$$

Calculation of the group Ext.

The eq. does not involve Λ. Hence it suffices to calc. 2 cases:

1) Λ — Z_p-module (p — prime)

2) $\Lambda = Q$

GELFAND-P000477

there remains X_{p^i}

$$\underline{A = \widehat{\prod} \otimes A_i}, \qquad A_i = Z_p[X_{p^i}]/(X_{p^i}^p) \underset{Z_p}{\otimes} \Lambda$$



Original source details: GELFAND-P000477

Uncertain reading. The product sign has a hat. A tensor sign is written immediately to its right.

$$H^*(A_i) = \Lambda_p(u_i) \otimes Z_p[v_i], \qquad \deg u_i = p^i, \quad \deg v_i = p^{i+1}$$

$$u_i \in \operatorname{Ext}^{1,p^i}; \qquad v_i \in \operatorname{Ext}^{2,p^{i+1}}$$

$$\operatorname{Ext}_A^{2,*} = \left\{ \underbrace{u_i u_j, \quad i < j, \quad v_k}_{\text{generators}} \right\}.$$



Original source details: GELFAND-P000477

Uncertain reading. The sign between i and j is heavily retraced. It is provisionally set as $i < j$.

~~This~~ But: symmetric ones are needed. $\underline{h(x,y) = h(y,x)}$



Original source details: GELFAND-P000477

Uncertain reading. The struck-out word before "But" may read «Это» ("This").

There are noncommut. one-dimensional groups!! (if there is torsion)

(corr. to the cycles $u_i u_j$)

Example: $x + y + axy^p$, where $a^2 = 0$ over $Z_p[a]/(a^2)$.

$x+y+axy^p$, где $a^2=0$ над $Z_p[a]/(a^2)$.

Original source details: GELFAND-P000477

Diagram and typed description. The term axy^p and the condition $a^2 = 0$ occur on the same line.

This is a noncommut. formal group!!

There are as many of them as there are cycles.

v_k corr. to commut. groups

$$h(x,y) = (x+y)^{p^{k+1}} - x^{p^{k+1}} - y^{p^{k+1}}$$

coeff. divisible by p (only)

коэфф. дел. на p (только)

Uncertain reading. The word in parentheses reads «только» (“only”).

Original source details: GELFAND-P000477

$L_{p^{k+1}}(x,y) = \frac{h(x,y)}{p}$

Diagram and typed description. A rule with upturned ends is drawn below the formula.

Original source details: GELFAND-P000477

(in $\forall$ dimension one generator each)

That is all for this semester.

(в $\forall$ размерности по 1-й образующей)

В этом семестре конец.

Original source details: GELFAND-P000477

Diagram and typed description. The last line has both a wavy underline and a broken straight underline.

GELFAND-P000478

12/II-73. Gelfand sem.

Plan: 1. Buchstaber, Mishchenko: Topology (Sullivan's work)

2. Works by Deligne and Langlands

V. Buchstaber. On Sullivan's first paper.

M^n — manif.

A smoothing of M^n — is a sm. manif. N^n and a homot. equiv. $N^n \xrightarrow{f} M^n$



Diagram and typed description. Three arrows connect the two smooth manifolds and their common target.

$$\begin{array}{ccc} N_1^n & \xrightarrow{f_1} & M^n \\ {\scriptstyle g}\downarrow & \nearrow_{f_2} & \\ N_2^n & & \end{array}$$

Original source details: GELFAND-P000478

Equiv. $\Longleftrightarrow \exists$ a diffeom. g, such that this square commutes (up to homotopy).

$S(M^n)$ — the set of classes of equiv. smoothings.

Undeciphered passage. A short entry above "Milnor" is heavily crossed out. Its reading is unresolved.

Original source details: GELFAND-P000478

Milnor: Card $S'(S^7) = 28$.

Uncertain reading. A short stroke is visible between the first S and the parenthesis. It is set as S'.

Original source details: GELFAND-P000478

Description of $S(M^n)$ — ?

Sullivan considers in M^n a fixed piecewise-linear structure.

(M^n — a polyhedron)

and solved the prob. in this formulation:

(in place of a diffeom. — a piecewise-lin.

Undeciphered passage. A heavily crossed-out entry follows "piecewise-lin.". Its reading is unresolved.

Original source details: GELFAND-P000478

homeomorphism)

Obtain $PL(M^n)$.

Here always $\underline{\underline{PL(S^n) = \{S^n\}}}$ — where the Poincaré prob. has been solved (for $n \geqslant 5$).

Consider on M^n (Vect.) a bundle ξ, stable (of large dim.).



Original source details: GELFAND-P000478

Undeciphered passage. The old entry before “bundle” is inked over. “Vect.” is inserted above it.

~~trivial in several degrees~~



Original source details: GELFAND-P000478

Uncertain reading. The struck-out phrase is provisionally read as «несколько степен. тривиальное».

T_ξ — the Thom complex of the bundle ξ,



Original source details: GELFAND-P000478

Diagram and typed description. The formula has a bottom rule with upturned ends.

$$\underline{\lfloor T_\xi = \frac{D(\xi)}{S(\xi)} \rfloor}$$

D — bundle of balls,

S — bundle of spheres.

dim $\xi = m$.

$$\underset{\text{at a point.}}{S^m} \overset{i}{\subset} T_\xi$$



Original source details: GELFAND-P000478

Diagram and typed description. A stroke connects “at a point” to the left-hand sphere.



Original source details: GELFAND-P000478

Diagram and typed description. In the diagram at right, the point maps by inclusion into the base.

$$\begin{array}{ccc} \mathbb{R}^m & \longrightarrow & \xi \\ \downarrow & & \downarrow \\ * & \hookrightarrow & M^n \end{array}$$

The bundle ξ is called J-trivial, if $\exists$ a map φ; such that



Original source details: GELFAND-P000478

Diagram and typed description. The first arrow is labelled i. The mark at the right-hand sphere and the large crossed-out entry to its right remain unresolved. The arc from the left sphere to the right sphere is labelled 1.



(homot.)

i.e. $\deg(\varphi \cdot i) = 1$



Original source details: GELFAND-P000478

Uncertain reading. A dot is visible between φ and i.

(the choice of $*$ does not matter since M^n is assumed connected).

$K_J(M^n)$ — the group of stab. bundles over M^n, each of which is J-trivial

GELFAND-P000479

Atiyah's thm.: (Mat. $10:5$)

Original source details: GELFAND-P000479

Diagram and typed description. A short reference follows the name, «Мат. 10:5».

constr. a map



Original source details: GELFAND-P000479

Undeciphered passage. The first letter of the struck-out entry resembles S. A full reading is unresolved.

$$S(M^n) \longrightarrow K_J(M^n).$$

$$N^n \longrightarrow M^n \qquad \text{difference.}$$

~~Sullivan:~~

$$\text{~~}0 \longrightarrow PL(M^n) \longrightarrow K_{PLJ}(M^n)\text{~~}$$

~~always~~



Original source details: GELFAND-P000479

Diagram and typed description. The name, sequence and word “always” are crossed out and remain legible underneath.

and

$$0 \longrightarrow PL(M^n) \longrightarrow K_{PLJ}(M^n)$$

Undeciphered passage. An entry after the second $K_{PLJ}(M^n)$ is crossed out. It may read $\to 0$.

Original source details: GELFAND-P000479

for $n \not\equiv 0, 2 \bmod 4$



Uncertain reading. The comparison sign has three horizontal strokes crossed by one stroke.

Original source details: GELFAND-P000479

$n \equiv 0 \bmod 4$	cokernel	Z
$n \equiv 2$ —//—	—//—	Z_2.



Diagram and typed description. The second row has ditto marks under “mod 4” and “cokernel”.

Original source details: GELFAND-P000479

Sullivan calc. the homot. groups of the repr. space $K_{PLJ}(M^n)$.

Uncertain reading. The loop on the descending stroke is retraced. The last letter of «группп» may be a second «п».

Original source details: GELFAND-P000479

For $K_J(M^n)$ it has not been done. A seq. for $S(M^n)$ exists too.

GELFAND-P000480

19/II-73. R. L. Dobrushin.



Original source details: GELFAND-P000480

Diagram and typed description. The month is written as a Roman numeral. Two lines with cross-strokes are drawn below the name.

On field theory.

Gelfand: 2 problems: — · —

1) quantize existing eqs.

Original source details: GELFAND-P000480

Uncertain reading. The end of the abbreviation is provisionally read as «существующ.» (“existing”).

2) write eqs. that actually correspond (phys.)

Original source details: GELFAND-P000480

Uncertain reading. The abbreviation after “actually” reads «ответ.».

— · —

A method of constr. objects satisfying the Wightman axioms (probab. objects).

Principal author — Nelson.

One can (almost) obtain the res. of Glimm and Jaffe.



Original source details: GELFAND-P000480

Uncertain reading. The manuscript writes Jaffe as «Джеаффе», with «е» before «а».

Random variable: $\xi_t, \quad t \in \mathbb{R}^{\nu+1}$



Original source details: GELFAND-P000480

Uncertain reading. The first sign in the exponent resembles Latin v or Greek ν. It is provisionally set as ν.

1) it is Eucl. invari.

2) Markov prop.

26/II-73 V. M. Buchstaber. $hs(M^n)$ — (homotopic) smoothings.



Diagram and typed description. “(homotopic)” is inserted above “smoothings”, with a pointer to the word.

Original source details: GELFAND-P000481

$ht(M^n)$ — homot. triangulations.
is described.



Diagram and typed description. “Is described.” is connected by a stroke to the bracket below $ht(M^n)$.

Original source details: GELFAND-P000481

Hauptvermutung — a homeomorphism (of manifolds) can be replaced by a piecewise-lin. homeom. (if M is simply conn. and there is in H^3 no 2-torsion)



Diagram and typed description. “Of manifolds” is inserted in a callout after “a homeomorphism”.

Original source details: GELFAND-P000481

Let $\alpha \in hs(M^n)$ (hom. smoothing).

$$\alpha \underset{\text{assoc.}}{\mapsto} \underbrace{\xi \longrightarrow M^n}_{\text{bundle (vect.)}} \qquad \text{smooth.}$$



Uncertain reading. The abbreviation under the first arrow is provisionally read as «сопст.». Another possible reading is «сопост.».

Original source details: GELFAND-P000481

$$f\colon N^n \longrightarrow M^n;$$
$$\exists\, g\colon M^n \longrightarrow N^n; \qquad f \circ g \sim 1, \quad g \circ f \sim 1.$$
$$\tau_{M^n} + g^* \nu_{N^n} \qquad (\nu_{N^n} = -\tau_{N^n} \text{ mod triv.})$$

Original source details: GELFAND-P000481

Uncertain reading. The sign for the normal bundle resembles v. It is provisionally set as ν.

Ex. Prove that 2 equiv. smoothings induce isom. bundles ξ.

The resulting smooth bundle ξ is J-trivial, i.e.



Original source details: GELFAND-P000481

Diagram and typed description. The square has an arrow labelled γ with a heavily retraced sign.

$$\begin{array}{ccc} \xi & \xrightarrow{\gamma} & M^n \times R^N \\ \downarrow & & \downarrow \\ M & \xrightarrow{\mathrm{id}} & M \end{array}$$

and γ is a proper map and a homot. equiv.

Original source details: GELFAND-P000481

Uncertain reading. The sign before "is" is heavily retraced. It is provisionally set as γ.

~~$T(\xi)$ equiv.,~~



Original source details: GELFAND-P000481

Uncertain reading. After the crossed-out $T(\xi)$, «эквив.» ("equiv.") is a provisional reading. «трив.» ("triv.") remains possible.

Thom complex

2nd def. — $\exists$ a map $T(\xi) \longrightarrow S^N$, such that



Original source details: GELFAND-P000481

Diagram and typed description. "Thom complex" is underlined with an arrow pointing to $T(\xi)$.

the composite



Original source details: GELFAND-P000481

Diagram and typed description. The lower arrow denotes the composite.

$$S^N \subset T(\xi) \longrightarrow S^N$$

is a homot. equiv.

Equivalence — thm. of Dold (technical, trivial in idea)



Diagram and typed description. Dold's name is underlined.

Original source details: GELFAND-P000481

GELFAND-P000482

5/III-73 Gelfand's Sem..

Theorem. ~~F. A. Berezin~~ Lomonosov

Uncertain reading. The heavily crossed-out name is provisionally read as "F. A. Berezin".

Original source details: GELFAND-P000482

R — a family of pairwise commut. (in Banach space B) op., containing a completely cont. op. $A \neq 0$.



Diagram and typed description. "In Banach space B" is written in a callout after "op.".

Original source details: GELFAND-P000482



Uncertain reading. The last sign is open on the right and resembles C. It is provisionally set as 0.

Original source details: GELFAND-P000482

Then R has a common (nontriv.) invariant subsp..



Diagram and typed description. "Nontriv." is inserted between "common" and "invariant".

Original source details: GELFAND-P000482

(generalization of the Aronszajn–Smith theorem)



Diagram and typed description. The first surname reads «Ароншайна» in Russian.

Original source details: GELFAND-P000482

The proof works in the case of an LCS, short and simple.

Original source details: GELFAND-P000482

Uncertain reading. A short sign before "short" is heavily crossed out. Its reading is unresolved.

Proof. S' — a closed ball, $r = 1$ centered at x_0, such that
(in B)

Original source details: GELFAND-P000482

Diagram and typed description. "In B" is inserted below "ball" in a callout.

Original source details: GELFAND-P000482

Diagram and typed description. The first occurrence of the ball symbol S' is primed. The manuscript subsequently writes S.

$$\inf_{x \in S} \|Ax\| > 1/2$$

$$\begin{matrix} Ax_0' \neq 0 \\ \|x_0'\| = 1 \end{matrix} \quad \text{and we take} \quad \|A\| \cdot x_0' = x_0.$$

Original source details: GELFAND-P000482

Uncertain reading. The letter between the norm bars is heavily retraced. A provisional reading is $\|A\|$.

$\overline{AS}$ — a compact set that does not contain zero.

Consid. the algebra $\mathcal{R}$ with 1, generated by the family R (without closure).

Original source details: GELFAND-P000482

Diagram and typed description. The symbol inserted above "algebra" is provisionally set as $\mathcal{R}$.

$$\forall y \in B, \qquad \mathcal{R}y \quad \text{— lin. set.}$$

It is easy to see that $\mathcal{R}y$ is invar. under $\mathcal{R}$.

$\overline{\mathcal{R}y}$ — an inv. subsp..

We must prove that it can be nontriv..

Let $y \in \overline{AS}$. We must check that $\exists y$; $\mathcal{R}y$ is not dense.

Suppose otherwise, then

Uncertain reading. The crossed-out word after "then" is undeciphered. «Оно» ("it") is a possible reading.

Original source details: GELFAND-P000482

$$\forall y \in \overline{AS} \quad \exists T \in \mathcal{R}, \qquad \|Ty - x_0\| < 1.$$

From the compactness of $\overline{AS}$ it follows that $\exists T_1, \ldots, T_n$

$$\forall y \; \exists i \qquad \|T_i y - x_0\| < 1,$$

$$\forall y \in AS \quad \{T_1 y, \ldots, T_n y\} \cap S \neq \varnothing.$$

Let $f(t) \in C(0, +\infty)$



Diagram and typed description. The graph of $f(t)$, the marks 1 on both axes and the point on the t-axis.



Original source details: GELFAND-P000482

GELFAND-P000483

Consid.

$$\Phi y \overset{\#}{=} \frac{\sum_{1}^{n} f(\|T_i y - x_0\|) T_i y}{\sum_{j} f(\|T_j y - x_0\|)} \qquad \text{(convex comb.)}$$



Uncertain reading. A sign resembling # is written above and to the left of the equals sign.

Original source details: GELFAND-P000483

$$\Phi\colon \overline{AS} \longrightarrow S$$

This is a cont. function on $\overline{AS}$.

Consid. $\Phi A\colon S \longrightarrow S$,



Uncertain reading. A sign after ΦA is overwritten. It may be x.

Original source details: GELFAND-P000483

where the image of ΦA is compact and it is cont..

By Schauder's thm. $\exists$ a fixed point, i.e.,

$$\sum_1^n \alpha_i T_i A x = x, \qquad \alpha_j = \frac{f(\|T_j y - x_0\|}{\sum_i f(\|T_i y - x_0\|)}$$



Diagram and typed description. Both arguments show x_0. The closing parenthesis after the norm is absent in the numerator.

Original source details: GELFAND-P000483

$T = \sum \alpha_i T_i A$ is completely continuous.

$\exists x\colon Tx = x$. Hence an eigenvect. with eigenval. 1 — a nontriv. invar. subsp. (even finite-dimensional). Hence $\mathcal{R}$ has an invar. subsp..

Diagram and typed description. End mark with an oval above two crossing strokes and a dot to the right.

Original source details: GELFAND-P000483

(This does not mean there is a finite-dimensional one in general).

Corollary. If a comm. (Banach) algebra has an elem.,



Diagram and typed description. "Banach" is inserted after "comm.".

Original source details: GELFAND-P000483



Uncertain reading. A sign resembling «и» (“and”) and an undeciphered word are crossed out after “elem.”.

Original source details: GELFAND-P000483

(by which)
mult. is completely cont., then ∃ a nontriv. ideal.



Diagram and typed description. “By which” is inserted after “mult.”.

Original source details: GELFAND-P000483

Henkin. (announcement)

Let there be in C^n a convex dom. $D \subset C^n$, given by the eq. $\rho(z) < 0$.

Uncertain reading. The letter D before the inclusion sign is heavily retraced.

Original source details: GELFAND-P000483

Leray integral formula for bounded holom. functions:

$$f(z) = \frac{(n-1)!}{(2\pi i)^n} \int_{\zeta \in \partial D} \frac{f(\zeta)\, \omega'\left(\frac{\partial \rho}{\partial z}(\zeta)\right) \wedge \omega(\zeta)}{\left(\sum_{k=1}^{n} \frac{\partial \rho}{\partial \zeta_k}(\zeta)(\zeta_k - z_k)\right)^n}$$



Original source details: GELFAND-P000483

Uncertain reading. The sign ρ in the numerator of the derivative in ω' is heavily retraced.

1) Leray-type integral:

$$f_g(z) = \cdot\ \cdot \int \frac{g(\zeta)\cdots}{\cdots} \qquad g(\zeta) \text{ — a function on the boundary.}$$

$$f \longrightarrow [f(\zeta)g(\zeta) - f_g(\zeta)] \quad \text{— a completely cont. operator}$$

and a Hölder condition with exp. $1/2$

2) $\rho(z)$ — strictly plurisubharm..

Diagram and typed description. Contour to the left of “Then”.



Original source details: GELFAND-P000483

Then D — ~~dom.~~ is a closed subset of a strictly convex dom., approaching the boundary transversely.

Uncertain reading. The crossed-out word is provisionally read as «обл.» (“dom.”), possibly «область» (“domain”).

Original source details: GELFAND-P000483

(follows from Oka’s thm.)

Diagram and typed description. A tilted oval with an interior arc. The arc reaches the upper edge and ends near the lower edge.



Original source details: GELFAND-P000483

3) in item 2) write out the extension from the subset with estimates! (in the class of bounded functions)

The converse is also true: such a subset is ~~a domain~~ a bounded domain of holomorphy.

Uncertain reading. The crossed-out word is provisionally read as «область» (“domain”), possibly «обл.» (“dom.”).

Original source details: GELFAND-P000483

4) Corollary: for functions anal. inside and cont. in the closure, the space of maximal ideals $=$ the closure of the domain.

GELFAND-P000484

F. A. Berezin.

Quantization problem.

M — sympl. manifold (ω — a form [illegible] with matrix ω_{ik}; ω^{ik} — inverse matrix)

Uncertain reading. A heavily retraced sign follows “form”. Possible readings are 2 or ξ.

Original source details: GELFAND-P000484

$$[f, g] = \sum \omega^{ik} \frac{\partial f}{\partial x^i} \frac{\partial g}{\partial x^k}$$

Quantization: a family of assoc. rings A_h with elements $f(x)$ (functions on M)

$$f_1 * f_2 = g(x \mid h)$$

$$\left.\begin{array}{ll} 1) & g(x \mid 0) = f_1(x) \cdot f_2(x) \\ 2) & \dfrac{\partial}{\partial h}(f_1 * f_2 - f_2 * f_1)\Big|_{h=0} = [f_1, f_2] \end{array}\right\} \quad \text{(correspondence principle)}.$$

Several further reqs. (less obligatory)

3) all A_h — algebras with 1, corresp. $f_0 \equiv 1$.

4) A_h — an algebra with trace (def. on a distinguished set of elements in A_h).



Uncertain reading. The ending of the word “elements” was rewritten. The earlier reading is unresolved.

Original source details: GELFAND-P000484

$$\mathrm{Sp}(f_1 * f_2) = \mathrm{Sp}(f_2 * f_1)$$

and

$$\mathrm{Sp}\, f = c \int f \, d\mu,$$

where $d\mu$ — the nat. measure on the manifold (a power of ω).

Diagram and typed description. The parenthetical reads «степень ω» (“a power of ω”).

Original source details: GELFAND-P000484

Req. of math. naturalness — functoriality with respect to canonical Diffeomorphisms (with respect to some family of maps — some fixed category).

A solution is known when $M \in$ a certain class (2 classes of Kähler manifolds).

1) dom. in C^n
2) compact symm. manifolds,



Diagram and typed description. A common stroke runs to the left of both items and below them.

Original source details: GELFAND-P000484

Fock space.

Uncertain reading. A sign above the start of the heading is heavily blacked out. Its reading is unresolved.

Original source details: GELFAND-P000484

$$M = C^n \qquad \omega = \sum dz_i \wedge d\bar{z}_i.$$

Functions — entire functions $f(z, \bar{z})$ (expan. in x, y in a series converg. everywhere)

$$(f_1 * f_2)(z, \bar{z}) = \frac{1}{h^n} \int f_1(z, \bar{v}) f_2(v, \bar{z}) e^{-\frac{1}{h}(z-v)(\bar{z}-\bar{v})}\, dv\, d\bar{v}$$

Important: the structure of lin. rep. of this ring.

Let $\varphi(z)$ — ordinary entire functions satisfying

$$(\varphi, \varphi) = \frac{1}{h^n} \int |\varphi(z)|^2 e^{-\frac{z\bar{z}}{h}}\, dz\, d\bar{z} < +\infty \qquad \text{(space } F_2\text{)}$$

There acts a lin. rep. of the ring A_h:

$$(\hat{f}\varphi)(z) = \frac{1}{h^n} \int f(z, v) \overline{\varphi(v)}\, e^{-\frac{1}{h}(v-z)\bar{v}}\, dv\, d\bar{v},$$

f — Wick symbol.

Diagram and typed description. The bar is over $\varphi(v)$. The preceding factor $f(z, v)$ has no bar over v.

Original source details: GELFAND-P000484

One more ring of operators:

$$(\hat{f}\varphi)(z) = \frac{1}{h^n}\int \mathring{f}(v,\bar{v})\varphi(v)e^{-\frac{1}{h}(v-z)\bar{v}}\,dv\,d\bar{v},$$

$\mathring{f}$ — anti-Wick symbol.

$$(\hat{a}_k\varphi)(z) = \frac{\partial\varphi}{\partial z_k}, \qquad (\hat{a}_k^*\varphi)(z) = z_k\varphi.$$

$$\hat{f} = \sum f_{mn}\hat{a}^{*m}\hat{a}^n \quad \longleftrightarrow \quad f(z,\bar{z}) = \sum f_{mn}\bar{z}^m z^n$$
$$\hat{f} = \sum \mathring{f}_{mn}\hat{a}^n\hat{a}^{*m} \quad \longleftrightarrow \quad \mathring{f}(z,\bar{z}) = \sum \mathring{f}_{mn}z^n\bar{z}^m.$$

Original source details: GELFAND-P000484

Uncertain reading. The sign at the upper right of the first $\hat{f}$ is overwritten. A possible reading is $*$.



Original source details: GELFAND-P000484

Uncertain reading. The exponents on the first $\hat{a}$ and the first z of the lower row are heavily retraced. Both are provisionally read as n.

GELFAND-P000485

Consid. $e_{\bar{v}}(z) = e^{\frac{1}{h}\bar{v}z}$ (coherent states or Poisson vectors).

~~$f\ldots$~~

Original source details: GELFAND-P000485

Uncertain reading. The letter f is visible in the crossed-out entry. The rest is undeciphered.

Consid. now

$$\hat{f} \longleftrightarrow f(v,\bar{v}) = \frac{(\hat{f}e_{\bar{v}}, e_v)}{(e_{\bar{v}}, e_v)} \quad \text{(extension)} =$$
$$= \mathrm{Sp}(\hat{f}P_v).$$



Original source details: GELFAND-P000485

Diagram and typed description. In both rows of the fraction the first e has subscript $\bar{v}$ and the second e has subscript v.

(P_v — orthog. proj. onto e_v)

$$\hat{f} = \int \mathring{f}(v, \bar{v}) P_v \, dv \, d\bar{v} \qquad \text{(ext. of anti-Wick symbols).}$$

Duality:

1.

Wick	↑	op. ⟶ symbol
anti-Wick		symb. ⟶ operator

Diagram and typed description. A heavily retraced upward arrow before "op." points toward the wavy underline. Its connection with the two rows is unresolved.

Original source details: GELFAND-P000485

2.

$$\hat{f} \text{ — bd.} \Longrightarrow f \text{ bd.}$$
$$\mathring{f} \text{ — bd.} \Longrightarrow \hat{f} \text{ bd.}$$

3.

$$\hat{f} \text{ comp.} \Longrightarrow f \to 0$$
$$\mathring{f} \to 0 \Longrightarrow \hat{f} \text{ comp.}$$



Uncertain reading. The arrow toward 0 in the second row is heavily retraced. It is provisionally set as $\to$.

Original source details: GELFAND-P000485

4. Nuclearity (analog.)

$$\operatorname{Sp} \hat{f} = \frac{1}{h^n} \int f(z, \bar{z}) \, dz \, d\bar{z} = \frac{1}{h^n} \int \mathring{f}(z, \bar{z}) \, dz \, d\bar{z}.$$

Conversion formula:

$$f(z, \bar{z}) = \frac{1}{h^n} \int \mathring{f}(v, \bar{v}) e^{-\frac{1}{h}(z-v)(\bar{z}-\bar{v})} \, dv \, d\bar{v}.$$

At $h/2$ one obtains the Weyl symbol. (Gelfand's remark: (these are symbols) of Poincaré .)



Diagram and typed description. "These are symbols" is inserted above, before "of Poincaré".

Original source details: GELFAND-P000485

General construction.

H — Hilbert space, M — set with a measure, $\alpha \in M$, measure $d\alpha$.

e_α — overcompl. system, if

$$(f, f) = \int |(f, e_\alpha)|^2 \, d\alpha.$$

Consid. then the correspondence:

$$\hat{A} \longrightarrow \frac{(\hat{A}e_\alpha, e_\alpha)}{(e_\alpha, e_\alpha)} = \underset{\operatorname{Sp}(\hat{A}\hat{P}_\alpha)}{A(\alpha)} \qquad \text{(covar. symbol)}.$$



Diagram and typed description. Two strokes and the trace expression appear below $A(\alpha)$.

Original source details: GELFAND-P000485

contravar. symbol.

$$\hat{A} = \int \mathring{A}(\alpha)\hat{P}_\alpha \, d\alpha.$$

Earlier: $e_\alpha = e^{\bar{v}z}$, $\alpha = (v, \bar{v})$.

All thms. hold.

Another method:

$H \hookrightarrow L^2(M)$, $\hat{T}$ — orthog. projector from $L^2(M)$ into H.



Uncertain reading. The heavily retraced sign between H and $L^2(M)$ is provisionally read as a rightward inclusion arrow.

Original source details: GELFAND-P000485

$$(\hat{B}f)(\alpha) = \mathring{A}(\alpha)f(\alpha) \quad \text{— operator in } L^2(M).$$

Then $\hat{A} = \hat{T}\hat{B}\hat{T}$.



Diagram and typed description. A stroke runs below and to either side of the formula.

Original source details: GELFAND-P000485

GELFAND-P000486

Example: $e^{i(p,x)}$ in bounded domains.

Let $\varphi(x)$ be an arbit. convex (downward) function of a real var. x.

Diagram and typed description. "Downward" is inserted above, after "convex". An arc is drawn beneath the word.

Original source details: GELFAND-P000486

Then

$$\int \varphi(A)\, d\mu \leqslant \operatorname{Sp} \varphi(\hat{A}) \leqslant \int \varphi(\mathring{A})\, d\alpha$$

Uncertain reading. The left differential is provisionally read as $d\mu$. Another possible reading is $d\alpha$.

Original source details: GELFAND-P000486



Diagram and typed description. A stroke runs below and to either side of the inequality.

Original source details: GELFAND-P000486

Left side — a consequence of Jensen's ineq..

Right side — $\rightarrow$

$$\boxed{\operatorname{Sp}(P\varphi(A)P) \geqslant \operatorname{Sp} \varphi(PAP)}$$

Uncertain reading. The sign before the box is provisionally set as a right arrow. It may be crossed out.

Original source details: GELFAND-P000486

Uncertain reading. On the right side the parenthesis merges with adjacent strokes. A provisional reading is $\operatorname{Sp} \varphi(PAP)$.

Original source details: GELFAND-P000486

Consid. the domain $G \subset \mathbb{C}^n$,

in it there exists a nat. | Kähler metric.



Diagram and typed description. A vertical stroke precedes "Kähler".

Original source details: GELFAND-P000486

We construct a ring ~~of~~ from real-anal. functions $f(z, \bar{z})$

Uncertain reading. A short sign after “ring” is crossed out. The provisional reading is «от» (“of”).

Original source details: GELFAND-P000486

$$f_1 * f_2 = \int f_1(z, \bar{v}) f_2(v, \bar{z}) G_h(v, \bar{v}, z, \bar{z})\, dv\, d\bar{v}$$

$$G_h = c(h) \left[\frac{K(z, \bar{z}) K(v, \bar{v})}{K(z, \bar{v}) K(\bar{z}, v)} \right]^{1/h},$$

(one can prove that $K(z, \bar{v}) \neq 0$)

where K — the Bergman kernel fn..



Diagram and typed description. The diagonal factors are in the numerator. The second denominator factor is $K(\bar{z}, v)$. The exponent is $1/h$.

Original source details: GELFAND-P000486

$$c(h) = h^{-\dim G} c_1(h),$$

$c_1(h)$ is cont. as $h \to 0$. (arbitrary)

$\longrightarrow$ unknown if $\exists$ a quantiz. also satisfying 3).



Diagram and typed description. The rightward arrow from “(arbitrary)” points to the underlined marginal note.

Original source details: GELFAND-P000486

Then all reqs. are met except 3).

on the basis of 3).
in a nat. way.

If G — a homog. dom., this too is met and $c_1(h)$ is specified



Diagram and typed description. Two callouts, one above the other, appear on the right above “is specified”.

Original source details: GELFAND-P000486

If G is even symmetric, and motions — autom. of the ring, then only this.
Overcompl. system here (for a homog. dom.)

$$M = G \subset \mathbb{C}^n = \mathbb{R}^{2n}$$

$e_v(z) = (K(z, \bar{v}))^{1/h}$ (for a homog. domain).

Uncertain reading. A sign below the exponent $1/h$ is crossed out. It may be an earlier exponent.

Original source details: GELFAND-P000486



Diagram and typed description. A stroke runs below and to either side of the formula.

Original source details: GELFAND-P000486

Hilbert space:

$$H = \{f : \int |f(z)|^2 K^{1/h}(z, \bar{z})\, d\mu(z) < +\infty \quad f \text{ (holom.)}\}.$$

Uncertain reading. A heavy additional stroke below $<$ resembles a crossed-out "2". A possible reading is $\leqslant$.

Original source details: GELFAND-P000486



Diagram and typed description. The weight has exponent $1/h$. There is no visible minus before the exponent.

Original source details: GELFAND-P000486

$\mu(z)$ — an invar. measure generated by the Bergman metric.
A larger space — all functions.
In the gen. case it is unknown whether $K(z, \bar{v})$ can become 0.
Covar. symbols: continuations are analytic on all of $G \times \bar{G}$.

(complex)
Compact case. Comp. symmetric space.



Diagram and typed description. "Complex" is inserted in a callout after "Comp.".

Original source details: GELFAND-P000486

Consid. the potential of the Kähler metric, i.e. $\Phi(z, \bar{z})$

GELFAND-P000487

Consid.

$$e^{\frac{1}{h}\Phi(z,\bar{z})} = K_h(z,\bar{z}) \qquad \left(\Phi \text{ is def. by the cond. } \omega^{ij} = \frac{\partial^2 \Phi}{\partial z_i \partial \bar{z}_j}\right).$$



Diagram and typed description. The two indices i, j on ω are written above.

Original source details: GELFAND-P000487

At $h = \underline{\underline{\frac{1}{n}}}\ \Phi(z,\bar{z})$ extends and there exists a single-valued fn.

$$K_h(z,\bar{v})$$

and the whole preceding theory.



Diagram and typed description. The formula $h = 1/n$ has a double stroke underneath with turned-up ends.

Original source details: GELFAND-P000487

Then the Hilbert space H_α is finite-dimensional and dim is easily computed.

Uncertain reading. The heavily retraced subscript is provisionally read as α. Another possible reading is h.

Original source details: GELFAND-P000487

Lobachevsky plane:

$$K^{1/h} = (1 - z\bar{z})^{+2/h}$$



Diagram and typed description. A plus sign is written before $2/h$.

Original source details: GELFAND-P000487

Autom. of the space generate autom. of the ring.

One obtains a projective rep. of the Lobachevsky (autom. of) plane.



Diagram and typed description. “Autom.” is inserted in a callout after “rep.”.

Original source details: GELFAND-P000487

GELFAND-P000488

12/III-73 Gelfand's Sem..

V. M. Buchstaber.

$S(M^n)$ — set of smoothings on M^n
$hS(M^n)$ — homot. smoothings
$t(M^n)$ — triangulations
$ht(M^n)$ — hom. triangul.

— · —

Consid. the set $hS(M^n)$.

On it, consid. smooth vect. bundles.

Original source details: GELFAND-P000488

Diagram and typed description. An arrow runs down from ξ to M^n.

$$\begin{array}{c} \xi \\ \downarrow \\ M^n \end{array}$$

J-triv. bundles (fibrewise homot. triv.), i.e.

Original source details: GELFAND-P000488

Uncertain reading. The first abbreviation is provisionally read as «псл.», possibly «посл.», for "fibrewise".



Original source details: GELFAND-P000488

Diagram and typed description. Square with an underline whose ends turn upwards.

$$\begin{array}{ccc} \xi & \xrightarrow{\varphi} & M^n \times \mathbb{R}^N \\ \downarrow & & \downarrow \\ M^n & \xrightarrow{\mathrm{id}} & M^n \end{array}$$

$N = \dim \xi$

Original source details: GELFAND-P000488

Diagram and typed description. The equality has a double underline.

φ — a proper homotop. equivalence.

$\Phi(M^n)$ — set of smooth J-triv. bundles on M^n. (up to trivial ones).

Let



Original source details: GELFAND-P000488

Diagram and typed description. The heavily retraced subscript on N is provisionally set as ξ. Another possible reading is ζ.

$$\alpha : \{ \quad N^n_\xi \underset{g}{\overset{f}{\rightleftarrows}} M^n \quad \}$$

g — a homot. inverse.

From α we construct an elem. of the group $\Phi(M^n)$



Original source details: GELFAND-P000488

Diagram and typed description. A stroke runs below the sum. An arrow points from it to the base.

$$\underbrace{(g^*(\nu_N) + \tau_M)}$$
$$\downarrow \quad \text{it is } J\text{-triv.}$$
$$M^n$$

(ν_N — norm. bundle of M^n — for an embedd. in a high-dimensional space)

invar. elem. of the K-functor.



Original source details: GELFAND-P000488

Uncertain reading. The explanation for ν_N reads M^n.

$$g \text{ — ident.} \Longrightarrow \nu_N + \tau_M \underset{\text{def}}{=} \text{triv.}$$
$$g \text{ — hom. equiv.} \Longrightarrow \ldots$$

(difficult to prove carefully —
— Atiyah–Dold thm.)
Matematika 10:5 Thom spaces. (Atiyah)



Original source details: GELFAND-P000488

Diagram and typed description. The note and reference are to the right of the calculation.

Let $\pi_1(M^n) = 0$.

Exact seq.

$$hS(M^n) \longrightarrow \Phi(M^n) \longrightarrow P_n$$

$$P_n = \begin{cases} 0, & n \neq 4k,\ 4k+2 \\ \mathbb{Z}, & n = 4k \\ \mathbb{Z}_2, & n = 4k+2 \end{cases}$$



Original source details: GELFAND-P000488

Diagram and typed description. The bottom horizontal connection is written as an equals sign.

$$\begin{array}{ccc} & \xi & \xrightarrow{\varphi} & M^n \times \mathbb{R}^N \\ \Phi(M^n) \ni & \downarrow & & \downarrow \\ & M^n & = & M^n \end{array}$$

Let us add ν_M:



Original source details: GELFAND-P000488

Diagram and typed description. The normal bundle is added to both upper entries.

$$\begin{array}{ccc} \xi + \nu_M & \xrightarrow{\varphi \times \mathrm{id}} & (M^n \times \mathbb{R}^N) + \nu_M \\ \downarrow & & \downarrow \\ M & = & M \end{array}$$

$\varphi \times \mathrm{id}$ — a proper homot. equiv..

Hence

$$T(\xi + \nu_M) \longrightarrow T(N + \nu_M) \qquad (*)$$



Original source details: GELFAND-P000488

Diagram and typed description. The argument on the right reads $N + \nu_M$.

GELFAND-P000489

Remark on the props. of the Thom complex, norm. bundle.

$M^n \subset \mathbb{R}^L$.

Original source details: GELFAND-P000489

Diagram and typed description. Three arcs and transverse strokes.



The space of the tube is the space of the norm. bundle.

There is a nat. map



Original source details: GELFAND-P000489

Diagram and typed description. The arrow λ and its endpoints have a stroke underneath. Below $T(\nu_M)$ are $\cup$ and M^n.

$$\underbrace{S^L \xrightarrow{\lambda} T(\nu_M).}_{\cup\ M^n}$$

Original source details: GELFAND-P000489

Uncertain reading. A sign below the left part is crossed out. Possible readings are β and φ.

The map λ is transversely regular on M^n. Its preimage is M^n. Only this will be used.

$\exists$ a map $S^L \xrightarrow{\lambda} T(\nu_M)$

Original source details: GELFAND-P000489

Uncertain reading. An entry following the second formula is crossed out. Its reading is unresolved.

and an embedding $M \subset T(\nu_M)$, which is transversely reg. on M.



Original source details: GELFAND-P000489

Diagram and typed description. The lower arc goes from A to B/C. Its endpoint is labelled "epi".

$$\Big(A \xrightarrow{\alpha} B \longrightarrow B/C \Big).$$
$$\cup$$
$$C \qquad \text{epi}$$

—— · ——

The map $\phi(M^n) \longrightarrow P_n$.



Original source details: GELFAND-P000489

Uncertain reading. The sign before (M^n) is provisionally set as ϕ.



Original source details: GELFAND-P000489

Diagram and typed description. The reverse arrow σ from $T(N+\nu_M)$ is dashed.



~~cont.~~

Original source details: GELFAND-P000489

Uncertain reading. The crossed-out abbreviation below the diagonal arrow is provisionally read as «непр.» (“cont.”).

φ_0 is a homot. equiv. by construction. σ — a hom. inverse.

$\sigma \circ \lambda$ — a cont. map. $\quad M \subset T(\xi + \nu_M)$

We homotope $\sigma \circ \lambda$ (to $\widetilde{\sigma \circ \lambda}$), so that on M it becomes transversely reg..



Original source details: GELFAND-P000489

Diagram and typed description. The callout after $\sigma \circ \lambda$ reads “to” followed by the same composite with a tilde.



Original source details: GELFAND-P000489

Diagram and typed description. The preimage M_1 is below S^L. The two rows have $\cup$ signs between them.

$$\begin{array}{ccc} S^L & \xrightarrow{(\widetilde{\sigma\lambda})} & T(\xi+\nu_M) \\ \cup & & \cup \\ \underline{M_1 = (\widetilde{\sigma\lambda})^{-1}(M)} & \longrightarrow & M \end{array}$$

M_1 — a smooth manifold. $\dim M_1 = \dim M$.

~~By Thom's theorem $(\widetilde{\sigma\lambda})^{-1}(M) \subset S^L$.~~



Original source details: GELFAND-P000489

Diagram and typed description. The entire line is crossed out.

Important:

$$\boxed{(\widetilde{\sigma\lambda})^*(\xi + \nu_M) = \nu_{M_1}.}$$

(reformul. of transverse regularity)



Original source details: GELFAND-P000489

Diagram and typed description. The equality is enclosed in a rectangle.

$\widetilde{\sigma\lambda} : M_1 \longrightarrow M$.

Thus from the bundle ξ we have constr. a manifold M_1 and its cont. map



Diagram and typed description. Below M_1 are $\cap$ and S^L.

$$\begin{array}{ccc} M_1 & \longrightarrow & M \\ \cap & & \\ S^L & & \end{array}$$

Original source details: GELFAND-P000489

M_1 with norm. bundle $\nu_{M_1} = (\widetilde{\sigma\lambda})^*(\xi + \nu_M)$. (depends on ξ)

There arose a ~~problem~~ surgery situation.

Uncertain reading. The crossed-out word is provisionally read as «задача» (“problem”).

Original source details: GELFAND-P000489

A problem in smooth topology: how uniquely is M_1 determined.

GELFAND-P000490

Milnor–Kervaire thm.. All M_1 are obtained from one another by Morse surgeries. (necess. and suff.)

Is there a manifold there homot. equiv. to M.

P_n — the obstruction group



Uncertain reading. A word after “obstructions” is crossed out. Its reading is unresolved.

Original source details: GELFAND-P000490

for surgery to a homotop. equiv.

$$\sigma_0 : M_1 \longrightarrow M$$

The seq. is exact.

$$? \longrightarrow hS(M^n).$$



Diagram and typed description. A question mark is written in place of the first term.

Original source details: GELFAND-P000490

$$\alpha_1. \quad \{N_1 \xrightarrow{f_1} M\},$$
$$\alpha_2 : \quad \{N_2 \xrightarrow{f_2} M\}.$$



Original source details: GELFAND-P000490

Diagram and typed description. A period follows α_1, and a colon follows α_2.

$\xi_1 \in \phi(M)$ is constr. from α_1.

Original source details: GELFAND-P000490

Diagram and typed description. The sign before (M) is set as ϕ.



Original source details: GELFAND-P000490

Diagram and typed description. Two arrows point to Thom complexes. Two vertical strokes stand between the targets.

$$\beta_1 : S^L \longrightarrow T(\xi_1 + \tau_M)$$
$$\| $$
$$\beta_2 : S^L \longrightarrow T(\xi_2 + \tau_M).$$



Original source details: GELFAND-P000490

Uncertain reading. The wavy stroke may be part of τ_M or a separate tilde over τ. It is provisionally set as τ_M.

We obtain the problem:

Original source details: GELFAND-P000490

Uncertain reading. An entry between “problem” and “diss.” is crossed out. Its reading is unresolved.

Novikov’s diss.:



Original source details: GELFAND-P000490

Diagram and typed description. Below the target are $\cup$ and M.

$$S^L \times I \longrightarrow T(\xi + \tau_M)$$
$$\cup$$
$$M$$

Film:

$$F\big|_{S^1\times 0} = \beta_1$$
$$F\big|_{S^1\times 1} = \beta_2$$



Diagram and typed description. The two restrictions of F at 0 and 1.

Original source details: GELFAND-P000490

Uncertain reading. The sign before the quantifier is overwritten. Its reading is unresolved.

Original source details: GELFAND-P000490

$\exists$ h-cobordisms among the films?

GELFAND-P000491

19/III-73 Gelfand's Sem.

Uncertain reading. A short entry before the date is crossed out. It may contain digits.

Original source details: GELFAND-P000491

Arnold. Consid. the germ of a fn. $f : (\mathbb{C}^n, 0) \longrightarrow (\mathbb{C}, 0)$. 0 — a crit. point.

Diagram and typed description. A yellow callout icon with three black strokes is visible above the line. Its text is unavailable in this frame.

Original source details: GELFAND-P000491

Consid. the space of k-jets. The group of k-jets of diffs. acts.

$j^k f$ k-suff. (the subsequent ones have no effect)

m — number of moduli. Thm.. $m = 0 \Longrightarrow$ the list

$$\begin{array}{ll} A_k & x^{k+1} \\ D_k & x^2 y + y^{k-1} \\ E_6 & x^3 + y^4 \\ E_7 & x^3 + xy^3 \\ E_8 & x^3 + y^5 \end{array}$$



Diagram and typed description. Several strokes in the list are retraced, including those in E_6 and E_8.

Original source details: GELFAND-P000491

Stab. equiv. $\oplus$ with nondeg. quadr. forms.

The quadr. form is positive definite.

GELFAND-P000492

An analyt. fn., up to an analyt. change of var., uniquely det. the change of var.

0-modality sing. — after changing the coeffs. $\exists$ only a finite number of variants.



Uncertain reading. The ending was overwritten. The line is provisionally read as «модульная», with «модульных» also possible.

Original source details: GELFAND-P000492

— · —

$f = \varepsilon$ level line: Intersection with a ball — an even-dimensional manifold with boundary.

$$f^{-1}(\varepsilon) \cap B_\delta$$

Diagram and typed description. Two closed curves are joined by inward-curving sides.

Original source details: GELFAND-P000492

Intersection index

Original source details: GELFAND-P000492

Uncertain reading. An entry after "intersection" is crossed out. Its reading is unresolved.

of real homology in the middle dim. (integral)

(neg. def.)

It is definite in sign exactly in the listed cases, provided $n \equiv 3 \pmod 4$. (otherwise add extra variables) — Tyurin's thm..



Original source details: GELFAND-P000492

Diagram and typed description. "(Neg. def.)" is inserted in a callout after "definite in sign".

$$f^{-1}(\varepsilon) \cap B_\delta \approx \underbrace{S^{n-1} \vee \ldots \vee S^{n-1}}_{\mu}.$$

$\mu =$ dim of the local ring.



Original source details: GELFAND-P000492

Diagram and typed description. Diagram of E_6. The leftmost vertex is marked -2 and the first edge is marked 1.



Original source details: GELFAND-P000492

Uncertain reading. An entry to the right of E_6 is crossed out. Its reading is unresolved.

The quadr. form is given by the Dynkin diag.

$\boxed{m = 1.}$ — one also finds a list (long).

First: $\underline{x_1^3 + x_2^3 + x_3^3}$.

$$\underline{\mu = \mu_+ + \mu_0 + \mu_-}$$

$\underline{\mu_+ \leqslant 1.} \Longrightarrow$ always $m = 1$.



Original source details: GELFAND-P000492

Uncertain reading. The sign before 1 is retraced. It is provisionally set as $\leqslant$. The conclusion reads $m = 1$.

For all of them

$$\mu_+ \leqslant 1 \Longrightarrow \mu_0 = 1 \qquad \text{(always degen.)}$$

$\mu_+ = 1$. $axyz + x^k + y^\ell + z^m$ — three-index series $T_{k\ell m}$.

A. S. Mishchenko.

Sullivan: localization, periodicity and ... Galois-

$$K(X)/J\text{-equiv.} = J(X) \quad \text{— a finite group.}$$

Adams: it is described in terms of the cohom. ops. of K-theory ψ^k.

$$\psi^k(\xi) = \xi^k \quad \text{and additive} \quad \Longrightarrow \quad \text{this determines them uniquely}$$

$(\dim \xi = 1) \qquad k = 2, 3, \ldots$

Thus $J(X)$ is determined by the group $K(X)$ as a module over these ops..

J-equiv. — fibrewise homot. equiv..



Original source details: GELFAND-P000492

Diagram and typed description. The arrow f joins ξ and η. Both letters have arrows to X.



f — proper. $\deg f = 1$ on fibres.

It was proved (Adams, Atiyah):

$$\xi \overset{J}{\sim} \text{triv.}.$$

X — a finite complex. (then $\exists N \in \mathbb{Z}$:)



Original source details: GELFAND-P000492

Diagram and typed description. "Then $\exists N \in \mathbb{Z}$:" is inserted after "complex".

$\forall$ J-triv. bundles ξ $(\forall k)$ $\exists$

Original source details: GELFAND-P000492

Diagram and typed description. The quantifier $\forall k$ is inserted between ξ and $\exists$.

Original source details: GELFAND-P000492

Uncertain reading. A word before “bundle” is crossed out. Its reading is unresolved.

a bundle y:

Original source details: GELFAND-P000492

Uncertain reading. An entry after the colon is crossed out. Its reading is unresolved.

$$\underline{\xi = k^N(\psi^k - 1)y}$$



Original source details: GELFAND-P000492

Diagram and typed description. A stroke runs below and to either side of the equality.

The converse — the Adams conjecture: $\forall$ finite compl. X $\exists N$; $\forall k$

$$k^N(\psi^k - 1)\xi \overset{J}{\sim} 0.$$

GELFAND-P000493

Idea.



Original source details: GELFAND-P000493

Diagram and typed description. The left side reads $\xi = f^*(\xi)$ and the right side ξ_n.

$$\begin{array}{ccc} \xi = f^*(\xi) & & \xi_n \\ \downarrow & & \downarrow \\ X & \xrightarrow{\ f\ } & BU(n) = G_{n,\infty} \end{array}$$

Original source details: GELFAND-P000493

Uncertain reading. The sign after f is heavily retraced and provisionally set as a star.



Original source details: GELFAND-P000493

Diagram and typed description. The second diagram shows $f^*(\eta)$ and η.

$$\begin{array}{ccc} f^*(\eta) & & \eta \\ \downarrow & & \downarrow \\ X & \longrightarrow & Y \end{array}$$

$$\psi^k(f^*(\eta)) = f^*\psi^k(\eta).$$

Hence the op. ψ^k is det. by specifying a bundle on $\underline{\underline{BU(n)}}$. $(\psi^k(\xi_n))$.

From ψ^k one constructs a map $BU(n) \longrightarrow BU(\infty)$ (unknown dimension).

$\psi^k(1) = 1 \Longrightarrow$ it follows that $\exists$ a sequence of maps.



Original source details: GELFAND-P000493

Diagram and typed description. Above $BU(n)$ is $\xi_n + 1$.

$$\begin{array}{ccccc} \xi_n + 1 & & & & \\ BU(n) & & \xrightarrow{\psi^k} & & BU(\infty) \\ & \searrow^{\text{std.}} & & \nearrow_{\psi^k} & \\ & & BU(n+1) & & \end{array}$$

Thus ψ^k is given by a single map.

$$\underline{\underline{BU(\infty) \xrightarrow{\psi^k} BU(\infty).}}$$



Original source details: GELFAND-P000493

Diagram and typed description. A double stroke runs below the arrow, with turned-up ends.

Suppose there is a cohom. op. $BU(\infty) \xrightarrow{A} BU(\infty)$, and suppose it preserves dim.



Original source details: GELFAND-P000493

Diagram and typed description. The square has A on both horizontal arrows.

$$\begin{array}{ccc} BU(n) & \xrightarrow{A} & BU(n) \\ \downarrow & & \downarrow \\ BU(\infty) & \xrightarrow{A} & BU(\infty) \end{array}$$

preserves dimension. They do not occur, but if they did, one could prove that $A\xi \overset{J}{\sim} \xi$.



Original source details: GELFAND-P000493

Diagram and typed description. The note on the right has a wavy underline.

Then $A\xi \overset{J}{\sim} \xi$.

spheres

Original source details: GELFAND-P000493

Diagram and typed description. The frame around “spheres” is open on the left.



Original source details: GELFAND-P000493

Diagram and typed description. The diagram has two levels and vertical ellipses.

$$\begin{array}{ccccccc} S(\xi_{n+1}) & \xrightarrow[\text{equiv.}]{\sim} & BU(n) & \xrightarrow{A} & BU(n) & \xleftarrow{\sim} & S(\xi_{n+1}) \\ \downarrow & & \downarrow & & \downarrow & & \downarrow \\ B(n+1) & = & BU(n+1) & \xrightarrow{A} & BU(n+1) & = & BU(n+1) \\ & & \downarrow & & \downarrow & & \\ & & \vdots & & \vdots & & \end{array}$$



Original source details: GELFAND-P000493

Diagram and typed description. The lower-left node reads $B(n+1)$.

Original source details: GELFAND-P000493

Uncertain reading. The upper-right arrow is heavily retraced. The arrowhead is visible on the left.

A fibrewise homot. equiv. is obtained.

~~But: how to~~



Original source details: GELFAND-P000493

Diagram and typed description. “But: how to” is crossed out.

There are none, but how do we “find” them?



Original source details: GELFAND-P000493

Diagram and typed description. Two arrows go from X to $BU(n)$.

$$\begin{array}{ccccc} X & \rightrightarrows & BU(n) & \xrightarrow{J} & B_F \\ & & & \searrow \quad \nearrow & \\ & & & BU(n)^\wedge & \end{array}$$

(classif. space of bundles with fibre a (homotopy) sphere)



Original source details: GELFAND-P000493

Diagram and typed description. “Homotopy” is inserted before “sphere”.

J — a functor.

Suppose $\exists BU(n)^\wedge$, to which the Adams operations transfer, i.e. $\exists$ an op. $(\psi^k)^\wedge$, for which the diag. commutes.



Original source details: GELFAND-P000493

Diagram and typed description. The lower-right arrow bends up toward B_F.

$$\begin{array}{ccccc} BU(n) & \longrightarrow & BU(n)^\wedge & \longrightarrow & B_F \\ \downarrow{\scriptstyle \psi^k} & & \downarrow{\scriptstyle (\psi^k)^\wedge} & & \uparrow \\ BU(\infty) & \longrightarrow & BU(\infty) & & \end{array}$$

Perhaps, it may be that $(\psi^k)^\wedge$ preserves dimension.

(orientations — dim.-preserving maps)

These spaces were constr. by Sullivan.

GELFAND-P000494

$BU(n)^\wedge$ will be the compl. Grassmannian.

On

Original source details: GELFAND-P000494

Uncertain reading. A short entry after “On” is crossed out. Its reading is unresolved.

S^{2n-1} the group $U(n)$.

Original source details: GELFAND-P000494

Uncertain reading. The sign in the exponent is heavily retraced. It is provisionally set as $2n-1$, possibly $2n+1$.

We obtain bundles (spher.) on $BU(n)$.

Sullivan: another space $\widehat{S}^{2n-1}$ and the group G_n. Consid. the bundle and the classif. space.



Original source details: GELFAND-P000494

Diagram and typed description. A stroke runs below the horizontal arrow. The separate entry on the right is $\widehat{S}^{2n+1}$.

$$\underbrace{BU(n)^\wedge \longrightarrow BU(n+1)^\wedge}_{\downarrow} \qquad \widehat{S}^{2n+1}$$
$$BU(n)^\wedge$$

and the fibrewise homot. type will be preserved.

Original source details: GELFAND-P000494

Undeciphered passage. The line is heavily crossed out. A continuous reading is unresolved.

Simply connected compls. with fin. gen. homot. grps. are considered.

Claim. $\overset{\forall X}{\exists}$

Original source details: GELFAND-P000494

Diagram and typed description. $\forall X$ is inserted above $\exists$.



Original source details: GELFAND-P000494

Diagram and typed description. A stroke runs under the upper arrow. Two arrows point to the bottom node.

$$\underbrace{X \xrightarrow{\alpha(X)} \widehat{X},}_{\forall f \searrow \quad \swarrow \hat{f}\ (\exists \text{ and unique})}$$
$$F$$

(functor)

$\alpha(X)$ — a transformation of the ident. functor.

($\forall F$, (for which) $\pi_i(F)$ are finite).



Original source details: GELFAND-P000494

Diagram and typed description. "For which" is inserted after F.

Original source details: GELFAND-P000494

Uncertain reading. An entry before "are finite" is blacked out. Its reading is unresolved.

$\pi_i(\widehat{X})$ are profinite ($\varprojlim$ fin. groups). (in partic., compact).

~~In particular~~



Original source details: GELFAND-P000494

Uncertain reading. The crossed-out words are provisionally read as “In particular”.

Then one can compute:

$$\pi_i(\widehat{X}) = \widehat{\pi_i(X)}$$

(profin. completion). Neighb. — subgroups of fin. index and their limit.

$Z^\wedge$ is descr. by p-adic (integral) numbers.



Original source details: GELFAND-P000494

Diagram and typed description. “Integral” is inserted before p.

The homot. groups of $\widehat{X}$ behave like integral p-ad. numbers.

~~Action of the Galois grp..~~

Original source details: GELFAND-P000494

Diagram and typed description. The heading is crossed out.



Original source details: GELFAND-P000494

Diagram and typed description. The lower arrow points right and has an equals sign above it.

$$\begin{array}{ccc} BU(n) & \longrightarrow & \widehat{BU(n)} \\ \downarrow & & \downarrow \\ B_F & \xrightarrow{=} & \widehat{B}_F \end{array}$$

all homot. grps. are finite (these are stable homot. groups of spheres)



Original source details: GELFAND-P000494

Diagram and typed description. The lower horizontal arrow points right. There is an additional stroke at its left end. The arrow from $\widehat{S}^{2n+1}$ crosses the neighbouring writing.

$$\begin{array}{ccccc} S^{2n+1} & & \widehat{S}^{2n+1} & & \\ \downarrow & & \downarrow & & \\ BU(n) & \longrightarrow & \widehat{BU(n)} & \longrightarrow & B_F \\ \downarrow & & \downarrow & & \\ BU(n+1) & \longrightarrow & \widehat{BU(n+1)} & & \end{array}$$

~~Suppose~~



Original source details: GELFAND-P000494

Uncertain reading. The following short word is crossed out. Its reading is unresolved.

(The constr. op. ψ_k) extends the Adams ops. and preserves dimension.



Original source details: GELFAND-P000494

Uncertain reading. The small sign to the right of ψ is provisionally set as subscript k. Another possible reading is $\widehat{\psi}^k$.

Consid. the Grassmannians: $G_{N,n}$. There are finitely many aff. alg. charts, with eqs. over Z (scheme over Z). — an alg. set over Q. $\Rightarrow$ the Galois grp. acts there $\mathrm{Gal}(\mathbb{C} : Q)$ — acts on $G_{N,n}$. It is discontinuous in the usual sense, but continuous in the Zariski top.. Consid. Étale top. ...

$$\mathrm{Gal}(\mathbb{C} : Q) \longrightarrow \mathrm{Gal}\Big(\underset{\text{max. ab. ext.}}{Q_{ab}} ; Q \Big) = \widehat{Z}^*$$



Original source details: GELFAND-P000494

Diagram and typed description. Below Q_{ab} is the label “max. ab. ext.”.

$$H_i(V_c, A) \approx H_i(V_{et}, A)$$
$$\widehat{V}_c \sim \varprojlim N(V_{et}), \qquad N \text{ — nerve.}$$

GELFAND-P000495

26.3.73

Statement of the res. of Atiyah, Patodi, Singer. (I. M. Gelfand).

Let A — be a self-adj. ell. op.

$$\zeta_A(s) = \mathrm{Tr}\, A^{-s} = \sum \lambda_i^{-s}$$

at $s = 0$ has no pole (Seeley).



Original source details: GELFAND-P000495

Uncertain reading. The Cyrillic spelling of the name is provisionally read as «Сили», possibly «Силли».

$\zeta_A(0)$ — Atiyah and others.

Consid. In place of the ζ-fn., L-series.



Original source details: GELFAND-P000495

Undeciphered passage. The crossed-out phrase to the right may begin “Not”. The rest is illegible.

Let A — not pos. def. (self-adj. ellip.)

$$\eta(s) = \sum_{\lambda \neq 0} (\operatorname{sign} \lambda_i)\, |\lambda_i|^{-s}$$

Difficult theor.: $s = 0$ — is no pole !!

Important example — 1st-order op.

General prob.: no pos. def. Consid. $\sum$ (mult. characters of λ_i) (L-series). On compl. numbers there are more complicated mult. characters.

Example.

Original source details: GELFAND-P000495

Uncertain reading. The crossed-out entry before A partly overlaps A.

$$A = i\frac{d}{dx} + t \qquad \text{on } [0, 2\pi] \qquad \text{periodic}$$

$$\eta(0) = 1 - 2t$$



Original source details: GELFAND-P000495

Manuscript excerpt. An open-topped bracket runs under the formula.

Eigenvals. $n + t$, $n = -2, -1, 0, 1, \ldots$

$\eta(0)$ — the "asymmetry" of the operator:

$$\sum_{\lambda_i > 0} 1 - \sum_{\lambda_i < 0} 1.$$

S. I. Gelfand. Account of Manin's last lecture:

p-adic integration (Mazur, Swinnerton — Dyer)

Original source details: GELFAND-P000495

Uncertain reading. The middle letters of the first part of the name run together. Provisionally read as Swinnerton.

GELFAND-P000496

Z_p — integral p-adic numbers, a fn. is defined on them. It is to be integrated.
(p-adic vals.)
lit. L. G. Schnirelmann, Dwork, Grauert, Krasner, Tate
$Z_p \supset A_i = p^i Z_p$ — syst. of neighb. of 0. The measure is def. on sets $a + A_i$
$\mu(a + A_i)$ — a p-adic number (not nec. integral).

$$a \in Z_p \quad \text{or} \quad a \in Z_p/p^i$$

There must be finite additivity; reduces to the cond.:

$$\mu(a + A_i) = \sum_{t=0}^{p-1} \mu(a + tp^i + A_{i+1})$$

2 examples: 1) invar. measure: indep. of a, but dep. on i. Then

$$\mu(a + A_i) = p^{-i} \qquad \text{(only possibility).}$$

The measure of a small set is large! — far from 0

$$\left(\left\| \frac{a}{b} \right\| = p^{-n}, \quad \text{where } \frac{a}{b} = p^n \frac{a_1}{b_1}, \quad a_1, b_1 \text{ rel. prime to } p \right).$$

2) More important example. (Leopoldt — Kubota measures).

2 parameters n and a

$$(n, p) = 1, \qquad 0 \le a \le p^i - 1$$

$$\mu_n(a + A_i) = \left[\frac{na}{p^i} \right] - \frac{n-1}{2}$$

$$\mu_2(a + A_i) = \begin{cases} +1/2, & \text{if } a > \dfrac{p^i}{2} \\ -1/2, & \text{if } a < \dfrac{p^i}{2} \end{cases}$$

It is addit. !! The measure of $\forall$ set is bounded
(it is obtained by the Mellin transf. from the | ζ-fn. of Leopoldt — Iwasawa)



Uncertain reading. A vertical stroke appears between “from” and ζ. Its function is unresolved.

Original source details: GELFAND-P000496

$$Q_p \ni f(x), \quad x \in Z_p \qquad \int_{Z_p} f(x)\mu(x) \qquad \text{in Riemann's sense}$$

R_m — representatives of $Z_p/p^m Z_p$ (1 from $\forall$ class)
This is a partition. Form

$$S(R_m) = \sum_{a \in R_m} f(a)\mu(a + A_m)$$

they converge under conds. on the measure and the fn.

Moderately growing measure — if it grows more slowly than the invariant one

$$\lim_{m\to\infty} \max |\mu(a + A_m)| p^{-m} = 0$$

f satisfies the Lipschitz cond. if

$$|f(a) - f(b)| < Cp^{-m}, \quad \text{if } |b - a| < p^{-m}$$

(in partic., if given by a conv. power series)

If the measure grows moderately and the fn. satisfies the Lipschitz cond., then, $\exists$ a limit, called the integral.

GELFAND-P000497

If we consid. the ordinary $\zeta(s) = \sum 1/n^s$. Then

$\zeta(1 - 2k)$ — a rat. number $\forall k > 0$ (expr. through Bern. numbers).

Uncertain reading. The crossed-out entry in the left margin resembles a sum. An s is visible on the right. The full reading is unresolved.

Original source details: GELFAND-P000497

Let k_i — ~~p-adic numbers~~ be integers and in the p-adic sense

$$k_i \longrightarrow a \in Z_p.$$

Iwasawa — Leopoldt:

$$\zeta(1 - 2k_i) \xrightarrow{p} \zeta(a) \quad !!$$



Manuscript excerpt. The right-hand side reads $\zeta(a)$, with p over the arrow.

Original source details: GELFAND-P000497

We obtain a cont. fn. on Z_p —



Uncertain reading. A short word is crossed out. Its reading is unresolved.

Original source details: GELFAND-P000497

p-adic var. It is the Mellin transf. of the measure of example 2.

A. Gabrielov. Dynkin diagr. of isol. sing. of fns.

$f(x)$ — complex-analytic in a neighb. of 0, 0 — an isol. sing.

Ball of rad. r_0 (small). Consid.

$$f(x) = \delta, \quad |x| < r_0$$

Choose also δ.

For small δ this is a complex set of dim. $(n-1)$, homot. equiv. to a bouquet of $(n-1)$-spheres.



Original source details: GELFAND-P000497

Uncertain reading. The first letter in the sphere dimension is heavily retraced. It is set provisionally as $(n-1)$, possibly $(k-1)$.

and van. cycles.

Original source details: GELFAND-P000497

Uncertain reading. The retraced mark at the start of the line is provisionally read as “and”.

GELFAND-P000498

9/IV-73 yr.



Original source details: GELFAND-P000498

Uncertain reading. A short entry to the right of the date is crossed out. Possibly «Сем.» (“Sem.”).

S. I. Gelfand. (account of lectures by Yu. I. Manin)

$Q_p \supset Z_p$,

{A measure μ on Z_p with vals. in the fin.-dim. space W over Q_p.}

$$\mu : U \longmapsto \mu(U) \in W, \qquad U \subset Z_p$$

$$\mu(U_1 \cup U_2) = \mu(U_1) + \mu(U_2).$$



Original source details: GELFAND-P000498

Manuscript excerpt. The additivity formula in the manuscript.

In Q_p a basis of open-and-closed sets $A_n = p^n Z_p$. $\quad U = (a + A_n)$.

Original source details: GELFAND-P000498

Uncertain reading. The letter before the subscript p is heavily retraced. Provisionally read as Q_p.

Riemann integral.

f — a fn. on Z_p with vals. in Q_p.

$m \geq 1$,

R_m — representatives of $Z_p / p^m Z_p$. (a finite set).

Riemann sum

$$S(R_m) = \sum_{a \in R_m} f(a)(a + A_m)$$



Original source details: GELFAND-P000498

Manuscript excerpt. The entry immediately after $f(a)$ is $(a + A_m)$.

Theor.: as $m \to \infty$ under certain conds. on the fn. and measure $\exists$ a limit

$$\lim_{m \to \infty} S(R_m) = \int_{Z_p} f(a)\mu(a) \in W$$

Conditions: μ is bounded, and the fn. is loc. constant

Leopoldt — Kubota measures:

k — an integer, $(k, p) = 1$,

$$\mu_k(a + A_n) = \left[\frac{ka}{p^n}\right] - \frac{k-1}{2}$$

$0 \leq a \leq p^n - 1$

Easy to check (useful) that it is finitely addit.

(Mellin transf.



Original source details: GELFAND-P000498

Diagram and typed description. A callout between “Mellin” and “mult.”.

Of this measure — ζ-fn.

mult. p-adic char. on Z_p)

Mult. char.: p-adic number to a p-adic power.

$$\chi_t(a) = e^{t \ln a}, \qquad a = 1 \bmod p.$$



Original source details: GELFAND-P000498

Uncertain reading. The crossed-out entry begins with t. The following signs are illegible.

$t \in Z_p$ (for convergence)

$$\ln a = (a-1) - \frac{(a-1)^2}{2} + \dots$$



Uncertain reading. A 2 is visible in the denominator. The other strokes below the fraction bar are illegible.

Original source details: GELFAND-P000498

2nd cl. of measures using modular forms:

$$H = (z \mid \operatorname{Im} z > 0)$$

Acts

$$SL(2,R)/(\pm 1) \supset \Gamma = SL(2,Z)/(\pm 1)$$

Consid.

$$\varphi(z) = \sum_{n=1}^{\infty} \lambda_n e^{2\pi i n z}$$

(var. invar. decr. fns.)

Autom. form of weight w

$$\varphi(gz) = (az+c)^{-w}\varphi(z), \qquad g = \begin{pmatrix} a & b \\ c & d \end{pmatrix}, \quad g \in \Gamma.$$



Original source details: GELFAND-P000498

Manuscript excerpt. The factor is written $(az+c)^{-w}$.

GELFAND-P000499

Further condition: φ eigenfn. with respect to all Hecke operators.



Diagram and typed description. "All" is inserted in a callout above the line.

Original source details: GELFAND-P000499

$$(T_k\varphi)(z) = \sum_{\substack{ad=k \\ 0 \le b \le d-1}} f\left(\frac{az+b}{d}\right)$$



Manuscript excerpt. The summand has f. The left-hand side has φ.

Original source details: GELFAND-P000499

(a, b, d, k — integers)

$T_k\varphi$ — also a modular form

Let $\lambda_1 = 1$. Then

$$T_k\varphi = \lambda_k\varphi \qquad (\lambda_k \text{ — coeff. of } e^{2\pi ikz}).$$

_____ . _____

$$p: \qquad \chi : (\mathbb{Z}/p^n\mathbb{Z})^* \to \mathbb{C}^*$$

(primitive character) (p^n — conductor of the char.)

(on $p^{n-1}\mathbb{Z}/p^n\mathbb{Z}$ nontriv.)

Uncertain reading. The sign between n and 1 is inked over. Provisionally set as $n - 1$.

Original source details: GELFAND-P000499

$$\varphi_\chi(z) = \sum \lambda_n \chi(n) e^{2\pi inz} \quad \text{— also modular.}$$

$$L(\varphi, \chi, 1) = \text{[factor illegible]} \int_0^{i\infty} \varphi_\chi(z)\, dz$$

Uncertain reading. The factor before the integral is heavily overwritten. Possibly C or a longer expression.

Original source details: GELFAND-P000499

Has the interpretation

$$L(\Phi, \chi, s) = C \int_0^{i\infty} \Phi_\chi(z) z^{s-1}\, dz = \sum \frac{\lambda_n \chi(n)}{n^s} \qquad (L\text{-fn.})$$

---

p-adic part.

χ — also a loc. const. fn. on integral p-adic numbers

(on the invertible ones as before, elsewhere 0).

Let $\chi(-1) = 1$

Aim: $L(\varphi, \chi, 1)$ repr. by $\int \chi$ on p-adic numbers.

$$\int \chi(a)\mu(a) = \textcircled{?}\, L(\varphi, \chi, 1).$$

Manuscript excerpt. The question mark is circled in the manuscript.

Original source details: GELFAND-P000499



Diagram and typed description. The line from 0 to x runs above the baseline. There are no arrows.

Original source details: GELFAND-P000499

$\int_0^x \varphi(z)\, dz$ 

x — rat. point.

(essentially an $\int$ over a cycle in the quotient space)

$$\ell(x) = \frac{1}{\omega} \operatorname{Re} \int_0^x \Phi(z)\, dz \text{ — an alg. integer}$$



Uncertain reading. The initial letter is provisionally set as ℓ. Its form is unusual.

Original source details: GELFAND-P000499

from a fixed ext. of Q.

$\exists\omega$ (transcend.)

(in many cases)

$$T^2 - \lambda_p T + p^{w-1} = 0, \qquad \pi, \bar{\pi} \text{ — roots}, \qquad \lambda_p \neq 0 \bmod p.$$

$$\mu(a + A_n) = \lim_{\substack{m\to\infty \\ m\geq n}} \frac{1}{\pi^m + \bar{\pi}^m} \sum_{\substack{b \bmod p^m \\ b\equiv 0 \bmod p^n}} \ell\left(\frac{b}{p^m}\right)$$



Original source details: GELFAND-P000499

Uncertain reading. The residue after $\equiv$ is heavily retraced. Its shape suggests 0, possibly a.

Original source details: GELFAND-P000499

Uncertain reading. The letter before the fraction is provisionally set as ℓ, as in the preceding formula.

lim exists.

Final result:

$$\pi^{k-1} \int_{\mathbb{Z}_p} \chi^{-1}(a)\mu(a) = -\frac{p^k}{\omega g(\chi)} L(\Phi, \chi, 1)$$

GELFAND-P000500

Original source details: GELFAND-P000500

Uncertain reading. The crossed-out word is provisionally read as «Числа» (“Numbers”).

Original source details: GELFAND-P000500

Diagram and typed description. Two lines with transverse hatching run under the name.

I. M. Gelfand.

$$1^k + 2^k + \ldots + n^k = P_{k+1}(n) \quad \text{— Bernoulli polynomial.}$$

$$\sum_{i=1}^{n} f(i), \qquad F'(x) = f(x).$$

$$F(n+1) - F(n) = f(n) + \frac{f'(n)}{2!} + \frac{f''(n)}{3!} + \ldots$$
$$F(n) - F(n-1) = f(n-1) + \frac{f'(n-1)}{2!} + \frac{f''(n-1)}{3!} + \ldots$$
$$F(2) - F(1) = f(1) + \frac{f'(1)}{2!} + \ldots$$

Uncertain reading. A heavily retraced entry in the right margin. Possibly “36” or “38”. A short separate stroke is visible below and to the left.

Original source details: GELFAND-P000500

Hence

$$F(n+1) - F(1) = S_n + \frac{S'_n}{2!} + \frac{S''_n}{3!} + \ldots$$

$$\left\| \begin{array}{l} S_n = \sum_{i=1}^{n} f(i) \\ S'_n = \sum_{i=1}^{n} f'(i) \\ \quad - \quad - \quad - \quad - \\ S_n^{(k)} = \sum_{i=1}^{n} f^{(k)}(i) \end{array} \right.$$

Similarly:



Uncertain reading. The crossed-out entry may begin “and take” and end with S_i or Σ_i.

Original source details: GELFAND-P000500



Undeciphered passage. Pen strokes cover the middle of the crossed-out entry. Its reading is unresolved.

Original source details: GELFAND-P000500

$$f(n+1) - f(1) = S'_n + \frac{S''_n}{2!} + \dots$$
$$f'(n+1) - f'(1) = S''_n + \dots$$

We shall consid. this as a syst. of eqs. in $S_n, S'_n, S''_n, \dots$

Hence

$$S_n = \begin{vmatrix} F(n+1) - F(1) & \frac{1}{2!} & \frac{1}{3!} & \frac{1}{4!} & \cdot \\ f(n+1) - f(1) & 1 & 1/2! & 1/3! & \cdot \\ f'(n+1) - f'(1) & 0 & 1 & 1/2! & \cdot \\ & & & & \cdot \end{vmatrix} =$$



Original source details: GELFAND-P000500

Manuscript excerpt. Three rows are written. The dots descend at the right and the bars extend below the written rows.

Expand along the 1st column:

$$= B_0\big(F(n+1) - F(1)\big) + B_1\big(f(n+1) - f(1)\big) + B_2\big(f'(n+1) - f'(1)\big) + \dots$$

But: B do not depend on the form of the fn.!

Take $f(x) = e^{tx}$. Then $f'(x) = te^{tx}$. Geom. progr.



Undeciphered passage. A crossed-out expression on the left begins with $\sum$. The rest and any limits are illegible.

Original source details: GELFAND-P000500

$$S_n = \frac{e^{t(n+1)} - e^t}{e^t - 1}$$ expand in t

in a power series — we get the coefficients.

Bernoulli numbers in arbitrary fields.

Math. Z., 1898 Hurwitz (Analogue of the Bernoulli numbers for Gaussian numbers)

Hurwitz, Math. Ann., 1899, pp. 196–226

(Über die Entwicklungskoeffizienten der Lemniskatischen functionen).



Uncertain reading. The initial letter of the last word is provisionally read as lowercase “f”.

Original source details: GELFAND-P000500

Chapter 7

GELFAND-P000501

[source number: 1]

3/IX-73. Sem. of



Undeciphered passage. The entry between “Sem.” and “Gelfand” is heavily crossed out. Its reading is unresolved.

Original source details: GELFAND-P000501

Gelfand.

Plan:

1. Derived category (Kirillov, Bernstein).

2. Ahlfors — Nevanlinna theory for many variables (and according to Grauert). (Henkin, Shabat).

3. K-theory (simplicial version) according to Quillen (Fuchs).

Uncertain reading. The faint words are provisionally read as “simplicial version”.

Original source details: GELFAND-P000501

4. Lichtenbaum’s conjecture on the connection between the ζ-fn. at integers and higher K-theories (Manin).

5. Weil: the ideas of «Герстенцуса».

Uncertain reading. The Cyrillic spelling is provisionally read as «Герстенцуса».

Original source details: GELFAND-P000501

Interlude:

Uncertain reading. The number at the left is heavily retraced, possibly 6 or 8.

Original source details: GELFAND-P000501

2 problems of Serre:

1) $k[t]$, k — finite; $SL_n(k[t])$, $n \geq 3$; $SL_n(k[t, t^{-1}])$, $n \geq 2$

These groups have finitely many generators. Are they finitely presented? (Do there exist generators with finitely many rels. among them.).

2) Coher. group: $\forall$ subgrp. with finitely many gens. is finitely presented. Free and nilpot. are coherent.

Original source details: GELFAND-P000501

Uncertain reading. The faint abbreviation reads “nilpot.”.

Fund. groups of 3-dimensional manifolds are coherent (G. P. Scott, J. Lond. Math. Soc., (2)6 (1973), 437–440). Article. $SL_2(\Lambda)$ is coher., where Λ — purely imaginary elem. of a quadr. field.



Original source details: GELFAND-P000501

Uncertain reading. The faint entry is provisionally read as “purely imaginary elem. of a quadr. field”.



Original source details: GELFAND-P000501

Uncertain reading. The crossed-out word is provisionally read as “also”.

Are $SL_3(\mathbb{Z})$ or $SL_2(\mathbb{Z}[\frac{1}{p}])$ coherent? $GL_n(\mathbb{Q})$?

[are there many rels. among distinct irreducibles? (a fin. number)]



Original source details: GELFAND-P000501

Uncertain reading. The faint abbreviation is provisionally read as “rels.”.



Original source details: GELFAND-P000501

Uncertain reading. The word is provisionally read as “irreducibles”.

[Which fund. groups occur?]

6. Smale: optimization of several functions.

Original source details: GELFAND-P000501

Uncertain reading. The digit is heavily retraced. Its outlines and the adjacent numbering support 6.

7. Brown, Douglas, Fillmore Proper K-theory of several variables (Kirillov).

8. Mishchenko: representations in his sense.

9. Lusztig: higher sign. of Novikov J. Diff. Geom. 197(1)

Uncertain reading. The faint name is provisionally read as “Lusztig”.

Original source details: GELFAND-P000501

10. Atiyah, Bott, Patodi on L-functions associated with eqs. (spectral asymmetry, etc.) (Shubin)

11. Donovan, Freilich a (V. Ponomarev) — a quadruple of subspaces, etc.

Uncertain reading. The small mark is provisionally read as «a».

Original source details: GELFAND-P000501

Modules, etc.

12. Yu. I. Manin.

13. Vershik, Gelfand, Graev — 6 variations on SL_2.

Yu. I. Manin. p-adic measures

Setting: $\mathbb{Q}_p$; K — a fin. ext. X — a compact p-adic analytic set over K. Example: integers in K, their direct prod., etc.



Diagram and typed description. The field tower at the left has no arrows. Beside it are an analytic map and an example of a coordinate.

$$\begin{array}{c} L \\ | \\ K \\ | \\ \mathbb{Q}_p \end{array} \qquad X \xrightarrow[\text{analyt.}]{f} L \qquad \text{integers } A \qquad \text{Ex.: } A \xrightarrow{x} K \quad \text{coordinate.}$$

Original source details: GELFAND-P000501

Problem: define $\int f\, d\mu$, i.e. determine a reasonable and inter. class of measures of p-adic type on X.

Uncertain reading. The abbreviation is provisionally read as “inter.”.

Original source details: GELFAND-P000501

GELFAND-P000502

Motivation: a) there are ζ-fns. $L(s) \qquad \mathbb{C} \longrightarrow \mathbb{C}$

$$\sum n^{-s}; \qquad \sum \chi(n) n^{-s}; \qquad \sum a_n n^{-s},$$

where $\sum a_n e^{2\pi i \lambda}$ is an autom. form.



Uncertain reading. The last sign in the exponent is provisionally set as λ.

Original source details: GELFAND-P000502

For them, a class of int. formulas with adelic integration

$$L(\chi) = \int_{G_A/G_K} \chi \, d\mu$$



Uncertain reading. The denominator is provisionally set as G_K. There is an additional loop at the base of G.

Original source details: GELFAND-P000502

G_K — princ. adeles



Uncertain reading. The faint note is provisionally read as "G_K — princ. adeles".

Original source details: GELFAND-P000502

In fact, the argument is a character $L(\chi)$

b) there are p-adic analogues of $L(\chi)$ and $\zeta(s)$ (Leopoldt — ~~Iwasawa~~ Kubota).



Uncertain reading. "Iwasawa" is crossed out. "Kubota" is inserted above.

Original source details: GELFAND-P000502

$$\zeta(2m) = B_{2m}\frac{\pi^{2m}}{\dots}$$

$$\zeta(1-2m) = ?\,\frac{B_{2m}}{2m},$$

$$\| \quad \left(\text{G.}\sum_{n=1}^{\infty} n^3 = \frac{B_4}{4}\right.$$

Uncertain reading. The letter after the parenthesis is provisionally read as «Г.». A hatched stroke is at the left.

Original source details: GELFAND-P000502



Original source details: GELFAND-P000502

Uncertain reading. There are faint marks below the line between the equals sign and $\frac{B_4}{4}$. Their reading is unresolved.

even and odd differ:

$$-y'' + p(x)y = \lambda y, \qquad \sum \lambda_n^k$$

integers and half-integers differ)

Still unknown why such a $\sum n^3$ is expr. through B .)

The point of the next plan — pres. of Kronecker's formulas.

Uncertain reading. The abbreviation before "formulas" is provisionally read as «пред.».

Original source details: GELFAND-P000502

Choose p from the Euler prod.

$$1-2m \longrightarrow \frac{B_{2m}}{2m}(1-p^{2m-1}) \qquad \text{Fix } p!$$

p-adic cont. and even analytic !!! ~~(from the Euler prod. we removed the chosen p)~~.

Uncertain reading. The ending of the last word is provisionally read as «аналитичне».

Original source details: GELFAND-P000502



Original source details: GELFAND-P000502

Uncertain reading. The crossed-out entry is provisionally reconstructed. A long stroke runs below the line in the manuscript.

$$\begin{array}{c}\zeta(s)(1-p^{-s})\\ \mathbb{C}\longrightarrow\mathbb{C}\end{array} \quad \text{between.} \quad \begin{array}{c}\zeta^{(p)}(s_p)\\ \mathbb{Z}_p\longrightarrow\mathbb{Q}_p\end{array}$$

Uncertain reading. The faint word between the two displays is provisionally read as “between”.



Original source details: GELFAND-P000502

there is an intersection of $\mathbb{C}$ and $\mathbb{Z}_p$ (integers), the values there are the same.



Original source details: GELFAND-P000502

Diagram and typed description. The lower left letter is provisionally set as $\mathbb{C}$. A short arrow leads upward from it. The right arrow goes up and to the right.

$$\{1-2m\} = E \subset \begin{array}{ccc}\mathbb{C} & & \mathbb{Q}_p\\ \uparrow & \nearrow & \\ \mathbb{C}\cap\mathbb{Q}_p & & \end{array}$$

and they are analytic

In fact, the correct argument is apparently adelic.

$$\mathbb{Q}_p \longrightarrow \mathbb{Q}_\ell \quad (p\neq\ell) \quad \text{apparently simpler (but unknown)}$$

Difficult $\mathbb{Q}_p \longrightarrow \mathbb{Q}_p$,

Was begun by Mazur.

Measures on compact p-adic spaces.

K — fin. ext. of $\mathbb{Q}_p$; A — integers in K; $A \supset \overline{m}$ (max. ideal)

(roots of eqs. with integral coeffs.)

$$\text{Card}(A/\overline{m}) \underset{\text{def}}{=} q.$$

Compact anal. set over K.

$$A^n = \underbrace{A\times\ldots\times A}_{n} \quad \text{— } n\text{-dimensional ball}$$

Anal. set: space and a sheaf of fns., loc. structure — a ball.

Theorem (Serre): X — a comp. an. set over K of dim. n. Then

a) $X \simeq rA^n$ (analytic isom.), $r\in\mathbb{N}$

Original source details: GELFAND-P000502

Uncertain reading. The number of balls is provisionally set as r, possibly τ.



Original source details: GELFAND-P000502

Diagram and typed description. Four ovals with a label at the right.

◯ ◯ ◯ ◯ — disjoint balls

b) ~~if~~

$$rA^n \simeq r'A^n \quad \Leftrightarrow \quad r \equiv r' \mod(q-1)$$

Original source details: GELFAND-P000502

Uncertain reading. The crossed-out word is provisionally read as “if”. The equivalence sign is encircled.

GELFAND-P000503

[source number: 2]

$$A = \{a \in K \mid a \text{ is integral}\}. \qquad A = \bigcup_{a_i \bmod m} \{a \equiv a_i \bmod m\}.$$

How to compute r?

Original source details: GELFAND-P000503

Uncertain reading. The letter is provisionally set as r.

Examples: a) X — an alg. set over A (a smooth scheme over Spec A).

~~How to compute r from pt. a) of Serre's theor.?~~



Original source details: GELFAND-P000503

Uncertain reading. The crossed-out question is read provisionally. The strokes over the part number are particularly heavy.

Reduction X_0 (closed fibre) — an alg. set over $A/\bar{m}$
over Spec A.

$$\text{Card}\, X_0(A/\bar{m}) = r(X).$$

Example of a scheme: $X = P^1$ or a circle. 2 aff. lines glued by $x = y^{-1}$
Reduction: proj. line over a fin. field of q elems. — there are $q+1$ elems.

$$q + 1 = 2 \bmod(q-1).$$

So 2 balls:

Original source details: GELFAND-P000503

Diagram and typed description. The top of the left contour is blacked out. The arrows of the right contour point towards its upper gap. At the right are “and” and a small round sign.

and

$$P^1(K) = \mathbb{Q}_p \cup \infty, \qquad pA \cup A^{-1}.$$

b) X — p-adic comp. Lie grp.; it is profinite, $\forall$ factor has an order.

Order: $2^2\, 3^\infty\, 5^1\, 7^0\, 11^\infty \ldots$ — a supernatural number (since they divide one another).

Manuscript excerpt. The stroke left of the exponent belongs to the digit 5. The exponent reads 1.

Original source details: GELFAND-P000503

It turns out ord $X = p^\infty \cdot N$, where $(p, N) = 1$, N — an ord. integer.

$$\underline{\underline{N = r(X)}}$$

SL_2 — $(p-1)$ balls $(= p^2 - 1 \bmod p)$

Original source details: GELFAND-P000503

Manuscript excerpt. The manuscript reads $p^2 - 1$ mod p.

Diagram and typed description. The mark between L and K is blacked out. Its shape and direction are unresolved.

L

•

K

Original source details: GELFAND-P000503

Definition: L-measure on X — an L-valued finitely addit. fn. on open-and-closed subsets of X.

(X — a comp. anal. set).

Uncertain reading. The start of "anal." is heavily overwritten.

Original source details: GELFAND-P000503

Examples: a) $X = \mathbb{Z}_p$

Diagram and typed description. Four branches descend from the vertex X. Some lower strokes merge.



Original source details: GELFAND-P000503

The vertices are open-and-closed subsets.

Construct these measures successively. We obtain a fund. syst. of neighbourhoods.

$$\text{Measure on } X \leftrightarrow \{\mu(a+(p^m)) \in L; \quad a \bmod (p^m),\ m \in \mathbb{N}\}.$$

$$\mu(a+(p^m)) = \sum_{b \equiv a \bmod p^m} \mu(b+(p^{m+1}))\}$$



Manuscript excerpt. Each of the two written lines ends in a closing brace.

Original source details: GELFAND-P000503

And this applies to any compact subset.

$$\text{b) } \mu(a+(p^m)) = \underbrace{\text{const} \cdot p^{-m}}_{\in L} \quad \text{— invar. measures.}$$

There is on L a metric (p-adic absolute value).

$$|\text{const} \cdot p^{-m}|_L \longrightarrow \infty \quad \text{as } m \longrightarrow \infty.$$

The smaller the sets, the larger the measure!!

It cannot tend to zero! It would follow from the non-Archim. property that the measure of the whole equals 0.

Invar. measures are bad.

The slowest-growing is bounded.

$$\text{c) } \mu(a+(p^m)) = 1 \text{ if } a < \frac{p^m}{2}, \qquad -1 \text{ if } a > p^m/2$$



Original source details: GELFAND-P000503

Manuscript excerpt. The left value is 1 and the right value is -1. The first threshold uses a stacked fraction and the second a slash.

|| nontriv. bounded measure

$0 < a < p^m, \quad (a,p) = 1$ Measure on $\mathbb{Z}_p^*$.

Undeciphered passage. A short entry between $0 < a < p^m$ and $(a,p) = 1$ is crossed out. Its reading is unresolved.

Original source details: GELFAND-P000503

Exercise: check additivity. Interference occurs.

Integr. against it — ζ-fns. of Leopoldt — Kubota.

Mazur devised this measure.

Integrals. X, μ — a measure with vals. in L.

Diagram and typed description. In the right margin an arrow points down from L to K.

$$\begin{array}{c} L \\ \downarrow \\ K. \end{array}$$

Original source details: GELFAND-P000504

$X \xrightarrow{f} L$, analyt. fn.

$$\int_X f\,d\mu$$

$$R = \{(U_i), \quad \underset{\text{open-and-closed}}{U_i} \text{ — a partition of } X, \quad a_i \in U_i\}$$

$$S(f,R) = \sum f(a_i)\mu(U_i).$$

$$\int_X f\,d\mu = \lim_R S(f;R)$$

if the limit exists under refinement

Example. $X = \mathbb{Z}_p$, μ — invar. $(\mu(a + (p^m)) = p^{-m}.)$,

$L = \mathbb{Q}_p$. $f = 1$ is integrable

$f = x$ — simple nonconst.

$$\int f\,d\mu \quad \text{does not exist!}$$

$$R = \{0 \le a \le p^m - 1, \quad a \in U_a \equiv \{b \mid b \equiv a \bmod p^m\}.$$

Uncertain reading. An entry resembling -1 is crossed out after the exponent m. The next -1 is part of the bound itself.

Original source details: GELFAND-P000504

$$S(f,R) = \frac{1}{p^m} \underbrace{\sum_{a=0}^{p^m-1} a}_{\frac{(p^m-1)p^m}{2}} \longrightarrow -\frac{1}{2}$$



Uncertain reading. Below the brace, an entry resembling -1 is crossed out after the exponent m of the first p.

Original source details: GELFAND-P000504

But this is not the only limit point.

$$R' = \{p^m \in U_0 \quad \text{the rest as in } R\}$$

The limit will be different: variation of the fn. on the interval $\approx$ measure of the interv.

hence a cond. on the measure: under refinement the ratio of the measure to the invar. measure must $\longrightarrow 0$ (this is in the case $n = 1$).

Theorem: let X be one-dimensional over $\mathbb{Q}_p$

1) μ — a measure on X with vals. in L, moderately growing, i.e.

$$U \longrightarrow \underset{\text{point}}{\bullet} \Longrightarrow \left|\frac{\mu(U)}{\mu_{\text{inv}}(U)}\right|_L \longrightarrow 0$$



Uncertain reading. The beginning of "moderately" is heavily retraced.

Original source details: GELFAND-P000504

(μ_{inv} — the usual inv. meas. on $\mathbb{Z}_p$).

2) $f : X \longrightarrow L$ satisfies the Lipschitz cond. with exponent 1

Then $\int f\, d\mu$ exists.

|| Next time: concrete measures and mod. forms.

GELFAND-P000505



Uncertain reading. The entry beyond the right border is cut off by the edge of the scan. Its reading is unresolved.

Original source details: GELFAND-P000505

10.9.73. Gelfand Sem.

Manin (continued).

X — 1-dimensional p-adic space;

μ — K-measure on X (K — a fin. ext. of $\mathbb{Q}_p$)

$f : X \longrightarrow K$

$$R: \quad \text{Riemann data: } \{X = \bigcup_{i=1}^{n} U_i\}, \quad a_i \in U_i\}.$$

Uncertain reading. A crossed-out closing brace is visible after U_i.

Original source details: GELFAND-P000505

$$S(f, R) = \sum \mu(U_i) f(a_i).$$

Theorem:

$\exists \int_X f\, d\mu$, if

a) f is Lipschitz with exp. 1

b) $(U \mapsto \text{point}) \Longrightarrow |\mu(U)/\mu_{\text{inv}}(U)| \longrightarrow 0$.

Example. $X = \mathbb{Z}_p$;

$$\mu(a + (p^m)) = \begin{cases} -1 & \text{if } 0 \le a < \dfrac{p^m}{2} \\ +1 & \text{if } \dfrac{p^m}{2} < a < p^m. \end{cases}$$

Tree of open-and-closed subsets:



Diagram and typed description. Three strokes extend upward from the top circle. There are two three-ray forks below. A 1 is written at the upper branch.



Original source details: GELFAND-P000505

$f(x) = x^{2r-1}$ (for $f(x) = x^{2r}$ one gets 0).



Uncertain reading. The letter resembles τ and is provisionally set as r.

Original source details: GELFAND-P000505

$$\int_{\mathbb{Z}_p} x^{2r-1}\,d\mu = (-1)^r(1-2^{-r})\frac{B_{r-1}}{2r}$$

$$\mathbb{Z}_p = \bigcup_{0\le a<p^{m-1}} \{a + p^m\mathbb{Z}_p\}.$$

Manuscript excerpt. In the upper bound, -1 is written at the level of the exponent m.

Original source details: GELFAND-P000505

R

Uncertain reading. The sign in the left margin is heavily retraced. Provisionally read as R.

Original source details: GELFAND-P000505

$$S(f,R) = -\sum_{0\le a<p^m/2} a^{2r-1} + \sum_{p^m>a>p^m/2} a^{2r-1}$$

There are Voronoi formulas interpreted as evaluations of integrals of this kind.

$$\int_{\mathbb{Z}_p^*} = \int_{\mathbb{Z}_p} - \int_{p\mathbb{Z}_p}$$

$$\int_{\mathbb{Z}_p^*} x^{2r-1}\,d\mu = (1-p^{2m-1})\int_{\mathbb{Z}^p}$$

$$= (-1)^r(1-p^{2m-1})\cdot(1-2^{-r})\frac{B_{r-1}}{2r} =$$



Manuscript excerpt. The exponent is written as $2m-1$ in both factors.

Original source details: GELFAND-P000505

Manuscript excerpt. The p is written to the upper right of $\mathbb{Z}$.

Original source details: GELFAND-P000505

(computed by the Mellin transf. of characters)

$$= (\ldots)\zeta_{(p)}(1-2r)$$

GELFAND-P000506

[source number: 5]

Consider $X = \mathrm{Hom}(\mathbb{Z}_p^*; K^*)$.

Uncertain reading. The mark above K merges with the parenthesis. Provisionally read as a star.

Original source details: GELFAND-P000506

$$\mathbb{Z}_p^* = (\mathbb{Z}/p\mathbb{Z})^* \times (1+p)^{\mathbb{Z}_p}.$$

$\chi \in X \Longrightarrow \chi = \chi_0 \cdot \chi_1$, where

$$\chi_0 = 1 \quad \text{on } (1+p)^{\mathbb{Z}_p}.$$
$$\chi_1 = 1 \quad \text{on } (\mathbb{Z}/p\mathbb{Z})^*.$$

$$\forall u \in \mathbb{Z}_p^*: \quad u = \varepsilon \cdot (1+p)^a, \qquad \text{where } \varepsilon^{p-1} = 1, \quad a \in \mathbb{Z}_p$$

Therefore



Diagram and typed description.
$X = X_0 \times X_1$
finite
p-adic set.

Original source details: GELFAND-P000506

Thus: X — p-adic set

$$\chi_1(1+p) = 1+t, \qquad t \in \overline{m}. \qquad \text{(notation: } \chi_{(t)})$$

Hence $X_1 \cong \overline{m}$ (but with a different law of composition)

Manuscript excerpt. The first letter of the Russian word for “but” is heavily retraced.

Original source details: GELFAND-P000506

Theorem. If μ grows moderately (more slowly than an invari. one), then

$$\int_{\mathbb{Z}_p^*} \chi \, d\mu \quad \text{is analytic in } \chi.$$

In more detail:

$$\int \chi_{(t)} \, d\mu = F(t) \in K[[t]]$$

converges for $|t| < 1$.

Next: $\int x^s \, d\mu$ is analytic in s for $s \equiv 0 \ (\mathrm{mod}(p-1))$ and for $s = k \,\mathrm{mod}(p-1)$

Manuscript excerpt. The integrand reads x^s.



Original source details: GELFAND-P000506

— · —

Modular forms. $\Gamma = SL(2,\mathbb{Z})/(\pm 1)$ acts on

$$H = \{z \in \mathbb{C} \mid \operatorname{Im} z > 0\}, \qquad w \equiv 0\ (2), \qquad w \geq 0$$

P_w: Parab. forms of weight $w+2$ on H:

a) $\varphi(z)(dz)^{\frac{w+2}{2}}$ Γ-invariant

b) $\varphi(z) = \sum_{n=1}^{\infty} a_n e^{2\pi i n z}$

1st nontriv. fn. at $w+2 = 12$ with gaps up to 26 (1-dimensional), then a fin.-dim. space throughout [Crossed out:

Undeciphered passage. The reading under the heavy strikeout is unresolved.

Original source details: GELFAND-P000506

]

$$w+2 = 12 \quad \Longrightarrow \quad e^{2\pi i z} \prod_{n=1}^{\infty} (1 - e^{2\pi i n z})^{24} = \sum_{n=1}^{\infty} \tau(n) e^{2\pi i n z}$$

— · —

In P_w there exists a basis of forms with algebraic integer coefficients

GELFAND-P000507

and such that if $\sum_{1}^{\infty} a_n e^{2\pi i n z}$ — an elem. of this basis, then

$$\sum a_n n^{-s} = \prod_p \frac{1}{1 - a_p p^{-s} + p^{w+1-[?]}}.$$



Uncertain reading. The end of the exponent in the first product is overwritten. Readings: $2s$ or a sign resembling k.

Original source details: GELFAND-P000507

(For each [Crossed out: p-adic.; above the line, circled: parab.] form we will construct a par. measure below)



Manuscript excerpt. The circled insertion "parab." points to the crossed-out word.

Original source details: GELFAND-P000507

Hecke op.: let us see what the values of a, are if

$$\sum a_n n^{-s} = \frac{1}{(1-\lambda_p p^{-s} + p^{w+1-2s})} \left(\sum \dots\right)$$

i.e.

$$\sum a_n n^{-s} = (\quad)\left(\sum b_n n^{-s}\right)$$

known undet.



Manuscript excerpt. The empty parentheses are labelled “known” and the series “undet.”.

Original source details: GELFAND-P000507

$$1 - \lambda p^{-s} + p^{w+1-2s} = (1 - \alpha_1 p^{-s})(1 - \alpha_2 p^{-s}).$$

We get a lin. condition on the coeffs. a_n.
All together — an infin. matrix.

Uncertain reading. The mark after the period is heavily overwritten. Its reading is unresolved.

Original source details: GELFAND-P000507

This cond. $\iff$ The coeff. vector is an eigenvector of the Hecke operator.
Let us write its action on the fn. instead of on the Fourier coeffs.

$$(\Phi \mid T_p)(z) \underset{\text{def}}{=} p^{w+1}\Phi(pz) + p^{-1}\sum_{k=0}^{p-1} \Phi\left(\frac{z+k}{p}\right).$$

Eigenfns. $\iff$ extract the p-factor from the corr. Dirichlet series.

$$(P_w \mid T_p) = P_w.$$

Measures: on $\mathbb{Z}_p^*$, assoc. with φ, $\varphi \mid T_p = \lambda_p \varphi \quad \forall p$.
[Crossed out:

Uncertain reading. Possibly $\mathbb{Q}_p$. The reading under the strikeout is unresolved.

Original source details: GELFAND-P000507

] with values in $\{\mathbb{Q}_p(\lambda_1, \ldots, \lambda_p, \ldots)\}_p$

Half-measures with values in [Crossed out:

Original source details: GELFAND-P000507

Uncertain reading. Possibly $\mathbb{Q}$. The reading under the strikeout is unresolved.

] $\mathbb{C}$.

$x \in \mathbb{Q}$. $\quad P(x) = \int_x^{i\infty} \Phi(z)\, dz$



Original source details: GELFAND-P000507

Diagram and typed description.



Convergence: obvious at the upper end ($e^{2\pi i n z} \to 0$), and unclear at the lower end. From the funct. eq.: it converges at the lower end too, but the dependence on x is discontinuous (from subtle arithmetic). At irr. points it generally diverges. $P(x+1) = P(x)$.

$\lambda_p P(x) = \int_x^{i\infty} \Phi(z) \mid T_p\, dz$ we substitute and get a funct. eq.

$$\lambda_p P(x) = p^w P(px) + \sum_{k=0}^{p-1} P\left(\frac{x+k}{p}\right)$$

Original source details: GELFAND-P000507

Uncertain reading. A separate sign resembling p or P stands over the argument in the right-hand summand.

$$\frac{a}{p^m} \sim a + p^m \mathbb{Z}_p.$$

The measure $P\left(\frac{a}{p^m}\right)$ gives almost fin. additivity.

GELFAND-P000508

[source number: 6]

Correction:

$$\mu_\Phi(a + p^m\mathbb{Z}_p) = \varrho^{-m} P\left(\frac{a}{p^m}\right) - p^w \varrho^{-(m+m)} P\left(\frac{a}{p^{m+1}}\right) \qquad (?).$$



Manuscript excerpt. The second exponent on ϱ reads $-(m+m)$. The last denominator reads p^{m+1}. The $(?)$ is in the manuscript.

Original source details: GELFAND-P000508

We get a measure on $\mathbb{Z}_p^*$.

~~Until next time~~



Manuscript excerpt. Two strokes cross out the phrase. The last word reads “раз”.

Original source details: GELFAND-P000508

— · —

GELFAND-P000509

17.9.73. Gelfand Sem.

Uncertain reading. The second digit of the day is overwritten. A 7 is visible over the earlier strokes.

Original source details: GELFAND-P000509

Yu. I. Manin (continued)

$$P(x) = \int_x^{i\infty} \Phi(z)\, dz$$

Consider the eq. $\varrho^2 - \lambda_p \varrho + p^{w+1} = 0$. and ϱ is any root of it

Proposition. Put

$$\mu_\Phi\big(a + (p^{m+1})\big) = \varrho^{-m} P\left(\frac{a}{p^{m+1}}\right) - p^w \varrho^{-(m+1)} P\left(\frac{a}{p^m}\right).$$

Then this is a half-measure (on $\mathbb{Z}_p^*$ taking values in $\mathbb{C}$ and fin.-additive).

Consider the periods of the form:

$$\tau_k(\varphi) = \int_0^{i\infty} \varphi(z) z^k\, dz, \qquad 0 \le k \le w.$$

$$L_\varphi(s) = \sum_{n=1}^{\infty} \lambda_n n^{-s} = \frac{(2\pi)^s}{\Gamma(s)} \int_0^\infty \varphi(iy) y^{s-1}\, dy$$

$$\tau_k(\varphi) = \frac{k!\, i^{k+1}}{(2\pi)^{k+1}} L_\varphi(k+1)$$

$[1, w+1]$ — crit. strip (funct. eq. relative to it)

Proposition. $\forall x \in \mathbb{Q},\ P(x) \in \sum_{k=0}^{w} \mathbb{Z} \cdot \tau_k(\Phi)$

Re and Im have a common transcend. factor. Dividing by it gives algebraic

$$\int_{b/d}^{i\infty} \Phi(z)\, dz = \int_0^{i\infty} - \int_0^{b/d}$$

(in neighbourhoods of points of the axis, integrate along geodesics).

Contour:



Original source details: GELFAND-P000509

Diagram and typed description.



The inner arcs partly overlap. The direction of the fourth arc from the top is unresolved.

from the cont. fraction exp.

$$\frac{b}{d} = \frac{b_m}{d_m}, \quad \frac{b_{m-1}}{d_{m-1}}, \quad \dots, \quad \frac{b_0}{d_0} = \frac{0}{1}$$

$$g_k = \begin{pmatrix} b_k & (-1)^{k-1} b_{k-1} \\ d_k & (-1)^{k-1} d_{k-1} \end{pmatrix} \in SL(2, \mathbb{Z}). \qquad \text{(choose signs).}$$

$$\begin{aligned} \int_0^{b/d} \varphi(z)\, dz &= \sum_{k=0}^{m} \int_{b_{k-1}/d_{k-1}}^{b_k/d_k} \Phi(z)\, dz \\ &= \sum_{k=1}^{m} \int_{g_k(0)}^{g_k(i\infty)} \varphi(z)\, dz \\ &= \sum_{k=1}^{m} \int_0^{i\infty} \varphi(z) \big(d_k z + (-1)^{k-1} d_{k-1}\big)^w\, dz. \end{aligned}$$



Manuscript excerpt. The first sum reads $k = 0$. The next two read $k = 1$.

Original source details: GELFAND-P000509

This is an integral lin. comb. of $\tau_k(\varphi)$.

Summary:

$$P\left(\frac{b}{d}\right) = \sum F(d_k, d_{k-1})$$

F — polynomial (form) of deg. w

Hence the arithmetical char.

$$P\left(\frac{b}{d}\right) = \sum_{k=0}^{w} A_k \left(\frac{b}{d}\right) \tau_k(\varphi)$$

— separating out the irrationalities

In this expr. addit. is unclear...

Manuscript excerpt. The abbreviation before "addit." reads "выраж." in Russian.

Original source details: GELFAND-P000509

$$\begin{aligned} k \text{ — even} \quad &\Rightarrow \quad \tau_k(\varphi) \text{ purely imaginary} \\ k \text{ — odd} \quad &\Rightarrow \quad \tau_k(\varphi) \text{ real} \end{aligned}$$

GELFAND-P000510

Uncertain reading. The mark in the upper right has two strokes joined by a third. It may read "II" or Cyrillic "И".

Original source details: GELFAND-P000510

Proposition.

$$\exists\, \omega^+, \omega^- \in \mathbb{C}, \qquad \left(\frac{\tau_0}{\omega^+}, \frac{\tau_2}{\omega^+}, \ldots, \frac{\tau_w}{\omega^+}\right), \quad \left(\frac{\tau_1}{\omega^-}, \ldots, \frac{\tau_{w-1}}{\omega^-}\right) \quad -$$

— algebraic (from the field containing the coeffs. of Φ)

Proof.

Linear eqs. for $\tau_k(\Phi)$.

a) Eichler — Shimura; depend only on w:

$$SL(2,\mathbb{Z})/(\pm 1). \qquad \text{Consider } s = \begin{pmatrix} 0 & 1 \\ -1 & 0 \end{pmatrix}, \quad t = \begin{pmatrix} 1 & -1 \\ 1 & 0 \end{pmatrix} \quad \text{(generators).}$$



Diagram and typed description.



Original source details: GELFAND-P000510

$$\left(\int_0^{i\infty} + \int_{s(0)}^{s(i\infty)}\right) \Phi(z)\, dz = 0 = \left(\int_0^{i\infty} + \int_{t(0)}^{\ldots} + \ldots\right)$$

$$\tau_k(\Phi) + (-1)^k \tau_{w-k}(\varphi) = 0 \qquad \text{(also follows from the funct. eq.)}$$

$$\int_0^{i\infty} \varphi(z) \left[z^k + z^{w-k}(z-1)^k + (-1)^k (z-1)^{w-k}\right] dz = 0.$$

This gives the sought lin. eq. for τ_k.

$S_{w+2} = R$-space of forms φ with real coeffs.

$$S_{w+2} \longrightarrow R$$



Diagram and typed description.



Original source details: GELFAND-P000510

In the period spaces take the subspaces given by the eqs.



Original source details: GELFAND-P000510

Diagram and typed description. $S_{w+2} \nearrow S^+ \searrow S^- \Big\} =_{\text{def}}$

spaces of solutions of the eqs. of Sh.-Eich.

Theorem.

a) $S_{w+2} \xrightarrow{\sim} S^-$

b) $S_{w+2} \hookrightarrow S^+$ embedding codim 1.

Theorem.



Original source details: GELFAND-P000510

Diagram and typed description.

$S_{w+2} \xrightarrow{\sim} S^-$

T_p T_p^- (Hecke op.).

matrix over $\mathbb{Z}[\lambda_p]$

Here

$$(\Phi \mid T_p)(z) = p^{w+1}\varphi(pz) - p^{-1}\sum_{k=0}^{p-1}\varphi\left(\frac{z+k}{p}\right)$$



Original source details: GELFAND-P000510

Manuscript excerpt. A minus sign is written before $p^{-1}\sum$.

Eigenfns. of the Hecke op. $\Leftrightarrow$ [Crossed out:

Original source details: GELFAND-P000510

Undeciphered passage. The reading under the heavy strikeout is unresolved.

] factor into an Euler prod.

T_p^- — expression in terms of periods (the lin. form is uniquely det.)

Application.

$$w = 10, \qquad S_{12} = R \cdot e^{2\pi iz}\prod_{n=1}^{\infty}(1-e^{2\pi inz})^{24}$$

$$= R\left(\sum_{n=1}^{\infty}\tau(n)e^{2\pi inz}\right)$$

(Ramanujan fn.)

Ramanujan identity

$$\tau(n) \equiv \sum_{d|n} d^{11} \pmod{691}$$

GELFAND-P000511

Measures.

$$P^+(x) = \frac{i}{\omega^+} \operatorname{Im} \int_x^{i\infty} \varphi(z)\, dz,$$

$$P^-(x) = \frac{1}{\omega^-} \operatorname{Re} \int_x^{i\infty} \Phi(z)\, dz$$

$$\mu_\varphi^\pm\left(a + (p^{m+1})\right) \underset{\text{def}}{=} \varrho^{-m} P^\pm\left(\frac{a}{p^{m+1}}\right) - p^w \varrho^{-(m+1)} P^\pm\left(\frac{a}{p^m}\right)$$



Uncertain reading. The P and the exponent on p in the last term are overwritten. Provisionally read as $P^\pm(a/p^m)$.

Original source details: GELFAND-P000511

measures with alg. values, and one can complete.



Uncertain reading. The last Russian verb is provisionally read “пополнять”. Another possible reading is “пополнить”.

Original source details: GELFAND-P000511

Growth. $P^\pm$ have bounded denominators. They may arise from ϱ.

$$\varrho^2 - \lambda_p \varrho + p^{w+1} = 0$$

$$\begin{cases} \varrho_1 \cdot \varrho_2 = p^{w+1} \\ \varrho_1 + \varrho_2 = \lambda_p. \end{cases}$$

Typ. case: λ_p copr. to $p \Rightarrow$ one root gives a bounded measure, the other a growing one!
Unknown relation [crossed out:

Undeciphered passage. The reading between “relation” and the next symbol is unresolved.

Original source details: GELFAND-P000511

] λ_p and p.

Integrals (Mellin transf. of p-adic char.)

$$\dots \int_{\mathbb{Z}_p^*} \chi \, d\mu_\Phi^\pm$$

Manin can do it only for a char. of finite ord. $\chi : \mathbb{Z}_p^* \to K^*$, $\chi^m = 1$ and primitive.

Theorem

$$\dots \int_{\mathbb{Z}_p^*} \chi \, d\mu_\varphi^\pm = \dots L_\varphi(1, \chi),$$

where

$$L_\Phi(s, \chi) = \sum_{n=1}^{\infty} \chi(n) a_n n^{-s}$$

$$\dots \dot{L}_\varphi(1, \chi) = \dots \int_{R_+^*} \varphi_\chi(z) \, dz, \qquad \text{where } \Phi_\chi = \sum \chi(n) a_n e^{2\pi i n z}.$$

Uncertain reading. A separate dot is visible above L in the manuscript. Its meaning is unresolved.

Original source details: GELFAND-P000511

On Lichtenbaum's conjectures: on the connection of K-groups of alg. fields with ζ-fns. at int. points.

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{\pi^2}{6}, \qquad \sum_{n=1}^{\infty} \frac{1}{n^3} = 2\pi^2 |K_4\mathbb{Z}| \cdot e_5(\alpha_5)$$

For the first time there is a conjecture

α_5 — a generator of $K_5\mathbb{Z}$. (of the free part)

e_5 — a homom. into the real numbers (a certain one)

It is unproved that $\sum_1^{\infty} \frac{1}{n^3}$ is transcend. Euler's const. also unproved.



Undeciphered passage. The text inside the rectangle is heavily crossed out. Its reading is unresolved.

Original source details: GELFAND-P000511

GELFAND-P000512

Uncertain reading. Clipped strokes are visible at the upper right. The reading is unresolved.

Original source details: GELFAND-P000512

24.9.73. Gelfand Sem.

Pincus Douglas, Coburn, Vilneyer and Singer Helton and Roger Howe. (Howe)



Original source details: GELFAND-P000512

Uncertain reading. The surname after Coburn is provisionally transcribed “Вилнейер” and romanized “Vilneyer”. The middle letters run together.

(interesting work in funct. analysis).

Theorem (Helton, How). close to the work of Krein, Gohberg, Simonenko, etc.

Let B — a bilin. form on 2 polynomials [inserted above the line: of 2 var.], with

$$B(P_1(Q), P_2(Q)) = 0,$$

if $P_1(z), P_2(z)$ — polyn. in one var. z, and Q — a polyn. in any number of var. Then

$$B(R, S) = L(\{R, S\}), \qquad \{R, S\} \text{ — Poisson bracket}$$

L — lin. form.



Original source details: GELFAND-P000512

Manuscript excerpt. The insertion “of 2 var.” is circled and points to the place after “polynomials”.

— · —

Let U, V — self-adj. and commuting mod nuclear operators. Then

$$\mathrm{Tr}\{[R(U,V), S(U,V)]\} = \iint \{R, S\}\, d\sigma$$

R, S — polynomials. The order of U and V in them is immaterial.

— · —

Book by Douglas Banach algebras technique.
$\Rightarrow$ in the p-adic case suitably chosen normed rings are needed in place of diff. operators.

— · —

Kirillov.
L. Brown, R. Douglas, P. Fillmore.
Extensions of Banach algebras (of a nontraditional type).
$\mathcal{K}$ — alg. of comp. operators on a sep. Hilbert space.
Def. 1.

$$0 \to \mathcal{K} \to \mathcal{A} \to C(X) \to 0, \qquad X \text{ — compact}$$

Exts. form a group $\mathrm{Ext}(X) = \mathrm{Ext}_1(X)$.
Another definition gives the same group:
Def. 2.



Diagram and typed description.

$$C(X) \hookrightarrow \mathcal{L}/\mathcal{K}$$

Original source details: GELFAND-P000512

1) consider all embeddings.
2) identify embeddings differing by a unit. op. (unit. eq. UAU^{-1}).
3) Embeddings of the form $C(X) \to \mathcal{L} \to \mathcal{L}/\mathcal{K}$ are regarded as triv.
Equiv. classes then form a group.



Diagram and typed description.

$$C(X) \underset{\tau_2}{\overset{\tau_1}{\rightrightarrows}} \mathcal{L}/\mathcal{K}$$

Original source details: GELFAND-P000512

$\tau_1 \oplus \tau_2$ already in $H_1 \oplus H_2 \cong H$

Functor

Diagram and typed description.

Top ⟶ Ab.

Original source details: GELFAND-P000512

Main result: the functor $\mathrm{Ell}(X)$ reduces to $\mathrm{Ext}(X)$ (answer to a question of Atiyah).

$$\mathrm{Ext}_{1-n}(X) = \mathrm{Ext}\left(\underset{\substack{| \\ n\text{-fold suspension}}}{S^n X} \right)$$



Manuscript excerpt. A short stroke under $S^n X$ points to the label.

Original source details: GELFAND-P000512

GELFAND-P000513

[source number: 14]

Th. 1. Exact seq.

$$\mathrm{Ext}_1(A) \to \mathrm{Ext}_1(X) \to \mathrm{Ext}_1(X/A) \to \mathrm{Ext}_0(A) \to \dots$$

$A \subset X$

Th. 2. There is a pairing

$$K^1 \times \mathrm{Ext}_1 \to \mathrm{Ext}_0$$

$$K^1(X \times Y) \times \mathrm{Ext}_1(X) \to K^0(Y)$$

~~The functor Ext_1 is computed for all~~



Undeciphered passage. The end of the crossed-out line is illegible.

Original source details: GELFAND-P000513

Uncertain reading. The crossed-out verb is provisionally read as “computed”.

Original source details: GELFAND-P000513



Diagram and typed description.

$\mathrm{Ext}_1 \oplus Z = K_0$

Original source details: GELFAND-P000513

for simpl. complexes.

Original source details: GELFAND-P000513

Uncertain reading. The sign before Z is heavily retraced. Provisionally set as $\oplus$. It could be $\otimes$.

Example of an extension.

$$0 \to \mathcal{K} \to C^*(\text{„}ax + b\text{”}) \to C(\infty) \to 0$$

$$\mathrm{Ext}(\infty) = Z + Z.$$

What is this pair of numbers for a specific op.?

— · —

~~$X = S^1$~~

Original source details: GELFAND-P000513

Manuscript excerpt. $X = S^1$ is crossed out on the left.

$$X = \mathbb{T} = S^1$$



Original source details: GELFAND-P000513

Diagram and typed description.

$C(\mathbb{T}) \longrightarrow \mathcal{L}/\mathcal{K}$

gen. by z
as an alg. with invol.

Let T — the image of z.

$$TT^* = 1 \bmod \mathcal{K}$$

up to unit. equiv. and mod $1 + \mathcal{K}$.

Answer: index (classific.).

— · —

Th.

$$\left\{ \begin{matrix} N \\ | \\ \text{norm.} \end{matrix} \quad + \mathcal{K} \right\}$$

is norm-closed among all op.,



Manuscript excerpt. A short stroke connects N to the label “norm.” below.

Original source details: GELFAND-P000513

but ~~$N_1N_2 = N_2N_1$~~ pairs $\{N_1 + K_1,\ N_2 + K_2\}$ with cond. $N_1N_2 = N_2N_1$ [inserted and circled at the left: not closed] in the set of all pairs of this kind.



Manuscript excerpt. The equality is crossed out before “pairs”. The insertion at the left is circled.

Original source details: GELFAND-P000513



Uncertain reading. The crossed-out word below the circle is provisionally read as “not closed”.

Original source details: GELFAND-P000513

Next time: Fuchs's talk pres. on Mishchenko.

Fuchs. Quillen Higher algebraic K-theory I

(Proc. of symp. on K-theory)

Introduction. M — a category (abelian or spec. additive). We define $K_i(M)$.

Constructions

QM — cat. of quotients $\Rightarrow$ classif. space $BQM \Rightarrow$

$$\Rightarrow \quad K_i(M) = \pi_{i+1}(BQM).$$

Essential part.

A simpl. object in a category S — a contravar. functor Ord $\to S$, where Ord — the can. category of nonnegative integers.

$$\mathrm{Ord}^{\circ} \longrightarrow S$$

Uncertain reading. There is a small oval above Ord. Provisionally set as $\circ$. It could also be o or 0.

Original source details: GELFAND-P000514

(Functor always means covar. functor).

Ord objects — $0, 1, 2, 3, \ldots$

Morphism [crossed out:

Undeciphered passage. The reading under the strikeout is unresolved.

Original source details: GELFAND-P000514

] $p \to q$ is called a monotonically nondecr. map

$$(0, 1, \ldots, p) \longrightarrow (0, 1, \ldots, q)$$

All are repr. as compositions of morphisms of 2 kinds:



Original source details: GELFAND-P000514

Diagram and typed description.

$$\begin{array}{cccc} & \underline{p \longrightarrow p+1} & & \underline{p+1 \longrightarrow p} \\ & 0, \longrightarrow 0 & & 0 \quad\quad 0 \\ & \vdots \quad\quad \vdots & & \vdots \quad\quad \vdots \\ 1). & i-1 \longrightarrow i-1 & & \\ & i \longrightarrow i+1 & & i \longrightarrow i \\ & \vdots \quad\quad \vdots & & i+1 \longrightarrow i \\ & p \longrightarrow p+1 & & \ldots \quad\quad \vdots \\ & & & p+1 \quad\quad p \end{array}$$

To specify a simpl. obj. it suffices to give a seq. of objects

$$S_0, S_1, S_2, \ldots$$

and morphisms



Diagram and typed description.

$S_0 \leftleftarrows S_1 \;\substack{\leftarrow\\ \leftarrow\\ \leftarrow}\; S_2 \;\substack{\leftarrow\\ \leftarrow\\ \leftarrow\\ \leftarrow}\; \cdots$

Original source details: GELFAND-P000514

(correspond to embeddings of type 1))

and

Diagram and typed description.

$S_0 \longrightarrow S_1 \;\substack{\rightarrow\\ \rightarrow}\; S_2 \;\substack{\rightarrow\\ \rightarrow\\ \rightarrow}\; S_3 \;\substack{\rightarrow\\ \rightarrow\\ \rightarrow\\ \rightarrow}\; \cdots$

Original source details: GELFAND-P000514

(corr. to maps of type 2))

(The relations must be satisfied).

they are easy to write down

S — either the cat. of sets or the cat. of top. spaces.

Groups, smooth manifolds, etc. are also possible.

Important example: sing. complex of a top. space. S — cat. of sets.

X — top. space. Denote by S_q — all sing. simplices of X



Manuscript excerpt. The Russian abbreviation reads “Обозн.”.

Original source details: GELFAND-P000514

(cont. maps $\Delta^q \to X$, where

$$\Delta^q = \{(x_1, \ldots, x_{q+1}) \in R^{q+1}, \quad x_i \geq 0, \quad \sum x_i = 1\}.$$



Manuscript excerpt. An opening parenthesis precedes “cont. maps”. There is no visible matching parenthesis before the next formula.

Original source details: GELFAND-P000514

$$\exists\ \delta_i : \Delta^{q-1} \longrightarrow \Delta^q$$

canon. map onto the i-th face (vertices ordered)



Uncertain reading. The letter with index i is provisionally set as δ_i. It could be γ_i.

Original source details: GELFAND-P000514

Sing. simplex — composition

$$\Delta^{q-1} \longrightarrow \Delta^q \longrightarrow X$$

Uncertain reading. The initial Russian abbreviation is provisionally read as “Син.”. Its last letter is uncertain.

Original source details: GELFAND-P000514

We get $q+1$ maps

Original source details: GELFAND-P000514

Diagram and typed description.
$S_q \overset{\longrightarrow}{\underset{\longrightarrow}{\cdots}} S_{q-1}$ (faces).



Original source details: GELFAND-P000514

Diagram and typed description.
$S_q \overset{\longrightarrow}{\underset{\longrightarrow}{\cdots}} S_{q+1}$
($q+1$ in all)

from $\Delta^{q+1} \longrightarrow \Delta^q$ affine projections (i-th identifies the i-th vertex with the $(i+1)$-st).

— · —

GELFAND-P000515

[source number: 15]

Realization.

Let S — the cat. of sets or top. spaces.

A top. space is associated with a simpl. obj. in the cat. of sets or top. spaces.

Elements of [inserted above the line, circled: the set] S_i are called simplices



Original source details: GELFAND-P000515

Manuscript excerpt. The circled abbreviation for “set” points to the place after “Elements”.

The images of arrows from left to right are called degenerate simplices.

The others are called nondegenerate. Arrows from right to left take nondeg. to nondegenerate simplices.



Original source details: GELFAND-P000515

Manuscript excerpt. The manuscript states that the right-to-left arrows take nondeg. to nondegenerate simplices.

Consider $\Delta^q \times S^0_q$

nondeg. simpl. from S_q. (S^0_q — a discrete top. space).

In $\coprod_q \Delta^q \times S^0_q$ (disjoint union) an identification.

$$\Delta^{q-1} \times s, \qquad s \in S^0_{q-1}$$

is identified with part of $\Delta^q \times s'$, $s' \in S^0_q$, when s — the image of s' under the map (i-th)

$$S_{q-1} \xleftarrow{i} S_q \qquad (i\text{-th face})$$

Manuscript excerpt. A prime is visible in the membership condition: $s' \in S^0_q$.

Original source details: GELFAND-P000515

We get a top. space. This is a cell space (the interiors are left unglued).

But: boundary points can be glued together (so it is not a simplicial space).

The same ex. if S — top. spaces. A top. struct. no longer arises, since in $\Delta^q \times S^0_q$ there is the direct product top.

Original source details: GELFAND-P000515

Manuscript excerpt. The manuscript reads “A top. struct. no longer arises”.

Ex.: for a good top. space the realization of the sing. [crossed out:

Undeciphered passage. The reading under the strikeout is unresolved.

Original source details: GELFAND-P000515

] complex is homotopy equiv. to X.

To reconstr. a polyhedron, take for S_i the aff. maps of simplices into it

Manuscript excerpt. The Russian abbreviation before “polyhedron” reads “восстан.”.

Original source details: GELFAND-P000515

Original source details: GELFAND-P000515

Diagram and typed description.



Realization commutes with multiplication.



Original source details: GELFAND-P000515

Diagram and typed description.

$$\begin{array}{ccc} S_0' \longleftarrow \dots & & \mathcal{S}\times\mathcal{S}' \longrightarrow \mathcal{S} \\ & & \qquad\quad \longrightarrow \mathcal{S}' \\ S_0\times S_0' \longleftarrow S_1\times S_1' & & \end{array}$$

hence



Original source details: GELFAND-P000515

Diagram and typed description.

$$\begin{array}{ccc} \operatorname{real}(\mathcal{S}\times\mathcal{S}') & \longrightarrow & \operatorname{real}\mathcal{S} \\ & & \operatorname{real}\mathcal{S}' \end{array}$$

and together they form



Original source details: GELFAND-P000515

Diagram and typed description.

$$\operatorname{real}(\mathcal{S}\times\mathcal{S}') \longrightarrow \operatorname{real}\mathcal{S}\times\operatorname{real}\mathcal{S}'.$$

Prop. It turns out to be — a homeomorphism.

Example.

Original source details: GELFAND-P000515

Diagram and typed description. ⟼

Ordered segment.

S^0 — 2 elements

S^1 — 3 elem. (counting degenerate ones)

$S^p = (p+2)$ elem. i-th:

$$[0, i-1] \longrightarrow 0, \qquad [i, p] \longrightarrow 1$$



Original source details: GELFAND-P000515

Uncertain reading. The raised sign to the right of S is heavily retraced. Provisionally set as p. A short stroke appears above S on the left.

$S_p \times S_p$

Uncertain reading. Faint detached strokes follow the product. Their reading is unresolved.

Original source details: GELFAND-P000515

(next time.)

GELFAND-P000516

§2. Classif. space in a category.

C — a category (small). Associated to it is its nerve NC (simpl. object of the cat. of sets).

$$NC_q = \{[?] \quad X_0 \longrightarrow \cdots \longrightarrow X_q\} \qquad \text{set of such diagrams}$$

Uncertain reading. An overwritten mark is visible after the opening brace before X_0. The reading is unresolved.

Original source details: GELFAND-P000516

$$NC_q \longrightarrow NC_{q-1}$$

0th



Diagram and typed description. X_0 (discard it).

Original source details: GELFAND-P000516

qth — discard X_q

ith — compose the ith and $(i+1)$st arrows



Diagram and typed description. $\cdots \longrightarrow X_i \longrightarrow \cdots$

Original source details: GELFAND-P000516

$$NC_q \longrightarrow NC_{q+1}$$

one of the X is doubled and the id. morphism is inserted.

~~Nerve~~ Real $NC = BC$ — classif. space of the category.

Uncertain reading. The crossed-out word is provisionally read as “Нерв.” (“Nerve”).

Original source details: GELFAND-P000516

Example: the classif. space of the group G is obtained from the following cat.:

Original source details: GELFAND-P000516

Undeciphered passage. The reading under the strikeout after the colon is unresolved.



Original source details: GELFAND-P000516

Manuscript excerpt. The Russian abbreviations after “from” read “след. катег.”.

1 object, with morphisms the elements of G.

$$NC_q = \underbrace{G \times \cdots \times G}_{q}$$

— · —

$G = Z_2$. Simplices:

Nondeg. simpl. — do not contain 1.

One nondeg. simpl. of each dimension.

Original source details: GELFAND-P000516



Diagram and typed description. Three long strokes and one short stroke in an oval. Dark overlapping marks at the left edge.

Ex. Wind the 2-dimensional one twice. One gets RP_∞.

Original source details: GELFAND-P000516

Manuscript excerpt. The manuscript reads “2-мерную намот. дважды”.



Original source details: GELFAND-P000516

Manuscript excerpt. The phrase ends with “дважды” (“twice”).

— · —

Let M — a category that is either abelian or a full subcat. of an abelian cat., closed under extensions. Suppose the isom. classes of objects form a set. Then it is equivalent to a small category. Category QM. $\mathrm{Ob}(QM) = \mathrm{Ob}(M)$.

$$\mathrm{Hom}_{QM}(X', X'') \Rightarrow \text{diagrams}$$



Diagram and typed description.

$X' \longleftarrow X \longrightarrow X''$

epimorphism with kernel

monomorphism with cokernel

Original source details: GELFAND-P000516

This is a category.

Definition.



Diagram and typed description.

$K_i(M) = \pi_{i+1}(BQM).$

Original source details: GELFAND-P000516

GELFAND-P000517

Continuation of Fuchs's talk (following Marchenko).

Example of realization

S_q consists of $q+2$ elements. Interpret it as the set of aff. maps from Δ^q into the segment Δ^1, compatible with the ordering of the vertices of Δ^q and Δ^1.

The morphisms $S_{q-1} \leftarrow S_q \rightarrow S_{q+1}$ are def. as for the singular simplices of the space $I = \Delta^1$ [inserted above the line: (restriction to affine maps)], i.e. by composition with an embedding and restrictions.



Manuscript excerpt. The circled insertion "restriction to affine maps" points to the place after the formula.

Original source details: GELFAND-P000517

Nondegenerate simplices — 2 0-dimensional $* \to I$ and 1 1-dimensional one.

$S_q \times S_q$ when is an element of $S_q \times S_q$ nondeg.?

Elem. — a pair (φ, ψ), it is nondeg. when there are no 2 vertices in Δ^q, mapped by φ and ψ [crossed out:

Undeciphered passage. The reading of the crossed-out sign is unresolved.

Original source details: GELFAND-P000517

] into one [crossed out:

Undeciphered passage. The reading of the crossed-out word is unresolved.

Original source details: GELFAND-P000517

] vertex.

$$S_0 \times S_0 \quad \text{— 4 elems.} \qquad * \to (0,0),(0,1),(1,0),(1,1)$$

$$S_1 \times S_1 \qquad \begin{pmatrix}1\\0\end{pmatrix} \to \begin{matrix}\varphi & \psi\\ 0 & 0\\ 0 & 1\end{matrix} \qquad \begin{pmatrix}0 & 1\\ 0 & 1\end{pmatrix} \text{degenerate}\Big)$$

$$\begin{pmatrix}0 & 0\\ 1 & 1\end{pmatrix}\begin{pmatrix}0 & 0\\ 1 & 0\end{pmatrix}\begin{pmatrix}0 & 1\\ 1 & 1\end{pmatrix}\begin{pmatrix}1 & 0\\ 1 & 1\end{pmatrix}$$

Uncertain reading. A stroke resembling a closing parenthesis is crossed out after the second column, before “degenerate”.

Original source details: GELFAND-P000517

$$S_2 \times S_2 \qquad \Delta \to \begin{matrix}0 & 0 & 0 & 0\\ 1 & 0 & 0 & 1\\ 1 & 1 & 1 & 1\end{matrix}$$

Original source details: GELFAND-P000517

Manuscript excerpt. The manuscript has four columns with no dividers.

Realization of $S \times S$.



Diagram and typed description. 

Strokes overlap at the right end of the lower side. Its direction is unresolved.

Original source details: GELFAND-P000517

Classif. space of a category.

C — a small cat., NC — the nerve of the category

$(NC)_q$ $(= S_q)$ — all diagrams in C of the form $X_0 \to \ldots \to X_q$

the maps — taking compositions, discarding endpoints and inserting id X_j.



Original source details: GELFAND-P000517

Uncertain reading. The Russian abbreviation before “endpoints” is provisionally read “отбрс.”. It could be “отброс.”.



Original source details: GELFAND-P000517

Uncertain reading. The subscript on X is provisionally set as j. It could be a capital J.

$$BC = \text{Real}\, NC.$$

The vertices of BC — objects of C, 1-dimensional simplices are nonidentity morphisms. Δ are stretched over commutative simplices

Original source details: GELFAND-P000517

Diagram and typed description. 

and so on.

Barycentr. subdiv. of a polyhedron of high deg. is the nerve of some category.

Original source details: GELFAND-P000517

Uncertain reading. The Russian abbreviation is provisionally read “подразд.”. The last letter could be “б”.

Properties:

$$B(C \times C') \cong BC \times BC'$$

$$f : C \rightsquigarrow C' \quad \Rightarrow \quad Bf : BC \to BC'$$

If there is also $g : C \to C'$ and a nat. map from f to g, then $Bg : BC \to BC'$ is connected to Bf by a canonical homotopy.

Let $\{0, 1\}$ — a cat. of 2 objects with one morphism $0 \to 1$

A morphism of the functors f and g — a functor from $C \times \{0, 1\}$ to C'.

GELFAND-P000518

[source number: 21]

$F : C \times \{0,1\} \to C'$. At the endpoints f, g; morph. $0, 1$ — nat. map.
It determines a map, a homotopy connecting f with g

$$BC \times I = B(C \times I) \to BC'.$$

If C has a terminal or an initial object, then BC is contractible —
— it is a cone.
If $f : C \rightsquigarrow C'$ has a left or right adjoint, then Bf — a homotopy equivalence.

$$BC^{\circ} = BC, \qquad B(C \times C') = BC \times BC'.$$

Analogue of the homotopy sequence of a fibration.
Let $f : X \to Y$ — a Serre fibration. Then

$$\ldots \to \pi_q(X, x) \to \pi_q(Y, f(x)) \to \pi_{q-1}(f^{-1}(f(x), x)$$
$$\to \pi_{q-1}(X, x) \to \ldots$$



Manuscript excerpt. The parentheses follow the manuscript. One closing parenthesis is visible before the comma.

Original source details: GELFAND-P000518

If f does not satisfy the homotopy lifting axiom, then after replacement by an equivalent map it will satisfy it and we get the sequence. Here is the construction:
Let $\widetilde{X} = \{(x, s),\ x \in X,\ s : I \to Y,\ s(0) = f(x)\}$.
$\widetilde{X} \underset{\sim}{\supset} X$. The map $\widetilde{f} : \widetilde{X} \to Y$ is constructed as follows:

$\widetilde{f}(x, s) = s(1), \qquad \widetilde{f}|_X = f$ but now the homotopy lifting axiom holds.
Because $\widetilde{X} \simeq X$ we have an exact sequence.



Uncertain reading. The sign between $\widetilde{X}$ and X is provisionally set as $\simeq$. A wavy stroke crosses a straight one in the manuscript.

Original source details: GELFAND-P000518

$$\ldots \to \pi_q(X) \to \pi_q(Y) \to \pi_{q-1}(\text{homot. fibre}) \to \pi_{q-1}(X) \to \ldots$$

Now let $g : C \rightsquigarrow C'$, then we have

$Bg : BC \rightsquigarrow BC'$. We would like to construct a "homotopy fibre" of Bg.

This has not been done. There is a surrogate.

The constr. also depends on some object $Y \in \mathrm{Ob}\, C'$.

Def. the category $Y\backslash g$. $\mathrm{Ob}(Y\backslash g)$ — the pairs (X, u), where

$$X \in \mathrm{Ob}\, C, \qquad u \in \mathrm{Mor}_{C'}(Y, g(x)).$$

A morphism (X, u) to (X', u') — a morphism $\varphi : X \to X'$, compat. with u and u'. There is a nat. map

$$B(Y\backslash g) \to \text{homot. fibre } Bg : BC \to BC'$$



Manuscript excerpt. The argument of $g(x)$ shows a lowercase x. The letters in the pairs in the description of the morphism read as uppercase X and X'.

Original source details: GELFAND-P000518

Theorem. Let the functor g be such that

$\forall v \in \mathrm{Mor}_{C'}(Y, Y')$ the resulting map is $Y'\backslash g \xrightarrow{v\backslash g} Y\backslash g$ and $B(v\backslash g) : B(Y'\backslash g) \to B(Y\backslash g)$ is a homot. equivalence (which in general is false). Then $B(Y\backslash g)$ — homot. fibre $BC \overset{Bg}{\rightsquigarrow} BC'$.

GELFAND-P000519

Construct the map $B(Y\backslash g)$ — homot. fibre of Bg.

If there is $(X_0, u_0) \leftarrow \cdots \leftarrow (X_\tau, u_\tau)$ (a simplex of $B(Y\backslash g)$) then there is also $X_0 \leftarrow \cdots \leftarrow X_\tau$ and one only needs to know $Y \to g(X_\tau)$ (from it all the following are recovered: u_j



Original source details: GELFAND-P000519

Manuscript excerpt. The manuscript has no closing parenthesis after this line.

$X_0 \leftarrow \cdots \leftarrow X_\tau$ — a simplex of BC of dimension τ. Together with u_τ it defines a simplex

$$g(X_0) \leftarrow \cdots \leftarrow g(X_\tau) \overset{u}{\leftarrow} Y$$

in BC'.



Uncertain reading. The index is provisionally set as τ. The same letter is used for the dimensions.

Original source details: GELFAND-P000519

Thus, from a simplex in $B(Y\backslash g)$ we have defined 2 simplices, in BC and in BC' of dimensions τ and $\tau+1$ resp.. A simplex from $B(Y\backslash g)$ is mapped as follows: the point of the space BC corresponding to that point (in barycentric coord.) and the straight path in the simplex of BC', connecting Bg of this point to Y:



Original source details: GELFAND-P000519

Diagram and typed description.



Overlapping strokes follow Bg on the left side of the quadrilateral. Their reading is unresolved.

This is a homot. equiv. $\forall v$ iff the conditions of the theorem hold.



Original source details: GELFAND-P000519

Manuscript excerpt. The beginning of the second line to the right of the sketch reads $\forall v$.

Remark by Fuchs: probably $Y\backslash g$ should be def. as the inverse limit over the spectrum of all $Y\backslash g$ with different Y.

Mishchenko. (Representations according to Mishchenko)

Λ — a ring with involution, H — a Hilbert space and 2 reprs. T_1 and T_2 of the ring Λ into the algebra of bounded op. in H, F — a Fredholm operator in H and let

$$\forall \lambda \in \Lambda \qquad FT_1(\lambda) - T_2(\lambda)F \in \text{Comp}(H)$$

This system $\{T_1, T_2, F\}$ is called a Fredholm repr. of Λ.

Atiyah considered $\Lambda = C(M)$, M — a manifold (symposium in Tokyo).

Original source details: GELFAND-P000519

Manuscript excerpt. The parenthetical in the manuscript reads “symposium in Tokyo”.

Constr. with these representations

1) Atiyah (1970) $\Lambda = C(M)$ $\quad \forall$ repr., assign index $T \in K_0(M)$

2) $\Lambda = \mathbb{Z}[\pi] \quad \Rightarrow \quad \forall$ repr., construct $\xi_T \in K^0(B\pi)$.

3) Λ — arbitrary, $\quad A = (a_{ij})$ — a quadr. form on $\Lambda^n \quad (a_{ij} \in \Lambda)$

$$A^* = A, \quad \exists A^{-1} \quad \Rightarrow \quad \text{Construct sign}_T A \in \mathbb{Z}.$$

Original source details: GELFAND-P000519

Undeciphered passage. Crossed-out number before “1)”. Possibly “4)”.

1) $\Lambda = C(M)$, T — a Fredh. repr. of Λ in H, $\quad T = (T_1, T_2, F)$.

H_i — modules over Λ. ind F — a number. Let η — a bundle, $\Gamma(\eta)$ — a proj. module over $C(M)$. Consider

GELFAND-P000520

[source number: 22]

$$H_1 \otimes_{C(M)} \Gamma(\eta) \xrightarrow{F \otimes 1_\eta} H_2 \otimes_{C(M)} \Gamma(\eta)$$

$$\operatorname{ind}(F \otimes 1_\eta) : K^0(M) \to \mathbb{Z}, \quad \text{i.e. an element of } K_0(M)$$

This is somewhat crude because $\exists$ elements of finite order in $K^0(M)$.

More precisely: T determines $\operatorname{index}_T : K^0(M \times Y) \to K^0(Y)$; $\quad \forall Y$. This is already an element of $K_0(M)$.

If $\sigma(A) \in K^0(T^*M)$, $\quad A : H \to H$, $\quad$ since $[f, A]$ — compact, there is

Undeciphered passage. The short crossed-out group of signs before “index” cannot be read.

Original source details: GELFAND-P000520

index$(A) \in K_0(M)$.

Uncertain reading. The stroke after the commutator has been retraced. It is provisionally set as a dash.

Original source details: GELFAND-P000520

Thus these elems. are Poincaré dual to one another $K^0(T^*M) \underset{\mathcal{D}}{\sim} K_0(M)$. Then

index $A = \mathcal{D}(\sigma(A))$

(NB one can constr. the direct image of A)

2) π — an arbitrary discr. group, $\Lambda = \mathbb{Z}[\pi]$ — its group ring, B_π —

— the classif. space. T — a Fredh. repr.: $T = (T_1, F, T_2)$. We need to constr. $\xi_T \in K(B_\pi)$.

$K(B_\pi)$ is understood as $[B_\pi, BU]$, but $BU \simeq \mathcal{F}$ (Fredh. op. [inserted below: in ℓ^2])



Manuscript excerpt. “In ℓ^2” is written below “Fredh. op.”.

Original source details: GELFAND-P000520

$$B_\pi \ni x \to \Phi_x \in \mathcal{F}.$$

Let. $\varphi_x : H_1 \to H_2$ where F from T acted, $\widetilde{B}_\pi$ — the universal cover of B_π, on which there acts π. Take $\widetilde{B}_\pi \times H_i$ with π acting on $\widetilde{B}_\pi$ in the standard way, and on H_i via T_i. Let $\widetilde{B}_\pi$ — a cell complex (even simplicial).

Constr. $\varphi_x : \widetilde{B}_\pi \times H_1 \to \widetilde{B}_\pi \times H_2$. Let $[\widetilde{B}_\pi]^k$ — the k-dim. skeleton of $\widetilde{B}_\pi$. Choose one $\sigma_i^0 \in [\widetilde{B}_\pi]^0$ in any orbit of the action of π and set $\Phi_{\sigma_i^0} \overset{\text{def}}{=} F$.



Original source details: GELFAND-P000520

Manuscript excerpt. The $\in$ sign touches the left bracket of the skeleton.

We have:

a) equivariance

b) $\forall x, y \in [\widetilde{B}_\pi]^0 \quad \Rightarrow \quad \varphi_x - \varphi_y \in \text{Comp}$

Extend this to $[\widetilde{B}_\pi]^1$; by the simplicial action of π we can choose one simplex in $\forall$ orbit and extend over the simplex as $p\varphi_1 + q\varphi_2$, $p + q = 1$ with equivariance satisfied. By ind. we obtain the whole family φ_x. From equivariance we have



Original source details: GELFAND-P000520

Diagram and typed description.

$$\begin{array}{ccc} (\widetilde{B}_\pi \times H_1)/\pi & \longrightarrow & (\widetilde{B}_\pi \times H_2)/\pi \\ & {\scriptstyle H_1}\searrow \quad \swarrow{\scriptstyle H_2} & \\ & \widetilde{B}_\pi/\pi = B_\pi & \end{array}$$

But by Kuiper $(\widetilde{B}_\pi \times H_i)/\pi \approx B_\pi \times H_i$.



Original source details: GELFAND-P000520

Manuscript excerpt. The manuscript gives the Russian genitive “Кюйпера” for Kuiper.

After identification we have $B_\pi \times H_1 \to B_\pi \times H_2$, which defines $\varphi_x : H_1 \to H_2$.

GELFAND-P000521

15/$\overline{X}$-73 Gelfand's seminar.

Rudakov. On representations of infinite-dimensional Lie algebras.

Consider W_n — the Lie alg. of form. vector fields ([inserted below: cont.] deriv. of the ring $k[[x_1, \ldots, x_n]]$).

Original source details: GELFAND-P000521

Manuscript excerpt. The circled “cont.” is inserted from below before “deriv.”.

$$\left(\sum_{i=1}^{n} a_i(x_1, \ldots, x_n)\frac{\partial}{\partial x_i}\right)$$

$W_n = \mathcal{L} \supset$ [crossed out] $M \supset M'$.

Uncertain reading. Lower loops are visible under the crossing out before M. This could also be M.

Original source details: GELFAND-P000521

[under M: subalg.]



Undeciphered passage. The crossed-out words under "subalg." cannot be read.

Original source details: GELFAND-P000521

[under M':] an ideal of finite codim. in M.

Suppose we are given a repr. of

$$M/M' \longrightarrow \text{repr. of } M \underset{\text{induc.}}{\longrightarrow} \text{representation of } \mathcal{L}.$$

Thm.: all irred. reprs. of W_n are obtained this way, with finitely many exceptions.

Spaces countable-dimensional discrete (without top.). E

[under «countable-dimensional»: (vect. spaces)]

Repr. $\varrho : \mathcal{L} \longrightarrow \operatorname{Aut} E$, with

$$x \in E,\ \exists V \subset \mathcal{L} \qquad \varrho(v)x = 0. \qquad \text{(loc. const. functions).}$$

[under V: nbhd. of 0]



Manuscript excerpt. The argument of ϱ is a lowercase v. The condition on the left uses a capital V.

Original source details: GELFAND-P000521

Filtrations of nbhds. of zero

$$\mathcal{L} = \mathcal{L}_{-1} \supset \mathcal{L}_0 \supset \ldots \supset \mathcal{L}_k \supset \ldots$$

$$\mathcal{L}_k = \left\{ \sum a_i \frac{\partial}{\partial x_i} \text{ [crossed out]}, \text{ deg. } a_i \geqslant k+1 \right\}.$$



Undeciphered passage. The crossed-out notation between the derivative and the comma cannot be read.

Original source details: GELFAND-P000521

Assertion: consider cont. reprs. of $\mathcal{L}_0/\mathcal{L}_k$ and irred. reprs. (and inducing representations).
Exceptions: in the dual spaces to spaces of closed forms
Suppose there is a repr. of the alg. $\mathcal{L}$.

$$x \in E; \quad p(x) = \{\min p : \mathcal{L}_p x = 0\}$$

($\exists$ there a bounded cont. repr.?).
Consider

$$\bar{p}(E) = \min_{x \in E,\ x \neq 0} p(x).$$

$$E_0 = \{x \in E,\ p(x) = \bar{p}(E)\} \text{ — } \mathcal{L}_0\text{-submodule}.$$

If $\bar{p}(E) > 1$, then the repr. is induced: $E = \mathrm{Ind}(E_0)$



Uncertain reading. The digit is retraced. The bottom stroke resembles the base of a 1. The overlapping strokes make this reading provisional.

Original source details: GELFAND-P000521

— · —

Exceptions:

Ω^p — form. forms of deg. p, $\quad d\Omega^p$ — exact forms,

$(d\Omega^p)^*$ — the dual space (with the natural topology)

— · —

There are corresponding results for Hamiltonian ones as well.

— · —

GELFAND-P000522

[source number: 23]

Kirillov. A similar result about the group
Unproved, but well known
M — a manifold, Diff M — the group of diffeomorphisms.

Uncertain reading. The Russian abbreviation is “мн-зие”, probably short for “manifold”.

Original source details: GELFAND-P000522

describe those reprs. that have finite funct. dimension.

$$\mathrm{Diff}\, M \supset H_{x_1,\dots,x_n}$$

[under $H_{x_1,\dots,x_n}$:] keeps fixed $x_1, \dots, x_n$.
Consider cont. reprs. of H/H_0 and induce.
[on the right:] H_0 preserves infin. nbhds. of order n.
Fuchs. (continuation).
$f : C \longrightarrow C'$ a functor
[under C, C':] small cats.

$$Y \in \mathrm{Ob}\, C', \qquad Y\backslash f$$

$$\mathrm{Ob}(Y\backslash f) = \{(X, u),\ X \in \mathrm{Ob}\, C,\ u : Y \longrightarrow f(X)\}.$$

$$v : Y \longrightarrow Y' \quad \rightsquigarrow \quad v\backslash f : Y'\backslash f \longrightarrow Y\backslash f$$

$\exists$ a nat. map

$$B(Y\backslash f) \longrightarrow \text{homot. fibre of the map } Bf : BC \longrightarrow BC'$$

over the point $Y \in BC'$.

$$\longleftarrow \cdot \longrightarrow$$

new cat. of pairs (X, u), where $X \in \mathrm{Ob}\, C$, $u : f(X) \longrightarrow Y$



Diagram and typed description. f/Y

Original source details: GELFAND-P000522

another model of the homot. fibre.
The thm. also holds (dual)
Theorem A. This condition holds if all cats. $Y\backslash f$ are contractible (i.e.



Undeciphered passage. The word after "i.e." is crossed out. Its reading is unresolved.

Original source details: GELFAND-P000522

have contractible classif. spaces). Then the conclusion also holds (in particular, the exact homot. seq.) $\Rightarrow Bf : BC \longrightarrow BC'$ induces isos. of homot. groups.

— · —

$\underline{\underline{K_i(M)}}$

M — a full subcat. of the ab. cat. A, closed under extensions, i.e. from

$$0 \longrightarrow X' \longrightarrow X \longrightarrow X'' \longrightarrow 0, \quad X', X'' \in \mathrm{Ob}\, M \quad \Rightarrow \quad X \in \mathrm{Ob}\, M.$$

If a morphism $i : X' \longrightarrow X$ (from M) is included in a short exact seq., it is called an admissible monomorphism.



Original source details: GELFAND-P000522

Diagram and typed description.

$$0 \to X' \to X \to X''$$
$$\downarrow$$
$$0$$

The final sign in the right-hand insertion is provisionally read as zero.

(exactness is understood in A)

Dual def. if a morph. $p : X \longrightarrow X''$ is included in a short exact seq., it is called an adm. epimorphism.



Original source details: GELFAND-P000522

Diagram and typed description.

$$\begin{array}{ccc} Y \times_X Z & \longrightarrow & Y \\ \downarrow{\scriptstyle *} & & \downarrow{\scriptstyle \text{adm. epim.}} \\ Z & \xrightarrow[\text{morph.}]{\text{arbitr.}} & X \end{array} \qquad (M)$$

Then $Y \times_X Z \in \mathrm{Ob}\, M$ and $\downarrow\!\!*$ — adm. epim..

From M we construct the cat. QM:

$$\operatorname{Ob} M = \operatorname{Ob} QM.$$

$$\operatorname{Mor}_{QM}(X_1, X_2) = \left\{ X_1 \xleftarrow{\text{a.e.}} X \xrightarrow{\text{a.m.}} X_2 \right\}.$$

Def. equivalence in the obvious way.

([crossed out] X_1 — an admiss. subquotient of X_2)

Original source details: GELFAND-P000523

Undeciphered passage. The crossed-out entry before X_1 cannot be read.

Def. of composition:



Original source details: GELFAND-P000523

Diagram and typed description.

$$X_1 \xleftarrow{\text{a.e.}} X \xrightarrow{\text{a.m.}} X_2 \xleftarrow{\text{a.e.}} X' \xrightarrow{\text{a.m.}} X_3$$

$$\text{a.e.} \swarrow \qquad \searrow \text{a.m.}$$

$$X_4$$

$X_4 = X \underset{X_2}{\times} X'$.

The subscript 4 in the lower vertex and the product formula overwrites an earlier sign. The earlier sign is unreadable. A short stroke is visible at the lower end of the left diagonal arrow.



Original source details: GELFAND-P000523

and one must take

$$X_1 \xleftarrow{\text{a.e.}} X_4 \xrightarrow{\text{a.m.}} X_3.$$

By definition

$$K_i(M) = \pi_{i+1}(BQM, 0),$$

where 0 — any of the zero objects of the category M.

Isom. classes of objects of M must form a set.

Original source details: GELFAND-P000523

Undeciphered passage. The crossed-out entry before “Special case” cannot be read.

Special case: (the main one).

A — an arbitrary ring, PA — the cat. of finitely generated projective left A-modules.



Diagram and typed description.

$K_i(A) = K_i(PA)$.
def

Original source details: GELFAND-P000523

~~Properties of a certain K-functor.~~

Uncertain reading. The crossed-out abbreviation between “Properties” and K is provisionally read as “некотор.” (“a certain”).

Original source details: GELFAND-P000523

$$\varinjlim \mathrm{GL}(n, A) = \mathrm{GL}(A).$$

$$B\,\mathrm{GL}(A)$$

We construct $B_+\,\mathrm{GL}(A)$ with the properties

1) it is an H-space,

2) $B\,\mathrm{GL}(A) \longrightarrow B_+\,\mathrm{GL}(A)$

3) the homot. fibre is acyclic

4) surj. map on π_1.

$K_i(A) = \pi_{i+1}(B_+\,\mathrm{GL}(A))$ — the old def. (Quillen’s)



Manuscript excerpt. The subscript $i+1$ in this formula follows the manuscript.

Original source details: GELFAND-P000523

Uncertain reading. A crossed-out entry before “Apparently” may be the beginning of “По-видимому”.

Original source details: GELFAND-P000523

Apparently $BQPA$ is $B_+ \mathrm{GL}(A)$. This is false, but there is a map.

$$B\,\mathrm{GL}(A) \longrightarrow BQPA.$$

Let S_n — a free A-mod. with n gens..

$$S_n \in \mathrm{Ob}(PA) = \mathrm{Ob}(QPA).$$

Elems. of the group $\mathrm{GL}(n, A)$ — the automs. $S_n \longrightarrow S_n$. This lets us def. the functor

$$\mathrm{GL}(n, A) \rightsquigarrow PA.$$

[under $\mathrm{GL}(n, A)$:] corr. cat. (a single obj.)

$$\text{obj.} \longrightarrow S_n$$



Manuscript excerpt. ‖ automs. in PA are morphs. in QPA

Original source details: GELFAND-P000523

Functor $\mathrm{GL}(n, A) \longrightarrow QPA$.

GELFAND-P000524

[source number: 24]

Hence we obtain a map of classif. spaces

$$B\,\mathrm{GL}(n, A) \longrightarrow BQPA$$

It remains to pass to the limit. (They are incompatible).

$$\begin{array}{c} QPA \longrightarrow QPA \\ X \longrightarrow X \oplus A \end{array}$$ is a homotopy equivalence.

Diagr.



Diagram and typed description.

$$\begin{array}{ccc} B\,\mathrm{GL}(n, A) & \longrightarrow & BQPA \\ \downarrow & & \downarrow \\ B\,\mathrm{GL}(n+1, A) & \longrightarrow & BQPA \end{array}$$ commutes.

Original source details: GELFAND-P000524

and hence the limit and the map

$$B\,\mathrm{GL}(A) \longrightarrow BQPA$$

GELFAND-P000525

22.10.73 Gelfand's seminar.

Undeciphered passage. The crossed-out entry before "Gelfand" cannot be read.

Original source details: GELFAND-P000525

Gelfand. Publicizing work on nonlin. scattering theory. (Straus)

Original source details: GELFAND-P000525

Manuscript excerpt. The surname in parentheses is written “Straus”.

$$U(t)U(s) = U(t+s),$$

Relation for $U(t)f$ as $t \longrightarrow \pm\infty$

Typical features: $E(U(t)f) = E(f)$; E — some functional

$\exists$ a simpler group $U_0(t)$, such that

$$E\big(U(t)f - U_0(t)f_\pm\big) \underset{t\to\pm\infty}{\longrightarrow} 0 \qquad (\exists f_\pm)$$

S — the relation between f_+ and f_-.

Examples: wave eq.

$$u_{tt} - \Delta u + u + |u|^2 u = 0;$$



Original source details: GELFAND-P000525

Uncertain reading. The sign before the Laplacian is retraced. The horizontal stroke supports a provisional minus.



Original source details: GELFAND-P000525

Diagram and typed description.

de Vries eq.

$$u_\tau + u_{xxx} + uu_x = 0$$

The first subscript is provisionally set as τ from its shape. It differs from the tt on the line above.

— • —

Kirillov.

1. Kostant’s work.

M — a symplectic manifold (a nondeg. closed 2-form is given ω).

TM — a bundle over M with struct. group $\mathrm{Sp}(2n,\mathbb{R})$. It is not simply connected.

Topol.



Original source details: GELFAND-P000525

Diagram and typed description.

$\mathrm{Sp}(2n,\mathbb{R}) \approx U(n)$

$\uparrow$

$M(2n,\mathbb{R})$ (2-sheeted cover)

Sometimes the struct. group lifts to

Undeciphered passage. The crossed-out sign before $M(2n, \mathbb{R})$ cannot be read.

Original source details: GELFAND-P000525

$M(2n, \mathbb{R})$.

Then on M one constructs a spinor bundle (if C_1 is divisible by 2).

M has a special

Undeciphered passage. The crossed-out word before "repr. T" cannot be read.

Original source details: GELFAND-P000525

repr. T, called the spinor repr. (or the Weyl repr.)

Alg. $\{p_1, \ldots, p_n, q_1, \ldots, q_n\}$ and the rel.

$$p_i q_j - q_j p_i = \delta_{ij}$$



Manuscript excerpt. The abbreviation at the start of the line reads "Ал.".

Original source details: GELFAND-P000525

(if $+$, then the spin repr. of the orthog. group).

$\mathrm{Sp}(2n, \mathbb{R})$ linearly changes p and q.

Realiz. $p_i \longrightarrow \frac{\partial}{\partial x_i}$, $q_i \longrightarrow x_i$ in $L^2(\mathbb{R}^n)$.

Automs. of the alg. $\Longrightarrow$ automs. of the alg. of bounded operators. But they are all inner: $A \longrightarrow UAU^{-1}$ (U up to a factor) $\Rightarrow$ a projective representation. The factors reduce to ± 1. The repr. becomes single-valued on the 2-sheeted cover.

GELFAND-P000526

[source number: 28]

2. [crossed out] p-adic measures.



Undeciphered passage. The crossed-out part of the heading cannot be read.

Original source details: GELFAND-P000526

p-adic measures; $\mathbb{Z}_p$ — integers;

Undeciphered passage. The crossed-out entry after “integers” cannot be read.

Original source details: GELFAND-P000526

Consider $C(\mathbb{Z}_p, K)$, K — a finite ext. of the p-adic field
(cont. funcs. with values in K)

$$\mathrm{Hom}\big(C(\mathbb{Z}_p, K), \mathbb{Q}_p\big) = C(\mathbb{Z}_p, K)' = M(\mathbb{Z}_p, K)$$

(measures with p-adic values)



Manuscript excerpt. The second argument of Hom reads $\mathbb{Q}_p$.

Original source details: GELFAND-P000526

There is a convolution on measures



Diagram and typed description.

$$\int f\, d(\mu * \nu) = \int \underbrace{\left(\int f(x+y)\, d\mu(x) \right)}_{\text{cont. func.}} d\nu(y)$$

Original source details: GELFAND-P000526

Theorem 1.



Undeciphered passage. The crossed-out entry after “Theorem 1” cannot be read.

Original source details: GELFAND-P000526

K-algebra of measures $M(\mathbb{Z}_p, K) = K[[T]]$.

$$\left\| \sum a_k T^k \right\| = \sup_k |a_k| \qquad \text{(series of finite norm)}$$

Form. series are obtained from unbounded measures.

Theorem 2. Consider $M(\mathbb{Z}_p^*, K) = (p-1)K[[T]]$.

Unbounded measures are finitely add. on elem. sets (dual to loc. const. funcs.).

Proof of Thm. 1.

$$\mu \longrightarrow \sum a_k T^k, \qquad \text{where } a_k = \int_{\mathbb{Z}_p} \frac{x(x-1)\cdots(x-k+1)}{k!}\, d\mu(x)$$

$$\sum a_k T^k = \int_{\mathbb{Z}_p} (1+T)^x \, d\mu(x).$$

it follows that convolution of measures $\longrightarrow$ product of series.

Original source details: GELFAND-P000526

Diagram and typed description.
A tilted shaded quadrilateral between the formulas. Its purpose is unclear.

$$1 + T = e^{\tau} \qquad (\tau \text{ — form. var.}) \qquad \int_{\mathbb{Z}_p} e^{\tau x}\, d\mu(x) = \widetilde{\mu}(\tau)$$

(rewrite the analysis!)

τ can be treated as a number.

$$\tau = \ln(1+T) = T - \frac{1}{2}T^2 + \frac{1}{3}T^3 - \dots$$

It is unclear what range of funcs. will result (after substitution one should get a series with integer coeffs.)

Example ([crossed out]) (Cartier) as presented by Gelfand



Original source details: GELFAND-P000526

Undeciphered passage. The entry in the first parentheses after “Example” is crossed out and cannot be read.

Consider

$$\ln(1-a) = a + \frac{a^2}{2} + \frac{a^3}{3} + \dots \qquad \text{and } a = 2 \in \mathbb{Z}_2.$$



Original source details: GELFAND-P000526

Manuscript excerpt. The manuscript has a after the equals sign, followed by plus signs.

The series converges [inserted below: and equals] $\ln(-1)$.

Original source details: GELFAND-P000526

Manuscript excerpt. The circled insertion “and equals” points to the line above.

$$\ln[(-1)^2] = 2\ln(-1) = 0 \quad \Rightarrow \quad \ln(-1) = 0.$$

hence the series converges to 0

$$2 + \frac{2^2}{2} + \frac{2^3}{3} + \frac{2^4}{4} + \frac{2^5}{5} + \ldots + \frac{2^n}{n} + \ldots = 0$$

$$S_n = 2 + \frac{2^2}{2} + \frac{2^3}{3} + \ldots + \frac{2^n}{n} \qquad \text{for large } n \text{ is divisible by } 2^k$$

2, 4, $\frac{20}{3}$, $\frac{32}{3}$ and so on.

— · —

Theorem.

$$\|\mu\| = \sup_k |a_k| \qquad (\approx \text{ Plancherel})$$

$$\|\mu\| \underset{\text{def}}{=} \sup_{|f|\le 1} \left| \int f \, d\mu \right|$$

From the formula $\|\mu\| \ge \sup_k |a_k|$

We need to check

$$|f| \le 1 \quad \Rightarrow \quad f(x) = \sum c_k P_k(x), \qquad |c_k| \le 1,$$

$$P_k(x) = \frac{x(x-1)\cdots(x-k+1)}{k!}$$

(Proof: approx. by polynomials and apply the thm.)

$$c_k = \sum_{i=0}^{k} (-1)^{i+k} C_k^i f(i) = \Delta^k f(0) \qquad \text{(Taylor formula)}$$

$$X^{\textcircled{k}} = x(x-1)\cdots(x-k+1),$$

$$\Delta X^{\textcircled{k}} = kx^{\textcircled{k-1}}, \qquad \text{where } \Delta f(x) = f(x+1) - f(x).$$

$i = 0$

$X^{\textcircled{k}} = x(x-1) \ldots (x-k+1)$,

$\Delta X^{\textcircled{k}} = kX^{\textcircled{k-1}}$, где $\Delta f(x) = f(x+1) - f(x)$.

Original source details: GELFAND-P000526

Uncertain reading. The first two letters with a circled index are provisionally set as X. The letter after the factor k is set as x.

$$f(x) = \sum_{k=0}^{\infty} \frac{1}{k!} X^{\textcircled{k}} \cdot f^{\textcircled{k}}(0), \qquad \text{where } f^{\textcircled{k}}(x) = (\Delta^k f)(x)$$



Manuscript excerpt. The letter with circled k in the first product reads as X. Both indices (k) on f are also circled.

Original source details: GELFAND-P000527

Assn.: $\forall$ cont. funcs.

Undeciphered passage. The crossed-out word before "series" cannot be read.

Original source details: GELFAND-P000527

the Maclaurin series converges uniformly, and,

$$\max |f| = \max |a_k|.$$



Uncertain reading. There is a thick stroke before f in the manuscript. It is provisionally set as one absolute-value bar.

Original source details: GELFAND-P000527

Next time Kirillov (3 more min.) and Mishchenko.

Fuchs. (continuation).

M — an add. full subcat. of an abelian category, closed under extensions

$$QM: \qquad \operatorname{Ob} QM = \operatorname{Ob} M.$$



Diagram and typed description.
$X \xleftarrow[\text{adm. e.}]{} X'' \xrightarrow[\text{adm. m.}]{} X'$

Original source details: GELFAND-P000527

$$\pi_i(BQM)$$

BQM is homol. equiv. to $B\,\mathrm{GL}(\infty, A)$

Def. Grothendieck gr. of the category M. Gens. — the objects of M, rels.

$$0 \to X' \to X \to X'' \to 0, \qquad \Rightarrow \quad X = X' + X''$$

The gr. is commutative, since $\exists\ X = X' \oplus X''$.

Theorem:

$$\underset{\pi_1(BQM,0)}{K_0(M)} \cong \text{Grothendieck gr. of the cat. } M.$$

Zero-dim. skeleton $= \mathrm{Ob}(M)$

1-dim. skeleton — the morphisms of QM

$\forall X$ a loop is def.



Original source details: GELFAND-P000527

Diagram and typed description.



If in M there is an exact seq. (short) $0 \to X' \to X \to X'' \to 0$, then

$$\zeta_X \sim \zeta_{X'} \cdot \zeta_{X''}.$$



Original source details: GELFAND-P000527

Uncertain reading. The letter denoting the loop is provisionally set as ζ.



Original source details: GELFAND-P000527

Diagram and typed description.



The lower ends of the arcs are left separate as in the sketch. The thin lines represent the diagonal hatching.

and recall the 2-simplices.

— • —

GELFAND-P000528

29/$\overline{X}$-73. Gelfand's seminar.

A. A. Kirillov.

There is a symplectic manifold M



Diagram and typed description.



Original source details: GELFAND-P000528



Diagram and typed description.

$\mathrm{Sp}(2n,\mathbb{R})$

$\uparrow$

$M(n,\mathbb{R})$ (2-sheeted cover)

Original source details: GELFAND-P000528

loc. we may take

$$\omega = \sum_{k=1}^{n} dp_k \wedge dq_k$$

Transition funcs. (in TM) $g_{ij} \in \mathrm{Sp}(2n,\mathbb{R})$

Suppose they are in the 2-sheeted cover $M(2n,\mathbb{R})$



Manuscript excerpt. The line reads $M(2n,\mathbb{R})$. The diagram above and the insertion below read $M(n,\mathbb{R})$.

Original source details: GELFAND-P000528

The spinor representation [inserted below: $M(n,\mathbb{R})$] in Hilb. space

Undeciphered passage. The crossed-out sign after "space" cannot be read.

Original source details: GELFAND-P000528

induces a Hilbert bundle HM over M

Manuscript excerpt. The circled insertion $M(n,\mathbb{R})$ points to "representation".

Original source details: GELFAND-P000528

$$SM \subset HM \subset S'M$$

Uncertain reading. The crossed-out sign before $S'M$ resembles H.

Original source details: GELFAND-P000528

[under SM: rapidly decreasing]

Symplectic transf. $\rightsquigarrow$ op. in Hilb. space (can. transf. with p_i, q_i)

We obtain a projective representation

$$\underbrace{GM} = TM \oplus \mathbb{R} \times M$$

[under the brace:] polyn. of deg. ≤ 2 in p and q (Heisenberg Lie alg.)



Manuscript excerpt. The sign before 2 reads $\leq$.

Original source details: GELFAND-P000528

GM acts on HM compat. with the bundle structure.

RM, R_x — Lagrangian subspaces in T_xM (max. dim.)

A. Shnirelman. On Fermi: equipartition of energy among degrees of freedom.

$$\ddot{x}_k = (x_{k-1} + x_{k+1} - 2x_k) + \varepsilon(x_{k-1} - x_k)^2 + \varepsilon(x_{k+1} - x_k)^2$$



Original source details: GELFAND-P000528

Manuscript excerpt. Both quadratic terms have plus signs in the manuscript.

Solved num. on a computer

$k = 16$ after fin. ~~time~~ time intervals they examined the Fourier transf..



Uncertain reading. The number 16 is legible. The retraced letter is provisionally set as k.

Original source details: GELFAND-P000528



Uncertain reading. The crossed-out word is provisionally read as “time”.

Original source details: GELFAND-P000528

Init. cond. — sin (all the energy in the 1st harm.)

By the estimate $t = 10^{-35}$ in this state.

Original source details: GELFAND-P000528

Manuscript excerpt. The exponent on the line reads -35.

Calculations:



Original source details: GELFAND-P000528

Diagram and typed description.



The numerals are placed by the curves as in the manuscript. Their precise assignment and the continuation of the short rising line among the crossings are unresolved.

larger residual

10 steps — per. $1/3$

Another 10 steps — again
the same thing!!

Cubic nonlin. was also computed. The same result was obtained.

GELFAND-P000529

Zakharov: approx. by a diff. system with first integrals. (Possible cause)

A string with sin — likewise.

There are init. data for which uniform distribution occurs.

$$u_{tt} = u_{xx} \qquad \text{on } S^1 \quad \text{all traj. are closed}$$

$$u_{tt} = u_{xx} + \varepsilon f'(u)$$

First-order drift of the trajectories: also periodic for $u_{tt} = u_{xx} - \varepsilon u^3$.



Original source details: GELFAND-P000529

Diagram and typed description.



The first stroke in “on” is heavily retraced. The Russian abbreviation reads “подмн-зии”.

Mishchenko.



Original source details: GELFAND-P000529

Diagram and typed description.

Λ — a ring,

$\Rightarrow$ (with invol.)

The sign below and to the right of Λ is rendered as $\Rightarrow$.



Original source details: GELFAND-P000529

Diagram and typed description.

$\lambda = \|\lambda_{ij}\|, \quad \lambda_{ij} \in \Lambda$

1) $\lambda^* = \lambda$

2) $\exists \mu : \quad \mu\lambda = \begin{pmatrix} 1 & & 0 \\ & \ddots & \\ 0 & & 1 \end{pmatrix}$

quadr. form over Λ

The short diagonal trace between the rows of the identity matrix is rendered as $\ddots$.

A Fredholm rep. is a triple $T = \{T_1, F, T_2\}$;

T_i — a rep. of Λ in $\mathcal{L}(H)$ (with involution), where

F — a Fredholm operator

$FT_1(x) - T_2(x)F \quad \in \text{comp} \qquad \forall x \in \Lambda.$

Original source details: GELFAND-P000529

Undeciphered passage. After the second F, before $\in$, a parenthesized fragment is heavily crossed out.

Construct $\lambda \in \mathcal{L}(H \oplus \cdots \oplus H)$ from the quadr. form.



Original source details: GELFAND-P000529

Manuscript excerpt. $\backslash\backslash\, H^n$

Below the direct sum are two slanted strokes and H^n. A rotated equality sign represents the strokes.

$$\lambda_{T_1} = (T_1(\lambda_{ij})), \qquad \lambda_{T_2} = (T_2(\lambda_{ij}))$$

[at right:] — invertible and self-adj.

They are bounded, invertible, self-adjoint.



Diagram and typed description.

$$\begin{array}{ccc} H^n & \xrightarrow{\lambda_{T_1}} & H^n \\ {\scriptstyle F\otimes id}\downarrow & & \downarrow{\scriptstyle F\otimes id} \\ H^n & \xrightarrow{\lambda_{T_2}} & H^n \end{array}$$

Fredh.

commutes mod comp.

Original source details: GELFAND-P000529

Choose bases so that

$$\lambda_{T_1} = \begin{pmatrix} A & 0 \\ 0 & -B \end{pmatrix} \qquad \lambda_{T_2} = \begin{pmatrix} A' & 0 \\ 0 & -B' \end{pmatrix}$$

A, B — inv. and self-adj. and > 0.

$$F \otimes id = \begin{pmatrix} F_1 & F_2 \\ F_3 & F_3 \end{pmatrix}$$

$F_2, F_3 \in$ comp.

$\Rightarrow$ F_1, F_4 — Fredholm



Manuscript excerpt. The lower-right entry of the matrix reads F_3. The final line reads F_4.

Original source details: GELFAND-P000529

GELFAND-P000530

[source number: 32]

Definition. $\operatorname{sign}_T \lambda = \operatorname{index} F_1 - \operatorname{index} F_4$.

Original source details: GELFAND-P000530

Manuscript excerpt. The definition gives the difference of the indices of F_1 and F_4.

It does not depend on the rep. as a direct sum or on the rep. in the class of equiv. quadr. forms.

Diagram and typed description.

Original source details: GELFAND-P000530

Let M — a manifold (comp.); $\pi_1(M) = \pi$, $\dim M = 4K$; $\Lambda = \mathbb{Z}[\pi]$.

Uncertain reading. The letter after 4 is provisionally set as K. The handwriting leaves the case unresolved.

Original source details: GELFAND-P000530

There is a quadr. form $\sigma(M)$ over Λ. Formula:

$$\operatorname{sign}_T(\sigma(M)) = \langle \operatorname{ch} \xi_T \cdot L(M), [M] \rangle$$

ξ_T — a bundle on M

Hirzebruch proved for $(\operatorname{ch} \xi_T = 1.)$

Finite-dimensional reps. are insufficient.

Diagram and typed description.

Original source details: GELFAND-P000530

Uncertain reading. A short isolated slanted stroke in the blank right margin. Its reading as the numeral “1” remains unresolved.

Original source details: GELFAND-P000530

GELFAND-P000531

[source number: 37]

12.11.73. Gelfand's sem..

V. Ponomarev.

Suppose the set has 2 operations $\cap$ and $+$ with the natural properties (assoc., commut., $x \cap x = x$, $x + x = x$, $a + (a \cap b) = a$, $a \cap (a + b) = a$) this is a lattice.

Distributive lattice:

$$\left.\begin{aligned} a \cap (b + c) &= (a \cap b) + (a \cap c) \\ a + (b \cap c) &= (a + b) \cap (a + c) \end{aligned}\right]$$

[at right:] these are only systems of subsets of some set.



Original source details: GELFAND-P000531

Manuscript excerpt. The right square bracket joins the two identities to the note.

example: the lattice of subspaces with intersection and sum.

order relation in the lattice: $a \leq b \iff a \cap b = a$

Uncertain reading. The heavily retraced sign between a and b is provisionally set as $\leq$.

Original source details: GELFAND-P000531

Modular latt.:

$$\forall\, a \subseteq b \text{ and } \forall c \qquad b \cap (a + c) = a + (b \cap c) \qquad \text{(Dedekind)}$$



Original source details: GELFAND-P000531

Manuscript excerpt. The condition in the modular law reads $a \subseteq b$.

(∀ distributive is modular, but not conversely).

Uncertain reading. The heavily retraced sign before "distributive" resembles ∀.

Original source details: GELFAND-P000531

the lattice of subspaces is modular, but not distributive.

the lattice of submodules of a module is modular too.

Question: are there more identities or is this all? (Conjecture: ∀ modular latt. is the latt. of submod. of a module).

For latt. of subspaces there are more!!

Let $e_1, \ldots, e_r$ — be letters.



Manuscript excerpt. The first subscript has the same shape as r in the second list and in the notation for generators below.

Original source details: GELFAND-P000531

Consider the free modular lattice generated by them (polyn. in $e_1, \ldots, e_r$ with relations) linearly equiv. polynomials $P(e_1, \ldots, e_r) \sim Q(e_1, \ldots, e_r)$, if it holds on substitution of subspaces.

V — a fin.-dim. space over the field k.

A representation of the latt. is a map into the lattice of subspaces of V (which is denoted $PG(V, k)$)

$$\begin{array}{cc} \mathcal{L} \longrightarrow PG(V,k) & ab \mapsto s(a)s(b) \\ a \in \mathcal{L} \quad \longrightarrow \quad a \mapsto s(a) \subset V & a + b \mapsto s(a) + s(b) \end{array} \Big\|$$



Manuscript excerpt. The arrows are written in two rows. A double vertical stroke follows the right column.

Original source details: GELFAND-P000531

Manuscript excerpt. The arrow after $a \in \mathcal{L}$ is overwritten or struck through with slanted loops.

Original source details: GELFAND-P000531



Uncertain reading. The looped letter is provisionally set as s throughout the notation for representations.

Original source details: GELFAND-P000531

$\mathcal{D}^r$ — the free modular lattice on r generators $e_1, \ldots, e_r$.

A rep. — is V and $s(e_1), \ldots, s(e_r)$ — a collection of subspaces $E_1^0, \ldots, E_r^0$, and conversely such a collection determines a representation.

Undeciphered passage. A heavily crossed-out fragment lies between "A rep. —" and "is V".

Original source details: GELFAND-P000531

Problem: describe all reps. of $\mathcal{D}^r$.

~~An elem. a is called perfect if~~

Original source details: GELFAND-P000531

Manuscript excerpt. A single stroke crosses out the beginning of the definition.

s_1, V_1; s_2, V_2

$$s_1 \oplus s_2 \text{ — a rep. in } V_1 \oplus V_2 : \qquad (s_1 \oplus s_2)(a) = s_1(a) \oplus s_2(a)$$

Decomposable representation is defined naturally.

An elem. $a \in \mathcal{L}$ (inserted above: modular latt.) is called perfect, if for $\forall$ rep. s in a fin.-dim. space V over $\forall$ field k the subspace $s(a)$ can be complemented by a subspace V_2 and the rep. decomposes as a direct sum [inserted below:] with direct summand V_2.



Uncertain reading. After V_2 a curl with a dot adjoins the descender from the line above.

Original source details: GELFAND-P000531

(Or: in an indecomp. rep. it maps to 0 or 1). If $a \sim b$ (lin.), then both are perfect at the same time.

Example. Consider the free mod. latt. on r generators $e_1, \dots, e_r$. Consider the elements

$$e_{i_1 i_2} = e_{i_1} \text{ [overwritten sign] } \sum_{k \neq i_1, i_2} e_k$$



Uncertain reading. The sign between e_{i_1} and the sum is heavily overwritten. Its reading remains unresolved.

Original source details: GELFAND-P000531

GELFAND-P000532

$$e_{i_1 i_2 \dots i_e} = e_{i_1} \sum_{\beta \in \Gamma(\alpha)} e_{k_1 \dots k_{e-1}}$$



Original source details: GELFAND-P000532

Uncertain reading. The length letter resembles e and is provisionally set that way. There is no separate sign between e_{i_1} and the sum.

$$\begin{aligned} \alpha &= (i_1, \dots, i_e), \qquad \beta = (k_1, \dots, k_{e-1}) \\ \Gamma(\alpha) &= \{\, k_1 \neq i_1, i_2; \quad k_2 \neq i_2, i_3, k_1; \quad \dots \\ &\qquad i_1 \neq i_2, \quad i_2 \neq i_3, \quad \dots \end{aligned}$$



Manuscript excerpt. The line of conditions on i_1, i_2, i_3 is indented. There is no closing brace.

Original source details: GELFAND-P000532

. . . . . .

Triv. perfect elements: $m_t = \sum_{i \neq t} e_i$ — perfect elements.

m_t generate a Boolean alg. with r generators.

S. Gelfand.

Bruhat–Tits complex.

G — a p-adic group, K — a max. comp. subgroup.

B.–T. cplx. — description of G/K, analogue of a symmetric space.



Original source details: GELFAND-P000532

Manuscript excerpt. The manuscript abbreviation reads “К Б.-Т.”.

K is open (contains a nbhd. of 1) $\Rightarrow G/K$ is discrete.

example: $G = \mathrm{GL}(2, Q_p)/C$ (C — the centre).

$$K = \mathrm{GL}(2, \mathcal{O}) \qquad \mathcal{O} \text{ — integers}$$

$$\mathrm{GL}(n, Q_p) \supset B, \qquad B \ni \begin{pmatrix} \alpha_1 & & \mathcal{O} \\ & \ddots & \\ p\mathcal{O} & & \alpha_n \end{pmatrix}, \qquad \alpha_i \in \mathcal{O}^*$$

[under the matrix:] Iwahori subgroup.



Manuscript excerpt. The diagonal letter matches the shape of α at the start of the frame. At upper right is $\mathcal{O}$ and at lower left is $p\mathcal{O}$.

Original source details: GELFAND-P000532

$x_1, \ldots, x_e$ — points of G/K

$K_1, \ldots, K_e \leftarrow$ the same ones, subgroups conjugate to K

Manuscript excerpt. A short leftward arrow precedes “the same ones”.

Original source details: GELFAND-P000532

They span a simplex if $gBg^{-1} \subseteq K_1 \cap \ldots \cap K_e$



Manuscript excerpt. The sign between gBg^{-1} and the intersection reads $\subseteq$.

Original source details: GELFAND-P000532

$n = 2 \Rightarrow$ it is contractible.

Uncertain reading. The heavily overwritten letter before $= 2$ is provisionally set as n.

Original source details: GELFAND-P000532

Undeciphered passage. A heavily struck-out rectangular fragment sits to the left of the tree sketch. The writing inside is illegible.

Original source details: GELFAND-P000532



Original source details: GELFAND-P000532

Diagram and typed description.



The slanted arrow at left is separate from the upper node. Two hooked strokes appear on the right branches.

Consider $V_3(F_q)$. Points of type 1 — lines in V_3, 2 — planes in V_3.
Incidence $\Rightarrow$ spans a simplex.

D. Kazhdan.

~~Consider the func.~~ $\sout{ax + \frac{b}{x},\ a, b \in \mathbb{Z}.}$



Original source details: GELFAND-P000532

Undeciphered passage. In the crossed-out line between “Consider” and “the func.” there is a raised 2. The writing below it remains undeciphered.

[in the left margin, crossed out:] $\sout{\sum e^{\frac{2\pi i}{p}}}$.



Original source details: GELFAND-P000532

Manuscript excerpt. In the crossed-out expression the numerator reads $2\pi i$ and the denominator p.

X — a curve over F_q. How many points are on it?

$$\left|[X_q] - q\right| \leq 2g\sqrt{q}$$



Original source details: GELFAND-P000532

Manuscript excerpt. Inside the absolute-value signs the manuscript reads $[X_q] - q$.

(g — genus of the curve, $[X_q]$ number of points of X over F_q).
This is equiv. to the Weil conjecture.
Stepanov's proof (in Bombieri's presentation at the Bourbaki sem.). He proved

$$[X_q] \leq q + 4g\sqrt{q}$$



Manuscript excerpt. The heavily retraced letter under the radical reads q.

Original source details: GELFAND-P000532

(from this the upper bound follows formally).



Original source details: GELFAND-P000532

Uncertain reading. The final stroke in the Russian abbreviation for "follows" is retraced. The reading is provisional.

(It even suffices, instead of $4g$ to put C, independent of q).
X — a curve, on it a divisor D. Number of funcs. divisible by the divisor D:

$$L(D) = \deg D - g + 1 \qquad \text{when } \deg D > 2g$$

(if there are many more poles than zeros).

Original source details: GELFAND-P000532

Manuscript excerpt. The left side is $L(D)$. The condition has a strict $>$ before $2g$.

GELFAND-P000533

[source number: 38]

Let $x_0 \in X$, fixed.

L_e — [inserted above:] space of funcs. with a pole of mult. $\leq e$ at pt. x_0.

L_e^q has the same number of elements as L_e.



Undeciphered passage. Two heavily crossed-out entries follow the dash on the L_e line. One follows L_e^q, and one precedes the product arrow. "Space" is circled above the second cancelled entry. The cancelled entries are illegible.

Original source details: GELFAND-P000533

$$0 \to \text{Ker} \to L_{q-1} \times L_e^q \longrightarrow L_{q-1} \cdot L_e \subset L_{q+e-1}$$

[under the middle term:] isom. tensor prod..



Original source details: GELFAND-P000533

Manuscript excerpt. The middle term uses $\times$. Below it is the note "isom. tensor prod." The index in L_e is provisionally set as e.

Elems. of Ker are 0 on $[X_q]$.



Original source details: GELFAND-P000533

Diagram and typed description.

dim :

$(q-g)(e-g+1) \; > \; (q+e-g)$

A short downward arrow points to the first product, and a longer diagonal arrow points to the right side.

And there is a kernel. Funcs. of low deg. are 0 on $[X_q]$.

Original source details: GELFAND-P000533

Diagram and typed description.

GELFAND-P000534

19/XI-73. Gelfand's sem.. (last meeting this semester).

Manuscript excerpt. The Roman XI has a rule above and below.

Original source details: GELFAND-P000534

Serre's problem on polyn. in 3 variables has been solved.

Vaserstein.



Undeciphered passage. An elongated entry to the right of the surname is crossed out with horizontal and slanting strokes. Its reading remains unresolved.

Original source details: GELFAND-P000534

Def. The stab. rank of the ring $A \leq 2$, if $\forall$ unimod. column $\begin{pmatrix} a \\ b \\ c \end{pmatrix}$ (rel. prime elems.)



Manuscript excerpt. The parenthesis "(rel. prime elems.)" is below the three-entry column.

Original source details: GELFAND-P000534

$\exists \alpha, \beta \in A$, such that

$$\begin{pmatrix} a+\alpha c \\ b+\alpha c \end{pmatrix} \quad \text{is unimodular.}$$



Manuscript excerpt. Both entries of the short column contain α. The condition above gives α, β.

Original source details: GELFAND-P000534

Thm.

$$\text{st. rank } k[x_1, x_2] = \begin{cases} 3 & \text{when } K_2 k \neq 0 \\ 2 — & \text{when } K_2 k = 0 \end{cases}$$



Manuscript excerpt. There is a short stroke after 2 before "when".

Original source details: GELFAND-P000534

$$\left(K_2 k = \begin{cases} 0 & k \text{ — alg. ext. of a finite field} \\ \neq 0 & \text{otherwise} \end{cases}\right)$$



Original source details: GELFAND-P000534

Uncertain reading. The Russian abbreviation before “ext.” is provisionally read as “ал.” and translated as “alg.”.

GELFAND-P000535

[source number: 45]

Example over $\mathbb{R}$.

Undeciphered passage. A long entry after $\mathbb{R}$ is crossed out with slanting and horizontal strokes.

Original source details: GELFAND-P000535

$$\begin{pmatrix} x_1 \\ x_2 \\ 1 - x_1^2 - x_2^2 \end{pmatrix}$$

there do not exist $\alpha, \beta \in \mathbb{R}$, such that

$$\begin{pmatrix} x_1 + \alpha(1 - x_1^2 - x_2^2) \\ x_2 + \beta(1 - x_1^2 - x_2^2) \end{pmatrix}$$

Undeciphered passage. There is a dense cancellation between “not” and “exist”. The underlying writing is illegible.

Original source details: GELFAND-P000535



Manuscript excerpt. The second entry of the short column here contains β.

Original source details: GELFAND-P000535

(by degree).

Manuscript excerpt. Below the line with “do not exist” is the note “(by degree)”.

Original source details: GELFAND-P000535

There is a curve $C(x_1, x_2) \equiv C = 0$

Winding index with respect to the set $a(x_1, x_2) = 0$, $b(x_1, x_2) = 0$

Original source details: GELFAND-P000535

Manuscript excerpt. The abbreviation before the equations reads “set”.

(a, b, c — polynomials).

$c(a, b)$. $a = x_1$, $b = x_2$ — number of turns about the origin.



Original source details: GELFAND-P000535

Uncertain reading. The sign before (a, b) is provisionally set as c. Its loop also permits e.

B — a ring

$K_1 \mathrm{Sp}\, B =$ Quotient of symplectic matrices of order $2n$ by the elementary ones.

Question: $z_1^2 + z_2^2 = 1$ index 0 or non 0?

Original source details: GELFAND-P000535

Manuscript excerpt. Both signs in the question are read as 0. A faint closing stroke is visible at the right of each oval.

$\Longleftrightarrow \exists$ are there 2 funcs. $f_1(z_1, z_2)$ and $f_2(z_1, z_2)$, such that

(entire, entire of exp. growth, etc.)

$$\begin{matrix}(z_1^2 + z_2^2 - 1) f_1 + z_1 \\ (z_1^2 + z_2^2 - 1) f_2 + z_2\end{matrix}$$ have no common div.

(no for polynomials, yes for cont. funcs.).



Original source details: GELFAND-P000535

Manuscript excerpt. The first phrase reads “for polynomials”.

Kazhdan. Derived category.

A — a ring, ~~$\forall$ — modules over A.~~

Original source details: GELFAND-P000535

Uncertain reading. The crossed-out initial sign is provisionally set as $\forall$. “Modul...” and “over A” are visible under the cancellation.

~~$\mathrm{Hom}(M, N)$ — functor~~

Original source details: GELFAND-P000535

Uncertain reading. The word after the crossed-out $\mathrm{Hom}(M, N)$ is provisionally read as “functor”.

Consider the category of modules over A.

(Everything will be illustrated by the functor $\mathrm{Hom}(M, N)$).

Define the derived functors $\mathrm{Ext}^i(M, N)$:

$$\ldots \to M_1 \to M_0 \to M \to 0 \qquad (M_i \text{ — free})$$



Original source details: GELFAND-P000535

Uncertain reading. The subscript before M is open at right. It is provisionally read as 0.

Consider the complex $C^i = \mathrm{Hom}(M_i, N)$

$$0 \to C^0 \to \ldots \to C^{i-1} \to C^i \to \ldots$$

Its cohomology grs. $\mathrm{Ext}^i(M, N)$. $\mathrm{Ext}^0(M, N) = \mathrm{Hom}(M, N)$.

Any 2 resol. are homotopic.

Invariant: complex, def. up to homotopy.



Original source details: GELFAND-P000535

Manuscript excerpt. The first word on the line reads “Invariant”.

There are complexes with isom. homologies that are not homotopic. (see topology).

The natural object is a complex.

Let $\dot{M}$ — a complex $0 \to M_1 \to \ldots \to M_i \to 0$

$\dot{N}$ — — " — $0 \to N_1 \to \ldots \to N_j \to 0$

$\mathrm{Hom}(\dot{M}, \dot{N})$

(!) M is interpr. as



Original source details: GELFAND-P000535

Diagram and typed description.

$$\begin{array}{ccccccc} \cdots & \longrightarrow & M_1 & \longrightarrow & M_0 & \longrightarrow & 0 \\ & & \downarrow & & \downarrow & & \\ 0 & \longrightarrow \cdots \longrightarrow & 0 & \longrightarrow & M & \longrightarrow & 0 \end{array}$$

(if a homomorphism)

(induc. an isom. of cohomology groups)

The lower letter beneath M_0 is provisionally set as M. The small stroke cannot securely be separated from the arrow. The caption at right is provisional.

GELFAND-P000536

M is replaced by a compl. of free modules, for which $\to 0 \to M \to 0 \to \dots$ is mapped with an induced isom. of cohomology grs..

(quasi-isomorphic complexes)

Resolution — replacement of M by a quasi-isom. compl. of free modules.

$\mathrm{Hom}(\dot{M}, \dot{N})$ in the derived category.

Replace $\dot{M}$ by a quasi-isom. complex of free modules



Original source details: GELFAND-P000536

Diagram and typed description.

$$\begin{array}{ccccc} \cdots & \longrightarrow F_1 & \longrightarrow F_0 & \longrightarrow 0 \\ & & \downarrow & \\ & \not{M_2} & \longrightarrow \not{M_0} & \longrightarrow \not{0} \end{array}$$

The first crossed-out subscript is provisionally read as 2. A downward arrow is visible below F_0. Below F_1 a separate arrow cannot be distinguished from the subscript stroke.

Construct the complex $C^i = \mathrm{Hom}^i(R, N)$ — derived functor. (maps with shift by i)



Original source details: GELFAND-P000536

Diagram and typed description.

$$\begin{array}{ccccccc} & & & & R_0 & & \\ & & & & \downarrow & & \\ M_i & \longrightarrow M_{i-1} & \longrightarrow \cdots & \longrightarrow M_0 & \longrightarrow 0 & & \\ & & & & \downarrow & & \\ M & \qquad N_i & \longrightarrow N_2 & \longrightarrow \cdots & \longrightarrow N_j & & \end{array}$$

(in opposite directions)

The first subscript below is provisionally set as i. An isolated M stands to the left of the lower chain. A faint leftward arrow is visible under the note at right.



Original source details: GELFAND-P000536

Diagram and typed description.

Its [inserted above: $\overset{\circ}{\mathrm{Hom}}$] homot. type is independent of the resol.



Original source details: GELFAND-P000536

Undeciphered passage. A short, crossed-out fragment lies below the chains. The underlying writing is illegible.

2 complexes of free modules are quasi-isom. $\Longleftrightarrow$ they are homot. equiv.

Original source details: GELFAND-P000536

Manuscript excerpt. Two heads are visible on the retraced arrow, rendered as $\Longleftrightarrow$.

$K(A)$ — the categ. of complexes. Morphisms — homot. classes of morphisms.
The category $D(A)$. $\mathrm{Ob}\,\mathcal{D}(A) = \mathrm{Ob}(K(A))$, and $\mathrm{Mor}(\mathcal{D}(A))$ — a seq.

$$\dot{M} \to \dot{M}_1 \to \ldots \to \dot{M}_k \to \dot{N} = \mathrm{Mor}(\dot{M}, \dot{N})$$

where $\to$ — a morph. to the right or a quasi-isom. to the left.
We want: to introduce a new Hom, so that it becomes a complex.
~~$\mathrm{Hom}_{D(A)}$~~

Uncertain reading. The crossed-out fragment shows Hom. The subscript resembles $D(A)$. The rest of the entry remains undeciphered.

Original source details: GELFAND-P000536

$$\mathrm{Hom}^i_{D(A)}(\dot{M}, \dot{N})$$



Uncertain reading. There is a dot over N. The mark over M touches a letter on the line above and is provisionally rendered as a dot.

Original source details: GELFAND-P000536

. . . . . .

F — a contravar. functor; $F : \underset{\text{modules over } A}{M(A)} \to \underset{\text{modules over } B}{M(B)}$

$\dot{M} \in D(A)$
It is bad to take $F(\dot{M})$, since quasi-isoms. will not go to quasi-isoms.



Diagram and typed description.
$\dot{F} : D(A) \longrightarrow D(B)$.

Original source details: GELFAND-P000536

(Its cohom. are the ordinary derived functors)

$\dot{M} \in D(A)$. Choose a representative of free modules $\dot{M}$ and apply to it F — we obtain a new complex. Regard it as an element of $D(B)$. Well-definedness follows from the stated theorem on homotopy.

More gen. def. $F : A \to B$, $\dot{F} : D(A) \to D(B)$



Original source details: GELFAND-P000536

Diagram and typed description.

$$\begin{array}{ccc} K(A) & \xrightarrow{F} & K(B) \\ \downarrow Q & & \downarrow Q \\ D(A) & \xrightarrow[G]{\dot{F}} & D(B) \end{array}$$

Req.: $\exists$ a map $Q\overline{F} \to \dot{F}Q$ (morph. of functors)



Original source details: GELFAND-P000536

Uncertain reading. The first superscript mark is a heavy slanted stroke, provisionally set as a bar. The second F has a dot.

$\forall G$ we obtain an isomorphism

$$\mathrm{Hom}(QF, G \cdot Q) \longrightarrow \mathrm{Hom}(\dot{F}Q, GQ)$$

would be an isomorphism for $\forall G$.



Original source details: GELFAND-P000536

Manuscript excerpt. The left side reads QF without a superscript mark, and the right side $\dot{F}Q$. The arrow points right.

GELFAND-P000537

11/II-74. Gelfand's sem..

Original source details: GELFAND-P000537

Uncertain reading. A crossed-out entry lies to the left of 11/II-74. Its first stroke resembles 1. The full entry remains unreadable.

Springer. Green polynomials.



Original source details: GELFAND-P000537

Manuscript excerpt. The title and the lines about the group are written in English in the manuscript.

$$G = \mathrm{GL}_n(k), \qquad k \text{ — finite field}, \qquad |k| = q.$$

G corresponding algeb-raic gr. $= \mathrm{GL}(\bar{k})$.

$G = G(k)$ gr. of points with values in k.



Original source details: GELFAND-P000537

Manuscript excerpt. Two rules below G distinguish the algebraic group from the plain G. After "gr." the manuscript gives $\mathrm{GL}(\bar{k})$ without the subscript n.

GELFAND-P000538

25/II-74. Gelfand's sem.

S. P. Novikov. (continued).

$$L = -\frac{d^2}{dx^2} + u(x),$$
$$A_1 = 4\frac{d^3}{dx^3} - 3\left(u\frac{d}{dx} + \frac{d}{dx}u\right),$$
$$A_0 = d/dx.$$



Manuscript excerpt. The definition of L has a minus sign before the second derivative.

Original source details: GELFAND-P000538

Gelfand: $y'' + u(x)y = \lambda y$



Manuscript excerpt. There is no separate minus sign before y'' on this line.

Original source details: GELFAND-P000538

Original source details: GELFAND-P000538

Undeciphered passage. A small entry to the right of λ_y lies under a heavy cancellation.

$$u(x+T) = u(x)$$

structure of the spectrum — shortest proof in Gelfand DAN (≈ 1950).



Original source details: GELFAND-P000538

Undeciphered passage. Two crossed-out entries lie below the year. A sign resembling $\approx$ precedes the upper one.

$u(x)$ — real and its closure (from C_0^∞) is self-adj.

Another case:

Original source details: GELFAND-P000538

Diagram and typed description.

$$y(0) = \pm y(2\pi), \qquad y'(0) = \pm y'(2\pi)$$



Original source details: GELFAND-P000538

Manuscript excerpt. Both boundary conditions carry a $\pm$ sign.



Original source details: GELFAND-P000538

Diagram and typed description.



periodic, antiper. (if nondegenerate)

The question mark stands for the overwritten label above the second arc. The fill of partially retraced circles follows the visible center.

(alternation!)

п а а п п а а п п ...

$\sim$ (altern. in pairs)



Original source details: GELFAND-P000538

Uncertain reading. A short wavy stroke below the letters is rendered as $\sim$. The final Russian word is provisionally read as “in pairs”.

GELFAND-P000539

[source number: 59]

On the line, consid. the following bound. conditions:

$$y(x+T) = e^{it}y(x)$$
$$y'(x+T) = e^{it}y'(x)$$

Original source details: GELFAND-P000539

Uncertain reading. The sign after i in the first exponent is heavily overwritten. The reading t is provisional. The second exponent it is independently legible.

$\forall t$ self-adj. prob. with discr. spectrum.



Original source details: GELFAND-P000539

Diagram and typed description.



Lemma. $\forall f(x)$,

$$f(x) = \int_0^{2\pi} f_t(x)\,dx, \qquad \text{where } f_t(x+2\pi) = e^{it}f(x)$$

At the same time

$$\int_{-\infty}^{+\infty} |f(x)|^2\,dx = \int_0^{2\pi}\int_0^1 |f_t(x)|^2\,dt\,dx$$



Original source details: GELFAND-P000539

Manuscript excerpt. The first integral has dx, and the right side of the condition has $f(x)$ without a subscript. In the second equality the upper limits are 2π and 1, with differentials $dt\,dx$.

(reduc. to a comp. group — Weyl)

$0 \le x \le 2\pi \Rightarrow$ expand in a Fourier series in the eigenfunctions of the problem.

Obtain an integral over the whole line now $\| \; f_t(x) = \sum_n a_{n,t} y_{t,n}(x)$

$y_{t,n}$ — Bloch funcs.

$$a_{n,t} = \int_0^{2\pi} f_t(x) y_{t,n}(x)\, dx.$$



Manuscript excerpt. There is no bar over $y_{t,n}(x)$ in the integral.

Original source details: GELFAND-P000539

$\rightleftarrows$ is calculated $\dfrac{d\lambda}{dt}$.

S.P.N.



Diagram and typed description.

x_0 $\qquad$ $x_0 + T$

Original source details: GELFAND-P000539

Consid. $y(x_0, x)$

$Ly = \lambda y, \quad \lambda = k^2$

$$y|_{x=x_0} = 1$$
$$y'|_{x=x_0} = ik$$

— one eigenfunc. (closer to e^{ikx}).

Undeciphered passage. A heavily crossed-out entry before “and”.

Original source details: GELFAND-P000539

and $\bar{y}(x_0, x)$ — another eigenfunc.

Monodromy matr.

$$y(x_0, x+T) = a y(x_0, x) + b\bar{y}(x_0, x),$$

moreover $a = a(x_0, \lambda)$.

(ord. transfer matr. [above the line: scattering] — over an ∞ period — triv. degener. case).



Original source details: GELFAND-P000539

Manuscript excerpt. “Scattering” is circled and linked by a stroke to the line at “transfer”.

$$\bar{y}(x_0, x+T) = \bar{b}y(x_0, x) + \bar{a}\bar{y}(x_0, x).$$

$$T = \begin{pmatrix} a & b \\ \bar{b} & \bar{a} \end{pmatrix} \text{ — monodromy matr.} \qquad T = T(x_0, \lambda)$$

$\det = 1$ (the Wronskian is constant)

$$|a|^2 - |b|^2 = 1;$$
$$\operatorname{Sp} T = 2a_R = a + \bar{a};$$

Eigenvalues

$$\alpha_\pm(\lambda) = a_R \pm \sqrt{a_R^2 - 1}$$

consid. the graph in λ



Original source details: GELFAND-P000539

Diagram and typed description.

λ

There is a small hook at the left of the line.

bounded solutions $\iff |a_R| \le 1 \implies$ obtain $e^{\pm it}$
unbounded solutions $\iff |a_R| > 1 \implies$ obtain $e^{\pm t}$

GELFAND-P000540

$(y, y') = (1, ik)$

Relation to the spectrum.

Original source details: GELFAND-P000540

Uncertain reading. Before “For” is a dense mark with two lower ends. The sign is undeciphered.

For $|a_R| \le 1$ there is Bloch spectrum.



Original source details: GELFAND-P000540

Diagram and typed description.

$a_R(\lambda)$

1

λ

−1

Extrema outside the strip. (monotonically in the band)



Original source details: GELFAND-P000540

Manuscript excerpt. “Extrema” is underlined.

G. $u(x) = \text{const}$ — spectrum > 0

$u(x) < 0$ is possible.

stability bands extend into the neg. region



Diagram and typed description.



The question mark at the lower point stands for the undeciphered mark.

Original source details: GELFAND-P000540

$$-y'' + (a + b\cos 2x)y = 0$$

bands of stability and instab.

1st stab. band when $a + b\cos 2x < 0$

(does not occur for constant ones)

N. monot. in the band — proved for small potentials

Original source details: GELFAND-P000540

Manuscript excerpt. The Russian abbreviations read “монот.” and “доказ.”.

G. Contest for a proof (for next time)

N. Periodic and antiperiodic $|a_R| = 1$ — band edges.



Diagram and typed description.



Original source details: GELFAND-P000540

For a const. or zero one it is always thus:

$$\begin{pmatrix} e^{iT} & 0 \\ 0 & e^{-iT} \end{pmatrix} \qquad a_R = \cos T$$

On inverse problems: $a_R(k) = a_R(x_0, k)$ does not determine the potential



Undeciphered passage. After “potential” there is a crossed-out entry in parentheses. Its reading is unresolved.

Original source details: GELFAND-P000540

(≈ inform. about the spectrum).

1) nondegener. $\lambda_n\colon b(x_0,\lambda)\neq 0$

2) doubly degener. $\lambda_n\colon b(x_0,\lambda_n)\equiv 0$.

Uncertain reading. A separate heavily overwritten sign precedes “doubly degener.”.

Original source details: GELFAND-P000540

What scattering data determine $u(x)$ (apart from the spectrum). Dubrovin and Faddeev's students are working on it. _____ · _____

If from some index onward $\forall$ eigenvalues are doubly degener., then the forbidden bands contract to a point. _____ · _____

Theorem.

1) Consid. $\sum_{i=0}^{n} Q_i(u,\dots,u^{(k_i)})\frac{d^i}{dx^i}$ and let

$$[A,L]=P(u,\dots,u^{(\ell)}) \qquad \text{(multiplication oper.)}$$

and consid. the diff. eq. $P(u,\dots,u^{(\ell)})=0$ and suppose it is periodic. Then it is a finite-gap potential.

~~or conversely~~ (in fact, the converse is true too).



Manuscript excerpt. “Or conversely” is crossed out with a wavy stroke.

Original source details: GELFAND-P000540

GELFAND-P000541

[source number: 60]

one of them at each odd order.
(and any lin. combination)
2) They are all Hamilton. syst. with n degrees of freedom. _____ · _____
N.'s question: can any potential be approx. by finite-gap ones? _____ · _____

$$P_0 = u', \qquad P_1 = 6uu' - u''' + cu', \dots$$

2) $\exists$ a matrix of order 2

$$\Lambda(u, \dots, u^{(k)}, \delta) = \begin{pmatrix} \lambda & \mu \\ \bar{\mu} & \bar{\lambda} \end{pmatrix}$$

polynomial of degree $2k+1$ in δ

$$\lambda + \bar{\lambda} = 0.$$

and another matrix

$$Q(u, \delta) = i\delta \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix} - \frac{iu}{2\delta} \begin{pmatrix} 1 & -1 \\ 1 & -1 \end{pmatrix},$$

such that $P(u, \dots, u^{(2k+1)}) = 0$ is equiv. to the eq. $\Lambda' = [\Lambda, Q]$
(in partic., the eigenvalues of Λ — integrals of the eq.)

$\alpha_\pm(\delta) = \pm\sqrt{\det \Lambda}$ — a polynomial in δ.



Manuscript excerpt. The symbol reads $\alpha_\pm(\delta)$. The radicand is written $\det \Lambda$.

Original source details: GELFAND-P000541

Commuting integrals — max set. _____ · _____
Consid. an eigenfunc.:

$$\psi_k = e^{ikx + \int_{-\infty}^{x} \chi(x,k)\,dx}, \qquad L\psi = k^2\psi.$$



Undeciphered passage. Below the exponent line after ikx there is a heavy cancellation. The plus and the integral are at exponent height.

Original source details: GELFAND-P000541

Undeciphered passage. A separate crossed-out mark precedes the parenthesis. There is an extra heavy stroke at the end of the word for "correction".

Original source details: GELFAND-P000541

(correction to the phase $\int_{-\infty}^{x} \chi(x,k)\,dx$)

$I = \int \chi(x,k)\,dx$ conserved

$$\chi(x,k) = \sum_{n\geq 1} \frac{\chi_n(x)}{k^n}, \qquad \chi_n(x) \text{ — a polynomial}$$

$$I_n = \int_{-\infty}^{\infty} \chi_n(x)\,dx$$

as a func. of u — int. of the KdV eq.

Let $(*)$ $\underline{\dot{u} = [A,L]}$ — mult. op.;

Undeciphered passage. A crossed-out word precedes L. Its reading is unresolved.

Original source details: GELFAND-P000541

L — Sturm–Liouville oper..

ψ_k — its eigenfunc. (evolution of ψ_k — according to the potential u).

$$\dot{\psi}_k = A\psi_k + \lambda\psi_k + \mu\bar{\psi}_k, \qquad \Lambda = \begin{pmatrix} \lambda & \mu \\ \bar{\mu} & \bar{\lambda} \end{pmatrix}.$$

(tail of the time dep. of the eigenfuncs.)

Uncertain reading. The initial letter is heavily overwritten. “Tail” is a provisional reading.

Original source details: GELFAND-P000541

Apply d/dx — obtain an eq.

$\psi_k(x_0, x)$

At $x = x_0$ $(1, ik)$

$\underline{\dot{T} = [\Lambda, T]}$ — evolution of the monodromy matr. T

|| *Novikov's thm.*

$$\frac{dT}{dx_0} = [Q,T], \qquad Q \text{ — stand. matrix (exercise for the second year)}$$



Manuscript excerpt. The parenthesis reads “exercise for the second year”.

Original source details: GELFAND-P000541

$\Lambda' = [\Lambda, Q]$. Band edges are the roots of a polynomial. (for stat. solns.)

Yakubovich, Starzhinskii: "Diff. eqs. with periodic coefficients".

Original source details: GELFAND-P000541

Manuscript excerpt. The upper rule touches the surname "Yakubovich".

GELFAND-P000542

4/III-73 Gelfand's sem..

Zakharov V.

Manuscript excerpt. The year is written "73".



Original source details: GELFAND-P000542

G. $L = -\dfrac{d^2}{dx^2} + u(x)$. Then $\exists$ oper. A_n, $[A_n, L] =$ mult. by the func. v

$$v = P_n(u, u', \dots, u^{(n)})$$

Manuscript excerpt. In both lines the letter reads v.



Original source details: GELFAND-P000542

$$A_n = \frac{d^{2n+1}}{dx^{2n+1}} + \dots \qquad \text{lower terms}$$

How to find A_n? How are A_n and P_n related?

Relation to the trace formula? Other eqs?

3. Results of A. B. Shabat and Zakharov.

Let $F(x,y)$ be given. $\int_{x_0}^{\infty} F(x,y)\,dy < C$ uniformly.



Original source details: GELFAND-P000542

Manuscript excerpt. The word after $F(x,y)$ reads "given".

Gelf.—Levitan. Eq.

$$K(x,y) + F(x,y) + \int_x^\infty K(x,s)F(s,y)\,ds = 0 \tag{1}$$

x — parameter.

We shall consid. them as oper. kernels.

$$1 + \hat{F} = (1 + \hat{K}_+)^{-1}(1 + \hat{K}_-), \qquad \hat{K}_\pm \text{ — Volterra.}$$

$$\begin{aligned} K_+(x,y) &= 0 \quad \text{when } y < x \\ K_-(x,y) &= 0 \quad \text{when } y > x \end{aligned}$$

This is the same thing,

$$K + F + K * F = 0 \qquad \text{form (1)}$$

Differentiate in t (parameter)

$$D_tK + D_tF + D_tK * F + K * D_tF = 0 \tag{2}$$

Let D and $\tilde{D}$ be other operators: D acts on F, $\tilde{D}$ acts on K. We seek to have

$$\tilde{D}K + DF + \tilde{D}K * F + K * DF = 0 \tag{3}$$

Let

$$DF = \frac{\partial F}{\partial x} + \frac{\partial F}{\partial y}, \qquad \tilde{D}K = \frac{\partial K}{\partial x} + \frac{\partial K}{\partial y}.$$

Then all is in order (direct calculation) shows that identity (3) holds.

$$DF = \frac{\partial^n}{\partial x^n}F \,?\, (-1)^n \frac{\partial^n}{\partial y^n}F \tag{4}$$



Original source details: GELFAND-P000542

Uncertain reading. The sign between the first F and $(-1)^n$ is heavily obliterated.



Original source details: GELFAND-P000542

Undeciphered passage. In the numerator of the second differential operator, to the right of ∂^n, there is a crossed-out sign.

For it one can construct $\tilde{D}$.

$DF = [D_n\, F]$, more precisely $DF =$ the kernel of $[\hat{D}_n, \hat{F}]$, where $\hat{D}_n = \dfrac{\partial^n}{\partial x^n}$.

Namely

$$\tilde{D}K = L_n K + (-1)^n \frac{\partial^n}{\partial y^n} K, \tag{5}$$

G.

$$\widehat{\frac{\partial^2 K}{\partial x^2} - \frac{\partial^2 K}{\partial y^2}} = \left[\hat{K}, \frac{d^2}{dx^2}\right]$$



Original source details: GELFAND-P000542

Manuscript excerpt. An arch spans the difference of derivatives. On the right $\hat{K}$ is first in the brackets.

where $L_n = \dfrac{\partial^n}{\partial x^n} + \ldots$ (lower terms)

K, F can also be matrices.

GELFAND-P000543

[source number: 61]

$$L_n = \frac{\partial^n}{\partial x^n} + n \underbrace{\left(\frac{d}{dx} K(x,x)\right)}_{u_0(x)} \frac{\partial^{n-2}}{\partial x^{n-2}} + \ldots \tag{6}$$

There are recurr. formulas for the lower terms.

L_n — nonlinear operator in K, but its coeffs. (all of them) are made from the quantities

$$\xi_n(x) = \left(\frac{\partial}{\partial x} - \frac{\partial}{\partial y}\right)^n K\Big|_{y=x}$$

$$u_0 = \frac{d\xi_0}{dx}$$

The coeffs. are already constant (of these).

These are not all the operators that differ. this convolution.

These D — linear opers. with const. coeffs. Variable ones are possible too. This is a Lie algebra



Undeciphered passage. A crossed-out entry follows the opening parenthesis. Its reading is unresolved.

Original source details: GELFAND-P000543

(all D, that can be extended (A. Shabat) — they are described).

Suppose that (1) is uniquely solvable for K (F given). And let F be such that $\exists D\colon DF = 0$. Hence

$$\underline{\tilde{D}K = 0} \tag{7}$$

(from (2) and unique solvability of the eq.)

Hence

$$\underline{DF = 0 \longleftrightarrow \tilde{D}K = 0.} \tag{8}$$

Obtain some linearizable eqs. But they are uninteresting.

Let

$$D_1F = 0 \quad \text{and} \quad D_2F = 0 \tag{9}$$

Uncertain reading. A separate loop-like stroke stands to the left of “Let”. Its meaning is unresolved.

Original source details: GELFAND-P000543

Uncertain reading. The crossed-out word provisionally reads “where”.

Original source details: GELFAND-P000543

2 parameters are given t, z; $\quad F = F(x, y; t, z)$ and

$$D_1F = \alpha\frac{\partial F}{\partial t} + ([\hat{L}_0^{(1)}, \hat{F}])_{\text{kernel}} \tag{10}$$

$$D_2F = \beta\frac{\partial F}{\partial z} + ([\hat{L}_0^{(2)}, \hat{F}])_{\text{kernel}} \tag{11}$$

$$\hat{L}_0^{(1,2)} = \sum C^{(n)}\frac{\partial^n}{\partial x^n}$$

$$\tilde{D}_1K = \alpha\frac{\partial K}{\partial t} + L^{(i)}K\ ?\ L_{0y}^{(1)+}K(x,y) \tag{12}$$



Manuscript excerpt. The index above the first L has a distinct dot and reads i.

Original source details: GELFAND-P000543



Uncertain reading. The sign between $L^{(i)}K$ and the next term is heavily obliterated.

Original source details: GELFAND-P000543



Uncertain reading. In (12) and on the next line the last operator carries a superscript provisionally read as $+$. The superscript is absent in (13).

Original source details: GELFAND-P000543

$$[\hat{L}^{(1)}, \hat{F}] = L_x^{(1)} F - L_y^{(1)+} F$$

$$\tilde{D}_2 K = \beta \frac{\partial K}{\partial z} + L^{(2)} K - L_{0y}^{(2)} K \tag{13}$$

$$\boxed{D_1 F = 0,\ D_2 F = 0 \Longrightarrow \tilde{D}_1 K = 0,\ \tilde{D}_2 K = 0.} \tag{14}$$

Theorem.

$$\boxed{\beta \frac{\partial L^{(1)}}{\partial z} - \alpha \frac{\partial L^{(2)}}{\partial t} = [L^{(1)}, L^{(2)}]} \tag{15}$$

$L^{(1)}, L^{(2)}$ — linear operators (for given K).

In $L^{(1)}$ and $L^{(2)}$ the coeffs. are expressed in terms of

$$\xi_n(x) = \left(\frac{\partial}{\partial x} - \frac{\partial}{\partial y} \right)^n K(x,y) \Big|_{y=x}$$

GELFAND-P000544

This is a syst. of nonlin. diff. eqs. for $\xi_n(x, y, t, z)$.

Uncertain reading. The crossed-out argument after x provisionally reads y.

Original source details: GELFAND-P000544

Undeciphered passage. A short crossed-out entry follows the first line. Its reading is unresolved.

Original source details: GELFAND-P000544

The syst. for K reduces to the syst. for F. using the G.–L. eq.

Manuscript excerpt. ~~from F construct $K \Rightarrow \xi_n$~~

Original source details: GELFAND-P000544

Undeciphered passage. There is a heavily crossed-out fragment after the arrow at the end of the line.

Original source details: GELFAND-P000544

Give a pair of lin. diff. ops. with const. coeffs. $L_0^{(1)}$ and $L_0^{(2)}$
from the pair construct the syst. of eqs. (15). Let $D_1F = D_2F = 0$, where
$F = F(x, y; t, z)$

From F construct K, and from K construct a soln. of the system.
Obtain a solution of the system.
1st nontriv. — eq. Kadomtsev–Petriashvili (?).

Original source details: GELFAND-P000544

Manuscript excerpt. The first name provisionally reads “Kadomtsev”. The second appears as “Petriashvili”. The parenthesized question mark is in the manuscript.

$$L_0^{(1)} = \frac{\partial^2}{\partial x^2}, \qquad L_0^{(2)} = \frac{\partial^3}{\partial x^3} + \lambda\frac{\partial}{\partial x}.$$

$$L^{(1)} = \frac{\partial^2}{\partial x^2} + u(x), \qquad \text{where } u(x) = 2\frac{d}{dx}K(x,x),$$
$$L^{(2)} = \frac{\partial^3}{\partial x^3} + \frac{3}{4}\left(u\frac{\partial}{\partial x} + \frac{\partial}{\partial x}u\right) + \lambda\frac{\partial}{\partial x} + w,$$



Original source details: GELFAND-P000544

Uncertain reading. The derivative signs in the leading terms of both operators are retraced. They are rendered as ∂.

where

$$w = \frac{3}{2}\frac{d}{dx}(\xi_1 + \xi_0^2)$$
$$\xi_0 = K(x,x), \qquad \xi_1 = \left(\frac{\partial}{\partial x} - \frac{\partial}{\partial y}\right)K(x,y)\Big|_{y=x}$$

(deriv. in the normal direction)



Original source details: GELFAND-P000544

Manuscript excerpt. The parenthesis reads “deriv. in the normal direction”.

$$\begin{cases} \frac{3}{4}\beta\frac{\partial u}{\partial z} = -\frac{\partial w}{\partial x}; \\ \beta\frac{\partial w}{\partial y} = \frac{1}{4}\left(u_{xxx} + 3uu_x\right) + \lambda u_x + \alpha\frac{\partial}{\partial t}u \end{cases}$$



Original source details: GELFAND-P000544

Uncertain reading. In the first equation the variable below the derivative sign is overwritten. The final outline reads z.

Original source details: GELFAND-P000544

Manuscript excerpt. In the second equation the variable below the derivative sign clearly reads y.



Original source details: GELFAND-P000544

Uncertain reading. The coefficient of uu_x is overwritten and reads 3. At the closing parenthesis is a circled insertion $\boxed{+3u_xu}$

u can be matrix-valued

$$\begin{pmatrix} u_0 & u_1 \\ 0 & u_0 \end{pmatrix}$$ for u_1 obtain a linearized eq. for u_0.

Next come the following linearizations.



Original source details: GELFAND-P000544

Manuscript excerpt. The abbreviation before "linearizations" reads "след.".

β real or imaginary, λ...

All have a phys. meaning.



Original source details: GELFAND-P000544

Diagram and typed description.



Flow around a thin wing of arbitrary shape.



Original source details: GELFAND-P000544

Manuscript excerpt. The manuscript describes a wing of arbitrary shape.

KdV if independent of z.

Nonlin. string.

$$\frac{\partial}{\partial x}\left\{\alpha\frac{\partial u}{\partial t} + 6uu_x + u_{xxx} + \lambda u_x = \frac{3}{4}\beta^2\frac{\partial^2 u}{\partial z^2}.\right.$$



Original source details: GELFAND-P000544

Manuscript excerpt. The sum starts with an opening brace. The manuscript has no closing brace before the equals sign.

A medium with sound dispersion and shallow water.

Karpman's book — see the derivations there. (book on nonlin. waves)

Uncertain reading. The middle letter of the surname is overwritten. The reading "Karpman" is provisional.

Original source details: GELFAND-P000544

$$L_0^{(1)} = \ell_1 \frac{\partial}{\partial x} + \ell_2 \frac{\partial}{\partial y}, \qquad [\ell_1, \ell_2] = 0, \qquad \ell_i \text{ — matrices (diagonal)},$$

$$L^{(1)} = \ell_1 \frac{\partial}{\partial x} + [\ell_1, \xi_0], \qquad \xi_0(x) = K(x,x), \qquad K \text{ — a matrix},$$

$$L^{(2)} = \ell_2 \frac{\partial}{\partial x} + [\ell_2, \xi_0].$$



Uncertain reading. The variable in the denominator of the second term of $L_0^{(1)}$ is overwritten. The reading y is provisional.

Original source details: GELFAND-P000544

GELFAND-P000545

[source number: 62]

$$\ell_1 = \begin{pmatrix} a_1 & & 0 \\ & \ddots & \\ 0 & & a_n \end{pmatrix}; \qquad \ell_2 = \begin{pmatrix} b_1 & & 0 \\ & \ddots & \\ 0 & & b_n \end{pmatrix}.$$

The 1st nontriv. one arises in a matrix of size 3×3

$$\frac{\partial \xi}{\partial t} + \vec{V} \nabla \xi \qquad u_1 = \xi_{13}, \quad u_2 = \xi_{12}, \quad u_3 = \xi_{23}. \qquad \xi^+ = \xi$$



Manuscript excerpt. The superscript on ξ is clearly a $+$.

Original source details: GELFAND-P000545

$$\begin{cases} \dfrac{\partial u_1}{\partial t} + \vec{V}_1 \nabla u_1 = i\lambda u_2 u_3, \\ \dfrac{\partial u_2}{\partial t} + \vec{V}_2 \nabla u_2 = i\lambda u_1 u_3^*; \\ \dfrac{\partial u_3}{\partial t} + \vec{V}_3 \nabla u_3 = i\lambda u_1 u_2^* \end{cases}$$

Manuscript excerpt. The rewritten subscript of the last factor reads 2.

Original source details: GELFAND-P000545

$u_i(t,x,z)$, ∇ — 2-dimensional, $\vec{V}_i$ — arb. vectors

Describes the interaction of waves of 3 types in a nonlin. medium.

Dissipation cannot be introduced (ever). _____ · _____

Conjecture: they are all Hamiltonian. From one L one constructs the symplect. form, and from the other, the Hamiltonian. _____ · _____

$u_{tt} - u_{xx} = \sin u$ also comes from the matrices



Diagram and typed description.

$$L_0^{(2)} = \begin{vmatrix} 1 & 0 & 0 \\ & -1 & \\ 0 & & 0 \end{vmatrix}$$

Original source details: GELFAND-P000545



Diagram and typed description.

$$L_0^{(1)} = \begin{vmatrix} 1 & 0 & \\ & 1 & \\ 0 & & -1 \end{vmatrix}$$

Original source details: GELFAND-P000545

and an eq. for propag. of a laser pulse in . . .



Manuscript excerpt. The manuscript has a series of dots after “in”.

Original source details: GELFAND-P000545

_____ · _____

Bloch eq. for density matrices (quant. mech. in a 2-level system). _____ · _____

Matrix ops. of high orders.

$$L_0^{(1)} = \ell_1 \frac{\partial}{\partial x}, \qquad L_0^{(2)} = \frac{\partial^2}{\partial x^2}.$$

One obtains

$$i\frac{\partial \xi}{\partial t} + \xi_{xx} \pm |\xi|^2 \xi = 0 \qquad \text{(nonlin. Schrödinger eq.)}$$

there is a scheme for solving the Cauchy prob. _____ · _____

11/III-74. Gelfand's sem..

Diagram and typed description.
Povzner. Witham.

Original source details: GELFAND-P000546

$$\frac{\partial^2 u}{\partial t^2} - \frac{\partial^2 u}{\partial x^2} + T'(u) = 0$$



Uncertain reading. The variable in the first denominator is overwritten and rendered as t.

Original source details: GELFAND-P000546

1) a wave travels $x \sim t$ (pract. theory).



Manuscript excerpt. The parenthesis reads "pract. theory".

Original source details: GELFAND-P000546

and the asympt. of what happens far away

$$x \longrightarrow \frac{x}{\epsilon}, \qquad t \longrightarrow \frac{t}{\epsilon}$$

the asympt. is now sought in a finite region and as $\epsilon \to 0$.
$f(x - vt)$, v depends little on t and x (varies slowly in the sense of ϵ).
The method consists of the following:

$$\epsilon^2 \left(\frac{\partial^2 v}{\partial t^2} - \frac{\partial^2 v}{\partial x^2} \right) + T'(u) = 0.$$



Manuscript excerpt. Both numerators carry v, and the last term is $T'(u)$.

Original source details: GELFAND-P000546

study the asympt. in a finite region.

Add. assumption (justif. by scientific experience):

$$u(x,t) = f\left(\frac{\Theta_0(x,t)}{\epsilon}; x, t\right)$$

$$f(x_{\text{old}} - ct_{\text{old}}) = f\left(\frac{x-ct}{\epsilon}\right)$$

— exact trav. waves are a special case with $\Theta_0(x,t) = x - ct$

Manuscript excerpt. Both coordinate subscripts read “cr”, translated as “old”.

Original source details: GELFAND-P000546

$$\frac{\Theta_0(x,t)}{\epsilon} = \Theta \qquad f(\Theta; x, t).$$

hence one obtains a diff. eq.

$$\epsilon^2(\omega_2^2 - \omega_1^2)\frac{\partial^2 u}{\partial \Theta^2} + T'(u)u + [\epsilon(u_x, u_t)\ldots] = 0$$



Uncertain reading. The letter in the derivative numerator is heavily overwritten. The reading u is provisional.

Original source details: GELFAND-P000546



Uncertain reading. Immediately after $T'(u)$ is a heavily overwritten mark. The reading u is provisional.

Original source details: GELFAND-P000546

where $\omega_2 = \Theta_{0t}, \quad \omega_1 = \Theta_{0x}$.

As $\epsilon \to 0$ one obtains

$$\epsilon^2(\omega_2^2 - \omega_1^2)\frac{\partial^2 u}{\partial \Theta^2} + T'(u) = 0$$



Original source details: GELFAND-P000546

Manuscript excerpt. The factor ϵ^2 remains in the displayed equation after $\epsilon \to 0$.

ordinary eq. of 2nd order, E_1, E_2 — arb. consts.

$$u = u(E_1, E_2; x, t, \Theta)$$

Equation for Θ.

Now substitute $\Theta = \dfrac{\Theta_0(x,t)}{\epsilon}$.

$$u = u\left(E_1, E_2; \frac{\Theta_0(x,t)}{\sqrt{\omega_2^2 - \omega_1^2} \cdot \varphi(E) \cdot \epsilon}\right)$$

(the solution is obtained in this form)

Add. eq.:

Uncertain reading. A crossed-out symbol resembling Θ_0 precedes the square root.

Original source details: GELFAND-P000546

$$\sqrt{\omega_2^2 - \omega_1^2}\, \varphi(E_1, E_2) = \text{const}$$

$$\varphi = \int_{u_0}^{u_1} \sqrt{E - T(u)}\, du$$



Manuscript excerpt. The letter φ has a closed right loop in all three places. The middle occurrence is retraced.

Original source details: GELFAND-P000546

Ref.: Witham. This eq., Korteweg, heavy fluid, radiophys., lasers.
J. of Fluid Mechanics 1972 "Two-timing ..." (Witham)



Original source details: GELFAND-P000546

Manuscript excerpt. The parenthesized name and the year follow the manuscript. "1972" is written below the journal title.

GELFAND-P000547

[source number: 66]

V. N. Tulovsky. On Hörmander's work.
Wave fronts.

$$u \in \mathcal{D}'(\Omega), \qquad \Omega \subset \mathbb{R}^n.$$

$(x_0, \xi_0) \notin WF(u)$, if $\exists \varphi \in C_0^\infty(\Omega), \quad \varphi(x_0) \neq 0$

$$\left|\langle u, \varphi e^{-i\langle x,\xi\rangle}\rangle\right| \leq C_N(1+|\xi|)^{-N}$$

in a small conic neighborhood of the point ξ_0:

$$\left|\frac{\xi}{|\xi|} - \frac{\xi_0}{|\xi_0|}\right| < \epsilon.$$

Examples:



Original source details: GELFAND-P000547

Diagram and typed description.

normals
convol. with a δ-like seq. and pass. to the limit.

G.

$$\int \varphi(x_1, x_2) e^{i(x_1\xi_1 + x_2\xi_2)}\, dx_1\, dx_2$$

stat. int. over the plane.

$$\int \psi(t) e^{ict}\, dt$$



Uncertain reading. A faint sign appears between i and t, provisionally read as c.

Original source details: GELFAND-P000547



Diagram and typed description.



— there will be a sing. here of the func. $\psi(t)$.

Original source details: GELFAND-P000547



Diagram and typed description.

no singularity of $\psi(t)$.

Original source details: GELFAND-P000547

Tul. $\pi WF(u) = \operatorname{sing\,supp} u.$

$$\pi(x, \xi) = x.$$

$$P : C_0^\infty(\Omega) \longrightarrow C^\infty(\Omega_1), \qquad \exists K_P \in \mathcal{D}'(\Omega \times \Omega_1),$$
$$\langle K_P, u(x)v(y)\rangle = \langle Pu, v\rangle$$
$$WF(K_P) \underset{\text{def}}{=} WF(P)$$

In the space (x, y, ξ, η).

Suppose $WF(P) \not\ni$ points where $\xi = 0$ or $\eta = 0$.

$$\boxed{WF(P) \cap (\{\xi = 0\} \cup \{\eta = 0\}) = \varnothing}$$



Original source details: GELFAND-P000547

Manuscript excerpt. A slashed ∋ precedes “points”.

Then one can extend $P : \mathcal{E}'(\Omega) \to \mathcal{D}'(\Omega_1)$.

Def.

$$WF'(P) = \{(x, y, \xi, \eta) : (x, y, \xi, -\eta) \in WF(P)\}.$$

Def.

$$WF'(P) \circ WF(u) = \{(y, \eta) : \exists (x, y, \xi, \eta) \in WF'(P),\ (x, \xi) \in WF(u)\}.$$

Theorem.

$$WF(Pu) \subset WF'(P) \circ WF(u).$$

Suppose there are 2 operators:

$$Q : \underset{y}{\mathcal{E}'(\Omega_1)} \longrightarrow \underset{z}{\mathcal{D}'(\Omega_2)},$$
$$P : \underset{x}{\mathcal{E}'(\Omega)} \longrightarrow \underset{y}{\mathcal{E}'(\Omega_1)}$$

$$WF'(Q \circ P) \subseteq WF'(P) \circ WF'(Q).$$

Original source details: GELFAND-P000547

Manuscript excerpt. The left side has $Q \circ P$ in parentheses. On the right $WF'(P)$ comes first.

$$(x, z; \xi, \zeta) \in WF'(P) \circ WF'(Q) \underset{\text{def}}{\Longleftrightarrow} \exists\, (x, y, \xi, \eta) \in WF'(P),$$
$$(y, z, \eta, \zeta) \in WF'(Q).$$



Uncertain reading. The overwritten second coordinate on the left provisionally reads z.

Original source details: GELFAND-P000547

GELFAND-P000548

Product of generalized funcs..

$\Gamma \subseteq T^*(\Omega) \setminus 0$, Γ — a conic closed set.

$$\mathcal{D}_\Gamma(\Omega) = \{u \in \mathcal{D}'(\Omega),\ WF(u) \subseteq \Gamma\}.$$



Original source details: GELFAND-P000548

Manuscript excerpt. The first $\mathcal{D}_\Gamma$ is written without a prime. The inner $\mathcal{D}'$ carries one.

Theorem: let Γ_1, Γ_2 — 2 closed conic sets in $T^*(\Omega) \setminus 0$ and suppose

$$\Gamma_1 + \Gamma_2 \subseteq \Omega \times (\mathbb{R}^n \setminus 0)$$

$$(x,\xi) \qquad (x,\eta) \qquad \Gamma_1 + \Gamma_2 = \{(x, \xi+\eta)\}, \qquad \xi + \eta \neq 0$$

Then there exists a cont. mapping

$$\mathcal{D}_{\Gamma_1}(\Omega) \times \mathcal{D}_{\Gamma_2}(\Omega) \longrightarrow \mathcal{D}_{\Gamma_1 \cup \Gamma_2 \cup (\Gamma_1+\Gamma_2)}(\Omega),$$

extending the product of ordinary funcs.
(and the product of a generalized func. by a smooth one)
(It is unique owing to the topology consid.)

Def. of Fourier integral ops.

$\varphi(x,\Theta), \quad (x,\Theta) \in \Omega \times (\mathbb{R}^N \setminus 0)$ — a phase func., if it is real, homogeneous of order 1 [in Θ] and $\varphi'_{x,\Theta} \neq 0$.

Original source details: GELFAND-P000548

Manuscript excerpt. The circled insertion "in Θ" is attached to "homogeneous".

$$S^m_{\rho,\delta}(X \times \mathbb{R}^N) \ni a(x,\Theta),$$
$$\left|\partial_x^\alpha \partial_\Theta^\beta a(x,\Theta)\right| \leq C_{\alpha,\beta}(1+|\Theta|)^{m-\rho|\beta|+\delta|\alpha|}, \qquad x \in K.$$



Original source details: GELFAND-P000548

Uncertain reading. Two indices in the exponent and the variable before $\in K$ are retraced. The reading is $m - \rho|\beta| + \delta|\alpha|$ and $x \in K$.

$$\langle A, u\rangle = \int e^{i\varphi(x,\Theta)} a(x,\Theta) u(x)\, dx\, d\Theta$$
$$= \lim_{\epsilon \to 0} \int e^{i\varphi(x,\Theta)} a(x,\Theta) \chi(\epsilon\Theta) u(x)\, dx\, d\Theta$$

where $\chi \in C_0^\infty(\mathbb{R}^N)$, $\chi = 1$ when $|\Theta| \leq 1$.

Original source details: GELFAND-P000548

Manuscript excerpt. The last condition clearly reads $|\Theta| \leq 1$.

18/III-74. Gelfand's sem.. A. B. Shabat.

$$4f_t + f_{xxx} + ff_x = 0.$$



Manuscript excerpt. The plus sign is followed immediately by ff_x.

Original source details: GELFAND-P000549

$$f(x,t) = g(x-ct) = \frac{2\lambda^2}{\mathrm{ch}^2[\lambda(x-\lambda^2 t - h)]};$$

2-solit. solution

$$f(t,x) = \frac{\lambda_1}{\cdot\cdot} + \frac{\lambda_2}{\cdot\cdot} + O(e^{-\varkappa t}) \quad \text{as } t \to +\infty.$$



Uncertain reading. The letter in the exponent has two loops. The reading $\varkappa$ is provisional.

Original source details: GELFAND-P000549

one can prove that it is unique.

1) Estimate the total amplitude at the instant of collision.

$$|f(t,x)| \le 2\sum_{j=0}^{n} \lambda_j(\lambda_{j+1} - \lambda_j), \qquad \lambda_0 = 0$$



Uncertain reading. A small sign above the sum touches a descender from the adjacent line. The reading n is provisional.

Original source details: GELFAND-P000549

(the amplit. do not add as in the lin. case)

2) The centers will shift. Calculate the shift. The answer is stand. — scattering.

Bargmann potential $q(x)$, if $\exists 2$ solns. of the eq.

$$y'' + (q(x) + \zeta^2)y = 0$$

of the form

$$y_{1,2} = P_{1,2}(x,\zeta)e^{\mp i\zeta x} \qquad \text{polynomial in } \zeta.$$



Uncertain reading. The spectral letter provisionally reads ζ.

Original source details: GELFAND-P000549

Undeciphered passage. A neighboring entry is cut off at the left edge. The closing parenthesis and equals sign are visible $\ldots) = \ldots$

Original source details: GELFAND-P000549

GELFAND-P000550

Let P, Q be such that:

$$c_k e^{2i\zeta x}\Big|_{\zeta=\zeta_k} = \frac{P(x,\zeta)}{Q(x,\zeta)}\Big|_{\zeta=\zeta_k}, \qquad \frac{P}{Q}\Big|_{\zeta=\infty} = 1$$



Uncertain reading. The spectral letter provisionally reads ζ.

Original source details: GELFAND-P000550

|| Points ζ_k $2n\,?\,1$ (and $+\infty$)



Uncertain reading. Ink obscures the sign between $2n$ and 1.

Original source details: GELFAND-P000550

For any choice of parameters c_k, ζ_k one obtains a fund. syst. of solutions of the S.–L. oper. with Bargmann pot.

$$y_1 = P(x,\zeta)e^{i\zeta x}$$
$$y_2 = Q(x,\zeta)e^{-i\zeta x}$$

1.

$$P'_x Q - Q'_x P - 2i\zeta PQ = \prod(\zeta - \zeta_k).$$

Diff. with respect to x.

$$\frac{d}{dx}\frac{P}{Q}\Big|_{\zeta=\zeta_k} = \frac{P'_x Q - Q'_x P}{Q^2}\Big|_{\zeta=\zeta_k} = 2i\zeta\,\frac{P}{Q}\Big|_{\zeta=\zeta_k}$$

is a rat. func. in ζ with zeros at the [crossed out] giv. points

Uncertain reading. The short crossed-out entry before “giv.” is illegible.

Original source details: GELFAND-P000550

$$\left.\frac{P_xQ - Q_xP - 2i\zeta PQ}{Q^2}\right|_{\zeta=\zeta_k} = 0.$$

and one cond. at ∞.

Now let c_k depend on t (the parameter):

$$c_k(t) = c_k(0)e^{2i\zeta^3 t}$$



Uncertain reading. The argument of $c_k(t)$ reads t over earlier strokes. The underlying entry is illegible.

Original source details: GELFAND-P000550

$$\left.\frac{P}{Q}\right|_{\zeta=\zeta_k} = \left. c_k(t)e^{2i\zeta x}\right|_{\zeta=\zeta_k}$$

Then also

$$\left(4\frac{\partial}{\partial t} + \frac{\partial^3}{\partial x^3} - 3q\frac{\partial}{\partial x}\right)P = (\qquad)Q = 0$$

Undeciphered passage. The manuscript leaves the parentheses before Q empty.

Original source details: GELFAND-P000550

Then $f = \frac{d}{dx}\log Pe^{?i\zeta x}$ satisf.



Uncertain reading. The sign before $i\zeta x$ is overwritten and its reading remains unresolved.

Original source details: GELFAND-P000550

$$4f_t + f_{xxx} + 3(f^2 + \zeta^2)f_x = 0,$$

while $f' + f^2 = q$ satisf. the eq.

$$4q_t + q_{xxx} + 6qq_x = 0.$$



Manuscript excerpt. In the first equation the 4, the $+$ sign and the 3 are retraced. In the second, qq_x is retraced.

Original source details: GELFAND-P000550

GELFAND-P000551

25/III-74. Gelfand's sem..

Kirillov. On inf. groups. Descr. of repres. of the fol. groups

$$G_1 = \text{Diff}\, M, \qquad G_2 = H^M = C^\infty(M, H) \qquad (H \text{ is a group}).$$

Original source details: GELFAND-P000551

Uncertain reading. A separate two-stroke glyph stands to the left of the diagram. Its reading remains unresolved.



Original source details: GELFAND-P000551

Diagram and typed description.

$$\begin{array}{ccc} & & E \\ & & \downarrow \\ H & & \\ & & M \end{array}$$

principal bundle and its automorphism group

It projects onto G_1 with fiber G_2

Original source details: GELFAND-P000551

Undeciphered passage. The rectangular entry below the diagram is densely crossed out and illegible.

$$e^H = H_0 \oplus H \oplus S^2(H) \oplus S^3(H) \oplus \dots$$



Original source details: GELFAND-P000551

Uncertain reading. Two horizontal strokes and a small loop between them stand above $H, \oplus, S^2(H)$. Their meaning and attachment remain unresolved.

(H_0 is one-dimensional; $S^k(H)$ is a symm. power

$$1 \qquad \xi \qquad \frac{\xi \otimes \xi}{2!} \qquad\qquad |\xi|^2 = \sum \frac{|\xi_n|^2}{n!}$$



Original source details: GELFAND-P000551

Uncertain reading. The circled sign in the numerator provisionally reads $\otimes$.

Gurevich. On the K.–d.–V. eq. by Whitham's method.

Uncertain reading. The ending of the abbreviated word for "equation" is overwritten in the Russian. Its exact reading remains unresolved.

Original source details: GELFAND-P000551

GELFAND-P000552

1/*IV*-74. Gelfand's sem..

Yura Koblents. On the asymptotics of the eigenvalues of the Laplace oper..

(from Leningrad)

M — closed Riem. manif., Δ — Beltrami–Laplace oper..

$$\lambda_0 = 0, \qquad 0 \le \lambda_1 \le \lambda_2 \le \dots \qquad \text{— spectrum.}$$

$$Z(s) = \operatorname{Tr}\exp(-s\Delta) = \sum_i e^{-\lambda_i s}$$

$$\Delta f = \frac{1}{\sqrt{g}} \frac{\partial}{\partial x^i}\left(\sqrt{g}\, g^{ij} \frac{\partial f}{\partial x^j}\right), \qquad \text{where } g = \det \|g_{ij}\|,$$

Undeciphered passage. There is a densely crossed-out entry between the equals sign and $1/\sqrt{g}$. A stroke on the right cannot confidently be separated from the cancellation.

Original source details: GELFAND-P000552

$$E(m, m', t) = \sum e^{-\lambda_i t} \varphi_i(m) \varphi_i(m').$$

Uncertain reading. The letter in both factors provisionally reads φ.

Original source details: GELFAND-P000552

$$Z(s) = \int E(m, m, s)\, dm$$

Minakshisundaram, 1949

$$Z(t) = (4\pi t)^{-n/2}(a_0 + a_1 t + a_2 t^2 + \ldots), \qquad t \to 0.$$

$$n = \dim M, \qquad a_0 = \operatorname{vol} M, \qquad \operatorname{Re} t > 0.$$

$$a_1 = \int_M \frac{\tau}{6}\, dV, \qquad \text{where } \tau \text{ — scal. curvature}$$

$$\tau = \sum_{\alpha\beta[?]\beta} R^{\alpha\beta}_{\alpha\beta[\ldots]}$$



Uncertain reading. The sum index shows an initial $\alpha\beta$ and a final β, with overwritten strokes between them. Two signs after the lower $\alpha\beta$ of R are crossed out.

Original source details: GELFAND-P000552

$$a_2 = \frac{1}{360} \int \left(2|R|^2 - 2|\rho|^2 + 5\tau^2\right)$$

R — curvature tensor; ρ — Ricci tensor,

$$\rho_{ij} = \sum_{\alpha} R^{\alpha}_{i\alpha j}$$



Uncertain reading. There is a heavily overwritten mark after the lower j of R. The original stroke is illegible.

Original source details: GELFAND-P000552

$$|R|^2 = \sum R^2_{\alpha\beta\gamma\delta} \qquad \text{in norm. coord.} \qquad |R|^2 = R_{\alpha\beta\gamma\delta}R^{\alpha\beta\gamma\delta}$$

$$|\rho|^2 = \rho_{\alpha\beta}\rho^{\alpha\beta}$$

$$E(t, m, m') = (4\pi t)^{-n/2}\left(u_0(m, m') + u_1(m, m')t + u_2(m, m')t^2 + \ldots\right)$$

in a neighb. of the diagonal.

a_3 — Sakai and the speaker (independently).

G. Number of int. points in a disk:

$$a(r) = \pi r^2 + \sum_{\lambda_n} \tau^{1/2} \sin \frac{\tau}{\lambda_n}$$



Uncertain reading. The letter at the start of the formula provisionally reads r. Both occurrences in the summand have a broad wavy top, provisionally read as τ.

Original source details: GELFAND-P000552

(λ_n — zeros of the Riemann ζ-func.) mod the Riemann hypothesis Schnirelmann.

In the ball λ_n — lengths of closed billiard paths.



Manuscript excerpt. The first letter of “шаре” has three strokes.

Original source details: GELFAND-P000552

$$\sum \delta(\lambda - \lambda_k) * \frac{\varepsilon}{\lambda^2 + \varepsilon^2} = f(\lambda)$$

GELFAND-P000553

[source number: 83]

$$f(\lambda) = f_0(\lambda) + \sum_k c_k \lambda^{\alpha_k} \sin(\ell_k \lambda + \omega_k)$$

There is exper. confirmation (Balian and Bloch)

Uncertain reading. The end of the surname Balian is retraced. The reading of the final n is provisional.

Original source details: GELFAND-P000553

(and even a precise statement).

$$\sum e^{i\lambda_k z} = \mathrm{Sp}(e^{-z\Delta}).$$



Manuscript excerpt. The exponent on the left is $i\lambda_k z$, and the one on the right is $-z\Delta$.

Original source details: GELFAND-P000553

contin. downward (from the upper half-plane)

Twin probl.:

$$\lambda_{k+1} - \lambda_k > c\lambda_k^{-\nu} \qquad \text{for general operators}$$

Uncertain reading. The letter after the minus has two converging strokes and provisionally reads ν.

Original source details: GELFAND-P000553

but on the circle they are double. (stably asympt. double spectrum).

T^2 $\quad g_{ij} \sim \delta_{ij}$ $\quad$ the theorem holds

Theorem.

$$\min(\lambda_{k+1} - \lambda_k, \lambda_k - \lambda_{k-1}) < C_N \cdot k^{-N}, \qquad \forall N$$

(Lazutkin, Schnirelmann)

Uncertain reading. The strokes leading into the last letters of “Schnirelmann” are overwritten. The underlying strokes are illegible.

Original source details: GELFAND-P000553

(a small but finite perturbation) — stab.

For T^3 this is no longer so. (apparently).

$$\frac{\partial u}{\partial t} = i\sqrt{-\Delta}\, u; \qquad u|_{t=0} = \delta_x$$



Uncertain reading. The overwritten letter after ∂ provisionally reads u.

Original source details: GELFAND-P000553

Its soln. $\quad u(x, y, t)$

$$\sum e^{i\lambda_k t} = \int_M u(x, x, t)\, dx = f(t);$$



Uncertain reading. The sign in the exponent of the sum and the final argument of the integrand are retraced. Both provisionally read t.

Original source details: GELFAND-P000553

singul. of $u(x, y, t)$ where $|x - y| = t$

Original source details: GELFAND-P000553

Diagram and typed description.



for some t bifurcations occ.

Original source details: GELFAND-P000553

Uncertain reading. The Russian ending of “bifurcations” is overwritten. The reading is provisional.

singul. move at speed 1

Chapter 8

GELFAND-P000554

2/IX-74. Gelfand's sem. (32nd year of the seminar)

Giusti.

1. Singularities [crossed out] and regularity

Uncertain reading. Crossed-out strokes lie between "Singularities" and "and". The original entry is illegible.

Original source details: GELFAND-P000554

[crossed out] of solutions of non-linear elliptic (and parabolic) systems.



Uncertain reading. A separate crossed-out entry precedes "of solutions". Its reading remains unresolved.

Original source details: GELFAND-P000554

Nash, De giorgi, Moser. — Regularity: 1 equation linear ~~di...~~ with discont. coeff. (Höld. coeff.) ⇒ regul. for non linear with smooth coeff.

Uncertain reading. There are crossed-out letters before "with". The opening provisionally reads "di".

Original source details: GELFAND-P000554

Systems — [crossed out] false. There are [?] coeff. and [?] solutions



Uncertain reading. A heavily crossed-out sign follows the dash before "false".

Original source details: GELFAND-P000554

Original source details: GELFAND-P000554

Uncertain reading. The Russian abbreviations before "coefficients" and "solutions" provisionally read "Быв. ср." and "несгр.".

1968 Miranda, Giusti — syst. with analytic coeff. with discont. solutions

Uncertain reading. The beginning of the surname Giusti is overwritten and the underlying strokes are illegible.

Original source details: GELFAND-P000554

Σ — singular set.

(1) Σ closed
(2) $\dim \Sigma < n - 2$

2. Boundary value problems. for surfaces of prescribed mean curvature.

$u : \Omega \longrightarrow \mathbb{R}$ graph $u = S$

Original source details: GELFAND-P000554

Diagram and typed description.





Original source details: GELFAND-P000554

Diagram and typed description.



$$H(x) = \frac{1}{n} \sum \frac{\partial}{\partial x_i} \left(\frac{\partial u / \partial x_i}{\sqrt{1 + |\operatorname{grad} u|^2}} \right)$$

H is not very large (otherwise unsolvable). Depends on the geometry of the domain, the func. $H(x)$ and so on

That is what will come next time.

S. P. Novikov. (and Dubrovin).

Abelian var. $\xi_1, \ldots, \xi_{2n}$ — basis in $\mathbb{C}^n$ (over $\mathbb{R}$), T^{2n} — corresp. torus. Let the Abelian var. (algebraic var.).

How to describe all tori?

$n = 2$ already nontrivial.

$y^2 = P_{2n+1}(x)$ Riem. surface $\Rightarrow$ torus.

Undeciphered passage. A crossed-out entry before H^1 provisionally begins “Вид...”. The rest is illegible.

Original source details: GELFAND-P000554

$$\underbrace{H^1(R,\mathbb{C})/H^1(R,\mathbb{Z})}_{\text{the torus is like this}} \qquad R \longrightarrow J^{2n}(R). \quad \text{(torus)}$$

$$k = 0, \dots, n-1, \qquad \boxed{\omega_k = \frac{x^k\,dx}{\sqrt{P_{2n+1}(x)}}} \quad \longleftarrow \quad \text{everywhere regular differentials.}$$

Basis — the forms ω_k.

$$P_{2n+1}(x) = \prod (x - x_\alpha).$$

Everything is det. by the set of roots.



Original source details: GELFAND-P000554

Diagram and typed description.

$$\begin{array}{ccccc} \widehat{M} & \longrightarrow & M & \xrightarrow{R} & B \\ & & & \nearrow & \\ \widehat{\widetilde{M}} & \longrightarrow & \widetilde{M} & & J(R) \\ | & & & & \end{array}$$

The lower diagonal arrow ends below and to the left of the upper B. Its exact connection remains unresolved.

M — collection of Riem. surfaces

B — Siegel upper half-space

(cover of the moduli set).

from the set of roots one constructs the polynomial, and from it the torus.

GELFAND-P000555

$$p_1, p_2, q_1, q_2, c, d. \qquad \mathbb{C}^6 \text{ or } \mathbb{C}^4_{c,d}$$

$$J_1 = p_1 p_2 + V(q_1, q_2)$$

$$J_2 = p_1^2 - 2q_1 p_1 p_2 + 2(q_2 - c)p_2^2 + \mathcal{D}(q_1, q_2)$$

$$\Omega = \sum_{\alpha=1}^{2} dp_\alpha \wedge dq_\alpha.$$

$\langle J_1, J_2 \rangle \equiv 0.$ Poisson br.

$$V = -\left(\frac{q_2^2}{2} + \frac{5}{2}q_1^2 q_2 + \frac{5}{2}q_1^4\right) + c_1 q_1^2 - d_1 q_1$$

Original source details: GELFAND-P000555

Uncertain reading. The sign before the equals sign is overwritten. It has two upper strokes and provisionally reads V.

$$\mathcal{D} = q_1^5 + 2c_1 q_1^3 + d_1 q_1^2 - 4q_1 q_2^2 + 4c_1 q_1 q_2 - 2d_1 q_2$$

$[X_{J_1}, X_{J_2}] = 0.$ Obtain 2 commut. fields.

The corresp. orbits — an Abelian var.

$$\left.\begin{array}{l} J_1 = \text{const} \\ J_2 = \text{const} \end{array}\right\} \quad \text{torus.}$$

Uncertain reading. A crossed-out entry left of the equations starts with a J-like form. The rest is illegible.

Original source details: GELFAND-P000555

Corollary: the coll. of them all — a unirat. variety.

$$R: \quad y^2 = x^5 + \frac{c_1}{4}x^3 - \frac{d_1}{16}x^2 + \left(\frac{J_1}{32} + \frac{c_1^2}{4}\right)x + \frac{J_2}{2^8} + \frac{c_1 d_1}{2^7}$$

R — Riem. surface, $S^n R$ — symm. power of R.

$(J_1, \ldots, J_n)$ and symmetrization.



Uncertain reading. Both letters in the row before “and symmetrization” have a hook. The reading J is provisional.

Original source details: GELFAND-P000555

$$S^n R \longrightarrow J(R).$$

$(P_1, \ldots, P_n) \xrightarrow{A} (\alpha_1, \ldots, \alpha_n)$ Abel map.

(Abel’s theor. — it is an isomorphism).

Diagram and typed description.



The upper curve thickens at P_1. An arrowhead cannot be distinguished.

Original source details: GELFAND-P000555

$$(P_1, \dots, P_n) \longrightarrow \left(\underbrace{\sum_{k=1}^{n} \oint_Q^{P_k} \omega_s}_{\| \ \alpha_s} \right)$$



Manuscript excerpt. A loop is visible on the integral sign. Two short strokes stand above α_s below the bracket.

Original source details: GELFAND-P000555

$$L = -\frac{d^2}{dx^2} + u(x),$$

$u(x+T) = u(x)$ or quasiperiodic.

Eigenfunc. $L\Psi(x, E) = E\Psi,$

$$\Psi(x+T) = \lambda\Psi(x), \qquad |\lambda| = 1, \qquad \lambda = e^{ip(E)}$$

(Bloch eigenfuncs.)

For almost periodic [crossed out] the collection of such eigenfuncs. does not form a complete system.

Undeciphered passage. A short densely crossed-out entry follows the Russian abbreviation for “periodic”.

Original source details: GELFAND-P000555

$\Psi|_{x_0} = 1$ — normalization

$\Psi(x, E, x_0)$ $(\Psi, \overline{\Psi})$ — 2 eigenfuncs.

branches in E at the endpoints of the spectral intervals. Obtain a Riem. surface of inf. genus. 2 sheets, since there are 2 eigenfuncs.

GELFAND-P000556

The set of pot. with given band structure — the Jacobian var. of this Riem. surface (there are formulas)



Uncertain reading. The first strokes in the Russian word for “band” are overwritten.

Original source details: GELFAND-P000556



Original source details: GELFAND-P000556

Diagram and typed description.



Pot. with given band structure — the corresp. torus (Jacobian var.). .....

9/IX-74 . Gelfand's sem..

Bessaga (Warsaw). Anderson's Z-sets and their applications. (R. D. Anderson)

X — a complete metriz. space. $A \subset X$, $\overline{A} = A$.

A is called a Z-set if $\forall$ cont. maps

$$f : \underbrace{I^\infty}_{\text{Hilb. cube}} \longrightarrow X, \qquad \forall \varepsilon > 0, \qquad \exists g : I^\infty \longrightarrow X \setminus A, \qquad \rho(f,g) < \varepsilon.$$

$$Q = [-1,1]^\infty, \qquad P = (-1,1)^\infty. \qquad (Q \setminus P) \text{ — } Z\text{-set}$$

Prop.: 1°. If A, B are Z-sets (in Q), then $f : A \xrightarrow{\sim} B$ extends to a ~~homeo~~ homeom. of the entire space.

Original source details: GELFAND-P000556

Uncertain reading. The numeral of 1° is heavily overwritten. The small circle and period are distinguishable.

Original source details: GELFAND-P000556

Uncertain reading. The crossed-out abbreviation before "homeom." provisionally reads "homeo".

Z_σ-set — a countable union of Z-sets.

2°. There exists a maximal Z_σ-set _____ · _____

Gelfand

Consid. $\mathbb{R}^\infty$ in the Tych. topology and the space S of rays [crossed out] issuing from 0 in the nat. topology. Prove that on S every cont. func. is [crossed out] const

Original source details: GELFAND-P000556

Undeciphered passage. There is a densely crossed-out entry between "rays" and "issuing".

Original source details: GELFAND-P000556

Uncertain reading. A small crossed-out mark precedes "const". Its reading remains unresolved.

(Gelf., Fuks. Funct. Anal. I, 4). _____ · _____

Bessaga. All separab. Fréchet spaces are homeomorphic.

Giusti. $\Omega \subset \mathbb{R}^n$

Original source details: GELFAND-P000556

Diagram and typed description.



$$\begin{cases} \sum_{i=1}^{n} D_i \left\{ \dfrac{D_i u}{\sqrt{1+|Du|^2}} \right\} = -H(x,u) \quad \text{in } \Omega, \\ u = \phi \quad \text{on } \partial\Omega \end{cases} \qquad D_i = \frac{\partial}{\partial x_i}.$$

n times the mean curvature $=$ the left-hand side of the eq.

$H \equiv 0 \quad \Rightarrow \quad$ minimal surface.



Original source details: GELFAND-P000556

Diagram and typed description.



A dark mark sits at the lower end of the inner vertical stroke. Its shape is indistinct.

Example 1. $\Omega, \quad n = 2, \quad H = 0$

Original source details: GELFAND-P000556

Diagram and typed description.



circular annulus. The labels 1 and 2 stand beside the two radial strokes.

$$\phi = \begin{cases} 0 & |x| = 2 \\ M & |x| = 1 \end{cases}$$

Solution: $u(r)$, $r = |x|$.

$$u(r) = c \log \frac{2 + \sqrt{4 - c^2}}{r + \sqrt{r^2 - c^2}}, \qquad 0 \le c \le 1,$$
$$u(1) = M \quad \Rightarrow \quad u(1) \le \log(2 + \sqrt{3}) = M_0.$$



Uncertain reading. The opening strokes of $u(r)$ and $u(1)$ are heavily overwritten. The underlying forms are illegible.

Original source details: GELFAND-P000556

GELFAND-P000557

For $M > M_0$ there are no solutions.

Exper. check: soap bubble

we carefully lift the stick steak.

Manuscript excerpt. Below the Russian word for “stick” the manuscript reads “steak.” with a wavy underline.

Original source details: GELFAND-P000557



Diagram and typed description.



Original source details: GELFAND-P000557

if it is a wire ring, then

Diagram and typed description.



Original source details: GELFAND-P000557

Example 2. $n = 1, \quad \Omega = (-1, 1)$

$u = 3x^{1/3}$



Uncertain reading. The initial letter is overwritten. Its final outline provisionally reads u.

Original source details: GELFAND-P000557

$$\left(\frac{u'}{\sqrt{1+u'^2}}\right)' = \underbrace{-\frac{2}{3}x^{1/3}\left(1+x^{4/3}\right)^{-3/2}}_{\text{cont.}}$$



Manuscript excerpt. The exponent on the first x is $1/3$. The exponent on the second x is $4/3$.

Original source details: GELFAND-P000557

[crossed out] u — nondiff.

Uncertain reading. The crossed-out Russian entry may begin “об...”. Its end is illegible.

Original source details: GELFAND-P000557

$$u(-1) = -3, \qquad u(1) = 3$$

Let

$$u(-1) = 3, \qquad u(1) = 3 + A$$



Manuscript excerpt. After “Let” the manuscript reads $u(-1) = 3$.

Original source details: GELFAND-P000557

$$\frac{u'}{\sqrt{1+u'^2}} = (1+x^{4/3})^{-1/2}$$

$$u' \le x^{-2/3}$$

$$u(x) \le -3 + \int_{-1}^{x} t^{-2/3}\,dt = 3x^{1/3}$$

_____ · _____

$$\mathcal{F}(u) = \int_\Omega \sqrt{1+|Du|^2}\,dx + \int_\Omega \lambda(x,u)\,dx$$

Need to find min.

$$\lambda(x,t) = \int_0^t H(x,s)\,ds$$

Under the cond. $|u'| \le K$ there is a min. (otherwise none).

u_k — soln. Let $k \to +\infty$. $\quad u_k \to u_0$? _____ · _____

u — Lip-contin. solut. $\quad A \subset \Omega$

$$\int_A H(x)\,dx = \int_{\partial A} n_i \frac{D_i u}{\sqrt{1+|Du|^2}}\,dH_{n-1}$$

$$\left|\int_A H(x)\,dx\right| \le (1-\varepsilon_0) H_{n-1}(\partial A)$$

$$\boxed{1-\varepsilon_0 = \sup_\Omega \frac{|Du|}{\sqrt{1+|Du|^2}}.}$$

Therefore H is not very large. _____ · _____

GELFAND-P000558

① $H^{1,1} = W_1^1$ ‖

$$\mathcal{F}(u) = \int_\Omega \sqrt{1+|Du|^2}\,dx + \int_\Omega \lambda(x,u)\,dx + \int_{\partial\Omega} |u-\phi|\,dH_{n-1}$$

$BV(\Omega) = L^1$ funcs., whose first derivs. are measures (Radon).

$$\text{i.e.} \quad f \in BV \iff f \in L^1,$$
$$\sup\left\{\int_\Omega f \operatorname{div}\vec{g}\,dx, \quad \vec{g} \in C_0^1(\Omega),\ |g| \le 1\right\} < +\infty$$

$$\sup = \int_\Omega |Df|\,dx$$



Uncertain reading. Two separate strokes stand above Df. The crossed-out mark to their left is illegible.

Original source details: GELFAND-P000558

Area $f \in BV$.

$$\mathcal{A}(f) = \int \sqrt{1+|Df|^2}\,dx \underset{\text{def}}{=}$$
$$\sup\left\{\int_\Omega (g_0 + f \operatorname{div}\vec{g})\,dx, \quad g_0, g \in C_0^1, \quad g_0^2 + |g|^2 \le 1\right\}.$$



Uncertain reading. The left stroke at g merges with the letter. The reading $|g|^2$ is provisional.

Original source details: GELFAND-P000558

area.

$(\mathcal{A}f)$ lower semicont. with respect to L^1 ~~cont...y~~.

Uncertain reading. The crossed-out English word provisionally reads “cont...y”. The full word remains unresolved.

Original source details: GELFAND-P000558

② Bounded sets in BV are relatively compact in L_1

. . . . . .

Dubrovin.

$$L = -\frac{d^2}{dx^2} + u(x), \qquad u(x+T) = u(x)$$

E — spectral parameter.



Diagram and typed description.



A small unfilled loop stands below E_1. Its meaning remains unresolved.

Original source details: GELFAND-P000558

Sometimes the gaps disappear.

Let $u(x)$ — a finite-gap potential

Let $R(E) = \prod(E - E_i)$

Consid. the Riem. surface of the func. $\sqrt{R(E)}$ — denote by Γ_N.

Bloch eigenfuncs. continue analyt. to $\Gamma_N \setminus \infty$ [crossed out]



Undeciphered passage. The parenthetical entry at the right is densely crossed out and illegible.

Original source details: GELFAND-P000558

(meromorphically)

N — genus.

and has N poles and N zeros

Bloch eigenfunc.: $\Psi(x, E, x_0)$

Poles $\gamma_i(x_0)$. || there is a natural proj.

$$\Gamma_N \longrightarrow \mathbb{C}_E.$$

2-sheeted covering



Diagram and typed description.



Original source details: GELFAND-P000558

An oval projects to a gap: on each of them lies one pole. The loc. of the poles depends on the normalization: x_0.

~~On one sheet [...], and on the other [...]~~

Uncertain reading. The crossed-out line provisionally begins “On one sheet”.

Original source details: GELFAND-P000558



Original source details: GELFAND-P000558

Undeciphered passage. There are isolated strokes after “sheet”. The next legible words provisionally read “and on the other”. The full reading remains unresolved.

On each oval also one zero. _____ · _____

Next time 18^{30}

GELFAND-P000559

16.9.74. Gelfand Sem. Dubrovin.

Uncertain reading. The second digit of the date has been written over with a heavy loop. The current reading “6” is provisional. The earlier mark is illegible.

Original source details: GELFAND-P000559

$$\text{Let} \quad L = -\frac{d^2}{dx^2} + u(x), \qquad u(x+T) = u(x).$$

The spectrum L — a set of intervals. If there are finitely many of them, it is [inserted above: called] finite-gap.



Uncertain reading. A letter at the end of the Russian word is heavily crossed out. The insertion above provisionally reads “й”. The earlier ending is illegible.

Original source details: GELFAND-P000559

The spectrum — those λ for which there is a bounded soln. of the eq. $Ly = \lambda y$.

$$y_1(x+T) = \alpha_{11} y_1(x) + \alpha_{12} y_2(x)$$
$$y_2(x+T) = \alpha_{21} y_1(x) + \alpha_{22} y_2(x).$$

The matrix $(\alpha_{ij}) = \widehat{T}$ (of monodromy).

We need $\widehat{T}^n y$ to be bounded, i.e. $\exists$ an eigenvalue with $|\lambda| = 1$

but: $\det \widehat{T} = 1$ (Wronskian); $\lambda_1 \lambda_2 = 1$.

$$\lambda^2 - (Sp\,\widehat{T})\lambda + 1 = 0$$

GELFAND-P000560

~~Roots~~



Original source details: GELFAND-P000560

Uncertain reading. The crossed-out word provisionally reads “Roots”. Crossing strokes obscure some letters.

$$|\alpha_{11} + \alpha_{22}| < 2 \quad \Rightarrow \quad \text{complex roots.}$$
$$|\alpha_{11} + \alpha_{22}| > 2 \quad \Rightarrow \quad \text{real roots.}$$

The roots run in one direction (can be proved).

Phys. interpret.: if there is a bounded eigenfunc., the particle will pass through, if not, it will ~~not~~ get trapped

Original source details: GELFAND-P000560

Uncertain reading. The short crossed-out word before the boxed word provisionally reads “not”.



Original source details: GELFAND-P000560

Diagram and typed description.



exp decrease forb. zones. (resonance of particle and field)

Original source details: GELFAND-P000560

Uncertain reading. At the start of the Russian word for “decrease”, there is a high stroke above overwritten marks. The earlier spelling is illegible.

Ince, Akhiezer, Hochstadt.

$$\text{Bloch func.} - \boxed{u(x+T) = \nu u(x)}, \qquad |\nu| = 1. \quad (\text{eigenvector } \widehat{T}).$$

$$\nu = e^{ip}, \qquad p \text{ — “quasimomentum”.}$$

Bounded eigenfuncs. — if $p \in \mathbb{R}$.



Diagram and typed description.



Original source details: GELFAND-P000560

$$\Gamma_N \text{ — Riemann surface of } \sqrt{R(E)}, \qquad \text{where} \quad R(E) = \prod_1^{2N+1} (E - E_i)$$

G. Let $y(x, E)$ — Bloch func. for complex E.

$$y(x+T) = \nu y(x)$$

$y(x_0, x, E)$ normalization: $y(x_0, x_0, E) = 1$.



Diagram and typed description.



Two short diverging strokes are visible where the loop meets the segment. The mark provisionally points upward.

Original source details: GELFAND-P000560

D. Th. 1. Bloch eigenfuncs. continue analyt. to Γ_N.

Th. 0. Any finite-gap pot. — a stat. soln. of a higher KdV eq..

Th. 2 The set of pots. with a given spectrum is $J(\Gamma_N)$ — the Jacobi manifold.



Uncertain reading. In the Russian abbreviation for “set”, the letter after the hyphen was written over. The earlier strokes are illegible.

Original source details: GELFAND-P000560

KdV (dyn. syst.) and its higher analogues act there.
On solns. $Ly = Ey$ acts $(\widehat{T}y)(x) = y(x+T)$

$$\begin{matrix} c=1, & c'=0 \\ s=0, & s'=1 \end{matrix} \quad \text{(at pt. } x_0) \qquad c(x, x_0, E)$$

In this basis the monodromy matr. $\alpha_{ij}(E, x_0)$.
Everything is det. by the matr. trace $\tau = \frac{1}{2} Sp\, \alpha_{ij}$

$$|\tau| \le 1 \quad \Rightarrow \quad \text{spectral bands}$$

Uncertain reading. The ending of the Russian word for "bands" is overwritten. The earlier strokes are illegible.

Original source details: GELFAND-P000560

τ is indep. of x_0, $\qquad \tau = \tau(E)$.

$$\lambda^2 - 2\tau\lambda + 1 = 0$$



Diagram and typed description.



Original source details: GELFAND-P000560

it is known that the graph looks like this — max and $min \gtrless 1$ — prob.

Uncertain reading. The sign before 1 consists of an upper stroke and two oblique strokes. The provisional reading is $\gtrless$.

Original source details: GELFAND-P000560

GELFAND-P000561

for the 2^* year There are always infinitely many of them (max and min).

Uncertain reading. A small crossed mark follows "2". The visible shape is retained. The ending remains unresolved.

Original source details: GELFAND-P000561

merger of 2 forb. zones — there is no allowed zone



Diagram and typed description.

Original source details: GELFAND-P000561

From the eq. $\tau(E) = \pm 1$ one must select the simple roots to det. the band edges.
The band edges give a Jordan block. If diagonal, we get the degenerate case.
See the work of Gelfand and Lidskii (1955) on systems with periodic coeffs..
Def. $\Psi(x, x_0, E), \qquad \Psi(x+T) = e^{ip}\Psi(x), \qquad \Psi(x_0) = 1.$
The other is complex conjugate (when $|\tau(E)| < 1$).

$$\text{Let} \qquad \chi = -i\frac{\Psi'}{\Psi}$$

1. $\chi = \chi(x, E)$ (indep. of x_0).

Uncertain reading. A detached ", and" stands to the right between the first and second items. Its attachment remains unclear.

Original source details: GELFAND-P000561

2. $-i\chi' + \chi^2 + u - E = 0$ (Riccati eq.).

3. $\chi_I = \frac{1}{2}\frac{\chi_R'}{\chi_R}, \qquad \chi = \chi_R + i\chi_I.$

4. $\chi(x, E) \sim k + \sum_{n=1}^{\infty} \frac{\chi_n(x)}{(2k)^n}, \qquad$ where $k = \sqrt{E}$

Uncertain reading. A wavy stroke lies over earlier strokes before k. The reading $\sim$ is provisional.

Original source details: GELFAND-P000561

5. $\chi(x+T)=\chi(x)$. (asympt. expansion).

$$2 \Rightarrow 3, \qquad 2 \Rightarrow 4$$



Undeciphered passage. A group of signs after $2 \Rightarrow 4$ is heavily crossed out. The surviving strokes are insufficient to read it.

Original source details: GELFAND-P000561

Uncertain reading. A short group is crossed out before χ_R. It provisionally reads χ with a subscript, possibly R.

Original source details: GELFAND-P000561

$$\chi_R(x,E) = k + \sum_{n=0}^{\infty} \frac{\chi_{2n+1}(x)}{(2k)^{2n+1}}$$

$$\Psi = \exp\left(i\int_{x_0}^{x} \chi\, dx\right) = \sqrt{\frac{\chi_R(x_0)}{\chi_R(x)}}\exp\left(i\int_{x_0}^{x} \chi_R\, dx\right).$$

1. $|\Psi|^2 = \dfrac{\chi_R(x_0)}{\chi_R(x)}$

2. $p(E) = \displaystyle\int_0^T \chi_R(x,E)\, dx + \pi n$

Uncertain reading. A heavy slanted mark precedes πn. A separate factor remains unresolved.

Original source details: GELFAND-P000561

Express χ in terms of the monodromy matr.

~~Th.~~ Lemma



Uncertain reading. The underlined “Th.” is crossed out. “Lemma” is inserted above and to its right.

Original source details: GELFAND-P000561

$$\chi(x,E) = \frac{\sqrt{1-\tau^2(E)}}{\alpha_{21}(E,x)} + \frac{i}{2}\frac{\alpha_{11}(E,x)\alpha_{22}(E,x)}{\alpha_{21}(E,x)} \tag{1}$$



Uncertain reading. A separate sign is indistinguishable between $\alpha_{11}(E,x)$ and $\alpha_{22}(E,x)$. The groups are typeset side by side.

Original source details: GELFAND-P000561

Proof. $\Psi(x, x_0, E)$ — an eigenvector of the monodr. matr. Use the rules of lin. algebra:

$$\Psi(x, x_0, E) = c(x, x_0, E) + i \begin{pmatrix} \text{right-hand side of} \\ \text{formula (1) at pt. } x_0 \end{pmatrix} s(x, x_0, E).$$

GELFAND-P000562

Find the Wronskian det. of this func. and c (it is indep. of x).

$$\{c, \Psi(x, x_0, E)\}|_{x_0} = \quad \text{everything works out.}$$
$$i\chi(x_0, E) = i(\ldots)$$
$$\{c, \Psi\}|_{x_0} = i\Psi'(x_0) = i\chi(x_0).$$

Original source details: GELFAND-P000562

Uncertain reading. An overwritten mark with a prime follows i. The current reading Ψ' is provisional.



Original source details: GELFAND-P000562

Diagram and typed description.



If $(1 - \tau(E))$ has a multiple zero, then the monodromy matr. is diagonal, i.e.

Original source details: GELFAND-P000562

Uncertain reading. A short mark resembling "π" is crossed out before the equalities. Its reading remains unresolved.

$$\alpha_{12}(\widetilde{E}, x_0) = 0, \qquad \alpha_{21}(\widetilde{E}, x_0) = 0.$$

$\dfrac{1 - \tau^2(E)}{R(E)}$ has only double degen. zeros.



Original source details: GELFAND-P000562

Uncertain reading. An oblique stroke and an upper line are heavily crossed out to the left of and above the fraction. They may be a deleted radical sign.

$\sqrt{\dfrac{1-\tau^2(E)}{R(E)}}$ has only simple zeros. (see Titchmarsh)

$\alpha_{21}(\widetilde{E}, x_0) = 0$ too

$$\alpha_{21} = \widetilde{\alpha}_{21} \cdot \sqrt{\frac{1-\tau^2(E)}{R(E)}} \qquad \text{(divided)}.$$

Substitute into the formula for χ_R:

$$\chi_R = \frac{\sqrt{R(E)}}{\widetilde{\alpha}_{21}(E,x)}, \qquad \text{where } \widetilde{\alpha}_{21}(E,x) \text{ — an entire anal. func. of } E.$$

$$\chi_R = k + O\left(\frac{1}{k}\right), \qquad \sqrt{R(E)} \sim E^N \quad \text{at infinity.}$$



Original source details: GELFAND-P000562

Uncertain reading. The visible exponent in this line is N. The numerator in the next line is kE^N.

$$\chi_R(x,E) \sim \frac{kE^N}{E^N} \quad \Rightarrow \quad \widetilde{\alpha}_{21}(E,x) \text{ — a polynomial in } E.$$

$P(E,x)$

$\chi_R(x,E)$ — 2-valued analyt. func. (analyt. continuation from real E in a band)

$$\chi_R(x,E) = \frac{\sqrt{R(E)}}{P(E,x)}$$

$$P(E,x) = \prod (E - \gamma_i(x)), \qquad \gamma_i(x) \text{ — roots of the polynomial}$$

Hence : $\boxed{\chi(x,E) = \left(\sqrt{R} - \frac{i}{2}\frac{d}{dx}P\right)/P.}$

$$\chi_R \sim k + \sum \frac{\chi_{2n+1}(x)}{(2k)^{2n+1}}$$

Uncertain reading. The letter n in the subscript $2n+1$ has been written over. The earlier strokes are illegible.

Original source details: GELFAND-P000562

Construct the functionals

$$I_n\{u\} = \int_0^T \chi_{2n+3}(x)\,dx$$

GELFAND-P000563

$$\underbrace{-i\chi' + \chi^2 + u - E = 0} \quad \Rightarrow \quad \text{asymptotics.}$$

and in this case $\chi_{2n+1} = Q(u, u', \ldots, u^{(n-1)})$ — a polynomial.



Uncertain reading. The order above the last u provisionally reads $(n-1)$.

Original source details: GELFAND-P000563

Uncertain reading. A group with vertical strokes and a loop is crossed out at the left. The visible sign resembles "δ" or "$\int$". The earlier writing remains unresolved.

Original source details: GELFAND-P000563

~~This [...]~~



Uncertain reading. The beginning of the crossed-out line provisionally reads "This".

Original source details: GELFAND-P000563



Undeciphered passage. The remaining words in the crossed-out line are illegible.

Original source details: GELFAND-P000563

$$\frac{\delta}{\delta u}\left\{\sum c_n I_n\right\} = d \quad (= const).$$

. . . . . .

GELFAND-P000564

23/IX – 74 Gelfand Sem.

On the work of Gabrielov, I. Gelfand and Losik on combinatorial topology.

It is interesting to do it analytically. ~~$\int$ [...]~~

Uncertain reading. A mark with two loops begins the crossed-out group. It provisionally reads $\int$.

Original source details: GELFAND-P000564

Undeciphered passage. Oblique strokes obscure the remaining marks. They are illegible.

Original source details: GELFAND-P000564

$$\int_{1-x}^{x} \left[\frac{\log|t|}{1-t} + \frac{\log|1-t|}{t} \right] dt$$

cannot be evaluated in elem. funcs.. But:

$$\int_0^1 \frac{\log|1-t|}{t}\, dt = \frac{\pi^2}{6} \quad \left(= \int_0^1 \sum_{n=1}^{\infty} \frac{t^{n-1}}{n} = \sum_{n=1}^{\infty} \frac{1}{n^2} \right).$$



Uncertain reading. There is no minus sign before $\pi^2/6$. The middle term has no written differential.

Original source details: GELFAND-P000564

One can evaluate

$$\int_{2-\sqrt{5}}^{\sqrt{5}-2} \left[\frac{\log|t|}{1-t} + \frac{\log|1-t|}{t} \right] dt = -\frac{\pi^2}{6}$$



Original source details: GELFAND-P000564

Uncertain reading. This line shows a minus sign before $\pi^2/6$. The limits read $2-\sqrt{5}$ and $\sqrt{5}-2$.

(from topological considerations).



Uncertain reading. Both Russian words contain overwritten letters. The earlier strokes are illegible.

Original source details: GELFAND-P000564

They occur in a finite combinatorial problem.

Graeme Segal — all of topology.

Giusti. On singularities. (On regularity of ~~[...]~~ solv. of nonlin. syst.).



Uncertain reading. The name in the Russian handwriting provisionally reads “Джусти”. The middle strokes run together.

Original source details: GELFAND-P000564

Undeciphered passage. A short entry before “solv.” in the English parenthesis is heavily crossed out and illegible.

Original source details: GELFAND-P000564

Symplest case:

$$\sum_{i,j=1}^{n}\sum_{h,k=1}^{N}\int a_{ij}^{hk}(x,u)D_iu^hD_j\varphi^k\,dx=0$$



Uncertain reading. There are overwritten marks in the argument (x,u) and before the superscript k. The current readings u and φ are provisional.

Original source details: GELFAND-P000564

$$D_i=\frac{\partial}{\partial x},\qquad \forall\varphi=(\varphi^1,\dots,\varphi^N),\qquad \varphi_i\in W_0^{1,2}(\Omega)$$



Uncertain reading. There is a heavy subscript mark below φ^1. It may be 2, i or z. Its reading remains unresolved.

Original source details: GELFAND-P000564

$$\sum_{i,j=1}^{n}\sum_{h=1}^{N}D_j\big(a_{ij}^{hk}(x,u)D_iu^k\big)=0\qquad(k=1,2,\dots,N)$$



Original source details: GELFAND-P000564

Uncertain reading. The written denominator of D_i is ∂x. In the sum over h the visible superscript of u is k.

$$u = (u^1, \dots, u^N).$$

Ellipticity:

$$\sum_{ijhk} a_{ij}^{hk}(x,t)\xi_i^h \xi_j^k \geqslant |\xi|^2, \qquad \forall x \in \Omega,\ \forall t \in \mathbb{R}^n$$



Original source details: GELFAND-P000564

Uncertain reading. The first subscript on ξ provisionally reads i. The final dimension reads n.

GELFAND-P000565

$$\sum_{i,j=1}^{n} D_j\big(A_{ij}(x,u)D_i u\big) = 0, \qquad \begin{matrix} u \text{ — a vector} \\ A_{ij} \text{ — a matrix.} \end{matrix}$$

$N = 1 \Rightarrow \forall$ solution is regular

or $n \leqslant 2$ $\quad \forall u \in W^{1,1}$ is regular (depende on reg. of A-coefficients)

Uncertain reading. The sign between n and 2 has been written over. The current reading $\leqslant$ is provisional.

Original source details: GELFAND-P000565

Uncertain reading. The mark before "coefficients" has been written over. It provisionally reads "A". The earlier strokes are illegible.

Original source details: GELFAND-P000565

$$A \in C^\infty \quad \Rightarrow \quad u \in C^\infty \quad \text{etc.}$$

$$W^{1,2}, \qquad u \in L_2, \qquad \int_\Omega |Du|^2\, dx < +\infty$$

$W_0^{1,2}$ — 0 boundary values.



Uncertain reading. The "d" in "boundary" has been written over. Above the word, Ω is below the integral in the previous line.

Original source details: GELFAND-P000565

$n = N \geqslant 3$ falls.

Uncertain reading. The digit “3” has been written over. The earlier strokes beneath it remain unresolved.

Original source details: GELFAND-P000565

Uncertain reading. The English word has two tall loops with no dot over the first. It is transcribed as “falls”.

Original source details: GELFAND-P000565

$$a_{ij}^{hk} = \delta_{ij}\delta_{hk} + \left(\delta_{jk} + \frac{1}{n-2}\frac{u_j u_k}{1+|u|^2}\right)\left(\delta_{ih} + \frac{4}{n-2}\frac{u_i u_h}{1+|u|^2}\right)$$



Original source details: GELFAND-P000565

Uncertain reading. The written factors preceding the fractions are $1/(n-2)$ and $4/(n-2)$, in that order.

$u_i = x_i/|x|$ — solution. coefficients are real analityc



Uncertain reading. The original English spelling “analityc” is retained.

Original source details: GELFAND-P000565

$n = 2$ $\forall$ sol. is regular

$n = 3,\ N = 2$ — there is an example of non regular solution.

For Dirichlet problem. $u_i = x_i$ when $|x| = 1$. $\exists!$ solution and it is not regular!

Suppose a_{ij}^{hk} are continuous

Then (1) $\forall$ solution u of system is regular in an open set $\Omega_0 \subset \Omega$

Uncertain reading. An entry in parentheses is crossed out before “(2)”. The earlier number is illegible.

Original source details: GELFAND-P000565

(2). $K = \Omega - \Omega_0$ (K is closed in Ω) ~~a[...]~~

$$\Rightarrow \underset{H_{n-2}}{\text{meas}} K = 0$$

Uncertain reading. An initial “a” is visible in the crossed-out English word. The remaining letters are unresolved.

Original source details: GELFAND-P000565

$$\underline{\dim K < n - 2.}$$

Uncertain reading. The lower stroke of the sign in the dim K line is thickened. The visible outline is transcribed as $<$.

Original source details: GELFAND-P000565

(for order $m > 2$ $\quad$ $\dim K \leqslant n - 2$).

~~There~~ Are ~~also~~ [inserted above] there variational problems with nonregular solutions?

Uncertain reading. The crossed-out words before and after “Are” provisionally read “There” and “also”. The inserted “there” is enclosed above the line.

Original source details: GELFAND-P000565

Problem of Gelfand. Devise an analogue of Hironaka’s resol. of sing. for elliptic eqs..

GELFAND-P000566

I. M. Gelfand recap of Dubrovin’s previous talk.



Diagram and typed description.

There is a small detached slanted stroke above the left end.

Original source details: GELFAND-P000566

$$-y'' + u(x)y = Ey$$
$$u(x + T) = u(y)$$

Uncertain reading. The right-hand side clearly reads $u(y)$.

Original source details: GELFAND-P000566

The spectrum — those E, for which there are bounded eigenfuncs.



Original source details: GELFAND-P000566

Uncertain reading. Both letters E are written over with heavy strokes. The earlier signs remain unresolved.

Novikov's problem: when are there finitely many forbidden zones?



Original source details: GELFAND-P000566

Diagram and typed description.



Th. Novik.–Dubrov.



Original source details: GELFAND-P000566

Uncertain reading. A heavy stroke is written over the end of the abbreviated name "Dubrov." The earlier letter remains unresolved.

These are the potentials $\Leftrightarrow$ satisf. the nonlin. eq.

$$K(u, u', \dots, u^{(2N)}) = 0$$

(Higher Korteweg–de Vries eq.)

$$\begin{aligned} c(x, x_0, E): &\qquad c(x_0) = 1, \quad c'(x_0) = 0 \\ s(x, x_0, E): &\qquad s(x_0) = 0, \quad s'(x_0) = 1. \end{aligned}$$

These are analyt. funcs. of the parameter E.

$$\widehat{T}\Psi = \Psi(x+T), \qquad \widehat{T} = \begin{pmatrix} \alpha_{11} & \alpha_{12} \\ \alpha_{21} & \alpha_{22} \end{pmatrix} \qquad \det \|\widehat{T}\| = 1.$$

Bloch func.: $\Psi(x+T) = \lambda\Psi(x)$, $\qquad \Psi(x_0) = 1$

This is an eigenvector for $\widehat{T}$.

$$\lambda^2 - (\alpha_{11} + \alpha_{22})\lambda + 1 = 0,$$

$$\lambda^2 - 2\tau\lambda + 1 = 0, \qquad \tau(E) = \frac{\alpha_{11} + \alpha_{22}}{2}.$$

$E \in$ an allowed interv. $\Leftrightarrow \exists$ a Bloch func. with $|\lambda| = 1$.

$\tau^2 \leqslant 1$ — allowed int., $\tau^2 > 1$ — forbidden



Original source details: GELFAND-P000566

Diagram and typed description.



all $max \geqslant 1$ (this shape).

Correct fig.:



Original source details: GELFAND-P000566

Diagram and typed description.



The forb. zones shrink.

Important conclusion: if all the zones have merged, then, max and min are equal from some point on to 1.

They cannot, since the problem with periodic conds. has infinite spectrum (there $\tau = 1$).



Original source details: GELFAND-P000566

Diagram and typed description.



(stand. perturbation theory for ordinary eqs.).

$$\tau^2(E) = 1 \quad \text{has a mult. root} \quad \Rightarrow \quad \alpha_{12} = \alpha_{21} = 0.$$

Uncertain reading. The first digit of the subscript on α_{12} has been written over. The visible reading is 1.

Original source details: GELFAND-P000566

$\alpha_{12}(E)$ and $\alpha_{21}(E)$ have a zero at the same points where $\tau^2(E) - 1$ has multiple zeros.
Consid. the Bloch func. $\Psi(x, x_0, E)$: $\Psi(x, x_0, E)$, $\Psi(x_0) = 1$.
there are 2 Bloch funcs. $\forall E$ (since the eq. is quadr. in λ).
it depends analyt. on E (two-valued).



Diagram and typed description.

Original source details: GELFAND-P000566

$\tau^2(E) - 1$ has a zero at $E_1, \ldots, E_{2N+1}$. The rest are double.

GELFAND-P000567

$$\sqrt{\frac{\tau^2(E) - 1}{(E - E_1) \cdots (E - E_{2N+1})}} \quad \text{— single-valued func.}$$



Uncertain reading. The top stroke of the radical ends over the numerator. The bottom of the radical descends to the denominator. Its scope remains ambiguous.

Original source details: GELFAND-P000567

Consid. the eq.

$$-\Psi'' + u(x)\Psi = E\Psi, \qquad \Psi(x+T) = \lambda\Psi(x)$$
$$u(x+T) = u(x)$$

Let $\chi = -i\,\Psi'/\Psi$.

1°. χ does not depend on x_0, $\quad \chi = \chi(x, E)$.

2°. $\chi(x+T) = \chi(x)$.

3°. $\quad -i\chi' + \chi^2 + u - E = 0$.

$\chi = \chi_R + i\chi_I$ in an allowed band — then analyt. continuation in E.

$$4^\circ. \quad \chi_I = \frac{1}{2}\,\chi_R'/\chi_R.$$

$$5^\circ. \quad \chi(x, E) \sim k + \sum_{n=1}^{\infty} \frac{\chi_n(x)}{(2k)^n}, \qquad E = k^2$$
$$\chi_n = P_n(u, u', \ldots, u^{(n)}) \text{ — a polynomial}$$

(det. successively from the asympt. equality)

$$4^\circ \Rightarrow 6^\circ. \quad \chi_R(x, E) \sim k + \sum_{n=0}^{\infty} \frac{\chi_{2n+1}(x)}{(2k)^{2n+1}}$$

$$7^\circ. \quad \Psi(x, x_0, E) = \sqrt{\frac{\chi_R(x_0, E)}{\chi_R(x, E)}} \cdot \exp\left[i \int_{x_0}^{x} \chi_R(t, E)\, dt\right].$$



Uncertain reading. The subscript of χ_R in the numerator has been written over. In the exponent, t, E and the final t of dt have been written over. The earlier strokes remain unresolved.

Original source details: GELFAND-P000567

$$7^\circ \Rightarrow 8^\circ. \quad |\Psi|^2 = \chi_R(x_0, E)/\chi_R(x, E) \qquad \underline{\text{in an allowed band}}$$

9°. ~~[...]~~

Uncertain reading. An entry before λ is heavily crossed out. Some strokes resemble an equals sign and $p(E)$. The exact reading remains unresolved.

Original source details: GELFAND-P000567

$$\lambda = e^{ip(E)} \quad \Rightarrow \quad p(E) = \int_{x_0}^{x_0+T} \chi_R(x,E)\,dx + 2\pi n.$$

The integral — a functional of u with an asympt. expansion. Its Euler eq. — KdV eqs., Allowed and forb. zones — where $|\lambda| = 1$

Uncertain reading. An earlier number with a superscript circle is crossed out to the left of "10°". A vertical stroke and a loop are visible. The exact digits remain unresolved.

Original source details: GELFAND-P000567

$$10^\circ. \quad \frac{\delta p(E)}{\delta u(x)} = -\frac{1}{2}\frac{1}{\chi_R(x,E)}$$

(left-hand side of the Euler eq. for KdV).

$$11^\circ. \quad \chi(x,E) = \frac{\sqrt{1-\tau^2(E)}}{\alpha_{21}(x,E)} + \frac{i}{2}\frac{\alpha_{11}(x,E)-\alpha_{22}(x,E)}{\alpha_{21}(x,E)}$$

Rough idea: eigenvalue obtained from the quadr. eq.

$$12^\circ. \quad \text{Let} \quad R(E) = \prod_1^{2N+1}(E-E_j). \qquad \text{Then}$$

$$\chi(x,E) = \frac{\sqrt{R(E)}}{P(E,x)} - \frac{i}{2}\frac{P'_x}{P},$$

where P — a polynomial in E of degree N.



Uncertain reading. A heavy stroke follows P'_x in the numerator. It resembles an opening parenthesis. Its meaning remains unresolved.

Original source details: GELFAND-P000567

GELFAND-P000568

$$P(E,x)=\prod_{j=1}^{N}(E-\gamma_j(x)).$$

G.'s problem. Let R and P — entire funcs. of the 1st order of growth. Then corresponding to them are potentials $u(x)$. Which ones?

class of potentials (not necessarily periodic). ____ · ____

Dubrovin.

Γ_N — Riem. surf. of $\sqrt{R(E)}$, $\chi(x,E)$ — an algebr. func. on this surface

Theorem: $\Psi(x,x_0,E)$ a single-valued func. on Γ_N, merom. on $\Gamma_N\setminus\infty$, has N zeros and N poles.



Uncertain reading. A comma follows the first x. A small mark is heavily crossed out above it. The earlier reading remains unresolved.

Original source details: GELFAND-P000568

Poles at $E=\gamma_i(x_0)$, zeros above $E=\gamma_i(x)$.

GELFAND-P000569

30/IX – 74. Gelfand Sem.

Polyakov. On elementary particles. Yang–Mills fields. (difference analogue).

Graeme Segal. A work of Dusa Mc Duff on config. space.

$$\mathbb{R}^n,\qquad C_k(\mathbb{R}^n)=\{\text{subsets of }\mathbb{R}^n\text{ with }k\text{ points (no ordered)}\}.$$

From a top. point of view it is not quite trivial.



Diagram and typed description.



Original source details: GELFAND-P000569

~~[...] f_S~~

Undeciphered passage. The left part of the crossed-out entry is illegible.

Original source details: GELFAND-P000569

Original source details: GELFAND-P000569

Uncertain reading. The end of the crossed-out entry provisionally reads f_S.

constr. a map $f_S : \mathbb{R}^n \longrightarrow \mathbb{R}^n \cup \infty$

$S \subset \mathbb{R}^n$ from it

finite.

Original source details: GELFAND-P000569

Uncertain reading. The abbreviation before "map" reads "стр." An arrow points up to it.



Original source details: GELFAND-P000569

Uncertain reading. The end of the word merges with the arrow. It provisionally reads "from it", possibly "after the German".

E — field strength (electr.), produced by unit charges at points $x \in S$. We get a vector $E \in \mathbb{R}^n \cup \infty$



Original source details: GELFAND-P000569

Diagram and typed description.



At the points $x \in S$ it will be ∞. $\infty \longrightarrow 0$

$$f_S : \mathbb{R}^n \cup \infty \longrightarrow \mathbb{R}^n \cup \infty$$

We get a map

$$C_k(\mathbb{R}^n) \longrightarrow \mathrm{Map}_k(S^n, S^n). \qquad (\text{map of degree } k).$$

(When far away, all k points are perceived as one).



Original source details: GELFAND-P000569

Uncertain reading. The k and the end of the Russian word for "points" are written over. The earlier strokes are illegible.

A point corresp. to a long vector — near one of the k charges
— and there are such points.

Uncertain reading. A letter in the middle of the Russian word for “such” is heavily overwritten. The earlier strokes are illegible.

Original source details: GELFAND-P000569

$C_k(\mathbb{R}^n)$ — a good approx. of $\mathrm{Map}_k(S^n, S^n)$!! (in a certain sense)
A good approx. for large k.

$$H_i(C_k(\mathbb{R}^n)) \underset{\cong}{\longrightarrow} H_i(\mathrm{Map}_k)$$

for $i \ll k$ (there are many proofs, including Segal’s)

Uncertain reading. Below the arrow is a wave over two horizontal strokes, in the form $\cong$.

Original source details: GELFAND-P000569

Inventiones

Uncertain reading. The underlined word reads “Inventiones”. The final letters are joined.

Original source details: GELFAND-P000569

GELFAND-P000570

A generalization of this thm. will be described (due to ~~[...]~~ Dusa Mc Duff)



Undeciphered passage. A short entry before the name “Dusa Mc Duff” is crossed out and illegible.

Original source details: GELFAND-P000570

Fuchs. $C_k(\mathbb{R}^n)$ gives various classifying spaces.

Uncertain reading. The initial letter of “Fuchs” is written over with a heavy stroke. The earlier strokes remain unresolved.

Original source details: GELFAND-P000570

2 kinds of questions arise:

The right side is indep. of k ($\approx$), on the left pass to the limit in k.

Original source details: GELFAND-P000570

Uncertain reading. The middle of the Russian word for “limit” is written over. The earlier strokes are illegible.

(homot. eq.)

$C_k^{\pm}(\mathbb{R}^n)$ finite subsets with charges of diff. signs

topology — if 2 oppositely charged particles approach, they disappear.

Many components (total charge), $-\infty < k < +\infty$

Does not depend strongly on k.

$$C_k^{\pm}(\mathbb{R}^n) \underset{2}{\simeq} \mathrm{Map}_k(S^n, S^n)$$



Original source details: GELFAND-P000570

Uncertain reading. A separate mark in the shape of 2 is below $\simeq$. Its meaning remains unresolved.

a very good approx. (hypothesis). or

Original source details: GELFAND-P000570

Uncertain reading. Heavy crossing strokes follow “hypothesis”. The provisional reading is “or”.

There is a space Y_n, $\dim Y_n = 2n$,

$$C_k^{\pm}(\mathbb{R}^n) \simeq \mathrm{Map}_k(S^n, Y_n).$$

Original source details: GELFAND-P000570

Uncertain reading. The upper stroke of the relation is written over. The visible wave over a line is transcribed as $\simeq$.



Original source details: GELFAND-P000570

Uncertain reading. The Y in the final Y_n is written over. The earlier strokes are illegible.

$C_k(M)$ M — a manifold

What in place of Map(S^n, S^n)?

$$C_k(M) \longrightarrow \Gamma(T_M^{\text{comp}}),$$

∞ is added in each fibre. (all fibres compactified).

At [...] infinity one can take 0 (with comp. supp.)

Uncertain reading. A small loop-shaped mark is crossed out before “infinity”. Its reading remains unresolved.

Original source details: GELFAND-P000570

$$C_k(M) \longrightarrow \Gamma_k^{\text{cpt}}(T_M^{\text{comp}})$$

induces a homol. isom. for $i \ll k$.

(The electr. field is taken to have finite range — then everything is constr.)

The proof method is of greater interest than the assertion.

$U \subset M$ a small piece of M. $C_k(U)$ [...] $C_k(M)$.

Uncertain reading. A sign between $C_k(U)$ and $C_k(M)$ is heavily crossed out. Its reading remains unresolved.

Original source details: GELFAND-P000570

We would like to obtain $C_k(M)$, by joining $C_k(U)$.



Diagram and typed description.



Original source details: GELFAND-P000570

$$C(M) \underset{\text{discontinuous}}{\longrightarrow} C(U) \times C(V)$$

Uncertain reading. “Discontinuous” is written below the formula and above the next line.

Original source details: GELFAND-P000570

Let U, V — manifolds with boundary.

$\overline{C}(U)$ — the quotient space of $C(U)$

$$S_1 \sim S_2 \quad \Leftrightarrow \quad S_1 \cap \overset{\circ}{U} = S_2 \cap \overset{\circ}{U}$$

(points on the boundary disappear)

Thm. U — a manif. with boundary (nonempty)

$$\Rightarrow \quad \overline{C}(U) \underset{\simeq}{\longrightarrow} \Gamma(TU^{\text{comp}}) \qquad \text{(homotopic equiv.)}.$$

Proof. Case 1. $U =$ the unit disk.

Left side: $C_\varepsilon(U)$ — configurs. with distance $> \varepsilon$. Configurs. of $\leqslant 1$ particles remain.

right side $\quad \text{Map}(U, S^n) \simeq S^n$

Radial stretch. $\longrightarrow S^n$ (pushed out to the boundary)

GELFAND-P000571



Original source details: GELFAND-P000571

Diagram and typed description.





Original source details: GELFAND-P000571

Diagram and typed description.

$$\begin{array}{ccc} \overline{C}(U \cup \dot{V}) & \longrightarrow & \overline{C}(U) \\ \downarrow & & \downarrow \\ \overline{C}(V) & \longrightarrow & \overline{C}(U \cap V) \end{array}$$

A dot stands above V in the upper left. Its meaning remains unresolved. The lower arrow points right.

there are well-defined maps and if 2 points from $\overline{C}(U)$ and $\overline{C}(V)$ det. one in $\overline{C}(U \cap V)$, then ~~this~~ det. a point in $\overline{C}(U \cup V)$.

Uncertain reading. "This" is crossed out after "then".

Original source details: GELFAND-P000571



Diagram and typed description.

$$\begin{array}{ccc} \Gamma(U \cup V) & \longrightarrow & \Gamma(U) \\ \downarrow & & \downarrow \\ \Gamma(V) & \longrightarrow & \Gamma(U \cap V) \end{array}$$

Original source details: GELFAND-P000571

Props. of covering homotopy.

Uncertain reading. The middle Russian abbreviation reads "накр.".

Original source details: GELFAND-P000571

the analogous thm. on $C_k(M)$ is omitted.

Next time: Polyakov or Dubrovin.

GELFAND-P000572

7/X–74. Gelfand Sem.

Kushnirenko. $f(z_1, \dots, z_n) = \sum a_m z^m$

0 — sing. point. (series without const. and linear terms).

Milnor number $\mu(f) =$ multiplicity of the zero sol.

$$\frac{\partial f}{\partial z_1} = 0, \dots, \frac{\partial f}{\partial z_n} = 0.$$

— max number [...] [...] sols.
$\frac{\partial f}{\partial z_i} = \varepsilon_i$
for small ε.



Original source details: GELFAND-P000572

Undeciphered passage. Two groups in the right margin are crossed out after “number” and before “sols.”. Remnants of strokes are visible. The full reading remains unresolved.

Problem: compute $\mu(f)$ from the coeffs. of the Taylor series.

2-dim. case. ($n = 2$)



Original source details: GELFAND-P000572

Diagram and typed description.



The third label is written over. Its shape and the formula below suggest γ. The reading remains provisional. The two small marks above the polygonal line are retained.

conv. polygonal line

$$\nu(f) = 2S - a - b + 1.$$

Theorem: 1) $\mu(f) \geqslant \nu(f)$

2) $\mu(f) = \nu(f)$, if certain nondegeneracy conds. hold

$\beta^2 \neq 4\alpha\gamma$ (α, β, γ — coefficients of the resp. monomials).

(in the gen. case $\neq 0$ discriminant of the left edge.)

↘ on the edge essentially a polynomial of 1 var.

$n = 3$.

$$\nu(f) = 3!V - 2!(S_{12} + S_{13} + S_{23}) + 1!(L_1 + L_2 + L_3) - 1.$$

S_{12} — area obtained on the plane.

Original source details: GELFAND-P000572

Diagram and typed description.



The contours and their spatial relation are schematic in the manuscript.

Original source details: GELFAND-P000572

Uncertain reading. A short detached oblique stroke is visible between the formula for ν and the drawing. Its function is unresolved.

Theorem: 1) $\mu(f) \geqslant \nu(f)$

2) nondegen. cond. $\Rightarrow$ equal-ty.

(holds almost always)

GELFAND-P000573



Original source details: GELFAND-P000573

Diagram and typed description.



The hatched region lies between the upper rays. Heavy and retraced strokes are drawn schematically. The precise directions of the extensions are unresolved.

$$z_i \frac{\partial f_\Delta}{\partial z_i}$$

f_Δ — corresp. to the monomials of the face.

$$\dim_{\mathbb{C}} \mathbb{C}[P(\Delta)] / \left(z_i \frac{\partial f}{\partial z_i} \right) < \infty.$$

nondegen. cond.

Proof: commut. algebra. Use that $\mathbb{C}[P(\Delta)]$ — a Cohen–Macaulay ring (Hochster).

Arnold.

$$\sum_{x,y:\begin{cases} P_n(x,y)=0 \\ Q_n(x,y)=0 \end{cases}}^{n^2} \frac{R_{n-4}(x,y)}{\det \frac{\partial (P_n\, Q)}{\partial (x,y)}} = 0.$$



Original source details: GELFAND-P000573

Uncertain reading. The numerator of the Jacobian shows Q after P_n. No distinct comma is visible, and any index on Q is obscured by the tail and parenthesis. The summation conditions separately show Q_n.

$P_n(x,y)$, $Q_n(x,y)$ — 2 polynomials.

(R — an arb. polynomial of deg. $\leq n-4$)

$\sum$ over all zeros.

Polyakov. Consider $\mathbb{Z}^2$ and a fn. of an oriented edge connecting adjacent vertices.

Source raster detail: GELFAND-P000573

Icon visible in the source raster. A yellow icon with three strokes is visible above the word for “oriented” in the raster. Its text is absent from the image and its origin is unresolved.

Yang–Mills fields.

$$B_{\tau,\alpha}, \quad \tau \in \mathbb{Z}^2, \quad \alpha \text{ — dir.}$$

a fn. with vals. in SU(2) (or another compact gr.).



Original source details: GELFAND-P000573

Diagram and typed description.



The label by the vertical arrow resembles β, but its shape is ambiguous. The horizontal arrow is labelled α.

$$F_{\vec{\tau},\alpha\beta} = \quad \text{circul.} = B_{\tau\alpha} B_{\tau+a_\alpha,\beta} B^{-1}_{\tau+a_\beta,\alpha} B^{-1}_{\tau\beta}.$$

Original source details: GELFAND-P000573

Manuscript excerpt. The top, left, bottom and right arrows point left, down, right and up, respectively.

(field strength of ~~[...]~~ B). $\hookleftarrow$ field



Original source details: GELFAND-P000573

Uncertain reading. The earlier word before B is crossed out, provisionally "of the contour". The inserted word "field" appears below with a connecting stroke.

Energy

$$E = \sum_{\tau,\alpha,\beta} \chi(F_{\tau,\alpha,\beta}) \qquad Z = \int \prod dB_{\tau,\alpha}\, e^{-\frac{1}{T}E[B]}.$$



Original source details: GELFAND-P000573

Uncertain reading. A dense dark patch is visible above F. The underlying sign and its function are unresolved.

χ — trace.

Correl. fns.:

$$\Pi(C) = Z^{-1} \int \prod dB_{\tau\alpha}\, \chi \left[\prod_{(C)} B_{\tau\lambda} \right] e^{-\frac{1}{T}E(B)}.$$

$\alpha, \beta = 1$ or 2

C — contour.

Lattice of size $N \times N$.

The planar prob. is solved exactly.

$$\widetilde{E} = \sum_{\tau,\alpha} \chi(g^{-1}_{\vec{\tau}} g_{\vec{\tau}+\vec{a}_\alpha})$$

$$\widetilde{\widetilde{E}} = \sum_{\tau,\alpha} \chi(g^{-1}_{\bar{\tau}} g_{\bar{\tau}+\bar{a}_\alpha} B_{\bar{\tau},\alpha}). + E[B].$$



Original source details: GELFAND-P000573

Uncertain reading. In the double-tilde line B follows the second g within the parentheses with no visible comma between them. The τ index on B has a bar. There is a small separate stroke near the baseline before the plus sign.

Field th. = stat. mech. in $\mathbb{R}^n$ (Euclidean).

(Fourier transf. in time)

Sinai.



Diagram and typed description.



Original source details: GELFAND-P000573

V — finite volume.

$$E(\{B_{\tau\alpha}\}) = \sum \operatorname{tr}\left(B_{\tau\alpha} B_{\tau+a_\alpha,\beta} B^{-1}_{\tau+a_\beta,\alpha} B^{-1}_{\tau,\beta}\right)$$

$$\underline{\underline{\mathcal{M} e^{-\beta E} = Z(\beta, V)}}$$

Calculated for the 2-dim. case.

$$\ln Z(\beta, V) = V \ln I_0(\beta) \qquad (I_0(\beta) \text{ — Bessel fn.})$$

GELFAND-P000574

$$B_{\tau\alpha} = e^{iA_{\tau\alpha}}$$

Uncertain reading. The first subscript on B and on A reads τ.

Original source details: GELFAND-P000574

$$\text{[...]}\ E = \sum \cos(A_{\tau\alpha} + A_{\tau+a_\alpha,\beta} - \ldots)$$



Uncertain reading. A short sign is densely crossed out before E. φ is possible, but the reading is unresolved.

Original source details: GELFAND-P000574



Uncertain reading. The second A under the cosine has $\tau + a_\alpha$, a comma and β in its subscript.

Original source details: GELFAND-P000574

$$\lim_{V\to\infty} \frac{\ln Z(\beta, V)}{V} = f(\beta)$$

does not depend on the choice of boundary conds.

$f(\beta)$ may have singularities — they are called phase transitions.

(≈ a rearrangement of typical configs. occurs).

$$p(\{B_{\tau,\alpha}\}) = Z^{-1} e^{-\beta E(\{B_{\tau\alpha}\})} \qquad \text{— Gibbs distrib.}$$

Correl. fn. — mean value of the circulation around the contour.
Phase trans. — in one phase ∼ area
in the other ∼ length.

GELFAND-P000575

~~[...]~~ 14/X–74. Gelfand Sem.

Uncertain reading. A short group is crossed out before the date. The Russian letters “Пo” are possible, but the strokes overlap.

Original source details: GELFAND-P000575

Graeme Segal.
Classifying space of category.
$\mathcal{C}$ — category, $|\mathcal{C}|$ is top. space
Objects — points
Morphisms — 1-dim symplex.
Compositions — ?



Diagram and typed description.



Original source details: GELFAND-P000575

we have a graph.
It describe not cat. [?]

Uncertain reading. A low loop-like sign follows “cat.”. The reading $\mathcal{C}$ is tentative. Its shape differs from the clearly written letter above.

Original source details: GELFAND-P000575

(composition!)

Diagram and typed description.



Original source details: GELFAND-P000575

two-symplex — composition of two morphisms.

3 morph., and all compos. — 3-dim symplex.

which can be composed ↑

Original source details: GELFAND-P000575

Diagram and typed description.



The solid arrows and discernible thin strokes are drawn schematically. Some overlapping edges have unresolved directions.

etc.

We define $|\mathcal{C}|$.

Diametr. opposed examples.

Partially ↓

Ordered sets.

≡ categ. with at most one morph. between two objects.

groups



Original source details: GELFAND-P000575

Diagram and typed description.



morphisms ≅ elts of group
one object.
compos =
= comp. of elem.

X top space, $\{U_\alpha\}_{\alpha\in S}$ — covering $U_\alpha \subset X$

open sets

We suppose:

Property:

$$U_\alpha \cap U_\beta = \bigcup_{\text{certain } \gamma} U_\gamma.$$

$$\alpha \le \beta \underset{\text{def}}{\iff} U_\alpha \subset U_\beta.$$

If all sets are contractible then $|\mathcal{C}| \underset{\text{hom. equiv.}}{\simeq} X$.

Add. intersections.

GELFAND-P000576

Example. $X = S^2$. $w = U \cap V$.



Original source details: GELFAND-P000576

Diagram and typed description.



A small mark is visible to the left of the upper outline. The band lines and side marks overlap in parts of the lower drawing.



Original source details: GELFAND-P000576

Diagram and typed description.

But W is not contractible.

$|\mathcal{C}| =$  segment.

$$w = W_1 \cup W_2.$$
$$x_1 \in (W_1 \cap W_2)_{\text{comp}}.$$
$$x_2 \in (W_1 \cap W_2)_{\substack{\text{connected} \\ \text{comp}}}.$$



Uncertain reading. “comp” is written to the right of the first parenthesis. “connected” with “comp” below follows the second.

Original source details: GELFAND-P000576

~~oc?~~ — surface of octahedron.

Uncertain reading. Two loop-like letters are visible under the cancellation, tentatively “oc”.

Original source details: GELFAND-P000576



Original source details: GELFAND-P000576

Diagram and typed description.



The redraw follows the clear outline and inner strokes. Some thin and superimposed edges are only partly discernible.

Ex. 2

V — finite dimensional vect. space ($\forall$ field).

$\mathcal{C}$ — cat of proper subspaces and inclusions.

$|\mathcal{C}|$ = "building" of V building

"immeuble"

Thm. (Solomon — Tits).

~~[...]~~ $|\mathcal{C}| \simeq$ wedge (bouquet) of spheres of dim $(n-2)$

$(n = \dim V)$,

Original source details: GELFAND-P000576

Uncertain reading. A cancelled group with a vertical and loops precedes $|\mathcal{C}|$. An earlier $|\mathcal{C}|$ is possible.

(quantity of spheres depends on field — infinite if the field is infinite).

Proof.

1. If ord. set has max elt then $|\mathcal{C}|$ is contractible.

Original source details: GELFAND-P000576

Diagram and typed description.

evidente.

max elements are ~~[...]~~ subsp. of codimension 1.

Original source details: GELFAND-P000576

Uncertain reading. A short abbreviation, possibly "vect", is crossed out before "subsp.".



Original source details: GELFAND-P000576

Undeciphered passage. Multiple horizontal strokes conceal the middle of the cancelled abbreviation.

$$|\mathcal{C}| = \bigcup_{H\text{—hyperplanes}} |\mathcal{C}_H|.$$

$\mathcal{C}_H$ — is the cat of subspace W, $0 \underset{\text{strict}}{\subset} W \subseteq H$.

Uncertain reading. The manuscript uses inclusion signs: $\subset$ annotated "strict" and $\subseteq$ with a lower bar.

Original source details: GELFAND-P000576

$|\mathcal{C}_H|$ is contractible.

be given ↙

Let ~~[...]~~ fixed ~~hyperplane~~ line L.

Uncertain reading. A group between "Let" and "fixed" is crossed out, possibly "We".

Original source details: GELFAND-P000576



Undeciphered passage. Dense slanted strokes obscure the full group. "be given" is written separately above the line.

Original source details: GELFAND-P000576

$$\text{Let} \quad Y = \bigcup_{H \supset L} |\mathcal{C}_H| \subset |\mathcal{C}|.$$

~~[...] $\Rightarrow$ dim$(W \cap H_0) > 0$ [...]~~



Original source details: GELFAND-P000576

Uncertain reading. The end of the cancelled line reads dim$(W \cap H_0) > 0$. The sign before "dim" resembles an implication arrow, and the final stroke may be Cyrillic "и".



Undeciphered passage. The opening and intervening parts of the cancelled line remain unresolved.

Original source details: GELFAND-P000576

Y is contractible because

$$|\mathcal{C}_{H_1}| \underset{\text{contr.,}}{\cap} |\mathcal{C}_{H_2}| = |\mathcal{C}_{H_1 \cap H_2}| \underset{\text{also contractible}}{}.$$

GELFAND-P000577

If Y is covered by pieces Y_i such that all $Y_{i_1} \cap \ldots \cap Y_{i_k}$

is contractible (and not ~~[...]~~ vide ~~empty?~~ [?]) $\Rightarrow Y$ contractible.



Original source details: GELFAND-P000577

Uncertain reading. “vide” is above the crossed-out word, tentatively Russian “пусто”. A loop-like sign with a descender is to the right. Its reading is unresolved.

Original source details: GELFAND-P000577

Undeciphered passage. The first short word after “not” is crossed out. “et” is possible, but the full lettering is indistinct.

~~[...]~~

Original source details: GELFAND-P000577

Uncertain reading. The short cancellation below “is” begins with strokes that resemble “te”.

Original source details: GELFAND-P000577

Undeciphered passage. Dense crossing strokes obscure the ending.

in partial.

$$|\mathcal{C}| = Y \cup \bigcup_{H \not\supset L} |\mathcal{C}_H|.$$

Original source details: GELFAND-P000577

Uncertain reading. The union is indexed by $H \not\supset L$. The negated curved sign has no separate lower bar.

Lemma 1.

If $X = Y \cup Y_1 \cup \ldots \cup Y_k$

and $Y_?, Y_1, \ldots, Y_k$ contractible.

Original source details: GELFAND-P000577

Uncertain reading. A subscript on the first Y is crossed out. Its reading is unresolved.

and $Y_i \cap Y_j \subset Y$, then

$$X \simeq \bigvee_{\text{wedge}} Y_i/(Y_i \cap Y)$$



Original source details: GELFAND-P000577

Uncertain reading. The numerator resembles Y_i. The short stroke at its foot matches Y in the denominator. V_i remains a possible reading.



Original source details: GELFAND-P000577

Diagram and typed description.



Y collaps to point

Lemma 2.

Also if Z is contractible and $Z_0 \subset Z$ then

$$Z/Z_0 \simeq \underset{\text{suspension}}{SZ_0}$$



Diagram and typed description.



Original source details: GELFAND-P000577

$$\Rightarrow X \simeq \bigvee S(Y_i \cap Y)$$

Lemma 3.

$|\mathcal{C}_H| \cap Y =$ "building" of H.

and reduction by dimension.

dim $= 2$. (first step of induction).

Original source details: GELFAND-P000577

Diagram and typed description.

Lines

wedge of !! points ~~[...]~~

Original source details: GELFAND-P000577

Uncertain reading. "of" is visible in an outline after "wedge", with two vertical marks nearby. Their function is uncertain.

~~[...]~~

Original source details: GELFAND-P000577

Uncertain reading. Some strokes in the lower cancelled group resemble "wedge".

Original source details: GELFAND-P000577

Undeciphered passage. The lower inscription and the cancelled group after "points" are incompletely legible.

Suspension of wedge of spheres is also a wedge of spheres.

$H_{n-2}(|\mathcal{C}|;\mathbb{Z}) =$ Steinberg module of V.

Original source details: GELFAND-P000577

Uncertain reading. Typeset as $=$. The lower stroke is retraced, so $\equiv$ is a possible reading.

(repres. in subgrps. of a fin. group)

Other extreme case.

$\mathcal{C}$ of group G. $\quad |\mathcal{C}| = BG$ — classifying space of group

$\pi_1(|\mathcal{C}|) = G$. $\quad$ (evidently)



Original source details: GELFAND-P000577

Diagram and typed description.



The outline and loops follow the discernible strokes. Short, superimposed marks near the outline do not establish further directions.

Universal covering is contractible.

Let $\widetilde{\mathcal{C}}$ $\quad$ objects $=$ elts of G.

$\exists\, 1$ morph. $g \to g'$ for each pair of elts.

GELFAND-P000578

$|\widetilde{\mathcal{C}}|$ is contractible.

($\forall$ el-t is connected by line with unity 1).

$\widetilde{\mathcal{C}} \xrightarrow{\text{functor}} \mathcal{C}$ universal covering space.

$g \mapsto *$

$g \to g' \mapsto g^{-1}g'$



Original source details: GELFAND-P000578

Diagram and typed description.



The short lower-left arrow points from a small loop towards g. An asterisk is visible at the right.

$|\widetilde{\mathcal{C}}| \to |\mathcal{C}|$ universal covering.



Original source details: GELFAND-P000578

Diagram and typed description.



Original source details: GELFAND-P000578

Uncertain reading. The crossed-out expression next to “bundle” tentatively reads “fibre space”.

$\{U_\alpha\}$ — covering, on U_α bundle is trivial.

Original source details: GELFAND-P000578

Uncertain reading. A heavy superimposed stroke follows “covering” before the comma. A separate character is uncertain.



Original source details: GELFAND-P000578

Diagram and typed description.

$U_\beta \longleftarrow U_\alpha \cap U_\beta \longrightarrow U_\alpha$

$\underset{g_{\beta,\alpha\beta}}{\longleftarrow}$ $\underset{g_{\alpha,\alpha\beta}}{\longrightarrow}$ two immersions $\in G$

Let us consider categ. of sets U_α and their finite intersections

~~let ... this cat. of sets~~

Original source details: GELFAND-P000578

Uncertain reading. The crossed-out line shows "let", tentatively "this", and "cat. of sets".



Original source details: GELFAND-P000578

Undeciphered passage. The strokes after "let" may include "us". The full passage is indistinct.

GELFAND-P000579

21/X-74. Gelfand Sem. Kushnirenko.

Melvin Hochster.

$P\colon \mathbb{C}^n \to \mathbb{C}$, P — a polynomial, $P = \sum a_m z^m$.

Singular points: $\{z : \frac{\partial P}{\partial z_i} = 0\}$. Consider all the sing. points. Suppose they are isolated.

How do we find them, counting multiplicity?

Consider the convex hull of 0 and all $m \in \mathbb{Z}^n$ for which $a_m \neq 0$.



Original source details: GELFAND-P000579

Diagram and typed description.



$$2S - a - b + 1.$$

1) the number of isol. sing. points, counting mult., $\leq 2S - a - b + 1$.

2) if the nondegeneracy cond. holds $= 2S - a - b + 1$.

Idea: consider the degree of the map $S^{2n-1} \to S^{2n-1}$.

$$\underset{z}{|z|=R} \longmapsto \frac{\left(\frac{\partial P}{\partial z_1}, \dots, \frac{\partial P}{\partial z_n}\right)}{|\operatorname{grad} P|}.$$

This was known in the homogeneous or quasihomog. case.

$\sum$ of Milnor numbers = degree (abs. fact)



Diagram and typed description.



Original source details: GELFAND-P000579

Hochster: consider the ring of monomials with exponents m in the angle.

Uncertain reading. The handwritten Russian preposition “в” before “угле” is retraced.

Original source details: GELFAND-P000579

Diagram and typed description.

Original source details: GELFAND-P000579

This is a Cohen–Macaulay ring.

Mumford — toric embeddings.

Polyakov:

Yang–Mills field.

$$S \dots = \int d^4x \left\{ \frac{1}{e^2} \operatorname{Sp}(\partial_\alpha b_{\alpha\beta} - \partial_\beta b_\alpha - [b_\alpha, b_\beta]^2) \right.$$

⟵ action
– Lagrangian
(under the integral sign)

Uncertain reading. A group of marks after S is crossed out. Its reading is obscured by dense strokes.

Original source details: GELFAND-P000579



Uncertain reading. Two subscripts, $\alpha\beta$, are visible after b in the first term.

Original source details: GELFAND-P000579



Original source details: GELFAND-P000579

Uncertain reading. The exponent 2 immediately follows the square bracket. The brace after d^4x is left open.

b_α — elem. of a Lie algebra, given at any point.

There is a vect. bundle over $\mathbb{R}^4$ with fibre a Lie algebra (preferably $SU(2)$)

If $(b_\alpha)^b_a$ — the matrix Γ_α, we obtain $R^b_{\alpha\beta a}$ under the integral sign.

Elem. of a Lie alg. at $\forall$ point $\longleftrightarrow$ connection.

Pontryagin class: $R^\beta_{\alpha,\delta_1\delta_2} \cdot R^\alpha_{\beta,\delta_3\delta_4}$.

Uncertain reading. The two pairs of lower indices read $\delta_1\delta_2$ and $\delta_3\delta_4$.

Original source details: GELFAND-P000579

GELFAND-P000580

28/X-74. Gelfand Sem.

M. I. Graev. On work by Vershik, Graev and Gelfand

Original source details: GELFAND-P000580

Uncertain reading. The second initial has been heavily retraced. Cyrillic “И.” is probable, with “Н.” also possible.

~~(Alg.?)~~



Original source details: GELFAND-P000580

Uncertain reading. The cancelled parenthetical abbreviation below the heading tentatively reads “Алг.” (“Alg.”).



Original source details: GELFAND-P000580

Undeciphered passage. The crossing strokes obscure some of the letters in the abbreviation.

On current algebra for physicists.

(Funct. Anal., vol. 2, $N = 1$)

$$g(x) = \begin{pmatrix} f_{11}(x) & f_{12}(x) \\ f_{21}(x) & f_{22}(x) \end{pmatrix}, \qquad x \in [0,1], \qquad \det g(x) = 1$$



Original source details: GELFAND-P000580

Uncertain reading. The upper-left entry tentatively has subscript 11. The second digit is overwritten.



Original source details: GELFAND-P000580

Uncertain reading. The strokes at the argument of g overlap. The probable reading is $\det g(x) = 1$.

$f_{ij} : [0,1] \to \mathbb{R}$ continuous functions.

A method for constructing irreducible representations is given, analogous to taking an integral.

Original source details: GELFAND-P000580

Uncertain reading. The line supports reading “взятию” (“taking”). Several final strokes run together.

GELFAND-P000581

G. Replace the interval by a set of points. Suppose there are 2 points

$$\begin{matrix} x_1 & x_2 \\ g_1 & g_2 \\ H & \end{matrix} \qquad T^{(1)}_{g_1}\xi \quad T^{(2)}_{g_2}\xi$$

Consider $H_1 \otimes H_2$ and the representation



Diagram and typed description.

infinite-dim.

$T = T^{(1)}_{g(x_1)}\xi \otimes T^{(2)}_{g(x_2)}\eta$

$T_g(\xi \otimes \eta)$

Original source details: GELFAND-P000581



Uncertain reading. The sign before the equals sign resembles T, with heavily retraced lower strokes. T_g is possible. Both operators in the upper pair act on ξ.

Original source details: GELFAND-P000581

Example: $e^{i\alpha(x)}$, commut. group. Rep. (irred.) is 1-dimensional

$$T_{g(x)}\xi_0 = e^{i\ell[\alpha(x)]}\xi_0, \qquad \ell \text{ — lin. functional} \qquad \int \alpha(x)\,dx$$

$\alpha \in C^\infty \Rightarrow \ell$ — a generalized function



Uncertain reading. The letter in the exponent resembles α in the lower formula. A handwritten L is also possible.

Original source details: GELFAND-P000581

Uncertain reading. The Russian abbreviation “непр.” is tentatively expanded as “irreducible”.

Original source details: GELFAND-P000581

matrix

Reps. of groups of order 1 $\Longleftrightarrow$ generalized functions

Is there an irred. rep. that is structured in the same way everywhere.

Grp. $SL_2(\mathbb{R})$ representations T_λ in spaces H_λ

H_λ — those $f(t)$ for which

$$\|f\|_\lambda^2 = \int_{-\infty}^{+\infty} |t_1 - t_2|^{-\lambda} f(t_1)\overline{f(t_2)}\, dt_1\, dt_2 < \infty.$$

$0 < \lambda < 1$ for pos. definiteness



Uncertain reading. One integral sign is visible with two differentials $dt_1 dt_2$. The variable strokes are heavily retraced.

Original source details: GELFAND-P000581

G. There are representations close to 1 (but infinite-dimensional!!)

Problem. There is a dimension in Kolmogorov's sense (see one Japanese person).



Uncertain reading. The end of the parenthesis reads "один японец", literally "one Japanese person".

Original source details: GELFAND-P000581

With a proper def. of the kernel we can consider dim in Kolmogorov's sense = mult. ... of the Plancherel measure.



Uncertain reading. The word after the abbreviation for "definition" reads "ядра" ("of the kernel").

Original source details: GELFAND-P000581



Uncertain reading. The abbreviation after the equals sign tentatively reads "множ." ("mult."). The final strokes overlap.

Original source details: GELFAND-P000581

Uncertain reading. A short group of strokes to the right of the abbreviation is crossed out.

Original source details: GELFAND-P000581

Undeciphered passage. The entire crossed-out group remains unread.

Original source details: GELFAND-P000581

Rep. of $SL_2(\mathbb{R})$,

$$f(t) \longrightarrow f\left(\frac{\alpha t+\gamma}{\beta t+\delta}\right)|\beta t+\delta|^{\rho-1}, \qquad \begin{pmatrix}\alpha & \beta\\ \gamma & \delta\end{pmatrix}$$

$(\dots)^{\rho-1}$

$\underline{\rho=1}$ — identity rep.
$\underline{\rho\approx 1}$ — close to the identity



Uncertain reading. The looped numerator letter with a rightward stroke matches the lower-left matrix entry, γ. The reading δ remains possible.

Original source details: GELFAND-P000581



Uncertain reading. The looped sign in both exponents and both following lines is rendered as ρ. s is possible.

Original source details: GELFAND-P000581

$$f(x_1,x_2) \longrightarrow f(\alpha x_1+\beta x_2, \gamma x_1+\delta x_2)$$

on homog. polynomials

$$x_2^n f(x_1/x_2,1) \qquad \begin{matrix} n \text{ — weight} \\ \approx \text{ dim.}\end{matrix}$$



Uncertain reading. Before x_1 in the second argument, the loop and rightward stroke resemble the lower-left matrix entry. The preferred reading is γ, with δ also possible.

Original source details: GELFAND-P000581

Gr.

$$(T_\lambda^{(g)} f)(t) = f\left(\frac{\alpha t+\gamma}{\beta t+\delta}\right)|\beta t+\delta|^{\lambda-2}, \qquad g=\begin{pmatrix}\alpha & \beta\\ \gamma & \delta\end{pmatrix}$$

$0<\lambda<1$



Original source details: GELFAND-P000581

Uncertain reading. The numerator letter resembles the matrix's γ. It is distinguishable from the shape of δ in the denominator, with some uncertainty.

$\lambda=0 \Rightarrow$ the inner prod. degenerates to

$$\left|\int_{-\infty}^{\infty} f(x)\,dx\right|^2 = \|f\|^2.$$

Analyt. cont.:



Original source details: GELFAND-P000581

Diagram and typed description.



Original source details: GELFAND-P000581

Uncertain reading. A two-line inscription below the interval 1–2 is crossed out. It tentatively reads "1 neg. quadr."



Original source details: GELFAND-P000581

Undeciphered passage. Both lines are only partially legible beneath the cancellation.

$\lambda=0$ — ~~func.? ...~~ obtain ~~...~~ a rep. in a subspace

Original source details: GELFAND-P000581

Uncertain reading. The crossed-out passage after the equality begins with what appears to be "функц." ("func.").



Original source details: GELFAND-P000581

Undeciphered passage. The remaining crossed-out strokes in the phrase are unresolved.

Original source details: GELFAND-P000581

Uncertain reading. A further word is crossed out between “obtain” and “rep.”

Original source details: GELFAND-P000581

Undeciphered passage. The crossed-out word remains unread.

$$\int_{-\infty}^{\infty} f(t)\,dx = \int_{-\infty}^{+\infty} f\left(\frac{\alpha t+\gamma}{\beta t+\delta}\right)|\beta t+\delta|^{-2}\,dt.$$

($\int$ — invariant)



Original source details: GELFAND-P000581

Uncertain reading. The left side has $f(t)\,dx$ and the right has dt. The looped numerator letter is read as γ. Heavy strokes near the denominator's δ obscure the earlier writing.

GELFAND-P000582

Fix λ, $(0 < \lambda < 1)$ and consider const. matrices $g(x) \equiv \text{const} = g$.

Original source details: GELFAND-P000582

Diagram and typed description.



This is $SL_2(\mathbb{R}) = G$.

Consider the rep. T_λ of this group in H_λ.

Divide the interval into 2 equal parts and take functions const. on the left and right halves



Original source details: GELFAND-P000582

Diagram and typed description.



$\dots$ This is $G \times G$.

Uncertain reading. A sign before "This is" is heavily crossed out. Its reading is unresolved.

Original source details: GELFAND-P000582

Consider $H_{\lambda/2} \otimes H_{\lambda/2}$ and define there a rep. of $G \times G$



Diagram and typed description.



Original source details: GELFAND-P000582

$$G \times G \times G \times G \longrightarrow \text{rep. in } H_{\lambda/4} \otimes H_{\lambda/4} \otimes H_{\lambda/4} \otimes H_{\lambda/4}.$$

and so on

$$G \subset G \times G \subset G \times G \times G \times G \subset \dots \qquad \varinjlim_{n \to +\infty} \underbrace{G \times \dots \times G}_{2^n \text{ times}} \underset{\text{def}}{=} \widetilde{G}.$$



Uncertain reading. A group of symbols between the outer factors is crossed out. The brace reads "2^n times".

Original source details: GELFAND-P000582

Representation of $\widetilde{G}$?

We need to embed $H_\lambda \subset H_{\lambda/2} \otimes H_{\lambda/2}$ compatibly with the group action.

Decomp. into irreducibles — in the discrete part enters H_λ once, and in the complement, the rest, and so on. This lets us embed

$$H_\lambda \hookrightarrow H_{\lambda/2} \otimes H_{\lambda/2} \hookrightarrow \underbrace{H_{\lambda/4} \otimes \dots \otimes H_{\lambda/4}}_{4 \text{ times}} \hookrightarrow .$$



Uncertain reading. The denominator of the first subscript under the brace is overwritten. The probable reading is $\lambda/4$.

Original source details: GELFAND-P000582

$$H_{\lambda/2} \otimes H_{\lambda/2} = H_\lambda \oplus \text{the rest}.$$

The embedding of H_λ is determined (up to a factor)

$$H_\lambda \hookrightarrow H_{\lambda/2} \otimes H_{\lambda/2}$$

$$f(t) \longrightarrow f(t)\delta(t-s) = f(t,s) \qquad \text{(unit. embedding)}$$



Uncertain reading. Both occurrences of the second argument are overwritten with a looped sign. s is a tentative reading.

Original source details: GELFAND-P000582

Uncertain reading. The last letter of "вложение" ("embedding") is heavily retraced. The ending of "вложения" may underlie it.

Original source details: GELFAND-P000582

$$\varinjlim H_{\lambda/2^n} \otimes \ldots \otimes H_{\lambda/2^n}$$ and take the completion

the group of step functions acts there. The rep. extends to a rep. of the group of cont. functions.

Elements of the space — ~~sequences?~~ functions $f(x,t)$, $-\infty < t < +\infty$, $0 < x < 1$



Uncertain reading. The crossed-out word resembles "последовательности" ("sequences"). Some letters are covered.

Original source details: GELFAND-P000582

~~$f(t_0)f(t)$~~? $\int_{-\infty}^{\infty} f(x,t)\,dt = 1$



Uncertain reading. The cancellation to the left of the integral resembles $f(t_0)f(t)$. The complete reading is unresolved.

Original source details: GELFAND-P000582

Consider formal lin. combs. $\sum \lambda_i \cdot f_i(x,t)$.

$\sum \lambda_i \cdot 0 \neq 0$ (!).

Inner prod.

$$\langle f_1(x,t), f_2(x,t)\rangle = e^{-\int \ln|t_1-t_2|\, \widetilde{f}_1(x,t)\widetilde{f}_2(x,t)\,dt_1\,dt_2\,dx}$$

and by linearity



Original source details: GELFAND-P000582

Uncertain reading. One integral sign is written, and both arguments of $\widetilde{f}_i$ are written (x,t). The tilde over the first f is retraced.

$f_1(x,t)$ — a curve in a Hilb. space. Inner prod. of δ-functions on them.

GELFAND-P000583

$$\widetilde{f}(x,t) = f(x,t) - \frac{1}{\pi(1+x^2)}.$$



Uncertain reading. The denominator of the subtracted fraction contains x^2.

Original source details: GELFAND-P000583

Representation:

$$U(g(x))f(x,t) = \lambda(g,f) \circ f\left(x, \frac{\alpha(x)t+\gamma(x)}{\beta(x)t+\delta(x)}\right)|\beta(x)t+\delta(x)|^{-2}$$



Uncertain reading. A small open circle is visible between $\lambda(g,f)$ and f.

Original source details: GELFAND-P000583



Uncertain reading. The numerator has a loop with a long rightward stroke, matching γ on frame 581. The denominator's δ has an upper hook.

Original source details: GELFAND-P000583

GELFAND-P000584

17/II-75 Gelfand Sem.
Tulovskii FIO — I and II.

$$\Omega \subset \mathbb{R}^n, \qquad u \in \mathcal{D}'(\Omega), \qquad \mathrm{WF}(u) \subseteq \Omega \times (\mathbb{R}^n \setminus 0).$$

~~$u \in \mathcal{D}'(\Omega)$~~

Uncertain reading. The cancelled formula resembles $u \in \mathcal{D}'(\Omega)$.

Original source details: GELFAND-P000584

Definition. $(x_0, \xi_0) \notin \mathrm{WF}(u)$, if $\exists\, \varphi(x) \in C_0^\infty(\Omega)$, $\varphi(x_0) \neq 0$

$$|\widetilde{u\varphi}(\xi)| \leq C_N(1+|\xi|)^{-N} \quad \text{when} \quad |\dot{\xi} - \dot{\xi}_0| < \varepsilon \qquad \left(\dot{\xi} = \frac{\xi}{|\xi|}\right)$$

G.

Original source details: GELFAND-P000584

Diagram and typed description.

Crossed-out diagram. The cancellation partly covers the upper arcs.

Smoothness of a function of one var., obtained as an $\int$ over parallel hyperplanes — $\sim$ membership of the covector in the wavefront.

Original source details: GELFAND-P000584

Uncertain reading. The initial letter of “фронту” (“front”) is heavily overwritten. The earlier layer is unresolved.

— · —

1 variable.



Original source details: GELFAND-P000584

Diagram and typed description.



$$(x_0, \xi_0) \notin \mathrm{WF}(u), \quad (\xi_0 > 0), \quad \text{if} \quad u = \varphi(x) + u_1 \quad \text{(locally)}$$

$\varphi \in C_0^\infty$, u_1 analytically continues into the upper half-plane.



Original source details: GELFAND-P000584

Uncertain reading. The overwritten subscript in C_0^∞ resembles 0. A separate dot is visible above φ.

$$\pi(\mathrm{WF}(u)) = \operatorname{sing\,supp} u. \qquad (\pi : T^*\Omega \to \Omega).$$



Uncertain reading. The lines read as $=$ overlap a heavier, arrow-like stroke.

Original source details: GELFAND-P000584

$$\pi' : \overset{\Omega\times(\mathbb{R}^n\setminus 0)}{\cancel{\mathrm{WF}(u)}} \longrightarrow \mathbb{R}^n \setminus 0.$$



Uncertain reading. The domain $\mathrm{WF}(u)$ is crossed out. $\Omega \times (\mathbb{R}^n \setminus 0)$ is inserted above it.

Original source details: GELFAND-P000584

$\pi'\mathrm{WF}(u)$ — the smallest closed cone outside which the Fourier transform decays rapidly.

Uncertain reading. The initial letter of “Фурье” (“Fourier”) is retraced, with short strokes above and below.

Original source details: GELFAND-P000584

Let $\Gamma \subseteq \Omega \times (\mathbb{R}^n \setminus 0)$ — an open conic set,

$$\Gamma_1, \Gamma_2 \subseteq \Omega \times (\mathbb{R}^n \setminus 0),$$
$$\Gamma_1 + \Gamma_2 = \{(x; \xi + \eta) : (x, \xi) \in \Gamma_1,\ (x, \eta) \in \Gamma_2\},$$
$$\mathcal{D}'_\Gamma(\Omega) = \{u \in \mathcal{D}'(\Omega) : \mathrm{WF}(u) \subseteq \Gamma\}.$$

~~Then ...~~ let $\Gamma_1 + \Gamma_2 \subseteq \Omega \times (\mathbb{R}^n \setminus 0)$.



Undeciphered passage. Before “let”, “Then” and a further word are crossed out. The second word remains partly unread.

Original source details: GELFAND-P000584

Then $\exists$ a bilin. map:

$$\mathcal{D}'_{\Gamma_1}(\Omega) \times \mathcal{D}'_{\Gamma_2}(\Omega) \longrightarrow \mathcal{D}'_{\Gamma_1+\Gamma_2\cup\Gamma_1\cup\Gamma_2}(\Omega).$$

—— · ——

$$\Omega_x \subseteq \mathbb{R}^{n_x},$$
$$\Omega_y \subseteq \mathbb{R}^{n_y}, \qquad A \in \mathcal{D}'(\Omega_x \times \Omega_y).$$
$$A : C_0^\infty(\Omega_y) \to \mathcal{D}'(\Omega_x), \qquad \langle Au(y), v(x)\rangle = \langle A, u(y)v(x)\rangle$$



Uncertain reading. The strokes near v and the closing sign on the right are heavily retraced.

Original source details: GELFAND-P000584

(x, ξ, y, η) — $\mathrm{WF}(\text{of the operator}) \underset{\text{def}}{=} \mathrm{WF}(\text{of the kernel})$

Thm. Suppose for simplicity that in $\mathrm{WF}(A)$ there are no points where $\xi = 0$ or $\eta = 0$
Then $A : C_0^\infty(\Omega_y) \to C^\infty(\Omega_x)$ and extends to a map $A : \mathcal{E}'(\Omega_y) \to \mathcal{D}'(\Omega_x)$.
Moreover: if $u \in \mathcal{E}'(\Omega_y)$, then $\mathrm{WF}(Au) \subseteq \mathrm{WF}'(A) \circ \mathrm{WF}(u)$,

GELFAND-P000585

where

$$\mathrm{WF}'(A) = \{(x, \xi, y, -\eta), \text{ where } (x, \xi, y, \eta) \in \mathrm{WF}(A)\}.$$

$$(x, \xi) \in \mathrm{WF}'(A) \circ \mathrm{WF}(u) \iff \exists\, (x, \xi, y, \eta) \in \mathrm{WF}'(A), \quad (y, \eta) \in \mathrm{WF}(u).$$

— · —

G.'s idea — integrate both lin. functions and polynomials.



Original source details: GELFAND-P000585

Diagram and typed description.

already different.

Original source details: GELFAND-P000585

Uncertain reading. The ending favors Russian "другое". "Другая" is a less likely reading.

— · —

$$\frac{A : \mathcal{E}'(\Omega_y) \to \mathcal{D}'(\Omega_x) \qquad B : \mathcal{E}'(\Omega_z) \to \mathcal{E}'(\Omega_y)}{\mathrm{WF}'(A \circ B) \subseteq \mathrm{WF}'(A) \circ \mathrm{WF}'(B)}$$

Original source details: GELFAND-P000585

Uncertain reading. Both occurrences of WF on the right of the inclusion carry a prime.

Sinai. Stat. physics (from the end)
Gibbs random field.



Original source details: GELFAND-P000585

Diagram and typed description.

Fig.?



Original source details: GELFAND-P000585

Uncertain reading. Crossed-out vertical strokes lie to the left of the outline. “II” and “III” are possible.

Original source details: GELFAND-P000585

Uncertain reading. The upper-left label resembles Russian “Рис” (“Fig.”). $\mathbb{R}^n$ is also possible.

G. Consider a measure μ on countable subsets of $\mathbb{R}^n$ without accumulation points (configurations denoted by X).

Measurable sets — the smallest σ-algebra generated by cylinder sets:

$$\{K : |X \cap K| = n\} = \text{Ц}_{K,n} \qquad (K \text{ — compact})$$

The measure is countably additive.

Main example: Poisson distribution.

(M — loc. comp. ...)
Let ... be given

and on M

(infinite)
... measure μ. Then



Undeciphered passage. Strokes overlap at the end of the upper insertion and in the notation after “Let”. The lower insertion reads “and on M”.

Original source details: GELFAND-P000585



Original source details: GELFAND-P000585

Undeciphered passage. A phrase before “measure” is heavily crossed out. “Infinite” is inserted in an outline above it.

$$\rho(\text{Ц}_{K,n}) = \frac{m(K)^n}{n!} e^{-m(K)}$$



Original source details: GELFAND-P000585

Uncertain reading. The first symbol is heavily retraced and resembles ρ. The numerator and exponent use m.

— · —

Gibbs distributions:

“Interaction is finite”: independence.



Original source details: GELFAND-P000585

Diagram and typed description.



The upper contour encloses five dots. Some of the five segments in the lower drawing stop short of the inner contour.

Consider $U(x_1, x_2)$, $U(x_1, x_2, x_3)$, …

$$U(x_1, \dots, x_n) = \begin{cases} 0 & \text{if the diameter is } \geqslant 1 \\ \infty \text{ if} & \text{... close?} \quad ? \end{cases}$$



Original source details: GELFAND-P000585

Undeciphered passage. The second case is cancelled. The infinity sign and “if” are visible, followed by what appears to end in “close”. The intervening strokes are obscured.

The seq. breaks off, since it becomes $\equiv +\infty$.

Original source details: GELFAND-P000585

Uncertain reading. The word after “since” reads “становится” (“becomes”).

Consider countable configurations.



Diagram and typed description.



The right subscript tentatively reads $n+1$. The final strokes meet the outline.

Original source details: GELFAND-P000585

$$d(X) = e^{-\sum U_k(x_1,\ldots,x_k)}$$

Density $d(x) = \dfrac{d(\text{Gibbs})}{d\mu}$.



Uncertain reading. The abbreviation to the left of the fraction resembles “Плотн.” (“density”).

Original source details: GELFAND-P000585

GELFAND-P000586

S. Consider $\underbrace{K \times \ldots \times K}_{n \text{ times}}$ with measure $m \times \ldots \times m$.

$$\frac{dG(X)}{dm} = d(X)$$

- - - -

m — a measure in $\mathbb{R}^2$. $\mathcal{M}$ — all such sets.

Poisson measure on $\mathcal{M}$: let O be a region.

$$\mu_0(|X \cap O| = k) = e^{-m(O)}[m(O)]^k/k! \qquad (1)$$

$m(O)$ — expected number of particles found in O.

More generally: (M, m) — a space with a measure [inserted below: "and a metric"]
$m(M) < \infty$ — uninteresting case

Interesting case: $m(M) = \infty$ and certain homogeneity properties.

Undeciphered passage. A short mark is crossed out above "certain".

Original source details: GELFAND-P000587

Let 2 functions be given: $U_1(x)$ [below: "bounded"] and

$$U_2(x, y) = \begin{cases} \infty & \text{if } \operatorname{dist}(x, y) < \varepsilon, \\ 0 & \text{if } \operatorname{dist}(x, y) \geq r_0. \end{cases}$$

Uncertain reading. The overwritten sign in the second row reads as 0.

Original source details: GELFAND-P000587

($U_2(x, y)$ is symmetric — a function on a pair of points.)

A Gibbs measure is constructed from a pair of [inserted: "functions"] U_1, U_2.



Undeciphered passage. The word beneath the insertion "functions" is crossed out.

Original source details: GELFAND-P000587

Def. by means of conditional probabilities.

Let there be a measure μ on the space of configurations $\mathcal{M}$

$$X = O \cap \ldots, \quad \underline{Y} = O' \cap \ldots$$

Uncertain reading. The overwritten sign before $\cap$ reads as O'.

Original source details: GELFAND-P000587

x — inside, y — outside (in the given configuration)



Diagram and typed description.



Original source details: GELFAND-P000587

A Gibbs measure is a measure such that:

$$\frac{d\mu(x_0 \mid y)}{d\mu_0(x_0)} = \frac{1}{\Xi(y;O)} e^{-\left[\sum_{x_i \in X} U_1(x_i) + \sum_{(x_i,x_j)\in X} U_2(x_i,x_j) + \sum_{\substack{x_i \in X \\ y_j \in Y}} U_2(x_i,y_j)\right.}$$



Uncertain reading. A subscript 0 is visible after x in the denominator.

Original source details: GELFAND-P000587



Uncertain reading. The first symbol in the final summand is overwritten and tentatively reads U_2. The closing square bracket is not visible.

Original source details: GELFAND-P000587

$$x = (x_1, \ldots, x_k) \qquad X = \{X_0 = X \cap O,\ Y = X \setminus X_0\}$$

All this depends only on the r_0-neighbourhood of O (on those points y, that fell within it).

$\mu(x \mid y)$ — a measure on configurations in O.

$\mu_0(x)$ — a measure — ” — O.

(In def. (1) it is understood, ~~the independence of different particles in different regions)~~ that we take the σ-algebra generated by the corresponding cylinder sets.)



Original source details: GELFAND-P000587

Uncertain reading. The first word in the crossed-out clause tentatively reads “independence”.

[G. $\mu(x \mid y)$ is defined because there is a measurable partition (Fubini's theorem — general) The measure on Y is induced by the measure on the whole space, by means of preimages.] Let there be 2 regions.



Diagram and typed description.



Original source details: GELFAND-P000587

From the measure μ on X a measure is constructed on Y (complete in all possible ways with the set X_0).

GELFAND-P000588

Diagram and typed description.





Original source details: GELFAND-P000588

Fix X_0, X_1 and Y. Then the (cond.) measure is calculated in two ways:

Theorem. ∃ at least one Gibbs distribution.

Undeciphered passage. A short mark before ∃ is crossed out.

Original source details: GELFAND-P000588

Proof.

Diagram and typed description.



Original source details: GELFAND-P000588

$O_1 \subset O_2 \subset O_3 \subset \ldots$ and the boundary conditions are fixed.

~~Let~~ The space of config. in O_1 is compact. $\exists$ a subseq. having a limit

and so on ...

Ex. 1 M — a line, m — Lebesgue measure $\Rightarrow$ there is only one Gibbs distribution.

Ex. 2 $M = \mathbb{R}^k$, $U_1 \equiv 0$, $m(O) \leq c\ell(O)$ (ℓ — Lebesgue measure)

For small c the Gibbs distrib. is unique.

— · —

Lattice Gibbs distrib.

Consider the lattice in $M = \mathbb{Z}^d$, $d \geq 2$.



Original source details: GELFAND-P000588

Diagram and typed description.



The lattice has two crosses and round marks. Region O encloses four sites. The drawing leaves the meaning of the marks unlabelled.

X — infinite subsets of lattice points

$\mathcal{M}$

μ_0 prob. that a particle is present $\frac{1}{2}$, a particle is absent $\frac{1}{2}$, and independence at different sites.

O — a finite region.

$$\mu(X_0 \mid Y) = \frac{1}{\Xi(Y,O)} e^{-\beta\left[\sum_{x\in X_0} U_1(x) + \sum_{(x_i,x_j)\in O} U_2(x_i,x_j) + \sum U(x_i,y_j)\right]}$$



Uncertain reading. No subscript is visible on U in the final sum. The symbol before the bracket reads β.

Original source details: GELFAND-P000588

U_2 also vanishes for large $|x-y|$.

$U_1 \equiv 0$, U_2 — small $\Rightarrow$ one Gibbs distrib.

(perturbation, prob. joint distrib. of independent random variables).

$$U_1(x) = \alpha \qquad U_2(x_i, x_j) = \cancel{U_2(|x_i - x_j|)}\, U_2(x_i - x_j)$$

$$U_2(-x) = U_2(x).$$

Original source details: GELFAND-P000588

Uncertain reading. A horizontal stroke is visible between x_i and x_j. The vertical strokes and outer parentheses of the cancelled formula are tentative.

1. Periodic ground state.

X — a periodic configuration (repetition of a rectangle)



Original source details: GELFAND-P000588

Diagram and typed description.

$$H(X) = \sum_{x \in X} U_1(x) + \sum_{x,y \in X} U_2(x,y) \qquad \text{(formal expression)}$$

Let X' be nonperiodic and differ from x in finitely many places. Write $H(X')$ (also formally).



Original source details: GELFAND-P000588

Uncertain reading. The symbol after "from" is a lowercase x.

If $\underbrace{H(X') - H(X) \geq 0}_{\text{already def.}}$ $\forall\, X'$, then X is called a ground state.

1) Let $(X_1, X_2, \dots, X_k) = G(U)$ — the set of periodic ground states corresponding to U.



Original source details: GELFAND-P000588

Undeciphered passage. One mark before the ellipsis is crossed out.

2) Peierls condition (nondegeneracy of ground states):

(so that ground states — the main contribution to $e^{-\beta H}$).

Original source details: GELFAND-P000589

Undeciphered passage. One mark between the dash and "main" is crossed out.

$$H(X') - H(X) > \dots$$

Original source details: GELFAND-P000589

Undeciphered passage. A short entry before "Let" is heavily crossed out.

Let $\bar{X}$ — an arbitrary configuration.



Original source details: GELFAND-P000589

Diagram and typed description.



Original source details: GELFAND-P000589

Undeciphered passage. The label by the arrow is crossed out.

ℓ is called a boundary point of $\bar{X}$, if in a neighbourhood of ℓ $\bar{X}$ does not agree with any of the periodic ground states.

Suppose $\forall$ config. X', differing from X in finitely many points,

Peierls cond.:

$$H(X') - H(X) \geq g\,\Gamma(X') \qquad (g > 0).$$

$\Gamma(X') \longleftarrow$ number of boundary points in X'.

Original source details: GELFAND-P000589

Undeciphered passage. A crossed-out entry stands between g and $\Gamma(X')$.

— · —

Include $\underset{\text{(pair } U_1, U_2)}{U}$ in a $(k-1)$-parameter family $U_{\mu_1,\dots,\mu_{k-1}}$, $U_{0,\dots,0} = U$ (there are k ground states — here the same k).

$$G(U_{\mu_1,\dots,\mu_{k-1}}) \le G(U) \qquad \text{for small } \mu$$



Uncertain reading. The sign between the two G expressions reads as $\le$.

Original source details: GELFAND-P000589

(ground states can only disappear). Let the perturbations be “lin. indep.”.

Then $\exists \beta_0, \forall \beta > \beta_0$

$$\exists!\big(\mu_1(\beta), \dots, \mu_{k-1}(\beta)\big) = \vec{\mu}$$



Uncertain reading. An exclamation mark is visible after $\exists$. The last subscript reads as $k-1$, with its end touching the parenthesis.

Original source details: GELFAND-P000589

for which there are k Gibbs distributions. Through it pass k curves, on which there are $(k-1)$ Gibbs distributions, C_k^2 surfaces, on which there are $(k-2)$ Gibbs distributions and so on.

Diagram and typed description.



The grouping of the short strokes is approximate.

Original source details: GELFAND-P000589

With shifts one obtains, “as a rule”, one ground state.

Nondegeneracy: as $\mu_1, \dots, \mu_k$ vary there is [inserted: “generally speaking”] one ground state, on the curves $\le (k-1)$ and so on.



Uncertain reading. Two altered signs precede “one”.

Original source details: GELFAND-P000589

Then the same holds for Gibbs distributions.

Gelfand’s question: Gibbs distrib. in the p-adic case.

GELFAND-P000590

[The upper part of the frame contains no text.]

—— · ——

3/III–75 Gelfand's sem.

V. N. Tulovskii. WF. $\Omega \subset \mathbb{R}^n$, $u \in \mathcal{D}'(\Omega)$.

$(x_0, \xi_0) \notin \mathrm{WF}(u)$, if $(x_0, \xi_0) \in \Omega \times (\mathbb{R}^n \setminus 0)$ and from $\phi'(x_0) = \xi_0$ it follows that

$$\left|\langle u, \varphi e^{i\lambda\phi}\rangle\right| \le C_N \lambda^{-N}, \qquad \forall N$$

(the linearity of ϕ does not matter)

—— · ——

Let $\Omega \subset \mathbb{R}^n$, $\theta \in \mathbb{R}^N$, $a(x,\theta) \in S^m_{1,0}(\Omega \times \mathbb{R}^N)$.

Φ — phase function.

$$\langle A, u\rangle = \int a(x,\theta) e^{i\phi(x,\theta)} u(x)\, dx\, d\theta =$$

GELFAND-P000591

$$= \lim_{\varepsilon \to 0} \int a(x,\theta) e^{i\phi(x,\theta)} u(x) \chi(\varepsilon\theta)\, dx\, d\theta$$

Φ - фазовая ф-я $\quad \langle A, u\rangle = \int a(x,\theta)\, e^{i\,\varphi(x,\theta)}\, u(x)\, dx\, d\theta =$

Original source details: GELFAND-P000590

Uncertain reading. An uppercase Φ precedes "phase", and a lowercase ϕ appears in the exponent.

Uncertain reading. The overwritten sign before (x) tentatively reads u.

Original source details: GELFAND-P000590



Diagram and typed description.



Original source details: GELFAND-P000591

Let $\phi'_\theta(x_0, \theta_0) \neq 0$. Write the decomposition $a = a_1 + a_2$,

(example: $a = 1$, $\phi = \langle x, \theta\rangle$, $\langle A, u\rangle = u(0)$, i.e. $A(x) = \delta(x)$.).

Undeciphered passage. A short entry before "i.e." is crossed out.

Original source details: GELFAND-P000591

where a_2 is supported in a conic neighbourhood of (x_0, θ_0), and $a_1(x, \theta) = 0$ in a neighbourhood of the point (x_0, θ_0).



Original source details: GELFAND-P000591

Undeciphered passage. An entry after "in" is crossed out. "Point" is inserted below the line.

$$\langle A_2, u\rangle = \int a_2(x,\theta) e^{i\phi(x,\theta)} u(x)\, dx\, d\theta, \qquad \text{here } \phi'_\theta \neq 0 \Rightarrow A_2 \in C^\infty.$$

$$C_\phi = \{(x,\theta) : \phi'_\theta = 0\}$$

Theorem. ~~WF~~ Consider the map

$$\lambda_\phi : C_\phi \longrightarrow \Omega \times (\mathbb{R}^n \setminus 0),$$
$$(x,\theta) \longrightarrow (x, \phi'_x).$$

Denote $\lambda_\phi(C_\phi) = \Lambda_\Phi$.

Then $\mathrm{WF}(A) \subset \Lambda_\Phi$.

Original source details: GELFAND-P000591

Uncertain reading. The sign following WF(A) is retraced and reads as $\subseteq$.

—— · ——

Nondegenerate phase functions — if $\mathrm{rank}(\phi''_{\theta x}, \phi''_{\theta\theta}) = N$ on C_ϕ.

Then λ_ϕ — a local diffeom. and Λ_ϕ — a conic Lagrangian manifold, i.e. $\langle \xi, dx\rangle|_{\Lambda_\phi} = 0$.

Original source details: GELFAND-P000591

Undeciphered passage. A short mark between "and" and Λ_ϕ is crossed out.

Conversely: $\forall$ conic Lagr. manifold can locally be obtained from a nondegenerate phase function (and one can take $N = n$).

—— · ——

~~Let there be 2 nondegenerate phase functions.~~



Original source details: GELFAND-P000591

Undeciphered passage. The crossed-out ending tentatively begins "Обра…" ("Converse…").

Check of the Lagrangian property:

$$\phi'_\theta(x,\theta) = 0 \;\Rightarrow\; \phi(x,\theta) = 0$$

$$\phi'_\theta(x+dx,\theta+d\theta) = 0, \qquad \phi'_x\,dx + \underbrace{\phi'_\theta\,d\theta}_{\text{“0”}} = 0.$$

hence $\phi'_x\,dx = 0$ on Λ_ϕ, or $\xi\,dx = 0$ on Λ_ϕ. $\triangleright$.

—— · ——

Let there be 2 phase functions ϕ_1 and ϕ_2,

$$\lambda_{\phi_1} : C_{\phi_1} \to \Lambda_\phi, \qquad \lambda_{\phi_2} : C_{\phi_2} \to \Lambda$$

Uncertain reading. A subscript is visible on the first target Λ and tentatively reads ϕ.

Original source details: GELFAND-P000591

(Λ is the same).

$$(x_0,\theta_1^0) \longrightarrow (x_0,\xi_0),$$
$$(x_0,\theta_2^0) \longrightarrow (x_0,\xi_0).$$

The class of functions A will be the same for ϕ_1 and for ϕ_2.

—— · ——

FIO:



Undeciphered passage. Two entries by X, Y are heavily crossed out.

Original source details: GELFAND-P000591

X, Y — 2 manifolds, Λ — a closed conic Lagr. manifold without singularities in $T^*(X \times Y) \setminus 0$.

Then locally Λ is given by means of a phase function $\phi(x,y,\theta)$. (In a neighbourhood of the point (x_0,ξ_0,y_0,η_0))

Undeciphered passage. A mark before “point” is heavily crossed out.

Original source details: GELFAND-P000591

and choose an amplitude a and define the operator by means of the kernel

$$\int a(x,y,\theta)e^{i\phi(x,y,\theta)}u(x,y)\,dx\,dy\,d\theta$$

Undeciphered passage. A short entry to the right of the integral is crossed out.

Original source details: GELFAND-P000591

GELFAND-P000592

[source number: 4]

Kirillov. Fact: M — a sympl. manifold, ω — the corresponding form.

Undeciphered passage. A short entry after "form" is crossed out.

Original source details: GELFAND-P000592

on M there is a Lagrangian foliation.

Diagram and typed description.



Original source details: GELFAND-P000592

Then there is an invariantly defined affine structure on its leaves.

Uncertain reading. A mark before "If" is crossed out.

Original source details: GELFAND-P000592

If the functions on M are constant on the leaves of the foliation, then their gradients (vectors corresponding to the covectors $d\varphi$) define parallel transport there. The corresponding vector fields commute.

$$\varphi \longrightarrow d\varphi \longrightarrow \xi_\varphi.$$

— these vector fields ~~commute~~ are called parallel.



Uncertain reading. The crossed-out word tentatively repeats “commute”.

Original source details: GELFAND-P000592

Corollary: the leaves — $\mathbb{R}^n$ or tori.

“Kokas.” construction — an example of a Lagr. foliation.

Uncertain reading. The overwritten abbreviation tentatively reads “Кокас.” (“Kokas.”).

Original source details: GELFAND-P000592

— · —

Tulovskii.

In the general case:

$$\sum_j \int a_j(x,y,\theta_j) e^{i\phi_j(x,y,\theta_j)} u(x,y)\, dx\, dy\, d\theta_j$$

— this is an FIO.

~~Theorem.~~

This is a class of operators for which $\mathrm{WF}(A) \subseteq \Lambda$ and which act well on rapidly oscillating exponentials.



Uncertain reading. The sign between $\mathrm{WF}(A)$ and Λ reads as $\subseteq$.

Original source details: GELFAND-P000592

Uncertain reading. The overwritten word reads as “which”.

Original source details: GELFAND-P000592

Let (x, Ψ'_x) be transverse to Λ.

$$A(e^{it\Psi}\varphi) \sim e^{it\phi} \sum_{j=0}^{\infty} b_j(x) t^{-\lambda_j}$$

Then this is an FIO.

— · —

GELFAND-P000593

[The upper part of the frame contains no text.]

10/III–75. Gelfand's sem.

Tulovskii. (continued) $\Omega_x \subseteq \mathbb{R}^{n_x}$, $\Omega_y \subseteq \mathbb{R}^{n_y}$.

$$Au(x) = \int a(x,y,\theta) e^{i\phi(x,y,\theta)} u(y)\, dy\, d\theta$$

$$A : \mathcal{E}'(\Omega_y) \longrightarrow \mathcal{D}'(\Omega_x)$$

With Φ is associated a Lagr. manifold

$$\Lambda \subset (\Omega_x \times \Omega_y) \times (\mathbb{R}^{n_x+n_y} \setminus 0)$$

Original source details: GELFAND-P000593

Uncertain reading. The overwritten sign after Λ reads as $\subset$.

PDO case: $\Lambda = (x, \xi, x, -\xi)$.

Original source details: GELFAND-P000593

Undeciphered passage. A short entry to the right of the formula is crossed out.

Question from G.: it would be good to construct this in the p-adic case.

When is the kernel $A(x,y)$ — the kernel of an FIO?

Tulovskii's answer:

$$1) \quad \mathrm{WF}(A) \subset \Lambda \qquad (\Lambda \text{ — some Lagr. manifold})$$

$$2) \quad \forall \Psi : \{(x, \Psi'_x, y, \Psi'_y)\} \text{ transverse to } \Lambda \quad \Rightarrow$$

$$\langle A, e^{it\Psi}\varphi(x,y)\rangle \sim \sum e^{it\tilde{\Psi}} a_j(t, \ldots)$$



Original source details: GELFAND-P000593

Undeciphered passage. A line beneath the asymptotic expression is heavily crossed out.

and $\widetilde{\Psi}$ is related to Ψ through Λ.

Thm. 1. $P(x, D_x)$ — a first-order PDO with real principal part $p(x, \xi)$, $p(x_0, \xi_0) = 0$,

$$p'_{x,\xi}(x_0, \xi_0) \neq 0 \quad \Rightarrow \quad \exists\, 2 \text{ FIOs}$$

$$A : \mathcal{E}'(\Omega_x) \longrightarrow \mathcal{E}'(\mathbb{R}^n),$$
$$B : \mathcal{E}'(\mathbb{R}^n) \longrightarrow \mathcal{E}'(\Omega_x)$$

$$\mathrm{WF}\left[P - B\frac{\partial}{\partial X_n}A\right] \not\ni (x_0, \xi_0, x_0, -\xi_0)$$

Uncertain reading. There are crossed-out strokes immediately after the first ξ_0.

Original source details: GELFAND-P000593

Moreover

$$\mathrm{WF}(B \circ A - I) \not\ni (x_0, \xi_0; x_0, -\xi_0)$$

Uncertain reading. The overwritten letters read as B and A. A small circle is visible between them.

Original source details: GELFAND-P000593

~~Theorem~~

Thm. 2 $P(x, D_x)u = f$,

$$H_p = \sum \left(\frac{\partial p}{\partial x_j}\frac{\partial}{\partial \xi_j} - \frac{\partial p}{\partial \xi_j}\frac{\partial}{\partial x_j}\right)$$

Undeciphered passage. A short mark between f and H_p is crossed out.

Original source details: GELFAND-P000593

$$\mathrm{WF}(u) \setminus \mathrm{WF}(f) \subset \{p(x, \xi) = 0\}$$

and invar. under the Ham. field H_p.

next time R. L. Dobrushin.

GELFAND-P000594

I. Bernstein. WF of a left ideal of diff. operators with polynomial coeffs.

Uncertain reading. The crossed-out abbreviation after “ideal” tentatively reads “oper.”.

Original source details: GELFAND-P000594

$$= \{(x_0, \xi_0) : \dddot{-} p(x_0, \xi_0) = 0,\ \forall p\}$$

Uncertain reading. The initial sign before p is heavily overwritten. The ending $\forall p$ is clear.

Original source details: GELFAND-P000594

Thm. $\dim \mathrm{WF} \geq \dim X$.

GELFAND-P000595

[The upper part of the frame contains no text.]

17/III–75. Gelfand's sem.

Seminar programme:

Dobrushin R. L.

Objects

1) random fields with a discrete argument

X — ~~measurable space~~ a finite set



Uncertain reading. The crossed-out expression tentatively reads "measurable space".

Original source details: GELFAND-P000595

T — a countable set

$$X^T = (x_t,\ t \in T)$$

A random field — a prob. measure on X^T.

Physical interp. — spin systems

2) point random fields

T — a continuous space $\mathbb{R}^\nu$

Realizations — ~~finite~~ subsets of $\mathbb{R}^\nu$, $\cap$ of which with $\forall$ finite volume is finite.



Uncertain reading. The crossed-out word tentatively reads "finite".

Original source details: GELFAND-P000595

A measure on realizations — a point random field.

$$3) \qquad \underset{\substack{\downarrow \\ \text{functions (real)}}}{X(t)} \quad , \quad t \in \mathbb{R}^\nu \qquad S^*(\mathbb{R}^\nu)$$

a random field — a measure on S^*

$\Rightarrow$ quantum field theory.

GELFAND-P000596

Problem: description of random fields

$$T = \mathbb{Z}, \qquad X^{\mathbb{Z}}\ (x_t,\ t \in \mathbb{Z})$$

Def

$$\Pr(x_n \mid x_k,\ k \le n) \underset{\text{Markov}}{=} \Pr(x_n \mid x_{n-1}) \qquad \text{(Markov chain)}$$

Cond. prob. is known.



Uncertain reading. The condition on the left reads $k \le n$.

Original source details: GELFAND-P000596

Task: first specify the conditional probability, then see which measures have these conditional probabilities.

—— · ——

$$V \subset \mathbb{Z}^\nu, \quad \text{specify} \quad \Pr\{\xi_n,\ n \in V \mid \xi_k,\ k \in \mathbb{Z}^\nu \setminus V\}.$$

—— · ——

Conditional probability: $(X, \mathcal{B}, \mu)$ — a prob. space.

$$\mu(A \mid B) = \frac{\mu(A \cap B)}{\mu(B)} \qquad \text{— insufficient}$$

Let $\widetilde{\mathcal{B}}$ — be a subalgebra in $\mathcal{B}$

Conditional probability — measure on $\mathcal{B}$, depending on $x \in X$



Uncertain reading. The crossed-out word under the insertion “measure” tentatively reads “function”.

Original source details: GELFAND-P000596



Uncertain reading. An entry before $\mathcal{B}$ is crossed out.

Original source details: GELFAND-P000596

$$\mu(\cdot \mid x), \quad x \in X. \qquad\qquad \mu(B \mid x), \quad B \in \mathcal{B},\ x \in X.$$

1) $\forall B:\ \mu(B \mid x)$ is measurable on $\widetilde{\mathcal{B}}$

2)

$$\int \psi(x)\varphi(x)\mu(dx) = \int \psi(x)\mu(dx \mid y)\varphi(y)\mu(dy)$$

(φ is measurable with respect to $\widetilde{\mathcal{B}}$)

Then the corresponding μ is called the conditional probability distribution.

In a broad class of cases $\exists$ and uniqueness..

Diagram and typed description.



The exact shape of the crossing marks on the middle segment is unclear.

Original source details: GELFAND-P000596

here the measure $\overset{\mu(B|x)}{\uparrow}$ sits on the segment. One must take Borel sets (rather than Lebesgue-measurable ones).

In this example:

$$\int \psi(x_1, x_2)\varphi(x_2)\,dx_1\,dx_2 = \int \left(\int \psi(x_1, x_2)\,dx_1 \right) \varphi(x_2)\,dx_2$$

$$\mathcal{P}\big(B \mid (\xi_\alpha, \alpha \in A)\big\}. \qquad \mathcal{P}_{\mathcal{B}(\xi_\alpha, \alpha \in A)}(B \mid X)$$



Uncertain reading. The first expression uses round parentheses and ends with a closing brace.

Original source details: GELFAND-P000596

$$\xi_\alpha : X \underset{\text{functions}}{\longrightarrow} F_\alpha \qquad \text{or one} \quad \xi : X \to F \quad \text{(into the direct product)}$$

points of F — layers

preimages of sets in F — $\widetilde{\mathcal{B}}$

↓ there the σ-algebra $\mathcal{B}_F$.

— · —

GELFAND-P000597

Gelfand Sem. 31/III-75

Polyakov (Sasha) On the idea of [inserted above the line and outlined: “spontaneously”] broken symmetries

“Bubbles in the ether of quant. field theory are particles”

Skyrme; Nielsen, Olsen, Faddeev, Polyakov, ’t Hooft.

Next time — Nevanlinna theory (following Griffiths)

GELFAND-P000598

7/IV-75. Gelfand Sem.

King (?) Nevanlinna theory following Griffiths.

Uncertain reading. The manuscript places a question mark in parentheses after “King”.

Original source details: GELFAND-P000598

2 ideas. 1) hyperbolic analysis

$$\underset{\text{holomorphic}}{f} : X \to V \qquad \text{negatively curved}$$

$\Rightarrow$ there are some restr. on behaviour of f.

2) “counting” of volume of divisers of analytic sets by residue calculus.

First 2)

g — holom. function, $D = \{g^{-1}(0)\}$

Diagram and typed description.

In the left margin two curved strokes cross a nearly vertical line. Their direction and exact closure are unclear.

Original source details: GELFAND-P000598

integral over a neighbourhood of a form (of lower order).

Let η — any form of deg. r on $\mathbb{C}^n \setminus D$

[outlined above the line] $\leftarrow$ this too is a form

$$\eta = \frac{dg}{2\pi i g} \wedge \zeta + \xi, \qquad \zeta, \xi \text{ — forms, [crossed out] then}$$

Uncertain reading. An entry before “then” is crossed out.

Original source details: GELFAND-P000598

$$\lim_{\varepsilon\to 0}\int_{C(\varepsilon)}\eta = \zeta|_D$$

η, ζ — currents (current) (functionals on forms): ~~so~~ the easiest way to define them:



Uncertain reading. A short entry before η, ζ is crossed out.

Original source details: GELFAND-P000598

Current:

$$T : A_c^k(V) \to \mathbb{C}$$

$$\lambda \in L^1_{\text{loc}}\ r\text{-form} \quad \Rightarrow \quad [\lambda](\varphi) = \int_X \lambda\wedge\varphi,$$

$$dT(\varphi) = \pm T(d\varphi).$$

The form $\zeta|_D$ defines a current:

$$[\zeta|_D](\varphi) = \int \zeta\wedge\varphi.$$

Def. Let η — L^1_{loc} form, $\in C^\infty$ on ^{D} an open dense set



Uncertain reading. D is written above the line, next to the outline.

Original source details: GELFAND-P000598

$$\operatorname{Res}\eta = [\zeta|_D] := d[\eta] - [d\eta]$$

[at right below the outlined line] η — an ordinary form



Uncertain reading. An entry below “ordinary form” is crossed out. It tentatively begins “(on”.

Original source details: GELFAND-P000598

$$d[\eta](\varphi) \underset{\text{def}}{=} [\eta](d\varphi) = \int_V \eta \wedge d\varphi$$
$$= \lim_{\varepsilon \to 0} \int_{V - U_\varepsilon(D)} \eta \wedge d\varphi =$$
$$= \int_V d\eta \wedge \varphi - \lim_{\varepsilon \to 0} \int_{\partial U_\varepsilon(D)}$$
$$= \int_V d\eta \wedge \varphi - \int_D \dots$$

Example:

$$\eta = \frac{dz}{z}, \qquad [\eta](\varphi) = \int \frac{dz \wedge \varphi}{z}$$

$$d[\eta](\varphi) - [\eta](d\varphi) = \lim_{\varepsilon \to 0} \int_{\text{[overwritten]}} \varphi \, dz = \varphi(0).$$



Uncertain reading. The round mark below the integral is overwritten and may be O. A short stroke above it is also crossed out.

Original source details: GELFAND-P000598

Res η — a current.!

g — holom. function on $\bar{V}$.



Uncertain reading. There are separate strokes above V, tentatively read as an overbar.

Original source details: GELFAND-P000598

$$\Rightarrow \quad \operatorname{Res}\left[\frac{dg}{2\pi i g}\right] = [Z],$$

$$Z = \{g = 0\}, \quad Z = \bigcup Z_i, \quad \operatorname{ord} g = m_i \text{ [overwritten] } Z_i$$



Uncertain reading. The word before Z_i is overwritten and may read “on”.

Original source details: GELFAND-P000598

$$Z = \sum m_i \int_{Z_i} \qquad \text{(as a current)}$$

GELFAND-P000599

Let $X \subset V$; Codim $X = 1$.

$$X \cap U_i = \{g_i = 0\} \qquad f_{ij} = \frac{g_i}{g_j} \text{ in } U_i \cap U_j$$

Diagram and typed description.

$$\begin{array}{c} L_X \\ \downarrow \\ V \end{array}$$

Original source details: GELFAND-P000599

$$\sigma = \{g_i\}, \quad \sigma \in \Gamma(L_X).$$

$\sigma = 0$ on X.

—— · ——

Let L have a Herm. metric (L — a 1-dim. bundle)
We can consider $|\sigma|^2 \in C^\infty$ on V and $= 0$ on X.

$$\eta = \frac{1}{2\pi i}\partial \log |\sigma|^2, \qquad \partial \log |z|^2 = \frac{dz}{z}.$$

Then Res $\eta = [X]$.

$$[d\eta] = \frac{\bar\partial\partial}{2\pi i} \log |\sigma|^2 = \frac{\bar\partial\partial}{2\pi i} \log h_i = c(L_D).$$

(Chern class)

where $|\sigma|^2 = h_i |g_i|^2$

$$\partial\bar\partial \log \bar g_i = 0$$

Uncertain reading. The separate line has a bar over the second ∂ and over g_i.

Original source details: GELFAND-P000599

De Rham's thm. holds! (in currents):

$$\underline{X = d[\eta] + [c(L_D)]}$$

(the Chern class is cohomologous to the zero set of any section)!

—— · ——

Let ψ — a closed form. [inserted above the line and outlined: Then]

$$\int_X \psi = \int_V c(L_D) \wedge \psi.$$

Bézout-type theorems. Let X, Y [crossed out] — two curves in $\mathbb{CP}^2$.



Original source details: GELFAND-P000599

Uncertain reading. A short mark after X, Y is crossed out.

$$X = d[\eta_X] + \varphi_X$$
$$Y = d[\eta_Y] + \varphi_Y$$



Original source details: GELFAND-P000599

Uncertain reading. The last term of each equation is heavily inked and reads φ_X, φ_Y.

(φ_X — Chern cl.)
[crossed out] for X — $[c(L_D)]$



Original source details: GELFAND-P000599

Uncertain reading. A small mark before "for" is crossed out.

Consider

$$\int_V \varphi_X \wedge \varphi_Y = \int_X \varphi_Y = [X \wedge Y](1)$$

(number of intersection points =
= prod. of Chern classes)

Example: $V = \mathbb{P}^2, \quad X, Y = H$. (hyperpl.)

$$d_X = \deg X = \#(X \cap H) = \int_X \omega$$

(ω — std. form dual to the hyperpl. section)

$$\varphi_X = X \sim \text{[small mark]}$$



Uncertain reading. The short mark after $\sim$ resembles a small angle.

Original source details: GELFAND-P000599

$$\int_{\mathbb{P}^2} \varphi_X \wedge \varphi_Y = d_X d_Y \int_{\mathbb{P}^2} \omega^2 = d_X \cdot d_Y$$

— this is the proof of Bézout's thm. on the number of intersection points of curves.

GELFAND-P000600

X with singularities $\Rightarrow$ the thm. still holds (Lelong, 1953)

—— · ——

1) idea.

$$f : \mathbb{C}^n \xrightarrow[\text{holom.}]{} V$$

[below $\mathbb{C}^n$:] $\varphi \leftarrow$ Eucl. Kähler
[arrow to V:] compact. Kaehler ([inserted above the line and outlined: with] form ω).
Let $B(r)$ — be the ball of rad. r.

$$\text{vol}(f(B(r))) = \int_{B(r)} f^*(\omega^n)$$

Diagram and typed description.



The right end of the horizontal axis is thickened. An arrowhead cannot be established.

Original source details: GELFAND-P000600

[at right] Γ [overwritten subscript] [inserted above the line and outlined: part] of the graph of f. over $B(r)$

Uncertain reading. The subscript of Γ is heavily overwritten and may be f or r.

Original source details: GELFAND-P000600

$$\int_{\Gamma(r)} (\varphi+\omega)^n = \sum \binom{n}{k} \int_{B(r)} \varphi^k \wedge f^*\omega^{n-k}$$

Def.

$$T_k(f,r) \underset{\text{def}}{=} \int_{B(r)} \varphi^{n-k} \wedge f^*(\omega^k)$$

In many cases $T_k = O(T_1)$ (growth in r).

[below the line] of the same order.



Diagram and typed description.

$$\begin{array}{ccc} L & \longleftarrow & \text{holom. line bundle.} \\ \downarrow & & \\ f:\ \mathbb{C}^n & \longrightarrow & V \end{array}$$

Original source details: GELFAND-P000600

Let $0 < \omega = c(L)$ — its Chern class

Let $\sigma \in O(L), \quad D = \{\sigma = 0\}$.

$$d[\eta] - [\omega] = [D]; \qquad D_f = f^{-1}D.$$

$$d[f^*\eta] - [f^*\omega] = [f^{-1}D] \quad \text{(on } \mathbb{C}^n\text{)}.$$

Mult. by $\chi_{B(r)}\varphi^{n-1}$:

$$\underbrace{\int_{S(r)} \varphi^{n-1} \wedge f^*\omega}_{\text{“}T_1} = \int_{D_f} \chi_{B(r)}\varphi^{n-1}.$$

Uncertain reading. The integral subscript tentatively reads $S(r)$.

Original source details: GELFAND-P000600

$$\eta = \underbrace{\frac{1}{4\pi} \text{[crossed out]}\ (\bar\partial - \partial) \log|\sigma|^2}_{d^c}.$$



Uncertain reading. A mark before $(\bar\partial - \partial)$ is crossed out and may be i.

Original source details: GELFAND-P000600

$$\int_{D_f \cap B(r)} \varphi^{n-1}$$

(volume of the zero set, meas. using the std. φ).

Uncertain reading. The abbreviation after "zero set" tentatively reads "помер." (meas.).

Original source details: GELFAND-P000600

$$T_1 = \int_0^r \frac{t_1(f,\varphi)}{\rho}\, d\rho$$

— $t_1 \leftrightarrow T_1$ in ordinary Nevanlinna th..



Uncertain reading. The argument of t_1 resembles φ. The denominator and differential have ρ.

Original source details: GELFAND-P000600

GELFAND-P000601

Uncertain reading. The beginning of a formula $N(\ldots)$ is heavily crossed out.

Original source details: GELFAND-P000601

$$N(D_f, r) = \int_0^r \frac{\int_{D_f \cap B(\rho)} \varphi^{n-1}}{\rho^{n+1}}\, d\rho$$



Uncertain reading. The argument of $B(\rho)$ is overwritten and reads ρ.

Original source details: GELFAND-P000601

$$N(D_f, r) \le T(f, r) + O(1) \qquad \text{(1st Nevanlinna inequality)}$$

GELFAND-P000602

14/IV-75. Gelfand Sem. King (continued).

$$\mathbb{C}^n \xrightarrow{f} \underset{\text{projective}}{V^n}, \qquad \underset{\text{divisor.}}{D} \subset V^n, \qquad D \sim c(L_D) = \underset{\text{Kähler form}}{\omega}$$

$$N(D_f, r) \le T(f, r)$$

[below N:] volume of the preimage of the divisor ("number of zeros")
[below T:]

$$\int_0^r \int''_{B(r)} f^*\omega \wedge \psi^{n-1} \frac{dt}{t}$$

("order of growth")



Uncertain reading. Two short vertical strokes are written above the second integral.

Original source details: GELFAND-P000602

[at right] (1st Nevanlinna thm. — triv.)
uses the residue thm.

$$\operatorname{Ric}\Omega = i\partial\bar\partial \log g \quad \Leftarrow \quad \left(\Omega = \frac{i}{2} g\, dz \wedge d\bar z\right).$$

(Ricci tensor).

$$n = 1 \quad \Rightarrow \quad \operatorname{Ric}\Omega = K\Omega \quad (K = -\text{gaussian curvature})$$



Original source details: GELFAND-P000602

Uncertain reading. The long stroke after $K =$ is read as a minus sign.

Ω — an (n, n) volume form

$$a(\cdot)\, dz_1\, d\bar{z}_1 \ldots dz_n\, d\bar{z}_n$$

$$\operatorname{Ric}\Omega = \frac{i}{2\pi}\partial\bar{\partial}\log a$$

1) $\operatorname{Ric}\Omega > 0$

2) $(\operatorname{Ric}\Omega)^n \geq \Omega$ (vol. form).

Ahlfors Lemma.

Let B^n or Δ^n have a Bergman form with curv. [overwritten] -1



Uncertain reading. A heavily overwritten mark before -1 resembles H or K.

Original source details: GELFAND-P000602

$\Rightarrow$ $\forall$ holom. $f : B^n \to V^n$; $\quad \Omega_V$ — volume form with neg. curv.



Uncertain reading. The letter before the superscript n is overwritten and tentatively reads V.

Original source details: GELFAND-P000602

$f^*\Omega_V \leq \Phi_B$ — volume form

$\ldots$ ___ $\cdot$ ___ $\ldots$

~~Acta~~ Acta Math.; Griffits, King, [crossed out]

Uncertain reading. A small mark after “King,” is crossed out and may read “a”.

Original source details: GELFAND-P000602

Herman $\Rightarrow$ Joahim Weil



Uncertain reading. The name and connecting sign are tentative. The end of “Joahim” is heavily inked.

Original source details: GELFAND-P000602

A nontriv. formulation is needed in the theory of eigenfunctions.

Griffits, Cowen

Chapter 9

GELFAND-P000603

15.9.75. Gelfand Sem.

There will be a series of lectures by Polyakov on physics.

Kirillov. Thm. J. Vey on deformation of the Poisson bracket.

Uncertain reading. The initial reads “J.”.

Original source details: GELFAND-P000603

(M, ω) — a sympl. manifold, $[u, v]$ — the Poisson bracket. There are essentially no other Lie alg. structures (Kirillov et al.). But if diff. oper. of order ∞ are allowed, the structure can be deformed.

Thm.: $\exists$ a formal deformation of the Poisson bracket, inequivalent to it.

$$[u, v]_t = \sum_{k=0}^{\infty} t^k [u, v]^{(k)}$$

[stroke from $[u, v]^{(k)}$:] oper. of order $(2k + 1)$ in u and v.

nontriviality: a change of coordinates does not reduce it to the original Poisson bracket.

$$[u, v]^{(k)} = \frac{1}{(2k+1)!} \left(\frac{\partial^{2k+1} u}{\partial p^{2k+1}} \frac{\partial^{2k+1} v}{\partial q^{2k+1}} - \frac{\partial^{2k+1} u}{\partial q^{2k+1}} \cdot \frac{\partial^{2k+1} v}{\partial p^{2k+1}} \right) + \dots$$

lower terms

On the plane (or torus) there are no lower terms.



Uncertain reading. The abbreviation in both places tentatively reads “мл.” (lower).

Original source details: GELFAND-P000603

Defined globally on M provided that $H^3(M, R) = 0$.

$$? \qquad pq - qp = t$$

GELFAND-P000604

Polyakov. (Alexander Markovich).

Elementary particle physics.

γ — photon. — a separate group

Leptons

$$\left.\begin{array}{ll} e^- & m = 0{,}5 \\ \mu^- & m = 105 \\ \nu_e & m = 0 \\ \nu_\mu & m = 0 \end{array}\right\} \text{ neutrinos}$$

Hadrons.

$$\begin{array}{ll} p & m = 940 \\ n & \text{— } \| \text{ —} \\ \pi & m = 140 \end{array}$$

etc.

Uncertain reading. The top stroke of π is separate from the lower strokes.

Original source details: GELFAND-P000604

Interactions: Intensity in units $x = \dfrac{E_{\text{int}}}{m}$

Gr	(gravit.)	$x \sim 10^{-38}$
W	(weak)	$x \sim 10^{-5}$
EM	(electromagn.)	$x \sim 10^{-2}$
S	(strong)	$x \sim 1$

The weaker the interact., the more accommodating it is (it violates fewer conservation laws).

They are distinguished only by symmetry (the strong from the weak, since both are [crossed out] short-range).



Undeciphered passage. The word after “both” is heavily crossed out.

Original source details: GELFAND-P000604

Leptons — all interact. except the strong.

Hadrons — all 4 interactions.

Quantum electrodynamics describes the electromagn. interact. of leptons. (the others are weaker and are ignored for now).

A particle is described by its own field. One must specify the action:

$$S = S[e(x), \mu(x), \dots]$$

Invariance: rot., transl., Lorentz transf..

Exper. fact: under rot. the electron transf. according to the spinor representation

$$\begin{pmatrix} e_1' \\ e_2' \end{pmatrix} = \exp\left(\frac{i}{2}(\bar{\sigma}\,\bar{\Theta})\right)\begin{pmatrix} e_1 \\ e_2 \end{pmatrix}$$

($e_j \in \mathbb{C}$ — components of the spinor)

$\bar{\sigma}$ [crossed out] — Pauli matrices (a set of 3 such matrices); $\bar{\Theta} \in \mathbb{R}^3$;



Uncertain reading. The entry after $\bar{\sigma}$ is heavily crossed out.

Original source details: GELFAND-P000604

$|\bar{\Theta}|$ — angle of rot., dir. of Θ — dir. of the axis of rotation.

GELFAND-P000605

$$\sigma_x = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \quad \sigma_y = \begin{pmatrix} 0 & -i \\ i & 0 \end{pmatrix}, \quad \sigma_z = \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix}.$$

Uncertain reading. There is a short stroke before the upper right 1 in σ_x. It may be a minus.

Original source details: GELFAND-P000605

Calc. also the transf. under the action of the Lorentz group. 2 possibilities:

Uncertain reading. The initial abbreviation tentatively reads “Вычис.” (calc.).

Original source details: GELFAND-P000605

$$e'_L = \exp\left(\frac{\bar\sigma\bar\psi}{2}\right) e_L,$$

where $\bar\psi$ — a vector collinear with the velocity vect.:

$$v = \operatorname{th}|\bar\psi|, \qquad \frac{\vec v}{|\bar v|} = \frac{\bar\psi}{|\bar\psi|} \qquad (\bar\psi \text{ — also a 3-vector})$$

[below the line] “rapidity”

$$e'_R = \exp\left(-\frac{\bar\sigma\bar\psi}{2}\right) e_R$$

Explan. (G.) [crossed out]. $SO(3) \longrightarrow$ [crossed out]. $SU(2)$.

Original source details: GELFAND-P000605

Undeciphered passage. An entry before $SO(3)$ is crossed out.



Original source details: GELFAND-P000605

Undeciphered passage. An entry before $SU(2)$ is crossed out.



Original source details: GELFAND-P000605

Uncertain reading. The handwritten arrow points from $SO(3)$ to $SU(2)$.

$$\bar\Theta \text{ — rot. in } \mathbb{R}^3 \Longrightarrow \text{matr.} \in SU(2)$$

(representation of $SU(2)$)

This rep. extends to a rep. of the Lorentz group.

Lorentz transf. — the velocity vector $\vec v$ (rotation is omitted) (proper Lorentz transf.)

Rapidity $\bar\psi$ — introduced in place of $\bar v$

P.

$$\begin{cases} t' = t\,\mathrm{ch}\,\psi + z\,\mathrm{sh}\,\psi \\ z' = z\,\mathrm{ch}\,\psi + t\,\mathrm{sh}\,\psi \end{cases}$$

Original source details: GELFAND-P000605

Uncertain reading. In the first line z is written over an earlier mark.

[at right] — Lorentz transf. written in terms of ψ. (proper Lorentz transf. — with no added rot. or translation).

The electron is either e_L or e_R.

But there is a symmetry $\vec{x} \longrightarrow -\vec{x}$, $\vec{v} \longrightarrow -\vec{v}$, they turn into each other.

If reflection is adjoined, the rep. is only obtained in combined form:

$$\hat{p}\begin{pmatrix} e_L \\ e_R \end{pmatrix} = \begin{pmatrix} e_R \\ e_L \end{pmatrix}.$$

We need to introd. a bispinor: $\begin{pmatrix} e_L \\ e_R \end{pmatrix}$.

Then the Lagrangian density:

$$\mathcal{L}' = e_L^+(x)\left\{\frac{\partial}{\partial t} - \left(\bar{\sigma}\frac{\partial}{\partial \bar{x}}\right)\right\} e_L(x) + e_R^+(x)\left\{\frac{\partial}{\partial t} + \left(\bar{\sigma}\frac{\partial}{\partial \bar{x}}\right)\right\} e_R(x)$$

$(z^+ = \bar{z})$.

Action: $S = \int \mathcal{L}\, dt\, d^3\bar{x}$.



Original source details: GELFAND-P000605

Uncertain reading. No prime is visible on $\mathcal{L}$ in the action formula.

Invariance is easy to check.

Masslessness Lagr. eq.

$$\left(\frac{\partial}{\partial t} - \bar{\sigma}\frac{\partial}{\partial \bar{x}}\right) e_L = 0$$

Take the Fourier transf.: $(E - \bar{\sigma}\bar{p})e_L = 0$ and hence $E^2 = p^2$.

GELFAND-P000606

Hence E is arbitrarily small (for small p) $\Rightarrow m = 0$.

We must add a term with the mass. The inv. way is unique

e_L [crossed out] ~~me~~

Original source details: GELFAND-P000606

Uncertain reading. Under the crossing-out, the mark between e_L and me resembles a right-pointing arrow.

$$m(e_L^+ e_R + e_R^+ e_L).$$

Thus, the final form of the Lagrangian:

$$\mathcal{L} = \mathcal{L}' + m(e_L^+ e_R + e_R^+ e_L).$$

Equiv. form: let $e = \begin{pmatrix} e_L \\ e_R \end{pmatrix}$. (bispinor).

$$\mathcal{L} = \bar{e}\left(i\gamma_\mu \frac{\partial}{\partial x_\mu} - m\right) e$$

$$\gamma_\mu \frac{\partial}{\partial x_\mu} = \gamma_0 \frac{\partial}{\partial t} - \bar{\gamma}\frac{\partial}{\partial \bar{x}}, \qquad \bar{e} = e^+\gamma_0$$

γ_μ — Dirac matr., $\gamma_\mu\gamma_\nu + \gamma_\nu\gamma_\mu = 2g_{\mu\nu}$,

$$g_{\mu\nu} = \begin{pmatrix} 1 & & & 0 \\ & -1 & & \\ & & -1 & \\ 0 & & & -1 \end{pmatrix}$$ — Minkowski metr..

γ_μ are written in terms of the matrices σ

(References: Landau, Berestetskii, Lifshitz, Pitaevskii — Relativistic Quant. Theory, pt. 1).

Spectrum: $E = \sqrt{p^2 + m^2}$.

(In the Dirac eq. $\left(i\gamma_\mu \frac{\partial}{\partial x_\mu} - m\right) e = 0$ we pass to the Fourier transf. and obtain this res.)

—— · ——

Gauge group $e' \Rightarrow e^{i\beta}e$. $(\beta \in \mathbb{R})$.



Original source details: GELFAND-P000606

Uncertain reading. There are two horizontal strokes between $e\prime$ and $e^{i\beta}e$. The upper stroke has a point at the right.

$\mathcal{L}$ is also invariant with resp. to this group $e' = (2,7\ldots)^{i\beta} e$

Hypothesis: vary the phase differently at different points and require covar. with resp. to these transformations (extreme locality)

$$e' = (2,7)^{i\beta(x)} e$$

Invar. is now lost:

$$\bar{e}\left(i\gamma_\mu\left(\frac{\partial}{\partial x_\mu} + i\partial_\mu\beta\right) - m\right)e.$$

$$\mathcal{L}' = \bar{e}\left(i\gamma_\mu\frac{\partial}{\partial x_\mu} + iA_\mu(x)\right) - m\Big)e$$



Original source details: GELFAND-P000606

Uncertain reading. A closing parenthesis follows $A_\mu(x)$, and another follows $-m$. No factor γ_μ is visible before $iA_\mu(x)$.

GELFAND-P000607

($A_\mu(x)$ — a connection).

$$A'_\mu(x) = A_\mu - \partial_\mu\beta.$$

$$\nabla_\mu = \partial_\mu + iA_\mu.$$

If we do this, general covariance will be restored.



Uncertain reading. The abbreviation before “covariance” reads “общ.” (general).

Original source details: GELFAND-P000607

From $\mathcal{L}'$ no eqs. arise for A_μ. We need the curvature

$$F_{\mu\nu} = \partial_\mu A_\nu - \partial_\nu A_\mu$$

This is a tensor, and in [crossed out] $\mathcal{L}$ we introd. its square.

Uncertain reading. An entry before $\mathcal{L}$ is crossed out.

Original source details: GELFAND-P000607

$$\mathcal{L} = \text{[crossed out]}\ \mathcal{L}' + \left(\frac{1}{4e^2}\right) F_{\mu\nu}^2$$

Uncertain reading. A sign before $\mathcal{L}'$ on the right-hand side is crossed out.

Original source details: GELFAND-P000607

(e — the electron charge)

—— · ——

Scattering. $S = S[\varphi(x)]$.

B $\varphi_{\text{in}}(x) \longrightarrow \varphi_{\text{out}}(x)$

Uncertain reading. A separate mark to the left of the arrow resembles a B with a vertical stroke.

Original source details: GELFAND-P000607

$$\varphi_{\text{in}}(x) = \lim_{t\to-\infty} \varphi(\bar{x}, t), \qquad \varphi_{\text{out}}(x) = \lim_{t\to+\infty} \varphi(\bar{x}, t).$$

$$\int_{\Phi_{\text{in}}}^{\Phi_{\text{out}}} D\varphi(x)\, e^{iS[\varphi]} = M \text{ — transition amplitude}$$

(functional integration, $D\varphi$ — the natural measure, [below the line] (Lebesgue), integral over all $\Phi(x,t)$, $\Phi(x,+\infty) = \Phi_{\text{out}}$, $\varphi(x,-\infty) = \varphi_{\text{in}}$)

There are rules for calculation.

[crossed out] [inserted above the line and outlined] Without A_μ — a Gaussian integral (Fresnel)

Undeciphered passage. An entry before the insertion and the words “Gaussian integral” is heavily crossed out.

Original source details: GELFAND-P000607

Then — perturbation theory (take A_μ small); $eA_\mu e$ — a cubic term

---

G. $\int e^{i(x^2+\varepsilon x^3)}\,dx$ — your theory

Important:

$$\int e^{-\sum a_{ik}x_ix_k+\varepsilon\sum x_i^3}\,dx$$

$$\int e^{ix^2(1+\varepsilon x^3)} = \sum c_k \int x^k e^{ix^2}\,dx$$



Uncertain reading. The exponent reads $ix^2(1+\varepsilon x^3)$.

Original source details: GELFAND-P000607

For this we use Feynman diagrs.

[crossed out at left] $\int \frac{}{(x^2+y^2+z^2+t\ldots)}$



Undeciphered passage. In the crossed-out entry the integral sign, fraction bar, and part of the denominator are legible.

Original source details: GELFAND-P000607

E.g.

$$\int \frac{dx\,dy\,dz\,dt}{(x^2+y^2+z^2+t^2+m_1)(x^2+y^2+z^2+t^2+m_2)}$$



Uncertain reading. A parenthesis is crossed out after the first t^2. The exponent on y in the second factor is overwritten.

Original source details: GELFAND-P000607

(stolen by F. from Schwinger)

$$\frac{1}{ab} = \int_0^1 \frac{ds}{(sa+(1-s)b)^2}. \qquad \frac{1}{abc} \text{ analogously.}$$

GELFAND-P000608

P. one can also do $\frac{1}{a^\lambda b^\mu c^\gamma}$

Uncertain reading. The exponent on a is overwritten and tentatively reads λ.

Original source details: GELFAND-P000608

$$\frac{1}{a^\lambda b^\mu} = \int_0^1 \frac{s^{\lambda-1}(1-s)^{\mu-1}}{(sa+(1-s)b)^{\lambda+\mu}}\, ds$$

$$\frac{1}{\prod a_i^{\lambda_i}} = \int_{s_i \geq 0.} \frac{\prod ds_i\, \delta(\sum s_i - 1)\, s_i^{\lambda_i - 1}}{(\sum s_i a_i)^{\sum \lambda_j}}$$



Original source details: GELFAND-P000608

Uncertain reading. Both formulas are written without a separate normalization factor.

— · —

We calculate by perturbation theory:

$x,\ x'$

Amplitude of trans. from x to x': $K(x,x')$ according to Maxwell

$$\left(i\gamma_\mu \frac{\partial}{\partial x_\mu} - m\right) K(x,x') = \delta(x-x').$$

Uncertain reading. The γ is heavily inked and may be overwritten.

Original source details: GELFAND-P000608



Diagram and typed description.



Original source details: GELFAND-P000608

Emission and absorption of a photon are accomp. by a factor e.

$$\int K(x_3 - z_1)K(z_1 - x_1)K(x_4 - z_2)K(z_2 - x_2)$$
$$D(z_2 - z_1)\, d^4 z_1\, d^4 z_2$$

D — fund. soln. of Maxwell's eqs.

Other pictures:



Original source details: GELFAND-P000608

Diagram and typed description.



The meeting of the strokes in the third sketch and the direction of the loop in the fourth are unclear.

$$(\gamma_\mu p_\mu - m)K(p) = 1$$
$$K(p) = \frac{\gamma_\mu p_\mu + m}{\underline{p}^2 - m^2}$$
$$K(x, x') = \int K(p) e^{ip(x-x')}\, d^4 p$$

The pole is bypassed if we take $K(p) = \dfrac{\gamma_\mu p_\mu + m}{\underline{p}^2 - m^2 + i0}$



Original source details: GELFAND-P000608

Uncertain reading. The last mark is open and is read as zero.

$$\underline{p}^2 = E^2 - \vec{p}^2.$$



Original source details: GELFAND-P000608

Diagram and typed description.



There are levels with neg. energy, nat. propagate backwards in time (pred. the existence of antiparticles).



Original source details: GELFAND-P000608

Uncertain reading. The abbreviation after "energy" tentatively reads "ество." (nat.).

There is a unique choice of bypass leading to a consistent theory: — nor have antiparticles



Uncertain reading. The last two lines are close together. The reading “nor have antiparticles” is tentative.

Original source details: GELFAND-P000608

GELFAND-P000609

Charge normalization.

e — is this the obs. electron charge?

Scattering: electrons exch. photons, force $\sim e^2$

Diagram and typed description.

Original source details: GELFAND-P000609

Correction: $\sim e^4$.

Diagram and typed description.



The directions of the two arrow-like strokes on the loop are unclear. The visible gaps are retained.

Original source details: GELFAND-P000609

Obs. charge $e^2_{\text{phys}} < e^2$.

In strong interact. theory the reverse holds $g^2_{\text{phys}} > g^2$.

— · —

GELFAND-P000610

22.9.75. Gelfand Sem.

Diagram and typed description.

Yellow comment icon in the upper right margin of the digitized frame.

Original source details: GELFAND-P000610

Gelfand on Atiyah's res.

$\mathfrak{A}$ — all oper. in Hilb. sp., $\mathcal{K}$ — comp. oper.

$$\mathfrak{A}/\mathcal{K} = \mathfrak{B}.$$

When are $B_1, B_2 \in \mathfrak{B}$ unitarily equivalent?

This is [crossed out] Brown, Douglas, Fillmore (Lect. Notes, $N = \ldots$)

Uncertain reading. An entry before the surnames is crossed out. It may read "Все" (all).

Original source details: GELFAND-P000610

a) spectra coincide (ess.)

b) indices coincide in [crossed out] $\forall$ conn. comp. of the complement



Undeciphered passage. An entry before the quantifier is crossed out.

Original source details: GELFAND-P000610

Thm. 2. [crossed out] Let X — be a compact space,

$$\underset{\substack{\uparrow \\ \text{set of embeddings of } C(X) \text{ in } \mathfrak{B}.}}{\mathrm{Ext}(X)} \qquad \cong K_1(X)$$



Undeciphered passage. An entry before "Let" is crossed out.

Original source details: GELFAND-P000610

—— · ——

Moser — Korteweg–de Vries

—— · ——

Kostant

$$\psi(x) = \prod_{n=1}^{\infty}(1 - x^n); \qquad \psi(x)^{-1} = \sum_{n=0}^{\infty} p(n)x^n$$

($p(n)$ — number of part. of n).

This is

$$\psi(x) = \sum (-1)^n x^{\frac{n^2-3n}{2}}$$



Uncertain reading. The exponent is written $(n^2 - 3n)/2$.

Original source details: GELFAND-P000610

- “The most remarkable formula in all of mathematics” (Jacobi).



Uncertain reading. The heavily overwritten abbreviation after “remarkable” tentatively reads “ф-ла” (formula).

Original source details: GELFAND-P000610

$$(\psi(x))^3 = \sum_{n=0}^{\infty} (-1)^n (2n+1) x^{\frac{n(n+1)}{2}}$$

$$\eta(x) = x^{1/24} \cdot \psi(x).$$

$$\eta^{24}(x) = \sum \tau(n) x^n, \qquad \tau(n) \text{ — Ramanujan's function}$$

$\psi^{10}(x)$ exists too

Manin: if 6 different fns., obt. from different considerations

$$\eta(x)^{\square} = \sum \dots$$

Macdonald found powers for which it makes sense: These are the dim of compact Lie groups.

$$\psi(x)^{\dim K} = \sum_{\lambda} \text{[crossed out]}\ \chi_\lambda(a)\ \dim V_\lambda \cdot x^{(\text{depends on } \lambda)}$$

Undeciphered passage. An entry after the summation sign and before $\chi_\lambda(a)$ is crossed out.

Original source details: GELFAND-P000610

$a \in K$, $\chi_\lambda(a) = \pm 1$ or 0

Kostant: $\mathrm{Sp}(-\Delta + a)^{-s}$ etc.

Internal [ч-ие] G.: $\psi(x)^z$ — ? $\qquad (z \in \mathbb{C})$

Uncertain reading. The middle abbreviation tentatively reads “ч-ие”.

Original source details: GELFAND-P000610

—— · ——

Polyakov. (continued).

References:

quant. mech.
1) Landau and Lifshitz (quant. mechanics). (≈ 5–7 chapters)
2) Dirac
3) Feynman (for schoolchildren)
4) Feynman. Path integrals



Uncertain reading. The word after “5–7” tentatively reads “глав” (chapters).

Original source details: GELFAND-P000610

Quant. field theory: 1st part of vol. IV Berestetskii, Lifshitz, Pitaevskii

GELFAND-P000611

$e(x)$ — field (bispinors)

$$\mathcal{L}_{\text{free}} = \bar{e}\, i\gamma_\mu \partial_\mu e - m\bar{e}e + \frac{1}{4e^2} F_{\mu\nu}^2$$

$$\mathcal{L}_{\text{int}} = \ldots \bar{e}\gamma_\mu e A_\mu \ldots \qquad \text{cont. 3-... terms}$$

Uncertain reading. The abbreviation after “3-” is uncertain.

Original source details: GELFAND-P000611

—— · ——

Localization of large int. symmetries — weak interaction.

Uncertain reading. “б-их вн.” tentatively reads “large internal”.

Original source details: GELFAND-P000611

$$\mathcal{L} = \bar{e}_L i\gamma_\mu \partial_\mu e_L + \bar{e}_R i\gamma_\mu \partial_\mu e_R + \bar{\nu}_L i\gamma_\mu \partial_\mu \nu_L +$$
$$+ \begin{pmatrix} e \to \mu \\ \nu_L \to \nu'_L \end{pmatrix} + m(\bar{e}_L e_R + \bar{e}_R e_L).$$

(all leptons) $\downarrow$

ν'_L — μ-meson neutrino

$$\mathcal{L} = \bar{e}_L i\gamma_\mu \partial_\mu e_L + \bar{\nu}_L i\gamma_\mu \partial_\mu \nu_L + \bar{e}_R i\gamma_\mu \partial_\mu e_R$$

$$\begin{cases} \begin{pmatrix} e'_L \\ \nu'_L \end{pmatrix} = U \begin{pmatrix} e_L \\ \nu_L \end{pmatrix} \qquad SU_L(2) \\ e'_R = e_R \end{cases}$$

•

A new symmetry gr. $SU(2)$ arises, and also $U(1)$

$$F = SU_L(2) \times U_R(1) \times U_L(1) \quad \text{— overall lepton group.}$$

$$\begin{pmatrix} e_L \\ \nu_L \end{pmatrix} \overset{U_L(1)}{\longrightarrow} e^{i\gamma} \begin{pmatrix} e_L \\ \nu_L \end{pmatrix}$$



Original source details: GELFAND-P000611

Uncertain reading. The letter in the phase tentatively reads γ, possibly δ.

Localization

Original source details: GELFAND-P000611

Undeciphered passage. The crossed-out entry in a box in the left margin is illegible.

[Crossed out: ~~A_μ ... electromagn. field~~.]



Original source details: GELFAND-P000611

Uncertain reading. A mark between A_μ and "electromagn. field" is obscured by the crossing-out.

Covar. derivative for $SU(2)$. $\bar{\tau}$ — Pauli matr. (3 in all)

$$\begin{pmatrix} e'_L \\ \nu'_L \end{pmatrix} = e^{i\frac{\bar{\tau}\vec{\alpha}(x)}{2}} \begin{pmatrix} e_L \\ \nu_L \end{pmatrix}, \qquad E' = e^{i\frac{\bar{\tau}\vec{\alpha}(x)}{2}} E$$



Original source details: GELFAND-P000611

Uncertain reading. The lower letter on the left and the lower subscript on the right are overwritten.

Infinitesim.:

$$E' = \left(1 - \frac{i}{2}(\bar{\tau}\bar{\alpha})\right) E$$



Original source details: GELFAND-P000611

Uncertain reading. The finite exponent is written with an implicit plus sign. A minus sign is visible in the infinitesimal expression.

$$\partial_\mu E' = \left(1 - \frac{i}{2}(\bar{\tau}\bar{\alpha})\right) \partial_\mu E - \frac{i}{2}(\bar{\tau}\partial_\mu\bar{\alpha})E$$

$$\boxed{\nabla_\mu E = \partial_\mu E + \frac{i}{2}(\vec{\tau}\vec{A}_\mu)E}$$

$$E' = e^{i\frac{\bar{\tau}\bar{\alpha}(x)}{2}} E$$

$$\nabla_\mu E' = e^{i\frac{\bar{\tau}\bar{\alpha}}{2}} \nabla_\mu E$$

Here 3 massless particles arise

GELFAND-P000612

one can write directly

$$\nabla_\mu E^\delta = \partial_\mu E^\delta + A_\mu^{\delta\beta} E^\beta$$



Original source details: GELFAND-P000612

Uncertain reading. The superscript tentatively reads δ, possibly γ.

and we look at how A transforms so that $\nabla_\mu E^\delta$ transforms like E^δ.

$$\mathcal{L}_{\text{int}} = (\bar{e}_i \gamma_\mu \nu_e) A_\mu^{(-)} + (\bar{\nu}_e \gamma_\mu e_i) A_\mu^{(+)} + (\bar{e}_L \gamma_\mu e_L - \bar{\nu}_L \gamma_\mu \nu_L) A_\mu^3$$



Uncertain reading. The electron index in the first two terms is written with a dotted i.

Original source details: GELFAND-P000612

where

$$A_\mu^\pm = A_\mu^1 \pm i A_\mu^2$$

Example of weak interaction: $\mu^- \to e^-, \bar{\nu}_e, \nu_\mu$.

$$\mathcal{L} = \bar{E}\left(i\gamma_\mu \frac{\partial E}{\partial x_\mu}\right) + \underbrace{\bar{E}\gamma_\mu \vec{\tau} E \vec{A}_\mu}_{\mathcal{L}_{\text{int}}} + \bar{e}_R i \gamma_\mu \partial_\mu e_R$$

Uncertain reading. There is a separate short stroke with dots to the left of $\mathcal{L}$. Its meaning is uncertain.

Original source details: GELFAND-P000612



Undeciphered passage. An entry beneath the left side of the bracket is crossed out.

Original source details: GELFAND-P000612

Undeciphered passage. A separate crossed-out entry in the right margin is illegible.

Original source details: GELFAND-P000612

We also localize the r. field



Uncertain reading. The abbreviation “пр.” tentatively means “right”.

Original source details: GELFAND-P000612

$$\bar{E}\left(i\gamma_\mu \frac{\partial E}{\partial x_\mu}\right) + \bar{E}\gamma_\mu \vec{\tau} E \vec{A}_\mu + \bar{e}_R i\gamma_\mu \partial_\mu e_R$$
$$+ \bar{e}_R \gamma_\mu e_R B_\mu$$
$$A_\mu = A_\mu^3 \cos\theta + B_\mu \sin\theta$$
. . . . . _ . . . . .

Next time — ≈ in 3 weeks.

12 quarks: 4 flavors and 3 colors.

Diagram and typed description.

Yellow comment icon to the right of the quark entry in the digitized frame.

Original source details: GELFAND-P000612

—— · ——

GELFAND-P000613

29.9.75. Gelfand Sem.

Yu. I. Manin.

$$x\prod_{n=1}^{\infty}(1-x^n)^{24} = \sum_{n=1}^{\infty}\tau(n)x^n; \qquad \tau \text{ — Ramanujan's function.}$$

I. M. Gelfand. (and Dikii)

∞-dimensional Lie algebra, more remarkable than all the Cartan ones.

Elements — polynomials $P(u, u', \ldots, u^{(n)})$ in any number of variables.

$\overset{''}{P}[u]$, where $u = \{u, u', \ldots, u^{(n)}, \cdot\}$



Uncertain reading. Two strokes stand above the left square bracket.

Original source details: GELFAND-P000613

There is a notion of

$$\frac{d}{dx}P(u,u',\dots,u^{(n)}) = \sum_{i=0}^{\infty}\frac{\partial P}{\partial u^{(i)}}\cdot u^{(i+1)}$$

There is multiplication (algebr.)

Unexpectedly, there is a notion of the commutator:

$$[P,Q] = \sum_{k=0}^{\infty}\left[\left(\frac{d}{dx}\right)^k P\cdot\frac{\partial Q}{\partial u^{(k)}} - \left(\frac{d}{dx}\right)^k Q\cdot\frac{dP}{du^{(k)}}\right]$$



Original source details: GELFAND-P000613

Uncertain reading. The mark after Q reads as a multiplication dot. The last fraction uses d.



Original source details: GELFAND-P000613

Uncertain reading. A short entry before the surname is crossed out.



Original source details: GELFAND-P000613

Undeciphered passage. The crossed-out entry cannot be read in full.

Povzner. This alg. is connected with the eq. $\frac{\partial u}{\partial t} = \frac{\partial u}{\partial x}$. Can be connected with $\forall$ eq.

$$\frac{\partial u}{\partial t} = a(u,u_x,\dots).$$

Consider fns. $F(u,u_x,\dots)$ and the operator

$$a[F(u,u_x,\dots)] = aF_u + \left(\frac{d}{dx}a\right)F_{u_x} + \frac{d^2a}{dx^2}F_{u_{xx}} + \dots$$

The operator is det. by the fn. a and an algebra is built from these oper.

$[a,b] = a[b] - b[a]$ — the same algebra.

— · —

Here the natural repr. of this algebra is indicated.

Original source details: GELFAND-P000613

Uncertain reading. A mark to the left of “Here” is blacked out.

Manin. 6 expressions for Ramanujan's fn. $\tau(n)$ (not obt. by a finite algorithm).

⊕ ① Definition ⇒

$$\tau(n) = \sum(-1)^k$$

$$n-1 = n_1 + \ldots + n_k, \qquad n_i \geq 1$$

$$n_1 \leq n_2 \leq \ldots \leq n_k$$

in a row ≤ 24 equality signs.

⊕ ② Macdonald (Dyson)

$$\tau(n) = \frac{1}{1!2!3!4!} \sum \prod_{i<j} (u_i - u_j)$$



Uncertain reading. The index condition below the product tentatively reads $i < j$.

Original source details: GELFAND-P000613

$$10n = \sum_{i=1}^{5} u_i^2, \qquad \sum u_i = 0, \qquad u_i \equiv i \bmod 5$$

$\binom{+}{+}$ ③ Ramanujan

$$\tau(n) = \frac{65}{756}\sigma_{11}(n) + \frac{691}{756}\sigma_5(n) - \frac{691}{3}\sum_{m=1}^{n-1} \sigma_5(m)\sigma_5(n-m)$$



Uncertain reading. The last digit of the first denominator is overwritten and reads as 6.

Original source details: GELFAND-P000613



Uncertain reading. The argument in the final factor reads $n - m$.

Original source details: GELFAND-P000613

$\sigma_k(n)$ — $\sum$ of the kth powers of the divisors of n.

Corollary: $\tau(n) \equiv \sigma_{11}(n) \bmod 691$. (guessed by Ramanujan).

GELFAND-P000614

④ Int. quad. forms with det $= 1$ in 24 variables. 2 in all.

$\binom{+}{+}$ Let Q_{24} — one of them.



Uncertain reading. The line reads “2 in all”.

Original source details: GELFAND-P000614

$$\tau(n) = \alpha\left(\sum_{Q_{24}=n} 1\right) - \beta\sigma_{11}(n)$$

(α, β computed from $n = 1$ and 2).

⑤ (Manin) $\binom{+}{+}$

$$\tau(n) = \sigma_{11}(n) - \sum_{n=\Delta\Delta'+\delta\delta'}{}' \left[(\Delta^8\delta^2 - \Delta^2\delta^8) + \frac{691}{6}(\Delta^6\delta^4 - \Delta^4\delta^6)\right],$$



Uncertain reading. There is a prime on the summation sign.

Original source details: GELFAND-P000614

$$\Delta > \delta > 0, \quad \text{and } [\,\Delta' > \delta' > 0 \quad (\text{integers})$$
$$\text{or } \Delta \mid n, \quad \Delta' = \frac{n}{\Delta}, \quad \delta' = 0, \quad 0 < \frac{\delta}{\Delta} \le \frac{1}{2}\,].$$

⑥ $\binom{+}{+}{+}$

$$\sum p(n)x^n = \prod_{n=1}^{\infty}(1 - x^n)^{-1}$$

($p(n)$ — number of partitions of n into any number of summands).

$$\Rightarrow \quad \sum \tau(n)x^n = x\left(\sum_{n=1}^{\infty} p(n)x^n\right)^{-24}$$



Uncertain reading. The lower limit of the inner sum is written $n = 1$.

Original source details: GELFAND-P000614

Using $p(n)$, find $\tau(n)$ recursively.

Hardy–Ramanujan–Rademacher formula

$$p(n) = \frac{1}{\sqrt{3}} \sum_{k=1}^{\infty} \frac{1}{\sqrt{k}} \sum_{\substack{h \bmod k \\ (h,k)=1}} \omega_{h,k} e^{-2\pi i n \frac{1}{k}} \cdot \frac{d}{dn} \frac{\operatorname{sh} \frac{\pi}{6k} \sqrt{24n-1}}{\frac{\pi}{6k} \sqrt{24n-1}}$$



Uncertain reading. The exponent is written with $1/k$.

Original source details: GELFAND-P000614

$\omega_{h,k}^{24} = 1$ there are also explicit formulas for $\omega_{h,k}$.

Hardy–Ramanuj. wrote [crossed out] sh $\to e^{\cdots}$.

Undeciphered passage. A short entry before "sh" is crossed out.

Original source details: GELFAND-P000614

[Below sh $\to e^{\cdots}$: diverges.] but if one truncates at the $\sqrt{n}$ term, it approximates well. One has to stop at $\sqrt{n}$ terms. Each of these formulas is part of an infinite series of formulas.

⑦ $\binom{+}{+}$ $\underline{\underline{\tau(mn) = \tau(m)\tau(n)}}$, $(m,n) = 1$

(not apparent from the formulas).

$$\tau(p) = \theta_p + \bar{\theta}_p, \qquad \theta_p \bar{\theta}_p = p^{11} \quad \Rightarrow$$

$$\underline{\underline{\tau(p^a) = \theta_p^a + \bar{\theta}_p^a.}}$$



Uncertain reading. The doubly underlined formula is given as written.

Original source details: GELFAND-P000614

One can substitute in each formula and obtain new identities.

⑧ $\begin{pmatrix} + \\ + \\ + \\ + \end{pmatrix}$ From this [circled insertion: the suspicion that] τ — trace of a representation (much harder) — Serre, Deligne.



Uncertain reading. The circled insertion reads "the suspicion that".

Original source details: GELFAND-P000614

Grothendieck, Weil, Kuga, Sato, [crossed out] Rankin.



Undeciphered passage. The crossed-out entry before Rankin is illegible.

Original source details: GELFAND-P000614

An ℓ-adic repr.

$$\mathrm{Gal}_{\{\ell\}}(\bar{Q}/Q) \longrightarrow Q_\ell^2$$

(ramif. only at ℓ). The trace is taken of the Frobenius autom. gen. by p.

From this it was possible to prove that θ_p are purely imaginary (nonreal)



Uncertain reading. The manuscript reads "purely imaginary".

Original source details: GELFAND-P000614

$\longrightarrow$ The longest thm. in modern mathematics (Deligne's estimate: 2,000 pages).

GELFAND-P000615

Levels of difficulty.

$+$	combinatorics
$++$	modular forms
$+++$	complex analysis
$++++$	alg. geom. and the like, étale cohom. and so on

—— · ——

How it is obtained.

$$\eta(z) = e^{\frac{2\pi i n z}{24}} \prod (1 - e^{2\pi i n z})$$



Uncertain reading. The prefactor exponent is written $2\pi inz/24$.

Original source details: GELFAND-P000615

Set $x = e^{\frac{2\pi i n z}{24}}$.



Uncertain reading. The heavily inked mark between i and z tentatively reads n. The denominator is overwritten.

Original source details: GELFAND-P000615

The fn. behaves [crossed out] well under the substitution $z \to \dfrac{az+b}{cz+d}$, $\begin{vmatrix} a & b \\ c & d \end{vmatrix} = 1$.

Undeciphered passage. Short strokes after the verb are crossed out.

Original source details: GELFAND-P000615

$$\eta(z+1) = e^{\pi i/12}\eta(z),$$
$$\eta(-1/z) = \sqrt{z/i}\,\eta(z).$$

or $\eta^{24}(\tau)(d\tau)^6$ — inv. under frac.-lin. subst..



Uncertain reading. The exponent on $d\tau$ is written 6.

Original source details: GELFAND-P000615

Loss of inf. — $\sqrt[24]{\ldots} = \omega_{c,d}$ — the same ones.

$$\begin{pmatrix} a, & \bar{b} \\ c, & d \end{pmatrix}$$



Uncertain reading. In the matrix below "Loss of inf." there is a separate stroke over b.

Original source details: GELFAND-P000615

Fns. of this kind (modular) form a ring with 2 generators, and one must write them in terms of the generators, [crossed out ~~or~~] Identity in the ring ⇒ equality of Fourier coeffs. (⇒ ③, ④).

Uncertain reading. A word above the line is crossed out. It tentatively reads "or".

Original source details: GELFAND-P000615

Pure algebra:

$$\left\{\varphi(z) \,\middle|\, \sum_{n=0}^{\infty} a_n e^{2\pi i n z}\right\}, \qquad \exists k: \quad \varphi(z)dz^k \,\middle|\, \begin{pmatrix} a & b \\ c & d \end{pmatrix} = \varphi(z)dz^k.$$

$\longleftarrow$ converg. series for $\operatorname{Im} z > 0$.

Thm.: the ring $\Phi = C[E_4, E_6]$.

$$\left.\begin{aligned} a_n|_{E_4} &= \sigma_3(n) \\ a_n|_{E_6} &= \sigma_5(n) \end{aligned}\right\| \qquad \sigma_3 \text{ — sums of cubes of divisors.}$$

—— · ——

H. R. R. (formula 6).

$$\sum p(n) e^{2\pi i n z} = \frac{1}{\prod(1 - e^{2\pi i z n})}.$$

Sing. points on the boundary of convergence (poles of order ∞ at rat. points).

Rademacher's integr. contour: at $\forall$ rat. point, circles of a given radius.



Original source details: GELFAND-P000615

Diagram and typed description.



The exact shape of the short arcs near the small circle is uncertain.

Original source details: GELFAND-P000615

Diagram and typed description.

— 1st approx.



Original source details: GELFAND-P000615

Diagram and typed description.

— 2nd approx.

etc.

Special case of Macdonald's formulas in the form transformed by Kostant:

$$\varphi(x) = \prod_{n=1}^{\infty}(1 - x^n), \qquad \varphi(x) = \sum_{\lambda \in D} \chi_\lambda(a) \dim V_\lambda \, x^{c(\lambda)}.$$

Original source details: GELFAND-P000615

Undeciphered passage. A short entry beneath the product is heavily crossed out.

[under $\lambda \in D$: highest weights of irred. reps.; under $\chi_\lambda(a)$: $0, \pm 1$.]

$$c(\lambda) = (\lambda + \rho, \lambda + \rho) - (\rho, \rho).$$

GELFAND-P000616

$6/\overline{X} - 75$ Gelfand Sem.



Undeciphered passage. Only the lower parts of a line of strokes are visible at right, level with the date.

Original source details: GELFAND-P000616

Leray.

Undeciphered passage. A hatched strip is visible under the name. Any letters beneath it are illegible.

Original source details: GELFAND-P000616

“5 years ago Arnold suggested that I understand one of Maslov’s books.”

“Now I am beginning to understand where this book leads.”

Uncertain reading. “мне” (to me) is overwritten. The next word tentatively reads “понять” (understand).

Original source details: GELFAND-P000616

Algebraic prelim. to Maslov’s work,
in part. Buslaev’s metaplectic group.

Maslov: $X = \mathbb{R}^\ell$, Buslaev: X — any set.

$$X = R^\ell: \quad S(X),\ S'(X),\ \mathcal{H}(X) \text{ — intermed. Hilb. sp..}$$

$$a\left(x, \frac{1}{\nu}\frac{\partial}{\partial x}\right), \qquad \frac{\nu}{i} \in \mathbb{R}_+.$$

Assume a — lin. [crossed out] in both arguments, to begin with.

Undeciphered passage. An entry after “lin.” is heavily crossed out.

Original source details: GELFAND-P000616

We seek a gr. of automorph. of $S'(X)$.

$$S: f' \longrightarrow Sf'.$$

$$SaS^{-1} \in A$$

(A — [crossed out] the class of oper. linear in x and $\partial/\partial x$.)

Undeciphered passage. An entry between A and “class of oper.” is crossed out.

Original source details: GELFAND-P000616

Example: $\overline{\mathcal{F}}$ $\overline{\mathcal{F}}^{-1}$ and $\overline{\mathcal{F}}$ in several coord..

lin. change of var. in x-sp..

Original source details: GELFAND-P000616

Uncertain reading. The first bar over $\mathcal{F}$ has an arched edge. The next two are closer to horizontal.

S — symb. autom. A (inner).



Original source details: GELFAND-P000616

Uncertain reading. The first abbreviation tentatively reads “симв.” (symbol).

$$a : X \oplus X^* \longrightarrow \mathbb{C}$$

$$a(x, p)$$

Original source details: GELFAND-P000616

Uncertain reading. A short blackened stroke is visible between X^* and the line below.

gr. of autom. — sympl. group

$$\langle p', x\rangle - \langle p, x'\rangle.$$

$$X \oplus X^* = Z(\ell).$$

$G(\ell)$ — gr. of autom. in the sp. of distr. $\Rightarrow$ obtain its repr.

$$G(\ell) \longrightarrow \mathrm{Sp}(\ell), \qquad \text{kernel: } \dot{\mathbb{C}}$$

Original source details: GELFAND-P000616

Undeciphered passage. A short entry to the left of “kernel” cannot be read with confidence.

$$G(\ell)/\dot{\mathbb{C}} = \mathrm{Sp}(\ell)$$

$$c \in \dot{\mathbb{C}} = \mathbb{C} \setminus 0$$

In particular, $G(\ell)$ — a Lie gr..

GELFAND-P000617

Many elem. are known — full and partial Fourier transf..

$$A : X \oplus X \longrightarrow \mathbb{R} \quad \text{real quadr.}, \qquad \Delta(A) = \sqrt{\det A(x, x')''} \neq 0$$



Original source details: GELFAND-P000617

Uncertain reading. Two strokes at the end of the radical tentatively read as $A(x, x')''$.

$$(S_A f')(x) = c\left(\frac{|\nu|}{2\pi i}\right)^{\ell/2} \Delta(A) \int_X e^{\nu A(x,x')} f'(x')\, d^\ell x'$$

$$(x,p) = s_A(x',p') \quad \Leftrightarrow \quad p = A_x,\ p' = -A_{x'}$$

— the corr. sympl. transformation.

S' — a unit. operator.

Original source details: GELFAND-P000617

Uncertain reading. The short stroke at the top of S tentatively reads as the prime in S'.

Unitarity $\Rightarrow$ metapl. group $M_p(\ell)$

I. Segal ; A. Weil ; K. Siegel

Math. phys. arbitr. field $\longrightarrow$ to understand Siegel's work

Original source details: GELFAND-P000617

Uncertain reading. The note beneath Weil tentatively reads "arbitr. field". The arrow leads to "to understand Siegel's work".

$M_p(\ell) \ni$ [crossed out] $S'_A \longmapsto s_A$

Original source details: GELFAND-P000617

Undeciphered passage. The entry after the membership sign is heavily crossed out.



Original source details: GELFAND-P000617

Uncertain reading. The stroke at the first S_A tentatively reads as the prime in S'_A.

this is the formula with $|c| = 1$.

Take $c = \pm 1$

$$S_A \cdot S_{A'} = S_{A''}$$

[crossed out] $\underline{\underline{S_A S_{A'} S_{A''} = \pm E}}$

$\Uparrow$ $\overset{\text{sign}}{\sim}$ Maslov ind.

$$s_A s_{A'} s_{A''} = e$$

Original source details: GELFAND-P000617

Undeciphered passage. An entry to the left of the doubly underlined equality is crossed out.

Decompose:

$$A(x,x') = \langle Px, x\rangle - \langle Lx, x'\rangle + \langle Qx', x'\rangle, \qquad P, Q, L : X \longrightarrow X'.$$

. . . . . .

Uncertain reading. A crossed stroke is visible to the left of the row of dots.

Original source details: GELFAND-P000617

GELFAND-P000618

—— · ——

13.10.75. Gelfand Sem.

Fradkin. (Efim [crossed out] Samoilovich).



Undeciphered passage. An entry before “Samoilovich” is crossed out.

Original source details: GELFAND-P000618

What does one need to know?

1. Quant. mechanics: Landau
2. Field theory Bogoliubov, Shirkov
   Akhiezer and Berestetskii
   Pauli — old.

Fradkin, Proceedings of FIAN, (field theory and stat. from the funct. approach)
vol. 29 (old) ↓ briefly. S-matr. and so on..

3. Theory of group reps. Gelfand, Minlos, Shapiro

Uncertain reading. The middle surname tentatively reads “Minlos”.

Original source details: GELFAND-P000618

4. Anticommuting vars. (Fermi vars.) Berezin; methods of second quant..

5. Abrikosov, Gor'kov, Dzyaloshinskii, "Methods of Field Theory in Stat. Physics" (book).

Original source details: GELFAND-P000618

Diagram and typed description.

The digitized frame's yellow icon obscures part of the name "Gor'kov" and nearby strokes.

6. "Gauge Fields" Konoplev and Popov.



Original source details: GELFAND-P000618

Uncertain reading. The surnames in the manuscript tentatively read "Коноплёв и Попов".

7. Reviews by Weinberg, Lee and others in

Perelomov. On completely int. Ham. systems. ($\exists n$ first int. in involution)

$$H = \frac{1}{2}\sum_{k=1}^{n} p_k^2 + U(q_1, \ldots, q_n)$$

G. Liouville's thm.: the syst. is then solved by quadratures.

$$H = \tfrac{1}{2}p^2 + \sin q$$

2nd int. — elliptic fn..

0th example — [crossed out] chain [crossed out] Toda.

Original source details: GELFAND-P000618

Undeciphered passage. An entry before "chain" is crossed out.

Original source details: GELFAND-P000618

Undeciphered passage. An entry before "Toda" is crossed out.

$$U = g^2 \sum_{k=1}^{n} \left(e^{-(q_{n+1}-q_n)} - e^{-(q_n-q_{n-1})}\right), \qquad q_{k+n} = q_k.$$



Original source details: GELFAND-P000618

Uncertain reading. The summation starts at $k = 1$. The exponents use $n+1, n, n-1$, and a minus separates the exponentials.

[crossed out] S. Manakov ξ 1974; Toda 1970 (Prog. Th. Ph.);

Original source details: GELFAND-P000618

Undeciphered passage. An entry before “S. Manakov” is crossed out.

Original source details: GELFAND-P000618

Uncertain reading. A heavily inked mark resembling ξ appears between “Manakov” and the date.

1973 Hénon, Flaschka [crossed out] 1974 $\longrightarrow$ there were int., but it was not proved that they were in invol..



Original source details: GELFAND-P000618

Undeciphered passage. An entry after “Flaschka” is crossed out.



Original source details: GELFAND-P000618

Uncertain reading. The abbreviation after “not” tentatively reads “док.” (proved).

M. Kac, van Moerbeke 1975.

[crossed out ~~1975 Moser J. Moser (prepr.)~~]



Original source details: GELFAND-P000618

Uncertain reading. The Moser reference is crossed out. The last abbreviation tentatively reads “prepr.”.

A:

$$U = g^2 \sum_{k<\ell} U(q_k - q_\ell).$$



Original source details: GELFAND-P000618

Uncertain reading. The letter under the summation sign in A resembles U.

G. Problems: a) find the int. b) prove invol. c) solve the inv. problem d) express the int. by quadratures.

B.

$$U = g^2 \sum_{k<\ell} [V(q_k - q_\ell) + \varepsilon V(q_k + q_\ell)] + g_1^2 \sum V(q_k) + g_2^2 \sum V(2q_k$$



Undeciphered passage. The closing parenthesis is not visible at the right edge of the frame.

Original source details: GELFAND-P000618

	$V(q)$	I_k	$\{I_k, I_\ell\} = 0$	I.P. (inv. problem)	$x(q)$
1	q^{-2}	M, OP	M, OP	?	q^{-1}
2	$a^2 \operatorname{sh}^{-2} aq$	CMR, OP	CMR, OP	?	$a \operatorname{cth} aq$
3	$a^2 \sin^{-2} aq$	M, OP	CMR, OP	?	$a \operatorname{ctg} aq$
4	$a^2 \wp(aq \mid \omega_1, \omega_2)$	C, OP	?, ?	?	$a \frac{\operatorname{cn} aq}{\operatorname{sn} aq}$
5	$q^{-2} + a^2 q^2$	P, P	ϕ, ϕ	?	



Undeciphered passage. In row 4 a short entry before the two question marks is crossed out.

Original source details: GELFAND-P000618

Uncertain reading. The involution column in row 5 has two looped letters, tentatively ϕ, ϕ.

Original source details: GELFAND-P000618

$\wp$ — Weierstrass fn.. 2, 3 — limiting cases of 4.

Undeciphered passage. Separate strokes before the note on the columns are crossed out.

Original source details: GELFAND-P000618

1 column — A

2 —"— — B

GELFAND-P000619

1975 J. Moser prepr.

F. Calogero, M., R., (3 authors) Lett. Notes

Uncertain reading. The manuscript reads “Lett.” before “Notes”.

Original source details: GELFAND-P000619

OP	Calogero Olshanetsky, Perelomov	} by name
P	Perelomov	



Uncertain reading. The words beside the brace tentatively read “по имен.” (by name).

Original source details: GELFAND-P000619

Coleman, Schroer — connection [crossed out ~~of the mod.~~] of the Thirring mod. with sin-Gordon.

Uncertain reading. An entry before “Thirring mod.” is crossed out. It tentatively reads “с мод.” (with the mod.).

Original source details: GELFAND-P000619

0 — inv. problem — Stieltjes.

Uncertain reading. The surname after “inv. problem” reads “Стильтьес” (Stieltjes).

Original source details: GELFAND-P000619

$$0. \qquad g^2 \sum_{k=1}^{n} e^{-(q_{k+1}-q_k)}$$

The inverse problem is solved nowhere (except case 0).

[left margin ‖ types 1–4.] The int. always have the form $I_k = \mathrm{Sp}(L^k)$, where the explicit form of L is written out (L-matrix).

$$L = P + iX, \qquad P_{k\ell} = p_k \delta_{k\ell}, \qquad X_{k\ell} = (1 - \delta_{k\ell}) x(q_k - q_\ell),$$

[under $P_{k\ell}$: diag. matr..] where $x(q)$ is written in the table.

The inv. problem here is to find matr. entries from the traces of powers. Idea: from Lax in KdV.

$$N = 5 \quad I_k = \mathrm{Sp}(N^k), \quad N = L^2 + \omega^2 Q^2, \qquad \text{where } Q_{ij} = q_j \delta_{ij}$$



Uncertain reading. $N = 5$ is written separately to the left of the formula.

Original source details: GELFAND-P000619

Manakov — finite-dim. analogue of higher KdV. Treated the first two. [under Manakov: (dissert.)] Quant. syst. have also been treated and are also of interest.

$$p = -i\frac{\partial}{\partial q}.$$

Then $H =$ Laplace oper. on a symm. sp. (radial part). Equiv. to syst. 3 — the quantized one.

Gelfand's question: can everything be reduced to group integrability, but in a larger sp..



Original source details: GELFAND-P000619

Uncertain reading. The abbreviation after "group" tentatively reads "интегрир." (integrability).

— · —

Connection with Dynkin diag.: $\{\alpha\}$ — roots, $q_\alpha = (\alpha, q)$.

$$U = \sum_{\alpha>0} g_\alpha^2 V(q_\alpha), \qquad g_\alpha = g_\beta, \quad \text{if } \alpha \text{ and } \beta \text{ have equal lengths}$$

$\alpha_{ij} = e_i - e_j$ — one obtains Moser's syst.. A — root syst. of type A_n. B — at diff. values of const. B, C, BC, D etc..

[crossed out] There are also all the exceptional groups.



Original source details: GELFAND-P000619

Undeciphered passage. A short entry before "There are" is crossed out.

It is unclear as yet whether the syst. for exceptional groups are completely integrable.

Fradkin. E. S. What is new in the last 20 years?

1. Consider an arbitr. system. It is given by a Lagr. or a Hamiltonian $H(p, q)$ (classical for now).

p, q can be Fermi and Bose (a mixture).

p, q — either Bose or Grassmann (Fermi)
$\downarrow$
$pq + qp = 1.$
(see Berezin).

There are also constraints $\varphi_k(p, q) = 0$.



Original source details: GELFAND-P000619

Uncertain reading. The second argument is heavily overwritten and tentatively reads q.

(distinguish between Bose and Fermi vars.).

Example: gauge fields (electrodynamics (Ab.), Yang–Mills, gravit. field, Einstein eqs.), grad. inv. of Maxwell's eqs..



Original source details: GELFAND-P000619

Uncertain reading. The parenthesis after "electrodynamics" tentatively reads "аб." (Ab.).

and light is in 2 states, rather than 3, the extra one is eliminated by gauge inv. all fields with higher spins.

$\varphi_k = 0$ Bose constraints

$\chi_k = 0$ Fermi constraints



Original source details: GELFAND-P000619

Uncertain reading. The first sign in the last line is heavily overwritten and tentatively reads χ.

GELFAND-P000620

[top left, crossed out: $\prod(d\varphi, d\pi, d\psi, d\pi^{(\psi)})$.]

Original source details: GELFAND-P000620

Uncertain reading. Parts of a product of differentials are legible. The formula is crossed out with diagonal strokes.

Lagrangian $L(q, \dot{q})$, $p = \dfrac{\partial L}{\partial^r \dot{q}}$. Poisson bracket: ($r$ — denotes the right derivative).

Original source details: GELFAND-P000620

Uncertain reading. The heading uses the singular "bracket".

$$\{A, B\} = \frac{\partial A}{\partial^r q}\frac{\partial B}{\partial^\ell p} - (-1)^{n_A n_B}\frac{\partial B}{\partial^r q}\frac{\partial A}{\partial^\ell p}.$$

$n_A = 0$, if the number of Fermi vars. is even

$n_A = 1$ —"— odd

(in A).

Nondegeneracy: $\dot{q} = f(q, p)$ (can be expressed). Sometimes it cannot: when $\det \dfrac{\partial^2 L}{\partial \dot{q}_i \partial \dot{q}_j} = 0$.

Then addit. constraints arise.

One can proceed in the same spirit and obtain (see Dirac's slim book). all the constraints. [crossed out] Close under the Poiss. bracket (to a Lie alg.).

Original source details: GELFAND-P000620

Undeciphered passage. A parenthesized entry after "all the constraints" is crossed out.

ψ_k — addit. conditions obtained in this way.

Dirac: [circled important] second-class constraints, between which $\{\varphi_k, \psi_j\} \neq 0$ taking the addit. conditions into account. Discard constraints belonging to the center, etc.

Original source details: GELFAND-P000620

Uncertain reading. The first abbreviation tentatively reads “Выбрас.” (discard).

Generating fn. for all Green’s fns.

[crossed out] ~~$Z = \frac{1}{C}\int d\varphi_j\, d\pi_j^{(\varphi)} \ldots d\psi_j\, d\pi_j^{(\psi)}\, \delta(\varphi_k)\delta(\chi_k)$ exp~~



Original source details: GELFAND-P000620

Uncertain reading. The whole preceding line is crossed out. The legible parts are typeset.



Original source details: GELFAND-P000620

Undeciphered passage. A measure factor in the crossed-out line is obscured by heavy ink.

$$Z = \frac{1}{C}\int \prod_x d\varphi_j(x)\, d\pi_j^{(\varphi)}(x)\, d\psi_j(x)\, d\pi_j^{(\psi)}(x)\, \delta(\varphi_k)\delta(\chi_k)\times$$
$$\times \exp i \int_{\mathbb{R}^4} \Big\{ \pi_j^{(\varphi)}\dot{\varphi}_j + \pi_j^{(\psi)}\dot{\psi}_j - H(\pi^{(\varphi)}, \varphi, \psi, \pi^{(\psi)}) -$$
$$- \pi_j \bar{I}_j^{(\varphi)} - \varphi_j I_j^{(\varphi)} - \pi_j^{(\psi)} I_j^{(\psi)} - \bar{I}_j^{(\psi)}\psi_j \Big\}\, d^4x + A,$$



Original source details: GELFAND-P000620

Uncertain reading. A minus is visible at the end of the H line and at the start of the next. The closing brace precedes $d^4x + A$.



Original source details: GELFAND-P000620

Uncertain reading. The overwritten sign between exp and the integral tentatively reads i.



Original source details: GELFAND-P000620

Uncertain reading. The subscript on the final I looks like j. The upper stroke merges with the letter.

where

$$A = \exp\left(-\frac{\delta(0)}{2}\right) \operatorname{Tr}\{\ln\{\chi_i, \chi_j\}_+\} - \operatorname{Tr}\ln\left[\{\varphi_i, \varphi_j\}_- - \{\varphi_i, \chi_j\}_-\{\chi_i, \chi_j\}_+^{-1}\{\chi\varphi\}_-\right]\Big\}.$$



Original source details: GELFAND-P000620

Uncertain reading. The grouping after $\delta(0)/2$ and at the end follows the manuscript.



Original source details: GELFAND-P000620

Uncertain reading. An additional closing brace follows the first bracket with a plus sign. The second Tr is inserted above the line.



Original source details: GELFAND-P000620

Uncertain reading. The last bracket contains χ and φ without explicit indices.

φ — Bose fields
ψ — Fermi fields

Tr of matrices

(general formula for all quantum theories).

φ, χ — constraints (only noncommuting ones).

I — "sources" φ and ψ — elem. of the conj. space.

One obtains an analogue of the Fourier transform.

A — a term associated with the constraints.

$\delta(0)$ then cancels (in the S-matrix)

$\{\chi, \chi\}_\pm$ — Poisson brackets (Bose and Fermi)

— · —

$20/\overline{X} - 75.$ Gelfand Sem.

I. M. Gelfand:

$$L = -\frac{d^2}{dx^2} + u(x), \qquad A = \frac{d^3}{dx^3} + \dots, \qquad [L, A] = K(u).$$

$A = L^{3/2}$ with the nondifferential terms cut off.

1-zone potential: $K(u) = 0$. The point (hypothesis): for u the operators L and A commute.

Higher eqs.. $A = L^{5/2}, L^{7/2}, \dots$ almost commute — the remaining oper. is multiplication by a fn.

[crossed out] Hypothesis: this is a piece of an unworked-out noncommut. theory.

Original source details: GELFAND-P000621

Undeciphered passage. A short entry before "Hypothesis" is crossed out.



Original source details: GELFAND-P000621

Uncertain reading. The adjective before "noncommut. theory" reads "несделанной" (unworked-out).

Krichever: in fact started from this.

[crossed out] Krichever. Igor.

Original source details: GELFAND-P000621

Undeciphered passage. An entry to the left of the name is crossed out.

Consider the operator eq. $[L_n, L_m] = 0$, where

$$L_n = \sum_{i=0}^{n} u_i(x) \frac{d^i}{dx^i}, \qquad u_n(x) \equiv c_0, \quad u_{n-1} \equiv c_1$$

$$L_m = \sum_{i=0}^{m} v_i(x) \frac{d^i}{dx^i},$$

[crossed out ~~$u_m(x) \equiv$~~] u_m and u_{m-1} are also const.

Original source details: GELFAND-P000621

Uncertain reading. The crossed-out expression tentatively reads $u_m(x) \equiv$.



Original source details: GELFAND-P000621

Uncertain reading. The two constant coefficients in this line are written with u.

(operators of this kind are always considered).

Write the syst. of eqs.:

$$0 = \sum_{k,\ell} u_k C_k^{k+\ell-s} v_\ell^{(k+\ell-s)} - \sum_{k,\ell} v_k C_k^{\ell+k-s} u_\ell^{(\ell+k-s)}$$
$$0 \le s \le m+n-3.$$

Number of eqs. $=$ number of unknowns.

$$mu'_{n-2} - nv'_{m-2} = 0 \quad \Rightarrow \quad v_{m-2} = \frac{m}{n} u_{n-2} + h_2 \qquad (h_2 = \text{const}).$$

It is easy to check that the first [above the line $(m-1)$] eqs. (for $n-1 \le s \le m+n-3$) allow one to express all v_i as polynomials in u_i (and their derivatives). Also [crossed out] constants of integration arise.

Undeciphered passage. A short entry after "Also" is crossed out.

Original source details: GELFAND-P000621

Substituting them in the eqs. $0 \le s \le n-2$, we obtain eqs. for the [crossed out] coeffs. of L_n.

Undeciphered passage. An entry before "coeffs." is crossed out.

Original source details: GELFAND-P000621

for $L = -\dfrac{d^2}{dx^2} + u(x)$ one obtains for $m = 2k+1$ a set of oper., [crossed out] whose commutator is multiplication by a fn.



Undeciphered passage. A word before "whose" is crossed out.

Original source details: GELFAND-P000621

For u one eq. remains, the higher KdV eq.. The family [crossed out] depends on the const. of integration.

Undeciphered passage. An entry between "The family" and "depends" is crossed out.

Original source details: GELFAND-P000621

Theorem (A. B. Shabat). If [crossed out] for L_n there exists an oper. L_m:

Undeciphered passage. Part of the hypothesis before "for" is crossed out.

Original source details: GELFAND-P000621

$$[L_n, L_m] = 0, \quad \text{then} \quad \exists \text{ polynomial } P(x,y): \qquad P(L_n, L_m) = 0$$

(commutative).

GELFAND-P000622

Proof. [crossed out ~~all simple when $(n,m)=1$.~~]



Uncertain reading. The crossed-out phrase tentatively reads “all simple when $(n,m)=1$”.

Original source details: GELFAND-P000622

Let y — a solution of the eq.:

$$L_n y = Ey, \qquad y_j(x,E) \text{ — basis of solns. (entire fns. of } E\text{).}$$

$$y_i^{(j)}(x_0, E) = \delta_{ij}$$

Uncertain reading. The equals sign meets the overwritten parenthesis.

Original source details: GELFAND-P000622

L_m gives a lin. oper. in the sp. of solutions of $L_n y = Ey$ $(\forall E)$. Its char. polynomial

$$0 = L_m^{n+1}(E) + r_n(E) L_m^n(E) + \ldots + r_0(E).$$



Uncertain reading. The first exponent is written $n+1$.

Original source details: GELFAND-P000622

Coeffs. — entire fns. of E. Prove that they are polynomials in E. This follows from the asymptotics of $y_i(E)$ in E (as $E \to \infty$).

$$y_i(x,E) \sim \sum_{j=0}^{n-1} a_{ij} e^{\varepsilon_j k x}, \qquad \varepsilon_j^n = 1, \quad k^n = E.$$

Hence the growth order of $r_j(E) \leq$ a polyn. in $k \Rightarrow$ they are themselves polynomials.

$$r_j(E) y = r_j(L_n) y$$



Uncertain reading. The r on the right is overwritten.

Original source details: GELFAND-P000622

Hence the char. polynomial

$$P(L_n, L_m)y = 0.$$

But there are sufficiently many solutions (E — arbitrary).



Uncertain reading. Below "many" the manuscript reads "E arbitrary".

Original source details: GELFAND-P000622

[circled inf.-dimensional sp.]

$$\Rightarrow P(L_n, L_m) = 0. \qquad \triangleright$$

I. Bernstein: for polynomial coeffs. it was in F. A., vol. 1, no. 4.

[crossed out ~~Let $\psi_i(x, E)$ — eigenfn..~~]



Uncertain reading. The opening word is crossed out and tentatively reads "Пусть" (let).

Original source details: GELFAND-P000622

Uncertain reading. The crossed-out line contains $\psi_i(x, E)$ and "соб." (eigenfn.).

Original source details: GELFAND-P000622

Let $\psi_i(x, E)$ be an eigenfn. for the pair of op.:

$$L_n\psi_i(x, E) = E\psi_i(x, E)$$
$$L_m\psi_i(x, E) = E_i\psi_i(x, E).$$

Then consider the surf. [left, crossed out ~~$\psi(x, P)$~~.]

Uncertain reading. The entry under the crossing-out tentatively reads $\psi(x, P)$.

Original source details: GELFAND-P000622

$P(x, y) = 0$, x, y — eigenvalues of L_n and L_m.

$\Rightarrow E_i$ alg. fns. of E,

$$\psi|_{x_0} = 1 \text{ (norm.)}.$$

$\Psi(x, P)$ — a fn. on this surf. [crossed out ~~BAKER~~.]

Uncertain reading. The hatched entry tentatively reads "BAKER". Some letters are obscured.

Original source details: GELFAND-P000622

$P \in X$.

—— · ——

Consider $\forall$ nonsing. alg. curve X with marked point $P_0 \in X$.

The following properties uniquely determine the fn. $\Psi(x, P)$, $x \in (a, b)$, $P \in X$. (Akhiezer).

1°. $\psi(x, P)$ is meromorphic on [crossed out ~~x_0~~] $X \setminus P_0$, has polar divisor D with $\deg D = g$, and D is nonspecial and independent of x.



Uncertain reading. The entry crossed out before X tentatively reads x_0.

Original source details: GELFAND-P000622

2°.

$$\psi(x, P) = e^{k(x-x_0)} \underbrace{\left(1 + \sum_{i=1}^{\infty} \frac{\xi_i(x)}{k^i}\right)}_{\text{regular fn. near } P_0}, \qquad \frac{1}{k} = z \text{ — loc. parameter near } x_0.$$

Uncertain reading. The overwritten letter in the numerator tentatively reads ξ.

Original source details: GELFAND-P000622

Uncertain reading. The note on the right reads "near x_0". The label under the bracket reads "near P_0".

Original source details: GELFAND-P000622